

Price Schedule: Supply and Refurbishment of Marshalling kiosks

Number	Description	Quantity	UoM	Unit Price	Year 1	Year 2	Year 3	Year 4	Total Price Excluded VAT
	<b>SUPPLY AND DELIVERY OF NEW KIOSKS</b>								
1	BOX: TYPE: CONTROL KIOSK, WIDTH: 600 MM, LENGTH: 900 MM, DEPTH: 260 MM, 80 SPRING LOADED TERMINALS; WDU10SL; 1 X WTI AND 1 OTI WITH 6M CAPILLARY	10	ea						
2	BOX: TYPE: CONTROL KIOSK, WIDTH: 600 MM, LENGTH: 900 MM, DEPTH: 260 MM, 80 SPRING LOADED TERMINALS; WDU10SL; 1 X WTI AND 1 OTI WITH 12M CAPILLARY	10	ea						
3	BOX: TYPE: CONTROL KIOSK, WIDTH: 900 MM, LENGTH: 1300 MM, DEPTH: 260 MM, 80 SPRING LOADED TERMINALS; WDU10SL; 1 X WTI AND 1 OTI WITH 6M CAPILLARY	10	ea						
4	BOX: TYPE: CONTROL KIOSK, WIDTH: 900 MM, LENGTH: 1300 MM, DEPTH: 260 MM, 110 SPRING LOADED TERMINALS; WDU10SL; 1 X WTI AND 1 OTI WITH 12M CAPILLARY	10	ea						
5	BOX: TYPE: CONTROL KIOSK, WIDTH: 900 MM, LENGTH: 1300 MM, DEPTH: 260 MM, 110 SPRING LOADED TERMINALS; WDU10SL; 1 X WTI 12M CAPILLARY, 1 X EPT202.	10	ea						
6	BOX: TYPE: CONTROL KIOSK, WIDTH: 900 MM, LENGTH: 1300 MM, DEPTH: 450 MM, 110 SPRING LOADED TERMINALS; WDU10SL; 1 X WTI AND 1 OTI WITH 12M CAPILLARY, 2 X FAN CONTROLLS	10	ea						
	<b>MODIFICATIONS &amp; REFURBISHMENT OF KIOSKS (AS PER SOW)</b>								
7	Collect, assess and test the kiosk, issue a condition report and repair quote, stating number of labour hours and materials price and quantity list, issueing of as built drawings and deliver after repair		Labour per hour						
8	Materials		material in percentage						
<b>TOTAL</b>									