


NOTE

RETAINING WALL :

1. ALL LEVELS AND DIMENSIONS TO BE CHECKED ON SITE
2. ALL CONCRETE WORK IS TO COMPLY WITH SANS 12006
3. CONCRETE GRADE - FUNDATION 20 / 10
4. ALL FOUNDATION WORK TO BE INSPECTED BY THE ENGINEER PRIOR TO CASTING OF CONCRETE
5. ALL REINFORCING FIXING IS TO BE INSPECTED BY THE ENGINEER PRIOR TO CASTING OF CONCRETE
6. SIX CONCRETE CUBES TO BE TAKEN PER BATCH. THREE CUBES TO BE TESTED AT SEVEN DAYS. THE REMAINDER AT TWENTY EIGHT DAYS. THE RESULTS ARE TO BE FORWARDED TO THE ENGINEER FOR REVIEW AND APPROVAL.
7. SET BOTTOM ROW OF BLOCKS IN WET CONCRETE.
8. ALL BLOCKS TO BE LAPPED TO THE REQUIRED DENSITY STRAP BOTTOM ROW BEHIND THE TOP OF THE WALL TO BE MANAGED IN SUCH A MANNER AS TO OBLIVATE SCOUR BEHIND OR OVER THE TOP OF THE WALL.
9. THE CONTRACTOR IS TO PROVIDE A SAMPLE AND THE PRODUCT SPECIFICATIONS OF THE RETAINING BLOCK TYPE FOR APPROVAL BY THE ENGINEER PRIOR TO PROCURING THE RETAINING BLOCKS FOR CONSTRUCTION.

SCALE (mm)

[illegible]

REV	DESCRIPTION	BY	DATE

Professional person S.SIRPUTH PrTechEng Registration 2014701

CLIENT



PROJECT **eTHEKWINI INCREMENTAL  
SERVICES GUMTREE ROAD,  
KENVILLE, WARD 34**

## DETAILS

## TYPICAL DRY STACK RETAINING WALL DETAILS



SUITE ESS108 STRATHMORE PARK, 305 MUSGRAVE ROAD, MUSGRAVE, DURBAN  
e-mail : [admin@mapafrica.co.za](mailto:admin@mapafrica.co.za)  
website : [www.mapafrica.co.za](http://www.mapafrica.co.za)  
FAX (031) 3092929 TEL. (031) 3095831

DESIGNED	Z.M	COPYRIGHT RESERVED	SCALES
DRAWN	Z.M		AS SHOWN
APPROVED	A.S	PL	DATE 2022.09.1
DRAWING No.		557/GUMT-PH2/904	
		REV	P