

# Boiler PB450 Coal Conveyor BOQ & EVALUATION

## CRITERIA

ITEM	QUANTITY	COMPLY/NOT COMPLY	PRICE
Geared motor drive with sprocket	1		
Plummer blocks with bearings and taper locks and nuts	2		
Cover structure top box	1		
Conveyor chain	1		
Conveyor chain drive shaft	1		
New chain sprocket	1		
Drive chain	10 meters		
Master links	2		
Half links	2		
Geared idler roller	1		
Idler roller flange bearings	2		
New idler shaft	1		
Labour costs (optional)			
<b>TOTAL</b>			
<b>VAT (If Applicable)</b>			
<b>Grand Total</b>			

**N.B: Works scope:**

1. Remove completely existing damaged chain.
2. Remove all above BOQ items and prepare for installation of the new.

3. Install all new BOQ items.
4. Install and align the new conveyor chain.
5. Lock conveyor chain sprocket into position.
6. Install drive chain and set tension correctly.
7. Test run without load and lubricate all moving parts accordingly.
8. Load and commission.
9. Hand over.