

TENDER NUMBER: TNPA/2024/11/0006/82453/RFP
FOR THE: REHABILITATION OF THE SHIP REPAIR FACILITY IN THE PORT OF MOSSEL BAY FOR A PERIOD OF TWENTY-FOUR (24) MONTHS
REQUEST FOR INFORMATION

RFI No. 3 **Date:** **Friday, 09 January 2026** **Company:** **H&I**

Query No.	Applicable section in tender documents	Page	Section / Item No	Information Required	TNPA Response
1	ECC3			Please clarify under which pay item must we price the Slipway Sub-station.	The substation building is included in the building works and electrical components are included in the electrical section
2	BOQ		Section 5, Item 29, BOQ 1	Please clarify under which pay item must we price the construction of the pump station, Item 29 of Section 5 only refer to the Mechanical equipment	Building works under building works section. Mechanical and electrical works under the respective sections.
3	BOQ			Please advise under which pay item we must price for the cable rubbing strips	
4	BOQ		Section 5, BOQ , Item 7, 8 and 9	Main & Side slip cradle sets: Supply and installation of 2 "Main and side slip cradle sets" complete as detailed in BOQ and / or Part C3 Scope of works and detailed construction drawings, inclusive of diving. What is the definition of cradle sets? What does this item refer too? If it refers to Wheel sets then the quantity is incorrect	Wheel sets, Please price for the number of wheel sets as per BOQ
5	BOQ		Section 5, BOQ 1 Item 10,11,12	Docking frames and Access Bridges: 4no.off frames for the main cradle and 6no.off frames for the side slip cradle. The tonnage stated is inclusive of all the docking frames and associated components. The Contractor shall supply the docking frames complete, with all associated parts assembled. The details and components of a complete main cradle docking frame and a complete side cradle docking frame are shown on the relevant drawings supplied to the Contractor. Contractor to supply and install the docking frames complete, with all associated parts assembled. The BOQ quantity of 75 no does calculate and we believe the unit should be Tons and not Number for these items. Please Clarify.	Unit is tons
6	BOQ			Please provide detailed cross section of 450x450 precast stormwater drain proposed	1002-011-1004 TYPICAL CHANNEL AND GRID INLET DETAILS
6					