

ERRATUM: TENDER NOTICE NUMBER 1

The following tender was previously advertised on the National Treasury at: www.etenders.gov.za on the 18 July 2023.

BID NUMBER: 10341477

DESCRIPTION: MINOR REPAIRS FOR THE PRETORIA TRACTION SUBSTATION

Take note of the following updates:

1. Prospective bidders to note that PRASA has updated bid /tender document due to the above mentioned changes. Therefore, PRASA requests all prospective bidders to utilise the latest updated bid/tender document uploaded on the 27 July 2023, when responding to this tender. Bidders are encouraged to use the latest updated bid/tender document as it is the one that will be used in the evaluation of bids.

2 Item number 11,12,13,14 and 15 were mistakenly omitted on the BOQ.

SECTION 10

BOQ/ PRICING SCHEDULE

Material Number	Description	Unit	Qty	Rate/unit (Excl VAT)	Total Price (Excl VAT)
1	Removal and transportation of old equipment from site to Rebecca stores	SUM	LOT	R.....	R.....
2	Supply deliver and install 44KV three phase SF6 Primary Circuit breaker, including filling up the SF6 gas in the breaker and all the associated works. As per clause 3.1.	EACH	1	R.....	R.....
3.	Supply Deliver and install single core feeder cable (500mm ²) XLPE copper cable and all associated works. As per clause 3.2.	M	25	R.....	R.....
4.	Supply deliver and install (127mm x12.5mm) aluminium busbar between the rectifier and the reactor coil, and all the associated works. As per clause 3.3.	M	6	R.....	R.....
5.	supply, delivery and installation of switch interlocking mechanism of unit B rectifier bay	EACH	1	R.....	R.....
6.	Supply and deliver Rectifier Temperature Card	EACH	5	R.....	R.....
7.	Supply and deliver Rectifier Diode monitor Card for 24 diodes rectifier.	EACH	5	R.....	R.....
8	Supply and deliver Electronic Control systems card of the rectifier box.	EACH	5	R.....	R.....
9.	Transformer oil Purification of 3340KVA, 44KV/3KV Traction Transformer at Pretoria Traction substation. As per clause 3.4.	SUM	1	R.....	R.....

10.	Testing of 3340KVA, 44KV/3KV Traction Transformer at Pretoria Traction substation. As per clause 3.4.	SUM	1	R.....	R.....
11	Installation of indoor earthing for RUA using 95mm copper cable and all associated works	1	SUM	R.....	R.....
12	Cleaning of oil spillage on the Transformer bay.	1	SUM	R.....	R.....
13	Supply and install Rectifier control Relays in the control Panel	4	EACH	R.....	R.....
14	Testing of 3340KVA, 44KV/3KV Traction Transformer at Pretoria Traction substation. As per clause 3.4.	1	SUM	R.....	R.....
15	Supply and deliver 210 litres drum of transformer oil to be topped up in the transformer	5	SUM	R.....	R.....
	Total Excluding VAT			R.....	
	VAT @ 15%			R.....	
	GRAND TOTAL			R.....	