

6. The Tenderers shall allow opposite each of the clauses whatever costs and charges he may consider necessary for the carrying out, complying with and due observance of the provisions, conditions and requirements set out herein. Only priced items will be considered in respect of any adjustment of this Section. Any items left unpriced will be understood to be provided free of charge and no claim for any extras arising out of the Tenderer's omission to price any item will be entertained.

7. Where modifications or amendments as described are made, such modifications and/or amendments shall supercede any conflicting provisions in the relevant clauses of the Standard Preliminaries or the Principal Building Agreement and the Tenderer shall make due allowance for whatever costs and charges he may consider necessary for the carrying out and observance of the provisions of the clauses as modified and/or amended.

8. Where any item is not relevant to this specific contract, such item is marked N/A.

9. If Alternative A as set out in clause B10.3 hereinafter is to be used for the adjustment of the preliminaries, each item priced is to be allocated to one or more of the three categories by insertion of "F", "V", "T" as the case may be against the price in the "rate" column immediately preceding the "amount" column, where "F" denotes a fixed amount (amount not to be varied), "V" denotes an amount variable in proportion to value, and "T" denotes an amount proportionate to time.

Carried to Collection

R

Section 1
Bill No. 1
Preliminaries

SECTION A: PRINCIPAL BUILDING AGREEMENT

DEFINITIONS

Definitions and interpretation (Clause 1).

1 F: V: T:

Item

OBJECTIVE AND PREPARATION

Offer, acceptance and performance (Clause 2).

2 F: V: T:

Item

Documents (Clause 3).

Clause 3.1 is deleted and substituted with: 'This tender is for a Government Contract. No Payment Guarantee will be provided.'

Clause 3.3 is deleted and substituted with:

The principal agent shall complete the schedule and arrange for formal signing of the agreement once the priced bill of quantities/lump sum document, security, insurances and waiver of lien, where acceptable, have been provided and effected'.

3 F: V: T:

Item

Design responsibility (Clause 4).

4 F: V: T:

Item

Employer's agents (Clause 5).

5 F: V: T:

Item

Site representative (Clause 6).

6 F: V: T:

Item

Compliance with regulations (Clause 7).

7 F: V: T:

Item

Carried to Collection

R

Section 1
Bill No. 1
Preliminaries

	Works risk (Clause 8)			
8	F: V: T: Indemnities (Clause 9). Clause 9.1.1 is deleted and substituted with: Claims from other parties consequent upon death of bodily injury or illness of any person or physical loss or damage to any property, other than the works, arising out or due to the execution of the works or occupation of the site by the contractor or his sub contractors'.	Item		
9	F: V: T: Works insurances (Clause 10).	Item		
10	F: V: T: Liability insurances (Clause 11).	Item		
11	F: V: T: Effecting insurances (Clause 12).	Item		
12	F: V: T: State Provisions (Clause 13).	Item		
13	F: V: T: Security (Clause 14).	Item		
14	F: V: T: <u>EXECUTION</u> Preparation for and execution of the works (Clause 15).	Item		
15	F: V: T: Access to the works (Clause 16).	Item		
16	F: V: T:	Item		
	Carried to Collection		R	
	Section 1 Bill No. 1 Preliminaries			

	Contract instructions (Clause 17).			
17	F: V: T: Setting out of the works (Clause 18.3). The contractor shall notify the principal agent if any encroachments of adjoining foundations, buildings, structures, pavements, boundaries, etc., exist in order that the necessary arrangements may be made for the rectification of any such encroachments. Should incorrect information be given to the contractor in terms of 18.1 and 18.2, which causes the incorrect setting out of the works, the contractor shall not be liable for such incorrect setting out.	Item		
18	F: V: T: Assignment (Clause 19).	Item		
19	F: V: T: Nominated subcontractors (Clause 20).	Item		
20	F: V: T: Selected subcontractors (Clause 21).	Item		
21	F: V: T: Employer's Direct contractors (Clause 22).	Item		
22	F: V: T: Contractor's Domestic subcontractors (Clause 23).	Item		
23	F: V: T: <u>COMPLETION</u> Practical completion (Clause 24).	Item		
24	F: V: T: Works completion (Clause 25).	Item		
Carried to Collection			R	
Section 1 Bill No. 1 Preliminaries				

25	<p>F: V: T:</p> <p>Final completion (Clause 26).</p> <p>Latent defects liability period (Clause 27).</p> <p>Clause 27.0 is amended by the addition of the following clauses:</p> <p>"27.3 Any water leakage into the building, whether in the roof, external wall or other element of the building susceptible to water leakage shall, unless proven to be a design defect, or as a result of obvious storm damage, be classified as a latent defect in terms of clause 1.0 Definitions and Interpretations".</p> <p>"27.4 The Contractor shall attend to defects during the Defects Liability Period on a progressive basis, to the satisfaction of the Principal Agent and will not be permitted to wait until the end of the Defect Liability Period or until the amount of defects accumulates in order to attend to a comprehensive list of defects"</p>	Item		
26	<p>F: V: T:</p> <p>Sectional completion (Clause 28).</p>	Item		
27	<p>F: V: T:</p> <p>Revision of date for practical completion (Clause 29).</p>	Item		
28	<p>F: V: T:</p> <p>Penalty for non-completion (Clause 30).</p>	Item		
29	<p>F: V: T:</p> <p><u>PAYMENT</u></p> <p>Interim payment to the contractor (Clause 31).</p> <p>The inclusion of materials and goods stored off site in the amount authorised for payment in terms of clause 31.3 shall be at the sole discretion of the principal agent and such inclusion shall only be considered upon the provision, by the contractor, of an approved guarantee issued by a registered commercial bank.</p>	Item		
Carried to Collection			R	
<p>Section 1 Bill No. 1 Preliminaries</p>				

Where prices are submitted by the contractor or nominated/selected sub contractor during the progress of the works in respect of contract instructions or in regard to a claim under the terms of the contract and notwithstanding the fact that such prices may be used in an interim payment certificate, there is to be no presumption of acceptance. Should the principal agent wish to accept any such prices prior to the issue of the final certificate, it will be in writing.

Adjustment to the contract value (Clause 32).

30 F: V: T:

Item

Recovery of expense and loss (Clause 33).

31 F: V: T:

Item

Final account and final payment (Clause 34).

32 F: V: T:

Item

Payment to other parties (Clause 35).

33 F: V: T:

Item

CANCELLATION

Cancellation by Employer - Contractor's default (Clause 36).

34 F: V: T:

Item

Cancellation by Employer - Loss and damage (Clause 37).

35 F: V: T:

Item

Cancellation by Contractor - Employer's default (Clause 38).

36 F: V: T:

Item

Cancellation - Cessation of the works (Clause 39).

37 F: V: T:

Item

Carried to Collection

R

Section 1
Bill No. 1
Preliminaries

DISPUTE

Dispute Settlement (Clause 40)

38 F: V: T:

Item

SUBSTITUTE PROVISIONS

State Clauses (Clause 41)

39 F: V: T:

Item

CONTRACT VARIABLES

The Schedule: Pre-Tender information (Clause 42).

40 F: V: T:

Item

CONTRACTING AND OTHER PARTIES (Clause 42.1)

Employer: The Mvula Trust

Postal Address: 67 Devereux Avenue, Vincent, East London

Telephone: 043 726 2255

Facsimile: 043 726 5967

Physical address: 67 Devereux Avenue, Vincent, East London

Principal Agent: The Mvula Trust

Postal Address: 67 Devereux Avenue, Vincent, East London

Telephone: 043 726 2255

Facsimile: 043 726 5967

Physical address: 67 Devereux Avenue, Vincent, East London

Carried to Collection

R

Section 1
Bill No. 1
Preliminaries

CONTRACT DETAILS (Clause 42.2)

Clause 42.2.1

Works Description: Construction of new ablution facilities.

Clause 42.2.2

Site Description: The site is the existing school.

Clause 42.2.3

Work or Installations by Others: NIL

Clause 42.2.4

This Agreement is for a State Contract :- Yes

Payment will be made for materials and goods:- Yes

Dispute resolution :- Mediation (in terms of clause 40) followed by litigation.

Arbitration rules as recommended by the Association of Arbitrators (SA) :- N/A

Clause 42.2.5

Date on which possession of the site is intended to be given on :-

To be advised.

Clause 42.2.6

Period for the commencement of the works after the contractor takes possession of the site :- 5 Working days.

Completion in Sections are required : NO

Clause 42.2.7

Intended date of practical completion and the penalty per calendar day for the works as a whole :-

Carried to Collection

Section 1
Bill No. 1
Preliminaries

R

DOCUMENTS (Clause 42.4)

Clause 42.4.1

Waiver of the contractor's lien is required :- YES

Clause 42.4.2

Number of construction document copies to be supplied to the Contractor free of charge :- 1

Clause 42.4.3

Bills of Quantities drawn up in accordance with :-

Standard System of Measuring Building Work - Seventh Edition including all amendments

Clause 42.4.4

Number of days for submission of priced documents : 5 working days from the Letter of Appointment.

Clause 42.4.5

JBCC Engineering General Conditions are to be included in the documents :- No

Clause 42.4.6

The contract value is to be adjusted using CPAP:- NO

SECTION B: PRELIMINARIES

DEFINITIONS AND INTERPRETATION (B1)

Definitions and Interpretation (B1)

41 F: V: T:

Item

DOCUMENTS (B2)

Checking of documents (B2.1)

Carried to Collection

R

Section 1
Bill No. 1
Preliminaries

Notwithstanding the issue of the tender drawings, it will remain the responsibility of the Tenderer to study all available drawings at the offices of the Principal Agent during normal working hours in order to acquaint himself with all the cost implications of the design, programming, phasing, etc.

42 F: V: T:

Item

Provisional Bills of Quantities (B2.2) YES

Prime Cost Amounts, Budgetary Allowances, Provisional Amounts, etc., contained herein may be omitted or reduced at the Principal Agent's sole discretion and the Contractor shall not be entitled to claim for any loss by way of reduction or omission of any discount, or percentage relating to Prime Cost Amounts, Budgetary Allowances, Provisional Amounts, Provisional Quantities, etc., or loss of profit related thereto.

43 F: V: T:

Item

Availability of construction documentation (B2.3)

44 F: V: T:

Item

Interests of Agents (B2.4)

45 F: V: T:

Item

Priced documents (B2.5)

46 F: V: T:

Item

Tender submission (B2.6)

Notwithstanding anything contained in this clause, Tenders shall be valid for a period of 20 (Twenty) weeks from the closing date of tenders.

47 F: V: T:

Item

THE SITE (B3)

Defined works area (B3.1)

Carried to Collection

R

Section 1
Bill No. 1
Preliminaries

	<p>The area of the works to be occupied by the contractor, any restriction on the area and the limit of access or exit will be pointed out to the contractor by the principal agent on handing over of the site.</p> <p>Workmen employed on the site are to be restricted to the immediate area of the site and access thereto.</p> <p>The Tenderer shall make all necessary provision in all rates to take into account these requirements as no claims for extras arising from these matters will be subsequently entertained or admitted.</p>			
48	<p>F: V: T:</p> <p>Geotechnical investigation (B3.2)</p> <p>A desktop geotechnical report is available upon request.</p>	Item		
49	<p>F: V: T:</p> <p>Inspection of the Site (B3.3)</p>	Item		
50	<p>F: V: T:</p> <p>Existing premises occupied (B3.4)</p>	Item		
51	<p>F: V: T:</p> <p>Previous work - dimensional accuracy (B3.5)</p>	Item		
52	<p>F: V: T:</p> <p>Previous work - defects (B3.6)</p>	Item		
53	<p>F: V: T:</p> <p>Services - known (B3.7)</p>	Item		
54	<p>F: V: T:</p> <p>Services - unknown (B3.8)</p>	Item		
55	<p>F: V: T:</p> <p>Protection of trees (B3.9)</p>	Item		
Carried to Collection			R	
<p>Section 1 Bill No. 1 Preliminaries</p>				

56	F: V: T: Articles of value (B3.10)	Item		
57	F: V: T: Inspection of adjoining properties (B3.11)	Item		
58	F: V: T: <u>MANAGEMENT OF CONTRACT (B4)</u> Management of the Works (B4.1)	Item		
59	F: V: T: Programme for the Works (B4.2)	Item		
60	F: V: T: Progress meetings (B4.3)	Item		
61	F: V: T: Technical meetings (B4.4)	Item		
62	F: V: T: <u>SAMPLES AND SHOP DRAWINGS (B5)</u> Samples of materials (B5.1)	Item		
63	F: V: T: Workmanship samples (B5.2)	Item		
64	F: V: T: Shop drawings (B5.3)	Item		
65	F: V: T: <u>TEMPORARY WORKS AND PLANT (B6)</u> Deposits and fees (B6.1)	Item		
Carried to Collection			R	
Section 1 Bill No. 1 Preliminaries				

66 F: V: T:

Enclosure of the works (B6.2)

The contractor shall erect, maintain and remove at completion, hoardings, safety screens, barriers, access gates, covered gangways and the like as necessary for the enclosure of the works and elements thereof all for the protection of the public and others.

67 F: V: T:

Advertising (B6.3)

68 F: V: T:

Item

Item

Item

Carried to Collection

R

Section 1
 Bill No. 1
 Preliminaries

	Plant and equipment (B6.4)		
69	F: V: T:	Item	
	Main notice board (B6.5)		
	One notice board shall be provided by the Contractor		
70	F: V: T:	Item	
	Subcontractors notice board (B6.6) (N/A)		
71	F: V: T:	Item	
	<u>TEMPORARY SERVICES (B7)</u>		
	Location (B7.1)		
72	F: V: T:	Item	
	Water (B7.2)		
	The contractor shall provide water for the works in accordance with:		
	Alternative A (i.e. to be provided for by the Contractor).		
73	F: V: T:	Item	
	Electricity (B7.3)		
	The contractor shall provide electricity for the works in accordance with:		
	Alternative A (i.e. to be provided for by the Contractor).		
74	F: V: T:	Item	
	Telecommunication equipment (B7.4)		
	The contractor shall provide telephones on site for the works in accordance with:		
	Alternative A (i.e. to be provided for by the Contractor).		
75	F: V: T:	Item	
	Carried to Collection		R
	Section 1		
	Bill No. 1		
	Preliminaries		

	Ablution facilities (B7.5)		
	The contractor shall provide toilet facilities on site for the works in accordance with:		
	Alternative A (i.e. to be provided for by the Contractor).		
76	F: V: T:	Item	
	<u>PRIME COST AMOUNTS (B8)</u>		
	Responsibility for prime cost amounts (B8.1)		
77	F: V: T:	Item	
	<u>ATTENDANCE ON N/S SUBCONTRACTORS (B9)</u>		
	General Attendance (B9.1)		
78	F: V: T:	Item	
	Special Attendance (B9.2)		
79	F: V: T:	Item	
	Commissioning - fuel, water and power (B9.3)		
80	F: V: T:	Item	
	<u>FINANCIAL ASPECTS (B10)</u>		
	Statutory taxes, duties and levies (B10.1)		
	Provision is made in the Final Summary of these Bills of Quantities for the inclusion of Value Added Tax (VAT).		
81	F: V: T:	Item	
	Payment of Preliminaries (B10.2)		
82	F: V: T:	Item	
	Adjustment of Preliminaries (B10.3)		
83	F: V: T:	Item	
	Carried to Collection		
	Section 1		
	Bill No. 1		
	Preliminaries		

	Payment certificate cash flow (B10.4)				
84	F: V: T:	Item			
	Contractor information supply (B10.5)				
85	F: V: T:	Item			
	<u>GENERAL (B11)</u>				
	Protection of the Works (B11.1)				
86	F: V: T:	Item			
	Protection/isolation of existing/sectionally occupied works (B11.2)				
87	F: V: T:	Item			
	Site security (B11.3)				
88	F: V: T:	Item			
	Notice before covering work (B11.4)				
89	F: V: T:	Item			
	Disturbance (B11.5)				
90	F: V: T:	Item			
	Works cleaning and clearing (B11.6)				
91	F: V: T:	Item			
	Vermin (B11.7)				
92	F: V: T:	Item			
	Overhand work (B11.8)				
93	F: V: T:	Item			
	Carried to Collection		R		
	Section 1 Bill No. 1 Preliminaries				

SECTION C: SPECIFIC PRELIMINARIES

Section C: Specific Preliminaries:

C1. Proprietary branded products

The contractor shall take delivery of, handle, store, use, apply and/or fix all proprietary branded products in strict accordance with the manufacturer's instructions after consultation with the manufacturer's authorised representative.

94 F: V: T:

Item

C2. Trade Names, etc.

All materials, fittings, finishings, etc., specified hereinafter under a trade name, catalogue number or reference, must be exactly as described. The Architect's approval in writing must be obtained for the use of any alternative to the specification before the submission of tenders otherwise the specified materials, fittings, finishings, etc., will be assumed to have been allowed for in the tender.

The Contractor must take delivery of, handle, store, use, apply and/or fix all proprietary branded products in strict accordance with the manufacturer's instructions after consultation with the manufacturer's authorised representative.

95 F: V: T:

Item

C3. Contractors responsibility

The Employer, the Principal Agent and the other professional consultants shall not be responsible for any act or omission on the part of the Contractor which may result in any patent or latent defects, in materials or workmanship, breach or neglect of any local regulations. The Contractor shall at all times be responsible for any such neglect, deviation or wrong act, whether the same is discovered before or after the final certificate, or any other Certificate, has been approved.

96 F: V: T:

Item

Carried to Collection

R

Section 1
Bill No. 1
Preliminaries

<p>C4. Overtime</p> <p>Should overtime be required to be worked for any reason whatsoever, the costs of such overtime are to be borne by the contractor unless the principal agent has specifically authorised in writing, prior to the execution thereof, that costs for such overtime are to be borne by the employer.</p>			
<p>97 F: V: T:</p>	Item		
<p>C5. As built drawings</p> <p>The position of construction breaks and the extent of individual concrete pours are to be recorded by the contractor on the structural engineer's drawings and are to be submitted to the principal agent and the structural engineer for their records.</p> <p>Three full sets of as-built drawings shall be submitted to the Principal Agent no later than fourteen days after practical completion.</p>			
<p>98 F: V: T:</p>	Item		
<p>C6. Construction Instructions</p> <p>Contract instructions issued on site are to be recorded in triplicate in a site instruction book which is to be maintained on site by the Contractor. The Contractor shall supply and have available at the site of the works at all times, the following site books:</p> <p>a) Construction Instruction Book:</p> <p>Receiving and recording instructions in a suitable A4 size triplicate book kept on site. Instructions issued shall be recorded by the Architect or other Employer's Agents to whom the Architect has delegated authority to in the book.</p> <p>Only instructions issued in such book shall be recognised.</p> <p>b) Daily Record Book:</p>			
<p style="text-align: right;">Carried to Collection</p> <p>Section 1 Bill No. 1 Preliminaries</p>		R	

	<p>The Contractor shall record in triplicate in a suitable A4 size triplicate book kept at the site, a daily record of work done, all site visits by the Principal Agent and other professional personnel and all events affecting the Works, such as progress, issue of plans, breakdown of machinery, etc. The labour, plant and material on site shall be recorded as well as work performed. Entries must be made by the Contractor and must be signed and forwarded to the Principal Agent for his counter-signature on a daily basis. Copies of these records shall be for the Architect, Quantity Surveyor and Contractor.</p>			
99	<p>F: V: T:</p> <p>C7. Labour record</p> <p>At the end of each week the contractor shall provide the principal agent with a written record, in schedule form, reflecting the number and description of tradesmen and labourers employed by him and all subcontractors on the works each day.</p>	Item		
100	<p>F: V: T:</p> <p>C8. Plant record</p> <p>At the end of each week the contractor shall provide the principal agent with a written record, in schedule form, reflecting the number, type and capacity of all plant, excluding hand tools, currently used on the works.</p>	Item		
101	<p>F: V: T:</p> <p>C9. Encroachment</p> <p>During the course of the building operations, the Contractor shall be held entirely responsible for any encroachment onto any adjoining properties, buildings, etc., or servitudes and the cost of any remedial measures as required by the Principal Agent shall be borne by the Contractor.</p>	Item		
102	<p>F: V: T:</p> <p>C10. Method Statement</p>	Item		
Carried to Collection			R	
<p>Section 1 Bill No. 1 Preliminaries</p>				

	<p>The Tenderer shall produce, when required to do so by the Principal Agent, a Method Statement outlining the methods of construction and labour and plant resources that he proposes to use in the execution of the Works. Any approval given or observation made by the Principal Agent shall not relieve the Contractor of his sole responsibility to adopt the methods of construction and to provide the labour and plant resources necessary for the due and proper timeous execution of the Works.</p>			
103	<p>F: V: T:</p> <p>C11. Unauthorised Persons/Workmen on Premises</p> <p>The Contractor shall at all times strictly exclude all unauthorised persons from the Works and the site and shall set up notice boards to that effect.</p> <p>No workmen or labourers (except security guards) are to be allowed under any circumstances to sleep or deposit any kit on the premises. The Contractor must provide any necessary independent shelter or shed required for any labour or watchmen on site, to the approval of the Employer.</p>	Item		
104	<p>F: V: T:</p> <p>C12. Mode of Procedure</p> <p>Notwithstanding anything to the contrary contained herein the Principal Agent at all times reserves the right to direct the order in which the various parts of the Contract are to be executed. The Contractor shall give priority to any individual section or portion of the Works that, in the opinion of the Principal Agent, requires to be expedited.</p> <p>Should it appear, in the Principal Agent's opinion, that work in any area is not being executed in accordance with the requirements of the Contract Programme, the Contractor shall provide additional manpower and resources and shall work additional overtime and do everything else required to bring the work back to programme to the satisfaction of the Principal Agent and to the Contractor's cost.</p>	Item		
105	<p>F: V: T:</p>	Item		
Carried to Collection			R	
<p>Section 1 Bill No. 1 Preliminaries</p>				

	<p>C13. Location of Temporary Buildings and Temporary Services</p> <p>The Contractor shall provide all necessary temporary works, including temporary roads, tracks, crossings, hardstanding and services, hoardings, dust screens, tunnelling, etc., required for his own and sub-contractors use during the construction and maintenance period.</p> <p>There is no guarantee given or implied that Site conditions will be such that the Contractor will be able to erect such temporary works, roads, hardhats, offices, stores and temporary accommodation within the site boundaries and it shall be the Contractor's responsibility to adopt whatever measures he deems necessary in this regard and to obtain all necessary permission and pay all costs in connection therewith.</p>			
106	<p>F: V: T:</p> <p><u>C14. Office accommodation</u></p> <p>The contractor shall provide, maintain and remove on practical completion air conditioned office accommodation with suitable tables and chairs for meetings to be held on the site. Such offices shall be kept clean and fit for use at all times [12.2.18]</p>	Item		
107	<p>F: V: T:</p> <p><u>C15. Storage Facilities</u></p>	Item		
108	<p>The Contractor shall provide a Container for storage of materials.</p>	Item		
109	<p>F: V: T:</p> <p>C16. Removal and Making Good of Temporary Works, etc, on Completion</p> <p>The Contractor shall remove (except where specifically stated otherwise) all temporary works, roads, services and the like used for this contract and shall make good to the entire satisfaction of the Principal Agent any damage resulting therefrom.</p>	Item		
110	<p>F: V: T:</p>	Item		
Carried to Collection			R	
<p>Section 1 Bill No. 1 Preliminaries</p>				

111 SUB - TOTAL: FIXED ITEMS

Item

112 SUB - TOTAL: VALUE - RELATED ITEMS

Item

113 SUB - TOTAL: TIME - RELATED ITEMS

Item

Carried to Collection

R

Section 1
Bill No. 1
Preliminaries

CLUSTER 121
HORTON PRIMARY SCHOOL
THE MVULA TRUST SAFE PROGRAMME

Section 1

Bill No. 1

Preliminaries

COLLECTION

Total Brought Forward from Page No.

**Page
No**

Amount

1

2

3

4

5

6

7

8

9

10

11

12

13

14

15

16

17

18

19

20

Carried Forward

R

Section 1

Bill No. 1

Preliminaries

Section 1

Bill No. 1

Preliminaries

COLLECTION

Brought Forward

Total Brought Forward from Page No.

**Page
No**

Amount

R

21

22

23

24

Carried Forward to Summary of Section No. 1

R

Section 1

Bill No. 1

Preliminaries

Item No	Quantity	Rate	Amount
<u>SECTION 1</u>			
<u>BILL No. 2</u>			
<u>HEALTH AND SAFETY</u>			
<u>MODEL PREAMBLES</u>			
The tenderer is referred to the "Model Preambles for Trades 2008" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates.			
<u>SUPPLEMENTARY PREAMBLES</u>			
Supplementary preambles and/or specifications are incorporated in these bills of quantities to satisfy the requirements of this project. Such supplementary preambles and/or specifications shall take precedence over the provisions of the General Preambles.			
The contractor's prices for all items throughout these bills of quantities shall take account of and include where applicable for all of the obligations, requirements and specifications given in the General Preambles and in any supplementary preambles and/or specifications.			
Prior to pricing the principal contractor must familiarize him/herself with the Occupational Health and Safety Act No. 85 Of 1993, Construction Regulations 2014, other relevant Regulations and Standards as well as project specific Health & Safety specifications.			
The items in this Bill do not contain quantities hence the Contractor must insert his own quantities based on his individual requirements to comply with the Health and Safety obligations and demands of the Occupational Health and Safety Act No. 85 of 1993, Construction Regulations 2014, other relevant Regulations and Standards as well as project specific Health & Safety Specifications.			
Carried to Collection			
			R
Section 1 Bill No. 2 Health and Safety			

The costs included herein must incorporate Community Liaison Officer (CLO).

OCCUPATIONAL HEALTH AND SAFETY

General:

1	Preparation of Contractor's site specific Health and Safety Plan.		Item
2	Submission of the Health and Safety File.		Item
3	Principal Contractor's initial obligations in respect of the OHS Act and Construction Regulations.		Item
4	Principal Contractor's time related obligations in respect of the OHS Act and Construction Regulations for the entire construction period.		Item
5	Provision of full time Health and Safety Officer for the entire construction period.		Item
6	Induction training of personnel.	No	20
7	Provision of first aid boxes.	No	1
8	SANS approved weld mesh type temporary barrier fencing 1,8m high covered with a net fixed to and including 100mm diameter gum poles set securely min 300mm deep in ground at max 3m spacing including excavation, backfilling, etc	m	50
9	Extra over mesh fence for pedestrian gate size 1.8 x 1,8m high.	No	1
<u>Provision for Personal Protective Equipment and Protective Clothing:</u>			
10	Reflective vests.	No	20
11	Hard hats.	No	20
12	Protective foot wear.	No	20
13	Ear Plugs.	No	900

Carried to Collection

R

Section 1
Bill No. 2
Health and Safety

[illegible]

Section 1

Bill No. 2

Health and Safety

COLLECTION

Total Brought Forward from Page No.

**Page
No**

Amount

27

28

29

Carried Forward to Summary of Section No. 1

R

Section 1

Bill No. 2

Health and Safety

[illegible]

Item No	Quantity	Rate	Amount
<p><u>SECTION 2</u></p> <p><u>BILL No. 1</u></p> <p><u>DEMOLITIONS</u></p> <p><u>MODEL PREAMBLES</u></p> <p>The tenderer is referred to the "General Preambles for Trades 2017" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates.</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>View site</u></p> <p>Before submitting his tender the tenderer shall visit the site and satisfy himself as to the nature and extent of the work to be done and the value of the materials contained in the buildings or portions of the buildings to be demolished. No claim for any variations of the contract sum in respect of the nature and extent of the work or of inferior or damaged materials will be entertained</p> <p><u>Explosives</u></p> <p>No explosives whatsoever may be used for demolition purposes unless otherwise stated.</p> <p><u>General</u></p> <p>Water supply pipes and other piping in ground that may be encountered and found necessary to disconnect or cut, shall be effectually stopped off or grubbed up and removed, and any new connections that may be necessary shall be made with proper fittings to the satisfaction of the principal agent.</p> <p>Unless otherwise described all materials are to become the property of the contractor and are to be removed from the site.</p>			
<p>Carried to Collection</p>			<p>R</p>
<p>Section 2 Bill No. 1 Demolitions</p>			

Removal of asbestos material

All preparatory work, alterations, etc., to existing asbestos cement roof sheeting, gutters, rainwater pipes, etc., is to be carried out strictly by an approved and certified specialist company and in accordance with statutory requirements (Occupational Health and Safety Act, 1993 - Asbestos Regulations 2001) and all necessary precautions must be taken when working with and disposing of asbestos cement products and the disposal of waste water resulting from cleaning operations, etc.

The following shall apply in respect of asbestos removal

The removal of asbestos shall be carried out by a certified entity, registered in accordance with the Occupational Health and Safety Act, 1993 and the Asbestos Regulations 2001

Asbestos in all forms/building elements that is to be removed, shall be carried out in strict accordance with aforementioned regulation and a certificate issued by the entity as contemplated in the above, shall be provided per block for the removal thereof, where the term block shall in this context refer to any single, free standing building structure, regardless of size or purpose

Corresponding disposal certificates shall be issued by the facility at which the asbestos is disposed off, with said facility to, prior to the disposal of any asbestos material provide satisfactory proof that the facility is duly registered and fully compliant in terms of the act, to receive the asbestos material

Under no circumstances is the Contractor nor any of his duly authorised representatives to sell and/or give away asbestos material to any member/s of the school community, the community in general or the public at large. Should this be found to be occurring, the Contractor will be held responsible contractually and may further be prosecuted criminally

The cost for complying with the above, and all requirements of regulation as reflected above is to be priced for in terms for removal of asbestos material. No further claims in this regard will therefore be entertained

Carried to Collection

Section 2
Bill No. 1
Demolitions

R

DEMOLISHING AND REMOVING

1	Demolish pit latrine zinc iron structure comprising on base slab, corrugated roof sheeting, approximate size 10 x 3m wide with 3,5m high top structure and 2,0m deep pit. Demolition is to only commence once the latrine has been completely emptied (elsewhere measured).	No	5
2	Cart away rubble from demolitions and dispose off site.		Item
3	Backfill existing hole with G7 fill material in max. 150mm layers and compact to 95% MOD AASHTO density.	m3	300
4	Allow for compaction tests by an approved laboratory to determine density of filling material.	No	7

SUNDRIES

Desludging

5	Clean out pit latrine by desludging including removal of all debris and waste including solid waste as per Health and Safety requirements and make good on completion including disposing of all debris and waste at an authorised municipal waste disposal facility. Contractor to price per seat	No	26
6	Issue of Certificate of Waste Disposal.		Item

Carried to Collection

R

Section 2
Bill No. 1
Demolitions

Section 2

Bill No. 1

Demolitions

COLLECTION

Total Brought Forward from Page No.

**Page
No**

Amount

32

33

34

Carried to Final Summary

R

Section 2
Bill No. 1
Demolitions

R

Dewatering of excavations:

The Contractor shall allow for removing seepage and other water from subterranean sources from the excavations by pumping, baling or otherwise. Accurate records of all such dewatering shall be kept to determine the total volume of water so removed and a clear distinction shall be made between water from subterranean sources and other water

Density testing on filling:

Rates for filling, etc. shall include for all density and soil type testing to prove that the specified compaction is achieved. When additional testing is done on instruction of the Principal Agent and these tests are successful, they will be paid for additionally.

Imported fill:

"Filling and bedding to trenches etc. to be in compliance with SABS 1200 DB and LB respectively"

Classification of excavated material

"Hard rock" shall mean granite, quartzitic sandstone or other rock of similar hardness, the removal of which requires drilling, wedging and splitting or the use of explosives.

"Soft rock" shall mean hard material, the removal of which warrants the use of pneumatic tools and includes hard shale, ferricite, compact outcrop and material of similar hardness.

"Earth" shall mean all ground other than that classified as "hard rock" or "soft rock" and shall include made-up ground and any loose stones or pieces of concrete not exceeding 0,03m³ in volume.

Carried to Collection

R

Section 3
Bill No. 1
Earthworks (Provisional)

<u>EXCAVATION OTHER THAN BULK</u>							
<u>Excavation in earth not exceeding 2m deep:</u>							
1	Trenches.	m3	13				
	A0 : 3 A1 : 3 A2 : 3 A3 : 3						
2	Holes.	m3	110				
	A0 : 22 A1 : 26 A2 : 27 A3 : 35						
3	Reduced levels under floors.	m3	44				
	A0 : 11 A1 : 11 A2 : 12 A3 : 10						
<u>Extra over trench and hole excavations in earth for excavation in:</u>							
4	Soft rock.	m3					
	A0 : 0.0 A1 : 0.0 A2 : 0.0 A3 : 0.0						
5	Hard rock.	m3					
	A0 : 0.0 A1 : 0.0 A2 : 0.0 A3 : 0.0						
<u>Extra over all excavations for carting away:</u>							
6	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the contractor.	m3	167				
	A0 : 36 A1 : 40 A2 : 43 A3 : 48						
<u>Risk of collapse of excavations:</u>							
7	Sides of trench and hole excavations not exceeding 1,5m deep.	m2	39				
	A0 : 10 A1 : 9 A2 : 11 A3 : 9						
8	Ditto, but from ground level to exceeding 1,5m.	m2	134				
	A0 : 30 A1 : 33 A2 : 33 A3 : 38						
<u>Keeping excavations free of water:</u>							
9	Keeping excavations free from mud and all water including subterranean sources.		Item				
<u>EARTH FILLING, ETC.</u>							
<u>Earth filling obtained from the excavations and / or prescribed stock piles on site (minimum G7 tested material) compacted to 93% Mod. AASHTO density:</u>							
10	Backfilling to trenches, holes, etc.	m3	2				
	A0 : 0 A1 : 1 A2 : 1 A3 : 1						
Carried to Collection							
Section 3							
Bill No. 1							
Earthworks (Provisional)							

11	Under floors, steps, pavings, trenches, etc. A0 : 3 A1 : 3 A2 : 3 A3 : 3 <u>Imported G5 filling, selected and supplied by the Contractor, including depositing in layers not exceeding 150mm thick and compacting to 98% modified AASHTO dry density to trenches, holes, etc.</u>	m3	12
12	Under floors, steps, pavings, trenches, etc. A0 : 5 A1 : 6 A2 : 7 A3 : 7 <u>Imported G7 filling, selected and supplied by the Contractor, including depositing in layers not exceeding 150mm thick and compacting to 98% modified AASHTO dry density to holes, trenches etc.</u>	m3	25
13	Under floors, steps, pavings, trenches, etc. A0 : 4 A1 : 4 A2 : 5 A3 : 5	m3	18
14	Backfilling to holes, trenches, etc. A0 : 2 A1 : 2 A2 : 2 A3 : 2 <u>Coarse river sand filling supplied by the contractor:</u>	m3	9
15	Under floors etc. A0 : 1 A1 : 1 A2 : 2 A3 : 2 <u>Compaction of surfaces:</u>	m3	6
16	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density. A0 : 28 A1 : 29 A2 : 33 A3 : 32 <u>Prescribed density tests on filling:</u>	m2	122
17	Allow for compaction tests by an approved laboratory to determine density of filling material. A0 : 8 A1 : 8 A2 : 8 A3 : 8	No	32

Carried to Collection

Section 3
Bill No. 1
Earthworks (Provisional)

R

SOIL POISONING

**Approved brand of anti-termite soil poison applied
by a Registered Pest Control company and
guaranteed against termite infestation for ten years:**

18	Under floors, etc., including forming and poisoning shallow furrows against foundation walls, etc., filling in furrows and ramming.	m2	79
	A0 : 19 A1 : 19 A2 : 22 A3 : 18		
19	To bottoms and sides of holes, etc.	m2	177
	A0 : 39 A1 : 43 A2 : 44 A3 : 52		

Carried to Collection

R

Section 3
Bill No. 1
Earthworks (Provisional)

Section 3

Bill No. 1

Earthworks (Provisional)

COLLECTION

Total Brought Forward from Page No.

**Page
No**

Amount

36

37

38

39

40

Carried Forward to Summary of Section No. 3

R

Section 3

Bill No. 1

Earthworks (Provisional)

Formwork:

Descriptions of formwork shall be deemed to include use and waste only (except where described as left in or permanent), for fitting together in the required forms, wedging, plumbing and fixing to true angles and surfaces as necessary to ensure easy release during stripping and for reconditioning as necessary before re-use.

The vertical strutting shall be carried down to such construction as is sufficiently strong to afford the required support without damage and shall remain in position until the newly constructed work is able to support itself.

Formwork to soffits of solid slabs etc., shall be deemed to be to slabs not exceeding 250mm thick unless otherwise described.

Formwork to sides of bases, pile caps, ground beams, etc., will only be measured where it is prescribed by the Engineer for design reasons. Formwork necessitated by irregularity or collapse of excavated faces will not be measured and the cost thereof shall be deemed to be included in the allowance for taking the risk of collapse of the sides of the excavations, provision for which is made in Earthworks.

Carried to Collection

Section 3
Bill No. 2
Concrete, Formwork and Reinforcement

R

**UNREINFORCED CONCRETE CAST AGAINST
EXCAVATED SURFACES**

15Mpa/19mm Concrete

1	Surface blinding under footings and bases.	m3	4
	A0 : 1 A1 : 1 A2 : 1 A3 : 1		

**REINFORCED CONCRETE CAST AGAINST
EXCAVATED SURFACES**

30MPa/20mm concrete:

2	Raft slab on waterproofing.	m3	26
	A0 : 6 A1 : 6 A2 : 7 A3 : 6		
3	Ground base slabs.	m3	9
	A0 : 2 A1 : 2 A2 : 2 A3 : 3		

**REINFORCED CONCRETE CAST IN
FORMWORK**

30MPa/20mm concrete:

4	Suspended Slabs.	m3	8
	A0 : 2 A1 : 2 A2 : 2 A3 : 2		
5	Cavity walls.	m3	14
	A0 : 3 A1 : 3 A2 : 4 A3 : 4		

TEST BLOCKS

Test blocks:

6	Making and testing of 150x150x150mm concrete strength test cubes (Provisional).	No	24
	A0 : 6 A1 : 6 A2 : 6 A3 : 6		

Carried to Collection

Section 3
Bill No. 2
Concrete, Formwork and Reinforcement

R

FINISHING TOP SURFACE OF CONCRETE

Finishing top surfaces of concrete smooth with a wood float:

7	Surface beds, suspended slabs, base slabs, etc.	m2	122
	A0 : 28 A1 : 29 A2 : 33 A3 : 32		

Finishing top surfaces of concrete smooth with a steel float:

8	Surface beds, suspended slabs, etc.	m2	19
	A0 : 4 A1 : 4 A2 : 5 A3 : 6		

Charmfers at corners

9	19 x 19mm triangular fillet at internal corners of bottom slab.	m	49
	A0 : 11 A1 : 12 A2 : 12 A3 : 14		

ROUGH FORMWORK (DEGREE OF ACCURACY III)

Rough Formwork to Sides:

10	Edges, risers, ends and reveals not exceeding 300mm high or wide.	m	53
	A0 : 12 A1 : 13 A2 : 13 A3 : 15		

Permanent Formwork:

11	Soffit of slab over pit.	m2	37
	A0 : 7 A1 : 9 A2 : 9 A3 : 12		

Extra on permanent formwork for boxing or blocking in or boxing out to form:

12	835mm diameter circular opening through 370mm thick slab.	No	8
	A0 : 2 A1 : 2 A2 : 2 A3 : 2		
13	450mm Diameter opening through 255mm thick slab.	No	4
	A0 : 0 A1 : 0 A2 : 1 A3 : 3		
14	200mm Diameter opening through 255mm thick slab.	No	5
	A0 : 2 A1 : 3 A2 : 0 A3 : 0		
15	150mm Diameter opening through 255mm thick slab.	No	2
	A0 : 0 A1 : 0 A2 : 2 A3 : 0		

Carried to Collection

Section 3
Bill No. 2
Concrete, Formwork and Reinforcement

R

16	110mm Diameter opening through 255mm thick slab. A0 : 2 A1 : 3 A2 : 3 A3 : 3	No	11
	<u>SMOOTH FORMWORK (DEGREE OF ACCURACY I)</u>		
	<u>Smooth Formwork to Sides:</u>		
17	Edges, risers, ends and reveals not exceeding 300mm high or wide. A0 : 7 A1 : 5 A2 : 5 A3 : 6	m	23
	<u>REINFORCEMENT (PROVISIONAL)</u>		
18	High tensile steel reinforcement bars to structural concrete work. A0 : 0.58 A1 : 0.60 A2 : 0.65 A3 : 0.65	t	2.48
	<u>Fabric reinforcement:</u>		
19	REF. 888 fabric reinforcement in concrete footings, walls, base slabs etc. A0 : 67 A1 : 73 A2 : 78 A3 : 87	m2	304

Carried to Collection

R

Section 3
Bill No. 2
Concrete, Formwork and Reinforcement

Section 3

Bill No. 2

Concrete, Formwork and Reinforcement

COLLECTION

Total Brought Forward from Page No.

**Page
No**

Amount

42

43

44

45

46

Carried Forward to Summary of Section No. 3

R

Section 3

Bill No. 2

Concrete, Formwork and Reinforcement

R

Face bricks

Bricks shall be ordered timeously to obtain uniformity in size and colour

Pointing

Descriptions of recessed pointing to fair face brickwork and face brickwork shall be deemed to include square recessed, hollow recessed, weathered pointing, etc

Samples

Samples of all masonry building units, except those of walls described as "loadbearing", shall consist of a minimum of 6 units. Samples of building units to be used in walls described as "loadbearing" shall consist of 30 units from every 30 000 units delivered to site

Trade names

Where trade names are specified it will read "or equal approved"

Carried to Collection

R

Section 3
Bill No. 3
Masonry

**BRICKWORK IN FOUNDATIONS
(PROVISIONAL)**

Brickwork consisting of solid bricks with 10.5 MPa minimum nominal compressive strength in Class I mortar with Coprox masonry waterproofing or equal approved waterproof cement additive. Add 2.5kg Coprox waterproof cement additive for every 50kg of cement used in mortar mix (Cement to be 42.5N all-purpose cement):

1	345mm thick cavity brick walls made of two leafs of 110mm wall with 135mm concrete fill (concrete elsewhere measured).	m2	110
	A0 : 25 A1 : 27 A2 : 27 A3 : 31		

BRICKWORK AND BLOCKWORK SUNDRIES

Galvanized brickwork reinforcement

2	230mm Wide reinforcement in foundations (Provisional).	m	378
	A0 : 85 A1 : 92 A2 : 94 A3 : 107		

FACE BRICK

"Rustgold FBS/Qunu Travertine" clay face brick or equal approved, size 222 x 106 x 73mm, bedded and jointed in Class II mortar and pointed with recessed vertical and recessed horizontal joints, suitable for exposure zones 1-2 (Cement to be 42.5N all-purpose cement):

3	Extra over for face brick in foundations (Provisional).	m2	9
	A0 : 2 A1 : 2 A2 : 2 A3 : 2		

Carried to Collection

R

Section 3
Bill No. 3
Masonry

Section 3

Bill No. 3

Masonry

COLLECTION

Total Brought Forward from Page No.

**Page
No**

Amount

48

49

50

Carried Forward to Summary of Section No. 3

R

Section 3
Bill No. 3
Masonry

Contractor to provide water proofing product that will be 100% resistant to extreme hydrostatic pressure at depth of 2m, from the positive (water from inside) of substrate. Resistant to aggressive chemicals i.e oil, salt water, sewage, weak acids and aggressive sulphate soils. The product must be able to withstand backfilling without protection and must not be subject to deterioration. The product must be able to ensure that the pit structure is fully sealed (100% free from water ingress from outside and it will not penetrate the pit).

The product and its methodology for application must be approved by Principal Agent before it is used.

It is a mandatory requirement for the Contractor to attend training to be provided by Supplier. Proof of attendance will be required prior to application of the approved waterproofing product.

Contractor must prepare a 1m x 1m sample in the presence of the Principal Agent or Engineer. In this case, the Contractor must give at least 48 hours notice prior to the date when the application of the waterproofing product is intended to be done.

Contractor to provide a Letter of Compliance confirming that waterproofing has been applied as per Manufacturer's instructions and data sheet.

Carried to Collection

Section 3
Bill No. 4
Waterproofing

R

DAMPPROOFING OF WALLS AND FLOORS

One layer of 250 micron 'USB GREEN' waterproof sheeting sealed at laps with 'Gunplas Pressure Sensitive Tape':

1	Under surface beds, bases, etc.	m2	122	
	A0 : 28 A1 : 29 A2 : 33 A3 : 32			

WATERPROOFING TO PIT WALLS

Waterproofing product to plastered walls, subject to approval by the Principal Agent prior to application.

2	On plastered wall surfaces including 100mm overlap at the base slab	m2	107	
	A0 : 24 A1 : 26 A2 : 27 A3 : 31			

Carried to Collection

R

Section 3
Bill No. 4
Waterproofing

Section 3

Bill No. 4

Waterproofing

COLLECTION

Total Brought Forward from Page No.

**Page
No**

Amount

52

53

54

Carried Forward to Summary of Section No. 3

R

Section 3

Bill No. 4

Waterproofing

Fixing of ironmongery is deemed to be fixed to timber unless otherwise described

R

Section 3
Bill No. 5
Ironmongery

SIGN PLATES:

All sign plates are to be with engraved blue perspex all in accordance with the standard sign plates for Schools.

- | | | | |
|---|----------------------------------------------------------------------------------|----|----|
| 1 | Sign plate plugged and screwed to walls with chromium plated dome headed screws. | No | 10 |
| | A0 : 2 A1 : 2 A2 : 3 A3 : 3 | | |

SUNDRIES

- | | | | |
|---|---------------------------------------------------------------------------|----|---|
| 2 | Stainless Steel Hat and coat hook, code DHC - SS-030-A or equal approved. | No | 4 |
| | A0 : 0 A1 : 1 A2 : 3 A3 : 0 | | |

- | | | | |
|---|-------------------------------------------------------------------|----|----|
| 3 | 38mm Diameter black rubber door stop plugged and screwed to wall. | No | 11 |
| | A0 : 2 A1 : 3 A2 : 3 A3 : 3 | | |

Halcast or equal approved"

- | | | | |
|---|--------------------------------------------|----|----|
| 4 | Thiefproof toilet roll holder plugged. | No | 11 |
| | A0 : 2 A1 : 3 A2 : 3 A3 : 3 | | |

Grade 304 stainless steel ware:

- | | | | |
|---|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|---|
| 5 | 32mm outside diameter x 1,6mm thick tubular wall mounted side stainless steel grab rail 1,06m girth with two 45 degree and two 90 degree formed bends and each end fitted with 80mm diameter x 5mm thick flange welded on and four times countersunk holed for and plugged and screwed to wall with stainless steel crews. | No | 2 |
| | A0 : 0 A1 : 0 A2 : 1 A3 : 1 | | |

- | | | | |
|---|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|---|
| 6 | 32mm outside diameter x 1,6mm thick tubular wall mounted around cistern back stainless steel grab rail 1,23m girth with two 90 degree formed bends and each end fitted with 80mm diameter x 5mm thick flange welded on and four times countersunk holed for and plugged and screwed to wall with stainless steel crews. | No | 2 |
| | A0 : 0 A1 : 0 A2 : 1 A3 : 1 | | |

Satin Grey Plastics or equal approved

- | | | | |
|---|-----------------------------------------------------------------------------------|----|---|
| 7 | "Satin plastic N-SBIN-12-SA SHE Bin size 463 x 140 x 480mm, floor standing loose. | No | 8 |
| | A0 : 2 A1 : 2 A2 : 2 A3 : 2 | | |

Carried to Collection

Section 3
Bill No. 5
Ironmongery

R

Section 3

Bill No. 5

Ironmongery

COLLECTION

Total Brought Forward from Page No.

**Page
No**

56

57

Amount

Carried Forward to Summary of Section No. 3

R

Section 3

Bill No. 5

Ironmongery

Item No		Quantity	Rate	Amount
	<u>SECTION 3</u>			
	<u>BILL No. 6</u>			
	<u>PLASTERING</u>			
	<u>Quantity Split:</u>			
	Note that the total quantity per each item is split into the various buildings and appears below each description as follows:			
	A0 - DWG 38 - Male Ablutions			
	A1 - DWG 39 - Female Ablutions			
	A2 - DWG 36 - Grade R Ablutions			
	A3 - DWG 37 - Staff Ablutions			
	<u>MODEL PREAMBLES</u>			
	The tenderer is referred to the "General Preambles for Trades 2017" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates.			
	<u>INTERNAL PLASTER (PIT WALLS)</u>			
	<u>15mm thick of 1:4 sand cement plaster with Coprox masonry waterproofing or equal approved waterproof cement additive. Add 2.5kg Coprox waterproof cement additive for every 50kg of cement used in plaster mix</u>			
1	On walls. A0 : 23 A1 : 25 A2 : 25 A3 : 29	m2	102	
	Carried Forward to Summary of Section No. 3			R
	Section 3			
	Bill No. 6			
	Plastering			

Item No		Quantity	Rate	Amount
	<u>SECTION 3</u>			
	<u>BILL No. 7</u>			
	<u>PLUMBING AND DRAINAGE</u>			
	<u>(PROVISIONAL)</u>			
	<u>Quantity Split:</u>			
	Note that the total quantity per each item is split into the various buildings and appears below each description as follows:			
	A0 - DWG 38 - Male Ablutions			
	A1 - DWG 39 - Female Ablutions			
	A2 - DWG 36 - Grade R Ablutions			
	A3 - DWG 37 - Staff Ablutions			
	<u>MODEL PREAMBLES</u>			
	The tenderer is referred to the "General Preambles for Trades 2017" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates.			
	<u>SANITARY PLUMBING</u>			
	<u>PVC waste or vent pipes and fittings:</u>			
1	50mm Waste pipe. A0 : 15 A1 : 15 A2 : 13 A3 : 13	m	56	
2	110mm Vent pipe fixed to wall with proprietary brackets at not exceeding 500mm centres. A0 : 8 A1 : 12 A2 : 12 A3 : 12	m	44	
	<u>uPVC gulleys</u>			
3	200mm Precast concrete gully dish and uPVC lowback assembly complete with 110mm P trap gully (code UGB 40) including 190mm diameter head (code UGA 40) and grate (code UGG 40), not exceeding 750mm deep, jointed to 110mm drain pipe, including excavations for and encasing in concrete (15MPa crushing strength after 28 days) worked up to form kerb, finished smooth on top in 1:3 cement mortar. A0 : 1 A1 : 1 A2 : 1 A3 : 1	No	4	
	Carried to Collection		R	
	Section 3			
	Bill No. 7			
	Plumbing and Drainage (Provisional)			

Extra for:

4	50mm Bend. A0 : 6 A1 : 9 A2 : 9 A3 : 9	No	33
5	50mm Access bend. A0 : 2 A1 : 3 A2 : 3 A3 : 3	No	11
6	Envirosan or equal approved fly screens to top of 110 diameter vent pipe. A0 : 2 A1 : 3 A2 : 3 A3 : 3	No	11

WATER SUPPLIES

Polycop pipes:

Pipes shall be class 10.

Fixing of pipes

Unless specifically otherwise stated, descriptions of pipes shall be deemed to include for fixing to walls etc. casting in, building in or suspending not exceeding 1m below suspension level

Reducing fittings:

Where fittings have reducing ends or branches they are described as 'reducing'. In the case of pipes with diameters not exceeding 60mm only the largest end or branch size is given. Should the Contractor wish to use other fittings and bushes or reducers he may do so on the understanding that no claim in this regard will be entertained. In the case of pipes with diameters exceeding 60mm all sizes are given and no claim for extra bushes, reducers, etc will be entertained.

Class 10 Polycop pipes:

7	15mm Pipes. A0 : 14 A1 : 14 A2 : 15 A3 : 15	m	58
8	22mm Pipes. A0 : 20 A1 : 15 A2 : 15 A3 : 15	m	65

Extra over polycop pipes for compression fittings:

9	15mm Fittings. A0 : 17 A1 : 15 A2 : 15 A3 : 15	No	62
---	------------------------------------------------------------------	----	----

Carried to Collection

Section 3
Bill No. 7
Plumbing and Drainage (Provisional)

R

10	22mm Fittings. A0 : 10 A1 : 12 A2 : 12 A3 : 15	No	49		
	<u>LOCKABLE MANHOLE COVERS</u>				
11	600mm diameter lockable circular type M4A product or similar approved manhole SANS 1882 medium duty Dough Moulding compound 4A hinged lid and frame cast into concrete upstand. A0 : 2 A1 : 2 A2 : 2 A3 : 2	No	8		
				R	
Section 3 Bill No. 7 Plumbing and Drainage (Provisional)		Carried to Collection			

Section 3

Bill No. 7

Plumbing and Drainage (Provisional)

COLLECTION

Total Brought Forward from Page No.

**Page
No**

Amount

60

61

62

Carried Forward to Summary of Section No. 3

R

Section 3

Bill No. 7

Plumbing and Drainage (Provisional)

[illegible]

[illegible]

	<u>Earth filling from excavated material</u>				
5	Dig, load and remove filling selected from spoil heaps on site and deposit as filling in platforms including spreading and compacting to cambers and falls in layers not exceeding 150 mm thick to a minimum of 95% Modified AASHTO dry density.	m3	408		
	<u>Surface Preparation:</u>				
6	Trim and level off surface of ground (excavated or filled under this Contract) including excavating or filling, ripping and scarifying as necessary and compacting the whole area for a depth of 300mm to a density of at least 90% Mod. AASHTO maximum density, part to falls.	m2	595		
	<u>Prescribed density tests on filling:</u>				
7	Modified AASHTO Density test.	No	51		
	<u>THE FOLLOWING IN WALKWAYS</u>				
	<u>Excavation not exceeding 2m deep</u>				
8	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	85		
	<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>				
9	Off site to a dumping site to be found by the Contractor.	m3	85		
	<u>Filling supplied by the contractor under walkways</u>				
10	G7 Base course material compacted to 98% Mod AASHTO density	m3	37		
11	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	37		
	<u>Rip and Re - compact insitu material on site compacted to 93% Mod. AASHTO density:</u>				
12	Under floors,etc.	m2	680		
	Carried to Collection			R	
	Section 4				
	Bill No. 1				
	External Works				

	<u>Prescribed density tests on filling:</u>				
13	In-situ dry density test.	No	7		
	<u>Approved brand of anti-termite soil poison applied by a Registered Pest Control Company and guaranteed against termite infestation for ten years:</u>				
14	Treat filling under paving with 'Chlordane Heptachlor Aldrin' or equal approved.	m2	153		
	<u>Concrete Paving Blocks</u>				
	<u>Paving of 50mm thick 200x100mm 25MPa Bevel Bond paver blocks grey in colour in herringbone pattern on and including 20mm thick sand bed with dry filler sand swept and vibrated into joints all laid on subgrade (elsewhere measured) conforming to SABS 1200D degree of accuracy I:</u>				
15	Paving to walkway areas, etc laid to falls.	m2	151		
16	Extra over ordinary paving for 200mm wide block-on-flat header course edging on 100mm thick mortar bed including unreinforced concrete haunching along outside edge.	m	151		
17	Ditto but circular on plan.	m	10		
	<u>Kerbing</u>				
	<u>Precast or in situ mass concrete (25 MPa - 19 mm stone) kerbs cast in convenient lengths with exposed faces finished smooth from the mould and all salient angles rounded, jointed and pointed in 1:3 cement mortar, including excavations, formwork, etc.</u>				
18	Figure 8B (300 x 275 x 175mm) semi mountable kerb laid in lengths not exceeding 1000mm on a well rammed earth bottom or base course.	m	158		
19	Ditto but circular on plan.	m	12		
20	Fig. 12 kerb size 75 x 150mm high overall, laid in lengths not exceeding 1000mm on a well rammed earth bottom or base course.	m	15		
21	Ditto but circular on plan.	m	9		
Carried to Collection				R	
Section 4					
Bill No. 1					
External Works					

Section 4 Bill No. 1 External Works	Carried to Collection			R	

<u>THE FOLLOWING IN ONE BRICK WALL (GARDEN WALL)</u>					
<u>Excavation in earth not exceeding 2m deep:</u>					
22	Trenches.	m3	9		
<u>Extra over all excavations for carting away:</u>					
23	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the Contractor.	m3	9		
<u>Risk of collapse of excavations:</u>					
24	Sides of trench and hole excavations not exceeding 1,5m deep.	m2	88		
<u>Earth filling obtained from the excavations and/or prescribed stock piles on site compacted to 93% MOD AASHTO density:</u>					
25	Backfilling to trenches, holes, etc.	m3	9		
<u>Earth filling (G7 material) supplied by the contractor in layers not exceeding 150mm thick and compacted to 98% Mod AASHTO density:</u>					
26	Under footings.	m3	9		
<u>Compaction of surfaces</u>					
27	Compaction of ground surface under floors, etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density.	m2	85		
<u>25 Mpa/19mm Concrete</u>					
28	Strip footings.	m3	5		
<u>Test blocks:</u>					
29	Making and testing of 150x150x150mm concrete strength test cubes (Provisional).	No	3		
Carried to Collection				R	
Section 4					
Bill No. 1					
External Works					

	<u>Reinforcement (Provisional)</u>				
30	High tensile steel reinforcement bars to structural concrete work.	t	1.26		
	<u>BRICKWORK IN FOUNDATIONS.</u>				
	<u>Brickwork of NFX bricks (14 MPa nominal compressive strength) in Class I mortar (Cement to be 42.5N all-purpose cement):</u>				
31	One brick walls.	m2	61		
	<u>BRICKWORK IN SUPERSTRUCTURE</u>				
	<u>Brickwork of NFP bricks (14 MPa nominal compressive strength) in Class II mortar (Cement to be 42.5N all-purpose cement):</u>				
32	One brick walls.	m2	151		
	<u>Brickwork reinforcement:</u>				
33	230mm Wide reinforcement built in horizontally.	m	452		
34	Ditto but in foundations.	m	182		
	<u>FACE BRICK</u>				
	<u>"Rustgold FBS/Qunu Travertine" clay face brick or equal approved, size 222 x 106 x 73mm, bedded and jointed in Class II mortar and pointed with recessed vertical and recessed horizontal joints, suitable for exposure zones 1-2 (Cement to be 42.5N all-purpose cement):</u>				
35	One brickwall faced on both sides.	m2	60		
	<u>Brick-on-edge header course copings, sills, etc, of "Rustgold FBS/Qunu Travertine" or equal approved face bricks pointed with recessed joints on all exposed faces, 220mm wide sill set sloping and slightly projecting:</u>				
36	230mm wide header course to top of one brick wall bedded and jointed in cement mortar and pointed on top and both sides as described.	m	90		
	Carried to Collection			R	
	Section 4				
	Bill No. 1				
	External Works				

<u>STORMWATER CHANNELS</u>					
<u>Excavation not exceeding 2m deep</u>					
37	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	36		
<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>					
38	Off site to a dumping site to be found by the Contractor.	m3	36		
<u>Filling supplied by the contractor under channels</u>					
39	G7 Base course material compacted to 98% Mod AASHTO density	m3	14		
40	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	7		
<u>Cast in-situ Ref 395 mesh reinforced concrete (25MPa) open stormwater channels having V-shaped waterway formed in top, finished smooth on all exposed surfaces in 3:1 cement plaster trowelled smooth and with angles rounded, cast in suitable lengths not exceeding 2m, including all formwork, moulds, shallow excavation, filling and ramming, laying to falls, bedding and pointing in 3:1 cement mortar. Concrete apron to be tinted, colour to be specified by the Engineer.</u>					
41	700 x 80mm thick V' channel 150mm deep in centre laid in position in ground in 2000mm sections including all formwork, reinforcement, expansion joints, smooth finishing to top of concrete surface etc.	m	32		
42	Extra for 700mm angle	No	12		
43	Extra for forming 200mm thick 700mm wide spreader with 200mm high edges fanning out to 1 960mm width at furthest end with hard burnt bricks pitching cast in ass diffusers including working off concrete to a smooth finish and draining onto natural ground with 150 - 200mm diameter loose stones.	No	12		
Carried to Collection				R	
Section 4					
Bill No. 1					
External Works					

	<u>Sundries:</u>				
44	Create earth berm for stormwater control with in situ material 1,5m wide at base x 500mm high	m	34		
45	Construct shaped earth V-drain 2m wide with grass runners	m	51		
	<u>THE FOLLOWING IN DISABLED ACCESS</u>				
	<u>SCREEN WALL</u>				
	<u>Excavation in earth not exceeding 2m deep:</u>				
46	Trenches.	m3	3		
	<u>Extra over all excavations for carting away:</u>				
47	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the Contractor.	m3	3		
	<u>Risk of collapse of excavations:</u>				
48	Sides of trench and hole excavations not exceeding 1,5m deep.	m2	10		
	<u>Earth filling obtained from the excavations and/or prescribed stock piles on site compacted to 93% MOD AASHTO density:</u>				
49	Backfilling to trenches, holes, etc.	m3	22		
	<u>Earth filling (G7 material) supplied by the contractor in layers not exceeding 150mm thick and compacted to 98% Mod AASHTO density:</u>				
50	Under footings.	m3	17		
	<u>Compaction of surfaces</u>				
51	Compaction of ground surface under floors, etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density.	m2	77		
	Carried to Collection			R	
	Section 4				
	Bill No. 1				
	External Works				

	<u>25 Mpa/19mm Concrete</u>			
52	Strip footings.	m3	7	
	<u>Test blocks:</u>			
53	Making and testing of 150x150x150mm concrete strength test cubes (Provisional).	No	7	
	<u>Reinforcement (Provisional)</u>			
54	High tensile steel reinforcement bars to structural concrete work.	t	1.26	
	<u>BRICKWORK IN FOUNDATIONS.</u>			
	<u>Brickwork of NFX bricks (14 MPa nominal compressive strength) in Class I mortar (Cement to be 42.5N all-purpose cement):</u>			
55	One brick walls.	m2	36	
	<u>BRICKWORK IN SUPERSTRUCTURE</u>			
	<u>Brickwork of NFP bricks (14 MPa nominal compressive strength) in Class II mortar (Cement to be 42.5N all-purpose cement):</u>			
56	One brick walls.	m2	156	
	<u>Brickwork reinforcement:</u>			
57	230mm Wide reinforcement built in horizontally.	m	425	
58	Ditto but in foundations.	m	51	
	<u>FACE BRICK</u>			
	<u>"Rustgold FBS/Qunu Travertine" clay face brick or equal approved, size 222 x 106 x 73mm, bedded and jointed in Class II mortar and pointed with recessed vertical and recessed horizontal joints, suitable for exposure zones 1-2 (Cement to be 42.5N all-purpose cement):</u>			
59	One brickwall faced on both sides.	m2	51	
	Carried to Collection			R
	Section 4			
	Bill No. 1			
	External Works			

	<u>Brick-on-edge header course copings, sills, etc, of "Rustgold FBS/Qunu Travertine" or equal approved face bricks pointed with recessed joints on all exposed faces, 220mm wide sill set sloping and slightly projecting:</u>				
60	230mm wide header course to top of one brick wall bedded and jointed in cement mortar and pointed on top and both sides as described.	m	60		
	<u>ACCESS RAMPS</u>				
	<u>Excavation not exceeding 2m deep</u>				
61	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	14		
	<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>				
62	Off site to a dumping site to be found by the Contractor.	m3	14		
	<u>Filling supplied by the contractor under floors, aprons, etc</u>				
63	G7 Base course material compacted to 98% Mod AASHTO density	m3	3		
64	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	3		
	<u>Coarse river sand filling supplied by the contractor:</u>				
65	Under floors etc.	m3	2		
	<u>Compaction of surfaces:</u>				
66	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density.	m2	12		
	<u>Prescribed density tests on filling:</u>				
67	In-situ dry density test.	No	3		

Carried to Collection

R

Section 4
Bill No. 1
External Works

	<u>Reinforced 25Mpa/19mm Concrete:</u>				
68	Ramps, Landings, etc.	m3	2		
	<u>Finishing top surfaces of concrete smooth with a wood float:</u>				
69	Surface beds, slabs, etc to falls and currents.	m2	14		
	<u>Test blocks:</u>				
70	Making and testing of 150x150x150mm concrete strength test cubes (Provisional).	No	7		
	<u>Expansion joints with bitumen impregnated softboard between vertical concrete or brick surfaces:</u>				
71	12mm Joints not exceeding 300mm high.	m	7		
	<u>Two-part grey polysulphide sealing compound including backing cord, bond breaker, primer, etc</u>				
72	10 x 12mm In movement joints in floors or walls including raking out expansion joint filler as necessary.	m	7		
	<u>Fabric reinforcement:</u>				
73	REF. 395 fabric reinforcement in concrete surface beds, slabs, etc.	m2	12		
	<u>Waterproofing under Surface beds</u>				
74	350 Micron USB orange polyethylene dampproof membrane in accordance with SABS 952 Type C laid on sand bed (elsewhere measured).	m2	12		
Carried to Collection					
Section 4					
Bill No. 1					
External Works					

R

<u>THE FOLLOWING IN ACCESS DRIVEWAY, ETC.</u>					
<u>Excavation not exceeding 2m deep</u>					
75	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	175		
<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>					
76	Off site to a dumping site to be found by the Contractor.	m3	111		
<u>Filling supplied by the contractor under driveways</u>					
77	G7 Base course material compacted to 98% Mod AASHTO density	m3	54		
78	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	54		
<u>Rip and Re - compact insitu material on site compacted to 93% Mod. AASHTO density:</u>					
79	Under floors,etc.	m2	119		
<u>Prescribed density tests on filling:</u>					
80	In-situ dry density test.	No	3		
<u>Approved brand of anti-termite soil poison applied by a Registered Pest Control Company and guaranteed against termite infestation for ten years:</u>					
81	Treat filling under paving with 'Chlordane Heptachlor Aldrin' or equal approved.	m2	425		
<u>150-175mm diameter bollards</u>					
82	2100mm long tanalith treated gum pole planted 800mm deep including excavations, cartaways, concrete base etc.	No	14		
Carried to Collection				R	
Section 4					
Bill No. 1					
External Works					

<u>THE FOLLOWING IN RETAINING WALLS, ETC.</u>					
	<u>Excavation in earth not exceeding 2m deep</u>				
83	Trenches.	m3	7		
	<u>Risk of collapse of excavations:</u>				
84	Sides of trench and hole excavations not exceeding 1,5m deep.	m2	20		
	<u>Keeping excavations free of water:</u>				
85	Keeping excavations free of all water other than subterranean water.		Item		
	<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>				
86	Off site to a dumping site to be found by the Contractor.	m3	5		
	<u>Filling with approved clean, hard, dry decomposed dolerite filling supplied and carted onto site by the Contractor, compacted to a density of at least 95% Mod. AASHTO maximum density:</u>				
87	Behind walls with selected backfilling supplied by the Contractor compacted to 98% Mod ASSHTO density	m3	43		
	<u>Compaction of surfaces</u>				
88	Compaction of ground surface under floors, etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density.	m2	3		
	<u>15Mpa/19mm Concrete</u>				
89	Surface blinding under footings and bases.	m3	3		
	<u>30Mpa/19mm Concrete</u>				
90	Strip footings.	m3	7		
91	Cavity walls.	m3	27		
Carried to Collection				R	
Section 4					
Bill No. 1					
External Works					

	<u>Test blocks:</u>				
92	Making and testing of 150x150x150mm concrete strength test cubes (Provisional).	No	7		
	<u>Fabric reinforcement:</u>				
93	REF. 395 fabric reinforcement in concrete infill, strip footings.	m2	32		
	<u>Brickwork of NFX bricks (14 MPa nominal compressive strength) in Class I mortar (Cement to be 42.5N all-purpose cement):</u>				
94	330mm thick cavity brick Walls made of two leafs of 110mm wall with 110mm mesh reinforced concrete fill (concrete and reinforcement elsewhere measured).	m2	32		
	<u>Brickwork reinforcement:</u>				
95	230mm Wide reinforcement built in horizontally.	m	94		
	<u>"Rustgold FBS/Qunu Travertine" clay face brick or equal approved, size 222 x 106 x 73mm, bedded and jointed in Class II mortar and pointed with recessed vertical and recessed horizontal joints, suitable for exposure zones 1-2 (Cement to be 42.5N all-purpose cement):</u>				
96	Extra over brickwork for face brickwork externally.	m2	26		
	<u>Brick-on-edge header course copings, sills, etc. of "Rustgold FBS/Qunu Travertine" or equal Architect approved clay face brick size 222 x 106 x 73mm, pointed with recessed joints on all exposed faces:</u>				
97	220mm Wide header course to top of one brick wall bedded and jointed in cement mortar and pointed on top and both sides as described.	m	19		
	<u>Openings in Walls etc.</u>				
98	Leave or form 32mm weephole through one brick wall	No	19		
	<u>Membranes</u>				
99	"Geofabric filter blanket wrapped around stone with 150mm side and 300mm end laps, including stitching.	m2	7		
Carried to Collection					R
Section 4					
Bill No. 1					
External Works					

	<u>Earth filling 300 x 300mm section of 19mm thick stone material surrounding 110mm uPVC pipe, supplied by the contractor compacted to 98% Mod AASHTO density:</u>				
100	19mm Stone.	m3	2		
	<u>THE FOLLOWING IN STORMWATER DRAINAGE, APRONS ETC.</u>				
	<u>STORMWATER APRONS</u>				
	<u>Excavation not exceeding 2m deep</u>				
101	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	10		
	<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>				
102	Off site to a dumping site to be found by the Contractor.	m3	14		
	<u>Filling supplied by the contractor under floors, aprons, etc</u>				
103	G7 Base course material compacted to 98% Mod AASHTO density	m3	3		
104	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	3		
	<u>Coarse river sand filling supplied by the contractor:</u>				
105	Under floors etc.	m3	4		
	<u>Compaction of surfaces:</u>				
106	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density.	m2	34		
Carried to Collection					R
Section 4					
Bill No. 1					
External Works					

	<u>Prescribed density tests on filling:</u>				
107	In-situ dry density test.	No	2		
	<u>Reinforced 25Mpa/19mm Concrete:</u>				
108	Surface beds cast in panels on waterproofing.	m3	2		
109	Edge thickening	m3	2		
	<u>Finishing top surfaces of concrete smooth with a wood float:</u>				
110	Surface beds, slabs, etc to falls and currents.	m2	27		
	<u>Test blocks:</u>				
111	Making and testing of 150x150x150mm concrete strength test cubes (Provisional).	No	3		
	<u>Expansion joints with bitumen impregnated softboard between vertical concrete or brick surfaces:</u>				
112	12mm Joints not exceeding 300mm high.	m	14		
	<u>Two-part grey polysulphide sealing compound including backing cord, bond breaker, primer, etc</u>				
113	10 x 12mm In movement joints in floors or walls including raking out expansion joint filler as necessary.	m	14		
	<u>Fabric reinforcement:</u>				
114	REF. 395 fabric reinforcement in concrete surface beds, slabs, etc.	m2	27		
	<u>Waterproofing under Surface beds</u>				
115	350 Micron USB orange polyethylene dampproof membrane in accordance with SABS 952 Type C laid on sand bed (elsewhere measured).	m2	27		
Carried to Collection					R
Section 4					
Bill No. 1					
External Works					

<u>STORMWATER CHANNELS</u>					
<u>Excavation not exceeding 2m deep</u>					
116	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	10		
<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>					
117	Off site to a dumping site to be found by the Contractor.	m3	7		
<u>Filling supplied by the contractor under channels</u>					
118	G7 Base course material compacted to 98% Mod AASHTO density	m3	3		
119	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	3		
<u>Cast in-situ Ref 395 mesh reinforced concrete (25MPa) open stormwater channels having V-shaped waterway formed in top, finished smooth on all exposed surfaces in 3:1 cement plaster trowelled smooth and with angles rounded, cast in suitable lengths not exceeding 2m, including all formwork, moulds, shallow excavation, filling and ramming, laying to falls, bedding and pointing in 3:1 cement mortar. Concrete apron to be tinted, colour to be specified by the Engineer.</u>					
120	700 x 80mm thick V' channel 150mm deep in centre laid in position in ground not exceeding 2000mm sections including all formwork, reinforcement, expansion joints, smooth finishing to top of concrete surface etc.	m	34		
121	Extra for 700mm angle	No	5		
122	Extra for forming 200mm thick 700mm wide spreader with 200mm high edges fanning out to 1 960mm width at furthest end with hard burnt bricks pitching cast in ass diffusers including working off concrete to a smooth finish and draining onto natural ground with 150 - 200mm diameter loose stones.	No	3		
Carried to Collection				R	
Section 4					
Bill No. 1					
External Works					

	<u>Sundries:</u>				
123	Create earth berm for stormwater control with in situ material 1,5m wide at base x 500mm high	m	15		
124	Construct shaped earth V-drain 2m wide with grass runners	m	22		
	<u>THE FOLLOWING IN STORMWATER DISH DRAIN, ETC.</u>				
	<u>Excavation not exceeding 2m deep</u>				
125	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	48		
	<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>				
126	Off site to a dumping site to be found by the Contractor.	m3	43		
	<u>Filling supplied by the contractor under floors, aprons, channels etc</u>				
127	G7 Base course material compacted to 98% Mod AASHTO density	m3	7		
128	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	7		
	<u>Coarse river sand filling supplied by the contractor:</u>				
129	Under floors etc.	m3	14		
	<u>Compaction of surfaces:</u>				
130	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density.	m2	29		
	Carried to Collection			R	
	Section 4				
	Bill No. 1				
	External Works				

	<u>Prescribed density tests on filling:</u>			
131	In-situ dry density test.	No	3	
	<u>Reinforced 25Mpa/19mm Concrete:</u>			
132	Surface beds cast in panels on waterproofing.	m3	9	
	<u>Finishing top surfaces of concrete smooth with a wood float:</u>			
133	Surface beds, slabs, etc to falls and currents.	m2	44	
	<u>Test blocks:</u>			
134	Making and testing of 150x150x150mm concrete strength test cubes (Provisional).	No	2	
	<u>Expansion joints with bitumen impregnated softboard between vertical concrete or brick surfaces:</u>			
135	12mm Joints not exceeding 300mm high.	m	20	
	<u>Two-part grey polysulphide sealing compound including backing cord, bond breaker, primer, etc</u>			
136	10 x 12mm In movement joints in floors or walls including raking out expansion joint filler as necessary.	m	20	
	<u>Fabric reinforcement:</u>			
137	REF. 617 fabric reinforcement in concrete surface beds, slabs, etc.	m2	46	
	<u>THE FOLLOWING IN SUB-SOIL DRAINAGE, ETC.</u>			
	<u>Site Clearance, ETC</u>			
138	Digging up and removing rubbish, debris, vegetation, hedges, shrubs and trees not exceeding 200mm girth, bush, etc	m2	24	
	<u>Excavation in earth not exceeding 2m deep:</u>			
139	Trenches.	m3	7	
	Carried to Collection			R
	Section 4			
	Bill No. 1			
	External Works			

	<u>Extra over all excavations for carting away:</u>				
140	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the Contractor.	m3	7		
	<u>Risk of collapse of excavations:</u>				
141	Sides of trench and hole excavations not exceeding 1,5m deep.	m2	14		
142	Ditto, but from ground level to exceeding 1,5m.	m2	14		
	<u>Earth filling obtained from the excavations and/or prescribed stock piles on site compacted to 93% MOD AASHTO density:</u>				
143	Backfilling to trenches, holes, etc.	m3	14		
	<u>Earth filling 300 x 300mm section of 19mm thick stone material surrounding 110mm uPVC pipe, supplied by the contractor compacted to 98% Mod AASHTO density:</u>				
144	19mm Stone.	m3	7		
	<u>Membrane</u>				
145	""Geofabric filter blanket wrapped around stone with 150mm side and 300mm end laps, including stitching.	m2	56		
	<u>Keeping excavations free of water:</u>				
146	Keeping excavations free from mud and all water including subterranean sources.		Item		
	<u>Compaction of surfaces</u>				
147	Compaction of ground surface under floors, etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density.	m2	37		
Carried to Collection				R	
Section 4					
Bill No. 1					
External Works					

[illegible]

	<u>Earth filling with stone material supplied by the contractor:</u>				
156	Stone (>53mm).	m2	3		
	<u>Membranes</u>				
157	"BidimGeotextile or equal approved, lined on all sides including the top and bottom faces.	m2	17		
	<u>Keeping excavations free of water</u>				
158	Keeping excavations free of all water other than subterranean water		Item		
	<u>THE FOLLOWING IN CULVERTS</u>				
	<u>Class 50D concrete pipes:</u>				
159	450mm Diameter Concrete pipe laid in trenches not exceeding 1m deep including excavation, backfill, bedding, cart away and compaction.	m	15		
	<u>Manholes:</u>				
160	Manhole size 600 x 600mm not exceeding 1m deep internally to invert level formed of hard burnt half brick sides in 1:3 cement mortar on and including 100mm thick mass concrete (25 MPa at 28 days in 19 mm stone) bottom reinforced with Y10 bars at 200c/c both directions and projecting 150mm beyond sides, cast on 50mm thick concrete Blinding (15Mpa) and mass concrete (15 MPa at 28 days in 12 mm stone) benching, rendered internally in 1:3 cement plaster with with C.I step irons staggered at 300c/c with 150mm thick grade 25 reinforced precast concrete manhole cover rebated for and fitted with and including cast iron double seal cover and frame type 14B in accordance with SABS 558, bedded in 1:3 cement mortar and sealed in to allow including all necessary vitrified clay channels and fittings, excavations, formwork, holes through sides for pipes, etc	No	3		
	<u>THE FOLLOWING IN HEADWALLS</u>				
161	Excavation not exceeding 2m deep.	m3	7		
162	Risk of collapse not exceeding 1,5m deep	m2	14		
	Carried to Collection			R	
	Section 4				
	Bill No. 1				
	External Works				

163	Keeping excavations free from water		Item		
164	Carting away surplus excavated material	m3	7		
165	150mm layer of G7 material compacted to 95% MOD AASHTO under concrete slab.	m3	2		
166	150mm layer of G5 material compacted to 95% MOD AASHTO under concrete slab.	m3	2		
167	25Mpa/19mm Reinforced concrete in bottom slabs and footings.	m3	2		
168	Formwork to edges, risers, ends and reveals not exceeding 300mm wide or high.	m	29		
169	Weld Mesh Ref 193 in Concrete bottom slab.	m2	12		
170	One brick wall of 14 MPa NFX bricks.	m2	12		
171	230mm Wide reinforcement built in horizontally.	m	31		
172	Plaster on brick walls.	m2	85		
173	Gabion mattress comprising of 20 to 30mm stones wrapped in A3 geotextile with voids filled with 1:3 cement/sand mortar.	m2	17		
<u>THE FOLLOWING IN RAINWATER TANKS AND STANDS</u>					
<u>Excavation in earth not exceeding 2m deep:</u>					
174	Trenches.	m3	14		
<u>Extra over all excavations for carting away:</u>					
175	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the Contractor.	m3	14		
<u>Risk of collapse of excavations:</u>					
176	Sides of trench and hole excavations not exceeding 1,5m deep.	m2	41		
Carried to Collection				R	
Section 4					
Bill No. 1					
External Works					

	<u>Earth filling obtained from the excavations and/or prescribed stock piles on site compacted to 93% MOD AASHTO density:</u>				
177	Backfilling to trenches, holes, etc.	m3	24		
	<u>Earth filling (G7 material) supplied by the contractor in layers not exceeding 150mm thick and compacted to 98% Mod AASHTO density:</u>				
178	Under footings.	m3	5		
	<u>Compaction of surfaces</u>				
179	Compaction of ground surface under floors, etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density.	m2	17		
	<u>25 Mpa/19mm Concrete</u>				
180	Strip footings.	m3	7		
	<u>25 MPa/19mm Concrete:</u>				
181	Tank concrete slab.	m3	7		
	<u>Test blocks:</u>				
182	Making and testing of 150x150x150mm concrete strength test cubes (Provisional).	No	3		
	<u>Finishing top surfaces of concrete smooth with a steel trowel including adding additional cement while concrete is still green to attain a smooth, hard surface:</u>				
183	Surface beds, slabs, etc.	m2	22		
	<u>Rough Formwork to Sides:</u>				
184	Edges, risers, ends and reveals not exceeding 300mm high.	m	32		
	<u>Allens Meshco Square Mesh Fabric reinforcement:</u>				
185	Type 617 fabric reinforcement in concrete slabs.	m2	14		
Carried to Collection				R	
Section 4					
Bill No. 1					
External Works					

	<u>BRICKWORK IN FOUNDATIONS.</u>				
	<u>Brickwork of NFX bricks (14 MPa nominal compressive strength) in Class I mortar (Cement to be 42.5N all-purpose cement):</u>				
186	One brick walls.	m2	37		
	<u>BRICKWORK IN SUPERSTRUCTURE</u>				
	<u>Brickwork of NFP bricks (14 MPa nominal compressive strength) in Class II mortar (Cement to be 42.5N all-purpose cement):</u>				
187	One brick walls.	m2	114		
	<u>Brickwork reinforcement:</u>				
188	230mm Wide reinforcement built in horizontally.	m	85		
189	Ditto but in foundations.	m	94		
	<u>FACE BRICK</u>				
	<u>"Rustgold FBS/Qunu Travertine" clay face brick or equal approved, size 222 x 106 x 73mm, bedded and jointed in Class II mortar and pointed with recessed vertical and recessed horizontal joints, suitable for exposure zones 1-2(Cement to be 42.5N all-purpose cement):</u>				
190	Extra over brickwork for face brickwork externally.	m2	37		
	<u>Brick-on-edge header course copings, sills, etc, of "Rustgold FBS/Qunu Travertine" or equal approved face bricks pointed with recessed joints on all exposed faces, 220mm wide sill set sloping and slightly projecting:</u>				
191	230mm wide header course to top of one brick wall bedded and jointed in cement mortar and pointed on top and both sides as described.	m	29		
	Carried to Collection			R	
	Section 4				
	Bill No. 1				
	External Works				

	<u>Plastic water tanks etc:</u>			
192	5000 Litre roto molded or equal approved plastic tank complete with lid, 15mm brass bibtap with handle suitable for locking and 4 No. galvanised stay wires 2.5m each long connected to tank, with and including 4 No. eye bolts cast into concrete.	No	5	
193	Hole top of tank for 100mm pipe.	No	5	
Carried to Collection				
Section 4 Bill No. 1 External Works				R

THE FOLLOWING IN SECURITY FENCING, ETC

Site clearance

194	Allow for clearing site for the width of 1 000 mm where fencing is to be erected including removing trees, shrubs etc. not exceeding 200 mm girth, grubbing up roots and roughly levelling.	m2	145
-----	---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	----	-----

Straining wires, fencing and razor wire:

195	Four strands of 4mm Class'A' galvanised straining wires secured to fencing posts with doubled 2 mm galvanised wire inserted through hole in post and turned a minimum of four turns around straining wire and attached to straining frame at one end with not less than four turns at the other end to straining bolts (elsewhere measured).	m	139
-----	----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	---	-----

196	3 Strands of galvanised barbed wire tied to standards, posts and eye bolts	m	107
-----	----------------------------------------------------------------------------	---	-----

197	Fencing formed of 50 x 50 x 2.0mm diameter galvanised fencing 1 800mm high and fixed to each straining wire with 8 guage binding wire at 500mm centres including Y12 pegs at 900mm c/c between posts (straining wires elsewhere measured).	m	143
-----	--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	---	-----

Posts for 1 800mm high security fence:

198	60mm Diameter galvanised steel intermediate fencing post 1800mm long fitted with a pressed steel mushroom cap one end and 150 x 150 x 5 mm baseplate at bottom and embedded in and including 350 x 350 x 600 mm mass concrete (15 MPa) base.	No	43
-----	----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	----	----

199	100mm Ditto as corner post, fitted with two 50mm diameter galvanised steel stay set raking and with top end flattened and bolted through post, with post and stay both embedded in mass concrete (15 MPa) bases as last.	No	10
-----	--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	----	----

200	150mm Ditto as gate post 1 800mm long, fitted with two 50mm diameter galvanised steel stay set raking and with top end flattened and bolted through post, with post and stay both embedded in mass concrete (15 MPa) bases as last.	No	3
-----	-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	----	---

Carried to Collection

R

Section 4
Bill No. 1
External Works

CLUSTER 121
HORTON PRIMARY SCHOOL
THE MVULA TRUST SAFE PROGRAMME

201	12mm Diameter galvanised mild steel straining eye bolt with hook, threaded portion and two nuts and washers.	No	27		
202	Form 12mm diameter hole through fence post.	No	27		
	<u>Gates:</u>				
203	Security fence single gate, size 1 000 mm wide x 1 800 mm high, formed of 50 mm diameter nominal bore x 3,25 mm wall thickness hot dip galvanised mild steel pipe framing all round with mitred and welded angles and cross braces mullion and transome, scribed and welded into angles and at cross intersections, with two 50 mm diameter nominal bore x 3,25 mm wall thickness security posts each 600 mm long with one end welded to top rail of gate and closure plate to other end, the gate covered with 100 x 50 x 2,5 mm weld mesh with four straining wires as before described and with four 2,37 mm four point core diameter single "kampeon" wires with crimped droppers to security posts as before described; including three strands flat wrap razor barbed tape wire fixed as before described, leaf fitted with three 24 mm diameter x 300 mm long eyebolt hinges and stops including all holes, etc., welded or bolted to adjoining galvanised gatepost with and including 500 mm long approved chain spot welded to gate	No	2		
204	Two leafed vehicular swing gate. Size 5500mm x 1800mm high.	No	2		
	<u>PADLOCKS</u>				
205	Supply 50 mm "Viro" Padlocks and Keys (or equal approved)	No	2		
Carried to Collection				R	
Section 4					
Bill No. 1					
External Works					

Section 4

Bill No. 1

External Works

COLLECTION

Total Brought Forward from Page No.

**Page
No**

Amount

65

66

67

68

69

70

71

72

73

74

75

76

77

78

79

80

81

82

83

84

Carried Forward

R

Section 4

Bill No. 1

External Works

Section 4

Bill No. 1

External Works

COLLECTION

Brought Forward

Total Brought Forward from Page No.

**Page
No**

Amount

R

85

86

87

88

89

90

91

92

Carried to Final Summary

R

Section 4

Bill No. 1

External Works

R

The Structures to be erected will be as follows:

Boys ablution structure on concrete slab, size 3860 x 3080 x 3120mm high complete with 1No. external door including security gate, 2No. internal doors, 6No. windows, 2No. WCs, 2No. urinals, 1No. wash hand basin etc.

Girls ablution structure on concrete slab, size 4480 x 3080 x 3120mm high complete with 1No. external door including security gate, 3No. internal doors, 6No. windows, 3No. WCs, 2No. wash hand basins etc.

Staff ablution structure on concrete slab, size 4360 x 3080 x 3120mm high complete with 3No. external doors including security gate, 3No. windows, 3No. WCs, 3No. wash hand basins etc.

Grade R ablution structure on concrete slab, size 5400 x 3080 x 3120mm high complete with 1No. external doors including security gate, 7No. windows, 1No. WC, 2No. junior WCs, 2No. wash hand basins etc.

Pre-fabricated Modular Units shall comprise of:

- Internal and external walls made of 40mm thick wall panel which consist of 0.5mm rigidised pre-painted white galvanised chromadek sheeting on both sides including base rails, top rails all joined with aluminium rivets
- 600 x 600mm high casement type (W1) natural anodised aluminium window including frames and 4mm obscure glass with one top hung opener; Windows are to be secured with aluminium profile burglar proofing
- 813 x 2032mm high external doors manufactured from the same materials as the walls and fitted with hinges, five lever mortice lock, complete with striker plates, two keys chrome plated handles, etc
- 813 x 1882mm high internal door manufactured from the same materials as the walls and fitted with hinges, 3 lever mortice lock complete with striker plates, two keys chrome plated handles, etc
- Galvanised mild steel security gate 900 x

Carried to Collection

Section 5
Bill No. 1
Provisional Sums

R

	<p><u>2050mm high overall size</u></p> <ul style="list-style-type: none"> • <u>2mm thick vinyl sheeting on floors</u> • <u>The roof is to be 0.5mm Chromadek IBR sheeting mono pitched roof with mono pitched galvanised ridge capping, 255mm lapping secured onto the roof including light steel frame roof at 6 degree slope</u> • <u>125mm half round PVC gutters including gutter brackets at 1000mm centres with 75mm rainwater PVC fluted downpipes connected to 5000L plastic water tanks (elsewhere measured)</u> • <u>Medium density plain un-grooved fascia boards</u> • <u>85 x 275 x 6.0mm barge board drilled and brass screwed to purlin ends including galvanised steel H-profile jointing strips, screws, holes, etc</u> • <u>Plumbing and sanitary fittings shall comprise of WCs, Urinals, Wash hand basins, 15mm and 22mm polycop water supply pipes, 50mm diameter PVC drainage pipes and associated accessories</u> 			
1	Provide the sum of R795 000.00 for the supply and installation of Alternative Building Technology (ABT) toilet structures, as above described, by a nominated sub-contractor.	Item		795 000.00
2	Profit	Item		
3	Attendance	Item		
	<u>ELECTRICAL INSTALLATION</u>			
4	Provide the sum of R80 000.00 for Electrical supply cables, flexible sleeves, terminations and lightning protection including COCs.	Item		80 000.00
5	Profit	Item		
	Carried to Collection		R	
	Section 5			
	Bill No. 1			
	Provisional Sums			

[illegible]

Section 5

Bill No. 1

Provisional Sums

COLLECTION

Total Brought Forward from Page No.

**Page
No**

Amount

95

96

97

98

Carried to Final Summary

R

Section 5

Bill No. 1

Provisional Sums

[illegible]