

### **Specification Supply, Deliver and Install – B2 Ceiling**

<b>Item</b>	<b>Description</b>	<b>Quantity</b>	<b>Instructions</b>
Roof Waterproofing	Waterproofing Acrylic Promac Liquid rubber (20L)	<b>15</b>	<ul style="list-style-type: none"><li>• Supply only</li><li>• Color to be determined on site</li></ul>
Ceiling Gypsum	Ceiling Gypsum 6.4mm 1.2x3	<b>Floor area (msq) = 71</b>	<ul style="list-style-type: none"><li>• White</li></ul>
Cornice Gypsum	Cornice Gypsum 75mm Cove LCC	<b>Floor area (msq) = 71</b>	<ul style="list-style-type: none"><li>• White</li></ul>

#### **NB**

- **Workmanship certification required after completion of project**
- **Appointed service provider will be required to produce at least 3 CV with certified trade certification of key workers conducting the work**
- **No tempering with electrical cables, appointed supply will be required to also install drop down lights (will be specified on site)**
- **Appointed service provider will be required to produce a project work plan specifying timeframes for deliverables, failure to do so will result to cancelation of PSO**