SECTION 4

PORT SHEPSTONE HOSPITAL NEW PSYCHIATRIC WARD (WIMS 044044)

LIFT INSTALLATION

BILL OF QUANTITIES

Prepared by:

MAHESH KHOOSAL AND ASSOCIATES cc 58 Hilken Drive UMHLANGA ROCKS 1320

Contact person: Mr M Khoosal Phone Number: (031) 5368306 Prepared for: Dept. of Public Works



LIFT INSTALLATION: BILL OF QUANTITIES PORT SHEPSTONE PSYCH WARD (WIMS 044044)

BILL NO. 4: PASSENGER LIFT INSTALLATION

ITEM	DESCRIPTION	Unit	Qty.	Rate	TOTAL
1	This bill of quantity has generally been measured in accordance with the Standard System of measuring building Work - ASAQS Sixth Edition 1996 (as amended 1999). Where the bill deviates from the standard system for reasons of clarity, the revised method of measurement will take precedence.	g			
2	All rates for items in this Bill shall be EXCLUDING Value added Tax				
3	This bill shall be read in conjunction with the technical specifications and drawings where provided				
4	All rates shall be for supply, installation and commissioning thereof unless otheriwse specifically stated				

LIFT INSTALLATION: BILL OF QUANTITIES

BILL NO. 4: PASSENGER LIFT INSTALLATION

ITEM	DESCRIPTION	Unit	Qty.	Rate	TOTAL		
1.0	Allowance for associated costs to comply with conditions of contract (including but not limited to insurances, securities, site establishment, site attendance, etc.) - shall be paid in equal amounts over the contract period	-	-	sum			
2.0	Supply and install 2000kg Passenger/stretcher lift complete as specified including car, shaft equipment, Shaft lighting, architraves, floor sills, apron, landing doors, call buttons, car position	-	-	sum			
3.0	Intercom system to front desk complete with wire way						
3.1	Intercom system	No.	1				
3.2	Cabling in conduit complete with fittings, supports and termination for intercom	m	300				
4.0	Production of shop drawings	-	-	sum			
5.0	Commissioning including installers Annexures	-	-	sum			
6.0	Lift Inspector's statuatory inspection and test	-	-	sum			
0.0	certificates	-	-	sum			
7.0	Electrical Compliance Certificate	-	-	sum			
8.0	Compilation of Operating and Maintenance manual complete hardcopy and soft copy on memory stick	No.	1				
9.0	Additional hardcopies of Operating and Maintenance manuals complete with soft copy on memory stick	No.	3				
10.0	Monthly Service and maintenance including callouts	month	12				
11.0	12-month Guarantee of installation and equipment	-	-	sum			
12.0	Other works required but not specifically mentioned above in order to complete all works			sum			
	a						
	b						
TOTAL CARRIED FORWARD TO TENDER PRICE SUMMARY (excluding VAT R							