

Item No		Quantity	Rate	Amount
	<u>SECTION 1</u>			
	<u>BILL NO.1</u>			
	<u>PRELIMINARIES</u>			
	<u>PRELIMINARIES</u>			
1	Site Establishment F:..... V:..... T:.....	Item		
2	Supervision F:..... V:..... T:.....	Item		
3	Safety and security F:..... V:..... T:.....	Item		
4	Plant and equipment F:..... V:..... T:.....	Item		
5	Enclosure of the works F:..... V:..... T:.....	Item		
6	Temporary Services: Water F:..... V:..... T:.....	Item		
	Carried Forward		R	
	PROVISIONAL BILLS OF QUANTITIES			

	Brought Forward			R
7	Temporary Services: Electricity F:..... V:..... T:.....	Item		
8	Temporary Services: Telecommunications F:..... V:..... T:.....	Item		
9	<u>LOCAL LABOUR</u> It is a general requirement of this contract that persons normally resident in the locality of the works (local labour) be given preference for employment on the contract. Provided, however, that should adequate and appropriate labour not be available within the locality, other may be employed subject to satisfactory proof being provided that every reasonable endeavour has been made to employ local labour. The Contractor shall identify the local community leaders with the purpose of negotiating with them regarding the utilization of local labour in the construction process. In this regard, the Contractor shall furthermore give preference, wherever possible to the employment of single heads of households, women and youth. The Contractor shall, in general, maximize the involvement of the local community. F:..... V:..... T:.....	Item		
10	Occupational Health and Safety Act No. 85 of 1993 Bidders are to allow for costs in providing and implementing a "Construction Phase Safety, Health and Environmental Plan". Bidders are further reminded that it is their responsibility to amend their safety plan if the assessed risk of the work changes in the slightest manner. F:..... V:..... T:.....	Item		
	Carried Forward			R
	PROVISIONAL BILLS OF QUANTITIES			

**THE MVULA TRUST
KZN - SAFE BATCH 3
OMITTED SCOPE - CLUSTER EIGHT
QHINQA HIGH SCHOOL**

[illegible]

Item No		Quantity	Rate	Amount
	<u>SECTION 2</u>			
	<u>BILL NO.1</u>			
	<u>IRONMONGERY</u>			
	<u>MODEL PREAMBLES</u>			
	The tenderer is referred to the "Model Preambles for Trades 2008" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates			
	<u>SUPPLEMENTARY PREAMBLES</u>			
	<u>Trade Names</u>			
	Where trade names are specified other ironmongery approved by the Principal Agent may be used			
	<u>Fixing</u>			
	Fixing of ironmongery is deemed to be fixed to timber unless otherwise described			
	<u>SUNDRIES</u>			
	<u>Satin Grey Plastics or similar approved</u>			
1	Mounted Plastic SHE bins - Heavy duty.	No	17	
	<u>'Franke (t/a Citimetal)' or equal Architect approved stainless steel catering ware:</u>			
2	Soap dispenser, surface mounted, item no. STRX 618, manufactured from 18/10 1.2mm stainless steel, satin finish, and with cylinder lock.	No	7	
	Carried Forward		R	
	PROVISIONAL BILLS OF QUANTITIES			

Brought Forward			R
<u>BILL NO. 2</u>			
<u>METALWORK</u>			
<u>MODEL PREAMBLES</u>			
The tenderer is referred to the "Model Preambles for Trades 2008" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates			
<u>MANHOLE COVER LOCKS.</u>			
3	Galvanized manhole cover locks	No	18
<u>PADLOCKS</u>			
4	Supply 50 mm Galvanized "Viro" Padlocks and Keys (or equal approved)	No	18
5	Supply 75 mm Galvanized "Viro" Padlocks and Keys (or equal approved)	No	5
<u>HANDRAILS, BALUSTRADES, ETC.</u>			
<u>Galvanised Mild Steel Balustrades:</u>			
6	Heavy duty, galvanised mild steel industrial railings, consisting of 1000mm high, 90° 48mm Ø x 4.0mm E90 stanchions spaced at 1400mm centres, with 38mm Ø x 2.5mm hand/knee rails. Side mounted stanchions to be fitted with pre-drilled base plates for fixing to concrete/brick/metal surface, including all necessary bends, closures, ferrules, etc	m	50
Carried Forward			R
PROVISIONAL BILLS OF QUANTITIES			

Brought Forward				R
<u>BILL NO. 3</u>				
<u>PAINTWORK</u>				
<u>MODEL PREAMBLES</u>				
The tenderer is referred to the "Model Preambles for Trades 2008" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates				
<u>SUPPLEMENTARY PREAMBLES</u>				
<u>Trade Names</u>				
Where trade names are specified it will read "or equal approved"				
<u>Epoxy paint</u>				
The product and its methodology for application must be approved by Principal Agent before it is used.				
Contractor must prepare a 1m x 1m sample in the presence of the Principal Agent. In this case, the Contractor must give at least 48 hours notice prior to the date when the application of the epoxy paint is intended to be done.				
Contractor to provide a Letter of Compliance confirming that epoxy paint has been applied as per Manufacturer's instructions and data sheet. Proof of payment for the epoxy paint must be provided to the Principal Agent once approval has been granted.				
<u>EPOXY FLOOR PAINT</u>				
<u>Scrub surface with degreaser, rinse thoroughly with tap water, and apply one coat sealer and two coats epoxy paint on:</u>				
7	Concrete floated or screeded floors	m2	150	
Carried Forward				R
PROVISIONAL BILLS OF QUANTITIES				

	Brought Forward			R
8	Granolithic skirting not exceeding 300mm girth.	m	194	
	<u>PAINTWORK ETC TO EXISTING WORK</u>			
	<u>ON FLOATED PLASTER</u>			
	<u>Prepare surfaces and remove all loose material, apply one coat Merit Plaster Primer and plaster primer and two coats "Plascon Gloss Enamel " or equal Architect approved emulsion paint for interior use</u>			
9	On internal walls	m2	46	
	<u>BILL No. 4</u>			
	<u>GLAZING</u>			
	<u>MODEL PREAMBLES</u>			
	The tenderer is referred to the "Model Preambles for Trades 2017" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates			
	<u>SUPPLEMENTARY PREAMBLES</u>			
	<u>Proprietary products in descriptions:</u>			
	Proprietary products shall be used as specified. Substitute products of similar quality and specification may only be used with prior approval by the Principal Agent.			
	Carried Forward			R
	PROVISIONAL BILLS OF QUANTITIES			

[illegible]

Item No		Quantity	Rate	Amount
	<u>SECTION 3</u>			
	<u>BILL NO. 1</u>			
	<u>EXTERNAL WORKS</u>			
	<u>THE FOLLOWING IN EXISTING WALKWAYS, RAMPS, ETC.</u>			
	<u>Kerbing</u>			
1	Fig. 12 kerb size 75 x 150mm high overall, laid in lengths not exceeding 1000mm on a well rammed earth bottom or base course.	m	214	
2	Ditto but circular on plan.	m	20	
	<u>THE FOLLOWING IN ACCESS DRIVEWAY, ETC.</u>			
	<u>Excavation not exceeding 2m deep</u>			
3	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	63	
	<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>			
4	Off site to a dumping site to be found by the Contractor.	m3	63	
	<u>Selected earth supplied by the Contractor including haulage (material to comply with Pi <10 GM = 1.2)</u>			
5	Over site of Selected Subgrade G7 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	32	
	Carried Forward		R	
	PROVISIONAL BILLS OF QUANTITIES			

Brought Forward			R
6	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	35
	<u>Rip and Re - compact insitu material on site compacted to 93% Mod. AASHTO density:</u>		
7	Under floors,etc.	m2	210
	<u>Prescribed density tests on filling:</u>		
8	In-situ dry density test.	No	2
	<u>Approved brand of anti-termite soil poison applied by a Registered Pest Control Company and guaranteed against termite infestation for ten years:</u>		
9	Treat filling under paving with 'Chlordane Heptachlor Aldrin' or equal approved.	m2	210
	<u>Gates:</u>		
10	Two leafed vehicular swing gate. Size 5500mm x 1800mm high.	No	1
	<u>PADLOCKS</u>		
11	Supply 50 mm "Viro" Padlocks and Keys (or equal approved)	No	1
<u>THE FOLLOWING IN LANDSCAPING</u>			
	<u>Ground preparation:</u>		
12	Cultivation and preparation of areas to be planted.	m2	190
	<u>Topsoil, compost, lime and fertilizer:</u>		
13	Topsoil supplied by the Contractor in plant beds, grassed areas and holes for trees, shrubs, etc.	m3	57
Carried Forward			R
PROVISIONAL BILLS OF QUANTITIES			

Brought Forward			R
14	Fertilize garden soil with 3:2:1 super phosphate spread at a rate of 1kg/10m2 including working evenly into top 20mm depth of soil.	m2	190
	<u>Trees</u>		
15	Tree felling and treatment.	No	5
	<u>Grassing, ground covers, etc</u>		
16	"Kikuyu" roots in rows at 250mm centres	m2	190
	<u>Pebble covering</u>		
17	White covering of pebbles varying from 10mm to 30mm diameter	m2	190
	<u>Maintenance Period:</u>		
18	Maintenance of grassed and ground covered areas for a period of 3 months (total area approximately 190m2) including regularly weeding and irrigating as necessary.	Item	
	<u>THE FOLLOWING IN STORMWATER DRAINAGE, ETC.</u>		
	<u>STORMWATER APRONS</u>		
	<u>Filling supplied by the contractor under concrete pavement, etc</u>		
19	G7 Base course material compacted to 98% Mod AASHTO density	m3	3
20	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	3
Carried Forward			R
PROVISIONAL BILLS OF QUANTITIES			

Brought Forward				R
	<u>Coarse river sand filling supplied by the contractor:</u>			
21	Under floors etc.	m3	2	
	<u>Compaction of surfaces:</u>			
22	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density.	m2	24	
	<u>Prescribed density tests on filling:</u>			
23	In-situ dry density test.	No	1	
	<u>Reinforced 25Mpa/19mm Concrete:</u>			
24	Surface beds cast in panels on waterproofing.	m3	2	
	<u>Finishing top surfaces of concrete smooth with a wood float:</u>			
25	Surface beds, slabs, etc to falls and currents.	m2	24	
	<u>Test blocks:</u>			
26	Making and testing set of three 150x150x150mm concrete strength test cubes.	No	1	
	<u>Expansion joints with bitumen impregnated softboard between vertical concrete or brick surfaces:</u>			
27	12mm Joints not exceeding 300mm high.	m	5	
	<u>Two-part grey polysulphide sealing compound including backing cord, bond breaker, primer, etc</u>			
28	10 x 12mm In movement joints in floors or walls including raking out expansion joint filler as necessary.	m	24	
Carried Forward				R
PROVISIONAL BILLS OF QUANTITIES				

Brought Forward			R
<u>Fabric reinforcement:</u>			
29	REF. 193 fabric reinforcement in concrete surface beds, slabs, etc.	m2	24
<u>Waterproofing under Surface beds</u>			
30	350 Micron USB orange polyethylene dampproof membrane in accordance with SABS 952 Type C laid on sand bed (elsewhere measured).	m2	24
<u>STORMWATER CHANNELS</u>			
<u>Cast in-situ Ref 395 mesh reinforced concrete (25MPa) open stormwater channels having V-shaped waterway formed in top, finished smooth on all exposed surfaces in 3:1 cement plaster trowelled smooth and with angles rounded, cast in suitable lengths not exceeding 1.8m, including all formwork, moulds, shallow excavation, filling and ramming, laying to falls, bedding and pointing in 3:1 cement mortar. Concrete apron to be tinted, colour to be specified by the Engineer.</u>			
31	700 x 150mm V' channel 75mm deep in centre laid in position in ground in 1800mm sections including all excavations, imported filling (G5), ramming, trimming, formwork, reinforcement, expansion joints, floating etc.	m	20
32	Extra for 700mm angle	No	4
33	Extra for forming 200mm thick 700mm wide spreader with 200mm high edges fanning out to 1 960mm width at furthest end with hard burnt bricks pitching cast in ass diffusers including working off concrete to a smooth finish and draining onto natural ground with 150 - 200mm diameter loose stones.	No	4
Carried to Summary			R
PROVISIONAL BILLS OF QUANTITIES			

THE MVULA TRUST
KZN - SAFE BATCH 3
OMITTED SCOPE - CLUSTER EIGHT
QHINQA HIGH SCHOOL

Bill No	<u>FINAL SUMMARY</u>	Page No	Amount
1	PRELIMINARIES	3	
2	BUILDING WORKS	8	
3	EXTERNAL WORKS	13	
	<u>SUB-TOTAL EXCLUDING VAT</u>		R
	ADD 15% VALUE ADDED TAX		R
	Carried to Cluster 8 Final Summary Page PROVISIONAL BILLS OF QUANTITIES		R