

Project Title

Supply, deliver and install mains cable

Scope of Works

The successful applicant will:

Supply, delivery and install mains cable at Meyerton MW MF3 site:

	ITEMS MUST BE DELIVERED TO MEYERTON MW MF3	Quantity	WEIGHT/MASS
	Delivery address:		
	<ul style="list-style-type: none"> Supply 15m 35mm² x 3 core 11KV XPLE HT Cable 		
	<ul style="list-style-type: none"> Supply 2 x 35mm² 11KV XPLE Heat Shrink Joint kits 		
	<ul style="list-style-type: none"> Open 15m of trenching 		
	<ul style="list-style-type: none"> HT test off cable to open ends 		
	<ul style="list-style-type: none"> Joint 15m cable and test 		
	<ul style="list-style-type: none"> Close trench and cleaning after completion 		

NOTE:

On submission of your quote please attach

- your company's CSD Report; Valid Tax & BEE Certificates