

PRICING SCHEDULE FOR TENDER REF: ARC/57/11/2025

All prospective bidders are to note that installation of the galvanised palisade fencing must conform to the standards.

Name of bidder _____

Bidders are required to complete the BOQ form and submit their quotations, aligned with the breakdown provided below

Area 2:

ITEM	BOQ	UOM	QTY	RATE/Unit Price	TOTAL
Concrete Foundation & double wall					
1.	Site clearance and removal of the old fence, rubble, etc.	5 m on both sides, per meter	1 183 m	R	R
2.	Trench excavation (600x300 mm) and backfill with suitable G5 material compacted to 95%	Per meter	1 183 m	R	R
3.	Concrete footing (250x300mm) at not less than 32MPa strength	Per meter	1 183 m	R	R
4.	Steel reinforcement cage with 6Y12 R08 strips at the suitable centre	Per meter	1 183 m	R	R
5.	Double brick wall height: 1m above natural ground level	Per meter	1 183 m	R	R
6.	Drainage openings in wall covered with galvanized grid fixed to wall, in fence facing river	Per 100 meter	900 m	R	R
Palisade fence					
7.	Galvanized, poly-coated PVC steel palisade with spear points, colour green	1.2m high	1 183 m	R	R
8.	Shark-teeth spikes, long teeth, 65-110 mm	Per meter	1 183 m	R	R
9.	H-beam post, hot-dip galvanized, poly coated PVC steel post 75 x 75mm, 2.4 m high, planted in the double wall	Per unit		R	R

PRICING SCHEDULE FOR TENDER REF: ARC/57/11/2025

10.	Earth tabs fitted on corner posts, 815mm from the bottom	30x6x20 mm	1 183 m	R	R
11.	Sliding gate, motorized	Per unit	2	R	R
Topping- Razor wire					
12.	Flat warp razor wire on top with coil diameter of 700mm	Per meter	1 183 m	R	R
General					
13.	Labour (Allow for all costs involved in the installation of fence, wall, etc.)	Per day		R	R
14.	Travelling	Per KM		R	R
15.	Sundries (Cement etc.)	Provide itemized billing		R	R
16.	Occupational Health and Safety plan	Sum	1	R	R
17.	P & G	Provide itemized billing		R	R
18.	SUBTOTAL 1				R
19.	CONTINGENCY 15%				R
20.	SUBTOTAL 2				R
21.	VAT (15%)				R
22.	GRAND TOTAL				R
23.	State guarantee on workmanship-		Fencing (defects):	Year/s	R
			Brick wall (defects):	Year/s	R
			Pipe installation (defects):	Year/s	R