

## **RFQ 10401146**

### **Annexure C3.2: Scope of Work (including drawings, where applicable)**

- The Wastewater treatment works is currently in a state of decay it is therefore highly recommended to attend the site briefing to ensure accurate pricing.
- The team attending the briefing should include engineering technical personnel

#### **BNR Repairs:**

- Conduct an in-depth condition assessment of the BNR and compile a full scope of repairs
- Conduct all necessary repairs and replacements to ensure functionality of components/equipment
- Test and commission the BNR back to full functionality

#### **Electrical main feeder cable installation:**

- Replace electrical main feeder cable

#### **Cable Protection:**

- Secure all exposed cables onto cable ways/cable racks with a suitable heavy duty bracket clamp for every meter(M) length of cables.
- Conduct on site measurements to determine the length and size of the cable ways.
- Install metal cover plates over the cables on the cable ways/cable racks.
- The cover plates must be welded to the cable ways