1200 GENERAL REQUIREMENTS AND PROVISIONS

	GENERAL REQUIREMENTS AND PROVISIONS				SECTION 1200
Item No.	Description	Unit	Quantity	Rate	Amount
B12.01	Accredited Training:  (a) Provisional Sum for training allowance to targeted labour undergoing training  (a) Technical skills and student training  (b) Generic skills	Prov Sum	1	R 180,000.00	R 180,000.00
	© Entrepeneural skills (d) Renumeration of workers undergoing technical skills training (e) Training Venue (f) Contractors handling costs, profit and all other charges in respect of subitems B 12.01 above	%	R 180,000.00		R -
B12.02	Allow a provisional sum for relocation/protection of existing services when ordered by the Eng.	Prov Sum	1	R 240,000.00	R 240,000.00
	(b) Contractors Handling cost and profit and all other charges in respect of subitem B12.02 above	%	R 240,000.00		R -
TOTAL CARRI	ED FORWARD TO SUMMARY				R -

1300 CONTRACTORS ESTABLISHMENT ON SITE AND GENERAL OBLIGATIONS

SECTION	1300
Amour	nt

	CONTRACTORS ESTABLISHMENT ON SITI	ı		1	D-4-	<u> </u>	Amount
Item No.	Description	Unit	Quantity	-	Rate		Amount
B13.01	Contractor`s General Obligation						
	(a) Contractors Fixed Establishment	LSum	1	R	-	R	-
	(b) Contractors Value related	LSum	1	R	-	R	-
	© Time related costs	Month	12	R	-	R	-
	Note: The combined total tender amount subpitems (a), (b) and © should not more than 15% of theTender sum (excluding Contingencies, CPA and VAT)						
B13.03	Contract Nameboard:						
	(a) Supply and erect two contract nameboards	Sum	1				
B13.06	Occupational Health & Safety:						
	(a) Preparation of a Health and Safety plan     (b) Compilation of a Risk Assesment	Sum	1				
	prior to construction	Sum	1				
	© Health and Safety Induction Training of employees	Sum	1				
	(d) Compilation and the keeping up to date of a Health and Safety file, which shall include all documentation required in terms of the Act	Sum	1				
	(e) Implementation of the Health and	Sum	'				
	Safety Plan over the entire construction period	Month	12				
TOTAL CARE	RIED FORWARD TO SUMMARY			•		R	-

1400 HOUSING,OFFICERS AND LABORATORIES FOR THE ENGINEER SITE PERSONNEL SECTION 1400

Item No.	Description	Unit	Quantity		Rate		Amount
			-				
14.01	Office and Laboratory Accomodation:						
	(a) Offices (Interior floor space only)	m <sup>2</sup>	40	R	-	R	-
	(e) Ablution units	m <sup>2</sup>	40	R	-	R	-
14.02	Office and laboratory from it we						
14.02	Office and laboratary furniture:						
	(a) Chairs	No	20	R	_	R	_
	(b) Draughtsman Stools	No	1	R	_	R	_
	(d) Desk complete with drawers and locks	No	1	R	-	R	-
	(e) Drawing Tables	No	1	R	-	R	-
	(f) Conference Tables	No	1	R	-	R	-
14.03	Carports as specified at offices	No	2	R	-	R	-
1,101	( ) ( ) ( ) ( ) ( ) ( )					_	
14.04	(a) (I) Services for offices and laboratories:	Lsum	1	R	-	R	-
	(a) (ii) Running costs	month	12	R		R	
	(a) (ii) Rullilling costs	monun	12	^	-		-
14.10	Provision of photostat facilities	month	12	R	_	R	_
	Processing and the second of t			``		``	
						<u> </u>	
TOTAL CA	RRIED FORWARD TO SUMMARY					R	-

6

#### 1500 ACCOMODATION OF TRAFFIC

	D ACCOMODATION OF TRAFFIC						110N 1500
em No.	Description	Unit	Quantity	F	Rate	A	mount
B15.01	Accomodation of traffic and maintaining temporary diviations	m	4300	R	-	R	-
15.02	Earthworks for deviations						
	(a) Shaping of temporary deviations	m	4300	R	-	R	-
	(b) Cut and Borrow to fill	m <sup>3</sup>	5,160	R	-	R	-
	© Cut to spoil	m <sup>3</sup>	4599	R	-	R	-
15.03	Temporary traffic-control facilities						
	(a) Flagperson	days	1500	R	-	R	-
	(b) Portable Stop and Go sign	NO	2	R	-	R	-
	(d) Amber flicker lights	No	2	R	-	R	-
	(g) Road Signs, STW-,DTG-,TGS-,and TG series (excluding delineators barricades)	No	10	R	-	R	-
	(h) (l) Single Plate Delineartors	no	5	R	-	R	-
	(h) (ii) Dual Plate Delineators 1000x250	no	10	R	-	R	-
	( n) Provision of High visibility Savety Jackets and safety hats	no	5	R	-	R	-
15.06	Watering of temporary deviations	kl	2500	R	-	R	-
15.07	Blading temporary deviations	km-pass	160	R	-	R	-
15.12	Temporary culverts						
	(a) Provision and laying of temporary prefabricated culverts Class 50D load concrete pipe culverts SC type with OG joints On class C bedding:						
	(a) (1) Temporary culverts 900mm	m	7.2	R	-	R	-
OTAL CARR	LI RIED FORWARD					R	_

6

1500	ACCOMMODATION OF TRAFFIC						
Item No.	Description	Unit	Quantity	R	ate	А	mount
BROUGHT FO	RWARD					R	-
	(a) (3) Temporary culverts 900mm	m	15	R	-	R	-
15/16.02	Overhaul on material hauled in excess of 1,0km	m <sup>3</sup> km	14,250	R	-	R	-
15/31.01	Excess Olverburden	m <sup>3</sup>	2,300	R	-	R	-
15/55.4 ( a)	Fences						
15/55.04 ( 1)	1.2m High Stock proof fences	m	960	R	-	R	-
TOTAL CARI	 RIED FORWARD TO SUMMARY					R	

1700 CLEARING AND GRUBBING

Item No.	Description	Unit	Quantity	Rate	Amount
B17.01	Clearing and Grubbing of:				
	(a) Normal areas				
	(I) Within road reserve	ha	0.3	R -	R -
	( ii) In borrow pits	ha	0.3	R -	R -
IED FORWARD	TO SUMMARY				R -

# C2.2-2 UPGRADING OF MASOYI POLICE STATION TO DINGINDODA ROAD WARD $\ensuremath{6}$

2100 DRAINAGE SECTION 2100

210	0 DRAINAGE					SE	CTION 2100
m No.	Description	Unit	Quantity	F	Rate		Amount
21.01	(a) Excavation for open drains in soft within the following depth ranges:						
	0 m to 1,5 m	m <sup>3</sup>	1,134	R	-	R	-
	Exceeding 1,5 m up to 3 m	$m^3$	284	R	-	R	-
21.03	Excavation for sub-soil drainage systems: (a) Excavating soft material situated within the following depths ranges:						
	( i) 0 m to 1, 5 m	m <sup>3</sup>	60	R	-	R	-
21.04	Impermeable Backfilling to subsoils drainage system	$m^3$	10	R	-	R	-
21.06	(b) (l) Natural permeable backfilling using fine grade stone (13,2mm)	m <sup>3</sup>	15	R	-	R	-
21.06	(b) (ii) Natural permeable backfilling using coarse grade stone (19 mm)	m <sup>3</sup>	15	R	-	R	-
21.07	(b) (l) Natural permeable material to subsoint Sand obtained from commercial sources	il: m³	30	R	-	R	-
B21.08	Pipes in subsoil drainage system:						
	© ( I) 160 mm internal dia pipe slotted	m	80	R	-	R	-
	© (Ii) 160 mm internal dia pipe unslotted	m	40	R	-	R	-
B21.09	Polyethylene sheeting 0,250mm thick or similar , approved material, for lining subsoil drainage	m2	288	R	-	R	-
21.10	Synthetic Fibre filter fabric ( a) Non- woven kaymat A4 geotextile	m2	384	R	-	R	-
21.12	or similar approved  Concrete outlet structures, manholes boxes	no	2	R	-	R	-
TAL CARR						R	_

#### 2200 PREFABRICATED CULVERTS

	RICATED CULVERTS					35	CTION 2200
Item No.	Description	Unit	Quantity	F	Rate		Amount
22.01	(a) (l) Excavating soft material situated within the following depth ranges: On	m³	70				
	up to 1,5 mm		72	R	-	R	-
22.01	(a) (ii) Excavating soft material: 1,5m up to 3,0	m <sup>3</sup>	30	R	-	R	-
B22.02	( a) Backfill with excavated material	m <sup>3</sup>	220	R	-	R	-
	( b) Backfill with imported material	m <sup>3</sup>	66	R	-	R	-
	© Exta Over for soil Cement Backfill (5%)	m <sup>3</sup>	36	R	-	R	-
22.03	(b) Concrete pipe culverts: On class C bedding:						
	75D- load pipes,SC type,Ogee joints						
	(i) 600mm Concrete Pipe	m	36	R	-	R	-
22.17	© ( i) Kerb inlet complete with kerb transitions  Type A	no	4	R	-	R	-
22.25	Overhaul on excavated material carted to spoil backfill material	m <sup>3</sup> km	52,560	R	-	R	-
TOTAL CARR	ED FORWARD TO SUMMARY					R	
I O I VE CARK	ILD I OVANUE TO COMMINATE					L'\	

						SEC	TION 2300
Item No.	Description	Unit	Quantity	F	Rate		Amount
23.01	Concrete kerbing-Class 25/19  ( a) Semi-Moutable kerbs ( 280 x 180) - Figure 7A	m	7,608	R	-	R	-
23.02	Concrete kerbing-channeling combination						
	(a) Type "B" (260 X 125) at guardrails	m	560	R	-	R	-
23.07	( a) Trim excavation in soft material	m <sup>2</sup>	3,840	R	-	R	-
23.08	(a) (i) Concrete Lining 25/19 side drains	m <sup>3</sup>	461	R	-	R	-
23.08	( b) Class U2 surface finish to cast insitu concrete Side drains	m²	3,840	R	-	R	-
23.09	(b) To sides with formwork on external face only	m²	600	R	-	R	-
23.09	© Formwork to ends of slabs (F2 surface finish)	m <sup>2</sup>	320	R	-	R	-
23,10	Sealed joints in concrete linings of open drains with Flexcell 10mm	m	41	R	-	R	-
23.12	Steel Reinforcement: Using welded mesh Ref 193 Welded steel fabric	m <sup>2</sup>	384	R	-	R	-
23.13	Polysheeting 0.15mm thick for concrete lined open drains	m <sup>2</sup>	240	R	-	R	-
23/51.04	Segmented block paving (80 mm interlocking 25Mpa)	m²	40,300	R	-	R	-
						<u> </u>	
TOTAL CARRI	ED FORWARD TO SUMMARY					R	-

3300 MASS EARTHWORKS

	MASS EARTHWORKS						CTION 3300
Item No.	Description	Unit	Quantity	R	Rate		Amount
33.01	(a) Cut and borrow to fill, including free-haul up to 0,5 F for material I compacted layer thickness of 200 mm and less:	km 					
	(i) Compacted to 90% of modified AASHTO density	m <sup>3</sup>	7,800	R	-	R	-
	( ii) Compacted to 93% of modified AASHTO density	m <sup>3</sup>	6,240	R	-	R	-
B33.04	( a) Cut to spoil, Including free-haul up to 1 km: Material obtained from soft excavation	m <sup>3</sup>	2,340	R	-	R	-
	(b) Cut to Spoil, Material obtained from Intermediate excavation	m <sup>3</sup>	1,560	R	-	R	-
B33.07	Removal of unsuitable material (including free-haul of 0,5 km)	m <sup>3</sup>	9,360	R	-	R	-
33.10	Roadbed preparation and the compaction 0f material						
	( b) Compaction to 93% of modified AASHTO density	m <sup>3</sup>	6,240	R	-	R	-
33.11	Finishing-off cut and fill slopes, medians and interchanges						
	(a) Cut slopes	m2	450	R	-	R	-
	(b) Fill slopes	m2	350	R	-	R	-
33/31.03	( c) Finish-off borrow areas in intermediate material	ha	0.2	R	-	R	-
TOTAL CARRI	ED FORWARD TO SUMMARY					R	-

em No.	GRAVEL PAVEMENT LAYERS					SECT	ION 3400
	Description	Unit	Quantity	F	Rate	А	mount
ROUGHT FOF	RWARD						
34.01	Pavement Layers constructed from gravel taken						
	from cut or borrow, including fre-haul						
	up to 1,0 km:						
34.01	(a) 200 mm or less Gravel Selected layer compacted to:	m <sup>3</sup>	5.000	_			
	(i) 93% of modified AASHTO density	m	5,688	R	-	R	-
	© 150 mm Gravel Subbase (unstabllised) compacted to:						
	( ii) 95% of modified AASHTO density	$m^3$	1,806	R	-	R	
	(d) 150 mm Gravel Subbase (chemically stabilised) compacted to:						
	( ii) 95% of modified AASHTO density	m <sup>3</sup>	5,878	R	-	R	-
34.01/36.01	(c) Crushed stone base constructed from type G2 material						
	obtained from commercial sources and compacted to 85%						
	of bulk relative density (150mm)	m <sup>3</sup>	5,878	R	-	R	
	( ii) 98% of modified AASHTO density	m <sup>3</sup>	1,080	R	-	R	
	(g) 150 mm Gravel Shoulders compacted to:						
	( ) 93% of modified AASHTO density	m <sup>3</sup>	187	R	-	R	
34.02	Extra over 34.01 for excavating material in:						
	( a) intermediate excavation	m <sup>3</sup>	1,138	R	-	R	
	( b) Hard Excavation	m <sup>3</sup>	284	R	-	R	
34.03	Pavement layers constructed from gravel obtained from existing pavement layers:						
	(a) (i) Gravel selected layer compacted to 93% of MOD	m <sup>3</sup>	2,988	R	-	R	
	AASHTO density, using non-cemented material 150 mm						

3500 **STABILIZATION** SECTION 3500 Item No. Description Unit Quantity Rate Amount 35.01  $\,m^3\,$ (a) E/o for unstabilized compacted layers: 294 R Crushed stone Base layer 150mm thick (b) E/o for unstabilized compacted layers  $m^3$ 5,878 R R for : Gravel Subbase layer 150mm thick 35.02 (a) Ordinary Portland Cement 388 R R ton (b) Portland Blast Furnace Cement Rate R Rate Only ton (d) Ground Granulated blast-furnace slag Rate R Rate Only ton 35.04 Provision and application of water for kl 3,780 R R curing R

Item No. Description Unit Quantity Rate	CTION 4100
41.01 (b) MC 30 Cut back bitumen litre 64,000 R - R	Amount
	Rate Only
41.02 Aggregate for blinding m <sup>2</sup> 6,400 R - R	-
	-
TOTAL CARRIED FORWARD TO SUMMARY R	

4200	ASPHALT BASE AND SURFACING					
Item No.	Description	Unit	Quantity	Rate	Amount	
42.02	Asphalt Surfacing (30mm thickness)					
	(a) Continuously graded (medium 13.2mm stone in all areas	m²	200	R -	R -	
	III all aleas	""	200	R -	-	
42.04	Tack coat of 30% stable-grade emulsion	I	82	R -	R -	
42/7300	CONCRETE BLOCK PAVING					
TOTAL CAR	RIED FORWARD TO SUMMARY				R -	

5100	EROSION CONTROL	SECTION 5100			
Item No.	Description	Unit	Quantity	Rate	Amount
51.01	(a) (i) Pitching Method 1	m²	320	R -	R -
51.01	( ii) Pitching method 2	m²	2	R -	Rate Only
51.01	(b) Grouted Stone Pitching	m <sup>2</sup>	260	R -	R -
51.05	Concrete edge beams and foundation trenches with class 25/19 concrete	m³	30	R -	R -
TOTAL CAR	RIED FORWARD TO SUMMARY				R -

5200 **GABIONS** SECTION 5200 Item No. Description Unit Quantity Rate Amount 52.01 Foundation trench excavation and backfilling  $m^3$ 52.01 (a) In solid rock (material which requires blasting) 50 R  $m^3$ 52.01 (b) Trench Excavation in all other classes 30 R  $m^2$ 52.02 20 R Surface Preparation for bedding the gabions R 52.03 (a) Galvanized Gabion boxes 52.03 ( ) 2,0 long by 1,0m wide by 0,3 m thick  $m^3$ 80mm x100mm by 2.7mm nominal internal wire mesh 30 R R 52.04 (a) Bidum/Kaymat u34 or similar R R TOTAL CARRIED FORWARD TO SUMMARY

5300	GUIDE BLOCKS	O			SECTION 530
m No.	Description	Unit	Quantity	Rate	Amount
53.01	Guide Blocks	No	6	R -	R -
53.01	Guide Blocks	INO	0	K -	R -
	RRIED FORWARD TO SUMMARY				R 0.00

5400	GUARDRAILS	SECTION 5400					
tem No.	Description	Unit	Quantity	Ra	te	P	Amount
53\54.01	Guardrails on timber posts Galvanised	m	80	R	-	R	-
53/54.04e	End Treatment Single Guardrails	no	2	R	-	R	-
53/54.05	Extra Timber Posts	No	10	R	-	R	-
53/54.06	New Reflective Plates	no	20	R	-	R	-
OTAL CAR	RIED FORWARD TO SUMMARY					1	R 0.00

5600 **ROAD SIGNS SECTION 5600** Item No. Description Unit Quantity Rate Amount 56.01 © Roadsign boards with painted or coloured semi-matt background. Symbols, lettering and bordersin semi-matt black or in class 1 retroreflective material, where the sign board is constructed from: Prepainted galvanised steel plate (chromadek 1,6mm thick or approved equivalent)  ${\rm m}^{\rm 2}$ (i) Area not exceeding 2m2 R 56.01 30  $\,m^2\,$ Areaexceeding 2m<sup>2</sup> but not 10m 56.01 R R 18 Area exceeding 10m<sup>2</sup>  $m^2$ 56.02 84 R 56.01 Danger Plates 600 x 150mm 32 R R No 56.02 (a) (iii) Eo B56.01 for using Retro-reflective materia  $m^2$ 112 R R Class 1  $m^2$ 56.02 (b) (ii) Eo Letters, symbol, numbers, arrows, embl R R 45 and borders of retro-reflective material: Class 3 56.03 125 R (b) 150mm Timber Supports R m 56.05  $m^3$ 80 R R Exc and backfill to road signs 56.06 Eo for soil cement backfill  $m^3$ 80 R R 56.07 EO for rock excavation R TOTAL CARRIED FORWARD

5700	ROAD MARKING	6			SECTION 5700
Item No.	Description	Unit	Quantity	Rate	Amount
57.01	(g) Kerb Markings	m²	20	R -	R -
57.02	(a) (1) 100mm White Reflective Lines	km	7	R -	R -
57.02b	(b) (l) 150mm Yellow Line reflective	km	16	R -	R -
57.04	( a) Variation White Paint	I	30	R -	R -
57.04	( b) Variations Yellow Paint	I	230	R -	R -
57.04	(d) Variations Retroreflective Beads	kg	480	R -	Rate Only
57.06	Setting out and Premarking ( excluding traffic island markings, lettering and symbols)	Sum	1	R -	R -
TOTAL CAR	RIED FORWARD TO SUMMARY				R -

6

5900 FINISHING THE ROAD RESERVE AND TREATING OLD ROADS SECTION 5900 Item No. Description Unit Quantity Rate Amount 59.01 (b) Finish Single Carriageway km R R 59.02 Treatment of old roads 12 R R km

TOTAL CARRIED FORWARD TO SUMMARY

R

8100 TESTING MATERIAL AND WORKMANSHIP SECTION 8100 Item No. Description Unit Quantity Rate Amount 81.02 (a) Cost of Testing R 450,000.00 R 450,000.00 **PCsum** 81.02 (b) Handling cost and profit % 450,000 R

TOTAL CARRIED FORWARD TO SUMMARY

#### **SUMMARY TOTALS**

SUB TOTAL	R -
SECTION 8100	R -
SECTION 5900	R -
SECTION 5700	R -
SECTION 5600	R -
SECTION 5400	R -
SECTION 5300	R -
SECTION 5200	R -
SECTION 5100	R -
SECTION 4200	R -
SECTION 4100	R -
SECTION 3500	R -
SECTION 3400	R -
SECTION 3300	R -
SECTION 2300	R -
SECTION 2200	R -
SECTION 2100	R -
SECTION 1700	R -
SECTION 1500	R -
SECTION 1400	R -
SECTION 1300	R -
SECTION 1200	R -

10% Contingencies	R	-
6% CPA	R	-
Sub Total	R	-
15% VAT	R	-
GRAND TOTAL	R	_