

Item No	Quantity	Rate	Amount
<p><b><u>SECTION No. 1 - PRELIMINARIES</u></b></p> <p><b><u>BILL NO. 1</u></b></p> <p><b><u>PRELIMINARIES</u></b></p> <p><b><u>MEANING OF TERMS "TENDER / TENDERER"</u></b></p> <p>Any reference to the words "Tender" or "Tenderer" herein and/or in any other documentation shall be construed to have the same meaning as the words "Bid" or "Bidder"</p> <p><b><u>PRELIMINARIES</u></b></p> <p>The JBCC Preliminaries Code 2103, May 2005 edition for use with the JBCC Principal Building Agreement Edition 4.1 Code 2101, March 2005 is taken to be incorporated herein. The tenderer is deemed to have referred to these documents for the full intent and meaning of each clause. These clauses are referred to by number and heading only. Where standard clauses or options are not applicable to the contract such modifications or corrections as are necessary are given under each relevant clause. Where an item is not relevant to this specific contract such item is marked "N/A" signifying "Not Applicable"</p> <p><b><u>PRICING OF PRELIMINARIES</u></b></p> <p>Should Option A, as set out in clause B10.3.1 hereinafter be used for the adjustment of preliminaries then each item priced is to be allocated to one or more of the three categories Fixed, Value Related or Time Related and the respective amounts entered in the spaces provided under each item</p> <p>Items not priced in these Preliminaries shall be deemed to be included elsewhere in these Bills of Quantities</p>			
<b>Carried to Collection</b>			R
<p>Section No. 1 Bill No. 1 PRELIMINARIES AND GENERAL <b>PROVISIONAL BILL OF QUANTITIES</b></p>			

**SECTION A: JBCC PRINCIPAL BUILDING AGREEMENT**

**DEFINITIONS**

1 **A1.0 DEFINITIONS AND INTERPRETATION**

Clause 1.0

Clause 1.1 Definition of "**Commencement Date**" is added:

"**COMMENCEMENT DATE**" means the date that is 5 working days after site hand over.

Clause 1.1 Definition of "**Construction Guarantee**" is amended by replacing it with the following:

"**CONSTRUCTION GUARANTEE**" means a guarantee at call obtained by the **contractor** from an institution approved by the **employer** in terms of the **employer's** construction guarantee form as selected in the **schedule**

Clause 1.1 Definition of "**Construction Period**" is amended by replacing it with the following:

"**CONSTRUCTION PERIOD**" means the period commencing on the **commencement date** and ending on the date of **practical completion**

Clause 1.1 Definition of "**Corrupt Practice**" is added:

"**CORRUPT PRACTICE**" means the offering, giving, receiving or soliciting of anything of value to influence the action of a public official in the procurement process or in contract execution

Clause 1.1 Definition of "**Fraudulent Practice**" is added:

**Carried to Collection**

Section No. 1  
Bill No. 1  
PRELIMINARIES AND GENERAL  
**PROVISIONAL BILL OF QUANTITIES**

R

**"FRAUDULENT PRACTICE"** means a misrepresentation of facts in order to influence a procurement process or the execution of a contract to the detriment of any tenderer and includes collusive practice among tenderers (prior to or after the tender submission) designed to establish tender prices at artificial non-competitive levels and to deprive the tenderer of the benefits of free and open competition

Clause 1.1 Definition of **"Interest"** is amended by replacing it with the following:

**"INTEREST"** means the interest rates applicable on this contract, whether specifically indicated in the relevant clauses or not, will be in terms of the legislation of the Republic of South Africa, and in particular:

(a) in respect of interest owed by the employer, the interest rate as determined by the Minister of Justice and Constitutional Development from time to time, in terms of section 1(2) of the Prescribed Rate of Interest Act, 1975 (Act No. 55 of 1975), will apply;

and

(b) in respect of interest owed to the employer, the interest rate as determined by the Minister of Finance, from time to time, in terms of section 80(1)(b) of the Public Finance Management Act, 1999 (Act No. 1 of 1999), will apply

Clause 1.1 Definition of **"Principal Agent"** is amended by replacing it with the following:

**"PRINCIPAL AGENT"** means the person or entity appointed by the **employer** and named in the **schedule**. In the event of a **principal agent** not being appointed, then all the duties and obligations of a **principal agent** as detailed in the **agreement** shall be fulfilled by a representative of the **employer** as named in the **schedule**

Clause 1.1 Definition of **"Security"** is amended by replacing it with the following:

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
PRELIMINARIES AND GENERAL  
**PROVISIONAL BILL OF QUANTITIES**

**"SECURITY"** means the form of security provided by the **employer** or **contractor**, as stated in the **schedule**, from which the **contractor** or **employer** may recover expense or loss

Clause 1.6 is amended by replacing the words "prepaid registered post, telefax or e-mail" with "prepaid registered post or telefax"

Clause 1.6.4 is amended by replacing it with the following:

No clause

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**OBJECTIVE AND PREPARATION**

**1 A2.0 OFFER, ACCEPTANCE AND PERFORMANCE**

Clause 2.0

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**2 A3.0 DOCUMENTS**

Clause 3.0

Clause 3.2.1 is amended by replacing "14.1" with "14.0"

Clause 3.7 is amended by the addition of the following:

The **contractor** shall supply and keep a copy of the **JBCC** Series 2000 Principal Building Agreement and Preliminaries applicable to this contract on the **site**, to which the **employer, principal agent** and **agents** shall have access at all times

Clause 3.10 is amended by replacing the second reference to "**principal agent**" with the word "**employer**"

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
**PRELIMINARIES AND GENERAL  
PROVISIONAL BILL OF QUANTITIES**

1 **A4.0 DESIGN RESPONSIBILITY**  
 Clause 4.0  
 Clause 4.3 is amended by replacing it with the following:  
 No clause  
 Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
 related: \_\_\_\_\_

Item

2 **A5.0 EMPLOYER'S AGENTS**  
 Clause 5.0  
 Clause 5.1.2 is amended to include clauses 32.6.3, 34.3  
 and 34.4 in terms of which the employer has retained its  
 authority and has not given a mandate to the principal  
 agent and in terms of which the employer shall sign all  
 documents.  
 Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
 related: \_\_\_\_\_

Item

3 **A6.0 SITE REPRESENTATIVE**  
 Clause 6.0  
 Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
 related: \_\_\_\_\_

Item

4 **A7.0 COMPLIANCE WITH REGULATIONS**  
 Clause 7.0  
 Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
 related: \_\_\_\_\_

Item

5 **A8.0 WORKS RISK**  
 Clause 8.0  
 Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
 related: \_\_\_\_\_

Item

**Carried to Collection**

R

Section No. 1  
 Bill No. 1  
**PRELIMINARIES AND GENERAL  
 PROVISIONAL BILL OF QUANTITIES**

1 **A9.0 INDEMNITIES**

Clause 9.0

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

2 **A10.0 WORKS INSURANCES**

Clause 10.0

Clause 10.0 is amended by the addition of the following clauses:

**10.5 Damage to the Works**

- (a) Without in any way limiting the **contractor's** obligations in terms of the contract, the **contractor** shall bear the full risk of damage to and/or destruction of the **works** by whatever cause during construction of the **works** and hereby indemnifies and holds harmless the **employer** against any such damage. The **contractor** shall take such precautions and security measures and other steps for the protection and security of the **works** as the **contractor** may deem necessary
- (b) The **contractor** shall at all times proceed immediately to remove or dispose of any debris arising from damage to or destruction of the **works** and to rebuild, restore, replace and/or repair the **works**
- (c) The **employer** shall carry the risk of damage to or destruction of the **works** and materials paid for by the **employer** that is the result of the excepted risks as set out in 10.6
- (d) Where the **employer** bears the risk in terms of this contract, the **contractor** shall, if requested to do so, reinstate any damage or destroyed portions of the **works** and the costs of such reinstatement shall be measured and valued in terms of 32.0 hereof

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
PRELIMINARIES AND GENERAL  
**PROVISIONAL BILL OF QUANTITIES**

**10.6 Injury to Persons or loss of or damage to Properties**

- (a) The **contractor** shall be liable for and hereby indemnifies the **employer** against any liability, loss, claim or proceeding whether arising in common law or by statute, consequent upon personal injuries to or the death of any person whomsoever arising out of or in the course of or caused by the execution of the **works** unless due to any act or negligence of any person for whose actions the **employer** is legally liable
  
- (b) The **contractor** shall be liable for and hereby indemnifies the **employer** against any liability, loss, claim or proceeding consequent upon loss of or damage to any moveable or immovable or personal property or property contiguous to the **site**, whether belonging to or under the control of the **employer** or any other body or person, arising out of or in the course of or by reason of the execution of the **works** unless due to any act or negligence of any person for whose actions the **employer** is legally liable
  
- (c) The **contractor** shall, upon receiving a **contract instruction** from the **principal agent**, cause the same to be made good in a perfect and workmanlike manner at his own cost and in default thereof the **employer** shall be entitled to cause it to be made good and to recover the cost thereof from the **contractor** or to deduct the same from amounts due to the **contractor**
  
- (d) The **contractor** shall be responsible for the protection and safety of such portions of the premises placed under his control by the **employer** for the purpose of executing the **works** until the issue of the **certificate of practical completion**

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
PRELIMINARIES AND GENERAL  
**PROVISIONAL BILL OF QUANTITIES**

- (e) Where the execution of the **works** involves the risk of removal of or interference with support to adjoining properties including land or structures or any structures to be altered or added to, the **contractor** shall obtain adequate insurance and will remain adequately insured or insured to the specific limit stated in the contract against the death of or injury to persons or damage to such property consequent on such removal or interference with the support until such portion of the **works** has been completed
  
- (f) The **contractor** shall at all times proceed immediately at his own cost to remove or dispose of any debris and to rebuild, restore, replace and/or repair such property and to execute the **works**

**10.7 High risk insurance**

In the event of the project being executed in a geological area classified as a "High Risk Area", that is an area which is subject to highly unstable subsurface conditions that might result in catastrophic ground movement evident by sinkhole or doline formation the following will apply:

**10.7.1 Damage to the works**

The **contractor** shall, from the **commencement date** of the **works** until the date of the **certificate of practical completion** bear the full risk of and hereby indemnifies and holds harmless the **employer** against any damage to and/or destruction of the **works** consequent upon a catastrophic ground movement as mentioned above. The **contractor** shall take such precautions and security measures and other steps for the protection of the **works** as he may deem necessary

When so instructed to do so by the **principal agent**, the **contractor** shall proceed immediately to remove and/or dispose of any debris arising from damage to or destruction of the **works** and to rebuild, restore, replace and/or repair the **works**, at the **contractor's** own costs

**Carried to Collection**

Section No. 1  
 Bill No. 1  
**PRELIMINARIES AND GENERAL  
 PROVISIONAL BILL OF QUANTITIES**

R

**10.7.2 Injury to persons or loss of or damage to property**

The **contractor** shall be liable for and hereby indemnifies and holds harmless the **employer** against any liability, loss, claim or proceeding arising at any time during the period of the contract whether arising in common law or by statute, consequent upon personal injuries to or the death of any person whomsoever resulting from, arising out of, or caused by a catastrophic ground movement as mentioned above

The **contractor** shall be liable for and hereby indemnifies the **employer** against any and all liability, loss, claim or proceeding consequent upon loss of or damage to any moveable or immovable or personal property or property contiguous to the **site**, whether belonging to or under the control of the **employer** or any other body or person whomsoever arising out of or caused by a catastrophic ground movement, as mentioned above, which occurred during the period of the contract

**10.7.3** It is the responsibility of the **contractor** to ensure that he has adequate insurance to cover his risk and liability as mentioned in 10.7.1 and 10.7.2. Without limiting the **contractor's** obligations in terms of the contract, the **contractor** shall, within twenty-one (21) **calendar days** of the **commencement date** but before commencement of the **works**, submit to the **employer** proof of such insurance policy, if requested to do so

**10.7.4** The **employer** shall be entitled to recover any and all losses and/or damages of whatever nature suffered or incurred consequent upon the **contractor's** default of his obligations as set out in 10.7.1; 10.7.2 and 10.7.3. Such losses or damages may be recovered from the **contractor** or by deducting the same from any amounts still due under this contract or under any other contract presently or hereafter existing between the **employer** and the **contractor** and for this purpose all these contracts shall be considered one indivisible whole

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
PRELIMINARIES AND GENERAL  
**PROVISIONAL BILL OF QUANTITIES**

1	<p><b>A11.0 LIABILITY INSURANCES</b></p> <p>Clause 11.0</p> <p>Fixed: _____ Value related: _____ Time related: _____</p>	Item	
2	<p><b>A12.0 EFFECTING INSURANCES</b></p> <p>Clause 12.0</p> <p>Fixed: _____ Value related: _____ Time related: _____</p>	Item	
3	<p><b>A13.0 No clause</b></p>	N/A	
4	<p><b>A14.0 SECURITY</b></p> <p>Clause 14.0</p> <p>Clauses 14.1 - 14.8 are amended by replacing them with the following:</p> <p>14.1 The security to be submitted by the contractor to the employer will be as a payment reduction of up to ten per cent (10%) of the value certified in the payment certificate (excluding VAT)</p> <p>14.1.1 The payment reduction of the value certified in a <b>payment certificate</b> shall be <i>mutatis mutandi</i> in terms of 31.8(A)</p> <p>14.1.2 The <b>employer</b> shall be entitled to recover expense and loss from the payment reduction in terms of 33.0 provided that the <b>employer</b> complies with the provisions of 33.4 in which event the <b>employer's</b> entitlement shall take precedence over his obligations to refund the payment reduction <b>security</b> or portions thereof to the <b>contractor</b></p> <p>14.2 Where security as a payment reduction of ten per cent (10%) of the value certified in the payment certificate (excluding VAT) has been selected:</p> <p>14.2.1 The payment reduction of the value certified in a <b>payment certificate</b> shall be <i>mutatis mutandi</i> in terms of 31.8(B)</p> <p style="text-align: right; margin-right: 50px;"><b>Carried to Collection</b></p>		R
	<p>Section No. 1 Bill No. 1 PRELIMINARIES AND GENERAL <b>PROVISIONAL BILL OF QUANTITIES</b></p>		

14.2.2 The **employer** shall be entitled to recover expense and loss from the payment reduction in terms of 33.0 provided that the **employer** complies with the provisions of 33.4 in which event the **employer's** entitlement shall take precedence over his obligations to refund the payment reduction **security** or portions thereof to the **contractor**

14.9 Should the **contractor** fail to furnish the **security** in terms of 14.2, the **employer**, in his sole discretion and without notification to the **contractor**, is entitled to change the **contractor's** selected form of **security** to that of a ten per cent (10%) payment reduction of the value certified in the **payment certificate** (excluding VAT), whereafter 14.7 shall be applicable

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**EXECUTION**

**1 A15.0 PREPARATION FOR AND EXECUTION OF THE WORKS**

Clause 15.0

Clause 15.1.1 is amended by replacing it with:

No clause

Clause 15.1.2 is amended by replacing it with:

The **security** selected in terms of 14.0

Clause 15.1 is amended by the addition of the following clause:

15.1.4 An acceptable health and safety plan, required in terms of the Occupational Health and Safety Act, 1993 (Act 85 of 1993), within fourteen (14) **calendar days of commencement date**

Clause 15.2.1 is amended by replacing it with the following clause:

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
PRELIMINARIES AND GENERAL  
**PROVISIONAL BILL OF QUANTITIES**

Give the **contractor** possession of the **site** within ten (10) **working days** of the **contractor** complying with the terms of 15.1.4

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**1 A16.0 ACCESS TO THE WORKS**

Clause 16.0

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**2 A17.0 CONTRACT INSTRUCTIONS**

Clause 17.0

Clause 17.1.11 is amended by deleting the words "and the appointment of **nominated** and **selected subcontractors**"

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**3 A18.0 SETTING OUT OF THE WORKS**

Clause 18.0

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_  
Time related: \_\_\_\_\_

Item

**4 A19.0 ASSIGNMENT**

Clause 19.0

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
**PRELIMINARIES AND GENERAL  
PROVISIONAL BILL OF QUANTITIES**

1    **A20.0 NOMINATED SUBCONTRACTORS**

Clause 20.0

Clause 20.1.3 is amended by replacing it with the following:

No clause

Note: See item B9.1 hereinafter for adjustment of attendance on **nominated subcontractors** executing work allowed for under provisional sums

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

2    **A21.0 SELECTED SUBCONTRACTORS**

Clause 21.0

Clause 21 is amended by replacing it with:

No clause

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

3    **A22.0 EMPLOYER'S DIRECT CONTRACTORS**

Clause 22.0

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

4    **A23.0 CONTRACTOR'S DOMESTIC SUBCONTRACTORS**

Clause 23.0

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
PRELIMINARIES AND GENERAL  
**PROVISIONAL BILL OF QUANTITIES**

**COMPLETION**

**1 A24.0 PRACTICAL COMPLETION**

Clause 24.0

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
related: \_\_\_\_\_

Item

**2 A25.0 WORKS COMPLETION**

Clause 25.0

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
related: \_\_\_\_\_

Item

**3 A26.0 FINAL COMPLETION**

Clause 26.0

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
related: \_\_\_\_\_

Item

**4 A27.0 LATENT DEFECTS LIABILITY PERIOD**

Clause 27.0

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
related: \_\_\_\_\_

Item

**5 A28.0 SECTIONAL COMPLETION**

Clause 28.0

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
related: \_\_\_\_\_

Item

**6 A29.0 REVISION OF DATE FOR PRACTICAL  
COMPLETION**

Clause 29.0

Clause 29.2.5 is amended by replacing it with:

No clause

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
related: \_\_\_\_\_

Item

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
PRELIMINARIES AND GENERAL  
**PROVISIONAL BILL OF QUANTITIES**

1 **A30.0 PENALTY FOR NON-COMPLETION**  
 Clause 30.0  
 Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
 related: \_\_\_\_\_

Item

**PAYMENT**

2 **A31.0 INTERIM PAYMENT TO THE CONTRACTOR**

Clause 31.0

Clause 31.5.2 is amended by replacing "14.7.1" with "14.0 and 31.8"

Clause 31.8 is amended by replacing it with the following two alternative clauses:

**Alternative A**

31.8(A) Where a **security** is selected in terms of 14.1; the value of the **works** in terms of 31.4.1 and **materials and goods** in terms of 31.4.2 shall be certified in full. The value certified shall be subject to the following percentage adjustments:

31.8(A).1 Ninety-five percent (95%) of such value in interim **payment certificates** issued up to the date of **practical completion**

31.8(A).2 Ninety-seven and half percent (97.5%) of such value in interim **payment certificates** issued on the date of **practical completion** and up to but excluding the date of **final completion**

31.8(A).3 Ninety-nine percent (99%) of such value in interim **payment certificates** issued on the date of **final completion** and up to but excluding the final **payment certificate** in terms of 34.6

31.8(A).4 One hundred percent (100%) of such value in the final **payment certificate** in terms of 34.6 except where the amount certified is in favour of the **employer**. In such an event the payment reduction shall remain at the adjustment level applicable to the final **payment certificate**

**Carried to Collection**

R

Section No. 1  
 Bill No. 1  
 PRELIMINARIES AND GENERAL  
**PROVISIONAL BILL OF QUANTITIES**

Clause 31.12 is amended by deleting the following:

Payment shall be subject to the **employer** giving the **contractor** a tax invoice for the amount due

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**1 A32.0 ADJUSTMENT TO THE CONTRACT VALUE**

Clause 32.0

Clauses 32.5.1, 32.5.4 and 32.5.7 are amended by the addition of the following at the end of the sentence:

"due to no fault of the **contractor**"

Add the following clauses: 33.2.9 to 33.2.13:

33.2.9 the **contractor's** failure or neglect to commence with the works on the dates prescribed in the contract

33.2.10 the **contractor's** failure or neglect to proceed with the works in terms of the contract

33.2.11 the **contractor's** failure or neglect for any reason to complete the works in accordance with the contract

33.2.12 the **contractor's** refusal or neglect to comply strictly with any of the conditions of contract or any contract instructions and/or orders in writing given in terms of the contract

33.2.13 the **contractor's** estate being sequestrated; liquidated or surrendered in terms of the insolvency laws in force within the Republic of South Africa.

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**2 A33.0 RECOVERY OF EXPENSE AND LOSS**

Clause 33.0

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
PRELIMINARIES AND GENERAL  
**PROVISIONAL BILL OF QUANTITIES**

**1 A34.0 FINAL ACCOUNT AND FINAL PAYMENT**

Clause 34.0

Clause 34.1 is amended by removing "#" next to 34.1

Clause 34.2 is amended by inserting "#" next to 34.2

Clause 34.13 is amended by replacing "seven (7) **calendar days**" with "twenty-one (21) **calendar days**" and deleting the words "subject to the **employer** giving the **contractor** a tax invoice for the amount due"

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**2 A35.0 PAYMENT TO OTHER PARTIES**

Clause 35.0

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**CANCELLATION**

**3 A36.0 CANCELLATION BY EMPLOYER - CONTRACTOR'S DEFAULT**

Clause 36.0

Clause 36.1 is amended by the addition of the following clauses:

36.1.3 refuses or neglects to comply strictly with any of the conditions of contract

36.1.4 estate being sequestrated, liquidated or surrendered in terms of the insolvency laws in force within the Republic of South Africa

36.1.5 in the judgement of the **employer**, has engaged in **corrupt** or **fraudulent practices** in competing for or in executing the contract

Clause 36.3 is amended by removing the reference to "No clause" and replacing the words "**principal agent**" with "**employer**"

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
PRELIMINARIES AND GENERAL  
**PROVISIONAL BILL OF QUANTITIES**

Clause 36.0 is amended by the addition of the following clause:

36.3 Remove reference to “No clause”, and replace “principal agent” with “employer”

36.7 Notwithstanding any clause to the contrary, on cancellation of this **agreement** either by the **employer** or the **contractor**; or for any reason whatsoever, the **contractor** shall on written instruction, discontinue with the **works** on a date stated and withdraw himself from the **site**. The **contractor** shall not be entitled to refuse to withdraw from the **works** on the grounds of any lien or right of retention or on the grounds of any other right whatsoever

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**1 A37.0 CANCELLATION BY EMPLOYER - LOSS AND DAMAGE**

Clause 37.0

Clause 37.3.5 is amended by replacing "ninety (90)" with "one hundred and twenty (120)"

Clause 37.0 is amended by the addition of the following clause:

37.3.5 Replace “ninety (90)” with “one hundred and twenty (120) and 38.5.4

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**2 A38.0 CANCELLATION BY CONTRACTOR - EMPLOYER'S DEFAULT**

Clause 38.0

Clause 38.5.4 is amended by replacing "ninety (90)" with "one hundred and twenty (120)"

Clause 38.0 is amended by the addition of the following clause:

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
PRELIMINARIES AND GENERAL  
**PROVISIONAL BILL OF QUANTITIES**

38.7 Notwithstanding any clause to the contrary, on cancellation of this **agreement** either by the **employer** or the **contractor**; or for any reason whatsoever, the **contractor** shall on written instruction, discontinue with the **works** on a date stated and withdraw himself from the **site**. The **contractor** shall not be entitled to refuse to withdraw from the **works** on the grounds of any lien or right of retention or on the grounds of any other right whatsoever

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**1 A39.0 CANCELLATION - CESSATION OF THE WORKS**

Clause 39.0

Clause 39.3.5 is amended by the addition of the following at the end of the sentence:

"within one hundred and twenty (120) **working days** of completion of such a report"

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
PRELIMINARIES AND GENERAL  
**PROVISIONAL BILL OF QUANTITIES**

**DISPUTE**

**1 A40.0 DISPUTE SETTLEMENT**

Clause 40.0

Clause 40.2.2 is amended by replacing "one (1) year" with "three (3) years"

Clause 40.6 is amended by removing the reference to:

No clause

Clause 40.7.1 is amended by replacing "(10)" with "(15)" and by the addition of the following:

Whether or not mediation resolves the dispute, the parties shall bear their own costs concerning the mediation and equally share the costs of the **mediator** and related costs

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**SUBSTITUTE PROVISIONS**

**2 A41.0 STATE CLAUSES**

Clause 41.0

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**CONTRACT VARIABLES**

**3 A42.0 THE SCHEDULE (C1.2)**

Clause 42.0

Tenderers are referred to the C1.2 CONDITIONS OF CONTRACT AND CONTRACT VARIABLES for variables pertaining to this contract

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
PRELIMINARIES AND GENERAL  
**PROVISIONAL BILL OF QUANTITIES**

**SECTION B: JBCC PRELIMINARIES**

**B1.0 DEFINITIONS AND INTERPRETATION**

1 ***B1.1 Definitions and interpretation***

See also clause A1.0 of Section A for additional and/or amended definitions which shall apply equally to this Section

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**B2.0 DOCUMENTS**

2 ***B2.1 Checking of documents***

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

3 ***B2.2 Provisional bills of quantities***

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

4 ***B2.3 Availability of construction documentation***

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

5 ***B2.4 Interests of agents***

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

6 ***B2.5 Priced documents***

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

7 ***B2.6 Tender submission***

Clause 2.6 is amended by replacing "JBCC Form of Tender" with "Form of Offer and Acceptance DPW-07(EC)"

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
PRELIMINARIES AND GENERAL  
**PROVISIONAL BILL OF QUANTITIES**

	<b><u>B3.0 THE SITE</u></b>			
1	<b>B3.1 Defined works area</b>			
	Fixed: _____ Value related: _____ Time related: _____	Item		
2	<b>B3.2 Geotechnical investigation</b>			
	Fixed: _____ Value related: _____ Time related: _____	Item		
3	<b>B3.3 Inspection of the site</b>			
	Fixed: _____ Value related: _____ Time related: _____	Item		
4	<b>B3.4 Existing premises occupied</b>			
	Fixed: _____ Value related: _____ Time related: _____	Item		
5	<b>B3.5 Previous work - dimensional accuracy</b>			
	Fixed: _____ Value related: _____ Time related: _____	Item		
6	<b>B3.6 Previous work - defects</b>			
	Fixed: _____ Value related: _____ Time related: _____	Item		
7	<b>B3.7 Services - known</b>			
	Fixed: _____ Value related: _____ Time related: _____	Item		
8	<b>B3.8 Services - unknown</b>			
	Fixed: _____ Value related: _____ Time related: _____	Item		
9	<b>B3.9 Protection of trees</b>			
	Fixed: _____ Value related: _____ Time related: _____	Item		
	<b>Carried to Collection</b>			
	Section No. 1			
	Bill No. 1			
	PRELIMINARIES AND GENERAL			
	<b>PROVISIONAL BILL OF QUANTITIES</b>			
			R	

1	<b>B3.10 Articles of value</b> Fixed: _____ Value related: _____ Time related: _____	Item	
2	<b>B3.11 Inspection of adjoining properties</b> Fixed: _____ Value related: _____ Time related: _____	Item	
<b><u>B4.0 MANAGEMENT OF CONTRACT</u></b>			
3	<b>B4.1 Management of the works</b> Fixed: _____ Value related: _____ Time related: R _____	Item	
4	<b>B4.2 Programme for the works</b> Fixed: _____ Value related: _____ Time related: _____	Item	
5	<b>B4.3 Progress meetings</b> Fixed: _____ Value related: _____ Time related: _____	Item	
6	<b>B4.4 Technical meetings</b> Fixed: _____ Value related: _____ Time related: _____	Item	
7	<b>B4.5 Labour and plant records</b> Fixed: _____ Value related: _____ Time related: _____	Item	
<b><u>B5.0 SAMPLES, SHOP DRAWINGS AND MANUFACTURERS' INSTRUCTIONS</u></b>			
8	<b>B5.1 Samples of materials</b> Fixed: _____ Value related: _____ Time related: _____	Item	

**Carried to Collection**

R

Section No. 1  
 Bill No. 1  
**PRELIMINARIES AND GENERAL  
 PROVISIONAL BILL OF QUANTITIES**

1	<b>B5.2 Workmanship samples</b> Fixed: _____ Value related: _____ Time related: _____	Item	
2	<b>B5.3 Shop drawings</b> Fixed: _____ Value related: _____ Time related: _____	Item	
3	<b>B5.4 Compliance with manufacturers' instructions</b> Fixed: _____ Value related: _____ Time related: _____	Item	
<b><u>B6.0 TEMPORARY WORKS AND PLANT</u></b>			
4	<b>B6.1 Deposits and fees</b> Fixed: _____ Value related: _____ Time related: _____	Item	
5	<b>B6.2 Enclosure of the works</b> Fixed: _____ Value related: _____ Time related: _____	Item	
6	<b>B6.3 Advertising</b> Fixed: _____ Value related: _____ Time related: _____	Item	
7	<b>B6.4 Plant, equipment, sheds and offices</b> Fixed: _____ Value related: _____ Time related: _____	Item	
8	<b>B6.5 Main notice board</b> Fixed: _____ Value related: _____ Time related: _____	Item	
9	<b>B6.6 Subcontractors' notice board</b> Fixed: _____ Value related: _____ Time related: _____	Item	
<b>Carried to Collection</b>			R
Section No. 1 Bill No. 1 <b>PRELIMINARIES AND GENERAL PROVISIONAL BILL OF QUANTITIES</b>			

**B7.0 TEMPORARY SERVICES**

1 **B7.1 Location**

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

2 **B7.2 Water**

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

3 **B7.3 Electricity**

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

4 **B7.4 Telecommunication facilities**

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

5 **B7.5 Ablution facilities**

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**B8.0 PRIME COST AMOUNTS**

6 **B8.1 Responsibility for prime cost amounts**

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**B9.0 ATTENDANCE ON N/S SUBCONTRACTORS**

7 **B9.1 General attendance**

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

8 **B9.2 Special attendance**

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
PRELIMINARIES AND GENERAL  
**PROVISIONAL BILL OF QUANTITIES**

1 **B9.3 Commissioning - fuel, water and electricity**  
Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
related: \_\_\_\_\_

Item

**B10.0 FINANCIAL ASPECTS**

2 **B10.1 Statutory taxes, duties and levies**  
Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
related: \_\_\_\_\_

Item

3 **B10.2 Payment for preliminaries**  
Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
related: \_\_\_\_\_

Item

4 **B10.3 Adjustment of preliminaries**  
  
Clauses B10.3.1 and B10.3.2 are amended by replacing  
"within fifteen (15) **working days** of taking possession  
of the **site**" with "when submitting his priced **bills of  
quantities / lump sum document**"  
  
Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
related: \_\_\_\_\_

Item

5 **B10.4 Payment certificate cash flow**  
Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
related: \_\_\_\_\_

Item

**B11.0 GENERAL**

6 **B11.1 Protection of the works**  
Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
related: \_\_\_\_\_

Item

7 **B11.2 Protection / isolation of existing / sectionally  
occupied works**  
Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
related: \_\_\_\_\_

Item

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
PRELIMINARIES AND GENERAL  
**PROVISIONAL BILL OF QUANTITIES**

1	<b>B11.3 Security of the works</b> Fixed: _____ Value related: _____ Time related: _____	Item	
2	<b>B11.4 Notice before covering work</b> Fixed: _____ Value related: _____ Time related: _____	Item	
3	<b>B11.5 Disturbance</b> Fixed: _____ Value related: _____ Time related: _____	Item	
4	<b>B11.6 Environmental disturbance</b> Fixed: _____ Value related: _____ Time related: _____	Item	
5	<b>B11.7 Works cleaning and clearing</b> Fixed: _____ Value related: _____ Time related: _____	Item	
6	<b>B11.8 Vermin</b> Fixed: _____ Value related: _____ Time related: _____	Item	
7	<b>B11.9 Overhand work</b> Fixed: _____ Value related: _____ Time related: _____	Item	
8	<b>B11.10 Instruction manuals and guarantees</b> Fixed: _____ Value related: _____ Time related: _____	Item	
9	<b>B11.11 As built information</b> Fixed: _____ Value related: _____ Time related: _____	Item	

**Carried to Collection**

R

Section No. 1  
 Bill No. 1  
**PRELIMINARIES AND GENERAL  
 PROVISIONAL BILL OF QUANTITIES**

1 **B11.12 Tenant installations**  
Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
related: \_\_\_\_\_

Item

**B12.0 SCHEDULE OF VARIABLES**

2 **B12.1 Schedule of variables**  
Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
related: \_\_\_\_\_

Item

This **schedule** contains all variables referred to in this document and is divided into pre-tender and post-tender categories. The pre-tender category must be completed in full and included in the tender documents. Both the pre-tender and post-tender categories form part of these **Preliminaries**

Spaces requiring information must be filled in, shown as "not applicable" or deleted and not left blank. Where choices are offered, the non-applicable items are to be deleted. Where insufficient space is provided the information should be annexed hereto and cross-referenced to the applicable clause of the **schedule**. Key cross reference clauses are italicised in [ ] brackets

**12.1 PRE-TENDER INFORMATION**

12.1.1 **Provisional bills of quantities**  
[2.2] The quantities are provisional

**YES**

12.1.2 **Availability of construction documentation**  
[2.3] *Construction documentation is complete*

**YES**

12.1.3 **Interests of agents**  
[2.4] Details:

12.1.4 **Defined works area**  
[3.1] Details:

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
PRELIMINARIES AND GENERAL  
**PROVISIONAL BILL OF QUANTITIES**

12.1.5 **Geotechnical investigation**

[3.2] Details:

12.1.6 **Existing premises occupied**

[3.4] Specific requirements:

12.1.7 **Previous work - dimensional accuracy**

[3.5] Details:

12.1.8 **Previous work - defects**

[3.6] Details:

12.1.9 **Services - known**

[3.7] Details:

12.1.10 **Protection of trees**

[3.9] Specific requirements:

12.1.11 **Inspection of adjoining properties**

[3.11] Specific requirements:

12.1.12 **Enclosure of the works**

[6.2] Specific requirements:

12.1.13 **Offices**

[6.4.3] Specific requirements:

The **contractor** shall provide, maintain and remove on completion of the works an office for the exclusive use of the **principal agent**, minimum size 4 x 3 x 3m high internally, suitably insulated and ventilated, provided with electric lighting and fitted with boarded floor, desk, chair, drawing stool, drawing board and lock-up drawers for drawings. The office shall be kept clean and fit for use at all times

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
PRELIMINARIES AND GENERAL  
**PROVISIONAL BILL OF QUANTITIES**

12.1.14 **Main notice board**

[6.5] Specific requirements:  
The **contractor** shall provide, erect where directed, maintain and remove on completion of the **works** a notice board size 3 x 3m as type Drawing GEN 063, constructed of suitable boarding with flat smooth surface and with edging bead 19mm thick round outer edges and projecting 12mm from face of boarding and rounded on front edge. The board shall be securely fixed to hoarding, where hoarding is provided, or fixed to and including a suitable supporting structure of timber or tubular posts and braces. The board is to be painted ivory white and the bead and 12mm wide dividing lines dark green. All wording shall be inscribed in dark green as per the coat of arms for SA. All wording shall be inscribed in dark green painted sans serif lettering

12.1.15 **Subcontractors' notice board**

[6.6] *A notice board is required*

**NO**

Specific requirements:

12.1.16 **Water**

[7.2] Option A (by **contractor**)

**NO**

Option B (by **employer** - free of charge)

**NO**

Option C (by **employer** - metered)

**YES**

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
PRELIMINARIES AND GENERAL  
**PROVISIONAL BILL OF QUANTITIES**

**12.1.17 Electricity**

[7.3] Option A (by **contractor**)

**NO**

Option B (by **employer** - free of charge)

**NO**

Option C (by **employer** - metered)

**YES**

**12.1.18 Telecommunications**

[7.4] Telephone

**YES**

Facsimile

**YES**

E-mail

**YES**

**12.1.19 Ablution facilities**

[7.5] Option A (by **contractor**)

**YES**

Option B (by **employer**)

**NO**

**12.1.20 Protection of existing/sectionally occupied works**

[11.2] Protection is required

**NO**

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
**PRELIMINARIES AND GENERAL  
PROVISIONAL BILL OF QUANTITIES**

12.1.21 **Special attendance**  
[9.2] **Subcontractor (1) details:**

**Subcontractor (2) details:**

**Subcontractor (3) details:**

**Subcontractor (4) details:**

12.1.22 **Protection of the works**  
[11.1] Specific requirements:

12.1.23 **Disturbance**  
[11.5] Specific requirements:  
The **contractor** shall keep the site, structures, etc well watered during operations to prevent dust and shall provide and erect and remove on completion of the **works** all necessary temporary dust screens all to the satisfaction of the **principal agent**

12.1.24 **Environmental disturbance**  
[11.6] Specific requirements:

**12.2 POST-TENDER INFORMATION**

12.2.1 **Payment of preliminaries**  
[10.2] Option A (prorated)

**NO**

Option B (calculated)

**YES**

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
**PRELIMINARIES AND GENERAL  
PROVISIONAL BILL OF QUANTITIES**

12.2.2 **Adjustment of preliminaries**  
[10.3] Option A (three categories)

**NO**

Option B (detailed breakdown)

**YES**

12.2.3 **Additional agreed preliminaries items**  
Details:

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
PRELIMINARIES AND GENERAL  
**PROVISIONAL BILL OF QUANTITIES**

**SECTION C: SPECIFIC PRELIMINARIES**

**Section C** contains specific preliminary items which apply to this contract except where N/A (Not Applicable) appears against an item

**1 C1.0 CONTRACT DRAWINGS**

The drawings issued with the tender documents do not comprise the complete set but serve as a guide only for tendering purposes and for indicating the scope of the work to enable the tenderer to acquaint himself with the nature and extent of the **works** and the manner in which they are to be executed

Should any part of the drawings not be clearly understood by the tenderer he shall, before submitting his tender, obtain clarification in writing from the **principal agent**

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_  
Time related: \_\_\_\_\_

Item

**2 C2.0 GENERAL PREAMBLES**

The document "Specification of Materials and Methods to be used - PW371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014)." is obtainable on the Department's website (<http://www.publicworks.gov.za/> under "Consultants Guidelines"), and shall be read in conjunction with the **bills of quantities / lump sum document** and be referred to for the full descriptions of work to be done and materials to be used

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_  
Time related: \_\_\_\_\_

Item

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
PRELIMINARIES AND GENERAL  
**PROVISIONAL BILL OF QUANTITIES**

1 **C3.0 TRADE NAMES**

Wherever a trade name for any product has been described in the **bills of quantities / lump sum document**, the tenderer's attention is drawn to the fact that any other product of equal quality may be used subject to the written approval of the **principal agent** being obtained prior to the closing date for submission of tenders

If prior written approval for an alternative product is not obtained, the product described shall be deemed to have been tendered for

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_  
Time related: \_\_\_\_\_

Item

2 **C4.0 HIV/AIDS AWARENESS**

It is required of the **contractor** to thoroughly study the HIV/AIDS Specification (PW 1544) of the Department that must be read together with and is deemed to be incorporated under this Section of the **bills of quantities / lump sum document**. Provision for pricing of HIV/AIDS awareness is made under items C10.1 to C10.5 hereafter and it is explicitly pointed out that all requirements of the aforementioned specification are deemed to be priced hereunder, as the said items represent the only method of measurement and no additional items or extras to the contract in this regard shall be entertained

The **contractor** must take note that compliance with the HIV/AIDS Specification is compulsory. In the event of partial or total non-compliance, the **principal agent**, notwithstanding the provisions of clause A 31.0 of Section A or any other clause to the contrary, reserves the right to delay issuing any progress **payment certificate** until the **contractor** provides satisfactory proof of compliance. The **contractor** shall not be entitled to any compensation of whatsoever nature, including interest, due to such delay of payment

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
PRELIMINARIES AND GENERAL  
**PROVISIONAL BILL OF QUANTITIES**

**C4.1 AWARENESS CHAMPION**

Selection, appointment, briefing and making available of an Awareness Champion including provision of all relevant services, all in accordance with the HIV/AIDS Specification

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_  
Time related: \_\_\_\_\_

Item

**C4.2 AWARENESS WORKSHOPS**

Selection and appointment of a competent Service Provider approved by the **principal agent**, provision of a Service Provider Workshop Plan and a suitable venue, conducting of awareness workshops by means of traditional and/or modern multi-media techniques, including follow-up courses, making available all tuition material and performing assessment procedures, all in accordance with the HIV/AIDS Specification

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_  
Time related: \_\_\_\_\_

Item

**C4.3 POSTERS, BOOKLETS, VIDEOS, ETC.**

Provision, displaying, maintaining and replacing when necessary of four plastic laminated posters, booklets and educational videos, etc. for the duration of the **construction period**, all in accordance with the HIV/AIDS Specification

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_  
Time related: \_\_\_\_\_

Item

**C4.4 ACCESS TO CONDOMS**

Provision and maintenance of condom dispensers fixed in position, including male and female condoms, replenishing male and female condoms on a daily basis as required for the duration of the **construction period**, all in accordance with the HIV/AIDS Specification

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_  
Time related: \_\_\_\_\_

Item

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
**PRELIMINARIES AND GENERAL  
PROVISIONAL BILL OF QUANTITIES**

**C4.5 MONITORING**

Monitoring HIV/AIDS awareness of workers, providing the **principal agent** with access to information including making available all reports, thoroughly completed and reflecting the correct information, for the duration of the **construction period** and close out, all in accordance with the HIV/AIDS Specification

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_  
 Time related: \_\_\_\_\_

Item

**Carried to Collection**

R

Section No. 1  
 Bill No. 1  
 PRELIMINARIES AND GENERAL  
**PROVISIONAL BILL OF QUANTITIES**

**FUNDANI HIGH SCHOOL  
THE MVULA TRUST FLUSH MAINTENANCE PROGRAMME**

Section No. 1

Bill No. 1

PRELIMINARIES AND GENERAL

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

**Amount**

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13
- 14
- 15
- 16
- 17
- 18
- 19
- 20

**Carried Forward**

R

Section No. 1

Bill No. 1

PRELIMINARIES AND GENERAL

**PROVISIONAL BILL OF QUANTITIES**

Section No. 1

Bill No. 1

PRELIMINARIES AND GENERAL

**COLLECTION**

**Brought Forward**

Total Brought Forward from Page No.

**Page  
No**

**Amount**

R

- 21
- 22
- 23
- 24
- 25
- 26
- 27
- 28
- 29
- 30
- 31
- 32
- 33
- 34
- 35
- 36
- 37

**Carried Forward to Summary of Section No. 1**

R

Section No. 1

Bill No. 1

PRELIMINARIES AND GENERAL

**PROVISIONAL BILL OF QUANTITIES**

Item No		Quantity	Rate	Amount
	<p><b><u>BILL No. 2</u></b></p> <p><b><u>HEALTH AND SAFETY REQUIREMENTS</u></b></p> <p><u>Note:</u></p> <p>For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014).</p> <p>The contractor's prices for all items throughout these bills of quantities shall take account of and include where applicable for all of the obligations, requirements and specifications given in the General Preambles and in any supplementary preambles and/or specifications.</p> <p>Prior to pricing the principal contractor must familiarize him/herself with the Occupational Health and Safety Act No. 85 Of 1993, Construction Regulations 2014, other relevant Regulations and Standards as well as project specific Health &amp; Safety specifications.</p> <p>The items in this Bill do not contain quantities hence the Contractor must insert his own quantities based on his individual requirements to comply with the Health and Safety obligations and demands of the Occupational Health and Safety Act No. 85 of 1993, Construction Regulations 2014, other relevant Regulations and Standards as well as project specific Health &amp; Safety Specifications.</p> <p><b><u>OCCUPATIONAL HEALTH AND SAFETY</u></b></p> <p><b><u>General:</u></b></p>			
1	Preparation of Contractor's site specific Health and Safety Plan.	Item		
2	Submission of the Health and Safety File.	Item		
3	Principal Contractor's initial obligations in respect of the OHS Act and Construction Regulations.	Item		
	<b>Carried to Collection</b>		R	
	<p>Section No. 1</p> <p>Bill No. 2</p> <p>HEALTH AND SAFETY</p> <p><b>PROVISIONAL BILL OF QUANTITIES</b></p>			

**FUNDANI HIGH SCHOOL  
THE MVULA TRUST FLUSH MAINTENANCE PROGRAMME**

1	Principal Contractor's time related obligations in respect of the OHS Act and Construction Regulations for the entire construction period.		Item		
2	Provision of full time Health and Safety Officer for the entire construction period.		Item		
3	Induction training of personnel.	No	12		
4	Provision of first aid boxes.	No	1		
	<b><u>Provision for Personal Protective Equipment and Protective Clothing:</u></b>				
5	Reflective vests.	No	12		
6	Hard hats.	No	12		
7	Protective foot wear.	No	12		
8	Ear Plugs.	No	12		
9	Dust Masks.	No	12		
	<b><u>Costs of Medical Certificates and Medical Surveillance:</u></b>				
10	Initial (baseline) medical examinations.	No	12		
11	Exit Examinations.	No	12		
	<b>Carried to Collection</b>				R
	Section No. 1				
	Bill No. 2				
	HEALTH AND SAFETY				
	<b>PROVISIONAL BILL OF QUANTITIES</b>				

Section No. 1

Bill No. 2

HEALTH AND SAFETY

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

40

41

**Amount**

**Carried Forward to Summary of Section No. 1**

R

Section No. 1

Bill No. 2

HEALTH AND SAFETY

**PROVISIONAL BILL OF QUANTITIES**

**SECTION SUMMARY - SECTION NO.1 - PRELIMINARIES**

Bill No		Page No	Amount
1	PRELIMINARIES AND GENERAL	39	
2	HEALTH AND SAFETY	42	
<b>Carried to Final Summary</b>			R
Section No. 1 <b>PROVISIONAL BILL OF QUANTITIES</b>			

Item No		Quantity	Rate	Amount
	<b><u>SECTION NO.1 - NEW ABLUTION BLOCK</u></b>			
	<b><u>BILL No. 1</u></b>			
	<b><u>EARTHWORKS (PROVISIONAL)</u></b>			
	<u>Note:</u>			
	For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014).			
	<b><u>EXCAVATIONS, FILLING, ETC.</u></b>			
	<b><u>Carting away of excavated material</u></b>			
1	Load surplus or unsuitable material from spoil heaps and cart away to a dumping site to be located by the Contractor.	m3	253	
	<b>Carried Forward to Summary of Section No. 2</b>			R
	Section No. 2 Bill No. 1 EARTHWORKS <b>PROVISIONAL BILL OF QUANTITIES</b>			

Item No		Quantity	Rate	Amount
	<p><b><u>BILL No. 2</u></b></p> <p><b><u>CONCRETE, FORMWORK &amp; REINFORCEMENT (PROVISIONAL)</u></b></p> <p><u>Note:</u></p> <p>For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014).</p> <p><b><u>Movement joints</u></b></p> <p><u>To horizontal surfaces</u></p>			
1	6mm Wide x 40mm deep saw cut joint in top of concrete.	m	71	
	<b>Carried Forward to Summary of Section No. 2</b>			R
	<p>Section No. 2</p> <p>Bill No. 2</p> <p>CONCRETE, FORMWORK AND REINFORCEMENT</p> <p><b>PROVISIONAL BILL OF QUANTITIES</b></p>			

Item No		Quantity	Rate	Amount
	<b><u>BILL No. 3</u></b>			
	<b><u>MASONRY</u></b>			
	<u>Note:</u>			
	For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014).			
	<b><u>MASONRY</u></b>			
	<b><u>SUPERSTRUCTURE BRICKWORK</u></b>			
	<u>Walls and linings in loadbearing brickwork (14MPa) in stock bricks in 5:1 cement mortar :</u>			
1	Half brick wall.	m2	16	
2	One brick wall.	m2	346	
	<u>Beamfilling</u>			
3	Half brick wall in beamfilling.	m2	27	
	<u>Bagging</u>			
4	Bag down outer face of inner skin of brick wall in 4:1 cement slurry.	m2	303	
	<u>Reinforcement to brickwork</u>			
5	Galvanised brick reinforcement 115mm wide built horizontally into brickwork.	m	207	
6	Galvanised brick reinforcement 230mm wide built horizontally into brickwork.	m	617	
	<b><u>Turning pieces</u></b>			
7	Turning piece to soffit of one rick wall at lintols, etc.	m	20	
	<b><u>EXTERNAL FACE BRICKWORK</u></b>			
	<b>Carried to Collection</b>			R
	Section No. 2			
	Bill No. 3			
	MASONRY			
	<b>PROVISIONAL BILL OF QUANTITIES</b>			

	<u>"Rustgold FBS / Qunu Travertine " or other equal approved FBX quality face bricks including jointing and square recess pointing 6 x 10mm joints</u>				
1	Extra over ordinary brickwork for facing and pointing in stretcher bond.	m2	30		
	<u>Face brick copings, lintols, cills, etc.</u>				
2	Extra over brickwork for 220mm brick-on-edge cill including pointing to face and top.	m	29		
3	Extra over brickwork for brick-on-edge header course coping including pointing to both faces and top.	m	33		
	<b><u>Walls faced both sides</u></b>				
	<u>"Rustgold FBS / Qunu Travertine " or other equal approved FBX quality face bricks including jointing and square recess pointing 6 x 10mm joints</u>				
4	Extra over ordinary half brick wall for facing and pointing on both sides in stretcher bond.	m2	26		
5	Extra over ordinary one brick wall for facing and pointing on both sides in stretcher bond.	m2	66		
	<u>Fair cutting to face brickwork</u>				
6	Fair cutting to raking facebrick.	m	36		
	<b><u>MISCELLANEOUS</u></b>				
	<u>Air bricks etc:</u>				
7	230 x 160 x 35mm Terracotta vermin proof air brick.	No	16		
	<b><u>Hoop iron ties, cramps, etc.</u></b>				
8	1.6 x 30mm Galvanized hoop iron roof tie 1500mm long with one end wrapped around and spiked to timber the other end built a minimum of six courses deep into brickwork as the work proceeds.	No	98		
	<b>Carried to Collection</b>				R
	Section No. 2				
	Bill No. 3				
	MASONRY				
	<b>PROVISIONAL BILL OF QUANTITIES</b>				

Section No. 2

Bill No. 3

MASONRY

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

46

47

**Amount**

**Carried Forward to Summary of Section No. 2**

R

Section No. 2

Bill No. 3

MASONRY

**PROVISIONAL BILL OF QUANTITIES**

Item No		Quantity	Rate	Amount
	<b><u>BILL No. 4</u></b>			
	<b><u>WATERPROOFING</u></b>			
	<u>Note:</u>			
	For Preambles see "PW 371 - A Edition 2.0 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (2nd Edition July 2013).			
	<b><u>WATERSTOPS, SEALING STRIPS, JOINT SEALANTS, ETC.</u></b>			
	<b><u>Joint sealants</u></b>			
	<u>To horizontal surfaces</u>			
1	Remove hinged blocking piece and fill 10 x 10mm top surface cavity with "Sikaflex Pro2HP" or other equal approved two part polyurethane sealer.	m	206	
	<u>Sundry</u>			
2	Seal and point around window and door frames with an approved external quality sealing compound applied with a pressure caulking gun.	m	239	
	<u>Prepare surface and apply two coats "Caprox" or equally approved masonry waterproofing on:</u>			
3	External plastered walls	m2	150	
	<b>Carried Forward to Summary of Section No. 2</b>			R
	Section No. 2			
	Bill No. 4			
	WATERPROOFING			
	<b>PROVISIONAL BILL OF QUANTITIES</b>			

Item No		Quantity	Rate	Amount
	<b><u>BILL No. 5</u></b>			
	<b><u>ROOF COVERINGS</u></b>			
	<u>Note:</u>			
	For Preambles see "PW 371 - A Edition 2.0 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (2nd Edition July 2013).			
	<b><u>PROFILED SHEETING OF METAL, FIBRE CEMENT, PLASTIC, ETC.</u></b>			
	<b><u>Metal roof sheeting</u></b>			
	<u>0,58mm Thick Z200 "IBR Profile" galvanised metal roof sheeting, in single sheet lengths, with "Chromadek" finish to external face and standard backing coat to internal face :</u>			
1	Roof sheeting laid to a pitch not exceeding 25° and secured to timber purlins at approximately 1 200mm centres including turning up sheet at ridge and turning down sheet at eaves.	m2	98	
	<b><u>Accessories</u></b>			
	<u>Accessories, etc. to match roof sheeting</u>			
2	Ridge capping 550mm girth.	m	40	
	<b><u>Insulation</u></b>			
3	"Sisalation 420" insulation laid taut over rafters at approximately 2400mm centres and fixed including galvanised steel straining wires where required.	m2	180	
	<b>Carried Forward to Summary of Section No. 2</b>			R
	Section No. 2			
	Bill No. 5			
	ROOF COVERING			
	<b>PROVISIONAL BILL OF QUANTITIES</b>			

Item No		Quantity	Rate	Amount
	<b><u>BILL No. 6</u></b>			
	<b><u>CARPENTRY AND JOINERY</u></b>			
	<u>Note:</u>  For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014).			
	<b><u>CARPENTRY</u></b>			
	<b><u>PLATE NAILED TIMBER ROOF CONSTRUCTION</u></b>			
	<u>Fixing:</u>  All nailing of timber roof trusses, purlins, etc shall be done with galvanised nails. In coastal areas, copper, aluminium or stainless steel nails shall be used.  Items described as "nailed" shall be deemed to be fixed with hardened steel nails or shot pins to brickwork or concrete.			
	<u>Erection certificates</u>			
1	Contractor is to supply a roof truss erection certificate for each of the buildings stating that the erection and installation of the roof trusses has been inspected and approved by a professional registered structural engineer.	No	4	
	<u>Sawn softwood :</u>			
2	38 x 114mm Wall plate.	m	17	
3	50 x 76mm Purlins.	m	75	
4	50 x 76mm Bracing.	m	12	
5	38 x 152mm Rafters.	m	44	
	<b>Carried to Collection</b>			R
	Section No. 2 Bill No. 6 CARPENTRY AND JOINERY <b>PROVISIONAL BILL OF QUANTITIES</b>			

<u>Sundries:</u>					
1	Hurricane clip fixed to purlin and rafter.	No	85		
<b><u>JOINERY</u></b>					
<b><u>Doors, windows, sashes, etc.</u></b>					
<u>Wrot hardwood :</u>					
2	44mm Thick framed, ledged, braced and battened door size 813 x 1832mm high, comprising 44 x 144mm stiles and top rail, 22 x 150mm middle rail, 22 x 230mm bottom rail and 2 No. 22 x 75mm diagonal braces and filled flush on one side between framing with 22mm thick tongued, grooved and V-jointed both sides vertical boarding in narrow matched widths and fitted with and including 44 x 70mm splayed and rebated weatherboard, countersunk brass screwed on at maximum 200mm centres.	No	20		
3	44mm Thick framed, ledged, braced and battened door size 813 x 2032mm high, comprising 44 x 144mm stiles and top rail, 22 x 150mm middle rail, 22 x 230mm bottom rail and 2 No. 22 x 75mm diagonal braces and filled flush on one side between framing with 22mm thick tongued, grooved and V-jointed both sides vertical boarding in narrow matched widths and fitted with and including 44 x 70mm splayed and rebated weatherboard, countersunk brass screwed on at maximum 200mm centres.	No	5		
4	44mm Thick framed, ledged, braced and battened door size 950 x 2032mm high, comprising 44 x 144mm stiles and top rail, 22 x 150mm middle rail, 22 x 230mm bottom rail and 2 No. 22 x 75mm diagonal braces and filled flush on one side between framing with 22mm thick tongued, grooved and V-jointed both sides vertical boarding in narrow matched widths and fitted with and including 44 x 70mm splayed and rebated weatherboard, countersunk brass screwed on at maximum 200mm centres.	No	2		
<b><u>Frames, rails, skirtings, etc.</u></b>					
<b>Carried to Collection</b>					R
Section No. 2					
Bill No. 6					
CARPENTRY AND JOINERY					
<b>PROVISIONAL BILL OF QUANTITIES</b>					

Meranti timber door frames

Note :

All units are to constructed using 70 x 108mm hardwood timber with 19 x 19mm quadrant bead to external face

1	Framed frame, to suit single door size 813 x 1832mm high overall.	No	20	
2	Framed frame, to suit single door size 813 x 2032mm high overall.	No	5	
3	Framed frame, to suit single door size 950 x 2032mm high overall.	No	2	

Sundries

4	19mm Hardwood quadrant moulding planted on.	m	45	
5	10 x 140mm Door frame anchor countersunk and pelleted in timber frame, at approximately 600mm centres, including forming mortice in brickwork or concrete.	No	201	

**Plastic, fibre cement, etc.**

Pressed fibre-cement:

6	12 x 225mm Fascia board drilled and brass screwed to rafter feet including galvanised steel H-profile jointing strips, etc.	m	80	
7	85 x 275mm Barge board drilled and brass screwed to timber rafter including galvanised steel H-profile jointing strips, etc.	m	36	

**Carried to Collection**

R

Section No. 2  
Bill No. 6  
CARPENTRY AND JOINERY  
**PROVISIONAL BILL OF QUANTITIES**

Section No. 2

Bill No. 6

CARPENTRY AND JOINERY

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

**Amount**

51

52

53

**Carried Forward to Summary of Section No. 2**

R

Section No. 2

Bill No. 6

CARPENTRY AND JOINERY

**PROVISIONAL BILL OF QUANTITIES**

**FUNDANI HIGH SCHOOL  
THE MVULA TRUST FLUSH MAINTENANCE PROGRAMME**

Item No		Quantity	Rate	Amount
	<b><u>BILL No. 7</u></b>			
	<b><u>IRONMONGERY</u></b>			
	<u>Note:</u>			
	For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014).			
	<b><u>IRONMONGERY TO TIMBER DOORS, FRAMES, ETC.</u></b>			
	<u>Hinges, bolts, etc.</u>			
1	100 x 75mm Heavy duty brass butt hinges.	No	54	
	<b><u>Push plates, kicking plates, indicator plates, etc.</u></b>			
	<u>3mm Thick x 32mm high blue perspex signs with white painted numerals or letters, countersunk tap screwed to steel door frame</u>			
2	Sign with "MALE ABLUTIONS" enscribed.	No	2	
3	Sign with "FEMALE ABLUTIONS" enscribed.	No	3	
4	Sign with "DISABLE" enscribed.	No	2	
	<u>Locksets, etc. to be masterkeyed</u>			
5	"Union 2277-78SS" or equally approved three lever upright mortice lockset with stainless steel forend and striking plate finish.	No	7	
6	"Union CZ80941SC" or equally approved satin chrome W/C indicator bolt.	No	20	
	<u>Handles, furniture, etc.</u>			
7	"Dormakaba DPH301 B" or other equal approved 325 x 25mm Stainless steel straight tubular pull handle with flange fixing. (Sets)	No	27	
	<b>Carried to Collection</b>			R
	Section No. 2			
	Bill No. 7			
	IRONMONGERY			
	<b>PROVISIONAL BILL OF QUANTITIES</b>			

**FUNDANI HIGH SCHOOL  
THE MVULA TRUST FLUSH MAINTENANCE PROGRAMME**

	<u>Stops, holders, hooks, etc.</u>			
1	"Dormakaba DHC-SS-030A" or other equal approved stainless steel single hat and coat hook plugged to door.	No	20	
	<b><u>IRONMONGERY FIXED TO CONCRETE, TILING, ETC.</u></b>			
	<u>Stops, holders, hooks, etc.</u>			
2	38mm Black rubber door stop plugged to wall or floor.	No	27	
	<b>Carried to Collection</b>			R
	Section No. 2			
	Bill No. 7			
	IRONMONGERY			
	<b>PROVISIONAL BILL OF QUANTITIES</b>			

Section No. 2

Bill No. 7

IRONMONGERY

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

55

56

**Amount**

**Carried Forward to Summary of Section No. 2**

R

Section No. 2

Bill No. 7

IRONMONGERY

**PROVISIONAL BILL OF QUANTITIES**

Item No		Quantity	Rate	Amount
	<b><u>BILL No. 8</u></b>			
	<b><u>METALWORK</u></b>			
	<u>Note:</u>			
	For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014).			
	<b><u>STEEL</u></b>			
	<b><u>Stairs, balustrading, cat ladders, grilles, gates, framework, etc.</u></b>			
	<u>GATES</u>			
	<u>Hot dipped galvanised mild steel</u>			
1	Single gate, size 900mm wide x 2050mm high, the leaf formed of 25 x 25 x 2mm wall thickness mild steel square tubing framing all round with mitred and welded angles, the gate filled in with 12 x 12mm mild steel bars welded, at each end, perimeter framing at not exceeding 100mm centres, the leaf fitted with lock housing (lock elsewhere measured) formed of 2.5mm thick mild steel flat plate, the leaf fitted with a set of hinges fixed to brickwall with and including masonry anchors.(G1)	No	4	
2	Double gate, size 1800mm wide x 2050mm high, in two equal leaves, ditto. (G2)	No	2	
	<b><u>OTHER METALS</u></b>			
	<b><u>Aluminium windows, doors, etc.</u></b>			
	All aluminium work is to be manufactured in accordance with AAMSA specifications by a registered Member of the Association			
	All units are to be pre-glazed in accordance with the requirements of the National Building Regulations, unless otherwise specifically noted			
	<b>Carried to Collection</b>			R
	Section No. 2			
	Bill No. 8			
	METALWORK			
	<b>PROVISIONAL BILL OF QUANTITIES</b>			

All units are to be supplied with a protective plastic covering, which is to be removed only once all adjacent plastering and painting is complete

All laminated safety glass panes are to bear the safety glass indicator mark, failing which they will be rejected and the Contractor will have to replace same at his own cost.

NATURAL ANODISED ALUMINIUM

Natural anodised pre-glazed aluminium windows complete with ironmongery and including setting up, building in, filling back of frame with cement mortar, sealing around same with silicone sealant, etc.

1 Top hung opening out window, size overall 600 x 600mm high, glazed with and including 6.38mm clear laminated safety glass.(W1)

No

48

**Carried to Collection**

R

Section No. 2  
Bill No. 8  
METALWORK  
**PROVISIONAL BILL OF QUANTITIES**

Section No. 2

Bill No. 8

METALWORK

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

58

59

**Amount**

**Carried Forward to Summary of Section No. 2**

R

Section No. 2

Bill No. 8

METALWORK

**PROVISIONAL BILL OF QUANTITIES**



Item No		Quantity	Rate	Amount
	<b><u>BILL No. 10</u></b>			
	<b><u>PLUMBING AND DRAINAGE (PROVISIONAL)</u></b>			
	<u>Note:</u>			
	For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014).			
	<b><u>GUTTERS, ETC</u></b>			
	<b><u>Roof gutters, rainwater pipes, etc.</u></b>			
	<u>Powder coated seamless aluminium rainwater gutters, downpipes and accessories</u>			
1	85 x 125mm Gutter fixed to fascia at maximum 600mm centres with and including proprietary fixings.	m	40	
2	Extra over gutter for forming discharge outlet to suit 75 x 100mm downpipe.	No	8	
3	Extra over gutter for stopped end.	No	8	
4	75 x 100mm Rainwater downpipe fixed to wall with and including proprietary holderbats.	m	32	
5	Extra over rainwater downpipe for bend.	No	14	
	<b><u>PIPEWORK, ETC.</u></b>			
	<b><u>Pipes, pipe fittings, etc.</u></b>			
	<b><u>WATER SUPPLIES</u></b>			
	<u>Class 10 polycop pipes with straight compression fittings</u>			
6	15mm Pipe and fixing to walls, floors, in roofs, in concrete, etc. including any necessary proprietary holderbats, fixings, etc.	m	40	
7	22mm Ditto.	m	20	
	<b>Carried to Collection</b>			R
	Section No. 2 Bill No. 10 PLUMBING AND DRAINAGE <b>PROVISIONAL BILL OF QUANTITIES</b>			

**FUNDANI HIGH SCHOOL**  
**THE MVULA TRUST FLUSH MAINTENANCE PROGRAMME**

1	15mm Pipe chased into brickwork.	m	123		
2	22mm Ditto.	m	56		
	<u>Extra over copper pipes for brass compression fittings</u>				
3	15mm Fittings.	No	78		
4	22mm Fittings.	No	78		
	<b><u>Connections</u></b>				
	<u>Connection of new to existing pipes</u>				
5	Connection of 32mm diameter HDPE to 22mm diameter polyprop pipes including all necessary reducers, saddles, etc.	No	4		
	<u>Testing :</u>				
6	Allow for testing the preceding water supply installation in accordance with the National Building Regulations.			Item	
	<b><u>SOIL DRAINAGE</u></b>				
	<u>uPVC Pipes with solvent welded straight joints :</u>				
7	50mm Pipes.	m	148		
8	110mm Pipes.	m	19		
	<u>uPVC Pipes with solvent welded straight joints with bedding and filling in accordance with SABS 1200 :</u>				
9	110mm Pipe and excavation not exceeding 1000mm deep.	m	19		
10	110mm Pipe and excavation exceeding 1000mm not exceeding 2000mm deep.	m	53		
	<u>White uPVC vent pipe in single lengths :</u>				
11	110mm Diameter vent pipe fixed to wall with proprietary brackets at not exceeding 500mm centres.	m	92		
	<b>Carried to Collection</b>				
	Section No. 2				
	Bill No. 10				
	PLUMBING AND DRAINAGE				
	<b>PROVISIONAL BILL OF QUANTITIES</b>				

R

<u>Extra over uPVC pipes for solvent welded fittings :</u>					
1	50mm Plain bend.	No	35		
2	110mm Plain bend.	No	15		
3	50mm Access bend.	No	17		
4	Black PVC whirlybird vent capping over the 110mm vent pipe.	No	22		
<b><u>Gulleys, grease traps, etc.</u></b>					
5	100mm Diameter uPVC gulley trap with universal gulley head set flush in with finished pavement level including encasing in 15MPa concrete 100mm thick all round.	No	4		
6	430 x 430 x 175mm Precast concrete gulley top, bedded over gulley in cement mortar.	No	4		
<b><u>Inspection chambers, catch pits, etc.</u></b>					
<u>Light Composite covers and frames</u>					
7	600mm diameter type M4A lockable medium duty manhole cover and frame fixed into concrete,	No	8		
<u>Testing :</u>					
8	Allow for testing the preceding sanitary plumbing installation in accordance with the National Building Regulations.			Item	
<b><u>SANITARY FITTINGS, TANKS, GEYSERS, ETC.</u></b>					
<b><u>Sanitary fittings, etc.</u></b>					
<u>Plastic sanitaryware</u>					
9	VIP 450 Pit pedestal complete with integral flap four times plugged to floor with and including 6 x 75mm masonry anchors.	No	2		
10	VIP 200 Pit pedestal complete with integral flap four times plugged to floor with and including 6 x 75mm masonry anchors.	No	20		
<b>Carried to Collection</b>					R
Section No. 2					
Bill No. 10					
PLUMBING AND DRAINAGE					
<b>PROVISIONAL BILL OF QUANTITIES</b>					

<u>White glazed vitreous china ware :</u>				
1	"Vaal 7050" or equally approved washhand basin, size 510 x 405mm, with two tapholes, one taphole stopper, integrated overflow and chainstay hole, mounted to wall on and including two proprietary semi-concealed cast iron wall brackets with 10mm bolts.	No	17	
2	"Vaal 704001" or equally approved wall hung flat back urinal, size overall 610 x 3850mm, complete with chromium plated back inlet spreader and 38mm chromium plated domical grating hung on and including two proprietary hanger brackets .	No	2	
<u>Grade 304 stainless steel ware :</u>				
3	"Franke TU101-1830R" or equally approved 0.9mm stainless steel flat back wall mounted urinal with tiling key to sides and rear walls,vermin proof bitumastic material to back including 40mm waste outlet, concealed sparge pipe, 22 mm inlet with chrome plated conex fitting, ect.	No	2	
<u>Sanitary fitting sundries</u>				
4	"N-SBIN-12-SA" or equally approved 12 Litre pedal sanitary bin, size 463 x 140 x 480mm.	No	10	
5	Satin chrome thief proof toilet roll holder, TR2, plugged to wall.	No	23	
6	Heavy-duty double-flap hinged toilet seat and cover.	No	23	
<u>Grade 304 stainless steel ware :</u>				
7	Grab rail 1200mm long with two flanges "SR 1" plugged to wall with and including stainless steel screws.	No	2	
8	Dog leg grab rail with three flanges "DL3" plugged to wall with and including stainless steel screws.	No	2	
<u>Taps, valves, etc.</u>				
<u>Solid cast brass taps, valves, etc.</u>				
9	15mm Brass ball-o-stop.	No	17	
<b>Carried to Collection</b>				R
Section No. 2 Bill No. 10 PLUMBING AND DRAINAGE <b>PROVISIONAL BILL OF QUANTITIES</b>				

**FUNDANI HIGH SCHOOL  
THE MVULA TRUST FLUSH MAINTENANCE PROGRAMME**

1	15mm Chromium plated brass metered bib tap with non-hold open feature and flow control.	No	21		
2	22mm Brass non-return valve.	No	19		
	<b><u>Waste unions, traps, etc.</u></b>				
	<u>Outlets, traps, etc :</u>				
3	38mm Chromium plated brass slotted sink waste outlet with plug, chain and chain stay.	No	17		
4	38mm Butyl rubber flexible deepseal sink P-trap.	No	17		
5	40mm Chromium plated brass basin bottle trap.	No	2		
	<b>Carried to Collection</b>			R	
	Section No. 2				
	Bill No. 10				
	PLUMBING AND DRAINAGE				
	<b>PROVISIONAL BILL OF QUANTITIES</b>				

Section No. 2

Bill No. 10

PLUMBING AND DRAINAGE

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

**Amount**

62

63

64

65

66

**Carried Forward to Summary of Section No. 2**

R

Section No. 2

Bill No. 10

PLUMBING AND DRAINAGE

**PROVISIONAL BILL OF QUANTITIES**

Item No		Quantity	Rate	Amount
	<b><u>BILL No. 11</u></b>			
	<b><u>PAINTWORK</u></b>			
	<u>Note:</u>			
	For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014).			
	<b><u>PAINT ON TIMBER</u></b>			
	<u>Prime or oil on :</u>			
1	Backs of frames or linings not exceeding 300mm girth.  <u>Prepare and apply one coat pink wood primer, one undercoat and two coats water based eggshell enamel on :</u>	m	135	
2	Surfaces of flush panel doors.	m2	90	
3	Surfaces of frames and linings.  <u>Prepare and apply two coats carbolineum on:</u>	m2	28	
4	Surfaces of exposed timber.	m2	45	
	<b><u>PAINT ON FIBRE-CEMENT</u></b>			
	<u>Prepare and apply one coat plaster primer and two coats quality matt acrylic PVA on :</u>			
5	External fibre cement fascia and barge boarding including priming cover strips.	m2	21	
	<b><u>PAINT ON PVC</u></b>			
	<u>Prepare and apply two coats black PVA paint on:</u>			
6	Vent pipes.	m2	88	
	<b>Carried Forward to Summary of Section No. 2</b>			R
	Section No. 2 Bill No. 11 PAINTWORK <b>PROVISIONAL BILL OF QUANTITIES</b>			

Item No		Quantity	Rate	Amount
	<b><u>BILL No. 12</u></b>			
	<b><u>EXTERNAL WORKS</u></b>			
	<u>Note:</u>			
	For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014).			
	<b><u>THE FOLLOWING IN WALKWAYS</u></b>			
	<b><u>EARTHWORKS</u></b>			
	<u>Excavate in earth not exceeding 2m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away</u>			
1	Reduced levels between buildings, retaining walls, etc.	m3	23	
	<b><u>Carting away of excavated material</u></b>			
2	Extra over all excavations for loading surplus or unsuitable material from spoil heaps and cart away to a dumping site to be located by the Contractor.	m3	23	
	<b><u>BASECOURSES</u></b>			
3	G7 Base course material, selected and supplied by the Contractor, deposited in layers not exceeding 150mm thick, watered and consolidated to 98% modified AASHTO density under pavings.	m3	23	
	<u>Sundries</u>			
4	Rip reduced platform level and recompact to 93% Mod. A.A.S.H.T.O. density.	m2	150	
	<u>Prescribed Testing</u>			
5	Provide and have filling compaction check tested by a Consulting Engineer's Laboratory and deliver the results to the Architect within 24 hours of the tests being completed.	No	4	
	<b>Carried to Collection</b>			R
	Section No. 2			
	Bill No. 12			
	EXTERNAL WORKS			
	<b>PROVISIONAL BILL OF QUANTITIES</b>			

<b><u>Weedkillers, insecticides, etc.</u></b>					
<u>Soil insecticide in accordance with SANS 5859</u>					
1	Under paving, etc.	m2	150		
<b><u>PRECAST CONCRETE PAVERS</u></b>					
<u>Grey interlocking precast concrete pavers type S-A laid in herringbone pattern with header course perimeter margin</u>					
2	50mm Thick laid on and including 25mm sand bed treated with weed killer and cement/sand mixture swept into joints on completion.	m2	150		
<u>Sundries</u>					
3	Circular cutting on 50mm thick non bevelled concrete pavers.	m	12		
<b><u>Channelling, kerbing, edging, etc.</u></b>					
<u>Precast concrete kerbing</u>					
4	Precast semi-mountable concrete Fig 8B edge kerb size 300 x 175mm high cast in lengths not exceeding 1m and with expansion joints at not exceeding 10m centres finished smooth off the mould on all exposed surfaces bedded on and including minimum 50mm thick mass concrete 15 MPa base and backing including all necessary excavation, formwork, expansion joints, etc.	m	112		
5	Ditto, but circular on plan to not exceeding 4m radius.	m	12		
<b><u>THE FOLLOWING IN DISABLE RAMPS (ALL TRADES)</u></b>					
<b><u>EXCAVATIONS FOR FOUNDATIONS, ETC. (Labour intensive)</u></b>					
<u>Excavate in earth not exceeding 2m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away</u>					
6	Surface trenches.	m3	6		
<b>Carried to Collection</b>				R	
Section No. 2					
Bill No. 12					
EXTERNAL WORKS					
<b>PROVISIONAL BILL OF QUANTITIES</b>					

1	Reduced levels between buildings, retaining walls, etc.	m3	0.2	
	<b><u>Carting away of excavated material</u></b>			
2	Load surplus or unsuitable material from spoil heaps and cart away to a dumping site to be located by the Contractor.	m3	3	
	<b><u>Risk of collapse of excavations</u></b>			
3	Allow for risk of collapse to sides of excavations not exceeding 1.5m deep including all necessary timber shoring, etc.	m2	15	
	<b><u>Keeping excavations free of water</u></b>			
4	Allow for keeping the excavations free from water.		Item	
	<b><u>Filling</u></b>			
5	Earth filling from the excavations and/or stockpiles in backfilling to trenches, column bases, etc., compacted to 93% Mod AASHTO dry density.	m3	3	
	<b><u>BASECOURSES</u></b>			
6	G7 Base course material, selected and supplied by the Contractor, deposited in layers not exceeding 150mm thick, watered and consolidated to 98% modified AASHTO density under pavings.	m3	0.3	
7	G5 Base course material, selected and supplied by the Contractor, deposited in layers not exceeding 150mm thick, watered and consolidated to 95% modified AASHTO density under pavings.	m3	0.3	
	<b><u>Sundries</u></b>			
8	Rip reduced platform level and recompact to 93% Mod. A.A.S.H.T.O. density.	m2	2	
	<b><u>Tests</u></b>			
9	Allow for Mod AASHTO density tests on filling.	No	1.00	
	<b><u>CONCRETE (Labour intensive)</u></b>			
	<b>Carried to Collection</b>			R
	Section No. 2			
	Bill No. 12			
	EXTERNAL WORKS			
	<b>PROVISIONAL BILL OF QUANTITIES</b>			

	<u>Reinforced concrete 25MPa (19mm stone) in:</u>			
1	Strip foundations cast against excavated surfaces.	m3	2	
2	Ramps, landings, ect.	m3	0.2	
	<b><u>Surface treatment</u></b>			
3	Float surface of concrete to a wood float finish.	m2	2	
	<b><u>Test blocks and testing</u></b>			
4	Allow for preparing and curing a set of three test cubes, each size 150mm x 150mm x 150mm and pay all transport and testing costs undertaken by an approved independent laboratory. (Provisional)	No	1	
	<b><u>Movement joints</u></b>			
	<u>To horizontal surfaces</u>			
5	10mm Thick closed cell polyethylene joint forming material with hinged blocking piece, not exceeding 300mm wide, between concrete and concrete or brickwork surfaces.	m	5	
6	Remove hinged blocking piece and fill 10 x 10mm top surface cavity with "Sikaflex Pro2HP" or other equal approved two part polyurethane sealer.	m	5	
	<b><u>REINFORCEMENT (PROVISIONAL)</u></b>			
	<b><u>Bar reinforcement</u></b>			
	<u>Mild steel rod reinforcement to structural concrete work</u>			
7	10mm Diameter bars.	t	0.023	
	<u>High tensile rod reinforcement to structural concrete work</u>			
8	10mm Diameter bars.	t	0.068	
9	12mm Diameter bars.	t	0.068	
10	16mm Diameter bars.	t	0.070	
	<b>Carried to Collection</b>			R
	Section No. 2			
	Bill No. 12			
	EXTERNAL WORKS			
	<b>PROVISIONAL BILL OF QUANTITIES</b>			

1	<u>High tensile welded steel mesh reinforcement :</u> Ref: 395 cast into concrete surfaces.	m2	2	
	<b><u>FOUNDATION BRICKWORK (PROVISIONAL)</u></b>			
	<b><u>Walls and linings in stock bricks in 5:1 cement mortar :</u></b>			
2	One brick wall.	m2	5	
	<b><u>Reinforcement to brickwork</u></b>			
3	Galvanised brick reinforcement 230mm wide built horizontally into brickwork.	m	15	
	<b><u>FACE BRICKWORK</u></b>			
	<u>"Rustgold FBS/Qunu Travertine " or other equal approved FBX quality face bricks including jointing and square recess pointing 6 x 10mm joints</u>			
4	Extra over ordinary brickwork for facing and pointing in stretcher bond.	m2	2	
	<b><u>SUPERSTRUCTURE BRICKWORK</u></b>			
	<b><u>Mass brickwork and piers in loadbearing brickwork (14MPa) in stock bricks in 5:1 cement mortar :</u></b>			
5	One brick wall.	m2	3	
	<b><u>Reinforcement to brickwork</u></b>			
6	Galvanised brick reinforcement 230mm wide built horizontally into brickwork.	m	9	
	<b><u>EXTERNAL FACE BRICKWORK</u></b>			
	<u>"Rustgold FBS/Qunu Travertine " or other equal approved FBX quality face bricks including jointing and square recess pointing 6 x 10mm joints</u>			
7	Extra over ordinary brickwork for facing and pointing in stretcher bond.	m2	6	
	<b>Carried to Collection</b>			R
	Section No. 2			
	Bill No. 12			
	EXTERNAL WORKS			
	<b>PROVISIONAL BILL OF QUANTITIES</b>			

<b><u>Face brick copings, lintols, cills, etc.</u></b>				
1	Extra over brickwork for 230mm wide brick-on-edge header course coping including pointing to both faces and top.	m	10	
<b><u>SHEET WATERPROOFING</u></b>				
<u>350 Micron orange polyethylene sheeting :</u>				
2	Laid under solid floor.	m2	2	
<b><u>THE FOLLOWING IN APRONS</u></b>				
<b><u>EXCAVATIONS FOR FOUNDATIONS, ETC. (Labour intensive)</u></b>				
<u>Excavate in earth not exceeding 2m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away</u>				
3	Reduced levels between buildings, retaining walls, etc.	m3	12	
<b><u>Carting away of excavated material</u></b>				
4	Load surplus or unsuitable material from spoil heaps and cart away to a dumping site to be located by the Contractor.	m3	12	
<b><u>BASECOURSES</u></b>				
5	G7 Base course material, selected and supplied by the Contractor, deposited in layers not exceeding 150mm thick, watered and consolidated to 98% modified AASHTO density under pavings.	m3	11	
6	G5 Base course material, selected and supplied by the Contractor, deposited in layers not exceeding 150mm thick, watered and consolidated to 95% modified AASHTO density under pavings.	m3	11	
<u>Sundries</u>				
7	Rip reduced platform level and recompact to 93% Mod. A.A.S.H.T.O. density.	m2	72	
<b>Carried to Collection</b>				R
Section No. 2				
Bill No. 12				
EXTERNAL WORKS				
<b>PROVISIONAL BILL OF QUANTITIES</b>				

<u>Tests</u>					
1	Allow for Mod AASHTO density tests on filling.	No	12.00		
<u>Reinforced concrete 25MPa (19mm stone) in:</u>					
2	Edge thickening.	m3	2		
3	Surface beds cast in panels including temporary formwork.	m3	7		
<u>Testing</u>					
4	Allow for preparing and curing a set of three test cubes, each size 150mm x 150mm x 150mm and pay all transport and testing costs undertaken by an approved independent laboratory. (Provisional)	Sets	6		
<u>Surface treatment</u>					
5	Float surface of concrete to a wood float finish.	m2	72		
<u>Edges, risers, ends and reveals</u>					
6	Edge, riser, etc exceeding 300mm high.	m	70		
<u>Movement joints</u>					
<u>To horizontal surfaces</u>					
7	Form toggle joint in concrete surface not exceeding 300mm thick including applying one coat of whitewash or bitumen to one face.	m	20		
8	10mm Thick closed cell polyethylene joint forming material with hinged blocking piece, not exceeding 300mm wide, between concrete and concrete or brickwork surfaces.	m	72		
9	Remove hinged blocking piece and fill 10 x 10mm top surface cavity with "Sikaflex Pro2HP" or other equal approved two part polyurethane sealer.	m	72		
<u>REINFORCEMENT (PROVISIONAL)</u>					
<b>Carried to Collection</b>				R	
Section No. 2					
Bill No. 12					
EXTERNAL WORKS					
<b>PROVISIONAL BILL OF QUANTITIES</b>					

1	<u>High tensile welded steel mesh reinforcement :</u> Ref: 395 cast into concrete surfaces.	m2	72	
<b><u>SHEET WATERPROOFING</u></b>				
	<u>350 Micron orange polyethylene sheeting :</u>			
2	Laid under solid floor.	m2	79	
<b>Carried to Collection</b>				R

Section No. 2  
 Bill No. 12  
 EXTERNAL WORKS  
**PROVISIONAL BILL OF QUANTITIES**

Section No. 2

Bill No. 12

EXTERNAL WORKS

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

**Amount**

69

70

71

72

73

74

75

76

**Carried Forward to Summary of Section No. 2**

R

Section No. 2

Bill No. 12

EXTERNAL WORKS

**PROVISIONAL BILL OF QUANTITIES**

Item No		Quantity	Rate	Amount
	<b><u>BILL No. 13</u></b>			
	<b><u>EXTERNAL PLUMBING &amp; DRAINAGE</u></b>			
	<u>Note:</u>  For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014).			
	<b><u>THE FOLLOWING IN STORMWATER DRAINAGE</u></b>			
	<u>Surface water channels</u>			
1	Reinforced concrete 25MPa V-shaped open surface water channel size 700mm wide x 80mm thick extreme and finished smooth on all exposed surfaces in untinted granolithic with angles rounded, laid to falls in lengths not exceeding 2000mm on a well rammed earth bottom, jointed in 3.1 cement mortar including shallow excavation, one layer 395 reinforced mesh, requisite formwork, ramming and depositing and levelling spoil on site where directed.	m	171	
	<u>Extra over surface water channels for :</u>			
2	Extra over for angles, intersections, ends, dressing into sides of catchpits, etc	No	24	
3	Extra over for widening concrete to form spreader 2000mm wide extreme for a length of 700mm and bedding hard burnt brick diffusers cast in concrete spaced at 200mm centre spacings to falls including brushing concrete between bricks.	No	6	
	<b><u>THE FOLLOWING IN RAINWATER TANKS AND TANKSTANDS (ALL TRADES)</u></b>			
	<b><u>Rainwater harvesting (Labour intensive)</u></b>			
	<b>Carried to Collection</b>			R
	Section No. 2 Bill No. 13 EXTERNAL PLUMBING AND DRAINAGE <b>PROVISIONAL BILL OF QUANTITIES</b>			

**FUNDANI HIGH SCHOOL  
THE MVULA TRUST FLUSH MAINTENANCE PROGRAMME**

	<u>Excavate in earth not exceeding 2m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away</u>			
1	Reduced levels under solid floors.	m3	2	
2	Surface trenches.	m3	13	
	<u>Excavations in earth of more difficult character</u>			
3	Extra over excavations in earth for excavation in soft rock.	m3	2	
4	Extra over excavations in earth for excavation in hard rock.	m3	1	
	<u>Carting away of excavated material</u>			
5	Load surplus or unsuitable material from spoil heaps and cart away to a dumping site to be located by the Contractor.	m3	14	
	<u>Risk of collapse of excavations</u>			
6	Allow for risk of collapse to sides of excavations not exceeding 1.5m deep including all necessary timber shoring, etc.	m2	64	
	<u>Keeping excavations free of water</u>			
7	Allow for keeping the excavations free from water.		Item	
	<u>Filling, layerworks, etc.</u>			
8	Earth filling from the excavations and/or stockpiles in backfilling to trenches, column bases, etc., compacted to 95% Mod AASHTO dry density.	m3	11	
9	Imported G7 filling, selected and supplied by the Contractor, including depositing in layers not exceeding 150mm thick and compacting to 95% modified AASHTO dry density to trenches, bases, etc.	m3	10	
	<u>Compaction of surfaces</u>			
10	Scarify in-situ material to a depth of 150mm and compact to 95% Mod AASHTO density.	m2	17	
	<b>Carried to Collection</b>			R
	Section No. 2			
	Bill No. 13			
	EXTERNAL PLUMBING AND DRAINAGE			
	<b>PROVISIONAL BILL OF QUANTITIES</b>			

**FUNDANI HIGH SCHOOL  
THE MVULA TRUST FLUSH MAINTENANCE PROGRAMME**

	<u>Tests</u>				
1	Allow for Mod AASHTO density tests on filling.	No	6.00		
	<u>Reinforced concrete 25MPa in:</u>				
2	Strip foundations cast against excavated surfaces.	m3	7		
3	Surface beds cast in panels including temporary formwork.	m3	3		
	<u>Sundries</u>				
4	Float surface of concrete to a wood float finish.	m2	22		
	<u>Rough formwork (use and waste) to concrete to:</u>				
5	Edge, riser, etc not exceeding 300mm high.	m	46		
	<u>High tensile welded steel mesh reinforcement :</u>				
6	Ref: 395 cast into concrete surfaces.	m2	21		
7	Ref: 395 cast into concrete strip footings.	m2	30		
	<u>Brickwork in stock bricks in 5:1 cement mortar :</u>				
8	One brick wall.	m2	12		
9	One brick wall in foundations. (Provisional)	m2	5		
	<u>Brickwork sundries :</u>				
10	Galvanised brick reinforcement 150mm wide built horizontally into brickwork.	m	30		
	<u>"Rustgold FBS / Qunu Travertine " or other equal approved FBX quality face bricks including jointing and square recess pointing 6 x 10mm joints</u>				
11	Extra over ordinary brickwork for facing and pointing in stretcher bond.	m2	5		
12	Extra over ordinary brickwork for facing and pointing in stretcher bond in foundations. (Provisional)	m2	2		
	<b>Carried to Collection</b>				R
	Section No. 2				
	Bill No. 13				
	EXTERNAL PLUMBING AND DRAINAGE				
	<b>PROVISIONAL BILL OF QUANTITIES</b>				

**FUNDANI HIGH SCHOOL  
THE MVULA TRUST FLUSH MAINTENANCE PROGRAMME**

	<u>Face brick copings, lintols, cills, etc.</u>				
1	Extra over brickwork for brick-on-edge header course coping including pointing to both faces and top.	m	12		
	<u>Movement joints</u>				
2	10mm Thick bitumen impregnated softboard built vertically between concrete and concrete or brickwork surfaces.	m2	15		
3	Rake out 10mm wide softboard for a depth of 10mm and seal with an approved 2 part polysulphide sealant.	m	27		
	<u>Ties, cramps, etc.</u>				
4	38 x 1,6mm Galvanised hoop iron strap around tank, both ends fitted with once holed 30 x 30 x 3mm thick galvanised flat plate and bolted together with and including M8 bolt and nut.	No	6		
5	38 x 1,6mm Galvanised hoop iron tie down, 1200mm long, one end wrapped around tank strap and twice bolted, the other end folded over and bolted to top of concrete with and including 8 x 60mm masonry anchor.	No	24		
	<u>250 Micron "Gunplas USB" green polyethylene sheeting</u>				
	∴				
6	Laid flat under solid floor and over walls.	m2	22		
	<u>Rainwater tanks:</u>				
7	5000 Litre polyethylene rotomoulded vertical water storage tank provided complete with lid and overflow outlet , fitted with suitable adaptor and setting in position on concrete tankstand (elsewhere measured). (The tanks are to be filled with water for the Practical Completion inspection)	No	6		
8	Hole through top of tank lid for 100mm diameter pipe.	No	6		
	<b>Carried to Collection</b>				
	Section No. 2				
	Bill No. 13				
	EXTERNAL PLUMBING AND DRAINAGE				
	<b>PROVISIONAL BILL OF QUANTITIES</b>				
					R

Section No. 2

Bill No. 13

EXTERNAL PLUMBING AND DRAINAGE

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

78

79

80

81

**Amount**

**Carried Forward to Summary of Section No. 2**

R

Section No. 2

Bill No. 13

EXTERNAL PLUMBING AND DRAINAGE

**PROVISIONAL BILL OF QUANTITIES**

Bill No	<b>SECTION SUMMARY - SECTION NO.2- NEW ABLUTION BLOCKS</b>	Page No	Amount
1	EARTHWORKS	44	
2	CONCRETE, FORMWORK AND REINFORCEMENT	45	
3	MASONRY	48	
4	WATERPROOFING	49	
5	ROOF COVERING	50	
6	CARPENTRY AND JOINERY	54	
7	IRONMONGERY	57	
8	METALWORK	60	
9	PLASTERING	61	
10	PLUMBING AND DRAINAGE	67	
11	PAINTWORK	68	
12	EXTERNAL WORKS	77	
13	EXTERNAL PLUMBING AND DRAINAGE	82	
<b>Carried to Final Summary</b>			R
Section No. 2 <b>PROVISIONAL BILL OF QUANTITIES</b>			

Item No		Quantity	Rate	Amount
	<b><u>SECTION NO.4 - PROVISIONAL SUMS , BUDGETARY ALLOWANCES, ECT.</u></b>			
	<b><u>BILL NO.1</u></b>			
	<u>Note:</u>			
	For Preambles see "PW 371 - A Edition 2.0 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (2nd Edition July 2013).			
	<b><u>PROVISIONAL SUM</u></b>			
	<b><u>ELECTRICAL INSTALLATION</u></b>			
1	Provided the Provisional sum of R 120 000.00 (One Hundred and Twenty Thousand Rand) for the new electrical installations to ablution facilities.	Item		120,000.00
2	Add for profit on the above, if desired.	Item		
3	Allow for attendance on the above, if desired.	Item		
	<b><u>COMMUNITY LIAISON OFFICER (CLO)</u></b>			
4	Provide the sum of R 39 000.00 (Thirty Nine Thousand Hundred Rand) for the employment of a CLO.(R 6 500.00 per month x contract period allowance)	Item		39,000.00
5	Add for profit on the above if required.	Item		
	<b>Carried to Final Summary</b>		R	
	Section No. 3 Bill No. 1 PROVISIONAL SUMS, BUDGETARY ALLOWANCES, EC <b>PROVISIONAL BILL OF QUANTITIES</b>			

<b>Section No</b>	<b><u>FINAL SUMMARY</u></b>	<b>Page No</b>		<b>Amount</b>
1	SECTION NO.1 - PRELIMINARIES	43		
2	SECTION NO.2- NEW ABLUTION BLOCKS	83		
3	SECTION NO.3 - PROVISIONAL SUMS, BUDGETARY ALLOWANCES,ECT	84		
	Sub-Total		R	
	<b><u>CREDIT FOR MATERIALS ON SITE</u></b>			
	Credit for Materials on site as per the attached list	Item		
	Sub-Total		R	
	<b><u>CONTINGENCY PROVISIONS</u></b>			
	Allow the Budgetary Provision of R 100 000.00 (One Hundred Thousand Rand) for construction contingencies of a general nature and for the finalisation of design detailing. This sum, or any portion thereof, shall be expended at the sole discretion of the Principal Agent. Any residual balance remaining subsequent to such expenditure shall be deducted in its entirety from the Contract Sum.	Item		100,000.00
	Sub - Total		R	
	Add Value - Added Tax at the rate applicable as at Tender closing date.		R	
	Sub - Total		R	
	<b>TOTAL</b>		R	
	<b>PROVISIONAL BILL OF QUANTITIES</b>			