

ITEM NO.	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
G	SANS 1200	SCHEDULE G: BOUNDARY WALL				
G.1		DEMOLITION				
G.1.1	LIC	Demolish existing damaged wall panel and foundation and cart away rubble to a suitable site identified by the Client within a radius of 7km from the site	m ²	7		
G.2	SANS 1200 D	EARTHWORKS				
G.2.1	8.3.2 a)	Excavate in all materials and use for fill compacted to 93% MOD AASHTO density				
G.2.1.1	8.3.3 a) (LIC)	Excavations in all materials for stripfootings	m ³	1,2		
G.3	SANS 1200 GB	CONCRETE, REINFORCEMENT AND FORMWORK				
		Supply all material, labour, equipment for the mix and placement of specified concrete. Allowance shall be made for concrete testing in terms of Clause 7,1 (SANS 1200 GB). The cost of making, storing and testing of concrete cubes shall include the provision of cube moulds. Tests shall be conducted by an independent and accredited concrete laboratory (Cubes measured elsewhere)				
G.3.1	8.2.4	Reinforcement				
		Supply, cut, bed, placing in position, fixing of reinforcement including spacer devices and binding wire				
G.3.2.1	LIC	Reinforcement to stripfooting	kg	120		
G.3.3	8.2.5	Concrete				
G.3.3.1	LIC	Concrete class 20/19 to stripfootings, main bldng	m ³	1,2		
G.3.4		Test Cubes				
G.3.4.1		Making and testing of 150x150x150mm concrete test cubes. Test reports to be issued to the Engineer	Sum	1		
G.4		MASONRY				
G.4.1		Boundary Walls				
G.4.1.1	LIC	190mm Freestanding brickwall - Hollowblock (2,8mm brickforce in every 3rd course)	m ²	6,5		
TOTAL CARRIED FORWARD SUMMARY						