

SGR -Drainage design and costing



www.prasa.com

Item	Description	Unit	Qty	Rate	Amount
Cleveland station					
1	Clearing of existing debris/waste including carting away and pumping underground water out of the trench	Sum	1		
2	Chop/break the existing reinforced concrete floor slab and cart away spoil	m ³	12		
3	Restricted excavation for the perforated pitch fibre sub-soil pipes (300 x 300) as shown in the drawing including compaction to 90% modified AASHTO	m ³	20		
4	Lay 100mm dia perforated pitch fibre pipe (sub-soil drainage pipe) including 250 micron impervious membrane (bidum) as shown in the drawing along the entire breadth of the station.rate to include compacting to 90% modified AASHTO and backfilling	m	100		
5	19mm crushed stone as shown in the drawing	m ³	20		
6	Cast concrete 25 Mpa (300mm x 200mm x 80m)	m ³	4.8		
7	Construct wing wall, headwall and apron slab for the eye of the sub-soil discharge point rate to include reinforcement, formwork as show in the drawing 25 mpa concrete	m ³	1.5		
8	Cast V-drain channel (500mm wide & 50mm thick)	m ³	3.5		
9	Install roof sheeting on the entrances of the sub-ways to prevent rain water from entering	Sum	1		
Sub-total 1					
George Gorch station					
1	Clearing of existing debris/waste including carting away and pumping underground water out of the trench	Sum	1		
2	Chop/break the existing reinforced concrete floor slab and cart away spoil	m ³	12		
3	Restricted excavation for the perforated pitch fibre sub-soil pipes (300 x 300) as shown in the drawing including compaction to 90% modified AASHTO	m ³	20		
4	Lay 100mm dia perforated pitch fibre pipe (sub-soil drainage pipe) including 250 micron impervious membrane (bidum) as shown in the drawing along the entire breadth of the station.rate to include compacting to 90% modified AASHTO and backfilling	m	100		
5	19mm crushed stone as shown in the drawing	m ³	20		
6	Cast concrete 25 Mpa (300mm x 200mm x 80m)	m ³	4.8		

7	Construct wing wall, headwall and apron slab for the eye of the sub-soil discharge point rate to include reinforcement, formwork as show in the drawing 25 mpa concrete	m ³	1.5		
8	Cast V-drain channel (500mm wide & 50mm thick)	m ³	3.5		
	Sub-total 2				
	Sub-Total 3 (sub-total 1 +2)				
	20% contingences				
	Sub-Total 4 (Sub-total 3 + contingences)				
	15% VAT				
	Grand Total				

Designed by Anele Mgudane **Pr Tech Eng**
Programme Manager



Signed