

- 1.) CHECK ALL DIMENSIONS AND LEVELS BEFORE COMMENCING ANY WORK. PLATFORM LEVELS TO BE VERIFIED BY THE ENGINEER  
ALL FINISHING WALL LEVELS TO BE VERIFIED ON SITE.  
ALL BANKS TO BE LEVELLED OUT.  
DO NOT SCALE FROM THE DRAWINGS.
- 2.) ANY QUERIES TO BE BROUGHT TO THE ARCHITECT'S ATTENTION.  
ALL CONDUITING, TIMBER, PVC ETC. SHOULD BE SABS APPROVED QUALITY MATERIALS.  
ALL STRUCTURAL STEEL, CONCRETE STRENGTH AND TIMBER SPECIFICATION ARE TO BE IN ACCORDANCE WITH ENGINEER'S DETAILS.

MINTEK  
200 MALIBONGWE DRIVE  
STRYDOM PARK,  
RANDBURG  
2194  
TEL: 041 995 2000

**IRMA ARCHITECTS**  
6 SHIRLEY STREET  
NEWTON PARK  
PORT ELIZABETH  
TEL: 041 365 2896



RAJ MAHARAJH  
ASSOCIATES  
ARCHITECTS

AIQS  
67 8th STREET  
RONDEBOSCH  
CAPE TOWN  
7780

**AKHA IZWE**  
QUANTITY SURVEYORS

AFRICOAST CONSULTING  
CNR ROSE & HAVELOCK STREET  
PORT ELIZABETH CENTRAL  
Gqeberha  
6001



DIHLASE CONSULTING ENGINEERS  
KENT HOUSE  
1 NEPTUNE ROAD  
WESTVILLE  
3630  
TEL: 031 266 7861

**DIHLASE**

Prepare cracks to plastered walls as per engineers specifications, apply one coat approved primer, repair defects with approved spot primer and two coats premium washable and stain resistant 100% acrylic emulsion. Colours of undercoat to match finishing coat but with enough difference to be able to distinguish between the two coats. Prepare colour sample of finishing coats before any bulk paint is to be purchased. Colour to

- Existing partition walls to be removed and replaced with new as per Architects plan. Paint as per finishing schedules.
- All internal cills made good, Paint as per finishing schedule.

- All existing flooring is to be removed and replaced with new as per the finishing schedules.
- New to be 500 x 500 x 9mm stain shield fibre (polypropylene) carpet tiles to be installed with an adhesive as per the

- Existing floor finish to be stripped and replaced with full bodied 10mm thick 600x600 porcelain tile, where required, with 3 PEI rating fixed to internal floor screed with rapid setting tile adhesive mixed with bonding liquid in lieu of water on concrete surface bed, and 3 mm joints continuous in both directions, jointed and flush pointed SABS approved tile grout.
- Porcelain floor tile skirting, 100mm high with a 24 hour adhesive solution to be plastered surfaces above

- floor tiles. Tiles to have 3mm joints. sealed joints between skirting tiles and floor tiles with silicone sealant.

- All internal and external doors to be removed and replaced as per door schedule.
- All partition internal and external doors to be removed and replaced as per door schedule.


- New curved glass panels with charcoal aluminium

- frames to be as per the window schedule. All details and installation to be done as per the specialist recommendations. All dimensions to be verified on site before manufacturing of glass panels and aluminium frames.

- All existing sanitary ware is to be removed and replaced with new as indicated in the sanitary Schedule.
- Existing drainage and pipe work systems to be flushed

- as per engineers  
recommendations

- All structural elements to be verified by engineer.
- If there are cracks to the existing floor prior to covering, engineers to confirm.
- If there are cracks on the walls, this is to be remedied to engineer's recommendation and specification.
- All services as per the relevant engineers drawings.
- All Fittings removed are to be assessed by Client for donation purposes.

**MINTEK 9000**

REF NO

DRAWING TITLE : LEVEL 13 FLOOR PLAN

RAWN BY	TRW		
CHECKED BY	SM		
LATEST ISSUE	07 JULY 2023		
SCALE	1:100		
PROJ. NO :	DWG NO.		REV NO.
MTK	MTK.DD.003		02