



Agricultural Research Council –Vegetable and Vegetable and Ornamental Plants (VIMP)
R573 KwaMhlanga/Moloto Road, Roodeplaat, Pretoria

Specification Supply, Deliver and Install – B2 Ceiling

Item	Description	Quantity	Instructions
Roof Waterproofing	Waterproofing Acrylic Promac Liquid rubber (20L)	15	<ul style="list-style-type: none"> Supply only Green as per the existing roof
Ceiling Gypsum	Ceiling Gypsum 6.4mm 1.2x3	Floor area (msq) = 71	<ul style="list-style-type: none"> White
Timber bandering	Supply & installation of all timber bandering Required for installation of the new ceiling	Floor area (msq) = 71	
Cornice Gypsum	Cornice Gypsum 75mm Cove LCC	Floor area (msq) = 71	<ul style="list-style-type: none"> White
Housekeeping	Clearing of the rubble to outside the building, cleaning of the walls and all of the surfaces within the working area.		

- Workmanship certification required after completion of project
- 12 months warranty of the workmanship
- Appointed service provider will be required to produce at least 3 CVs with certified tradecertification of key workers conducting the work
- The appointed will be required to remove the existing lights from the ceiling, and reinstall the same lights on to the new ceiling.

Supplier is liable for any damages incurred during the process.

Please be advised that appointed supplier should be capable of completing the project as per the work plan below because of the extremely sensitive nature of the work in the laboratory.

- Day 1 – Removing of the existing ceiling and clearing out of the rubble.
- Day 2 – Installation of the new ceiling
- Day 3 – Painting, final touch ups and cleaning before handover.