

**MLM/MayoralW/22-23 - APPOINTMENT OF A SERVICE PROVIDER FOR CONSTRUCTION OF MAYORAL SECURITY WALL**

[illegible]

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<b>SECTION NO. 2</b>				
	<b>BILL NO. 1</b>				
	<b>FOUNDATIONS (PROVISIONAL)</b>				
	<b>EXCAVATION, FILLING, ETC.</b>				
	<u>Excavate in pickable material not exceeding 2m deep below natural or reduced ground level</u>				
A	Surface trenches	m3	109.20		
B	Holes	m3	21.97		
	<u>Extra over trench and hole excavations in earth for excavation in</u>				
C	Soft rock	m3	10.92		
D	Hard rock	m3	5.46		
	<u>Risk of collapse of excavations</u>				
E	Allow for risk of collapse to sides of excavations to column bases, trenches, etc. from ground level to not exceeding 1.5m deep	m2	447.20		
	<u>Extra over all excavations for loading, carting away and dumping surplus excavated materials (No allowance for increase in bulk)</u>				
F	Off site to a dumping site located by contractor	m3	154		
	<u>Compaction of surfaces</u>				
G	Scarify and compact ground surfaces on bottom of holes and strip footings etc. for a depth of 150mm, breaking down oversized material, adding suitable material where necessary and compact to 95% Modified AASHTO density	m2	131.17		
	<u>SOIL POISONING</u>				
	<u>Soil insecticide including certificate of registration of the pest control operator as issued by the Department of Agriculture</u>				
H	In trenches, including forming and poisoning shallow furrows against foundation walls, etc., filling in walls and ramming	m2	578.37		
	<u>CONCRETE</u>				
	<u>Mass concrete (15Mpa/19mm) in:</u>				
I	Blinding under footings to walls	m3	6.56		
	<u>Reinforced concrete (25Mpa/19mm) in:</u>				
J	Strip footing	m3	21.84		
K	Bases	m3	4.39		
	<u>MASONRY</u>				
	<u>BRICKWORK</u>				
	<u>Sizes in descriptions</u>				
	Where sizes in descriptions are given in brick units, "one brick" shall represent the length and "half brick" the width of a brick				
	<u>Stock Bricks in Class I mortar</u>				
L	Mass Brickwork	m3	8.80256		
M	One brick wall	m2	124.8		
	<u>Reinforcement</u>				
N	Cotts No. C2 or other approved high tensile steel brick reinforcement 150mm wide well lapped at all angles and passings and built into brick walls	m	1472		
	<b>Total Carried to Collection</b>				

[illegible]

[illegible]

[illegible]

[illegible]

[illegible]

ITEM NO	DESCRIPTION				AMOUNT
	SUMMARY - SECTION 2				
1	Foundations				
2	Masonry				
3	Metalwork				
4	Plastering				
5	Painting				
	Total Section 2 Carried to Grand Summary				



	GRAND SUMMARY				
1	PRELIMINARY & GENERAL				
2	BUILDING WORK				
	SUB TOTAL				
	Allow 5% for Contingency				
	VAT @ 15%	VAT	15%		
	TOTAL CARRIED TO TENDER				