



## ROAD MARKINGS - BIFURCATION ARROWS




SCALE 1 : 25



**NOTES:**

1. THESE ARROWS MAY BE USED TO INDICATE THAT THE NUMBER OF LANES ARE INCREASING AHEAD. ONLY ONE SET OF ARROWS SHOULD BE USED UNLESS A LEFT AND RIGHT TURN LANE ARE ADDED TO A MULTI-LANE ROADWAY AT THE SAME POINT WHERE TWO SETS MAY BE USED.
2. DIRECTION ARROWS AHEAD SHALL NOT BE USED TO INDICATE THE ADDITION OF LANES AHEAD.
3. AS A GENERAL RULE BIFURCATION ARROWS SHOULD BE LOCATED TWO TO THREE MARKING MODULES BEFORE THE START OF THE LANE GENERATING TAPES OR CURVE.



## APPLICATIONS

DIMENSIONS (mm)

OPERATING SPEED km/h	TYPICAL APPLICATIONS	a	b	c	d	e	f	g	h	i	j
30 - 40	CITY CENTRE	2500	1500	1000	2170	1141	268	761	1235	81	855
50 - 60	URBAN ROADS	4000	2400	1600	3472	1826	429	1218	1976	129	1367
70 - 90	URBAN ARTERIAL ROADS/ RURAL EXPRESSWAYS	5000	3000	2000	4340	2282	536	1522	2470	161	1709
100 - 120	RURAL ROADS AND FREEWAYS	7500	4500	3000	6510	3423	804	2283	3705	242	2564

ALL OPERATING SPEEDS	K	L	M	N	O	P	Q	R	S	T
AND APPLICATIONS	1700	1250	1100	210	180	921	329	300	188	161

ARROW AREA (m²)			
a	GM3.1/GM3.3	GM3.2	GM3.4
2500	1.30	1.27	1.93
4000	2.07	2.04	3.09
5000	2.59	2.55	3.87
7500	3.89	3.82	5.80

[illegible]

**THE MASTER HELD AT NYELETI PRETORIA OFFICE  
BEARS THE ORIGINAL SIGNATURE OF APPROVAL**