|     | Brought Forward   | 1  |      | F        | 8  |    |
|-----|---|----|------|----------|----|----|
| 174 | 80mm Twin booster complete with non-return valve  | No | 1    |          |    |    |
| 175 | Fire blanket 1800 x 1800mm  | No | 1    |          |    |    |
|     | FIRE APPLIANCES   |    |      |          |    |    |
| 176 | Fire hose reel complete with 30m rubber hose, chromium plated stopcock, shut-off nozzle, wall bracket and cover.  | No | 15   |          |    |    |
| 177 | 5kg Carbon dioxide fire extinguisher including approved bracket and meranti backing board fixed to wall   | No | 1    |          |    |    |
| 178 | 4.5kg DCP portable fire extinguisher including approved bracket and meranti backing board fixed to wall   | No | 30   |          |    |    |
|     | PIPE INSULATION   |    |      |          |    |    |
|     | Geberit Mepla or other equally approved red lagged insulation for hot water piping, neatly cut around pipe as required  |    |      |          |    |    |
| 179 | Insulation to 16mm diameter piping and couplings including working around fittings (LI)   | m  | 16   |          |    |    |
| 180 | Insulation to 20mm diameter piping and couplings including working around fittings (LI)   | m  | 178  |          |    |    |
| 181 | Insulation to 26mm diameter piping and couplings including working around fittings (LI)   | m  | 32   |          |    |    |
| 182 | Insulation to 32mm diameter piping and couplings including working around fittings (LI)   | m  | 76   |          |    |    |
|     | WATER METER   |    |      |          |    |    |
|     | 50mm Sealed counter semi-positive rotary piston type water meter with a body length 165mm as "Kent PSM Size 5", suitable for vertical or horizontal installation and joints to brass connectors (elsewhere measured). | No | 1    |          |    |    |
|     | SUNDRIES  |    |      |          |    |    |
|     | Provide a full set of as-built drawings on completion of the installation   |    | Item |          |    |    |
|     | Allow for pressure testing of the plumbing and drainage system.   |    | ltem |          |    |    |
|     | Carried Forward   |    |      | R        |    |    |
|     | Bill No. 13 Plumbing and Drainage (Provisional)   |    |      |          |    |    |
|     |   |    |      | 1        | ^  | ļ  |
|     | -121-   |    | R.   | /        | m, |    |
|     |   |    | 12   | <u>J</u> |    | 20 |

|     | Brought F   | Forward |  | R  |
|-----|---|---------|--|----|
| 186 | Allow for disinfecting the system in this building in accordance with SANS 10252. |         | Item   |    |
| 187 | Testing and Commissioning of the plumbing and drainage system.                    |         | ltem   |    |
| 188 | 12 month guarantee period   |         | Item   |    |
|     |   |         |  |    |
|     |   |         |  |    |
|     |   |         |  |    |
|     |   |         |  |    |
|     |   |         |  |    |
|     |   |         |  |    |
|     |   |         |  |    |
|     |   |         |  |    |
|     |   |         |  |    |
|     |   |         |  |    |
|     |   |         |  |    |
|     |   |         |  |    |
|     |   |         |  |    |
|     |   |         |  |    |
|     |   |         |  |    |
|     |   |         |  |    |
|     |   |         |  |    |
|     |   |         |  |    |
|     |   |         |  |    |
|     | Carried to Sun  | nmary   |  | R  |
|     | Plumbing and Drainage (Provisional)   |         |  |    |
|     |   |         | No. in the second secon |    |
|     | -12:  | 2-      | R,   | My |

p.

| Item<br>No | y-  | Unit | Quantity | Rate | Amount |
|------------|---|------|----------|------|--------|
|            | BILL NO. 14   |      |          |      |        |
|            | ELECTRICAL WORKS  |      |          |      |        |
|            | (CPAP WORK GROUP NO. 160 UNLESS<br>OTHERWISE STATED)  |      |          |      |        |
|            | PREAMBLES   |      |          |      |        |
|            | The descriptions given in the various items below are not necessarily full and complete and reference must be made to the "General Preambles for Trades 2017" as published by the Association of South African Quantity Surveyors", and Supplementary Preambles for further description and amplification of work in this section |      |          |      |        |
|            | SUPPLEMENTARY PREAMBLES   |      |          |      |        |
|            | Specifications drawings etc   |      |          |      |        |
| 44         | Tenderers are referred to the specification and drawings annexed to these bills of quantities for the electrical work, for the full descriptions of the following items which are to be read and priced in conjunction with the said specification and drawings   |      |          |      |        |
|            | Distribution boards etc   |      |          |      |        |
|            | Rates for distribution boards, etc. are to include for bus bars, jumpers, neutral bars, internal wiring and connections, circuit identification markers, control gear labels, circuit legend cards and working drawings   |      |          |      |        |
|            | Switches socket outlets etc.  | a I  |          |      |        |
|            | Rates for switches, socket outlets, etc. are to include for screwing to outlet boxes, connecting up and cover plates  |      |          |      |        |
|            | <u>Light fittings</u>   |      |          |      |        |
|            | Rates for light fittings are to include for hanging, fixing and connecting and for lamp holders and fluorescent tubes and lamps of the type and wattage described   |      |          |      |        |
|            | Carried Forward Bill No. 14 Electrical Works  |      |          | R    |        |
|            | LIGOUIDAI VVOINO  |      |          |      |        |

R. My LM

|    | Brought Forward   |    |      | F | ₹ |  |
|----|---|----|------|---|---|--|
|    | GENERAL ITEMS   |    |      |   |   |  |
| 1  | Guarantee and maintenance for the complete Electrical Installation including fittings, materials and workmanship for a period of TWELVE MONTHS after date of completion and handover  |    | ltem |   |   |  |
| 2  | Allow for testing and commissioning the whole of the electrical installation as laid down in the specification and for re-testing as may be required after the making good of all defective work to the satisfaction f the Engineer |    | Item |   |   |  |
| 3  | 3 sets of as built drawings showing all conduit routes, draw boxes and positions of outlets etc.  |    | Item |   |   |  |
| 4  | Allowance for final testing and Certificate of Compliance to be issued on completion of the project in addition to the detailed testing specified.  |    | ltem |   |   |  |
| 5  | Allowance for Power application   |    | Item |   |   |  |
|    | SITE RETICULATION   |    |      |   |   |  |
| 6  | Excavate not exceeding 800mm deep in soft material for cabling and cable pipe trench including bedding, backfilling, compaction and disposal of surplus material  | m3 | 155  |   |   |  |
| 7  | Excavate not exceeding 800mm deep in intermediate rock material for cabling and cable pipe trench including bedding, backfilling, compaction and disposal of surplus material   | m3 | 55   |   |   |  |
| 8  | Excavate not exceeding 800mm deep in hard rock material for cabling and cable pipe trench including bedding, backfilling, compaction and disposal of surplus material   | m3 | 22   |   |   |  |
| 9  | Earthing and bonding of cable ladder and galvanised trunking 10mm² Cu PVC jumpers with lugs   |    | Item |   |   |  |
|    | ELECTRICAL / ELECTRONIC MANHOLES  |    |      |   |   |  |
| 10 | Supply and install 600 x 600 x 600mm manhole to specification complete with heavy duty manhole cover  | No | 2    |   |   |  |
| 11 | Supply and install 800 x 800 x 800mm manhole to specification complete with heavy duty manhole cover  | No | 10   |   |   |  |
|    | Carried Forward Bill No. 14 Electrical Works  |    |      | R |   |  |
|    |   |    |      |   |   |  |

23

od Mr

| 28 25mm² 4 core m 240  |    | Brought Forward   |    |  | R |
|--|----|---|----|--|---|
| Supply the following cable sleeves:  | 12 |   | No | 3  |   |
| 13 160mm uPVC sleeves m 335 15 75mm uPVC sleeves m 345 16 50mm uPVC sleeves m 345 16 50mm uPVC sleeves m 160  Extra on last to install the following in trench (trenching measured elsewhere) 17 160mm uPVC sleeves m 335 19 75mm uPVC sleeves m 345 20 50mm uPVC sleeves m 345 20 50mm uPVC sleeves m 160  Supply the following 600/1000 Volt Cu PVC SWA PVC ECC cables: 21 185mm² 4 core m 20 22 150mm² 4 core m 35 24 95mm² 4 core m 260 25 70mm² 4 core m 326 26 50mm² 4 core m 340 27 35mm² 4 core m 340 28 25mm² 4 core m 340 29 16mm² 4 core m 240 29 16mm² 4 core m 105 28 25mm² 4 core m 105 28 25mm² 4 core m 105 29 16mm² 4 core m 105 20 1245  |    | SLEEVES   |    |  |   |
| 14 110mm uPVC sleeves m 335 15 75mm uPVC sleeves m 345 16 50mm uPVC sleeves m 160  Extra on last to install the following in trench itrenching measured elsewhere) 17 160mm uPVC sleeves m 335 19 75mm uPVC sleeves m 345 20 50mm uPVC sleeves m 345 20 50mm uPVC sleeves m 160  Supply the following 600/1000 Volt Cu PVC SWA PVC ECC cables: 21 185mm² 4 core m 20 22 150mm² 4 core m 35 24 95mm² 4 core m 260 25 70mm² 4 core m 260 26 50mm² 4 core m 340 27 35mm² 4 core m 105 28 25mm² 4 core m 105 28 25mm² 4 core m 240 29 16mm² 4 core m 1245  |    | Supply the following cable sleeves:   |    |  |   |
| 15       75mm uPVC sleeves       m       345         16       50mm uPVC sleeves       m       160         Extra on last to install the following In trench (trenching measured elsewhere)         17       160mm uPVC sleeves       m       220         18       110mm uPVC sleeves       m       335         19       75mm uPVC sleeves       m       345         20       50mm uPVC sleeves       m       160         Supply the following 600/1000 Volt Cu PVC SWA PVC ECC cables:       m       20         21       185mm² 4 core       m       20         22       150mm² 4 core       m       35         23       120mm² 4 core       m       260         25       70mm² 4 core       m       340         27       35mm² 4 core       m       105         28       25mm² 4 core       m       240         29       16mm² 4 core       m       1245         Carried Forward       R         Bill No. 14   | 13 | 160mm uPVC sleeves  | m  | 220  |   |
| 16   50mm uPVC sleeves   | 14 | 110mm uPVC sleeves  | m  | 335  |   |
| Extra on last to install the following in trench (trenching measured elsewhere)  17  | 15 | 75mm uPVC sleeves   | m  | 345  |   |
| Itenchina measured elsewhere)         m         220           18         110mm uPVC sleeves         m         335           19         75mm uPVC sleeves         m         345           20         50mm uPVC sleeves         m         160           Supply the following 600/1000 Volt Cu PVC SWA PVC ECC cables:         m         20           21         185mm² 4 core         m         15           23         120mm² 4 core         m         35           24         95mm² 4 core         m         260           25         70mm² 4 core         m         340           26         50mm² 4 core         m         340           27         35mm² 4 core         m         240           28         25mm² 4 core         m         240           29         16mm² 4 core         m         1 245    Carried Forward  R   | 16 | 50mm uPVC sleeves   | m  | 160  |   |
| 18   |    | Extra on last to install the following in trench (trenching measured elsewhere) |    |  |   |
| 19 75mm uPVC sleeves m 345 20 50mm uPVC sleeves m 160  Supply the following 600/1000 Volt Cu PVC SWA PVC ECC cables: 21 185mm² 4 core m 20 22 150mm² 4 core m 35 24 95mm² 4 core m 260 25 70mm² 4 core m 22 26 50mm² 4 core m 340 27 35mm² 4 core m 340 28 25mm² 4 core m 105 28 25mm² 4 core m 240 29 16mm² 4 core m 1245  Carried Forward R  | 17 | 160mm uPVC sleeves  | m  | 220  |   |
| Somm uPVC sleeves  | 18 | 110mm uPVC sleeves  | m  | 335  |   |
| Supply the following 600/1000 Volt Cu PVC SWA PVC ECC cables:   21   | 19 | 75mm uPVC sleeves   | m  | 345  |   |
| PVC ECC cables:  21  | 20 | 50mm uPVC sleeves   | m  | 160  |   |
| 22 150mm² 4 core m 15 23 120mm² 4 core m 35 24 95mm² 4 core m 260 25 70mm² 4 core m 22 26 50mm² 4 core m 340 27 35mm² 4 core m 105 28 25mm² 4 core m 240 29 16mm² 4 core m 1245  Carried Forward R  Bill No. 14  |    |   |    |  |   |
| 23 120mm² 4 core m 35 24 95mm² 4 core m 260 25 70mm² 4 core m 322 26 50mm² 4 core m 340 27 35mm² 4 core m 105 28 25mm² 4 core m 240 29 16mm² 4 core m 1245  Carried Forward R  Bill No. 14   | 21 | 185mm² 4 core   | m  | 20   |   |
| 24 95mm² 4 core m 260 25 70mm² 4 core m 340 26 50mm² 4 core m 340 27 35mm² 4 core m 105 28 25mm² 4 core m 240 29 16mm² 4 core m 1245  Carried Forward R  Bill No. 14   | 22 | 150mm² 4 core   | m  | 15   |   |
| 25 70mm² 4 core m 22 26 50mm² 4 core m 340 27 35mm² 4 core m 105 28 25mm² 4 core m 240 29 16mm² 4 core m 1 245  Carried Forward R  Bill No. 14   | 23 | 120mm² 4 core   | m  | 35   |   |
| 26 50mm² 4 core m 340 27 35mm² 4 core m 105 28 25mm² 4 core m 240 29 16mm² 4 core m 1 245  Carried Forward R  Bill No. 14  | 24 | 95mm² 4 core  | m  | 260  |   |
| 27 35mm² 4 core m 105 28 25mm² 4 core m 240 29 16mm² 4 core m 1 245  Carried Forward R  Bill No. 14  | 25 | 70mm² 4 core  | m  | 22   |   |
| 28 25mm² 4 core m 240 29 16mm² 4 core m 1 245  Carried Forward R  Bill No. 14  | 26 | 50mm² 4 core  | m  | 340  |   |
| 29 16mm² 4 core m 1 245  Carried Forward R  Bill No. 14  | 27 | 35mm² 4 core  | m  | 105  |   |
| Carried Forward R Bill No. 14  | 28 | 25mm² 4 core  | m  | 240  |   |
| Bill No. 14  | 29 | 16mm² 4 core  | m  | 1 245  |   |
| The state of the s |    | Bill No. 14   |    | Classification of the Control of the | R |

-125-

RJ

m

|    | Brought Forward  | 1   |       | F | ₹ |
|----|--|-----|-------|---|---|
| 30 | 10mm² 4 core   | m   | 165   |   |   |
| 31 | 6mm² 4 core  | m   | 620   |   |   |
| 32 | 16mm² 2 core   | m   | 129   |   |   |
| 33 | 10mm² 2 core   | m   | 55    |   |   |
| 34 | 6mm² 2 core  | m   | 45    |   |   |
|    | Extra оп last to install in cable sleeve, ladder, tray, basket |     |       |   |   |
| 35 | 185mm² 4 core  | m   | 20    |   |   |
| 36 | 150mm² 4 core  | m   | 15    |   |   |
| 37 | 120mm² 4 core  | m   | 35    |   |   |
| 38 | 95mm² 4 core   | m   | 260   |   |   |
| 39 | 70mm² 4 core   | m   | 22    |   |   |
| 40 | 50mm² 4 core   | m   | 340   |   |   |
| 41 | 35mm² 4 core   | m   | 105   |   |   |
| 42 | 25mm² 4 core   | m   | 240   |   |   |
| 43 | 16mm² 4 core   | m   | 1 245 |   |   |
| 44 | 10mm² 4 core   | m   | 165   |   |   |
| 45 | 6mm² 4 core  | m   | 620   |   |   |
| 46 | 16mm² 2 core   | m   | 129   |   |   |
| 47 | 10mm² 2 core   | m   | 55    |   |   |
| 18 | 6mm² 2 core  | m   | 45    |   |   |
|    | Termination inclusive of cable glands, lugs etc.               |     |       |   |   |
| 19 | 185mm² 4 core  | No  | 2     |   |   |
| 50 | 150mm² 4 core  | No  | 2     |   |   |
|    | Carried Forward<br>Bill No. 14<br>Electrical Works             |     |       | R |   |
|    |  | i i |       |   |   |

|    | Brought Forward   |     |    | R |
|----|---|-----|----|---|
| 51 | 120mm² 4 core   | No  | 4  |   |
| 52 | 95mm² 4 core  | No  | 8  |   |
| 53 | 70mm² 4 core  | No  | 4  |   |
| 54 | 50mm² 4 core  | No  | 2  |   |
| 55 | 35mm² 4 core  | No  | 12 |   |
| 56 | 25mm² 4 core  | No  | 6  |   |
| 57 | 16mm² 4 core  | No  | 8  |   |
| 58 | 10mm² 4 core  | No  | 4  |   |
| 59 | 6mm² 4 core   | No  | 4  |   |
| 60 | 16mm² 2 core  | No  | 8  |   |
| 61 | 10mm² 2 core  | No  | 6  |   |
| 62 | 6mm² 4 core   | No  | 6  |   |
|    | Supply and install Scotchcast cable joint for the following PVC SWA PVC ECC cables:   |     |    |   |
| 63 | 95mm² 4 core  | No  | 1  |   |
| 64 | 50mm² 4 core  | No  | 1  |   |
| 65 | 35mm² 4 core  | No  | 1  |   |
| 66 | 16mm² 4 core  | No  | 2  |   |
|    | DISTRIBUTION BOARDS   |     |    |   |
|    | Supply and delivery of the following distribution boards  |     |    |   |
| 67 | Main Metering Kiosk As per single line diagram, Tenderer's are referred to Electrical Engineer's drawings annexed to these bills of quantities, Drawing No. 23029_405 | No  | 1  |   |
| 68 | Extra on last to install  | No  | 1  |   |
|    | Carried Forward Bill No. 14 Electrical Works  |     |    | R |
|    | -127-   | - 1 |    | 4 |

R. 27

| Brought Forward   |  |   | F  | 8   |
|---|--|---|--|---|
| Main LV Panel As per single line diagram. Tenderer's are referred to Electrical Engineer's drawings annexed to these bills of quantities. Drawing No. 23029_400                                   | No   | 1   |  |   |
| Extra on last to install  | No   | 1   |  |   |
| Ground Floor Distribution board - DB-A/AE/AUPS As per single line diagram. Tenderer's are referred to Electrical Engineer's drawings annexed to these bills of quantities. Drawing No. 23029_401  | No   | 1   |  |   |
| Extra on last to install  | No   | 1   |  |   |
| Ground Floor Distribution board - DB-B/BE/B-UPS As per single line diagram. Tenderer's are referred to Electrical Engineer's drawings annexed to these bills of quantities. Drawing No. 23029_402 | No   | 1   |  |   |
| Extra on last to install  | No   | 1   |  |   |
| Ground Floor Distribution board - DB-C/CE/C-UPS As per single line diagram. Tenderer's are referred to Electrical Engineer's drawings annexed to these bills of quantities. Drawing No. 23029_403 | No   | 1   |  |   |
| Extra on last to install  | No   | 1   |  |   |
| Ground Floor Distribution board - DB-D/DE/D-UPS s per single line diagram. Tenderer's are referred to Electrical Engineer's drawings annexed to these bills of quantities. Drawing No. 23029_404  | No   | 1   |  |   |
| Extra on last to install  | No   | 1   |  |   |
| Ground Floor Distribution board - DB-G/GE/G-UPS As per single line diagram. Tenderer's are referred to Electrical Engineer's drawings annexed to these bills of quantities. Drawing No. 23029_409 | No   | 1   |  |   |
| Extra on last to install  | No   | 1   |  |   |
| DB-LK - single line diagram - Drawing No. 23029_407   | No   | 1   |  |   |
| Extra on last to install  | No   | 1   |  |   |
| PV Load DB - single line diagram - Drawing No. 23029_412  | No   | 2   |  |   |
| Carried Forward Bill No. 14   |  |   | R  |   |
|   | Main LV Panel As per single line diagram. Tenderer's are referred to Electrical Engineer's drawings annexed to these bills of quantities. Drawing No. 23029_400  Extra on last to install  Ground Floor Distribution board - DB-A/AE/AUPS As per single line diagram. Tenderer's are referred to Electrical Engineer's drawings annexed to these bills of quantities. Drawing No. 23029_401  Extra on last to install  Ground Floor Distribution board - DB-B/BE/B-UPS As per single line diagram. Tenderer's are referred to Electrical Engineer's drawings annexed to these bills of quantities. Drawing No. 23029_402  Extra on last to install  Ground Floor Distribution board - DB-C/CE/C-UPS As per single line diagram. Tenderer's are referred to Electrical Engineer's drawings annexed to these bills of quantities. Drawing No. 23029_403  Extra on last to install  Ground Floor Distribution board - DB-D/DE/D-UPS s per single line diagram. Tenderer's are referred to Electrical Engineer's drawings annexed to these bills of quantities. Drawing No. 23029_404  Extra on last to install  Ground Floor Distribution board - DB-G/GE/G-UPS As per single line diagram. Tenderer's are referred to Electrical Engineer's drawings annexed to these bills of quantities. Drawing No. 23029_404  Extra on last to install  DB-LK - single line diagram - Drawing No. 23029_407  Extra on last to install  PV Load DB - single line diagram - Drawing No. 23029_412  Carried Forward | Main LV Panel As per single line diagram. Tenderer's are referred to Electrical Engineer's drawings annexed to these bills of quantities. Drawing No. 23029_400  Extra on last to install  Ground Floor Distribution board - DB-A/AE/AUPS As per single line diagram. Tenderer's are referred to Electrical Engineer's drawings annexed to these bills of quantities. Drawing No. 23029_401  Extra on last to install  Ground Floor Distribution board - DB-B/BE/B-UPS As per single line diagram. Tenderer's are referred to Electrical Engineer's drawings annexed to these bills of quantities. Drawing No. 23029_402  Extra on last to install  Ground Floor Distribution board - DB-C/CE/C-UPS As per single line diagram. Tenderer's are referred to Electrical Engineer's drawings annexed to these bills of quantities. Drawing No. 23029_403  Extra on last to install  Ground Floor Distribution board - DB-D/DE/D-UPS s per single line diagram. Tenderer's are referred to Electrical Engineer's drawings annexed to these bills of quantities. Drawing No. 23029_404  Extra on last to install  Ground Floor Distribution board - DB-G/GE/G-UPS As per single line diagram. Tenderer's are referred to Electrical Engineer's drawings annexed to these bills of quantities. Drawing No. 23029_404  Extra on last to install  No  Ground Floor Distribution board - DB-G/GE/G-UPS As per single line diagram. Tenderer's are referred to Electrical Engineer's drawings annexed to these bills of quantities. Drawing No. 23029_409  Extra on last to install  No  DB-LK - single line diagram - Drawing No. 23029_407  Extra on last to install  No  Carried Forward | Main LV Panel As per single line diagram. Tenderer's are referred to Electrical Engineer's drawings annexed to these bills of quantities. Drawing No. 23029_400  Extra on last to install  Ground Floor Distribution board - DB-A/AE/AUPS As per single line diagram. Tenderer's are referred to Electrical Engineer's drawings annexed to these bills of quantities. Drawing No. 23029_401  Extra on last to install  Ground Floor Distribution board - DB-B/BE/B-UPS As per single line diagram. Tenderer's are referred to Electrical Engineer's drawings annexed to these bills of quantities. Drawing No. 23029_402  Extra on last to install  Ground Floor Distribution board - DB-C/CE/C-UPS As per single line diagram. Tenderer's are referred to Electrical Engineer's drawings annexed to these bills of quantities. Drawing No. 23029_403  Extra on last to install  Ground Floor Distribution board - DB-D/DE/D-UPS s per single line diagram. Tenderer's are referred to Electrical Engineer's drawings annexed to these bills of quantities. Drawing No. 23029_404  Extra on last to install  Ground Floor Distribution board - DB-D/DE/D-UPS As per single line diagram. Tenderer's are referred to Electrical Engineer's drawings annexed to these bills of quantities. Drawing No. 23029_409  Extra on last to install  No  1  Carried Forward  Carried Forward  Carried Forward | Main LV Panel As per single line diagram. Tenderer's are referred to Electrical Engineer's drawings annexed to these bills of quantities. Drawing No. 23029_400  Extra on last to install  Ground Floor Distribution board - DB-A/AE/AUPS As per single line diagram. Tenderer's are referred to Electrical Engineer's drawings annexed to these bills of quantities. Drawing No. 23029_401  Extra on last to install  Ground Floor Distribution board - DB-B/BE/B-UPS As per single line diagram. Tenderer's are referred to Electrical Engineer's drawings annexed to these bills of quantities. Drawing No. 23029_402  Extra on last to install  Ground Floor Distribution board - DB-C/CE/C-UPS As per single line diagram. Tenderer's are referred to Electrical Engineer's drawings annexed to these bills of quantities. Drawing No. 23029_403  Extra on last to install  Ground Floor Distribution board - DB-D/DE/D-UPS s per single line diagram. Tenderer's are referred to Electrical Engineer's drawings annexed to these bills of quantities. Drawing No. 23029_404  Extra on last to install  Ground Floor Distribution board - DB-G/GE/G-UPS As per single line diagram. Tenderer's are referred to Electrical Engineer's drawings annexed to these bills of quantities. Drawing No. 23029_404  Extra on last to install  No  1  Extra on last to install  No  1  B-LK - single line diagram - Drawing No. 23029_407  No  1  Extra on last to install  PV Load DB - single line diagram - Drawing No. 23029_412  Carried Forward  R |

-128-

2.

W 208

|     | Brought Forward  |    |       | R  |   |
|-----|--|----|-------|----|---|
| 84  | Extra on last to install   | No | 2     |    |   |
| 85  | PV GT DB - single line diagram - Drawing No. 23029_413   | No | 2     |    |   |
| 86  | Extra on last to install   | No | 2     |    |   |
| 87  | DB- CO- As per single line diagram - Drawing No. 23029_414   | No | 2     |    |   |
| 88  | Extra on last to install   | No | 2     |    |   |
|     | LIGHTING   |    |       |    |   |
| 89  | 25mm PVC conduit surface mounted   | m  | 433   |    |   |
| 90  | 25mm PVC conduit cast-in to floor slab   | m  | 120   |    |   |
| 91  | 25mm PVC conduit in partion wall   | m  | 202   |    |   |
|     | PVC insulated 1 000 V grade hard drawn copper wire drawn into trunking/conduit and coloured as per phase                       |    |       |    |   |
| 92  | 2.5mm²   | m  | 3 341 |    |   |
| 93  | 2.5mm² PVC insulated surfix cable  | m  | 244   |    |   |
| 94  | Extra on last to terminate inclusive of glands etc.  | No | 36    |    |   |
| 95  | Single lever 1 way 16 amp Crabtree classic or equal and approved light switch in 100 x 50/50 galvanised box inclusive of cover | No | 245   |    |   |
| 96  | 2 lever 1 way 16 amp Crabtree classic or equal approved light switch or other in 100 x 50/50 galvanised box inclusive of cover | No | 8     |    |   |
| 97  | Two lever 2 way 16 amp Crabtree classic or equal and approved light switch in 100 x 50/50 galvanised box inclusive of cover    | No | 6     |    |   |
| 98  | Three lever 1 way 16 amp Crabtree classic or equal and approved light switch in 100 x 50/50 galvanised box inclusive of cover  | No | 6     |    |   |
|     | Carried Forward Bill No. 14 Electrical Works   |    |       | R  |   |
| ifi | -129-  |    |       | Ĭ, | 1 |

-129-

R. nd

|     |  |    |     |   | OUT Mageing | LAL. 7   |
|-----|--|----|-----|---|-------------|----------|
|     | Brought Forward  | a  |     | R | :1          | Ī        |
| 99  | Four lever 1 way 16 amp Crabtree classic or equal and approved light switch in 100 x 50/50 galvanised box inclusive of cover | No | 4   |   |             |          |
| 100 | 6 amp unswitched socket outlet (yellow)  | No | 340 |   |             |          |
| 101 | 65mm PVC round box for 25mm conduit  | No | 45  |   |             |          |
| 102 | 65mm 3 way PVC round draw box  | No | 36  |   |             |          |
| 103 | 20A Photocell inclusive of bulkhead enclosure  | No | 12  |   |             |          |
| 104 | Occupancy sensor - Province Lighting (PS-PIR3) or equal and approved flush mounted, white with 360 degree detection angle    | No | 36  |   |             |          |
| 105 | Supply and install P9000 trunking complete with cover plate to soffit  | m  | 755 |   |             |          |
| 106 | Supply and install P9000 crossover   | No | 10  |   |             |          |
| 107 | Supply and install P9000 elbow   | No | 8   |   |             |          |
| 108 | Supply and install P9000 Tee-piece   | No | 12  |   |             |          |
| 109 | Supply and install P9000 4-way piece   | No | 12  |   |             |          |
| 110 | Supply and install P9000 end caps  | No | 18  |   |             |          |
|     | SMALL POWER  |    |     |   |             |          |
| 111 | 20mm PVC conduit surface mounted   | m  | 456 |   |             |          |
| 112 | 20mm PVC conduit cast-in slab  | m  | 102 |   |             |          |
| 113 | 20mm PVC conduit in partition wall   | m  | 190 |   |             |          |
| 114 | 25mm PVC conduit surface mounted   | m  | 336 |   |             |          |
| 115 | 25mm PVC conduit cast-in to floor slab   | m  | 542 |   |             |          |
| 116 | 25mm PVC conduit in partition wall   | m  | 616 |   |             |          |
| 117 | 32mm PVC conduit surface mounted   | m  | 334 |   |             |          |
| 118 | 32mm PVC conduit cast-in to floor slab   | m  | 655 |   |             |          |
|     | Carried Forward Bill No. 14 Electrical Works   |    |     | R |             |          |
|     | -130-  |    |     | 1 | . ^         | sel II I |

-130-

RT

|     | Brought Forward   |    |       | R   | 1 |
|-----|---|----|-------|-----|---|
| 119 | 32mm PVC conduit in partition wall  | m  | 318   |     |   |
|     | PVC insulated 1 000 V grade hard drawn copper wire drawn into trunking/conduit and coloured as per phase                                      |    |       |     |   |
| 120 | 2.5mm²  | m  | 1 970 |     |   |
| 121 | 4.0mm²  | m  | 3 348 |     |   |
| 122 | 6,0mm²  | m  | 1 976 |     |   |
| 123 | 2,5mm² PVC insulated surfix cable   | m  | 744   |     |   |
| 124 | Extra on last to terminate inclusive of glands, etc.  | No | 22    |     |   |
| 125 | Supply and install single switch socket outlet, with euro combo outlet in 100 x 100/50 PVC conduit box Crabtree classic or equal and approved | No | 46    |     |   |
| 126 | Supply and Install 20A Three pin UPS switch socket outlet installed in power skirting / floor box   | No | 82    |     |   |
| 127 | Supply and Install 20A Three pin dedicated switch socket outlet installed in power skirting / floor box                                       | No | 82    |     |   |
| 128 | Supply and Install 20A Three pin normal switch socket outlet in installed in power skirting / floor box                                       | No | 82    |     |   |
| 129 | Supply and Install 20A Three pin euro switch socket outlet in installed in power skirting / floor box   | No | 82    |     |   |
| 130 | Blank cover plate   | No | 40    |     |   |
| 131 | 65mm PVC round box for 25mm conduit   | No | 159   |     |   |
| 132 | 100x50/50 PVC conduit boxes for AC controller   | No | 155   |     |   |
| 133 | Supply and install P9000 trunking complete with cover plate to soffit   | m  | 366   |     |   |
| 134 | Supply and install P9000 crossover  | No | 10    |     |   |
| 135 | Supply and install P9000 elbow  | No | 10    |     |   |
| 136 | Supply and install P9000 Tee-piece  | No | 8     |     |   |
|     | Carried Forward Bill No. 14 Electrical Works  |    |       | R   |   |
| 1   | -131-   | ı  |       | . ( | M |

|     | Brought Forward  |    |    | R∥  |   |
|-----|--|----|----|-----|---|
| 137 | Supply and install P9000 end caps  | No | 20 |     |   |
| 138 | Supply and install P9000 4-way piece   | No | 4  |     |   |
| 139 | Supply and install 10A single phase isolator for extraction  | No | 8  |     |   |
| 140 | Supply and install 20A single phase isolators for aircon supply  | No | 40 |     |   |
| 141 | Supply and install 20A single phase isolators for hydroboil / kitchen equipment  | No | 10 |     |   |
| 142 | Supply and install 20A single phase isolators for hand drier power supplies  | No | 8  |     |   |
| 143 | Supply and install 30A single phase isolators  | No | 45 |     |   |
| 144 | Supply and install 30A single phase weather proof isolator for aircon supply   | No | 10 |     |   |
| 145 | Supply and install 40A single phase weather proof isolator for aircon supply   | No | 15 |     |   |
| 146 | Supply and install 30A three phase isolators for aircon supply   | No | 33 |     |   |
| 147 | Supply and install 40A three phase isolators for aircon supply   | No | 20 |     |   |
| 148 | Supply and install 40A three phase weather proof isolator for aircon supply  | No | 12 |     |   |
| 149 | Supply and install 16A weather proof switch socket outlet  | No | 22 |     |   |
| 150 | Supply and install Cabstrut or other equally approved Corporate connection system complete with:  2 x Normal S.S.O (SANS 164-1) (white / white toggle)  2 x Normal Euro S.S.O (SANS 164-2) (white / white toggle)  2 x Essential S.S.O (SANS 164-1) (white / red toggle) | No | 12 |     |   |
|     | 4 x RJ45 outlets   | No | 12 |     |   |
| 45. | TELEPHONE AND DATA   |    |    |     |   |
| 151 | Supply and Install Krone RJ 11 telephone outlets installed in power skirting   | No | 20 |     |   |
|     | Carried Forward  |    |    | R   |   |
|     | Bill No. 14 Electrical Works   |    |    | 2   |   |
| I   | -132-  | 1  | 1  | 1/2 | ^ |

|     | Brought Forward   | d  | 1     | F | ર∥ |    |
|-----|---|--|-------|---|----|----|
| 152 | Supply and Install Krone RJ 45 data outlets installed in power skirting inclusive of cradle and cover plate   | No   | 44    |   |    |    |
|     | SENSORS AND RELAYS  |  |       |   |    |    |
|     | Supply and install the following DEMAN master unit relays / Slave units or other equally approved   |  |       |   |    |    |
| 153 | Alux Controller Alux M6 Master unit - AluxM6A10   | No   | 30    |   |    |    |
| 154 | Alux Controller Alux M7 Master unit - AluxM7A10   | No   | 15    |   |    |    |
| 155 | Alux Slave Alux S1 unit AluxS1A11   | No   | 90    |   |    |    |
| 156 | Alux Slave Alux S2 unit - AluxS2A10   | No   | 15    |   |    |    |
|     | GENERATOR INSTALLATION  |  |       |   |    |    |
|     | The complete supply, transport to site, install, test and commission in accordance with the specification of a standby generation system.  NOTE: ONLY GENUINE ENGINE AND ALTERNATORS WITH LOCAL FACTORY BACKUP, SERVICE AND SPARES WILL BE ACCEPTED. NO "GREY" PRODUCTS FROM THE EAST WILL BE CONSIDERED (Refer schedule 17052 602) |  |       |   |    |    |
| 157 | Standby generator. Tenderer's are referred to Electrical Engineer's drawings annexed to these bills of quantities.  Drawing no. 23029_601   | No   | 1     |   |    |    |
| 158 | Connection of all generator control and protection, AMF and communication information wired to terminals within the Main LV Panel for changeover requirements   |  | Item  |   |    |    |
| 159 | The complete supply and installation of Generator Earthing as specified, including testing and commissioning the entire earthing installation as per I.E.C.standards, including re-testing as may be required after making good, and typed test certificates  | ** Company of the Com | Item  |   |    |    |
| 160 | Allowance to fill/re-fill diesel tanks after testing -<br>Lowsulphur diesel to manufacturers specification.   | LTS  | 1 500 |   |    |    |
|     | Supply the following 600/1000 Volt Cu PVC SWA PVC ECC cables:   | ,  |       |   |    |    |
| 161 | 4 mm² 7 core Cable  | m  | 230   |   |    |    |
|     | Carried Forward Bill No. 14 Electrical Works  |  |       | R |    |    |
| J   | -133-   |  |       | Į |    | l, |

-133-

ny

|     | Brought Forward  | d  |     | R |   |
|-----|--|----|-----|---|---|
| 162 | 2,5 mm² 7 core Cable   | m  | 230 |   |   |
|     | Extra on last to install in cable sleeve, ladder, tray, basket   |    |     |   |   |
| 163 | 4 mm² 7 core Cable   | m  | 230 |   |   |
| 164 | 2,5 mm² 7 core Cable   | m  | 230 |   |   |
|     | Termination inclusive of cable glands, lugs etc.   |    |     |   |   |
| 165 | 4 mm² 7 core Cable   | No | 12  |   |   |
| 166 | 2,5 mm² 7 core Cable   | No | 20  |   |   |
|     | SOLAR PHOTOVOLTAIC INSTALLATION  |    |     |   |   |
| 167 | Supply 550 Watt Solar Panel (Art Solar Monocrystalline or other equally approved)  | No | 156 |   |   |
| 168 | Extra on last to install on purpose made brackets  | No | 156 |   |   |
| 169 | Supply and install aluminium purpose made brackets for mounting of solar panels (16 panels per frame)  | No | 12  |   |   |
| 170 | Wattmon Mini3-4G IOT data logger or equal and approved with rs-485 comms, 15 Slaves and 10 servers, input power of 6-60V DC, 100Mbit Ethernet, 4G LTE, sim slot, 16gb micro SD card with inverter monitoring (grid tie and hybrid monitoring) AC/DC power monitoring, weather station monitoring, zero feed in and DG protection | No | 1   |   |   |
| 171 | 6mm² Cu PVC 1800V DC UV stablised cable  | m  | 128 |   |   |
| 172 | 4mm² black/Red Cu PVC 1800V DC UV stablised cable  |    |     |   |   |
| 173 |  | m  | 128 |   |   |
| 113 | DC combiner boxes consisting of 2 No. 40 Amp 2P DC circuit breakers for each string, 4 No. Class Type 2, 1500V DC 8/20µs 50 kA surge protection device   | No | 6   |   |   |
| 174 | Supply and install on load 2 pole 40A DC isolators   | No | 12  |   |   |
| 175 | Supply and install Schneider PM 5320 complete with CT's, PT fuses in existing Main LV Board  | No | 12  |   |   |
| 176 | 10mm air termination rod fixed to metal support structure inclusive of 2No. Saddle clamps  | No | 50  |   |   |
|     | Carried Forward Bill No. 14 Electrical Works   |    |     | R |   |
|     | -134-  |    |     | 6 | ^ |

-134-

01

Par

|     |  |    | t Orth | OIL TO LEIN ( | 3334 ikageng EXL 4 |
|-----|--|----|--------|---------------|--------------------|
|     | Brought Forward  |    |        | R             |                    |
| 177 | Bonding of PV structure frame with 10mm copper insulated earth cables inclusive of lugs. Equipotential Bonding   | No | 120    |               |                    |
| 178 | Provide an budgetary amount of R450,000.00 power application / municipal application   |    | ltem   |               | 450 000,00         |
| 179 | Profit   |    | %      |               |                    |
| 180 | Attendance   |    | %      |               |                    |
| 181 | Provision for final testing and Certificate of Compliance to be issued on completion of the project in addition to the detailed testing specified.   |    | ltem:  |               |                    |
| 182 | Supply and install 60A 10KA single phase circuit breaker in existing main LV panel (CBi, Schneider, ABB or other equally approved)   | No | 2      |               |                    |
| 183 | Supply and install 40A 10KA single phase circuit breaker in existing distirbution board (CBi, Schneider, ABB or other equally approved)  | No | 8      |               |                    |
| 184 | Supply and install Class II Surge protection 20KA 4 pole with intergral health indicators in existing distribution board   | No | 4      |               |                    |
| 185 | Supply and install 60A 3 way break before make rotary switch   | No | 2      |               |                    |
| 186 | Supply and install AVD Lith Ex 9L Lithium fire extinguisher or equal and approved  | No | 12     |               |                    |
|     | Supply the following Canadian Solar, Sunsynk / Deve / Victron equal andapproved hybrid / grid tied inverter complete with battery monitoring system, LCD screen, charge controller enclosure to be IP54 rated, 50Hz 230V Single phase with reverse polarity Protection, Insulation Resistor Detection Residual Current monitoring Unit, Cuput over current protection, Output Shorted protection, Surge protection. Inverter to have <3% THD and <0,5% input current - DC current injection. Complete with 5 year warantee |    | e e    |               |                    |
| 187 | 25 kW hybrid inverter, SMA 3 phase or equal and approved complete with MPPT  | No | 3      |               |                    |
|     | Carried Forward Bill No. 14 Electrical Works   |    |        | R             |                    |
| - 1 | -135-  |    | 1      | 1             | L A 1              |

-135-

00

R.

|     | Brought Forward  |    |     | F | ₹ |  |
|-----|--|----|-----|---|---|--|
|     | RACK MOUNTED BATTERIES   |    |     |   |   |  |
|     | Supply the following Hubble, Solar MD, Freedom One, Weco or equal and approved 51,2V, IP54 enclosure (excluding battery terminals), rack mounted complete with LiFe - Lithium-lon cell technology, SOC status indicator, LED indicators, 80% Depth of discharge capable low self discharge, intergrated battery monitoring system with current limiting function, over charge protection, over discharge and over temperature battery protection and 2m canbus cable. Compete with 10 year warantee. |    |     |   |   |  |
| 188 | 5 kWh Battery  | No | 10  |   |   |  |
| 189 | 50 kWh Battery   | No | 2   |   |   |  |
| 190 | 100 kWh Battery  | No | 1   |   |   |  |
| 191 | 12 module high rack frame for Rack mount batteries and inclusive of space for control box  | No | 2   |   |   |  |
| 192 | High Voltage control box for 120VDC - 750VDC as DEYE-HV-B750/100A-EU or equal and approved   | No | 2   |   |   |  |
|     | Supply the following.  |    |     |   |   |  |
| 193 | Victron Lynx's distributor 1000 with 4 battery connections   | No | 2   |   |   |  |
| 194 | DP DC 500V 250A fuse holders (suitable for cylindrical fuses)  | No | 11  |   |   |  |
| 195 | DC 500V 125A fuse holders (suitable for cylindrical fuses)   | No | 11  |   |   |  |
| 196 | 250A 500V DC fuses (cylindrical)   | No | 10  |   |   |  |
| 197 | 125A 500V DC fuses (cylindrical)   | No | 22  |   |   |  |
|     | Data cabling   |    |     |   |   |  |
| 198 | Supply and install Cat6E grey  | m  | 120 |   |   |  |
| 199 | RJ 45 Terminations for Cat6E   | No | 8   |   |   |  |
|     | Carried Forward Bill No. 14 Electrical Works   | 3. |     | R |   |  |
|     | -136-  |    |     |   |   |  |

|     | ă.   |    |     |                        | ovor magent | , LAL 4 |
|-----|--|----|-----|------------------------|-------------|---------|
|     | Brought Forwar   | d  |     | F                      | R           | 1       |
| 20  | O Supply and install Cat6E grey 1 meter flyleads (RJ45 to RJ45)  | No | 2   |                        | 1           |         |
| 20  | 1 'Supply and install Cat6E grey 5 meter flyleads (RJ45 to RJ45) | No | 1   |                        |             |         |
|     | DC CABLING   |    |     |                        |             |         |
|     | PVC Insulated 1000V DC stranded Cu Cable                         |    |     |                        |             |         |
| 202 |  | m  | 190 |                        |             |         |
| 203 | 35mm² - Red / Black  | m  | 60  |                        |             |         |
| 204 | 50mm² - Red / Black  | m  | 180 |                        |             |         |
| 205 | 70mm² - Red / Black  | m  | 90  |                        |             |         |
| 206 | 95mm² - Red / Black  | m  | 120 |                        |             |         |
|     | Extra on last to install in cable sleeve or on basket            |    |     |                        |             |         |
| 207 | 25mm   | m  | 190 |                        |             |         |
| 208 | 35mm   | m  | 60  |                        |             |         |
| 209 | 50mm   | m  | 180 | 1                      |             |         |
| 210 | 70mm   | m  | 90  | 1                      |             |         |
| 211 | 95mm   | m  | 120 |                        |             |         |
|     | Termination using crimped lugs                                   |    |     | Produce and the second |             |         |
| 212 | 25mm² - Red / Black  | No | 32  | 100                    |             |         |
| 213 | 35mm² - Red / Black  | No | 16  |                        |             |         |
| 214 | 50mm² - Red / Black  | No | 32  |                        |             |         |
| 215 | 70mm² - Red / Black  | No | 52  |                        |             |         |
| 216 | 95mm² - Red / Black  | No | 40  |                        |             |         |
|     | CABLE LADDERS  |    |     |                        |             |         |
|     | Carried Forward<br>Bill No. 14<br>Electrical Works               |    |     | R                      |             |         |
|     | -137-  |    |     |                        | 101         |         |

R.

|     | Brought Forward   | i le |     | F | R |  |
|-----|---|------|-----|---|---|--|
|     | The complete supply, transport to site, and storage of hot dipped galvanised heavy duty cable ladder and offsets as required below:   |      |     |   |   |  |
| 217 | 300mm wide  | m    | 94  |   |   |  |
| 218 | 600mm wide  | m    | 55  |   |   |  |
| 219 | 800mm wide  | m    | 75  |   |   |  |
|     | Extra on last to install horizontally (trapeeze) or vertically (P1000 unistrut). Fixings at 1000mm. Installation is to include for all joiner splices, raw bolts and fixing cable ladder to unistrut with bolt fasteners complete with spring washer, fixing bolts etc. |      |     |   |   |  |
| 220 | 300mm wide  | m    | 94  |   |   |  |
| 221 | 600mm wide  | m    | 55  |   |   |  |
| 222 | 800mm wide  | m    | 75  |   |   |  |
|     | CABLE BASKETS   |      |     |   |   |  |
|     | The complete supply, transport to site, and storage of hot dipped galvanised medium duty cable basket and offsets as required below:  |      |     |   |   |  |
| 223 | 150mm wide  | m    | 85  |   |   |  |
| 224 | 300mm wide  | m    | 220 |   |   |  |
|     | Extra on last to install horizontally (trapeeze) or vertically (P1000 unistrut). Fixings at 1000mm. Installation is to include for all joiner splices, raw bolts and fixing cable basket to unistrut with bolt fasteners complete with spring washer, fixing bolts etc. |      |     |   |   |  |
| 225 | 150mm wide  | m    | 85  |   |   |  |
| 226 | 300mm wide  | m    | 220 |   |   |  |
|     | LUMINAIRES  |      |     |   |   |  |
|     | Carried Forward<br>Bill No. 14<br>Electrical Works  |      |     | R |   |  |

-138-

R,

y her

|     | Brought Forward  |    |     | R |      | 1 |
|-----|--|----|-----|---|------|---|
|     | Supply the following luminaries, inclusive of lamps.  Tenderer's are referred to Electrical Engineer's drawings annexed to these bills of quantities.  Drawing No. 23029 600                           |    |     |   |      |   |
| 227 | Type A1 - LED  | No | 250 |   |      |   |
| 228 | Type A1e - LED   | No | 30  |   |      |   |
| 229 | Type A2 - LED  | No | 12  |   |      |   |
| 230 | Type A2e - LED   | No | 12  |   |      |   |
| 231 | Type B -   | No | 40  |   |      |   |
| 232 | Type 8e -  | No | 5   |   |      |   |
| 233 | Type C -   | No | 55  |   |      |   |
| 234 | Type Ce -  | No | 12  |   |      |   |
| 235 | Type D -   | No | 22  |   |      |   |
| 236 | Type De -  | No | 8   |   |      |   |
| 237 | Type E1 -  | No | 20  |   |      |   |
| 238 | Type E1e -   | No | 20  |   |      |   |
| 239 | Type F -   | No | 8   |   |      |   |
| 240 | Type Fe -  | No | 8   |   |      |   |
| 241 | Type G   | No | 12  |   |      |   |
| 242 | Type H   | No | 20  |   |      |   |
| 243 | Туре К   | No | 20  |   |      |   |
| 244 | install and connect the following luminaries, inclusive of lamps. Tenderer's are referred to Electrical Engineer's drawings annexed to these bills of quantitles. Drawing No. 23029 600  Type A1 - LED | No | 250 |   |      |   |
|     | Carried Forward Bill No. 14 Electrical Works   |    |     | R | 1. A |   |
|     | -139-  | •  |     | 1 | Marc |   |

|     |  |    | FOIL | IVII 4 OI EKF | 6934 ikageng i | EXL 4 |
|-----|--|----|------|---------------|----------------|-------|
|     | Brought Forwar   | d  | 1    | R             |                |       |
| 245 | Type A1e - LED   | No | 30   |               |                |       |
| 246 | Type A2 - LED  | No | 12   |               |                |       |
| 247 | Type A2e - LED   | No | 12   |               |                |       |
| 248 | Туре В   | No | 40   |               | 4              |       |
| 249 | Type Be  | No | 5    |               |                |       |
| 250 | Type C   | No | 55   |               |                |       |
| 251 | Туре Се  | No | 12   |               |                |       |
| 252 | Type D   | No | 22   |               |                |       |
| 253 | Týpe De  | No | 8    |               |                |       |
| 254 | Type E1  | No | 20   |               |                |       |
| 255 | Type E1e   | No | 20   |               |                |       |
| 256 | Type Fe  | No | 8    |               |                |       |
| 257 | Type F   | No | 8    |               |                |       |
| 258 | Type G   | No | 12   |               |                |       |
| 259 | Туре Н   | No | 20   |               |                |       |
| 260 | Туре К   | No | 20   |               |                |       |
|     | POWER SKIRTING. INTERCOM & METAL<br>DETECTOR   |    |      |               |                |       |
|     | Supply and Install the following:  |    |      |               |                |       |
| 261 | Two Compartment 2 cover, epoxy powder coated power skirting, surface mounted, inclusive of cover | m  | 420  |               |                |       |
| 262 | Supply and install End caps  | No | 65   |               |                |       |
| 263 | Supply and install 90° bends   | No | 36   |               |                |       |
|     | Carried Forward  |    |      | P             |                |       |
|     | Bill No. 14 Electrical Works   |    |      | R             |                |       |
|     | - (ann   |    |      | h             | m,             |       |

2. P.

|     | Brought Forward   |    |       | F | <b>*</b> |
|-----|---|----|-------|---|----------|
|     | Supply, install and commission intercom with colour video system complete with all hardware, airphone or other equally approved system and central equipment  |    |       |   |          |
| 264 | Master station unit suitable for 10 slave stations and hands free with 3.5" colour LCD display  | No | 1     |   |          |
|     | Field Equipment   |    |       |   |          |
| 265 | Door station with audio and video, flush mounted with stainless steel face  | No | 12    |   |          |
| 266 | Door maglock release connection via a I/O interface to access control system located in IT Room   | No | 12    |   |          |
|     | Cabling   |    |       |   |          |
| 267 | Cat 6A cabling  | m  | 3 550 |   |          |
| 268 | RJ45 termination  | No | 48    |   |          |
| 269 | 4 core 1.0 mm Cu PVC PVC cable  | m  | 1 366 |   |          |
| 270 | Terminated in above equipment   | No | 24    |   |          |
|     | Supply, install, test and commission Metal Detector (or other equally approved) complete with connectors, adapters, fixings, power sockets, cables, consumables and all material to complete required |    |       |   |          |
| 271 | Supply and install walk through metal detector incorporating 42 zones with illuminating indicator strip along the length of the unit  | No | 1     |   |          |
|     | EARTHING AND LIGHTNING PROTECTION   |    |       |   |          |
| 272 | Undertake soil resistivity test, witnessed by the Engineer inclusive of submitting a typed test report/certificate  |    | Item  |   |          |
| 273 | 70mm² PVC insulated copper earth wire   | m  | 188   |   |          |
| 274 | Extra on last to install  | m  | 188   |   |          |
| 275 | Earthing tails clamped to top of column rebar   | No | 40    |   |          |
|     |   |    |       |   |          |
|     | Carried Forward Bill No. 14 Electrical Works  |    |       | R |          |
| ļ   | -141-   | 1  |       |   | 1 10 1   |

-141-

n 1

|     |   |     |      |     | 4 ikayeny Ext. 4 |
|-----|---|-----|------|-----|------------------|
|     | Brought Forwa   | ird | 1    | R   | 1                |
| 27  | Bonding of earth tails to sheet trusses/roof sheeting   | No  | 36   |     |                  |
| 27  | 7 Monitor bonding of pile caps steel to column steel  | No  | 40   |     |                  |
| 27  | 8 Supply and install 25mm conduit   | m   | 160  |     |                  |
| 27  | Supply and install 10mm aluminium ridge conductor   | m   | 755  |     |                  |
| 280 | Supply and install stainless steel lugs   | No  | 40   |     |                  |
| 28  | Supply and install stainless steel bolts and nuts   | No  | 40   |     |                  |
| 282 | Supply and install stop cork box  | No  | 36   |     |                  |
| 283 | Supply and install 1.8m earth spike   | No  | 36   |     |                  |
|     | EARTHING AND BONDING  |     |      |     |                  |
| 284 | Allowance for general electrical earthing and bonding in accordance with SABS 0142  |     | ltem |     |                  |
| 285 | Test and commissioning inclusive of test report   |     | Item |     |                  |
|     | SOIL RESISTIVITY SURVEY   |     |      |     |                  |
|     | Soil sensitivity survey allow to survey the site to establish any prevailing conditions and carry out soil resistivity testing in the locations adjacent to each Sub Station. A detailed report indicating test results and regulrements to achieve the necessary earth resistance for each area is to be submitted to the Electrical Engineer. |     |      |     |                  |
| 286 | Resistivity Test survey in earth  | No  | 1    |     |                  |
| 287 | Test report indicating electrode requirements, etc. toachieve 1 ohm or less   | No  | 1    |     |                  |
|     | TRENCHING   |     |      |     |                  |
|     | Excavate by hand for cable trench or earth mats including backfill with sifted sand, cable trench 350mm wide x 600mm deep x 1 500mm Jong  |     |      |     |                  |
| 288 | in earth  | No  | 1    |     |                  |
| 289 | In Shale  | No  | 2    |     |                  |
|     | Carried Forward<br>Bill No. 14<br>Electrical Works  |     |      | R   |                  |
|     | -142-   |     | 7.   | " \ | 1                |

-142-

RJ

|     | Brought Forward   |    |    | R   | ĺ |
|-----|---|----|----|-----|---|
| 290 | In hard rock  | No | 2  |     |   |
|     | Bonding to earth electrodes   |    |    |     |   |
| 291 | Supply and install 20mm lengths of 95mm² Green PVC insulated copper conductors fitted into sleeves and trench complete with lugs, ferrules and termination clamps between substation earth bar and earth electrode.   | No | 1  |     |   |
|     | Earth Mats  |    |    |     |   |
| 292 | Supply and install 1,600mm copper clad Earth Electrodes driven into ground at 1,500mm by 1,500mm spacing including brass termination clamps and 50mm² bare copper conductor interlinking to 2 No.earth grid adjacent earth spike to form an earth grid  | No | 2  |     |   |
|     | Earth electrodes  |    |    |     |   |
| 293 | Supply and install additional 1,600mm copper clad earth electrode driven into the ground including the ferrel   | No | 1  |     |   |
|     | ACCESS CONTROL & ALARM  |    |    |     |   |
|     | Supply, install, test and commission Impro Access Portal Basic (or other equally approved) access control and intercom system complete with connectors, adapters, fixings, power sockets, cables, consumables and all material to complete required Control room equipment complete with all power supplies and mounting equipment. |    |    |     |   |
| 294 | Programming and enrolment station, PC (I7 processor, 8 Gb RAM 500 Gb SSD storage, Windows 10, Office and Acrobat) with 21 "monitor, mouse, keyboard etc.  | No | 1  |     |   |
| 295 | Biometric fingerprint enrolment reader  | No | 2  |     |   |
| 296 | Enrolment camera  | No | 1  |     |   |
| 297 | Set up and program access control software for 100 users and 20 No. doors   | No | 1  |     |   |
|     | Door control complete with all mounting equipment located in IT cupboard  |    |    |     |   |
| 298 | Wall mounted door controller in IP 54 housing complete with 2 No.Wiegard reader modules and power supply  | No | 11 |     |   |
|     | Carried Forward Bill No. 14 Electrical Works  |    |    | R   |   |
|     | -143-   | 2  | I, | U . |   |

-143-

24

W 223

|     | Brought Forward  |    | ĺ     | R |
|-----|--|----|-------|---|
| 299 | Biometric fingerprint and Mifare reader - Morpho Access  |    |       |   |
| 200 | Sigma lite   | No | 1     |   |
| 300 | 600kg surface mounted monitored maglock with LED   | No | 11    |   |
| 301 | ZL bracket for maglock   | No | 11    |   |
| 302 | No touch exit sensor   | No | 11    |   |
| 303 | Green Breakglass unit with internal buzzer (resettable)  | No | 11    |   |
| 304 | 25Khz, 150 Khz card reader   | No | 30    |   |
|     | Supply and installation of cable and wiring on cable basket in ceiling vold or drawn into conduit as specified, including all lables and terminations at both ends.  |    |       |   |
| 305 | Category 6 UTP   | m  | 1 417 |   |
| 306 | Termination of UTP Cat 6   | No | 60    |   |
| 307 | 8 twisted pair PVC insulated mylar cable. 0.22mm² stranded tinned copper cores. Aluminium polyester shield and drain.  | m  | 1 312 |   |
| 308 | Termination of above cable   | No | 72    |   |
|     | ALARM SYSTEM (PROVISIONAL)   |    |       |   |
|     | Supply and installation of a Alarm system complete. Prices shall include for all materials, labour, profit, transport, etc. Everything necessary for the execution and complete installation of the work in accordance with the description. |    |       |   |
|     | CENTRAL EQUIPMENT  |    |       |   |
| 309 | I/O controller (minimum of 16 input, 8 output) as specified connected on to the access control system network  | No | 1     |   |
| 310 | Flush mounted door position switch connected to I/O controller   | No | 4     |   |
| 311 | Long range wall mounted PIR detectors connected to I/O controller  | No | 4     |   |
|     | Carried Forward Bill No. 14 Electrical Works   |    |       | R |
|     |  |    |       |   |

R

20

M 22

|     | Brought Forward  | i  |       | R | 1 |  |
|-----|--|----|-------|---|---|--|
| 312 | Ceiling Mount 360° PIR connected to I/O controller   | No | 6     |   |   |  |
| 313 | Ceiling mounted PIR / microwave intrustion detector (Dual Detector) connected to I/O controller              | No | 55    |   |   |  |
| 314 | Panic button wall mounted connected to I/O controller  | No | 12    |   |   |  |
| 315 | Push button mounted in polyester box with green LED for panic alarm connected to I/O controller              | No | 12    |   |   |  |
| 316 | Flashing red high intensity LED and siren mounted above disabled WC alarm connected to I/O controller        | No | 12    |   |   |  |
| 317 | Pushbutton mounted in polyester box with green LED for acceptance of Panic alarm connected to I/O controller | No | 12    |   |   |  |
|     | CENTRAL EQUIPMENT  |    |       |   |   |  |
| 318 | 0,5mm² 4-core Mylar  | m  | 756   |   |   |  |
| 319 | Terminate 0,5mm² 4-core Mylar  | No | 28    |   |   |  |
| 320 | 0,75mm² 4-core Myla  | m  | 1 523 |   |   |  |
| 321 | Terminate 0,75mm² 4-core Mylar   | No | 26    |   |   |  |
| 322 | 1mm² 4-core Mylar  | m  | 2 120 |   |   |  |
| 323 | Terminate 1mm² 4-core Mylar  | No | 28    |   |   |  |
|     | Carried to Summary Bill No. 14 Electrical Works  |    |       | R |   |  |
|     | 145  | 1  | 1     | 1 | 1 |  |

-145-

. 0

| Item<br>No | 4.  | Quantity | Rate | Amount |
|------------|---|----------|------|--------|
|            | BILL NO. 15   |          |      |        |
|            | MECHANICAL INSTALLATION   |          |      |        |
|            | (CPAP WORK GROUP NO. 170 UNLESS OTHERWISE STATED)   |          |      |        |
|            | PREAMBLES   |          |      |        |
|            | The descriptions given in the various items below are not necessarily full and complete and reference must be made to the "General Preambles for Trades 2017" as published by the Association of South African Quantity Surveyors", and Supplementary Preambles for further description and amplification of work in this section |          |      |        |
|            | AIR-CONDITIONING & VENTILATION INSTALLATION   |          |      |        |
|            | GENERAL ITEMS   |          |      |        |
|            | Any additional, items that the Tenderer deems necessary for the successful and total completion of the portion of the work required for this Bill.  Specify:  |          |      |        |
| 1          | Allow for builders work, drilling and making good of holes through slabs or walls including sleeves.  | Item     |      |        |
| 2          | Allow for painting of ducting and insulation of the Air conditioning and Ventilation installation as specified to SANS 10173. The surfaces shall be cleaned, primed, undercoated and finished in high quality gloss paint.  | Item     |      |        |
| 3          | Allow for painting and labelling of equipment as specified.   | Item     |      |        |
| 4          | Allow for Commissioning and testing the complete installation as specified.   | Item     |      |        |
| 5          | Allow for three sets of maintenance and operation manuals, including wiring diagrams, spare part lists as specified.  | Item     |      |        |
|            | Carried Forward  Bill No. 15  Mechanical Works  |          | R    |        |
|            | -146-   |          | J.   | S .    |

-146-

n .1

km 2

|    | Brought Forward   |    |  | R |
|----|---|----|--|---|
| 6  | Allow for twelve months free maintenance and guarantee.   |    | Item   |   |
| 7  | Allow for instructing the clients staff in the correct operation of the installation.   |    | Item   |   |
| 8  | Allow for preparation of "as installed drawings" and printing (3 sets).   | No | 1  |   |
| 9  | Allow for preparation of Workshop drawings and printing (3 sets).   | No | 1  |   |
| 10 | Any items not specifically listed above but required to complete the installation as per the specification and drawings (list the items) a) b) c)   |    | ltem   |   |
|    | Air conditioning equipment and plping   |    |  |   |
|    | Supply and deliver the following Direct Expansion, Inverter split type air conditioning system (YORK or other equally approved), complete with condensing and evaporator units, all with electrical connection to isolator, refrigeration- and drain piping, electrical control wiring, brackets, supports, auxiliary extended drip tray at each indoor unit and all necessary accessories, as per the specification and manufacturer's recommendation. |    | All constitutions and appropriate annually, and a series among |   |
| 11 | Wall mounted type Evapourator Unit<br>(Y5HJH009BAMFY)<br>Cooling capacity - 2.64 kW<br>Heating capacity - 2.74 kW   | No | 9  |   |
| 12 | Matching Outdoor Condensing unit, complete with wall mounted bracket. (Y5HJH009BAM-A-Y)   |    |  |   |
|    | EER - 3.26<br>COP - 3,61  | No | 9  |   |
| 13 | Diameter 6.35mm insulated refrigerant piping, installed inside trunking.  | m  | 90   |   |
| 14 | Diameter 9,52mm insulated refrigerant piping, installed inside trunking.  | m  | 90   |   |
|    | Carried Forward Bill No. 15 Mechanical Works  |    |  | R |
|    |   |    |  |   |

-147-

not

*پ* ر

|    | Brought Forward   |    | 1  | R | 1 |
|----|---|----|----|---|---|
| 15 | Diameter 32mm uPVC condensate drain piping, installed inside trunking.  | m  | 60 |   |   |
| 16 | Hard wired controller   | No | 9  |   |   |
| 17 | 100 x 40mm uPVC Trunking.   | m  | 60 |   |   |
| 18 | Wall mounted type Evapourator Unit<br>(Y5HJH012BAM-FY)<br>Cooling capacity - 3.52 kW<br>Heating capacity - 3.6 kW | No | 1  |   |   |
| 19 | Matching Outdoor Condensing unit, complete with wall mounted bracket. (Y5HJH012BAM-A-Y) EER - 3.23 COP - 3,61     |    |    |   |   |
|    | 001 - 0,07  | No | 1  |   |   |
| 20 | Diameter 6.35mm insulated refrigerant piping, installed inside trunking.  | m  | 10 |   |   |
| 21 | Diameter 9,52mm insulated refrigerant piping, installed inside trunking.  | m  | 10 |   |   |
| 22 | Diameter 32mm uPVC condensate drain piping, installed inside trunking.  | m  | 10 |   |   |
| 23 | Hard wired controller   | No | 1  |   |   |
| 24 | 100 x 40mm uPVC Trunking.   | m  | 15 |   |   |
| 25 | Wall mounted type Evapourator Unit<br>(Y5HJH024BAMFY)<br>Cooling capacity - 7.03 kW<br>Heating capacity - 7.03 kW | No | 6  |   |   |
| 26 | Matching Outdoor Condensing unit, complete with wall mounted bracket. (Y5HJH024BAM-A-Y)                           | No | 6  |   |   |
| 27 | Diameter 9,52mm insulated refrigerant piping, installed inside trunking.  | m  | 90 |   |   |
| 28 | Diameter 15,88mm insulated refrigerant piping, installed inside trunking.   | m  | 90 |   |   |
|    | Carried Forward Bill No. 15 Mechanical Works  |    |    | R |   |

|    | Brought Forward   |    | 1  | R |
|----|---|----|----|---|
| 29 | Diameter 32mm uPVC condensate drain piping, installed inside trunking.  | m  | 60 |   |
| 30 | Hard wired controller   | No | 6  |   |
| 31 | 100 x 40mm uPVC Trunking  | m  | 60 |   |
| 32 | Wall mounted type Evapourator Unit<br>(Y5HJH030BAM–FY)<br>Cooling capacity - 8.64 kW<br>Heating capacity - 8.64 kW  | No | 4  |   |
| 33 | Matching Outdoor Condensing unit, complete with wall mounted bracket. (Y5HJH030BAM-A-Y) EER - 3.47 COP - 3,51   | No | 4  |   |
| 34 | Diameter 9,52mm insulated refrigerant piping, installed inside trunking.  | m  | 60 |   |
| 35 | Diameter 15,88mm insulated refrigerant piping, installed inside trunking.   | m  | 60 |   |
| 36 | Diameter 32mm uPVC condensate drain piping, installed inside trunking.  | m  | 40 |   |
| 37 | Hard wired controller   | No | 4  |   |
| 38 | 100 x 40mm uPVC Trunking  | m  | 40 |   |
| 39 | Supply and deliver the following Inverter Console type air conditioning system (YORK or other equally approved), complete with all with electrical connection to isolator, electrical control wiring, brackets, supports and all necessary accessories, as per the specification and manufacturer's recommendation.  Inverter console Unit (MIHP09A) Cooling capacity - 2.64 kW Heating capacity - 2.85 kW EER - 2.75 |    |    |   |
|    | COP - 2.94  | No | 26 |   |
|    | Carried Forward<br>Bill No. 15<br>Mechanical Works  |    |    | R |

, ;

W 229

|    | Brought Forwar  | rd |      | R∥ | 1 |
|----|---|----|------|----|---|
| 4  | Inverter console Unit (MIHP13A) Cooling capacity - 3.8 kW Heating capacity - 3.5 kW EER - 2.24 COP - 2.82   | No | 12   |    |   |
| 4  | Inverter console Unit (MIHP15A) Cooling capacity - 4.4 kW Heating capacity - 3.5 kW EER - 2.25 COP - 2.82   | No | 7    |    |   |
|    | Ventilation equipment   |    |      |    |   |
| 42 | For the Supply (including delivery), installation (including testing, commissioning and handing over of the following ventilation fan complete with electrical connection to isolator or light circuit as specified, ducting, flexible connections, including hangers, supports, brackets, sound attenuators matching the fan capacities and all necessary accessories.  TD SILENT 2000/315 @ the following flow rate and pressure drops 242 l/s @ 330 Pa 223 l/s @ 380 Pa 204 @ 355 Pa inline fan complete with speed controller and timer switch. Supply 220/50/1, 260W. AMS or other equally approved. | No | 4    |    |   |
| 43 | Matching Sound Attenuators.   | No | 8    |    |   |
| 44 | TD SILENT 1300/250 @ the following flow rate and pressure drops 126 I/s @ 300 Pa 66 I/s @ 273 Pa inline fan complete with speed controller and timer switch. Supply 220/50/1, 260W. AMS or other equally approved.  | No | 2    |    |   |
| 45 | Matching Sound Attenuators.   | No | 4    |    |   |
|    | Carried Forward<br>Bill No. 15<br>Mechanical Works  |    | Chan | R  |   |

-150-

n J

han

|    | Brought Forward   | ı  |    | R |  |
|----|---|----|----|---|--|
| 46 | TD SILENT 1000/200 @ the following flow rate and pressure drops 50 l/s @ 250 Pa 30 l/s @ 271 Pa   |    |    |   |  |
|    | inline fan complete with speed controller and timer switch. Supply 220/50/1, 260W. AMS or other equally approved.   | No | 2  |   |  |
| 47 | Matching Sound Attenuators.   | No | 4  |   |  |
| 48 | Vortice vario (150/6 ARI LLS) - Donkin or other equally approved  | No | 4  |   |  |
|    | Ductwork and fittings   |    |    |   |  |
|    | Supply, deliver and install LOW PRESSURE galvanized un-insulated ductwork as per the specification including fittings, reducers, radius bends, stop end, branches, tees and transformations all hangers, straps, supports, clamps and necessary accessories.  |    |    |   |  |
|    | FLEXIBLE DUCTING (foil faced 50mm mineral wool)   |    |    |   |  |
| 49 | Ø100mm  | m  | 40 |   |  |
| 50 | Ø160mm .  | m  | 25 |   |  |
| 51 | Ø200mm  | m  | 25 |   |  |
|    | RECTANGULAR DUCTING   |    |    |   |  |
|    | Rectangular galvanised mild steel sheetmetal ductwork installed as per specification complete with fittings including hangers, clamps, brackets, etc. (excluding insulation) Square meterage of ducting is inclusive of area over fittings. The following sheetmetal thicknesses shall apply to the corresponding categories; Category One: 0.6mm Category Two: 0.6mm Category Three: 0.8mm Category Four: 1,0mm Category Five: 1.2mm |    |    |   |  |
| į  | CATEGORY ONE  |    |    |   |  |
| 52 | Width or height not exceeding 750mm and the sum of the two adjacent sides not exceeding 1150mm  | m2 | 30 |   |  |
|    | Carried Forward   |    |    | R |  |
|    | Bill No. 15<br>Mechanical Works   |    |    |   |  |

1 pm 231

|    | Brought Forward  | 1  | 1  | R | 1 |
|----|--|----|----|---|---|
|    | Extra over for low pressure galvanised fittings (reducers, radius bends, transformations, spigots tees and square-to-rounds)   |    |    |   |   |
| 53 | Category one fittings other than stop ends   | No | 20 |   |   |
|    | Stop ends  |    |    |   |   |
| 54 | Category one Stop End fittings   | No | 8  |   |   |
|    | CATEGORY TWO   |    |    |   |   |
| 55 | Width or height not exceeding 750mm and the sum of the two adjacent sides exceeding 1150mm   | m2 | 15 |   |   |
|    | Extra over for low pressure galvanised fittings (reducers, radius bends, transformations, spigots, tees and square-to-rounds)  |    |    |   |   |
| 56 | Category two fittings other than stop ends   | No | 8  |   |   |
|    | Stop ends  |    |    |   |   |
| 57 | Category two Stop End fittings   | No | 2  |   |   |
|    | ROUND DUCTING  |    |    |   |   |
|    | Complete with fittings including hangers clamps brackets nuts, bolts etc   |    |    |   |   |
|    | Sheetmetal Thickness for round ducting unless otherwise indicated up to 300mm dia. :0.5mm 301dia to 800dia : 0.6mm 801dia to 1000dia. : 0.8mm 1001 to 1200dia : 1.0mm Jointing shall be beaded |    |    |   |   |
|    | STRAIGHT SECTIONS  |    |    |   |   |
| 58 | Ø100mm   | m  | 45 |   |   |
| 59 | Ø150mm   | m  | 15 |   |   |
| 60 | Ø160mm   | m  | 22 |   |   |
| 61 | Ø200mm   | m  | 10 |   |   |
|    |  |    |    |   |   |
|    | Carried Forward  |    |    | R |   |
|    | Bill No. 15<br>Mechanical Works  |    |    |   |   |
|    | -152-  | Į  |    |   |   |

R

lon 2

|    |                                 | Brought Forward |    | R | ĺ |
|----|---------------------------------|-----------------|----|---|---|
| 62 | Ø250mm                          | m               | 48 |   |   |
| 63 | Ø315mm                          | m               | 10 |   | - |
| 64 | Ø350mm                          | m               | 10 |   |   |
|    | 90 DEGREE BENDS                 |                 |    |   |   |
| 65 | Ø100mm                          | No              | 10 |   |   |
| 66 | Ø150mm                          | No              | 5  |   |   |
| 67 | Ø160mm                          | No              | 6  |   |   |
| 68 | Ø200mm                          | No              | 5  |   |   |
| 69 | Ø250mm                          | No              | 5  |   |   |
|    | TRANSFORMATION PIECES           |                 |    |   |   |
| 70 | Ø150mm - Ø100mm                 | No              | 5  |   |   |
| 71 | Ø200mm - Ø100mm                 | No              | 5  |   |   |
| 72 | Ø200mm - Ø150mm                 | No              | 3  |   |   |
| 73 | Ø200mm - Ø160mm                 | No              | 2  |   |   |
| 74 | Ø250mm - Ø200mm                 | No              | 5  |   |   |
| 75 | Ø300mm - Ø250mm                 | No              | 10 |   |   |
| 76 | Ø315mm - Ø250mm                 | No              | 2  |   |   |
| 77 | Ø315mm - Ø300mm                 | No              | 2  |   |   |
| 78 | Ø350mm - Ø300mm                 | No              | 2  |   |   |
| 79 | Ø350mm - Ø315mm                 | No              | 3  |   |   |
| 80 | 300 x 200 - Ø200mm              | No              | 2  |   |   |
| 81 | 315 x 300 - Ø200mm              | No              | 2  |   |   |
| 82 | 400 x 300 - Ø250mm              | No              | 3  |   |   |
| 83 | 500 x 300 - Ø315mm              | No              | 5  |   |   |
|    | Bill No. 15<br>Mechanical Works | Carried Forward |    | R |   |

ſ.

n 4

|    | Brought Forward   | 1  |    | R∥ |    |
|----|---|----|----|----|----|
|    | STOP ENDS   |    |    |    |    |
| 84 | Ø150mm  | No | 4  |    |    |
| 85 | Ø200mm  | No | 2  |    |    |
| 86 | Ø250mm  | No | 4  |    |    |
|    | Air Terminals   |    |    |    |    |
|    | For the Supply (including delivery), installation (including testing, commissioning and handing over of the following grilles, weather louvers, disc valves, diffusers, filters, dampers and associated items including all necessary accessories and fittings. |    |    |    |    |
|    | Louvres   |    |    |    |    |
| 87 | 200 x 400mm Weather Louver (Trox AWG or other equally approved) complete with wire mesh screen epoxy colour coated finish to Engineers detail   | No | 2  |    |    |
| 88 | 300 x 400mm Weather Louver (Trox AWG or other equally approved) complete with wire mesh screen epoxy colour coated finish to Engineers detail   | No | 6  |    |    |
|    | Disc Valves   |    |    |    |    |
| 89 | Diameter 100mm duct mounted disc valve for supply air (Trox type Z-LVS or other equally approved) epoxy colour coated to matching ceiling detail. Various air flow rate. Please refer to drawing.   | No | 26 |    |    |
| 90 | Diameter 160mm duct mounted disc valve for extract air (Trox type Z-LVS or other equally approved) epoxy colour coated to matching ceiling detail. Various air flow rate. Please refer to drawing.  | No | 18 |    |    |
| 91 | Diameter 200mm duct mounted disc valve for extract air (Trox type Z-LVS or other equally approved) epoxy colour coated to matching ceiling detail. Various air flow rate. Please refer to drawing.  | No | 13 |    |    |
|    | <u>Dampers</u>  |    |    |    |    |
| 92 | Ø100mm Circular Volume Control Damper, (manual) (Trox type VFC or other equally approved).  | No | 26 |    |    |
|    | Carried Forward Bill No. 15 Mechanical Works  |    |    | R  |    |
| 1  |   |    | 1  | 3  | Į. |

 $\mathcal{R}$ 

1 6 234

|     | Brought Forward  | 1  |      | R |   |  |
|-----|--|----|------|---|---|--|
| 93  | Ø160mm Circular Volume Control Damper, (manual) (Trox type VFC or other equally approved).   | No | 15   |   |   |  |
| 94  | Ø200mm Circular Volume Control Damper, (manual) (Trox type VFC or other equally approved).   | No | 12   |   |   |  |
|     | Fire Dampers   |    |      |   |   |  |
| 95  | 500 x 500mm Fire Damper with Fusible link (2hr fire-rated, Normally open)  | No | 5    |   |   |  |
| 96  | 250 x 250mm Fire Damper with Fusible link (2hr fire-rated, Normally open)  | No | 5    |   |   |  |
|     | Washable Pleated Filters   |    |      |   |   |  |
| 97  | PF1 - 595 x 295 x 50mm Washable primary pleated filters (Trox type WP-PS/ 595 x 295 x 50mm or other approved) complete with filter box   | No | 8    |   |   |  |
|     | Grilles (Supply & extract air)   |    |      |   |   |  |
| 98  | 400 x 300mm Extract air grille (Trox type VAT-AG or other approved), made from aluminium, complete with OBD, spigot connection to ducting, epoxy colour coated finish to architect's detail.  Pressure drop at 25 Pa   | No | 1    |   |   |  |
|     | Supply, deliver and install the following extract canopy complete with make-up and extract air connections, filters, drip trays, stainless steel impingement filters electrical connection to isolator or light circuit as specified, including hangers, supports, brackets and all necessary accessories. |    |      |   |   |  |
| 99  | 2000 x 1500mm Stainless steel "Cyclovent" or equally approved model CV 100B kitchen extraction canopy complete with "Cycloclean" or equally approved filters, grease cups and on/off switch linked to extract and make up air fans, set up and fixed in position complete                                  | No | 1    |   |   |  |
| 100 | On-off control / starters for fans   |    | item |   |   |  |
| 101 | Brushed stainless steel bulkhead to match canopy, to be installed between canopy and ceiling   |    | Item |   |   |  |
|     | Carried Forward Bill No. 15 Mechanical Works   |    |      | R |   |  |
|     | 4==  |    |      |   | 0 |  |

R.

of the

|     | Brought Forward  | 1  |    | R | 1 |
|-----|--|----|----|---|---|
|     | Supply, deliver and install the following dehumidifiers complete with drip trays, supports, brackets and all necessary accessories.  |    |    |   |   |
| 102 | Dehumidifiers (Maeco dry artete 25L or equal approved)   | No | 9  |   |   |
| 103 | Supply, deliver and install 250 x 100mm galvanized trunking, with removable covers, including brackets, supports and all necessary accessories, to install refrigeration piping in. <b>Provisional</b>   | m  | 40 |   |   |
| 104 | Supply, deliver and install 200 x 100mm galvanized trunking, with removable covers, including brackets, supports and all necessary accessories, to install refrigeration piping in (Provisional)   | m  | 30 |   |   |
| 105 | Supply, deliver and install 100mm wide wire mesh cable basket (Cabstrut or other equally approved), including brackets, supports and all necessary accessories, to install refrigeration piping on (Provisional)   | m  | 50 |   |   |
| 106 | Supply, deliver and install 200mm wide wire mesh cable basket (Cabstrut or other equally approved), including brackets, supports and all necessary accessories, to install refrigeration piping on (Provisional)   | m  | 40 |   |   |
| 107 | R410A Refrigerant charge (Provisional)   | kg | 10 |   |   |
| 108 | Supply and install 41 x 41mm Unistrut channel (Cabstrut or other equally approved) as brackets and supports for the air conditioning units, ducting and cable trays to the building roof and wall structure, complete with necessary fittings and accessories as per manufacturer's recommendation (Provisional) | m  | 80 |   |   |
|     | KITCHEN EQUIPMENT  |    |    |   |   |
|     | Specifications, drawings, etc  |    |    |   |   |
|     | Tenderers are referred to the specification at the back of<br>these bills of quantities for the mechanical work, for the<br>full descriptions of the following items which are to be<br>read and priced in conjunction with the said specification<br>and drawing  | *  |    |   |   |
|     | KITCHEN EQUIPMENT  |    |    |   |   |
|     | Carried Forward<br>Bill No. 15<br>Mechanical Works   |    |    | R |   |
|     |  |    |    |   |   |

-156-

R.

of han

|     | Brought Forward  | i  | 1 | R |  |
|-----|--|----|---|---|--|
|     | Supply and install "Vulcan" or other equally approved stainless steel sinks, tables, shelves, racks, trolleys, etc,  |    |   |   |  |
| 109 | 1850 x 650 x 910mm x 85kg stainless steel (PS□Lor PS-R) double combination pot sink with 150mm splashback at rear  | No | 1 |   |  |
| 110 | 2250 x 300mm Single tier wall mounted shelf code 2749331   | No | 1 |   |  |
| 111 | 1850 x 400mm Wall mounted tubular pot rack   | No | 1 |   |  |
| 112 | 910 x 530 x 310mm "Cambro" model DRS36480 or other equally approved dunnage rack code 2610096  | No | 4 |   |  |
| 113 | 1070 x 540 x 1830mm "Cambro" or other equally approved vented four shelf add-on unit code 2610151A   | No | 4 |   |  |
| 114 | 1840 x 650 x 910mm Table code 3044702 with 150mm splashback to rear, all 430 type stainless steel with heavy duty backing sheet with bitumastic sound deadening and fitted on stainless steel legs with        |    |   |   |  |
|     | adjustable foot pieces   | No | 1 |   |  |
| 115 | 1140 x 610 x 1670mm Model MCR-6 mobile 600 piece crockery rack code 2745007  | No | 1 |   |  |
| 116 | 1200 x 600 x 1450mm Model MPR mobile pot rack code 3043447 mounted on 100mm casters  | No | 1 |   |  |
| 117 | 1100 x 300mm Two tier heated riser shelf code 3028966 fitted with code 3318639 H-Infra heating   | No | 2 |   |  |
| 118 | 1200 x 300mm Two tier heated riser shelf code 3018962 fitted with code 3318639 G-Infra heating   | No | 2 |   |  |
| 119 | 1090 x 530 x 934mm x 20kg Model TCT tray and cutlery trolley code 3081860 with provision for two (2No) cutlery boxes and four (4No) code 2707002 four division cutlery boxes                                   | No | 2 |   |  |
| 120 | 890 x 533 x 940mm x 16kg Model DCT dish clearing trolley frame code 3081101 with six (6No) code 2715805 dish boxes, two (2No) code 3381268A stainless steel shelves and two (2No) code 3381292 stainless steel |    |   |   |  |
|     | trash bins   | No | 2 |   |  |
|     | Carried Forward Bill No. 15 Mechanical Works   |    |   | R |  |
|     | -157-  | 0  | P |   |  |

Q

of him

|     | Brought Forward  | 1  |      | F |
|-----|--|----|------|---|
|     | Supply and install "Vulcan" or other equally approved kitchen equipment, etc all in accordance with the specification  |    |      |   |
| 121 | 240Ltr mobile food refuse bin code 2790406   | No | 4    |   |
| 122 | 1000 x 850 x 910mm Model RE-3 range with three solid top electric stove with oven code 3005561   | No | 1    |   |
| 123 | 135L Oil Jacketed Boiling Pot (Electric)   | No | 1    |   |
| 124 | 1180 x 750 x 915mm Model QUB4/PLTS/C 1Ž door<br>self contained cabinet underbar refrigerator complete<br>with Just Polar Top   | No | 2    |   |
| 125 | 1780 x 750 x 915mm Just Model QUB-6/SC self contained 2Ž door underbar fridge code 2729087   | No | 1    |   |
| 126 | 625 x 760 x 1460mm x 140kg "Comenda" or other equally approved model LC-1200M hood type dish washer code 2614811 complete with two (2No) code 2618030 peg type plate racks, one (1No) code 2608035 open type cup rack and one (1No) code 2618033 flatware cutlery rack | No | 1    |   |
|     | GENERAL ITEMS FOR KITCHEN EQUIPMENT  |    |      |   |
|     | Guarantee and Maintenance  |    |      |   |
| 127 | The Guarantee and Kitchen Equipment including materials and workmanship will be for a period of TWELVE MONTHS after date of Works Completion   |    | Item |   |
|     | Testing and Commissioning  |    |      |   |
| 128 | Allow for the Testing and Commissioning the whole of all of the Kitchen Equipment as laid down in the specification and for re-testing as maybe required after making good of all defective work to the satisfaction of the Principal Agent                            |    | Item |   |
|     | Certificate for Compliance   |    |      |   |
| 129 | Allow for the issuing of a Certificate of Compliance in line with the standard regulations applying at the time  |    | Item |   |
|     | Carried Forward Bill No. 15 Mechanical Works   |    |      | R |
| 1   | 450  | 3  | - 1  |   |

|     | Brought Forward   | d  |      | F | 2 | 1 |
|-----|---|----|------|---|---|---|
|     | Training  |    |      |   |   |   |
| 130 | Allow for the training of the Employer's operators to enable them to be responsible for and capable of operating the plant  |    | Item |   |   |   |
|     | Operating Manuals   |    |      |   |   |   |
| 131 | Allow for three complete sets of indexed loose leaf operating instructions and maintenance manuals  |    | Item |   |   |   |
|     | LAUNDRY EQUIPMENT   |    | 4    |   |   |   |
|     | Specifications, drawings, etc   |    |      |   |   |   |
|     | Tenderers are referred to the specification at the back of these bills of quantities for the mechanical work, for the full descriptions of the following items which are to be read and priced in conjunction with the said specification and drawing |    |      |   |   |   |
|     | LAUNDRY EQUIPMENT   |    |      |   |   |   |
|     | Supply and install laundry equipment, etc   |    |      |   |   |   |
| 132 | Electrolux Professional model El-T5550 or other equally approved 18kW 30kg dryer  | No | 2    |   |   |   |
| 133 | Electrolux Professional model El-W5180H or other equally approved 450G 20kg washer  | No | 2    |   |   |   |
| 134 | Electrolux model El-IB42316 or other equally approved 1.65m chest type flatwork ironer  | No | 1    |   |   |   |
| 135 | Pony model PI-FVC or other equally approved electrically heated and vacuum finishing table  | No | 2    |   |   |   |
|     | Sundry equipment  |    |      |   |   |   |
| 136 | Blue laundry trolley  | No | 2    |   |   |   |
| 137 | Red laundry trolley   | No | 2    | - |   |   |
|     | GENERAL ITEMS FOR LAUNDRY EQUIPMENT   |    |      |   |   |   |
|     | Carried Forward Bill No. 15 Mechanical Works  |    |      | R |   |   |

-159-

1 per

|     | Brought Forward   |    |      | R | Ì |
|-----|---|----|------|---|---|
|     | Guarantee and Maintenance   |    |      |   |   |
| 138 | The Guarantee and Laundry Equipment including materials and workmanship will be for a period of TWELVE MONTHS after date of Works Completion  |    | Item |   |   |
|     | Testing and Commissioning   |    |      |   |   |
| 139 | Allow for the Testing and Commissioning the whole of all of the Laundry Equipment as laid down in the specification and for re-testing as maybe required after making good of all defective work to the satisfaction of the Principal Agent |    | Item |   |   |
|     | Certificate for Compliance  |    |      |   |   |
| 140 | Allow for the issuing of a Certificate of Compliance in line with the standard regulations applying at the time   |    | Item |   |   |
|     | <u>Training</u>   |    |      |   |   |
| 141 | Allow for the training of the Employer's operators to enable them to be responsible for and capable of operating the plant  |    | Item |   |   |
|     | Operating Manuals   |    |      |   |   |
| 142 | Allow for three complete sets of indexed loose leaf operating instructions and maintenance manuals  |    | Item |   |   |
|     | FIRE SUPPRESSION  |    |      |   |   |
|     | AUTOMATIC FIRE SUPPRESSION SYSTEM   |    |      |   |   |
|     | Supply, delivery & installation to be in accordance with SANS 14520 and/or SANS 306 & SANS 10400.   |    |      |   |   |
| 143 | TC 3001 Fire Panel with gas control EN54  | No | 1    |   |   |
| 144 | Smoke detectors and surface mount bases   | No | 4    |   |   |
| 145 | Sirens with LED flashing beacons for discharge warning  | No | 2    |   |   |
| 146 | Fire Bells for Alarm warning  | No | 2    |   |   |
|     |   |    |      |   |   |
|     | Carried Forward Bill No. 15   |    |      | R |   |
|     | Mechanical Works  |    |      |   |   |
|     | 160   |    |      |   |   |

R. show

## Ikageng New Police Station Portion 4 of ERF 6934 Ikageng Ext. 4

|             | Brought Forward   | d  |      | R |
|-------------|---|----|------|---|
| 147         | Gas relay Interface for activation of the suppressant cylinder  | No | 1    |   |
| 148         | Power supply and batteries for Suppression control  | No | 1    |   |
| 149         | 25LT cylinder with bracket and FM200  | No | 2    |   |
| 150         | Courier/freight costs   | No | 1    |   |
| 151         | Schedule 40 ASTM 106 Grade B to manufacturers specification and Industry standards, supply 3000lb fittings for piping |    | Item |   |
| 152         | Supply PH 30 1mm 2 cr Fire resistant cable  |    | Item |   |
| 153         | Training and handover   |    | Item |   |
| 154         | Provide certification and documentation   |    | Item |   |
|             | FIRE DETECTION SYSTEM   |    |      |   |
|             | Supply, delivery & installation to be in accordance with SANS 10139 & SANS 10400.                                     |    |      |   |
| 155         | Fire retardant cable Class A wiring (ph 120)  | m  | 200  |   |
| 156         | 25mm PVC conduit in accordance with SANS 10139  | m  | 200  |   |
| 157         | Base sounder and strobe combination   | No | 14   |   |
| 158         | Manual call point   | No | 14   |   |
| 159         | Sundries  |    | Item |   |
| 160         | Commissioning, Testing and Provision of new COC for fire detection system   |    | Item |   |
| <b>1</b> 61 | Health and safety file  |    | Item |   |
| 162         | Preparation of Shop drawings for Engineers approval by SAQCC Qualified designer                                       |    | ltem |   |
| 163         | Handover files (2x hard copies and 1x soft copy)  |    | ltem |   |
| 164         | Quarterly service   | No | 4    |   |
|             | Carried Forward Bill No. 15 Mechanical Works  |    |      | R |
| - 1         |   | ļ  | 1    |   |

-161-

R. Arr

|     |                                  | Brought Forward      |    |      | F | 3 | į   |
|-----|----------------------------------|----------------------|----|------|---|---|-----|
| 165 | End-user training                |                      |    | ltem |   |   |     |
|     |                                  |                      |    |      |   |   |     |
|     |                                  |                      |    |      |   |   |     |
|     |                                  |                      |    |      |   |   |     |
|     |                                  |                      |    |      |   |   |     |
|     |                                  |                      |    |      |   |   |     |
|     |                                  |                      |    |      |   |   |     |
|     |                                  |                      |    |      |   |   |     |
|     |                                  |                      |    |      |   |   |     |
|     |                                  |                      |    |      |   |   |     |
|     |                                  |                      |    |      |   |   |     |
|     |                                  |                      |    |      |   |   |     |
|     |                                  |                      |    |      |   |   |     |
|     |                                  |                      |    |      |   |   |     |
|     |                                  |                      |    |      |   |   |     |
|     |                                  |                      |    |      |   |   |     |
|     |                                  |                      |    |      |   |   |     |
|     |                                  |                      |    |      |   |   |     |
|     |                                  | Carried to Summary   |    |      | R |   | -   |
| E   | Bill No. 15<br>/lechanical Works | outlied to outlining |    |      | " |   | -   |
|     |                                  |                      |    |      |   |   |     |
|     |                                  | -162-                | R. | 1    | W |   |     |
|     |                                  |                      |    | 07   |   |   | 242 |

| tem<br>No |   | Unit | Quantity | Rate | Amount |
|-----------|---|------|----------|------|--------|
|           | BILL NO. 16   |      |          |      |        |
|           | GLAZING   |      |          |      |        |
|           | (CPAP WORK GROUP NO. 150 UNLESS OTHERWISE STATED)   |      |          |      |        |
|           | PREAMBLES   |      |          |      |        |
|           | The descriptions given in the various items below are not necessarily full and complete and reference must be made to the "General Preambles for Trades 2017" as published by the Association of South African Quantity Surveyors", and Supplementary Preambles for further description and amplification of work in this section |      |          |      |        |
|           | MIRRORS   |      |          |      |        |
|           | 6mm Silvered float glass copper backed mirrors with polished edges, holed for and fixed with chromium plated dome capped mirror screws with rubber buffers to plugs in brickwork or concrete  |      |          |      |        |
| 1         | 450 x 450 x 6mm Silvered float glass copper backed mirror with 10mm bevelled and polished edges, holed for and fixed with four number chromium plated domed capped mirror screws with rubber buffers to plugs in brickwork or concrete.   | No   | 24       |      |        |
|           |   |      |          |      |        |
|           |   |      |          |      |        |
|           |   |      |          |      |        |
|           |   |      |          |      |        |
|           |   |      |          |      |        |
|           |   |      |          |      |        |
|           |   |      |          |      |        |
|           |   |      |          |      |        |
|           |   |      |          |      |        |
|           | Bill No. 16 Glazing   |      |          | R    |        |
|           | -163-   |      |          |      |        |

| Item<br>No |   | Unit | Quantity | Rate | Amount |
|------------|---|------|----------|------|--------|
|            | BILL NO. 17   |      |          |      |        |
|            | PAINTWORK   |      |          |      |        |
|            | (CPAP WORK GROUP NO. 152 UNLESS<br>OTHERWISE STATED)  |      |          |      |        |
|            | PREAMBLES   |      |          |      |        |
|            | The descriptions given in the various items below are not necessarily full and complete and reference must be made to the "General Preambles for Trades 2017" as published by the Association of South African Quantity Surveyors", and Supplementary Preambles for further description and amplification of work in this section |      |          |      |        |
|            | PAINT SPECIFICATIONS  |      |          |      |        |
|            | Painting, etc.  |      |          |      |        |
|            | All painting shall be done in accordance with SANS specifications unless otherwise described  |      |          |      |        |
|            | COLOURS   |      |          |      |        |
|            | Colours, etc.   |      |          |      |        |
|            | Unless otherwise described all paintwork shall be deemed to have a colour value in excess of 7 on the Munsell system in accordance with SANS 1091   |      |          |      |        |
|            | PAINTWORK, ETC. TO NEW SURFACES   |      |          |      |        |
|            | ON INTERNAL FLOATED PLASTER SURFACES  |      |          |      |        |
|            | One coat plaster primer and two coats of arylic matt paint to SANS 1586. Colour to Principal Agent's approval   | ×    |          |      |        |
| 1          | On walls (LI)   | m2   | 6 139    |      |        |
| 2          | On beams (LI)   | m2   | 55       |      |        |
| 3          | On soffits (LI)   | m2   | 618      |      |        |
|            |   |      |          |      |        |
|            | Carried Forward Bill No. 17 Paintwork   |      |          | R    |        |
|            | r all two it  |      |          |      |        |
| 1          | -164-   |      |          |      | . ^    |

R.

|    | Brought Forward  | 4  |     | F | ₹ |
|----|--|----|-----|---|---|
| 4  | On narrow widths (LI)  | m2 | 409 |   |   |
|    | ON EXTERNAL FLOATED PLASTER SURFACES   |    |     |   |   |
|    | One coat plaster primer and two coats "Micatex" emulsion paint for exterior use  |    |     |   |   |
| 5  | On beams (LI)  | m2 | 55  |   |   |
|    | ON FIBRE-CEMENT BOARD SURFACES   |    |     |   |   |
|    | One universal undercoat and two coats Eggshell enamel, colour to Principal Agent's approval  |    |     |   |   |
| 6  | On fascia boards (LI)  | m2 | 657 |   |   |
|    | ON METAL SURFACES  |    |     |   |   |
|    | Prepare and apply one coat of zinc chromate primer one coat universal undercoat and two coats of universal SABS approved gloss enamel paint.  Colour to Principal Agent's approval |    |     |   |   |
| 7  | On steel gates (LI)  | m2 | 38  |   |   |
| 8  | On steel doors (LI)  | m2 | 51  |   |   |
| 9  | On steel door frames (Li)  | m2 | 971 |   |   |
| 10 | On steel window frames (LI)  | m2 | 74  |   |   |
| 11 | On balustrades (LI)  | m2 | 246 |   |   |
| 12 | On handrails (LI)  | m  | 14  |   |   |
|    | ON WOOD SURFACES   |    |     |   |   |
|    | One coat wood primer, one coat universal undercoat and two coats Silthane Silk. Colour to Principal Agent's approval   |    |     |   |   |
| 13 | On doors (LI)  | m2 | 353 |   |   |
|    | Lightly sand down in the direction of the grain.  Apply 2 coats matt varnish to all exposed sides.  Colour to Principal Agent's approval   |    |     |   |   |
| 14 | On doors (LI)  | m2 | 154 |   |   |
|    | Carried Forward Bill No. 17 Paintwork  |    |     | R |   |

-165-

R.

of for

## **Ikageng New Police Station** Portion 4 of ERF 6934 lkageng Ext. 4

| One coat alkyd based primer and two coats professional gloss enamel paint. Colour to Principal Agent's approval  15 On skirtings, rails, etc not exceeding 300mm girth (LI) m 15  Two coats of carbolinium  16 On exposed timber trusses (LI) m2 730  ON PLASTERBOARD SURFACES  Prepare surfaces and remove all loose material, apply one coat gypsum primer (PP700) and two coats professional super matt (PEM 990/TSA) for interior use to Principal Agent's approval  17 On ceilings including priming metal cover strips and nail heads (LI) m2 35  18 On dry walls (LI) m2 2 541 |
|---|
| Two coats of carbolinium  16 On exposed timber trusses (LI) m2 730  ON PLASTERBOARD SURFACES  Prepare surfaces and remove all loose material, apply one coat gypsum primer (PP700) and two coats professional super matt (PEM 900/TSA) for interior use to Principal Agent's approval  17 On ceilings including priming metal cover strips and nail heads (LI) m2 35  |
| On exposed timber trusses (LI)  ON PLASTERBOARD SURFACES  Prepare surfaces and remove all loose material, apply one coat gypsum primer (PP700) and two coats professional super matt (PEM 900/TSA) for interior use to Principal Agent's approval  On ceilings including priming metal cover strips and nail heads (LI)  m2  730  m2  730  m3   |
| ON PLASTERBOARD SURFACES  Prepare surfaces and remove all loose material, apply one coat gypsum primer (PP700) and two coats professional super matt (PEM 900/TSA) for interior use to Principal Agent's approval  On ceilings including priming metal cover strips and nail heads (LI)  m2  35   |
| Prepare surfaces and remove all loose material, apply one coat gypsum primer (PP700) and two coats professional super matt (PEM 900/TSA) for interior use to Principal Agent's approval  On ceilings including priming metal cover strips and nail heads (LI)  m2  35   |
| apply one coat gypsum primer (PP700) and two coats professional super matt (PEM 900/TSA) for interior use to Principal Agent's approval  On ceilings including priming metal cover strips and nail heads (LI)  m2  35   |
| heads (LÍ) m2 35  |
| 18 On dry walls (LI) m2 2 541   |
|   |
|   |
| Carried to Summary R Bill No. 17 Paintwork  |

-166-

R. of her

| Item<br>No |   | Unit | Quantity | Rate | Amount |
|------------|---|------|----------|------|--------|
|            | BILL NO. 18   |      |          |      |        |
|            | EXTERNAL WORKS (ALL TRADES)   |      |          |      |        |
|            | PREAMBLES   |      |          |      |        |
|            | The descriptions given in the various items below are not necessarily full and complete and reference must be made to the "General Preambles for Trades 2017" as published by the Association of South African Quantity Surveyors", and Supplementary Preambles for further description and amplification of work in this section |      |          |      |        |
|            | SITE CLEARANCE  |      |          |      |        |
|            | (CPAP WORK GROUP NO. 146 UNLESS<br>OTHERWISE STATED)  |      |          |      |        |
| 1          | Allow for clearing the area of the site to be built upon of all grass, weeds, shrubs, trees with trunks not exceeding 200mm girth, debris, etc., including grubbing up all roots, scoffling up as required and cart away all vegetation and debris.   | m2   | 12 100   |      |        |
|            |   |      |          |      |        |
|            |   |      |          |      |        |
|            |   |      |          |      |        |
|            |   |      |          |      |        |
|            |   |      |          |      |        |
|            |   |      |          |      |        |
|            | Carried Forward Bill No. 18 External Works  |      |          | R    |        |
|            | -167-   | J    | I.       |      |        |

-167-

R.

ay N

| Brought Forwa   | rd |        |   | R   |  |
|---|----|--------|---|---|--|
| BULK EXCAVATION, FILLING, ETC.  |    |        |   |   |  |
| Bulk earthworks quantities are based on the final levels required. Rates are deemed to include for sequencing o work if required, temporary ramps, double handling etc, deemed necessary during the construction period.                        | f  |        |   |   |  |
| Backfilling to platforms, embankments, etc. using in-situ material or imported fill from commercial sources, must be evenly spread, graded and mechanically compacted in layers not exceeding 200mm thick to a 95% Mod. AASHTO maximum density. |    |        |   |   |  |
| The contractor shall make his own arrangement for disposal of spoil materials off site and the cost of all royalty and haulage; loading and unloading are to be included in the relevant rate.  |    |        |   |   |  |
| Rates for bulk excavations are deemed to include for risk of collapse/shoring to sides of excavated faces.  |    |        |   |   |  |
| Rates for bulk excavations are deemed to include for any neccessary precautions or varied method of excavation required for excavating along the lateral support structure, existing services, etc.   |    |        |   |   |  |
| Temporary access ramps, forming temporary support banks, etc, as required by the Contractor and the sequencing and staging thereof have not been separately measured and are deemed to be included in the items described hereunder.            |    |        |   |   |  |
| Open face excavation in earth   |    |        |   |   |  |
| Strip average 150mm thick layer of topsoil, stockpile on site and maintain  | m2 | 1 267  |   |   |  |
| Strip average 150mm thick layer of topsoil and cart off site  | m2 | 10 833 |   |   |  |
| Open face excavation over sloping site to reduce levels   | m3 | 3 243  |   |   |  |
| Filling with selected material from the excavations including haulage from within the boundary of the site to form slopes, contours, platforms, etc. compacted to 95% Mod. AASHTO maximum density   | m3 | 2 703  |   |   |  |
| Average 75mm topsoil from stockpiles on site, spread and levelled over site, and abutting kerbs, walls, etc.  | m2 | 2 534  |   |   |  |
| Carried Forward   |    |        | R | Total Control |  |
| Bill No. 18   |    |        |   |   |  |

|    | Brought Forward  |    |      | F | ₹ |
|----|--|----|------|---|---|
| 7  | Allow for all necessary tests by an independent testing authority of compaction and moisture content of compacted earth to ensure that the required compaction are being attained and for submitting results to the Engineer | No | 235  |   |   |
| 8  | Keeping excavations free of all subterranean water by methods to be determined by the contractor   |    | Item |   |   |
|    | Extra over bulk excavation in earth for excavation in:   |    |      |   |   |
| 9  | Intermediate material  | m3 | 230  |   |   |
| 10 | Hard material  | m3 | 173  |   |   |
|    | Extra over all excavations for carting away  |    |      |   |   |
| 11 | Surplus material from excavations and/or stock piles on site, to a dumping site to be located by the contractor  | m3 | 540  |   |   |
|    | Sundries   |    |      |   |   |
| 12 | 1000mm Wide x 500mm high platform drainage berms   | m  | 108  |   |   |
|    | STORMWATER DRAINAGE  |    |      |   |   |
|    | (CPAP WORK GROUP NO. 146 UNLESS<br>OTHERWISE STATED)   |    |      |   |   |
|    | Class 34 heavy duty uPVC pipes laid in class B bedding including all excavation, bedding, backfilling and compaction and disposal of surplus material  |    |      |   |   |
| 13 | 200mm Pipes laid in and trenches not exceeding 1m deep (LI)  | m  | 44   |   |   |
| 14 | 200mm Pipes laid in and including trenches exceeding 1m and not exceeding 2m deep (LI)   | m  | 80   |   |   |
| 15 | 250mm Pipes laid in and including trenches exceeding 1m and not exceeding 2m deep (LI)   | m  | 160  |   |   |
| 16 | 375mm Pipes laid in and including trenches exceeding 1m and not exceeding 2m deep (LI)   | m  | 21   |   |   |
|    | Carried Forward Bill No. 18 External Works   |    |      | R |   |

R

|    | Brought Forward   |    | 1  | R | 1 |
|----|---|----|----|---|---|
|    | Extra over Class 6 Heavy Duty uPVC pipes for fittings   |    |    |   |   |
| 17 | 250mm Bend (LI)   | No | 15 |   |   |
|    | Sumps, catchpits, inspection chambers, etc (gratings and covers elsewhere)  |    |    |   |   |
| 18 | Brick manhole 1380 x 920mm internally and not exceeding 1000mm deep internally comprising suitable 2340 x 1880 x 250mm thick 25MPa/26mm unreinforced concrete base, 230mm brickwork of NFX clay bricks (14 MPa nominal compressive strength) in class I mortar, 1840 x 1380 x 200mm thick 25Mpa/26mm reinforced concrete cover slab with Y10 high tensile steel bars at 150mm centres set in both directions and rebated opening to accommodate cover and frame (cover and frame elsewhere measured) including all excavation, backfilling, formwork etc. all in accordance to Type A, annexured to these Bills of Quantities for the full details, drawing number: TGC/03, (LI)                  | No | 8  |   |   |
| 19 | Brick manhole 1380 x 920mm internally exceeding 1000mm and not exceeding 1250mm deep internally comprising suitable 2340 x 1880 x 250mm thick 25MPa/26mm unreinforced concrete base, 230mm brickwork of NFX clay bricks (14 MPa nominal compressive strength) in class I mortar, 1840 x 1380 x 200mm thick 25Mpa/26mm reinforced concrete cover slab with Y10 high tensile steel bars at 150mm centres set in both directions and rebated opening to accommodate cover and frame (cover and frame elsewhere measured) including all excavation, backfilling, formwork etc. all in accordance to Type A, annexured to these Bills of Quantities for the full details, drawing number: TGC/03. (LI) | No | 2  |   |   |
|    | Carried Forward<br>Bill No. 18<br>External Works  |    |    | R |   |

-170-

R. , [ N 25