

ITEM NO.	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
B		SCHEDULE B: Refurbishment of Existing Combination Sport Court <i>(To be constructed by Specialist Contractor)</i>				
B.1	SANS 1200 C	SITE CLEARANCE				
B.1.1	8.2.1 (LIC)	Clear and grub additional area of proposed combination sport court and 1m beyond on all sides	m ²	192		
B.2	SANS 1200 GA	CONCRETE WORKS				
B.2.1	5.4.10	DEFECTS				
B.2.1.1	(LIC)	Structural repairs to existing combination sport court. Cracks to be repaired by routing and sealing. Suitable approved sealants to be used may include (but not limited to) epoxies or asphaltic materials.	Sum	1		
B.2.2		JOINTS				
B.2.2.1	8.5 (LIC)	Construction of 10mm Contraction Joints (rate to include soft board, sealers as per detail)	m	20		
B.2.2.2	(LIC)	Construction of 10mm Expansion Joints (rate to include soft board, sealers as per detail)	m	200		
B.2.3		CONCRETE FINISHING				
B.2.3.1	5.5.10 (LIC)	Woodfloated finishing to concrete surfaces to a Degree of Accuracy I	m ²	45		
B.2.4		Demolition Works				
B.2.4.1		Demolish surface bed slabs identified on site and dispose	m ³	6,5		
B.2.5		Reinforced Concrete				
B.2.5.1	(LIC)	Cast reinforced concrete surfacebed panels (concrete class: 25/19) (mesh ref 395)	m ³	45		
TOTAL CARRIED FORWARD						

ITEM NO.	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
TOTAL BROUGHT FORWARD						
B.3	(LIC)	COURT SURFACING				
B.3.1		Apply primer coat to existing concrete surface	m ²	660		
B.3.2		Apply multi-layer heavy duty plasticised all Weatherflex fibre to primed concrete surface				
B.3.2.1		Course sand layers	m ²	660		
B.3.2.2		Unpigmented fine silica sand layers	m ²	660		
B.3.2.3		Pigmented fine silica sand layers (colour to client's specification)	m ²	660		
B.3.2.4		Pigmented final surfacing	m ²	660		
B.4	(LIC)	MARKINGS				
B.4.1		Skid texture acrylic paint - in accordance to international standards (100m wide)				
B.4.1.1		Tennis Court - White	m	800		
B.4.1.2		Volley Ball - Blue	m	82		
B.4.1.3		Mini Soccer - Yellow	m	220		
B.4.1.4		Netball - Purple	m	850		
B.4.1.5		Basketball - Red	m	160		
B.5		FENCING				
B.5.1		EARTHWORKS				
B.5.1.1	D 8.3.1.2 (LIC)	Foundation excavation 600 x 600 x 600mm for straight posts	m ³	7,8		
B.5.1.2	D 8.3.2(2)	Extra over item E.2.1 for excavation in hard rock.	m ³	4,000		
B.5.2		FOUNDATIONS				
B.5.2.1	(LIC)	Unreinforced concrete foundations, 600 x 600 x 600mm, 15MPa/19mm concrete, 1500mm C/C.	m ³	7,8		
TOTAL CARRIED FORWARD						

ITEM NO.	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
TOTAL BROUGHT FORWARD						
B.5.3	(LIC)	CHAIN LINK FENCE				
B.5.3.1		Supply and install 2mm diameter galvanised diamond mesh fencing to combination sport courts - nominal height of 3125mm, complete with 100mm dia dished capped posts, anchors, stays, 3mm straining wire, etc. The rate to allow for all earthworks, unreinforced concrete bases associated with the installation	m	110		
B.5.4	(LIC)	DIAMOND MESH GATES				
B.5.4.1		Supply and install diamond mesh gates (single leaf) (900 W x 1800 H)	No.	4		
B.5.5		GOALPOSTS				
B.5.5.1		Supply and deliver goalposts - Tennis	No.	1		
B.5.5.2		Supply and deliver goalposts - Volleyball	No.	1		
B.5.5.3		Supply and deliver goalposts - Minisoccer	No.	1		
B.5.5.4		Supply and deliver goalposts - Netball	No.	1		
B.5.5.5		Supply and deliver goalposts - Basketball	No.	1		
TOTAL CARRIED FORWARD TO SUMMARY						