

## SECTION 1 : 1200

PORT ST JOHNS MUNICIPALITY  
CONTRACT No: PSJLM - MIG - 2023/24 – 04  
LUZUPHU ACCESS ROAD

ITEM NO	PAYMENT	DESCRIPTION	LIC	UNIT	QUANTITY	RATE	AMOUNT
		<b><u>GENERAL REQUIREMENTS AND PRVISIONS</u></b>					
	<b>B12.01</b>	<b>Community Participation</b>					
1.1.1		(a) Payment of expenses/disbursements to the members of the PSC		PC sum	1	35,000.00	35,000.00
1.1.2		(b) Handling costs and profit in respect of sub item B12.01 (a)		%	35,000		
	<b>B12.02</b>	<b>Community Liason Officer (CLO)</b>					
1.1.3		(a) Salary plus expenses incurred by the CLO		Prov sum	1	40,000.00	40,000.00
1.1.4		(b) Security Allowance		Prov sum	1	24,000.00	24,000.00
1.1.5		(c) Handling costs and profit in respect of sub item B12.06 (a)		%	64,000		
	<b>B12.03</b>	<b>Relocation and protecting of Existing services</b>					
1.1.6		(a) Relocation, including lowering or raising, protection and/or repair of existing services as instructed by Engineer		Prov sum	1.00	7,000.00	7,000.00
1.1.7		(b) Contractor's handling costs, profit and all other charges in respects of subitems B12.03(a)		%	7,000		
		(c) Removal and installation of fencing		km	1.00		
	<b>B12.04</b>	<b>Training:</b>					
1.1.8		(a) Structured Training		Prov. Sum	1	R100,000.00	R100,000.00
1.1.9		(b) Non-Structured Training		Prov. Sum	1	R10,000.00	R10,000.00
1.1.10		(c) Contractor's handling costs, profit and all other charges in respects of Subitems B12.04(a) and (b):		%	R110,000.00		
	<b>B12.05</b>	<b>Occupational Health and Safety Requirements</b>					
1.1.11		(a) Preparation of Site Specific OHS plan & file		Sum	1		
1.1.12		(b) Contractor's initial obligations in respect of the OH&S Act and Construction Regulations Government Gazette volume 658 29 April 2020 and. The Department of Employment and Labour Workplace Preparedness: COVID-19 (SARS-CoV-19 virus) document.		Prov.Sum	1	10,000.00	R10,000.00
1.1.13		(c) Contractor's time related obligations in respect OH&S Act and Construction Regulations Government Gazette volume 658 29 April 2020 and. The Department of Employment and Labour Workplace Preparedness: COVID-19 (SARS-CoV-19 virus) document.		month	8		
		(d) Provision of Personal Protective Equipment & Protective clothing					
1.1.14		(i) Reflective vests		No	20		
1.1.15		(ii) Work suits		No	20		
1.1.16		(iii) Hard hats		No	20		
1.1.17		(iv) Protective footwear		No	20		
1.1.18		(v) Earplugs and goggles		No	20		
1.1.19		(vi) Dust masks		No	20		
1.1.20		(vii) Cloth Face Masks for Covid 19(3 person)		No	45		
1.1.21		(viii) Infrared Thermometer(for covid 19 screening)		No	3		
1.1.22		(ix) 70% or more alcoholic sanitiser		No	40		
1.1.23		(e) Provision of full time Construction Health and Safety Officer		Month	7		
1.1.24		(g) Environmental Management Plan Monitoring		Month	0		
1.1.25	B12.06	(a) Allow survey on site as per item B13.0 Prov Sum	<b>1</b>	1	300,000	300,000.00	
		( b) charges in respects of Subitems B12.06(a)	<b>%</b>	300000			
1.1.27	B12.07	(a) Allow for Civil Engineering Trainee Prov Sum	<b>1</b>	1	40,000	40,000.00	
		( b) charges in respects of Subitems B12.07(a)	<b>%</b>	40000			
<b>1200</b>		<b>TOTAL CARRIED FORWARD</b>					

ITEM NO	COLTO	DESCRIPTION	LIC	UNIT	QUANTITY	RATE	AMOUNT
		<u>CONTRACTOR'S ESTABLISHMENT ON SITE</u> <u>AND GENERAL OBLIGATIONS</u>					
	B13.01	The Contractor's general obligations:					
2.1.1		(a) Fixed obligations		lump	1.00		
2.1.2		(b) Value-related obligations		lump	1.00		
2.1.3		(c) Time-related obligations		month	7		
1300		TOTAL CARRIED TO SUMMARY					

**PORT ST JOHNS MUNICIPALITY  
CONTRACT No: PSJLM-MIG-2023/24-04  
LUZUPHU ACCESS ROAD**

[illegible]

PORT ST JOHNS MUNICIPALITY  
CONTRACT No: PSJLM - MIG - 2023/24 – 04  
LUZUPHU ACCESS ROAD

TOTAL BROUGHT FORWARD:							
ITEM No.	PAYMENT	DESCRIPTION	LI	UNIT	QUANTITY	RATE	AMOUNT
	14.04	Car ports					
3.1.18	(a)	Carports as specified, at offices and laboratory buildings		No	1		
	14.05	Services:					
	(a)	Services at offices and laboratories:					
3.1.19	(i)	Fixed costs		lump sum	1		
3.1.20	(ii)	Running costs		month	7		
TOTAL BROUGHT FORWARD:							

ITEM No.	PAYMENT	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	COLTO	ACCOMODATION OF TRAFFIC				
	B15.03	Temporary traffic-control facilities				
4.1.1	LI	(a) Flagmen (including equipment)	man-day	298		
4.1.2		(b) Portable STOP and GO-RY signs	No	4		
4.1.3		(j) Traffic cones (750 mm)	No	12		
CARRIED FORWARD TO SUMMARY :						

## UPGRADING OF THE AGGATE TERRACE ROAD

## SECTION 5: 1600

PORT ST JOHNS MUNICIPALITY  
CONTRACT No: PSJLM-MIG-2023/24-04  
LUZUPHU ACCESS ROAD

ITEM No.	PAYMENT	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
5.1	COLTO 1600	<u>OVERHAUL</u>  Overhaul on material hauled in excess over 1,0 km	m³-km	49,162		
5.1.64	8.3.14	Borrow pits		1	30,000.00	
5.1.65		a) Obtaining of Borrow Pit Provisional Sums	Sums	30,000.00		30,000.00
5.1.66		a) Opening up and closing down of designation borrow pit	Prov. Sum	1	30,000.00	30,000.00
5.1.67		b) Dealing with overburden	m³	70		
5.1.67		c) Rehabilitation of borrow	Sum	1	10,000.00	10,000.00
1600		TOTAL CARRIED TO SUMMARY				

ITEM No.	PAYMENT	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	COLTO					
	1700	CLEARING AND GRUBBING				
6.1.1	17.01	Clearing and grubbing	ha	6.20		
	17.02	Removal and grubbing of large trees and tree stumps:				
6.1.2	(a)	Girth exceeding 1m up to and including 2m	No	0		
6.1.3	(b)	Girth exceeding 2m up to and including 3m	No	0		
CARRIED FORWARD TO SUMMARY :						

PORT ST JOHNS MUNICIPALITY  
CONTRACT No: PSJLM-MIG-2023/24-04  
LUZUPHU ACCESS ROAD

ITEM No.	PAYMENT	DESCRIPTION	LI	UNIT	QUANTITY	RATE	AMOUNT
	COLTO 1900	<b>DAYWORKS (PROVISIONAL)</b>					
	19.01	<b>Personnel during normal working hours</b>					
7.1		(a) Unskilled labour		hr			Rate Only
7.2		(b) Semi-skilled labour		hr			Rate Only
7.3		(c) Skilled labour		hr			Rate Only
7.4		(d) Ganger		hr			Rate Only
7.5		(e) Flagman		hr			Rate Only
7.6		(f) Artisan		hr			Rate Only
	19.02	<b>Plant</b>					
7.7		(a) Flat bed truck (specify size)		hr			Rate Only
7.8		(b) Tipper Trucks - 3 to 5 ton capacity		hr			Rate Only
7.9		(c) Tipper Trucks - more than 5 ton		hr			Rate Only
7.10		(d) Loader (0,5m³) bucket		hr			Rate Only
7.11		(e) Backhoe TLB (digger loader)		hr			Rate Only
7.12		(f) Excavator (20-30 ton)		hr			Rate Only
7.13		(g) Grader (CAT 140 G or similar)		hr			Rate Only
7.14		(h) Compactor (Bomag 90 or similar)		hr			Rate Only
7.15		(i) Water truck (5000 liter)		hr			Rate Only
7.16		(j) Dozer (D7 or similar))		hr			Rate Only
7.17		(k) Mechanical broom		hr			Rate Only
7.18		(l) Tractor-trailor combination (43KW, 3 ton min)		hr			Rate Only
7.19		(m) Suitable truck/bus for transporting labourers (30 people minimum)		hr			Rate Only
7.20		(n) Safety vehicle for pre-marking purposes		hr			Rate Only
TOTAL BROUGHT FORWARD:							



PORT ST JOHNS MUNICIPALITY  
CONTRACT No: PSJLM-MIG-2023/24-04  
LUZUPHU ACCESS ROAD

TOTAL BROUGHT FORWARD:							0.00
ITEM No.	PAYMENT	DESCRIPTION	LI	UNIT	QUANTITY	RATE	AMOUNT
7.21	COLTO 1900	(o) Compressor (air) including hose and tools (specify)		hr			Rate Only
7.22		(p) Dewatering pump including generators and accessories (specify size)		hr			Rate Only
7.23		(q) Mobile electric welding sets and accesories (specify size)		hr			Rate Only
7.24		(r ) Cutting torch with mobile electric & oxy acetylene installation		hr			Rate Only
7.25		(s) Mobile concrete mixers (specify size)		hr			Rate Only
7.26		(t) Light delivery vehicle (LDV)		hr			Rate Only
7.27		(u) Centre-mount crane (specify size)		hr			Rate Only
7.28		(v) Low bed truck (specify size)		hr			Rate Only
7.29		(x) Bomag Roller		hr			Rate Only
7.30		(y) Other (specify)		hr			Rate Only
	19.03	Materials					
7.31		(a) Procurement of materials	ProvSu		1.00	1,000.00	1,000.00
7.32		(b) Contractor's handling costs, profit and all other charges in respect of subitem B19.03(a)	%		1,000		
CARRIED FORWARD TO SUMMARY :							

ITEM No.	PAYMENT	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
8.01	COLTO					
	2100	<u>DRAINS</u>				
	21.01	Excavation for open drains:				
		(a) Excavating soft material situated within the following depth ranges below the surface level:				
		(i) 0 m up to 1,5 m	m³	1,420		
		(ii) Exceeding 1,5m up to 3m	m³	45		
8.02		(b) Extra over subitem 21.01(a) for excavation in hard material, irrespective of depth	m³	0		
2100		CARRIED FORWARD TO SUMMARY :				

ITEM No.	PAYMENT	LI	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	2200		<b>SECTION 2200: PREFABRICATED CULVERTS</b>				
			<b>Excavation:</b>				
9.01	22.01	LI	(a) Excavating in soft material with the following depth ranges below the surface level				
			(i) 0m up to 1,5m	m³	151		
9.02			(ii) Exceeding 1,5m and up to 3m	m³	3		
9.03			(iii) Exceeding 3m and up to 4.5m	m³			
9.04			(b) Extra over subitem B22.01(a) for excavation in hard material, irrespective of depth	m³	0		
	22.02		<b>Backfilling:</b>				
9.05		LI	(a) Using excavated material	m³	16		
9.06		LI	(b) Using imported selected material	m³	12		
			<b>(c ) Concrete pipe culverts (On Class C Bedding)</b>				
9.07			(i) 450 mm dia. Type 50D	m			Rate Only
9.08			(ii) 600 mm dia. Type 50D	m	172.50		
9.09			(iii) 750 mm dia. Type 50D	m			Rate Only
9.10			(iv) 900 mm dia. Type 50D	m	37.50		
	22.03		<b>Removing existing concrete</b>				
9.11			(a) Plain Concrete	m³	0		
9.12			(b) Reinforced Concrete	m³	8		
			Inlet and Outlet Structures, Skewed ends, Catchpits, Manhole, Thrust and Anchor Blocks, excluding formwork, but not including class U2 surface finish				
			a) Catchpits (complete, as per drawing)	No	28		
			b) Headwalls (complete, as per drawing)	No	28		
			(c)Class 25/19MPa concrete	m³	31		
TOTAL BROUGHT FORWARD:							

## SCHEDULE A : ROAD CONSTRUCTION

PORT ST JOHNS MUNICIPALITY  
CONTRACT No: PSJLM - MIG - 2023/24 – 04  
LUZUPHU ACCESS ROAD

TOTAL BROUGHT FORWARD:							
ITEM No.	PAYMENT	LI	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<b>COLTO</b>						
	<b>2200</b>						
	<b>22.04</b>		<b>Removing and stacking existing prefabricated culverts</b>				
9.13			(i) 450mm dia on Bedding C	m	0		
9.14			(ii) 600mm dia on Bedding C	m	0		
	<b>22.05</b>		<b>Manholes, catchpits, precast inlet and outlet structures complete</b>				
			(a) Manholes: (standard depth: 1.2m)				
9.15		LI	(i) 450mm dia. brick manhole: (As detailed on drawing No.	No			
9.16		LI	(iii) 600mm dia. Stock brick manhole:(As detailed on drawing No	No	0		
9.17		LI	(iv) 900mm dia. Stock brick manhole:(As detailed on drawing No	No	0		
			(b) Kerb inlet (standard depth: 1.2m)				
9.18		LI	(i) 450mm dia. kerb inlet (As detailed on drawing No.	No	0		
9.19		LI	(ii) 450mm dia. kerb inlet (Low Point) (As detailed on drawing No	No	0		
9.20		LI	(iii) 600mm dia. kerb inlet (As detailed on drawing No.	No	0		
9.21		LI	(iii) 750mm dia. kerb inlet (As detailed on drawing No.	No	0		
9.22		LI	(iv) 900mm dia. kerb inlet (As detailed on drawing No.				
			(c) Headwalls				
9.23		LI	(i) 450mm dia. (Normal) (As detailed on drawing No.	No	0		
9.24		LI	(ii) 600mm dia. (Single)	No	0		
9.25		LI	(iii) 600mm dia. (double)	No	0		
9.26		LI	(iii) 900mm dia. (Single)	No	0		
9.27			(iv) 900mm dia. (double)	No.	0		
9.28	<b>22.06</b>		<b>Hand excavation to determine the position of existing services</b>	m³	0		
9.29	<b>22/B16.02</b>		<b>Overhaul on material hauled in excess of 1.0km</b>	m³-km	60		
CARRIED FORWARD TO SUMMARY :							

## SECTION 10: 2300

PORT ST JOHNS MUNICIPALITY  
CONTRACT No: PSJLM-MIG-2023/24-04  
LUZUPHU ACCESS ROAD

ITEM No.	PAYMENT	LI	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<b>COLTO 2300</b>		<b>CONCRETE KERBING, CONCRETE CHANNELLING, CHUTES AND DOWNPIPES, AND CONCRETE LININGS FOR OPEN DRAINS</b>				
	<b>23.01</b>		<b>Concrete kerbing</b>				
			(a) Precast mountable kerbing (figure 8) . complete with concrete screed:				
10.01		LI	(i) Radius exceeding 4m up to 20 m	m	0		Rate Only
			(b) Precast concrete barrier kerbing Figure 3 complete with concrete screed:				
10.02		LI	(i) Radius exceeding 4m up to 20 m	m	0		Rate Only
	<b>23.02</b>		<b>Concrete kerbing channelling combination</b>				
			(a) Precast barrier kerbing Figure 3, complete with precast kerbing Figure 14 channel and concrete backing, for 150mm base course and for curvatures indicated:				
10.03		LI	(i) Radius exceeding 4m up to 20 m	m	0		Rate Only
			(b) Precast mountable kerbing Figure 8, complete with precast kerbing Figure 14 channel and concrete backing,				
10.04			(ii) Radius exceeding 4m up to 20 m	m	0		Rate Only
	<b>23.03</b>		<b>Inlet, outlet, transition and similar structures</b>				
10.05		LI	(a) (i) 1m long transition piece and barrier kerbing and mountable kerb and channel as per Drawing No.	No	0		
10.06		LI	(ii) 1m long transition piece between barrier and channel and edge strip as per Drawing No.	No	0		
10.07		LI	(iii) 1m long transition piece between barrier kerbing and edge strip as per Drawing No.	No	0		
	<b>23.04</b>		<b>Trimming of excavations for concrete-lined open drains</b>				
10.08		LI	(a) In soft material	m <sup>2</sup>	0		
<b>TOTAL BROUGHT FORWARD:</b>							

PORT ST JOHNS MUNICIPALITY  
CONTRACT No: PSJLM-MIG-2023/24-04  
LUZUPHU ACCESS ROAD

TOTAL BROUGHT FORWARD:							
ITEM No.	PAYMENT	LI	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
10.09	23.04	LI	(b) In hard material	m²	0		
		23.05	Concrete-lined open drains				
10.10		LI	(a) Cast in situ concrete lining Class 15/19	m³	8		
10.11	23.05	LI	(b) Class U2 surface finish to cast in situ concrete as per Drawing No.	m²	0		
		23.06	Formwork to cast in-situ concrete lining for open drains (class F2 surface finish):				
10.12			(a) To sides with formwork on the internal face only	m²	230		
10.13			(b) To sides with formwork on both internal and external faces (each face measured)	m²			
10.14	23.06		(c ) To ends of slabs	m²	14		
			Sealed joints in concrete lignings of open drains				
10.15	23.07		(a) With Flexcell and polysuphide seal, complete	m	182		
			Steel reinforcement				
10.16			(c ) Welded steel fabric (ref 193)	m²	156		
CARRIED FORWARD TO SUMMARY :							

SECTION 11: 3100

PORT ST JOHNS MUNICIPALITY  
CONTRACT No: PSJLM-MIG-2023/24-04  
LUZUPHU ACCESS ROAD

ITEM No.	PAYMENT	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
		<u>BORROW MATERIALS</u>				
	31.01	Excess overburden	m³	122.00		
	31.03	Finishing-off borrow areas in:				
11.01		(a) Hard material	ha	1.00		
11.02		(b) Intermediate material	ha	1.00		
11.03		(c) Soft material	ha	1.00		
11.04		(d) Stockpiling	m³	1,450.00		
3100	TOTAL CARRIED TO SUMMARY					

## SECTION 12: 3300

PORT ST JOHNS MUNICIPALITY  
CONTRACT No: PSJLM-MIG-2023/24-04  
LUZUPHU ACCESS ROAD

ITEM No.	PAYMENT	LI	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<b>COLTO</b>						
	<b>3300</b>		<b>MASS EARTHWORKS</b>				
	<b>33.01</b>		Cut and borrow to fill, including freehaul up to 1.0km:				
		(a)	Material in compacted layer thickness of 200mm :				
12.01		(ii)	Compacted to 93% of mod AASHTO	m³	670		
		(ii)Cut slopes		m³	4500		
		(iii)Fill slopes		m³	525		
	<b>33.03</b>		<b>Extra over item 33.01 for excavating and breaking down oversize materials in :</b>				
12.02		(a)	Intermedite excavation	m³	60		
12.03		(b)	Hard Excavation	m³	320		
	<b>33.04</b>		<b>Cut to spoil, including freehaul up to 1.0km. Material obtained from:</b>				
12.04		(a)	Soft excavation	m³	120		
12.05		( c)	Hard excavation	m³	20		
	<b>33.07</b>		<b>Removal of unsuitable material (including freehaul of 0.5km):</b>				
		(a)	In layer thickness of 200 mm and less:				
12.06		(i)	Stable material	m³	60		
12.07		(ii)	Unstable material	m³	130		
	<b>33.10</b>		<b>Roadbed preparation and the compactic in layer thickness exceeding 150 mm:</b>				
12.08		(b) (i)	Compaction to 93% of modified AASHTO density	m³	8,820		
<b>3300</b>	<b>TOTAL BROUGHT FORWARD:</b>						



ITEM No.	PAYMENT	LI	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
13.01	COLTO 3400		PAVEMENT LAYERS OF GRAVEL MATERIAL				
	34.01		Pavement layers constructed from gravel obtained from commercial sources:  (a) Gravel selected layer compacted to:  (ii) 95% of modified AASHTO density compacted in 150mm layer thickness (G7)	m³	8,190		
CARRIED FORWARD TO SUMMARY:							

**PORT ST JOHNS MUNICIPALITY**  
**CONTRACT No: PSJLM-MIG-2023/24-04**  
**LUZUPHU ACCESS ROAD**

ITEM No.	PAYMENT	LI	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
12.1.2	COLTO						
			<u>PITCHING, STONEWORK AND PROTECTION</u>				
			<u>AGAINST EROSION</u>				
			Stone pitching:				
			125mm Grouted stone pitching	m²	1240		
			Erosion Protection				
	51.01		Packed stones across drains	m	32		
CARRIED FORWARD TO SUMMARY :							

ITEM No.	PAYMENT	LI	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
12.1.0 12.1.3	COLTO						
		<u>GABIONS</u>					
	52.01	Foundation trench excavation and backfilling:					
	(a)	In solid rock (material which requires bla	m³	1			
	(b)	In all other classes of material	m³	1			
	52.02	Surface preparation for bedding the gabions	m²	16			
	52.03	Gabions:					
	(a)	----- gabion mattresses.	m³	2.00			
		Using aggregate from commercial sources					
		a) 1m x 1m x 2m	m³	4			
		b) 1.5m x 1m x 2m	m³	0			
		c) Reno mattresses (230mm deep)	m³	0			
	Geotextile (U24 bidim)	m²	40				
CARRIED FORWARD TO SUMMARY :							

**PORT ST JOHNS MUNICIPALITY**  
**CONTRACT No: PSJLM-MIG-2023/24-04**  
**LUZUPHU ACCESS ROAD**

[illegible]

ITEM No.	PAYMENT	LI	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
15.1.1	COLTO		<p><u>FINISHING THE ROAD AND ROAD RESERVE</u></p> <p><u>AND TREATING OLD ROADS</u></p> <p>Finishing the road and road reserve:</p> <p>(b) Single-carriageway road</p>	km	7		
CARRIED FORWARD TO SUMMARY :							

ITEM	PAYMENT	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	COLTO 7100	<u>CONCRETE PAVEMENTS</u>				
15.1	71.01	Concrete trial pavement: (a) Manual construction	m²	1.00		
15.2	71.02	Concrete pavement 100mm thick (25MPa) excluding texturing and curing	m³	120		
15.3	71.03	Extra over item 71.02 for concrete pavement requiring hand placing	m²	0		
	71.04	Texturing and curing the concrete pavement:				
15.4		(a) Burlap-dragged and grooved texture	m²	150		
15.5		(b) Curing	m²	110		
	71.06	Joints:				
15.6		(a) Expansion joints complete (excluding dowels)	m	78		
	71.08	Steel reinforcement in concrete pavement:				
15.7		(a) Welded steel fabric ref193	m²	550		
7100		CARRIED FORWARD TO SUMMARY				

ITEM NO		DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
		<u>TESTING MATERIALS AND WORKMANSHIP</u>				
	81.02	Other special tests requested by the Engineer:	Prov. Sum	1.00	30,000.00	30,000.00
15.01		(a) Contractors handling cost on item B81,02 above	%	30000.00		
8100		TOTAL CARRIED TO SUMMARY				

PORT ST JOHNS MUNICIPALITY  
CONTRACT No: PSJLM-MIG-2023/24-04  
LUZUPHU ACCESS ROAD

SUMMARY OF SCHEDULE OF QUANTITIES			
SECTION	SCHEDULE A : ROAD CONSTRUCTION		AMOUNT
1200	GENERAL REQUIREMENTS AND PROVISIONS		
1300	CONTRACTOR'S ESTABLISHMENT ON SITE AND GENERAL OBLIGATIONS		
1400	HOUSING, OFFICES AND LABORATORY		
1500	ACCOMMODATION OF TRAFFIC		
1600	OVERHAUL		
1700	CLEARING AND GRABBING		
1900	DAYWORKS (PROVISIONAL)		
2100	DRAINS		
2200	PREFABRICATED CULVERTS		
2300	CONCRETE KERBING, CONCRETE CHANNELLING, CHUTES AND DOWNPIPES,AND CONCRETE LININGS FOR OPEN DRAINS		
3100	BORROW MATERIALS		
3100	BORROW MATERIALS		
3300	MASS EARTHWORKS		
3400	PAVEMENT LAYERS OF GRAVEL MATERIAL		
5100	PITCHING, STONEMWORK AND PROTECTION		
5200	GABIONS		
5600	ROAD SIGNS		
5900	FINISHING THE ROAD AND ROAD RESERVE		
7100	CONCRETE PAVEMENTS		
8100	TESTING MATERIAL AND WORKMANSHIP		
SUBTOTAL A			
SUBTOTAL B			
VAT (15%)			
TOTAL OF SCHEDULE OF QUANTITIES			