

Item No	Quantity	Rate	Amount
<u>SECTION 1</u>			
<u>BILL No.1</u>			
<u>PRELIMINARIES</u>			
1. The Principal Building Agreement shall be the JBCC Series Edition 4.1, March 2005 as recommended by the Joint Building Contract Committee and as amended by this Tender Enquiry. 2. The Preliminaries shall be JBCC Series 2000, May 2005 for use with the Principal Building Agreement as recommended by the Joint Building Contracts Committee and as amended by this Tender Enquiry shall be deemed to be incorporated herein. 3. Tenderers are referred to the abovementioned documents for the full intent and meaning of each clause thereof. These clauses are hereinafter referred to by clause number and heading only. 4. Where standard clauses or alternatives are not entirely applicable to this contract, such modifications, corrections or additions as are necessary, are given as far as possible under each relevant clause heading. Additional Preliminary clauses are contained in Section C hereof. 5. No claim whatsoever shall be entertained in respect of errors or omissions in pricing due to brevity of descriptions of items which are fully described when read in conjunction with the relevant clauses of the said Principal Building Agreement, Preliminaries and Preambles. 6. The Tenderers shall allow opposite each of the clauses whatever costs and charges he may consider necessary for the carrying out, complying with and due observance of the provisions, conditions and requirements set out herein. Only priced items will be considered in respect of any adjustment of this Section. Any items left unpriced will be understood to be provided free of charge and no claim for any extras arising out of the Tenderer's omission to price any item will be entertained.			
Carried to Collection			
Section 1 Bill No. 1 Preliminaries			R

**COMPLETION OF TEMBILE JUNIOR SECONDARY SCHOOL
THE MVULA TRUST SAFE PROGRAMME**

7. Where modifications or amendments as described are made, such modifications and/or amendments shall supercede any conflicting provisions in the relevant clauses of the Standard Preliminaries or the Principal Building Agreement and the Tenderer shall make due allowance for whatever costs and charges he may consider necessary for the carrying out and observance of the provisions of the clauses as modified and/or amended.

8. Where any item is not relevant to this specific contract, such item is marked N/A.

9. If Alternative A as set out in clause B10.3 hereinafter is to be used for the adjustment of the preliminaries, each item priced is to be allocated to one or more of the three categories by insertion of "F","V","T" as the case may be against the price in the "rate" column immediately preceding the "amount" column, where "F" denotes a fixed amount (amount not to be varied), "V" denotes an amount variable in proportion to value, and "T" denotes an amount proportionate to time.

Carried to Collection

R

Section 1
Bill No. 1
Preliminaries

SECTION A: PRINCIPAL BUILDING AGREEMENT

DEFINITIONS

Definitions and interpretation (Clause 1).

1 F: V: T:

Item

OBJECTIVE AND PREPARATION

Offer, acceptance and performance (Clause 2).

2 F: V: T:

Item

Documents (Clause 3).

Clause 3.1 is deleted and substituted with: 'This tender is for a Government Contract. No Payment Guarantee will be provided.'

Clause 3.3 is deleted and substituted with:

The principal agent shall complete the schedule and arrange for formal signing of the agreement once the priced bill of quantities/lump sum document, security, insurances and waiver of lien, where acceptable, have been provided and effected'.

3 F: V: T:

Item

Design responsibility (Clause 4).

4 F: V: T:

Item

Employer's agents (Clause 5).

5 F: V: T:

Item

Site representative (Clause 6).

6 F: V: T:

Item

Compliance with regulations (Clause 7).

7 F: V: T:

Item

Carried to Collection

R

Section 1
Bill No. 1
Preliminaries

**COMPLETION OF TEMBILE JUNIOR SECONDARY SCHOOL
THE MVULA TRUST SAFE PROGRAMME**

	Works risk (Clause 8)			
8	F: V: T: Indemnities (Clause 9). Clause 9.1.1 is deleted and substituted with: Claims from other parties consequent upon death of bodily injury or illness of any person or physical loss or damage to any property, other than the works, arising out or due to the execution of the works or occupation of the site by the contractor or his sub contractors'.	Item		
9	F: V: T: Works insurances (Clause 10).	Item		
10	F: V: T: Liability insurances (Clause 11).	Item		
11	F: V: T: Effecting insurances (Clause 12).	Item		
12	F: V: T: State Provisions (Clause 13).	Item		
13	F: V: T: Security (Clause 14).	Item		
14	F: V: T: <u>EXECUTION</u> Preparation for and execution of the works (Clause 15).	Item		
15	F: V: T: Access to the works (Clause 16).	Item		
16	F: V: T: Contract instructions (Clause 17).	Item		
Carried to Collection			R	
Section 1 Bill No. 1 Preliminaries				

**COMPLETION OF TEMBILE JUNIOR SECONDARY SCHOOL
THE MVULA TRUST SAFE PROGRAMME**

17	F: V: T: Setting out of the works (Clause 18.3). The contractor shall notify the principal agent if any encroachments of adjoining foundations, buildings, structures, pavements, boundaries, etc., exist in order that the necessary arrangements may be made for the rectification of any such encroachments. Should incorrect information be given to the contractor in terms of 18.1 and 18.2, which causes the incorrect setting out of the works, the contractor shall not be liable for such incorrect setting out.	Item		
18	F: V: T: Assignment (Clause 19).	Item		
19	F: V: T: Nominated subcontractors (Clause 20).	Item		
20	F: V: T: Selected subcontractors (Clause 21).	Item		
21	F: V: T: Employer's Direct contractors (Clause 22).	Item		
22	F: V: T: Contractor's Domestic subcontractors (Clause 23).	Item		
23	F: V: T: <u>COMPLETION</u> Practical completion (Clause 24).	Item		
24	F: V: T: Works completion (Clause 25).	Item		
25	F: V: T: Final completion (Clause 26).	Item		
Carried to Collection			R	
Section 1 Bill No. 1 Preliminaries				

**COMPLETION OF TEMBILE JUNIOR SECONDARY SCHOOL
THE MVULA TRUST SAFE PROGRAMME**

Latent defects liability period (Clause 27).

Clause 27.0 is amended by the addition of the following clauses:

"27.3 Any water leakage into the building, whether in the roof, external wall or other element of the building susceptible to water leakage shall, unless proven to be a design defect, or as a result of obvious storm damage, be classified as a latent defect in terms of clause 1.0 Definitions and Interpretations".

"27.4 The Contractor shall attend to defects during the Defects Liability Period on a progressive basis, to the satisfaction of the Principal Agent and will not be permitted to wait until the end of the Defect Liability Period or until the amount of defects accumulates in order to attend to a comprehensive list of defects"

26 F: V: T:

Item

Sectional completion (Clause 28).

27 F: V: T:

Item

Revision of date for practical completion (Clause 29).

28 F: V: T:

Item

Penalty for non-completion (Clause 30).

29 F: V: T:

Item

PAYMENT

Interim payment to the contractor (Clause 31).

The inclusion of materials and goods stored off site in the amount authorised for payment in terms of clause 31.3 shall be at the sole discretion of the principal agent and such inclusion shall only be considered upon the provision, by the contractor, of an approved guarantee issued by a registered commercial bank.

Carried to Collection

R

Section 1
Bill No. 1
Preliminaries

**COMPLETION OF TEMBILE JUNIOR SECONDARY SCHOOL
THE MVULA TRUST SAFE PROGRAMME**

Where prices are submitted by the contractor or nominated/selected sub contractor during the progress of the works in respect of contract instructions or in regard to a claim under the terms of the contract and notwithstanding the fact that such prices may be used in an interim payment certificate, there is to be no presumption of acceptance. Should the principal agent wish to accept any such prices prior to the issue of the final certificate, it will be in writing.

Adjustment to the contract value (Clause 32).

30 F: V: T:

Item

Recovery of expense and loss (Clause 33).

31 F: V: T:

Item

Final account and final payment (Clause 34).

32 F: V: T:

Item

Payment to other parties (Clause 35).

33 F: V: T:

Item

CANCELLATION

Cancellation by Employer - Contractor's default (Clause 36).

34 F: V: T:

Item

Cancellation by Employer - Loss and damage (Clause 37).

35 F: V: T:

Item

Cancellation by Contractor - Employer's default (Clause 38).

36 F: V: T:

Item

Cancellation - Cessation of the works (Clause 39).

37 F: V: T:

Item

Carried to Collection

R

Section 1
Bill No. 1
Preliminaries

DISPUTE

Dispute Settlement (Clause 40)

38 F: V: T:

Item

SUBSTITUTE PROVISIONS

State Clauses (Clause 41)

39 F: V: T:

Item

CONTRACT VARIABLES

The Schedule: Pre-Tender information (Clause 42).

40 F: V: T:

Item

CONTRACTING AND OTHER PARTIES (Clause 42.1)

Employer: The Mvula Trust

Postal Address: 67 Devereux Avenue, Vincent, East
London

Telephone: 043 726 2255

Facsimile: 043 726 5967

Physical address: 67 Devereux Avenue, Vincent, East
London

Principal Agent: The Mvula Trust

Postal Address: 67 Devereux Avenue, Vincent, East
London

Telephone: 043 726 2255

Facsimile: 043 726 5967

Physical address: 67 Devereux Avenue, Vincent, East
London

Carried to Collection

R

Section 1
Bill No. 1
Preliminaries

<u>CONTRACT DETAILS (Clause 42.2)</u> Clause 42.2.1 Works Description: Construction of new ablution facilities. Clause 42.2.2 Site Description: The site is the existing school. Clause 42.2.3 Work or Installations by Others: NIL Clause 42.2.4 This Agreement is for a State Contract :- Yes Payment will be made for materials and goods:- Yes Dispute resolution :- Mediation (in terms of clause 40) followed by litigation. Arbitration rules as recommended by the Association of Arbitrators (SA) :- N/A Clause 42.2.5 Date on which possession of the site is intended to be given on :- To be advised. Clause 42.2.6 Period for the commencement of the works after the contractor takes possession of the site :- 5 Working days. Completion in Sections are required : NO Clause 42.2.7 Intended date of practical completion and the penalty per calendar day for the works as a whole :- To be advised. Carried to Collection Section 1 Bill No. 1 Preliminaries			
---	--	--	--

Penalty amount will be R2 000.00 per calendar day.

Clause 42.2.8

Intended dates of practical completion and the penalties per calendar day for the works in sections :

N/A

Clause 42.2.9

The law applicable to this agreement shall be that of - Republic of South Africa.

INSURANCES (Clause 42.3)

Clause 42.3.1

Contract works insurance to be effected by Contractor for the sum of: Contract Sum plus 10%

With a deductible of : Not exceeding 5% of each and every claim.

Clause 42.3.2

Supplementary insurance is required : Yes

SASRIA insurance required to be effected by the Contractor for the amount of: Contract Sum plus 20% (with a deductible to be determined by the Insurance company issuing the policy).

Clause 42.3.3

Public liability insurance to be effected by Contractor

For the amount of: R 5million

With a deductible of: Not exceeding 5% of each and every claim.

DOCUMENTS (Clause 42.4)

Clause 42.4.1

Waiver of the contractor's lien is required :- YES

Carried to Collection

Section 1
Bill No. 1
Preliminaries

R

Clause 42.4.2	Number of construction document copies to be supplied to the Contractor free of charge :- 1	Clause 42.4.3	Bills of Quantities drawn up in accordance with :-	Standard System of Measuring Building Work - Seventh Edition including all amendments	Clause 42.4.4	Number of days for submission of priced documents : 5 working days from the Letter of Appointment.	Clause 42.4.5	JBCC Engineering General Conditions are to be included in the documents :- No	Clause 42.4.6	The contract value is to be adjusted using CPAP:- NO	<u>SECTION B: PRELIMINARIES</u>	<u>DEFINITIONS AND INTERPRETATION (B1)</u>	Definitions and Interpretation (B1)	F: V: T:	<u>DOCUMENTS (B2)</u>	Checking of documents (B2.1)	Notwithstanding the issue of the tender drawings, it will remain the responsibility of the Tenderer to study all available drawings at the offices of the Principal Agent during normal working hours in order to acquaint himself with all the cost implications of the design, programming, phasing, etc.	F: V: T:	Provisional Bills of Quantities (B2.2) YES	Carried to Collection	Section 1 Bill No. 1 Preliminaries
---------------	---	---------------	--	---	---------------	--	---------------	---	---------------	--	--	---	-------------------------------------	----------------------------	------------------------------	------------------------------	---	----------------------------	--	------------------------------	--

**COMPLETION OF TEMBILE JUNIOR SECONDARY SCHOOL
THE MVULA TRUST SAFE PROGRAMME**

	Prime Cost Amounts, Budgetary Allowances, Provisional Amounts, etc., contained herein may be omitted or reduced at the Principal Agent's sole discretion and the Contractor shall not be entitled to claim for any loss by way of reduction or omission of any discount, or percentage relating to Prime Cost Amounts, Budgetary Allowances, Provisional Amounts, Provisional Quantities, etc., or loss of profit related thereto.			
43	F: V: T: Availability of construction documentation (B2.3)	Item		
44	F: V: T: Interests of Agents (B2.4)	Item		
45	F: V: T: Priced documents (B2.5)	Item		
46	F: V: T: Tender submission (B2.6)	Item		
	Notwithstanding anything contained in this clause, Tenders shall be valid for a period of 20 (Twenty) weeks from the closing date of tenders.			
47	F: V: T: <u>THE SITE (B3)</u> Defined works area (B3.1) The area of the works to be occupied by the contractor, any restriction on the area and the limit of access or exit will be pointed out to the contractor by the principal agent on handing over of the site. Workmen employed on the site are to be restricted to the immediate area of the site and access thereto. The Tenderer shall make all necessary provision in all rates to take into account these requirements as no claims for extras arising from these matters will be subsequently entertained or admitted.	Item		
48	F: V: T:	Item		
	Carried to Collection		R	
	Section 1 Bill No. 1 Preliminaries			

	Geotechnical investigation (B3.2)			
	A desktop geotechnical report is available upon request.			
49	F: V: T:	Item		
	Inspection of the Site (B3.3)			
50	F: V: T:	Item		
	Existing premises occupied (B3.4)			
51	F: V: T:	Item		
	Previous work - dimensional accuracy (B3.5)			
52	F: V: T:	Item		
	Previous work - defects (B3.6)			
53	F: V: T:	Item		
	Services - known (B3.7)			
54	F: V: T:	Item		
	Services - unknown (B3.8)			
55	F: V: T:	Item		
	Protection of trees (B3.9)			
56	F: V: T:	Item		
	Articles of value (B3.10)			
57	F: V: T:	Item		
	Inspection of adjoining properties (B3.11)			
58	F: V: T:	Item		
	<u>MANAGEMENT OF CONTRACT (B4)</u>			
	Management of the Works (B4.1)			
59	F: V: T:	Item		
	Carried to Collection		R	
	Section 1 Bill No. 1 Preliminaries			

COMPLETION OF TEMBILE JUNIOR SECONDARY SCHOOL THE MVULA TRUST SAFE PROGRAMME

	Programme for the Works (B4.2)			
60	F: V: T:	Item		
	Progress meetings (B4.3)			
61	F: V: T:	Item		
	Technical meetings (B4.4)			
62	F: V: T:	Item		
	SAMPLES AND SHOP DRAWINGS (B5)			
	Samples of materials (B5.1)			
63	F: V: T:	Item		
	Workmanship samples (B5.2)			
64	F: V: T:	Item		
	Shop drawings (B5.3)			
65	F: V: T:	Item		
	TEMPORARY WORKS AND PLANT (B6)			
	Deposits and fees (B6.1)			
66	F: V: T:	Item		
	Enclosure of the works (B6.2)			
	The contractor shall erect, maintain and remove at completion, hoardings, safety screens, barriers, access gates, covered gangways and the like as necessary for the enclosure of the works and elements thereof all for the protection of the public and others.			
67	F: V: T:	Item		
	Advertising (B6.3)			
68	F: V: T:	Item		
	Carried to Collection		R	
	Section 1			
	Bill No. 1			
	Preliminaries			

COMPLETION OF TEMBILE JUNIOR SECONDARY SCHOOL THE MVULA TRUST SAFE PROGRAMME

	Plant and equipment (B6.4)			
69	F: V: T: Main notice board (B6.5) One notice board shall be provided by the Contractor	Item		
70	F: V: T: Subcontractors notice board (B6.6) (N/A)	Item		
71	F: V: T: <u>TEMPORARY SERVICES (B7)</u> Location (B7.1)			
72	F: V: T: Water (B7.2) The contractor shall provide water for the works in accordance with: Alternative A (i.e. to be provided for by the Contractor).	Item		
73	F: V: T: Electricity (B7.3) The contractor shall provide electricity for the works in accordance with: Alternative A (i.e. to be provided for by the Contractor).	Item		
74	F: V: T: Telecommunication equipment (B7.4) The contractor shall provide telephones on site for the works in accordance with: Alternative A (i.e. to be provided for by the Contractor).	Item		
75	F: V: T:	Item		
Carried to Collection			R	
Section 1 Bill No. 1 Preliminaries				

COMPLETION OF TEMBILE JUNIOR SECONDARY SCHOOL THE MVULA TRUST SAFE PROGRAMME

	Ablution facilities (B7.5)			
	The contractor shall provide toilet facilities on site for the works in accordance with:			
	Alternative A (i.e. to be provided for by the Contractor).			
76	F: V: T:	Item		
	<u>PRIME COST AMOUNTS (B8)</u>			
	Responsibility for prime cost amounts (B8.1)			
77	F: V: T:	Item		
	<u>ATTENDANCE ON N/S SUBCONTRACTORS (B9)</u>			
	General Attendance (B9.1)			
78	F: V: T:	Item		
	Special Attendance (B9.2)			
79	F: V: T:	Item		
	Commissioning - fuel, water and power (B9.3)			
80	F: V: T:	Item		
	<u>FINANCIAL ASPECTS (B10)</u>			
	Statutory taxes, duties and levies (B10.1)			
	Provision is made in the Final Summary of these Bills of Quantities for the inclusion of Value Added Tax (VAT).			
81	F: V: T:	Item		
	Payment of Preliminaries (B10.2)			
82	F: V: T:	Item		
	Adjustment of Preliminaries (B10.3)			
83	F: V: T:	Item		
	Payment certificate cash flow (B10.4)			
	Carried to Collection		R	
	Section 1			
	Bill No. 1			
	Preliminaries			

**COMPLETION OF TEMBILE JUNIOR SECONDARY SCHOOL
THE MVULA TRUST SAFE PROGRAMME**

84	F: V: T: Contractor information supply (B10.5)	Item		
85	F: V: T: <u>GENERAL (B11)</u> Protection of the Works (B11.1)	Item		
86	F: V: T: Protection/isolation of existing/sectionally occupied works (B11.2)	Item		
87	F: V: T: Site security (B11.3)	Item		
88	F: V: T: Notice before covering work (B11.4)	Item		
89	F: V: T: Disturbance (B11.5)	Item		
90	F: V: T: Works cleaning and clearing (B11.6)	Item		
91	F: V: T: Vermin (B11.7)	Item		
92	F: V: T: Overhand work (B11.8)	Item		
93	F: V: T:	Item		
Section 1 Bill No. 1 Preliminaries		Carried to Collection		R

SECTION C: SPECIFIC PRELIMINARIES

Section C: Specific Preliminaries:

C1. Proprietary branded products

The contractor shall take delivery of, handle, store, use, apply and/or fix all proprietary branded products in strict accordance with the manufacturer's instructions after consultation with the manufacturer's authorised representative.

94 F: V: T:

Item

C2. Trade Names, etc.

All materials, fittings, finishings, etc., specified hereinafter under a trade name, catalogue number or reference, must be exactly as described. The Architect's approval in writing must be obtained for the use of any alternative to the specification before the submission of tenders otherwise the specified materials, fittings, finishings, etc., will be assumed to have been allowed for in the tender.

The Contractor must take delivery of, handle, store, use, apply and/or fix all proprietary branded products in strict accordance with the manufacturer's instructions after consultation with the manufacturer's authorised representative.

95 F: V: T:

Item

C3. Contractors responsibility

The Employer, the Principal Agent and the other professional consultants shall not be responsible for any act or omission on the part of the Contractor which may result in any patent or latent defects, in materials or workmanship, breach or neglect of any local regulations. The Contractor shall at all times be responsible for any such neglect, deviation or wrong act, whether the same is discovered before or after the final certificate, or any other Certificate, has been approved.

96 F: V: T:

Item

C4. Overtime

Carried to Collection

R

Section 1
Bill No. 1
Preliminaries

COMPLETION OF TEMBILE JUNIOR SECONDARY SCHOOL THE MVULA TRUST SAFE PROGRAMME

	Should overtime be required to be worked for any reason whatsoever, the costs of such overtime are to be borne by the contractor unless the principal agent has specifically authorised in writing, prior to the execution thereof, that costs for such overtime are to be borne by the employer.		
97	F: V: T: C5. As built drawings The position of construction breaks and the extent of individual concrete pours are to be recorded by the contractor on the structural engineer's drawings and are to be submitted to the principal agent and the structural engineer for their records. Three full sets of as-built drawings shall be submitted to the Principal Agent no later than fourteen days after practical completion.	Item	
98	F: V: T: C6. Construction Instructions Contract instructions issued on site are to be recorded in triplicate in a site instruction book which is to be maintained on site by the Contractor. The Contractor shall supply and have available at the site of the works at all times, the following site books: a) Construction Instruction Book: Receiving and recording instructions in a suitable A4 size triplicate book kept on site. Instructions issued shall be recorded by the Architect or other Employer's Agents to whom the Architect has delegated authority to in the book. Only instructions issued in such book shall be recognised. b) Daily Record Book:	Item	
	Carried to Collection Section 1 Bill No. 1 Preliminaries		R

**COMPLETION OF TEMBILE JUNIOR SECONDARY SCHOOL
THE MVULA TRUST SAFE PROGRAMME**

	The Contractor shall record in triplicate in a suitable A4 size triplicate book kept at the site, a daily record of work done, all site visits by the Principal Agent and other professional personnel and all events affecting the Works, such as progress, issue of plans, breakdown of machinery, etc. The labour, plant and material on site shall be recorded as well as work performed. Entries must be made by the Contractor and must be signed and forwarded to the Principal Agent for his counter-signature on a daily basis. Copies of these records shall be for the Architect, Quantity Surveyor and Contractor.			
99	F: V: T: C7. Labour record At the end of each week the contractor shall provide the principal agent with a written record, in schedule form, reflecting the number and description of tradesmen and labourers employed by him and all subcontractors on the works each day.	Item		
100	F: V: T: C8. Plant record At the end of each week the contractor shall provide the principal agent with a written record, in schedule form, reflecting the number, type and capacity of all plant, excluding hand tools, currently used on the works.	Item		
101	F: V: T: C9. Encroachment During the course of the building operations, the Contractor shall be held entirely responsible for any encroachment onto any adjoining properties, buildings, etc., or servitudes and the cost of any remedial measures as required by the Principal Agent shall be borne by the Contractor.	Item		
102	F: V: T: C10. Method Statement	Item		
Carried to Collection			R	
Section 1 Bill No. 1 Preliminaries				

**COMPLETION OF TEMBILE JUNIOR SECONDARY SCHOOL
THE MVULA TRUST SAFE PROGRAMME**

	The Tenderer shall produce, when required to do so by the Principal Agent, a Method Statement outlining the methods of construction and labour and plant resources that he proposes to use in the execution of the Works. Any approval given or observation made by the Principal Agent shall not relieve the Contractor of his sole responsibility to adopt the methods of construction and to provide the labour and plant resources necessary for the due and proper timeous execution of the Works.			
103	F: V: T: C11. Unauthorised Persons/Workmen on Premises The Contractor shall at all times strictly exclude all unauthorised persons from the Works and the site and shall set up notice boards to that effect. No workmen or labourers (except security guards) are to be allowed under any circumstances to sleep or deposit any kit on the premises. The Contractor must provide any necessary independent shelter or shed required for any labour or watchmen on site, to the approval of the Employer.	Item		
104	F: V: T: C12. Mode of Procedure Notwithstanding anything to the contrary contained herein the Principal Agent at all times reserves the right to direct the order in which the various parts of the Contract are to be executed. The Contractor shall give priority to any individual section or portion of the Works that, in the opinion of the Principal Agent, requires to be expedited. Should it appear, in the Principal Agent's opinion, that work in any area is not being executed in accordance with the requirements of the Contract Programme, the Contractor shall provide additional manpower and resources and shall work additional overtime and do everything else required to bring the work back to programme to the satisfaction of the Principal Agent and to the Contractor's cost.	Item		
105	F: V: T:	Item		
Carried to Collection			R	
Section 1 Bill No. 1 Preliminaries				

**COMPLETION OF TEMBILE JUNIOR SECONDARY SCHOOL
THE MVULA TRUST SAFE PROGRAMME**

	C13. Location of Temporary Buildings and Temporary Services The Contractor shall provide all necessary temporary works, including temporary roads, tracks, crossings, hardstanding and services, hoardings, dust screens, tunnelling, etc., required for his own and sub-contractors use during the construction and maintenance period. There is no guarantee given or implied that Site conditions will be such that the Contractor will be able to erect such temporary works, roads, hardhats, offices, stores and temporary accommodation within the site boundaries and it shall be the Contractor's responsibility to adopt whatever measures he deems necessary in this regard and to obtain all necessary permission and pay all costs in connection therewith.			
106	F: V: T: <u>C14. Office accommodation</u> The contractor shall provide, maintain and remove on practical completion air conditioned office accommodation with suitable tables and chairs for meetings to be held on the site. Such offices shall be kept clean and fit for use at all times [12.2.18]	Item		
107	F: V: T: <u>C15. Storage Facilities</u>	Item		
108	The Contractor shall provide a Container for storage of materials.	Item		
109	F: V: T: C16. Removal and Making Good of Temporary Works, etc, on Completion The Contractor shall remove (except where specifically stated otherwise) all temporary works, roads, services and the like used for this contract and shall make good to the entire satisfaction of the Principal Agent any damage resulting therefrom.	Item		
110	F: V: T:	Item		
Carried to Collection			R	
Section 1 Bill No. 1 Preliminaries				

COMPLETION OF TEMBILE JUNIOR SECONDARY SCHOOL THE MVULA TRUST SAFE PROGRAMME

[illegible]

COMPLETION OF TEMBILE JUNIOR SECONDARY SCHOOL
THE MVULA TRUST SAFE PROGRAMME

Section 1

Bill No. 1

Preliminaries

COLLECTION

Total Brought Forward from Page No.

**Page
No**

Amount

1

2

3

4

5

6

7

8

9

10

11

12

13

14

15

16

17

18

19

20

21

Carried Forward

R

Section 1

Bill No. 1

Preliminaries

[illegible]

OCCUPATIONAL HEALTH AND SAFETY

General:

- 1 The Contractor shall allow for all costs associated with compliance with the Occupational Health and Safety Act (Act 85 of 1993), the Construction Regulations, 2014, and all other applicable statutory requirements, including but not limited to the preparation, implementation, and maintenance of a project-specific Health and Safety Plan; appointment of a competent Health and Safety Officer for the full duration of the project; provision of personal protective equipment (PPE) to all site personnel; conducting of baseline, periodic, and exit medical examinations; safety induction and training of all employees and visitors; preparation and submission of a compliant Health and Safety File at project close-out; and the establishment and maintenance of adequate site safety measures such as temporary fencing, signage, and first-aid facilities. The Contractor is to make provision for all obligations of the Principal Contractor as defined in the Construction Regulations, as well as for the employment and facilitation of a Community Liaison Officer (CLO), ensuring compliance with community participation requirements. All costs for compliance with the above, including risk assessments, safety audits, statutory appointments, reporting, and incident management, shall be deemed to be included in this item, and no additional claims will be entertained.

Item

Carried to Collection

R

Section 1
Bill No. 2
Health and Safety

COMPLETION OF TEMBILE JUNIOR SECONDARY SCHOOL
THE MVULA TRUST SAFE PROGRAMME

Section 1

Bill No. 2

Health and Safety

COLLECTION

Total Brought Forward from Page No.

**Page
No**

26

27

Amount

Carried Forward to Summary of Section No. 1

Section 1

Bill No. 2

Health and Safety

R

**COMPLETION OF TEMBILE JUNIOR SECONDARY SCHOOL
THE MVULA TRUST SAFE PROGRAMME**

[illegible]

Removal of asbestos material

All preparatory work, alterations, etc., to existing asbestos cement roof sheeting, gutters, rainwater pipes, etc., is to be carried out strictly by an approved and certified specialist company and in accordance with statutory requirements (Occupational Health and Safety Act, 1993 - Asbestos Regulations 2001) and all necessary precautions must be taken when working with and disposing of asbestos cement products and the disposal of waste water resulting from cleaning operations, etc.

The following shall apply in respect of asbestos removal

The removal of asbestos shall be carried out by a certified entity, registered in accordance with the Occupational Health and Safety Act, 1993 and the Asbestos Regulations 2001

Asbestos in all forms/building elements that is to be removed, shall be carried out in strict accordance with aforementioned regulation and a certificate issued by the entity as contemplated in the above, shall be provided per block for the removal thereof, where the term block shall in this context refer to any single, free standing building structure, regardless of size or purpose

Corresponding disposal certificates shall be issued by the facility at which the asbestos is disposed off, with said facility to, prior to the disposal of any asbestos material provide satisfactory proof that the facility is duly registered and fully compliant in terms of the act, to receive the asbestos material

Under no circumstances is the Contractor nor any of his duly authorised representatives to sell and/or give away asbestos material to any member/s of the school community, the community in general or the public at large. Should this be found to be occurring, the Contractor will be held responsible contractually and may further be prosecuted criminally

The cost for complying with the above, and all requirements of regulation as reflected above is to be priced for in terms for removal of asbestos material. No further claims in this regard will therefore be entertained

Carried to Collection

Section 2
Bill No. 1
Demolitions

R

**COMPLETION OF TEMBILE JUNIOR SECONDARY SCHOOL
THE MVULA TRUST SAFE PROGRAMME**

<u>REMOVAL OF EXISTING WORK</u>					
<u>Breaking up and removing unreinforced concrete</u>					
1	100mm Thick surface beds.	m2	4		
2	100mm Thick concrete channels.	m	10		
<u>Lift Paving and set aside for later re-use</u>					
3	Carefully take out paving, set aside for later re-use, compact disturbed areas, provide required materials, sand and re-lay paving to match existing level.	m2	2		
<u>Hacking up/off and removing granolithic, screeds, plaster, etc from concrete or brickwork and preparing surfaces for new screed, plaster, tile finishes, etc</u>					
4	40mm Granolithic from floors.	m2	44		
<u>DEMOLISHING AND REMOVING</u>					
5	All rubble from the demolished ablution areas shall be raked and cleared, after which the area shall be compacted to provide a stable surface. A 300mm layer of topsoil shall then be placed and properly leveled to make good and match the surrounding ground levels. All rubble resulting from the demolitions shall be carted away and disposed of at an approved off-site location. This is for demolished ablutions roughly 8m x 8m each for 2 building areas.			Item	
6	Backfill existing hole with G7 fill material in max. 150mm layers and compact to 95% MOD AASHTO density.	m3	10		
<u>Earth filling obtained from the excavations and / or prescribed stock piles on site (topsoil material) slightly compacted:</u>					
7	Over site and rehabilitation to demolished areas.	m3	10		
Carried to Collection				R	
Section 2					
Bill No. 1					
Demolitions					

COMPLETION OF TEMBILE JUNIOR SECONDARY SCHOOL
THE MVULA TRUST SAFE PROGRAMME

Section 2

Bill No. 1

Demolitions

COLLECTION

Total Brought Forward from Page No.

**Page
No**

Amount

30

31

32

Carried to Final Summary

R

Section 2
Bill No. 1
Demolitions

**COMPLETION OF TEMBILE JUNIOR SECONDARY SCHOOL
THE MVULA TRUST SAFE PROGRAMME**

SIGN PLATES:

**All sign plates are to be with engraved blue perspex
all in accordance with the standard sign plates for
Schools.**

1	Sign plate plugged and screwed to walls with chromium plated dome headed screws.	No	10		
	A0 : 2 A1 : 2 A2 : 3 A3 : 3				

SUNDRIES

Satin Grey Plastics or equal approved

2	"Satin plastic N-SBIN-12-SA SHE Bin size 463 x 140 x 480mm, floor standing loose.	No	8		
	A0 : 2 A1 : 2 A2 : 2 A3 : 2				

Carried to Collection

R

Section 3
Bill No. 1
Ironmongery

COMPLETION OF TEMBILE JUNIOR SECONDARY SCHOOL
THE MVULA TRUST SAFE PROGRAMME

Section 3

Bill No. 1

Ironmongery

COLLECTION

Total Brought Forward from Page No.

**Page
No**

34

35

Amount

Carried Forward to Summary of Section No. 3

Section 3

Bill No. 1

Ironmongery

R

Item No		Quantity	Rate	Amount
	<u>SECTION 3</u> <u>BILL No. 2</u> <u>PLASTERING</u> <u>Quantity Split:</u> Note that the total quantity per each item is split into the various buildings and appears below each description as follows: A0 - DWG 38 - Male Ablutions A1 - DWG 39 - Female Ablutions A2 - DWG 36 - Grade R Ablutions A3 - DWG 37 - Staff Ablutions <u>MODEL PREAMBLES</u> The tenderer is referred to the "Model Preambles for Trades 2008" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates <u>SCREEDS</u> <u>Untinted granolithic, on concrete:</u>			
1	30mm Thick on floors and landings. A0 : 9 A1 : 10 A2 : 11 A3 : 14	m2	44	
	Carried Forward to Summary of Section No. 3		R	
	Section 3			
	Bill No. 2			
	Plastering			

COMPLETION OF TEMBILE JUNIOR SECONDARY SCHOOL
THE MVULA TRUST SAFE PROGRAMME

Section 3

SECTION SUMMARY - BUILDING WORKS

**Bill
No**

Ironmongery

Plastering

**Page
No**

36

37

Amount

Carried to Final Summary

Section 3

R

**COMPLETION OF TEMBILE JUNIOR SECONDARY SCHOOL
THE MVULA TRUST SAFE PROGRAMME**

Item No		Quantity	Rate	Amount
	<u>SECTION No. 4</u>			
	<u>BILL No. 1</u>			
	<u>EXTERNAL WORKS (PROVISIONAL)</u>			
	<u>MODEL PREAMBLES</u>			
	The tenderer is referred to the "General Preambles for Trades 2017" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates.			
	<u>THE FOLLOWING IN WALKWAYS</u>			
	<u>Excavation not exceeding 2m deep</u>			
1	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	0.4	
	<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>			
2	Off site to a dumping site to be found by the Contractor.	m3	0.4	
	<u>Filling supplied by the contractor under walkways</u>			
3	G7 Base course material compacted to 98% Mod AASHTO density	m3	0.3	
4	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	0.3	
	<u>Rip and Re - compact insitu material on site compacted to 93% Mod. AASHTO density:</u>			
5	Under floors,etc.	m2	2	
	<u>Prescribed density tests on filling:</u>			
6	In-situ dry density test.	No	2	
	Carried to Collection			
	Section 4			
	Bill No. 1			
	External Works			
			R	

**COMPLETION OF TEMBILE JUNIOR SECONDARY SCHOOL
THE MVULA TRUST SAFE PROGRAMME**

	<u>Approved brand of anti-termite soil poison applied by a Registered Pest Control Company and guaranteed against termite infestation for ten years:</u>				
7	Treat filling under paving with 'Chlordane Heptachlor Aldrin' or equal approved.	m2	2		
	<u>Concrete Paving Blocks</u>				
	<u>Paving of 50mm thick 200x100mm 25MPa Bevel Bond paver blocks grey in colour in herringbone pattern on and including 20mm thick sand bed with dry filler sand swept and vibrated into joints all laid on subgrade (elsewhere measured) conforming to SABS 1200D degree of accuracy I:</u>				
8	Paving to walkway areas, etc laid to falls.	m2	2		
	<u>Kerbing</u>				
	<u>Precast or in situ mass concrete (25 MPa - 19 mm stone) kerbs cast in convenient lengths with exposed faces finished smooth from the mould and all salient angles rounded, jointed and pointed in 1:3 cement mortar, including excavations, formwork, etc.</u>				
9	Figure 8B (300 x 275 x 175mm) semi mountable kerb laid in lengths not exceeding 1000mm on a well rammed earth bottom or base course.	m	2		
10	Ditto but circular on plan.	m	1		
	Carried to Collection			R	
	Section 4 Bill No. 1 External Works				

Section 4
Bill No. 1
External Works

R

**COMPLETION OF TEMBILE JUNIOR SECONDARY SCHOOL
THE MVULA TRUST SAFE PROGRAMME**

<u>STORMWATER CHANNELS</u>					
<u>Excavation not exceeding 2m deep</u>					
11	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	1		
<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>					
12	Off site to a dumping site to be found by the Contractor.	m3	1		
<u>Filling supplied by the contractor under channels</u>					
13	G7 Base course material compacted to 98% Mod AASHTO density	m3	2		
14	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	2		
<u>Cast in-situ Ref 395 mesh reinforced concrete (25MPa) open stormwater channels having V-shaped waterway formed in top, finished smooth on all exposed surfaces in 3:1 cement plaster trowelled smooth and with angles rounded, cast in suitable lengths not exceeding 2m, including all formwork, moulds, shallow excavation, filling and ramming, laying to falls, bedding and pointing in 3:1 cement mortar. Concrete apron to be tinted, colour to be specified by the Engineer.</u>					
15	700 x 80mm thick V' channel 150mm deep in centre laid in position in ground in 2000mm sections including all formwork, reinforcement, expansion joints, smooth finishing to top of concrete surface etc.	m	10		
16	Extra for 700mm angle	No	3		
17	Extra for forming 200mm thick 700mm wide spreader with 200mm high edges fanning out to 1 960mm width at furthest end with hard burnt bricks pitching cast in ass diffusers including working off concrete to a smooth finish and draining onto natural ground with 150 - 200mm diameter loose stones.	No	4		
Carried to Collection				R	
Section 4					
Bill No. 1					
External Works					

THE FOLLOWING IN HEADWALLS

18 Gabion mattress comprising of 20 to 30mm stones wrapped in A3 geotextile with voids filled with 1:3 cement/sand mortar.

m2

10

Carried to Collection

R

Section 4
Bill No. 1
External Works

**COMPLETION OF TEMBILE JUNIOR SECONDARY SCHOOL
THE MVULA TRUST SAFE PROGRAMME**

THE FOLLOWING IN ACCESS DRIVEWAY, ETC.

Excavation not exceeding 2m deep

19	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	186
----	--	----	-----

Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):

20	Off site to a dumping site to be found by the Contractor.	m3	186
----	---	----	-----

Filling supplied by the contractor under driveways

21	G7 Base course material compacted to 98% Mod AASHTO density	m3	70
----	---	----	----

22	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	70
----	--	----	----

Rip and Re - compact insitu material on site compacted to 93% Mod. AASHTO density:

23	Under floors,etc.	m2	465
----	-------------------	----	-----

Prescribed density tests on filling:

24	In-situ dry density test.	No	8
----	---------------------------	----	---

Approved brand of anti-termite soil poison applied by a Registered Pest Control Company and guaranteed against termite infestation for ten years:

25	Treat filling under paving with 'Chlordane Heptachlor Aldrin' or equal approved.	m2	465
----	--	----	-----

150-175mm diameter bollards

26	2100mm long tanalith treated gum pole planted 800mm deep including excavations, cartaways, concrete base etc.	No	30
----	---	----	----

Carried to Collection

R

Section 4
Bill No. 1
External Works

**THE FOLLOWING IN STORMWATER
DRAINAGE, APRONS ETC.**

STORMWATER APRONS

Excavation not exceeding 2m deep

27	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	1	
----	--	----	---	--

Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):

28	Off site to a dumping site to be found by the Contractor.	m3	1	
----	---	----	---	--

Filling supplied by the contractor under floors, aprons, etc

29	G7 Base course material compacted to 98% Mod AASHTO density	m3	1	
----	---	----	---	--

Coarse river sand filling supplied by the contractor:

30	Under floors etc.	m3	0.2	
----	-------------------	----	-----	--

Compaction of surfaces:

31	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density.	m2	4	
----	--	----	---	--

Prescribed density tests on filling:

32	In-situ dry density test.	No	4	
----	---------------------------	----	---	--

Reinforced 25Mpa/19mm Concrete:

33	Surface beds cast in panels on waterproofing.	m3	0.4	
----	---	----	-----	--

Finishing top surfaces of concrete smooth with a wood float:

34	Surface beds, slabs, etc to falls and currents.	m2	4	
----	---	----	---	--

Carried to Collection

Section 4
Bill No. 1
External Works

R

COMPLETION OF TEMBILE JUNIOR SECONDARY SCHOOL THE MVULA TRUST SAFE PROGRAMME

[illegible]

**COMPLETION OF TEMBILE JUNIOR SECONDARY SCHOOL
THE MVULA TRUST SAFE PROGRAMME**

THE FOLLOWING IN RAINWATER TANKS AND STANDS

Plastic water tanks etc:

38	Supply and deliver water to existing 5000 Litre roto molded for testing all plumbing works.	No	5
39	Tighten wires securing tanks to the tank stands, provide any missing wires, anchors, etc and ensure the tank is properly secured to the tank stand.	No	5

THE FOLLOWING IN SECURITY FENCING, ETC (GRADE R)

Site clearance

40	Allow for clearing site for the width of 1 000 mm where fencing is to be erected including removing trees, shrubs etc. not exceeding 200 mm girth, grubbing up roots and roughly levelling.	m2	18
----	---	----	----

Straining wires, fencing and razor wire:

41	Four strands of 4mm Class'A' galvanised straining wires secured to fencing posts with doubled 2 mm galvanised wire inserted through hole in post and turned a minimum of four turns around straining wire and attached to straining frame at one end with not less than four turns at the other end to straining bolts (elsewhere measured).	m	15
42	3 Strands of galvanised barbed wire tied to standards, posts and eye bolts	m	15
43	Fencing formed of 50 x 50 x 2.0mm diameter galvanised fencing 1 800mm high and fixed to each straining wire with 8 guage binding wire at 500mm centres including Y12 pegs at 900mm c/c between posts (straining wires elsewhere measured).	m	15

Posts for 1 800mm high security fence:

44	60mm Diameter galvanised steel intermediate fencing post 2 400mm long fitted with a pressed steel mushroom cap one end and 150 x 150 x 5 mm baseplate at bottom and embedded in and including 350 x 350 x 600 mm mass concrete (15 MPa) base.	No	2
----	---	----	---

Carried to Collection

R

Section 4
Bill No. 1
External Works

COMPLETION OF TEMBILE JUNIOR SECONDARY SCHOOL THE MVULA TRUST SAFE PROGRAMME

[illegible]

COMPLETION OF TEMBILE JUNIOR SECONDARY SCHOOL
THE MVULA TRUST SAFE PROGRAMME

Section 4

Bill No. 1

External Works

COLLECTION

Total Brought Forward from Page No.

**Page
No**

Amount

39

40

41

42

43

44

45

46

47

48

Carried to Final Summary

R

Section 4

Bill No. 1

External Works

Item No	Quantity	Rate	Amount
<u>SECTION 5</u>			
<u>BILL No. 1</u>			
<u>PROVISIONAL SUMS</u>			
<u>SUPPLEMENTARY PREAMBLES</u>			
Tenderers are advised that no claim in respect of loss of profit or Preliminary charges based on the omission of these amounts will be considered and the said amounts will be omitted strictly without any financial compensation payable to the Contractor. Provisional sums and Budgetary allowances contained herein may be omitted or reduced at the Employer's discretion and the Contractor shall not be entitled to claim for any loss by way of reductions or omission of any discount, or percentage relating to Provisional amounts and Budgetary sums or any loss of profit related thereto.			
<u>PRE-FABRICATED STRUCTURES</u>			
NOTE: Shop drawings / Specifications will be required for approval by the Principal Agent PRIOR to installation. The ABT Specialist Supplier must be competent person registered with relevant statutory body, all ABT construction shall comply with SABS standards and approved by AGREEMENT SA.			
Carried to Collection			
			R
Section 5 Bill No. 1 Provisional Sums			

The Structures to be erected will be as follows:

Boys ablution structure on concrete slab, size 3860 x 3080 x 3120mm high complete with 1No. external door including security gate, 2No. internal doors, 6No. windows, 2No. WCs, 2No. urinals, 1No. wash hand basin etc.

Girls ablution structure on concrete slab, size 4480 x 3080 x 3120mm high complete with 1No. external door including security gate, 3No. internal doors, 6No. windows, 3No. WCs, 2No. wash hand basins etc.

Staff ablution structure on concrete slab, size 4360 x 3080 x 3120mm high complete with 3No. external doors including security gate, 3No. windows, 3No. WCs, 3No. wash hand basins etc.

Grade R ablution structure on concrete slab, size 5400 x 3080 x 3120mm high complete with 1No. external doors including security gate, 7No. windows, 1No. WC, 2No. junior WCs, 2No. wash hand basins etc.

Pre-fabricated Modular Units shall comprise of:

- Internal and external walls made of 40mm thick wall panel which consist of 0.5mm rigidised pre-painted white galvanised chromadek sheeting on both sides including base rails, top rails all joined with aluminium rivets
- 600 x 600mm high casement type (W1) natural anodised aluminium window including frames and 4mm obscure glass with one top hung opener; Windows are to be secured with aluminium profile burglar proofing
- 813 x 2032mm high external doors manufactured from the same materials as the walls and fitted with hinges, five lever mortice lock, complete with striker plates, two keys chrome plated handles, etc
- 813 x 1882mm high internal door manufactured from the same materials as the walls and fitted with hinges, 3 lever mortice lock complete with striker plates, two keys chrome plated handles, etc
- Galvanised mild steel security gate 900 x 2050mm high overall size

Carried to Collection

Section 5
Bill No. 1
Provisional Sums

R

**COMPLETION OF TEMBILE JUNIOR SECONDARY SCHOOL
THE MVULA TRUST SAFE PROGRAMME**

- 2mm thick vinyl sheeting on floors
- The roof is to be 0.5mm Chromadek IBR sheeting mono pitched roof with mono pitched galvanised ridge capping, 255mm lapping secured onto the roof including light steel frame roof at 6 degree slope
- 125mm half round PVC gutters including gutter brackets at 1000mm centres with 75mm rainwater PVC fluted downpipes connected to 5000L plastic water tanks (elsewhere measured)
- Medium density plain un-grooved fascia boards
- 85 x 275 x 6.0mm barge board drilled and brass screwed to purlin ends including galvanised steel H-profile jointing strips, screws, holes, etc
- Plumbing and sanitary fittings shall comprise of WCs, Urinals, Wash hand basins, 15mm and 22mm polycop water supply pipes, 50mm diameter PVC drainage pipes and associated accessories

PAYMENT OF OUTSTANDING WAGES AND SUB-CONTRACTOR'S

1 Provide the sum of R 25 000.00 for the payment of outstanding wages and or subcontractor's from terminated contractor.

Item

25 000.00

2 Add: Profit on above

%

3 Add: Attendance on above

%

COMMUNITY LIAISON OFFICER

4 Provide the sum of R 13 000.00 for the employment of a Community Liaison Officer to be employed by the Main Contractor and be paid an allowance of R6 500.00 a month.

Item

13 000.00

5 Add: Profit on above

%

6 Add: Attendance on above

%

Carried to Collection

R

Section 5
Bill No. 1
Provisional Sums

COMPLETION OF TEMBILE JUNIOR SECONDARY SCHOOL
THE MVULA TRUST SAFE PROGRAMME

Section 5

Bill No. 1

Provisional Sums

COLLECTION

Total Brought Forward from Page No.

**Page
No**

Amount

50

51

52

Carried to Final Summary

R

Section 5

Bill No. 1

Provisional Sums

**COMPLETION OF TEMBILE JUNIOR SECONDARY SCHOOL
THE MVULA TRUST SAFE PROGRAMME**

Section No	<u>FINAL SUMMARY</u>	Page No	Amount
1	PRELIMINARIES	29	
2	DEMOLITIONS (PROVISIONAL)	33	
3	BUILDING WORKS	38	
4	EXTERNAL WORKS (PROVISIONAL)	49	
5	PROVISIONAL SUMS	53	
	SUB-TOTAL		R
	<u>CONTINGENCIES</u>		
	Allow five per cent (5%) of the above sub-total for contingencies to be used as directed and deducted in whole or in part if not required.		R
	SUB-TOTAL		R
	Add Value Added Tax at the rate of 15%		R
	Carried to Form of Offer and Acceptance		R