

**SPECIFICATIONS FOR SUPPLY AND INSTALL 20KVA UPS AND ELECTRICAL
RETICULATION AT A9-A12 VIMP BUILDING**

20KVA UPS with intelligent display

Supply and installation of 20Kva On-line UPS, 3 phase input and output with external battery pack.

- UPS with digital display, static bypass and manual bypass switch
- Anticipate battery life span 3-5 years
- Backup time at full load of 10-20 minutes
- One year UPS warranty

Electrical reticulation

Supply and install of electrical reticulation

Item name	Item description	No of Item
DB	Main Circuit breaker 30 Amp	1
Sub DB	12 way	4
Circuit breaker	20 Amp	4
Cable	10mm x 20m	
Cable	Cable linking buildings	
Plugs	UPS plug points	55
Electrical Certificate of compliance	COC	1
Labelling	Label and update drawing	1

NB: Site inspection is compulsory