

Item No		Quantity	Rate	Amount
	<p><u>SECTION 1</u></p> <p><u>BILL No.1</u></p> <p><u>PRELIMINARIES</u></p> <p>1. The Principal Building Agreement shall be the JBCC Series Edition 4.1, March 2005 as recommended by the Joint Building Contract Committee and as amended by this Tender Enquiry.</p> <p>2. The Preliminaries shall be JBCC Series 2000, May 2005 for use with the Principal Building Agreement as recommended by the Joint Building Contracts Committee and as amended by this Tender Enquiry shall be deemed to be incorporated herein.</p> <p>3. Tenderers are referred to the abovementioned documents for the full intent and meaning of each clause thereof. These clauses are hereinafter referred to by clause number and heading only.</p> <p>4. Where standard clauses or alternatives are not entirely applicable to this contract, such modifications, corrections or additions as are necessary, are given as far as possible under each relevant clause heading. Additional Preliminary clauses are contained in Section C hereof.</p> <p>5. No claim whatsoever shall be entertained in respect of errors or omissions in pricing due to brevity of descriptions of items which are fully described when read in conjunction with the relevant clauses of the said Principal Building Agreement, Preliminaries and Preambles.</p> <p>6. The Tenderers shall allow opposite each of the clauses whatever costs and charges he may consider necessary for the carrying out, complying with and due observance of the provisions, conditions and requirements set out herein. Only priced items will be considered in respect of any adjustment of this Section. Any items left unpriced will be understood to be provided free of charge and no claim for any extras arising out of the Tenderer's omission to price any item will be entertained.</p>			
	Carried to Collection		R	
	Section 1			
	Bill No. 1			
	Preliminaries			

	<p>7. Where modifications or amendments as described are made, such modifications and/or amendments shall supercede any conflicting provisions in the relevant clauses of the Standard Preliminaries or the Principal Building Agreement and the Tenderer shall make due allowance for whatever costs and charges he may consider necessary for the carrying out and observance of the provisions of the clauses as modified and/or amended.</p> <p>8. Where any item is not relevant to this specific contract, such item is marked N/A.</p> <p>9. If Alternative A as set out in clause B10.3 hereinafter is to be used for the adjustment of the preliminaries, each item priced is to be allocated to one or more of the three categories by insertion of "F","V","T" as the case may be against the price in the "rate" column immediately preceding the "amount" column, where "F" denotes a fixed amount (amount not to be varied), "V" denotes an amount variable in proportion to value, and "T" denotes an amount proportionate to time.</p>				
	Carried to Collection		R		
	Section 1 Bill No. 1 Preliminaries				

	<p><u>SECTION A: PRINCIPAL BUILDING AGREEMENT</u></p> <p><u>DEFINITIONS</u></p> <p>Definitions and interpretation (Clause 1).</p> <p>1 F: V: T:</p> <p><u>OBJECTIVE AND PREPARATION</u></p> <p>Offer, acceptance and performance (Clause 2).</p> <p>2 F: V: T:</p> <p>Documents (Clause 3).</p> <p>Clause 3.1 is deleted and substituted with: 'This tender is for a Government Contract. No Payment Guarantee will be provided.'</p> <p>Clause 3.3 is deleted and substituted with:</p> <p>The principal agent shall complete the schedule and arrange for formal signing of the agreement once the priced bill of quantities/lump sum document, security, insurances and waiver of lien, where acceptable, have been provided and effected'.</p> <p>3 F: V: T:</p> <p>Design responsibility (Clause 4).</p> <p>4 F: V: T:</p> <p>Employer's agents (Clause 5).</p> <p>5 F: V: T:</p> <p>Site representative (Clause 6).</p> <p>6 F: V: T:</p> <p>Compliance with regulations (Clause 7).</p> <p>7 F: V: T:</p> <p style="text-align: right;">Carried to Collection</p> <p>Section 1 Bill No. 1 Preliminaries</p>	<p>Item</p> <p>Item</p> <p>Item</p> <p>Item</p> <p>Item</p> <p>Item</p> <p>Item</p>		
			R	

8	<p>Works risk (Clause 8)</p> <p>F: V: T:</p> <p>Indemnities (Clause 9).</p> <p>Clause 9.1.1 is deleted and substituted with:</p> <p>Claims from other parties consequent upon death of bodily injury or illness of any person or physical loss or damage to any property, other than the works, arising out or due to the execution of the works or occupation of the site by the contractor or his sub contractors'.</p>	Item		
9	<p>F: V: T:</p> <p>Works insurances (Clause 10).</p>	Item		
10	<p>F: V: T:</p> <p>Liability insurances (Clause 11).</p>	Item		
11	<p>F: V: T:</p> <p>Effecting insurances (Clause 12).</p>	Item		
12	<p>F: V: T:</p> <p>State Provisions (Clause 13).</p>	Item		
13	<p>F: V: T:</p> <p>Security (Clause 14).</p>	Item		
14	<p>F: V: T:</p> <p><u>EXECUTION</u></p> <p>Preparation for and execution of the works (Clause 15).</p>	Item		
15	<p>F: V: T:</p> <p>Access to the works (Clause 16).</p>	Item		
16	<p>F: V: T:</p> <p>Contract instructions (Clause 17).</p>	Item		
<p style="text-align: right;">Carried to Collection</p> <p>Section 1 Bill No. 1 Preliminaries</p>			R	

**QIBIRA PRIMARY SCHOOL
THE MVULA TRUST FLUSH MAINTENCE PROGRAMME**

17	F: V: T: Setting out of the works (Clause 18.3). The contractor shall notify the principal agent if any encroachments of adjoining foundations, buildings, structures, pavements, boundaries, etc., exist in order that the necessary arrangements may be made for the rectification of any such encroachments. Should incorrect information be given to the contractor in terms of 18.1 and 18.2, which causes the incorrect setting out of the works, the contractor shall not be liable for such incorrect setting out.	Item			
18	F: V: T: Assignment (Clause 19).	Item			
19	F: V: T: Nominated subcontractors (Clause 20).	Item			
20	F: V: T: Selected subcontractors (Clause 21).	Item			
21	F: V: T: Employer's Direct contractors (Clause 22).	Item			
22	F: V: T: Contractor's Domestic subcontractors (Clause 23).	Item			
23	F: V: T: <u>COMPLETION</u> Practical completion (Clause 24).	Item			
24	F: V: T: Works completion (Clause 25).	Item			
25	F: V: T: Final completion (Clause 26).	Item			
Carried to Collection			R		
Section 1 Bill No. 1 Preliminaries					

	<p>Latent defects liability period (Clause 27).</p> <p>Clause 27.0 is amended by the addition of the following clauses:</p> <p>"27.3 Any water leakage into the building, whether in the roof, external wall or other element of the building susceptible to water leakage shall, unless proven to be a design defect, or as a result of obvious storm damage, be classified as a latent defect in terms of clause 1.0 Definitions and Interpretations".</p> <p>"27.4 The Contractor shall attend to defects during the Defects Liability Period on a progressive basis, to the satisfaction of the Principal Agent and will not be permitted to wait until the end of the Defect Liability Period or until the amount of defects accumulates in order to attend to a comprehensive list of defects"</p>				
26	<p>F: V: T:</p> <p>Sectional completion (Clause 28).</p>	Item			
27	<p>F: V: T:</p> <p>Revision of date for practical completion (Clause 29).</p>	Item			
28	<p>F: V: T:</p> <p>Penalty for non-completion (Clause 30).</p>	Item			
29	<p>F: V: T:</p> <p><u>PAYMENT</u></p> <p>Interim payment to the contractor (Clause 31).</p> <p>The inclusion of materials and goods stored off site in the amount authorised for payment in terms of clause 31.3 shall be at the sole discretion of the principal agent and such inclusion shall only be considered upon the provision, by the contractor, of an approved guarantee issued by a registered commercial bank.</p>	Item			
Carried to Collection				R	
<p>Section 1 Bill No. 1 Preliminaries</p>					

	<p>Where prices are submitted by the contractor or nominated/selected sub contractor during the progress of the works in respect of contract instructions or in regard to a claim under the terms of the contract and notwithstanding the fact that such prices may be used in an interim payment certificate, there is to be no presumption of acceptance. Should the principal agent wish to accept any such prices prior to the issue of the final certificate, it will be in writing.</p> <p>Adjustment to the contract value (Clause 32).</p>				
30	<p>F: V: T:</p> <p>Recovery of expense and loss (Clause 33).</p>	Item			
31	<p>F: V: T:</p> <p>Final account and final payment (Clause 34).</p>	Item			
32	<p>F: V: T:</p> <p>Payment to other parties (Clause 35).</p>	Item			
33	<p>F: V: T:</p> <p><u>CANCELLATION</u></p> <p>Cancellation by Employer - Contractor's default (Clause 36).</p>	Item			
34	<p>F: V: T:</p> <p>Cancellation by Employer - Loss and damage (Clause 37).</p>	Item			
35	<p>F: V: T:</p> <p>Cancellation by Contractor - Employer's default (Clause 38).</p>	Item			
36	<p>F: V: T:</p> <p>Cancellation - Cessation of the works (Clause 39).</p>	Item			
37	<p>F: V: T:</p>	Item			
Carried to Collection			R		
<p>Section 1 Bill No. 1 Preliminaries</p>					

	<p><u>DISPUTE</u></p> <p>Dispute Settlement (Clause 40)</p> <p>38 F: V: T:</p> <p><u>SUBSTITUTE PROVISIONS</u></p> <p>State Clauses (Clause 41)</p> <p>39 F: V: T:</p> <p><u>CONTRACT VARIABLES</u></p> <p>The Schedule: Pre-Tender information (Clause 42).</p> <p>40 F: V: T:</p> <p><u>CONTRACTING AND OTHER PARTIES (Clause 42.1)</u></p> <p>Employer: The Mvula Trust</p> <p>Postal Address: 67 Devereux Avenue, Vincent, East London</p> <p>Telephone: 043 726 2255</p> <p>Facsimile: 043 726 5967</p> <p>Physical address: 67 Devereux Avenue, Vincent, East London</p> <p>Principal Agent: The Mvula Trust</p> <p>Postal Address: 67 Devereux Avenue, Vincent, East London</p> <p>Telephone: 043 726 2255</p> <p>Facsimile: 043 726 5967</p> <p>Physical address: 67 Devereux Avenue, Vincent, East London</p> <p style="text-align: right;">Carried to Collection</p> <p>Section 1 Bill No. 1 Preliminaries</p>	<p>Item</p> <p>Item</p> <p>Item</p>		
			R	

	<p><u>CONTRACT DETAILS (Clause 42.2)</u></p> <p>Clause 42.2.1</p> <p>Works Description: Construction of new ablution facilities.</p> <p>Clause 42.2.2</p> <p>Site Description: The site is the existing school.</p> <p>Clause 42.2.3</p> <p>Work or Installations by Others: NIL</p> <p>Clause 42.2.4</p> <p>This Agreement is for a State Contract :- Yes</p> <p>Payment will be made for materials and goods:- Yes</p> <p>Dispute resolution :- Mediation (in terms of clause 40) followed by litigation.</p> <p>Arbitration rules as recommended by the Association of Arbitrators (SA) :- N/A</p> <p>Clause 42.2.5</p> <p>Date on which possession of the site is intended to be given on :-</p> <p>To be advised.</p> <p>Clause 42.2.6</p> <p>Period for the commencement of the works after the contractor takes possession of the site :- 10 Working days.</p> <p>Completion in Sections are required : NO</p> <p>Clause 42.2.7</p> <p>Intended date of practical completion and the penalty per calendar day for the works as a whole :-</p> <p>To be advised.</p> <p style="text-align: right;">Carried to Collection</p> <p>Section 1 Bill No. 1 Preliminaries</p>			
			R	

	<p>Penalty amount will be R 2000.00 per Calendar day to a maximum of 10% of Contract Value.</p> <p>Clause 42.2.8</p> <p>Intended dates of practical completion and the penalties per calendar day for the works in sections :</p> <p>N/A</p> <p>Clause 42.2.9</p> <p>The law applicable to this agreement shall be that of - Republic of South Africa.</p> <p><u>INSURANCES (Clause 42.3)</u></p> <p>Clause 42.3.1</p> <p>Contract works insurance to be effected by Contractor for the sum of: Contract Sum plus 10%</p> <p>With a deductible of : 5% of insured amount</p> <p>Clause 42.3.2</p> <p>Supplementary insurance is required : Yes</p> <p>SASRIA insurance required to be effected by the Contractor for the amount of: Contract Sum plus 20% (with a deductible to be determined by the Insurance company issuing the policy).</p> <p>Clause 42.3.3</p> <p>Public liability insurance to be effected by Contractor</p> <p>For the amount of: R 5million</p> <p>With a deductible of: 5% of insured amount</p> <p><u>DOCUMENTS (Clause 42.4)</u></p> <p>Clause 42.4.1</p> <p>Waiver of the contractor's lien is required :- YES</p> <p>Clause 42.4.2</p> <p style="text-align: right;">Carried to Collection</p> <p>Section 1 Bill No. 1 Preliminaries</p>			
			R	

	<p>Number of construction document copies to be supplied to the Contractor free of charge :- 1</p> <p>Clause 42.4.3</p> <p>Bills of Quantities drawn up in accordance with :-</p> <p>Standard System of Measuring Building Work - Seventh Edition including all amendments</p> <p>Clause 42.4.4</p> <p>Number of days for submission of priced documents : 5 working days from the Letter of Appointment.</p> <p>Clause 42.4.5</p> <p>JBCC Engineering General Conditions are to be included in the documents :- No</p> <p>Clause 42.4.6</p> <p>The contract value is to be adjusted using CPAP:- NO</p> <p><u>SECTION B: PRELIMINARIES</u></p> <p><u>DEFINITIONS AND INTERPRETATION (B1)</u></p> <p>Definitions and Interpretation (B1)</p>				
41	<p>F: V: T:</p> <p><u>DOCUMENTS (B2)</u></p> <p>Checking of documents (B2.1)</p> <p>Notwithstanding the issue of the tender drawings, it will remain the responsibility of the Tenderer to study all available drawings at the offices of the Principal Agent during normal working hours in order to acquaint himself with all the cost implications of the design, programming, phasing, etc.</p>	Item			
42	<p>F: V: T:</p> <p>Provisional Bills of Quantities (B2.2) YES</p>	Item			
Carried to Collection				R	
<p>Section 1 Bill No. 1 Preliminaries</p>					

	<p>Prime Cost Amounts, Budgetary Allowances, Provisional Amounts, etc., contained herein may be omitted or reduced at the Principal Agent's sole discretion and the Contractor shall not be entitled to claim for any loss by way of reduction or omission of any discount, or percentage relating to Prime Cost Amounts, Budgetary Allowances, Provisional Amounts, Provisional Quantities, etc., or loss of profit related thereto.</p>				
43	<p>F: V: T:</p> <p>Availability of construction documentation (B2.3)</p>	Item			
44	<p>F: V: T:</p> <p>Interests of Agents (B2.4)</p>	Item			
45	<p>F: V: T:</p> <p>Priced documents (B2.5)</p>	Item			
46	<p>F: V: T:</p> <p>Tender submission (B2.6)</p> <p>Notwithstanding anything contained in this clause, Tenders shall be valid for a period of 20 (Twenty) weeks from the closing date of tenders.</p>	Item			
47	<p>F: V: T:</p> <p><u>THE SITE (B3)</u></p> <p>Defined works area (B3.1)</p> <p>The area of the works to be occupied by the contractor, any restriction on the area and the limit of access or exit will be pointed out to the contractor by the principal agent on handing over of the site.</p> <p>Workmen employed on the site are to be restricted to the immediate area of the site and access thereto.</p> <p>The Tenderer shall make all necessary provision in all rates to take into account these requirements as no claims for extras arising from these matters will be subsequently entertained or admitted.</p>	Item			
Carried to Collection			R		
<p>Section 1 Bill No. 1 Preliminaries</p>					

48	F: V: T: Geotechnical investigation (B3.2) A desktop geotechnical report is available upon request.	Item			
49	F: V: T: Inspection of the Site (B3.3)	Item			
50	F: V: T: Existing premises occupied (B3.4)	Item			
51	F: V: T: Previous work - dimensional accuracy (B3.5)	Item			
52	F: V: T: Previous work - defects (B3.6)	Item			
53	F: V: T: Services - known (B3.7)	Item			
54	F: V: T: Services - unknown (B3.8)	Item			
55	F: V: T: Protection of trees (B3.9)	Item			
56	F: V: T: Articles of value (B3.10)	Item			
57	F: V: T: Inspection of adjoining properties (B3.11)	Item			
58	F: V: T: <u>MANAGEMENT OF CONTRACT (B4)</u> Management of the Works (B4.1)	Item			
Carried to Collection			R		
Section 1 Bill No. 1 Preliminaries					

**QIBIRA PRIMARY SCHOOL
THE MVULA TRUST FLUSH MAINTENCE PROGRAMME**

59	F: V: T: Programme for the Works (B4.2)	Item		
60	F: V: T: Progress meetings (B4.3)	Item		
61	F: V: T: Technical meetings (B4.4)	Item		
62	F: V: T: <u>SAMPLES AND SHOP DRAWINGS (B5)</u> Samples of materials (B5.1)	Item		
63	F: V: T: Workmanship samples (B5.2)	Item		
64	F: V: T: Shop drawings (B5.3)	Item		
65	F: V: T: <u>TEMPORARY WORKS AND PLANT (B6)</u> Deposits and fees (B6.1)	Item		
66	F: V: T: Enclosure of the works (B6.2) The contractor shall erect, maintain and remove at completion, hoardings, safety screens, barriers, access gates, covered gangways and the like as necessary for the enclosure of the works and elements thereof all for the protection of the public and others.	Item		
67	F: V: T: Advertising (B6.3)	Item		
68	F: V: T:	Item		
Carried to Collection			R	
Section 1 Bill No. 1 Preliminaries				

Section 1
Bill No. 1
Preliminaries

R

69	Plant and equipment (B6.4)				
	F: V: T:	Item			
	Main notice board (B6.5)				
	One notice board shall be provided by the Contractor				
	70 F: V: T:	Item			
	Subcontractors notice board (B6.6) (N/A)				
	71 F: V: T:	Item			
	<u>TEMPORARY SERVICES (B7)</u>				
	Location (B7.1)				
	72 F: V: T:	Item			
	Water (B7.2)				
	The contractor shall provide water for the works in accordance with:				
	Alternative A (i.e. to be provided for by the Contractor).				
73	F: V: T:	Item			
	Electricity (B7.3)				
	The contractor shall provide electricity for the works in accordance with:				
	Alternative A (i.e. to be provided for by the Contractor).				
74	F: V: T:	Item			
	Telecommunication equipment (B7.4)				
	The contractor shall provide telephones on site for the works in accordance with:				
	Alternative A (i.e. to be provided for by the Contractor).				
75	F: V: T:	Item			
	Carried to Collection				
Section 1 Bill No. 1 Preliminaries			R		

	<p>Ablution facilities (B7.5)</p> <p>The contractor shall provide toilet facilities on site for the works in accordance with:</p> <p>Alternative A (i.e. to be provided for by the Contractor).</p>				
76	<p>F: V: T:</p> <p><u>PRIME COST AMOUNTS (B8)</u></p> <p>Responsibility for prime cost amounts (B8.1)</p>	Item			
77	<p>F: V: T:</p> <p><u>ATTENDANCE ON N/S SUBCONTRACTORS (B9)</u></p> <p>General Attendance (B9.1)</p>	Item			
78	<p>F: V: T:</p> <p>Special Attendance (B9.2)</p>	Item			
79	<p>F: V: T:</p> <p>Commissioning - fuel, water and power (B9.3)</p>	Item			
80	<p>F: V: T:</p> <p><u>FINANCIAL ASPECTS (B10)</u></p> <p>Statutory taxes, duties and levies (B10.1)</p> <p>Provision is made in the Final Summary of these Bills of Quantities for the inclusion of Value Added Tax (VAT).</p>	Item			
81	<p>F: V: T:</p> <p>Payment of Preliminaries (B10.2)</p>	Item			
82	<p>F: V: T:</p> <p>Adjustment of Preliminaries (B10.3)</p>	Item			
83	<p>F: V: T:</p> <p>Payment certificate cash flow (B10.4)</p>	Item			
	Carried to Collection			R	
	<p>Section 1</p> <p>Bill No. 1</p> <p>Preliminaries</p>				

**QIBIRA PRIMARY SCHOOL
THE MVULA TRUST FLUSH MAINTENCE PROGRAMME**

84	F: V: T: Contractor information supply (B10.5)	Item			
85	F: V: T: <u>GENERAL (B11)</u> Protection of the Works (B11.1)	Item			
86	F: V: T: Protection/isolation of existing/sectionally occupied works (B11.2)	Item			
87	F: V: T: Site security (B11.3)	Item			
88	F: V: T: Notice before covering work (B11.4)	Item			
89	F: V: T: Disturbance (B11.5)	Item			
90	F: V: T: Works cleaning and clearing (B11.6)	Item			
91	F: V: T: Vermin (B11.7)	Item			
92	F: V: T: Overhand work (B11.8)	Item			
93	F: V: T:	Item			
Carried to Collection			R		
Section 1 Bill No. 1 Preliminaries					

<u>SECTION C: SPECIFIC PRELIMINARIES</u>					
<u>Section C: Specific Preliminaries:</u>					
C1. Proprietary branded products					
The contractor shall take delivery of, handle, store, use, apply and/or fix all proprietary branded products in strict accordance with the manufacturer's instructions after consultation with the manufacturer's authorised representative.					
94	F: V: T:	Item			
C2. Trade Names, etc.					
All materials, fittings, finishings, etc., specified hereinafter under a trade name, catalogue number or reference, must be exactly as described. The Architect's approval in writing must be obtained for the use of any alternative to the specification before the submission of tenders otherwise the specified materials, fittings, finishings, etc., will be assumed to have been allowed for in the tender.					
The Contractor must take delivery of, handle, store, use, apply and/or fix all proprietary branded products in strict accordance with the manufacturer's instructions after consultation with the manufacturer's authorised representative.					
95	F: V: T:	Item			
C3. Contractors responsibility					
The Employer, the Principal Agent and the other professional consultants shall not be responsible for any act or omission on the part of the Contractor which may result in any patent or latent defects, in materials or workmanship, breach or neglect of any local regulations. The Contractor shall at all times be responsible for any such neglect, deviation or wrong act, whether the same is discovered before or after the final certificate, or any other Certificate, has been approved.					
96	F: V: T:	Item			
C4. Overtime					
Carried to Collection					
Section 1					
Bill No. 1					
Preliminaries					

<p>97</p>	<p>Should overtime be required to be worked for any reason whatsoever, the costs of such overtime are to be borne by the contractor unless the principal agent has specifically authorised in writing, prior to the execution thereof, that costs for such overtime are to be borne by the employer.</p> <p>F: V: T:</p> <p>C5. As built drawings</p> <p>The position of construction breaks and the extent of individual concrete pours are to be recorded by the contractor on the structural engineer's drawings and are to be submitted to the principal agent and the structural engineer for their records.</p> <p>Three full sets of as-built drawings shall be submitted to the Principal Agent no later than fourteen days after practical completion.</p>	<p>Item</p>		
<p>98</p>	<p>F: V: T:</p> <p>C6. Construction Instructions</p> <p>Contract instructions issued on site are to be recorded in triplicate in a site instruction book which is to be maintained on site by the Contractor. The Contractor shall supply and have available at the site of the works at all times, the following site books:</p> <p>a) Construction Instruction Book:</p> <p>Receiving and recording instructions in a suitable A4 size triplicate book kept on site. Instructions issued shall be recorded by the Architect or other Employer's Agents to whom the Architect has delegated authority to in the book.</p> <p>Only instructions issued in such book shall be recognised.</p> <p>b) Daily Record Book:</p>	<p>Item</p>		
	<p style="text-align: right;">Carried to Collection</p> <p>Section 1 Bill No. 1 Preliminaries</p>		<p>R</p>	

	<p>The Contractor shall record in triplicate in a suitable A4 size triplicate book kept at the site, a daily record of work done, all site visits by the Principal Agent and other professional personnel and all events affecting the Works, such as progress, issue of plans, breakdown of machinery, etc. The labour, plant and material on site shall be recorded as well as work performed. Entries must be made by the Contractor and must be signed and forwarded to the Principal Agent for his counter-signature on a daily basis. Copies of these records shall be for the Architect, Quantity Surveyor and Contractor.</p>				
99	<p>F: V: T:</p> <p>C7. Labour record</p> <p>At the end of each week the contractor shall provide the principal agent with a written record, in schedule form, reflecting the number and description of tradesmen and labourers employed by him and all subcontractors on the works each day.</p>	Item			
100	<p>F: V: T:</p> <p>C8. Plant record</p> <p>At the end of each week the contractor shall provide the principal agent with a written record, in schedule form, reflecting the number, type and capacity of all plant, excluding hand tools, currently used on the works.</p>	Item			
101	<p>F: V: T:</p> <p>C9. Encroachment</p> <p>During the course of the building operations, the Contractor shall be held entirely responsible for any encroachment onto any adjoining properties, buildings, etc., or servitudes and the cost of any remedial measures as required by the Principal Agent shall be borne by the Contractor.</p>	Item			
102	<p>F: V: T:</p> <p>C10. Method Statement</p>	Item			
Carried to Collection				R	
<p>Section 1 Bill No. 1 Preliminaries</p>					

103	<p>The Tenderer shall produce, when required to do so by the Principal Agent, a Method Statement outlining the methods of construction and labour and plant resources that he proposes to use in the execution of the Works. Any approval given or observation made by the Principal Agent shall not relieve the Contractor of his sole responsibility to adopt the methods of construction and to provide the labour and plant resources necessary for the due and proper timeous execution of the Works.</p>	Item		
104	<p>F: V: T:</p> <p>C11. Unauthorised Persons/Workmen on Premises</p> <p>The Contractor shall at all times strictly exclude all unauthorised persons from the Works and the site and shall set up notice boards to that effect.</p> <p>No workmen or labourers (except security guards) are to be allowed under any circumstances to sleep or deposit any kit on the premises. The Contractor must provide any necessary independent shelter or shed required for any labour or watchmen on site, to the approval of the Employer.</p>	Item		
105	<p>F: V: T:</p> <p>C12. Mode of Procedure</p> <p>Notwithstanding anything to the contrary contained herein the Principal Agent at all times reserves the right to direct the order in which the various parts of the Contract are to be executed. The Contractor shall give priority to any individual section or portion of the Works that, in the opinion of the Principal Agent, requires to be expedited.</p> <p>Should it appear, in the Principal Agent's opinion, that work in any area is not being executed in accordance with the requirements of the Contract Programme, the Contractor shall provide additional manpower and resources and shall work additional overtime and do everything else required to bring the work back to programme to the satisfaction of the Principal Agent and to the Contractor's cost.</p>	Item		
<p style="text-align: right;">Carried to Collection</p> <p>Section 1 Bill No. 1 Preliminaries</p>			R	

	<p>C13. Location of Temporary Buildings and Temporary Services</p> <p>The Contractor shall provide all necessary temporary works, including temporary roads, tracks, crossings, hardstanding and services, hoardings, dust screens, tunnelling, etc., required for his own and sub-contractors use during the construction and maintenance period.</p> <p>There is no guarantee given or implied that Site conditions will be such that the Contractor will be able to erect such temporary works, roads, hardhats, offices, stores and temporary accommodation within the site boundaries and it shall be the Contractor's responsibility to adopt whatever measures he deems necessary in this regard and to obtain all necessary permission and pay all costs in connection therewith.</p>				
106	<p>F: V: T:</p> <p><u>C14. Office accommodation</u></p> <p>The contractor shall provide, maintain and remove on practical completion air conditioned office accommodation with suitable tables and chairs for meetings to be held on the site. Such offices shall be kept clean and fit for use at all times [12.2.18]</p>	Item			
107	<p>F: V: T:</p> <p><u>C15. Storage Facilities</u></p>	Item			
108	The Contractor shall provide a Container for storage of materials.	Item			
109	F: V: T:	Item			
	<p>C16. Removal and Making Good of Temporary Works, etc, on Completion</p> <p>The Contractor shall remove (except where specifically stated otherwise) all temporary works, roads, services and the like used for this contract and shall make good to the entire satisfaction of the Principal Agent any damage resulting therefrom.</p>				
110	<p>F: V: T:</p> <p>C17. SMME Management</p>	Item			
	Carried to Collection			R	
	<p>Section 1 Bill No. 1 Preliminaries</p>				

Company and head office overhead costs for the management of SMME's in accordance with the contract conditions, including the provision of a dedicated individual to fulfill this function. Training of SMME's in building up BOQ rates at the start of the project is to be priced in this item.

Item

Item

Item

Item

Item

R

Section 1
Bill No. 1
Preliminaries

QIBIRA PRIMARY SCHOOL
THE MVULA TRUST FLUSH MAINTENCE PROGRAMME

Section 1 Bill No. 1 Preliminaries <u>COLLECTION</u>
--

[illegible]

Item No		Quantity	Rate	Amount
	<p><u>SECTION 1</u></p> <p><u>BILL No. 2</u></p> <p><u>HEALTH AND SAFETY</u></p> <p><u>MODEL PREAMBLES</u></p> <p>The tenderer is referred to the "General Preambles for Trades 2017" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates.</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p>Supplementary preambles and/or specifications are incorporated in these bills of quantities to satisfy the requirements of this project. Such supplementary preambles and/or specifications shall take precedence over the provisions of the General Preambles.</p> <p>The contractor's prices for all items throughout these bills of quantities shall take account of and include where applicable for all of the obligations, requirements and specifications given in the General Preambles and in any supplementary preambles and/or specifications.</p> <p>Prior to pricing the principal contractor must familiarize him/herself with the Occupational Health and Safety Act No. 85 Of 1993, Construction Regulations 2014, other relevant Regulations and Standards as well as project specific Health & Safety specifications.</p> <p>The items in this Bill do not contain quantities hence the Contractor must insert his own quantities based on his individual requirements to comply with the Health and Safety obligations and demands of the Occupational Health and Safety Act No. 85 of 1993, Construction Regulations 2014, other relevant Regulations and Standards as well as project specific Health & Safety Specifications.</p> <p>The costs included herein must incorporate Community Liaison Officer (CLO).</p>			
	Carried to Collection		R	
	Section 1			
	Bill No. 2			
	Health and Safety			

<u>OCCUPATIONAL HEALTH AND SAFETY</u>				
<u>General:</u>				
1	Preparation of Contractor's site specific Health and Safety Plan.		Item	
2	Submission of the Health and Safety File.		Item	
3	Principal Contractor's initial obligations in respect of the OHS Act and Construction Regulations.		Item	
4	Principal Contractor's time related obligations in respect of the OHS Act and Construction Regulations for the entire construction period.		Item	
5	Provision of full time Health and Safety Officer for the entire construction period.		Item	
6	Induction training of personnel.	No	1	
7	Provision of first aid boxes.	No	1	
<u>Provision for Personal Protective Equipment and Protective Clothing:</u>				
8	Reflective vests.	No	1	
9	Reflective vests - SMME's.	No	1	
10	Hard hats.	No	1	
11	Hard hats - SMME's.	No	1	
12	Protective foot wear.	No	1	
13	Protective foot wear - SMME's.	No	1	
14	Ear Plugs.	No	1	
15	Ear Plugs - SMME's.	No	1	
16	Dust Masks.	No	1	
17	Dust Masks - SMME's.	No	1	
Carried to Collection			R	
Section 1 Bill No. 2 Health and Safety				

[illegible]

[illegible]

[illegible]

Item No		Quantity	Rate	Amount	
	<p><u>SECTION 2</u></p> <p><u>BILL No. 1</u></p> <p><u>DEMOLITIONS</u></p> <p><u>MODEL PREAMBLES</u></p> <p>The tenderer is referred to the "General Preambles for Trades 2017" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates.</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>View site</u></p> <p>Before submitting his tender the tenderer shall visit the site and satisfy himself as to the nature and extent of the work to be done and the value of the materials contained in the buildings or portions of the buildings to be demolished. No claim for any variations of the contract sum in respect of the nature and extent of the work or of inferior or damaged materials will be entertained</p> <p><u>Explosives</u></p> <p>No explosives whatsoever may be used for demolition purposes unless otherwise stated.</p> <p><u>General</u></p> <p>Water supply pipes and other piping in ground that may be encountered and found necessary to disconnect or cut, shall be effectually stopped off or grubbed up and removed, and any new connections that may be necessary shall be made with proper fittings to the satisfaction of the principal agent.</p> <p>Unless otherwise described all materials are to become the property of the contractor and are to be removed from the site.</p>				
	Carried to Collection		R		
	Section 2				
	Bill No. 1				
	Demolitions				

All preparatory work, alterations, etc., to existing asbestos cement roof sheeting, gutters, rainwater pipes, etc., is to be carried out strictly by an approved and certified specialist company and in accordance with statutory requirements (Occupational Health and Safety Act, 1993 - Asbestos Regulations 2001) and all necessary precautions must be taken when working with and disposing of asbestos cement products and the disposal of waste water resulting from cleaning operations, etc.

The removal of asbestos shall be carried out by a certified entity, registered in accordance with the Occupational Health and Safety Act, 1993 and the Asbestos Regulations 2001

Corresponding disposal certificates shall be issued by the facility at which the asbestos is disposed off, with said facility to, prior to the disposal of any asbestos material provide satisfactory proof that the facility is duly registered and fully compliant in terms of the act, to receive the asbestos material

The cost for complying with the above, and all requirements of regulation as reflected above is to be priced for in terms for removal of asbestos material. No further claims in this regard will therefore be entertained

R

-33-

DESLUDGING EXISTING TOILETS

1 | Issue of Certificate of Waste Disposal.

DEMOLISHING AND REMOVING

2	Backfill existing hole with G7 fill material in max. 150mm layers and compact to 95% MOD AASHTO density.
---	--

m3

Item

104

3 Allow for compaction tests by an approved laboratory to determine density of filling material.

No

5

4	Provision of a certificate of safe disposal for asbestos.
---	---

Item

Carried to Collection

R

Section 2
Bill No. 1
Demolitions

[illegible]

Item No		Quantity	Rate	Amount
	<p><u>SECTION 3</u></p> <p><u>BILL No. 1</u></p> <p><u>EARTHWORKS (PROVISIONAL)</u></p> <p><u>MODEL PREAMBLES</u></p> <p>The tenderer is referred to the "General Preambles for Trades 2017" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates.</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Proprietary products in descriptions:</u></p> <p>Proprietary products shall be used as specified. Substitute products of similar quality and specification may only be used with prior approval by the Principal Agent.</p> <p><u>Nature of material to be excavated:</u></p> <p>The material to be excavated is assumed to be predominantly of a composition that will allow excavation in "earth" as specified, but including a percentage of excavation in "soft rock" and "hard rock".</p> <p><u>Carting away of excavated material:</u></p> <p>Descriptions of carting away of excavated material shall be deemed to include loading excavated material onto trucks directly from the excavations, or alternatively, from stock piles situated on the building site.</p> <p><u>Dewatering of excavations:</u></p> <p>The Contractor shall allow for removing seepage and other water from subterranean sources from the excavations by pumping, baling or otherwise. Accurate records of all such dewatering shall be kept to determine the total volume of water so removed and a clear distinction shall be made between water from subterranean sources and other water</p>			
	Carried to Collection		R	
	<p>Section 3</p> <p>Bill No. 1</p> <p>Earthworks (Provisional)</p>			

	<p><u>Density testing on filling:</u></p> <p>Rates for filling, etc. shall include for all density and soil type testing to prove that the specified compaction is achieved. When additional testing is done on instruction of the Principal Agent and these tests are successful, they will be paid for additionally.</p> <p><u>Imported fill:</u></p> <p>"Filling and bedding to trenches etc. to be in compliance with SABS 1200 DB and LB respectively"</p> <p><u>Classification of excavated material</u></p> <p>"Hard rock" shall mean granite, quartzitic sandstone or other rock of similar hardness, the removal of which requires drilling, wedging and splitting or the use of explosives.</p> <p>"Soft rock" shall mean hard material, the removal of which warrants the use of pneumatic tools and includes hard shale, ferricite, compact outcrop and material of similar hardness.</p> <p>"Earth" shall mean all ground other than that classified as "hard rock" or "soft rock" and shall include made-up ground and any loose stones or pieces of concrete not exceeding 0,03m³ in volume.</p>				
	Carried to Collection		R		
	<p>Section 3 Bill No. 1 Earthworks (Provisional)</p>				

EXCAVATION OTHER THAN BULK

Excavation in earth not exceeding 2m deep:

1	Trenches.	m3	83
2	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	43

Extra over trench and hole excavations in earth for excavation in:

3	Soft rock.	m3	9
4	Hard rock.	m3	4

Extra over all excavations for carting away:

5	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the contractor.	m3	58
---	---	----	----

Risk of collapse of excavations:

6	Sides of trench and hole excavations not exceeding 1,5m deep.	m2	232
---	---	----	-----

Keeping excavations free of water:

7	Keeping excavations free from mud and all water including subterranean sources.	Item
---	---	------

Carried to Collection

Section 3
Bill No. 1
Earthworks (Provisional)

R

<u>EARTH FILLING, ETC.</u>				
<u>Earth filling obtained from the excavations and / or prescribed stock piles on site (minimum G7 tested material) compacted to 93% Mod. AASHTO density:</u>				
8	Backfilling to trenches, holes, etc.	m3	55	
<u>Imported G7 filling, selected and supplied by the Contractor, including depositing in layers not exceeding 150mm thick and compacting to 98% modified AASHTO dry density to holes, trenches etc.</u>				
9	Under floors, etc.	m3	103	
<u>Coarse river sand filling supplied by the contractor:</u>				
10	Under floors etc.	m3	26	
<u>Compaction of surfaces:</u>				
11	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density.	m2	158	
<u>Prescribed density tests on filling:</u>				
12	Allow for compaction tests by an approved laboratory to determine density of filling material.	No	35	
<u>SOIL POISONING</u>				
<u>Approved brand of anti-termite soil poison applied by a Registered Pest Control company and guaranteed against termite infestation for ten years:</u>				
13	Under floors, etc., including forming and poisoning shallow furrows against foundation walls, etc., filling in furrows and ramming.	m2	108	
14	To bottoms and sides of trenches, holes, etc.	m2	311	
Carried to Collection				R
Section 3 Bill No. 1 Earthworks (Provisional)				

Section 3 Bill No. 1 Earthworks (Provisional) <u>COLLECTION</u> Total Brought Forward from Page No.					
<p style="text-align: right;">Carried Forward to Summary of Section No. 3</p> Section 3 Bill No. 1 Earthworks (Provisional)					

Item No		Quantity	Rate	Amount
	<p><u>BILL No. 2</u></p> <p><u>CONCRETE, FORMWORK AND REINFORCEMENT</u></p> <p><u>MODEL PREAMBLES</u></p> <p>The tenderer is referred to the "General Preambles for Trades 2017" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates.</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Proprietary products in descriptions:</u></p> <p>Proprietary products shall be used as specified. Substitute products of similar quality and specification may only be used with prior approval by the Principal Agent.</p> <p><u>Cost of tests:</u></p> <p>The costs of making, storing and testing of concrete test cubes as required under clause 7 'Tests' of SABS 1200 G shall include the cost of providing cube moulds necessary for the purpose, for testing costs and for submitting reports on the tests to the Architect. The testing shall be undertaken by an independent firm or institution nominated by the Contractor to the approval of the Architect. (Test cubes are measured separately).</p> <p><u>Formwork:</u></p> <p>Descriptions of formwork shall be deemed to include use and waste only (except where described as left in or permanent), for fitting together in the required forms, wedging, plumbing and fixing to true angles and surfaces as necessary to ensure easy release during stripping and for reconditioning as necessary before re-use.</p>			
	Carried to Collection		R	
	<p>Section 3</p> <p>Bill No. 2</p> <p>Concrete, Formwork and Reinforcement</p>			

	<p>The vertical strutting shall be carried down to such construction as is sufficiently strong to afford the required support without damage and shall remain in position until the newly constructed work is able to support itself.</p> <p>Formwork to soffits of solid slabs etc., shall be deemed to be to slabs not exceeding 250mm thick unless otherwise described.</p> <p>Formwork to sides of bases, pile caps, ground beams, etc., will only be measured where it is prescribed by the Engineer for design reasons. Formwork necessitated by irregularity or collapse of excavated faces will not be measured and the cost thereof shall be deemed to be included in the allowance for taking the risk of collapse of the sides of the excavations, provision for which is made in Earthworks.</p>			
	<p style="text-align: right;">Carried to Collection</p>		<p style="text-align: center;">R</p>	
	<p>Section 3 Bill No. 2 Concrete, Formwork and Reinforcement</p>			

<u>UNREINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES</u>				
<u>15Mpa/19mm Concrete</u>				
1	Surface blinding under footings and bases.	m3	4	
<u>REINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES</u>				
<u>30MPa/20mm concrete:</u>				
2	Strip footing to walls.	m3	31	
3	Surface beds on waterproofing.	m3	12	
<u>TEST BLOCKS</u>				
<u>Test blocks:</u>				
4	Making and testing of 150x150x150mm concrete strength test cubes (Provisional).	No	24	
<u>FINISHING TOP SURFACE OF CONCRETE</u>				
<u>Finishing top surfaces of concrete smooth with a wood float:</u>				
5	Surface beds, suspended slabs, ground slabs, etc.	m2	108	
<u>ROUGH FORMWORK (DEGREE OF ACCURACY III)</u>				
<u>Rough Formwork to Sides:</u>				
6	Edges, risers, ends and reveals not exceeding 300mm high or wide.	m	91	
Carried to Collection			R	
Section 3 Bill No. 2 Concrete, Formwork and Reinforcement				

SMOOTH FORMWORK (DEGREE OF ACCURACY I)

Smooth Formwork to Sides:

7	Edges, risers, ends and reveals not exceeding 300mm high or wide.	m2	45
---	---	----	----

MOVEMENT JOINTS ETC

Two layers of 375 micron damp proof course in slip joints between horizontal concrete and brick surfaces including cement mortar bed (Provisional)

8	Not exceeding 300mm wide.	m	133
---	---------------------------	---	-----

Saw cut joints:

9	6 x 40mm Saw cut joints in top of concrete (Provisional).	m	69
---	---	---	----

REINFORCEMENT (PROVISIONAL)

10	High tensile steel reinforcement bars to structural concrete work.	t	1.49
----	--	---	------

Fabric reinforcement:

11	REF. 245 fabric reinforcement in concrete surface beds, raft slabs etc.	m2	108
----	---	----	-----

12	REF. 617 fabric reinforcement in concrete surface beds, raft slabs etc.	m2	107
----	---	----	-----

13	REF. 888 fabric reinforcement in concrete surface beds, raft slabs etc.	m2	82
----	---	----	----

Carried to Collection

Section 3
Bill No. 2
Concrete, Formwork and Reinforcement

R

Section 3 Bill No. 2 Concrete, Formwork and Reinforcement <u>COLLECTION</u> Total Brought Forward from Page No.					
<p style="text-align: right;">Carried Forward to Summary of Section No. 3</p> Section 3 Bill No. 2 Concrete, Formwork and Reinforcement					

Item No		Quantity	Rate	Amount	
	<p><u>BILL No. 3</u></p> <p><u>MASONRY</u></p> <p><u>Quantity Split:</u></p> <p>Note that the total quantity per each item is split into the various buildings and appears below each description as follows:</p> <p>A0 - DWG 04 - Staff Ablutions A1 - DWG 06 - Grade R Ablutions A6 - DWG 14 - Male Ablutions AD - DWG 35 - Female Ablutions</p> <p><u>MODEL PREAMBLES</u></p> <p>The tenderer is referred to the "General Preambles for Trades 2017" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates.</p> <p>All references to SABS shall be deemed to be the relevant SANS specification</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>BRICKWORK</u></p> <p><u>Sizes in descriptions</u></p> <p>Where sizes in descriptions are given in brick units, "one brick" shall represent the length and "half brick" the width of a brick</p> <p><u>Hollow walls etc</u></p> <p>Descriptions of hollow walls shall be deemed to include leaving every fifth perpend of the bottom course of the external skin open as a weep hole.</p>				
	Carried to Collection		R		
	<p>Section 3 Bill No. 3 Masonry</p>				

	<p>Walls in two skins described as "bagged and sealed" shall be deemed to include having the outer face of the inner skin bagged with 1:6 cement and sand mixture and sealed with two coats "Brixal" bitumen emulsion waterproofing coating.</p> <p><u>Face bricks</u></p> <p>Bricks shall be ordered timeously to obtain uniformity in size and colour</p> <p><u>Pointing</u></p> <p>Descriptions of recessed pointing to fair face brickwork and face brickwork shall be deemed to include square recessed, hollow recessed, weathered pointing, etc</p> <p><u>Samples</u></p> <p>Samples of all masonry building units, except those of walls described as "loadbearing", shall consist of a minimum of 6 units. Samples of building units to be used in walls described as "loadbearing" shall consist of 30 units from every 30 000 units delivered to site</p> <p><u>Trade names</u></p> <p>Where trade names are specified it will read "or equal approved"</p>				
	<p style="text-align: right;">Carried to Collection</p>		R		
	<p>Section 3 Bill No. 3 Masonry</p>				

<u>BRICKWORK IN FOUNDATIONS</u> <u>(PROVISIONAL)</u>					
<u>Brickwork of NFX bricks (14 MPa nominal compressive strength) in Class I mortar:</u>					
1	One brick walls.	m2	45		
<u>BRICKWORK IN SUPER STRUCTURE</u> <u>(PROVISIONAL)</u>					
<u>Brickwork of NFX bricks (14 MPa nominal compressive strength) in Class I mortar:</u>					
2	Half brick walls.	m2	28		
3	One brick walls.	m2	171		
<u>BRICKWORK AND BLOCKWORK SUNDRIES</u>					
<u>Galvanized brickwork reinforcement</u>					
4	115mm Wide reinforcement built in horizontally	m	81		
5	230mm Wide reinforcement built in horizontally.	m	502		
6	Ditto, but in foundations (Provisional).	m	131		
<u>Cramps, ties, etc:</u>					
7	30 x 2mm Galvanized roof tie 1500mm long with one end fixed to timber and other built into brickwork or concrete.	No	52		
<u>Air bricks etc:</u>					
8	229 x 152mm terracotta clay vermin proof air brick	No	18		
<u>Bagging and sealing the outer face of the inner skin of walls with 1:3 cement and sand mixture and seal with two coats "Brixal" bitumen emulsion waterproofing coating:</u>					
9	To walls (Provisional).	m2	249		
<p style="text-align: center;">Carried to Collection</p> <p>Section 3 Bill No. 3 Masonry</p>				R	

	<u>Samples</u>				
10	Prepare and construct for approval L-Shaped one brickwall faced and pointed both sides as per given specification, size: 1000x1000x1000mm high. same area (1000x1000mm) to be paved as per given specifications.		Item		
	<u>Turning pieces to lintels etc</u>				
11	230mm Wide turning pieces	m	20		
	<u>FACE BRICK</u>				
	<u>"Rustgold FBS/Qunu Travertine" clay face brick or equal approved, size 222 x 106 x 73mm, bedded and jointed in Class II mortar and pointed with recessed vertical and recessed horizontal joints, suitable for exposure zones 1-2:</u>				
12	Extra over brickwork for face brickwork externally.	m2	250		
13	Half brick wall in beam filling pointed one side including cutting and fitting around roof timbers and bedding roofing solid on top in cement mortar.	m2	23		
14	One brickwall pointed on both sides.	m2	150		
15	Half brickwall pointed on both sides.	m2	59		
16	Fair raking cutting.	m	28		
	<u>Face brick copings, lintels, sills, etc, of "Rustgold FBS/Qunu Travertine" or equal approved face bricks pointed with recessed joints on all exposed faces:</u>				
17	220mm Brick on edge sill bedded sloping and jointed in cement mortar and pointed on top, edge and projecting soffit including cutting and fitting between reveals and splay cutting brickwork under.	m	50		
18	220mm Wide header course to top of one brick wall bedded and jointed in cement mortar and pointed on both sides.	m	25		
	Carried to Collection			R	
	Section 3				
	Bill No. 3				
	Masonry				

[illegible]

Item No		Quantity	Rate	Amount
	<p><u>BILL No. 4</u></p> <p><u>WATERPROOFING</u></p> <p><u>MODEL PREAMBLES</u></p> <p>The tenderer is referred to the "General Preambles for Trades 2017" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates.</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Proprietary products in descriptions:</u></p> <p>Proprietary products shall be used as specified. Substitute products of similar quality and specification may only be used with prior approval by the Principal Agent.</p> <p><u>Waterproofing</u></p> <p>The product and its methodology for application must be approved by Principal Agent before it is used.</p> <p>It is a mandatory requirement for the Contractor to attend training to be provided by Supplier. Proof of attendance will be required prior to application of the approved waterproofing product.</p> <p>Contractor must prepare a 1m x 1m sample in the presence of the Principal Agent or Engineer. In this case, the Contractor must give at least 48 hours notice prior to the date when the application of the waterproofing product is intended to be done.</p> <p>Contractor to provide a Letter of Compliance confirming that waterproofing has been applied as per Manufacturer's instructions and data sheet.</p> <p><u>DAMPPROOFING OF WALLS AND FLOORS</u></p>			
	Carried to Collection		R	
	<p>Section 3</p> <p>Bill No. 4</p> <p>Waterproofing</p>			

One layer of 250 micron 'USB GREEN' waterproof sheeting sealed at laps with 'Gunplas Pressure Sensitive Tape':

One layer of 350 micron embossed dampcourse waterproof sheeting below walls, sills, etc:

JOINT SEALANTS ETC

Clear Neutral silicone sealant:

Two-part grey polysulphide sealing compound including backing cord, bond breaker, primer, etc

4	10 x 12mm In movement joints in floors or walls including raking out expansion joint filler as necessary (Provisional).	m	69
---	---	---	----

Carried to Collection

Section 3
Bill No. 4
Waterproofing

R

[illegible]

Item No		Quantity	Rate	Amount	
	<p><u>BILL No. 5</u></p> <p><u>ROOF COVERINGS</u></p> <p><u>MODEL PREAMBLES</u></p> <p>The tenderer is referred to the "General Preambles for Trades 2017" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates.</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Flashings</u></p> <p>Flashings shall be approved by roof sheeting manufacturer and fixed to the sheeting with S10 clips to obviate any direct fixing perforations. Prior to flashings being fixed, all troughs at the apex shall be stop-ended to the full depth of the sheet in order to prevent any penetration of wind driven water. The trough shall be lipped at the eaves end to form a drip. Flashing flanges shall be notched to the sheet profile where necessary. All these operations must be performed with special tools available from the manufacturer. Care shall be taken to ensure that no sheeting or flashing will be cut with abrasive disc on roof surface in order to prevent steel splatter from penetrating colour coated areas. The flashings shall be supplied with a paint finish consisting of a full top coat silicon modified polyester Colour : White to one side</p> <p><u>Quality Assurance</u></p> <p>The manufacturer shall be assessed and certified as complying with ISO 9001: 2008 Quality Management System</p> <p><u>Guarantee</u></p> <p>Z200 Galvanized Metal or equal approved sheeting shall be laid in strict accordance with manufacturer's specifications by an approved contractor. The employer shall be provided with a ten year written guarantee on materials by the manufacturer.</p>				
	Carried to Collection		R		
	<p>Section 3</p> <p>Bill No. 5</p> <p>Roof Coverings Etc.</p>				

	<p><u>Safety</u></p> <p>The contractor shall exercise special care when handling long length sheeting, particularly in windy conditions. Should work be interrupted for any reason, all loose sheeting and incomplete sections must be adequately secured against possible movement by wind and gravity</p> <p><u>Handling and Storage</u></p> <p>The contractor shall ensure that all materials used on site for cladding, etc are transported, handled and stored in accordance with the manufacturer's recommendations. Material damaged shall be rejected and replaced with undamaged material at the contractor's expense. Repair of damaged material will not generally be permitted. Rates are to include for preventing damage and protecting sheets through all stages of construction</p> <p><u>Inspection Prior to Installation or Erection</u></p> <p>Before commencing with installation, the contractor shall verify that the following items have been checked and accepted:</p> <ul style="list-style-type: none"> a. The entire structure or the portion thereof to be sheeted has been correctly aligned, levelled and grouted b. Purlins and sheeting rails are at the correct spacing and are within the specified tolerances c. The corners of the roof are square and the wall framework is perpendicular or as specified d. No protrusions such as bolt heads, splice plates, cleats, etc. appear on the face of the framework e. All members to which roofing and cladding are to be fixed in aesthetically sensitive areas are true and square f. Paint and any other materials that may be incompatible with the sheeting, have been painted over or so dealt with that direct contact with the sheeting is avoided g. The contact faces between the purlins or the girts and the cladding are in the same plane. Should the alignment be inadequate, the contractor shall request instructions from the engineer before proceeding with the fixing of the cladding 				
	<p>Carried to Collection</p>		<p>R</p>		
	<p>Section 3 Bill No. 5 Roof Coverings Etc.</p>				

	<p><u>Protrusion through Sheeted Surfaces</u></p> <p>Protrusions such as pipes, ducts and the like, shall be adequately flashed where they pass through the sheeting surface. Where ribs have to be cut away to permit penetration, additional framing is to be installed as required to support the sheeting. Depending on the position of the penetration through the roof, special attention shall be given to back flashing the sheeting to the ridge or point of water entry. In all cases, all cutting and flashings shall be so arranged that adequate provision is made for the drainage of all troughs and corrugation</p> <p><u>Cleaning of Roofs, etc</u></p> <p>All debris, etc arising from the fixing of the cladding shall be removed from the sheetin as the fixing progresses. In addition, off-cuts of insulation, surplus fastners and sealants, mandrels from pop rivets, off-cuts of flashings and sheeting, surplus flashing, food packaging, cartons, bottles, cans, etc shall not be left on the roof or in the gutters. Care shall be taken to ensure that no such material enters, blocks or partially impedes the flow of water into the outlets, downpipes, etc</p>			
	<p style="text-align: right;">Carried to Collection</p>		<p style="text-align: right;">R</p>	
	<p>Section 3 Bill No. 5 Roof Coverings Etc.</p>			

ROOF COVERINGS

PROFIED METAL SHEETING AND ACCESSORIES

0,58mm Thick Z200 "IBR Profile" galvanised metal roof sheeting, in single sheet lengths, with "Chromadek" finish to external face and standard backing coat to internal face :

- | | | | |
|---|--|----|-----|
| 1 | Roof sheeting laid to a mono-pitch. | m2 | 135 |
| | <u>0.58mm Flashings pre-painted to match roof sheeting and fixed in strict accordance with manufacturer's instructions:</u> | | |
| 2 | Mono pitched ridge capping with 225mm lapping secured onto the roof. | m | 34 |

ROOF AND WALL INSULATION

"Sisalation Grade FR430" or equal approved heavy industrial insulation

- | | | | |
|---|--|----|-----|
| 3 | Insulation laid taut over roof trusses (at approximately 1 100mm centres) and fixed concurrent with SA Pine purlins at 900mm centres, etc including galvanised steel straining wires | m2 | 135 |
|---|--|----|-----|

Carried to Collection

Section 3
Bill No. 5
Roof Coverings Etc.

R

[illegible]

Item No		Quantity	Rate	Amount	
	<p><u>BILL No. 6</u></p> <p><u>CARPENTRY & JOINERY</u></p> <p><u>MODEL PREAMBLES</u></p> <p>The tenderer is referred to the "General Preambles for Trades 2017" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates.</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>FIXING</u></p> <p>All nailing of timber roof rafters, purlins, etc shall be done with galvanised nails. In coastal areas, copper, aluminium or stainless steel nails shall be used.</p>				
	Carried to Collection		R		
	<p>Section 3</p> <p>Bill No. 6</p> <p>Carpentry and Joinery</p>				

<u>CARPENTRY</u>					
<u>Sawn softwood:</u>					
1	38 x 114mm Wall plate.	m	94		
2	50 x 76mm Purlins.	m	193		
3	50 x 76mm Bracing.	m	48		
4	38 x 152mm Rafters.	m	115		
5	30 x 90mm rafter laid flat as coping on top of brickwall.	m	33		
<u>Sundries:</u>					
6	TRI FIX or equal approved hurricane clip fixed using 10 x 32mm galvanised clout nails (Provisional).	No	172		
<u>EAVES, VERGES, ETC</u>					
<u>"Everite Nutec" or equal approved fibre cement</u>					
7	12 x 225mm Fascia board drilled and brass screwed to rafter feet including galvanised steel H-profile jointing strips, etc.	m	67		
8	85 x 275 x 6mm Barge board drilled and brass screwed to purlin ends including galvanised steel H-profile jointing strips, screws, holes, etc.	m	32		
<p style="text-align: center;">Carried to Collection</p> <p>Section 3 Bill No. 6 Carpentry and Joinery</p>				R	

Section 3
Bill No. 6
Carpentry and Joinery

R

[illegible]

BILL No. 7

IRONMONGERY

MODEL PREAMBLES

SUPPLEMENTARY PREAMBLES

Keys/Locks

Trade Names

Fixing

Carried to Collection

Section 3
Bill No. 7
Ironmongery

**QIBIRA PRIMARY SCHOOL
THE MVULA TRUST FLUSH MAINTENCE PROGRAMME**

<u>HINGES:</u>				
1	75 x 100mm Brass Medium duty ball bearing HMP butt hinges.	Pairs	54.0	
<u>LOCKS</u>				
2	"UNION 2277-78SS" or equal approved three lever sash mortice lockset.	No	7	
3	"UNION w/c indicator bolt satin chrome - Code CZ80941SC	No	13	
4	"E1511 Erebus HD Adjustable" or equal approved roller catch SC	No	3	
<u>HANDLES</u>				
5	"Dorma DPH301B" or equal approved Stainless Steel Straight Tubular Pull handle flange fixing.	No	3	
6	"Dorma DPH301C" or equal approved Stainless Steel Tubular Pull handle flange fixing.	No	3	
7	"Union CZ682-24SC" or equal approved radius lever handle.	No	5	
<u>Sundries:</u>				
8	Stainless Steel Hat and coat hook, code DHC - SS-030-A or equal approved.	No	18	
9	38mm Diameter black rubber door stop plugged and screwed to wall.	No	21	
<u>SIGN PLATES:</u>				
<u>All sign plates are to be with engraved blue perspex all in accordance with the standard sign plates for Schools.</u>				
10	Sign plate plugged and screwed to walls with chromium plated dome headed screws.	No	21	
Carried to Collection			R	
Section 3 Bill No. 7 Ironmongery				

[illegible]

[illegible]

Item No		Quantity	Rate	Amount
	<p><u>BILL No. 8</u></p> <p><u>METALWORK</u></p> <p><u>MODEL PREAMBLES</u></p> <p>The tenderer is referred to the "General Preambles for Trades 2017" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates.</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p>The Contractor is to check and verify on site that the item specified in the BoQ matches existing prior to placing orders. Additional costs will not be borne by the client for items that do not match existing and are not approved by the Principal Agent</p> <p><u>ALUMINIUM WINDOWS</u></p> <p>All aluminium windows are to be manufactured by manufacturers who are members of AAAMSA. All aluminium systems to be approved by AAAMSA.</p> <p>All aluminium work is to be protected by covering with plastic sheeting fixed with low tack adhesive prior to leaving the factory. Plastic sheeting is to remain in place during construction.</p> <p>All glazing shall be in accordance with SABS 0400 - 1990, SABS 1263 - 1. All safety glazing materials (individual panes) shall be permanently marked. Such marking shall be visible after glazing process. If it is not marked, it is not safety glass.</p> <p><u>Natural anodised aluminium windows glazed with 6.38mm safety laminated glass and plugged to brickwork:</u></p>			
1	Window Size 600 x 600mm high complete, including ironmongery etc, all as per Window Type W01.	No	38	
	<p style="text-align: right;">Carried Forward to Summary of Section No. 3</p> <p>Section 3 Bill No. 8 Metalwork</p>		R	

[illegible]

Item No		Quantity	Rate	Amount
	<p><u>SECTION No. 3</u></p> <p><u>BILL No. 1</u></p> <p><u>EXTERNAL WORKS (PROVISIONAL)</u></p> <p><u>MODEL PREAMBLES</u></p> <p>The tenderer is referred to the "General Preambles for Trades 2017" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates.</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>uPVC pipes and fittings</u></p> <p>Soil, waste and vent pipes and fittings shall be solvent weld jointed.</p> <p>Sewer and drainage pipes and fittings shall be jointed and sealed with butyl rubber rings.</p> <p><u>Excavations:</u></p> <p>No claim for rock excavation will be entertained unless the Contractor has timeously notified the quantity surveyor thereof prior to backfilling.</p> <p>Soft rock and hard rock shall be as defined in Earthworks.</p> <p><u>Laying, backfilling, bedding, etc of pipes:</u></p> <p>Pipes shall be laid and bedded and trenches shall be carefully backfilled in accordance with manufacturers' instructions.</p>			
	Carried to Collection		R	
	Section 4			
	Bill No. 1			
	External Works			

1	<p>Where no manufacturers' instructions exist pipes shall be laid in accordance with clauses 5.1 and 5.2 of each of the following:</p> <p>SABS 1200</p> <p>L : Medium pressure pipelines</p> <p>LD : Sewers</p> <p>LE : Stormwater drainage Pipe trenches etc shall be backfilled in accordance with clause 3, 5.5, 5.6, 5.7 and 7 of SABS 1200</p> <p>DB: Earthworks (Pipe trenches) Clause 5.7.2 will only be applicable if authorised by the Engineer in writing.</p> <p><u>Descriptions of pipes laid in trenches:</u></p> <p>Descriptions of pipes laid in and including trenches and of inspection chambers, catch pits, etc shall be deemed to include excavation, bedding, backfilling, compaction to a minimum of 95% Mod AASHTO density and disposal of surplus material on site</p> <p><u>Descriptions of catchpits, junction boxes, manholes, etc:</u></p> <p>Descriptions of catchpits, junction boxes, manholes, etc, shall be deemed to include for compaction, disposal of surplus excavated material to a dumping site located by the contractor, risk of collapse and keeping excavations free from water.</p> <p><u>Density testing on filling:</u></p> <p>Rates for filling, etc. shall include for all density and soil type testing to prove that the specified compaction is achieved. When additional testing is done on instruction of the Principal Agent and these tests are successful, they will be paid for additionally.</p> <p><u>THE FOLLOWING IN PLATFORMS, ETC.</u></p> <p><u>Prescribed density tests on filling:</u></p> <p>Modified AASHTO Density test.</p> <p><u>THE FOLLOWING IN DISABLED ACCESS</u></p> <p><u>SCREEN WALL</u></p> <p style="text-align: right;">Carried to Collection</p> <p>Section 4 Bill No. 1 External Works</p>	No	7	R	

Carried to Collection

11	<p>Brick-on-edge header course copings, sills, etc, of "Rustgold FBS/Qunu Travertine" or equal approved face bricks pointed with recessed joints on all exposed faces, 220mm wide sill set sloping and slightly projecting:</p> <p>230mm wide header course to top of one brick wall bedded and jointed in cement mortar and pointed on top and both sides as described.</p>	m	22	
	<p style="text-align: right;">Carried to Collection</p> <p>Section 4 Bill No. 1 External Works</p>		R	

ACCESS RAMPS

Prescribed density tests on filling:

12	In-situ dry density test.	No	6
----	---------------------------	----	---

Reinforced 25Mpa/19mm Concrete:

13	Ramps, Landings, etc.	m3	2
----	-----------------------	----	---

Test blocks:

14	Making and testing of 150x150x150mm concrete strength test cubes (Provisional).	No	6
----	---	----	---

Expansion joints with bitumen impregnated softboard between vertical concrete or brick surfaces:

15	12mm Joints not exceeding 300mm high.	m	27
----	---------------------------------------	---	----

Two-part grey polysulphide sealing compound including backing cord, bond breaker, primer, etc

16	10 x 12mm In movement joints in floors or walls including raking out expansion joint filler as necessary.	m	27
----	---	---	----

17	REF. 888 fabric reinforcement in concrete surface beds, raft slabs etc.	m2	28
----	---	----	----

Waterproofing under Surface beds

18	350 Micron USB orange polyethylene dampproof membrane in accordance with SABS 952 Type C laid on sand bed (elsewhere measured).	m2	28
----	---	----	----

THE FOLLOWING IN WALKWAYS

EARTHWORKS

Excavate in earth not exceeding 2m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away

19	Reduced levels between buildings, retaining walls, etc.	m3	10
----	---	----	----

Carried to Collection

R

Section 4
Bill No. 1
External Works

[illegible]

<p>26</p>	<p><u>Precast concrete kerbing</u></p> <p>Precast semi-mountable concrete Fig 8B edge kerb size 300 x 175mm high cast in lengths not exceeding 1m and with expansion joints at not exceeding 10m centres finished smooth off the mould on all exposed surfaces bedded on and including minimum 50mm thick mass concrete 15 MPa base and backing including all necessary excavation, formwork, expansion joints, etc.</p> <p style="text-align: right;">m</p>	<p>76</p>		
	<p style="text-align: right;">Carried to Collection</p>		<p>R</p>	
	<p>Section 4 Bill No. 1 External Works</p>			

<u>THE FOLLOWING IN BULK WATER RETICULATION</u>				
<u>ALTERATIONS TO EXISTING</u>				
27	Locate, cut into and temporarily stop off 40mm diameter water pipe for insertion of stop end (elsewhere).	No	2	
28	Locate, cut into and temporarily stop off 54mm diameter water pipe for insertion of Tee Junction (elsewhere).	No	1	
<u>HDPE 100PN 12.5 pressure pipes:</u>				
29	25mm pipes laid in depths not exceeding 1m including excavation, bedding, backfilling, compaction and disposal of surplus material.	m	146	
<u>Extra over (PN12.5) HDPE piping for fittings:</u>				
30	25mm Bend.	No	4	
31	25mm Tee.	No	2	
<u>TAPS, VALVES, ETC</u>				
32	25mm "Cobra" Ball Valve complete with adaptors for HDPE pipe.	No	4	
33	25mm Non-return valve.	No	1	
<u>Water supply valve or meter chambers</u>				
34	Excavate for and build valve chamber size 460 x 460 x not exceeding 1000mm deep internally, formed of 300mm thick layer of well backfilling , 200mm high half brick corbelled sides with 75mm brickforce between each course including Type 3A cast iron valve cover and frame size 100 x 230 x 300 encased in a 300mm thick 25mpa mass concrete base.	No	2	
<u>Sundries:</u>				
<u>Connection</u>				
35	Allow for connecting to the main water supply.		Item	5 000.00
<u>Testing:</u>				
36	Testing water pipe system.		Item	
Carried to Collection				R
Section 4 Bill No. 1 External Works				

<u>THE FOLLOWING IN STORMWATER DRAINAGE, APRONS ETC.</u>				
<u>STORMWATER APRONS</u>				
<u>Excavation not exceeding 2m deep</u>				
37	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	9	
<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>				
38	Off site to a dumping site to be found by the Contractor.	m3	9	
<u>Filling supplied by the contractor under floors, aprons, etc</u>				
39	G7 Base course material compacted to 98% Mod AASHTO density	m3	9	
<u>Coarse river sand filling supplied by the contractor:</u>				
40	Under floors etc.	m3	2	
<u>Compaction of surfaces:</u>				
41	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density.	m2	37	
<u>Prescribed density tests on filling:</u>				
42	In-situ dry density test.	No	8	
<u>Reinforced 25Mpa/19mm Concrete:</u>				
43	Surface beds cast in panels on waterproofing.	m3	5	
<u>Finishing top surfaces of concrete smooth with a wood float:</u>				
44	Surface beds, slabs, etc to falls and currents.	m2	37	
Carried to Collection			R	
Section 4 Bill No. 1 External Works				

Test blocks:

45	Making and testing of 150x150x150mm concrete strength test cubes (Provisional).	No	12
----	---	----	----

Expansion joints with bitumen impregnated softboard
between vertical concrete or brick surfaces:

46	12mm Joints not exceeding 300mm high.	m	64
----	---------------------------------------	---	----

Two-part grey polysulphide sealing compound including backing cord, bond breaker, primer, etc

47	10 x 12mm In movement joints in floors or walls including raking out expansion joint filler as necessary.	m	64
----	---	---	----

Fabric reinforcement:

48	REF. 888 fabric reinforcement in concrete surface beds, raft slabs etc.	m2	37
----	---	----	----

Waterproofing under Surface beds

49	350 Micron USB orange polyethylene dampproof membrane in accordance with SABS 952 Type C laid on sand bed (elsewhere measured).	m2	37
----	---	----	----

Carried to Collection

R

Section 4
Bill No. 1
External Works

<u>STORMWATER CHANNELS</u>					
<u>Excavation not exceeding 2m deep</u>					
50	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	55		
<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>					
51	Off site to a dumping site to be found by the Contractor.	m3	55		
<u>Filling supplied by the contractor under channels</u>					
52	G7 Base course material compacted to 98% Mod AASHTO density	m3	27		
<u>Cast in-situ Ref 395 mesh reinforced concrete (25MPa) open stormwater channels having V-shaped waterway formed in top, finished smooth on all exposed surfaces in 3:1 cement plaster trowelled smooth and with angles rounded, cast in suitable lengths not exceeding 2m, including all formwork, moulds, shallow excavation, filling and ramming, laying to falls, bedding and pointing in 3:1 cement mortar. Concrete apron to be tinted, colour to be specified by the Engineer.</u>					
53	700 x 80mm thick V' channel 150mm deep in centre laid in position in ground not exceeding 2000mm sections including all formwork, reinforcement, expansion joints, smooth finishing to top of concrete surface etc.	m	155		
54	Extra for 700mm angle	No	21		
55	Extra for forming 200mm thick 700mm wide spreader with 200mm high edges fanning out to 1 960mm width at furthest end with hard burnt bricks pitching cast in ass diffusers including working off concrete to a smooth finish and draining onto natural ground with 150 - 200mm diameter loose stones.	No	5		
Carried to Collection				R	
Section 4 Bill No. 1 External Works					

<u>BULK SEWER RETICULATION</u>					
<u>Heavy duty (Class 34) PVC-U sewer and drain pipes</u>					
56	110mm Diameter Class 34 pipe laid in ground to falls on and including Class C bedding (SABS 1200LB) and selected fill blanket, including excavation in compacted earth 750mm wide exceeding 1000mm deep and not exceeding 2000mm deep and backfilling to 90% modified AASHTO density in 150mm layers, including carting away surplus excavated material, risk of collapse, dewatering of trenches, shoring, etc.	m	250		
<u>Extra over heavy duty (Class 34) PVC-U sewer and drain pipes for fittings</u>					
57	110mm Bend	No	2		
58	110mm Rodding eye	No	6		
59	110mm Junction	No	15		
60	160 x 110mm Reducing junction	No	1		
<u>PRE-CAST CONCRETE MANHOLES</u>					
<u>Excavate in earth for and including circular type precast concrete manhole formed of 1000mm diameter x 350mm thick 20Mpa concrete base with manhole formed of 1000mm diameter (internally) precast concrete rings with joints sealed with 1:3 cement to sand grout caulked with and including precast concrete cover slab 160mm thick with opening for and including heavy duty road type manhole cover and lockable frame as type 2A set in cement mortar and sealed in tallow and with 20Mpa concrete benching in bottom floated smooth with falls and finished on all exposed surfaces with 25mm thick granolithic with angles rounded including all necessary excavation, backfilling, carting away, risk of collapse, shoring, dewatering, concrete blinding, formwork, step irons, etc.:</u>					
61	Manhole not exceeding 1500m deep.	No	5		
<u>SUNDRIES</u>					
Carried to Collection				R	
Section 4 Bill No. 1 External Works					

**QIBIRA PRIMARY SCHOOL
THE MVULA TRUST FLUSH MAINTENCE PROGRAMME**

	<u>Earthworks</u>				
62	Selected granular filling Class 'B' supplied by the Contractor in bedding under pipes.	m3	128		
63	Selected 19mm stone supplied by the Contractor in bedding under pipes.	m3	25		
64	300 x 300 x 75mm Pre-cast concrete inspection eye marker slab set in ground.	No	1		
	<u>Connection</u>				
65	Allow for connecting to sewer drainage system		Item		
	<u>Testing:</u>				
66	Testing drainage system.		Item		
	<u>THE FOLLOWING IN RAINWATER TANKS AND STANDS</u>				
	<u>Excavation in earth not exceeding 2m deep:</u>				
67	Trenches.	m3	28		
	<u>Extra over trench and hole excavations in earth for excavation:</u>				
68	Soft rock.	m3	3		
69	Hard rock.	m3	1		
	<u>Extra over all excavations for carting away:</u>				
70	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the Contractor.	m3	13		
	<u>Risk of collapse of excavations:</u>				
71	Sides of trench and hole excavations not exceeding 1,5m deep.	m2	32		
	<u>Earth filling obtained from the excavations and/or prescribed stock piles on site compacted to 93%:</u>				
72	Backfilling to trenches, holes, etc.	m3	16		
	Carried to Collection			R	
	Section 4				
	Bill No. 1				
	External Works				

	<u>Imported G7 filling, selected and supplied by the Contractor, including depositing in layers not exceeding 150mm thick and compacting to 98% modified AASHTO dry density to holes, trenches etc.</u>				
73	Under floors, etc.	m3	5		
	<u>Compaction of surfaces</u>				
74	Compaction of ground surface under floors, etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density.	m2	20		
	<u>25Mpa/19mm Un-reinforced Concrete</u>				
75	Strip footings.	m3	6		
	<u>25 MPa/19mm Concrete:</u>				
76	Tank concrete slab.	m3	2		
	<u>Finishing top surfaces of concrete smooth with a steel trowel including adding additional cement while concrete is still green to attain a smooth, hard surface:</u>				
77	Surface beds, slabs, etc.	m2	20		
	<u>Rough Formwork to Sides (Degree of Accuracy III):</u>				
78	Edges, risers, ends and reveals not exceeding 300mm high or wide.	m	40		
	<u>Allens Meshco Square Mesh Fabric reinforcement:</u>				
79	Type 167 fabric reinforcement in concrete surface beds, slabs, etc.	m2	20		
	<u>Foundation brickwork of NFX bricks (14 MPa nominal compressive strength) in Class I mortar:</u>				
80	One brick walls.	m2	32		
	Carried to Collection			R	
	Section 4				
	Bill No. 1				
	External Works				

	<u>Super Structure brickwork of NFP bricks (14 MPa nominal compressive strength) in Class II mortar:</u>				
81	One brick walls.	m2	21		
82	110mm Wide header course to top of one brick wall in lining to concrete bedded and jointed in cement mortar and pointed on one side.	m	40		
	<u>Brickwork reinforcement:</u>				
83	230mm Wide reinforcement built in horizontally.	m	57		
84	Ditto, but in foundations (Provisional).	m	89		
	<u>"Corobrik Firelight Satin FBX" clay face brick or equal approved, size 222 x 106 x 73mm, bedded and jointed in Class II mortar and pointed with recessed vertical and recessed horizontal joints, suitable for exposure zones 1-2:</u>				
85	Extra over brickwork for face brickwork externally.	m2	21		
	<u>Plastic water tanks etc:</u>				
86	5000 Litre light duty cylindrical tank complete with lid, 15mm brass bibtap with handle suitable for locking and 4 No. galvanised stay wires 2.5m each long connected to tank, with and including 4 No. eye bolts cast into concrete.	No	5		
87	Hole top of tank for 100mm pipe.	No	5		
	<u>THE FOLLOWING IN GROUND STORAGE TANKS</u>				
	<u>EXCAVATIONS, FILLING, ETC.</u>				
	<u>Excavate in earth not exceeding 2m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away</u>				
88	Reduced levels under solid floors.	m3	2		
	<u>Carting away of excavated material</u>				
89	Load surplus or unsuitable material from spoil heaps and cart away to a dumping site to be located by the Contractor.	m3	2		
	Carried to Collection			R	
	Section 4				
	Bill No. 1				
	External Works				

	<u>Risk of collapse of excavations</u>				
90	Allow for risk of collapse to sides of excavations not exceeding 1.5m deep including all necessary timber shoring, etc.	m2	14		
	<u>Keeping excavations free of water</u>				
91	Allow for keeping the excavations free from water.		Item		
92	Imported G5 filling, selected and supplied by the Contractor, including depositing in layers not exceeding 150mm thick and compacting to 98% modified AASHTO dry density under solid floors.	m3	2		
	<u>Compaction of surfaces</u>				
93	Scarify in-situ material to a depth of 150mm and compact to 93% Mod AASHTO density.	m2	32		
	<u>Tests</u>				
94	Allow for Mod AASHTO density tests on filling.	No	3.00		
	<u>CONCRETE (Labour intensive)</u>				
	<u>Reinforced concrete 30MPa (19mm stone) in:</u>				
95	Rafter slabs cast against excavated surfaces.	m3	2		
	<u>Testing</u>				
96	Allow for preparing and curing a set of three test cubes, each size 150mm x 150mm x 150mm and pay all transport and testing costs undertaken by an approved independent laboratory. (Provisional)	Sets	3		
	<u>Surface treatment</u>				
97	Float surface of concrete to a wood float finish.	m2	32		
Carried to Collection				R	
Section 4					
Bill No. 1					
External Works					

	<u>FORMWORK</u>				
	<u>Edges, risers, ends and reveals</u>				
98	Edge, riser, etc exceeding 300mm high.	m2	14		
	<u>Projections, grooves, etc.</u>				
99	Labour and material in forming 25 x 25mm chamfer to exposed top edge of concrete.	m	27		
	<u>REINFORCEMENT (PROVISIONAL)</u>				
	<u>High tensile welded steel mesh reinforcement :</u>				
100	Ref: 395 cast into concrete surfaces.	m2	32		
101	Reinforcement in various sizes.	t	0.2		
	<u>Switch</u>				
102	Float switch fitted inside of tank.	No	3		
	<u>Rainwater tanks:</u>				
103	20 000 Litre polyethylene rotomoulded vertical water storage tank provided complete with lid and overflow outlet, fitted with suitable adaptor and setting in position on concrete tankstand (elsewhere measured). (The tanks are to be filled with water for the Practical Completion inspection)	No	3		
104	Hole through side of tank for 40mm diameter pipe including adaptor.	No	3		
	<u>Ties, cramps, etc.</u>				
105	38 x 1,6mm Galvanised hoop iron strap around tank, both ends fitted with once holed 30 x 30 x 3mm thick galvanised flat plate and bolted together with and including M10 bolt and nut.	No	17		
106	38 x 1,6mm Galvanised hoop iron tie down, 2500mm long, one end wrapped around tank strap and twice bolted, the other end folded over and bolted to top of concrete with and including 8 x 60mm masonry anchor.	No	17		
	Carried to Collection			R	
	Section 4				
	Bill No. 1				
	External Works				

**QIBIRA PRIMARY SCHOOL
THE MVULA TRUST FLUSH MAINTENCE PROGRAMME**

	<u>Water supply valve or meter chambers</u>				
107	Excavate for and build valve chamber size 565 x 665 x 550mm deep overall formed of precast concrete valve chamber units 1, 2, 3 and 4 with valve box lid-V and 19mm thick layer of 19mm stone in bottom including filling in and ramming.	No	3		
	<u>Pump and Pumphouse</u>				
108	Allow the Budgetary Allowance of R 20 000,00 (Twenty Thousand Rand) for the installation of a 0.75kw water pump including housing, etc.		Item		20 000.00
	<u>ELECTRICAL CONNECTION</u>				
	<u>Electrical Works</u>				
109	Allow the Budgetary Allowance of R 30 000,00 (Thirty Thousand Rand) for the electrical supply to the water pumps, float switches, ect.		Item		30 000.00
	<u>SECURITY FENCING</u>				
	The Contractor is to allow in his rates for any site clearance, preparation of ground, etc. in order to carry out the work successfully.				
	<u>"Clearvu" or equally approved fencing products to be executed in strict accordance with the Manufacturer's instructions</u>				
	<u>Fencing</u>				
110	High security galvanised, marine fusion bond coated, mesh fencing panel, size 3350 x 1800mm high fixed to posts (elsewhere).	m	45		
	<u>Posts</u>				
111	Intermediate locking taper post, marine fusion bond coated, 2400mm long, with UV stabilised polymer cap including embedding in 400 x 400 x 600mm (25Mpa) concrete base including all necessary excavations, backfilling, etc.	No	8		
	Carried to Collection			R	
	Section 4				
	Bill No. 1				
	External Works				

End or corner square post, marine fusion bond coated, 2400mm long, with UV stabilised polymer cap including embedding in 400 x 400 x 600mm (25Mpa) concrete base including all necessary excavations, backfilling, etc.

No

4

113	Square gate post, marine fusion bond coated, 2400mm long, with UV stabilised polymer cap and gate mooring bracket including embedding in 400 x 400 x 600mm (25Mpa) concrete base including all necessary excavations, backfilling, etc.
-----	---

No

2

Gates

114	Single gate, size 1000 x 1800mm high overall formed of square section perimeter framing, rails, etc. and the gate covered with high security galvanised, marine fusion bond coated, mesh including locking mechanism, hinges, drop bolts, etc. as per manufacturer's specifications.
-----	--

No

1

Accessories

115	100mm High, marine fusion bond coated, steel shark spikes in 1500mm lengths pre-drilled and bolted to top of fencing panels (elsewhere).
-----	--

m

45

116	"Union 3122" or other approved 51mm brass padlock with stainless steel shackle.
-----	---

No

1

Sundries

117	Extra over excavations in earth (concrete bases) for excavation in soft rock.
-----	---

m3

1

118	Extra over excavations in earth (concrete bases) for excavation in hard rock.
-----	---

m3

1

THE FOLLOWING IN GRADE R SECURITY FENCING, ETC

SECURITY FENCING

The Contractor is to allow in his rates for any site clearance, preparation of ground, etc. in order to carry out the work successfully.

Carried to Collection

R

Section 4
Bill No. 1
External Works

	<p><u>"Clearvu" or equally approved fencing products to be executed in strict accordance with the Manufacturer's instructions</u></p> <p><u>THE FOLLOWING IN SEPTIC TANKS AND SOAK AWAYS, ETC</u></p> <p><u>EXCAVATIONS, FILLING, ETC.</u></p> <p><u>Risk of collapse of excavations</u></p>				
119	<p>Allow for risk of collapse to sides of excavations not exceeding 1.5m deep including all necessary timber shoring, etc.</p>	m2	94		
	<p><u>Keeping excavations free of water</u></p>				
120	<p>Allow for keeping the excavations free from water.</p>		Item		
	<p><u>Tests</u></p>				
121	<p>Allow for Mod AASHTO density tests on filling.</p>	No	1.00		
	<p><u>CONCRETE</u></p>				
	<p><u>Unreinforced concrete 10MPa (19mm stone) in:</u></p>				
122	<p>Surface blinding under footings and bases.</p>	m3	5		
	<p><u>Reinforced concrete 25MPa (19mm stone) in:</u></p>				
123	<p>Surface beds cast against excavated surfaces.</p>	m3	20		
124	<p>Slabs, including beams and inverted beams.</p>	m3	20		
125	<p>Filling to cavity walls (measured elsewhere).</p>	m3	10		
	<p><u>Manhole covers, gratings, frames, etc.</u></p>				
126	<p>600 x 600mm Heavy duty polymer concrete cover slab including frame with Y12 bars as lifting eyes, reinforcement, etc.</p>	No	2.00		
	<p><u>Surface treatment</u></p>				
	<p><u>FORMWORK</u></p>				
	<p style="text-align: center;">Carried to Collection</p>			R	
	<p>Section 4 Bill No. 1 External Works</p>				

	<u>Rough formwork to:</u>				
127	Soffits of slabs including horsing up exceeding 1.5m and not exceeding 3.5m above bearing level.	m2	102		
	<u>Rough formwork to sides of:</u>				
128	Edges, riser, etc not exceeding 300mm high.	m2	92		
	<u>Boxing in or out rough formwork to form:</u>				
129	600 x 600mm Access hatch.	No	2		
	<u>REINFORCEMENT (PROVISIONAL)</u>				
	<u>High tensile steel reinforcement bars to structural concrete work:</u>				
130	Reinforcement in various sizes.	t	2		
	<u>Fabric Reinforcement</u>				
131	REF. 617 fabric reinforcement in cavity wall infill etc.	m2	90		
	<u>BRICKWORK IN SEPTIC TANKS</u>				
	<u>Loadbearing brickwork of extra hard burnt clay NFP bricks (21 Mpa nominal compressive strength) in Class I cement mortar:</u>				
132	One brick wall.	m2	11		
133	335mm Cavity walls formed of two half brick skins with and including wire ties and 110mm wide cavity.	m2	90		
	<u>Galvanized brickwork reinforcement</u>				
134	230mm Wide reinforcement built in horizontally.	m	296		
	<u>Pipework, etc</u>				
135	50mm PVC pipe through cavity wall.	m	3		
136	100mm PVC pipe through cavity wall.	m	3		
	<u>Extra Over for:</u>				
137	50mm Tee.	No	1		
	Carried to Collection			R	
	Section 4				
	Bill No. 1				
	External Works				

100mm Tee.

No

1

SOAK AWAY

Excavate in earth for soak away, size overall 6000mm long x 450mm wide x 1500mm deep with and including suitable polyester filter fabric lined on sides and bottoms of the trench, filling excavation with 20mm to 100mm diameter uniformly graded clean stone, 50mm diameter open jointed distribution pipe 6000mm long, 1No. 100mm diameter inspection pipes 1800mm long, one layer of suitable polyester filter fabric on top of the excavation filling, hessian, straw or fine gravel over the width of the trench, coarse sand or soil backfill to form cove over hessian, joint caps spaced at 1000mm centres along the length of the pipe, including all necessary excavation, scarifying trench surfaces, backfilling, carting away, risk of collapse, shoring, dewatering, concrete blinding, formwork, etc.:

139

Soak away exceeding 1500mm deep.

No

1

Carried to Collection

R

Section 4
Bill No. 1
External Works

QIBIRA PRIMARY SCHOOL
THE MVULA TRUST FLUSH MAINTENCE PROGRAMME

Section 4 Bill No. 1 External Works <u>COLLECTION</u>

[illegible]

Item No		Quantity	Rate	Amount	
	<u>SECTION 5</u>				
	<u>BILL No. 1</u>				
	<u>PROVISIONAL SUMS</u>				
	<u>SUPPLEMENTARY PREAMBLES</u>				
	Tenderers are advised that no claim in respect of loss of profit or Preliminary charges based on the omission of these amounts will be considered and the said amounts will be omitted strictly without any financial compensation payable to the Contractor.				
	Provisional sums and Budgetary allowances contained herein may be omitted or reduced at the Employer's discretion and the Contractor shall not be entitled to claim for any loss by way of reductions or omission of any discount, or percentage relating to Provisional amounts and Budgetary sums or any loss of profit related thereto.				
	<u>BUDGETARY ALLOWANCES</u>				
	<u>The following budgetary allowances are for work to be executed at rates in the bills of quantities or to be agreed by the Principal agent:</u>				
	<u>BOREHOLE INSTALLATION</u>				
1	Provisional Sum of R450 000.00 (Four Hundred and Fifty Thousand Rand) for the drilling of the borehole, to be carried out by a specialist contractor.	Item		450 000.00	
2	Add: Profit		%		
3	Add: Attendance		%		
	<u>COMMUNITY LIAISON OFFICER</u>				
4	Allow for the employment of a Community Liaison Officer by the Main Contractor, to be paid an allowance of R6 500.00 per month.	Item		45 500.00	
5	Add: Mark-up		%		
	Carried to Collection		R		
	Section 5				
	Bill No. 1				
	Provisional Sums				

ELECTRICAL INSTALLATION

Provide the sum of R 200 000.00 (Two Hundred Thousand Rand) for Electrical installation.	Item	200 000.00
--	------	------------

Add: Profit		%		
-------------	--	---	--	--

Add: Attendance			%		
-----------------	--	--	---	--	--

TRAINING SMME'S

Provide the sum of R 100 000.00 (One Hundred Thousand Rand) for training SMME's.	Item	100 000.00
---	------	------------

Add: Profit		%		
-------------	--	---	--	--

Add: Attendance			%		
-----------------	--	--	---	--	--

SMME WORK PACKAGES

Provide the sum of R 118 000.00 (One Hundred and Eighteen Thousand Rand) for demolitions.	Item	118 000.00
--	------	------------

Add: Profit			%	
-------------	--	--	---	--

Add: Attendance			%		
-----------------	--	--	---	--	--

Provide the sum of R 140 000.00 (One Hundred and Forty Thousand Rand) for masonry.	Item	140 000.00
---	------	------------

Add: Profit			%		
-------------	--	--	---	--	--

Add: Attendance			%		
-----------------	--	--	---	--	--

Provide the sum of R 93 000.00 (Ninety Three Thousand Rand) for carpentry and joinery.	Item	93 000.00
---	------	-----------

Add: Profit			%	
-------------	--	--	---	--

Add: Attendance			%		
-----------------	--	--	---	--	--

Provide the sum of R 11 000.00 (Eleven Thousand Rand) for metalwork.	Item	11 000.00
--	------	-----------

Add: Profit			%	
-------------	--	--	---	--

Add: Attendance			%		
-----------------	--	--	---	--	--

Carried to Collection

Section 5
Bill No. 1
Provisional Sums

QIBIRA PRIMARY SCHOOL
THE MVULA TRUST FLUSH MAINTENCE PROGRAMME

24	Provide the sum of R 18 000.00 (Eighteen Thousand Rand) for plastering.	Item		18 000.00	
25	Add: Profit		%		
26	Add: Attendance		%		
27	Provide the sum of R 74 000.00 (Seventy Four Thousand Rand) for tiling.	Item		74 000.00	
28	Add: Profit		%		
29	Add: Attendance		%		
30	Provide the sum of R 195 000.00 (One Hundred and Ninety Five Thousand Rand) for plumbing and drainage.	Item		195 000.00	
31	Add: Profit		%		
32	Add: Attendance		%		
33	Provide the sum of R 13 000.00 (Thirteen Thousand Rand) for glazing.	Item		13 000.00	
34	Add: Profit		%		
35	Add: Attendance		%		
36	Provide the sum of R 68 000.00 (Sixty Eight Thousand Rand) for paintwork.	Item		68 000.00	
37	Add: Profit		%		
38	Add: Attendance		%		
39	Provide the sum of R 450 000.00 (Four Hundred and Fifty Thousand Rand) for external works.	Item		450 000.00	
40	Add: Profit		%		
41	Add: Attendance		%		
42	Provide the sum of R 20 000.00 (Twenty Thousand Rand) for SMME workmanship sample construction.	Item		20 000.00	
43	Add: Profit		%		
44	Add: Attendance		%		
Carried to Collection				R	
Section 5					
Bill No. 1					
Provisional Sums					

[illegible]

[illegible]