SCHEDULE 1: PRELIMINARY INSTALLATION OF A BACKUP POWER SYSTEM FOR HAARTEBEESHOEK AND WILDERBEESFONTEIN DOSING STATIONS WHICH ARE BEING AFFECTED BY LOADSHEDDING AND GENERAL

ITEM NO	PAYMENT REF.	ITEM DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT(R)
1		INSTALLATION OF A BACKUP POWER SYSTEM FOR HAARTEBEESHOEK AND WILDERBEESFONTEIN DOSING STATIONS WHICH ARE BEING AFFECTED BY LOADSHEDDING				
1.1		SUPPLY SKW SMART INVERTER	EA	4		
1.2			EA	6		
		SUPPLY 5.2KW LITHIUM BATTERY				
1.3		SUPPLY 555W MONO SOLAR PANELS	EA	10		
1.4		SUPPLY GROCOL CABLE PACK	EA	8		
1.5		SUPPLY PV MOUNTING STRUCTURE-SECURED	EA	2		
1.6		SUPPLY25MM BATTERY CABLE	EA	6		
1.7		SUPPLY 160A BATTERY FUSE HOLDER	EA	6		
1.8		SUPPLY160A FUSES	EA	20		
1.9		SUPPLY 20XMM LUGS	EA	8		
1.10		OMM PV WRE-RED	EA	40		
1.11		OMM PV WRE-BLACK	EA	40		
1.12		SUPPLY 10MM EARTH WIRE	EA	20		
1.13		SUPPLY 4MM TWIN AND EARTH CABLE	EA	40		
1.14		SUPPLY TRUNKING AND ACCESSORIES	EA	2		
1.15		SUPPLY COMBINER BOX	EA	6		
1.16		SUPPLY AC BOARD CW CHANGEOVER SWITCH AND SURGE PROTECTION	EA	6		
1.17		SUPPLY MC4 CONNECTORS	EA	8		
1.18		SUPPLY AND CONFIGURE FLEY EWON 265	EA	2		
1.19		INSTALLATION	EA	2		
1.20		сос	EA	2		
TOTAL AMOUNT, Excluding 19% VAT						

ITEM NO	PAYMENT REF.	ITEM DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT(R)
3.1						
3.2						
3.3						
3.4						
3.5						
TOTAL, Excluding 15% VAT						

SUMMARY OF SCHEDULES

ITEM DESCRIPTION	Amount
Schedule 1	R
TOTAL, Excl. VAT	R
VAT (15%)	R
TOTAL, Incl. VAT	R