

SCHEDULE OF QUANTITIES

UPGRADING AT ELSBURG SIGNAL DEPOT

SECTION A

TABLE OF CONTENT

Contents	Page no
Annexure A Civil and Minor works BoQ.....	3 to 20
Annexure C Final Summary.....	20

PART A: SCHEDULE OF QUANTITIES

	<u>BILL NO. 1</u>	<u>Unit</u>	<u>QTY</u>	<u>Rate</u>		<u>Amount</u>	
	<u>ALTERATIONS (PROVISIONAL)</u>						
	<u>REMOVAL OF EXISTING WORK</u>						
	Carefully breaking down and removing brickwork etc						
	Taking out and removing piping, sanitary fittings, etc including disconnection piping from fittings						
1	Pan and cistern	No.	5	R	-	R	-
2	Kitchen sink cabinet	No.	2	R	-	R	-
3	Ceramic wash hand basin	No.	5	R	-	R	-
4	0.15 x 0.15m high box gutter including down pipes	m	80	R	-	R	-
5	0.25 x 0.2m high box gutter including down pipes	m	40	R	-	R	-
6	50mm uPVC piping including fittings and brackets	m	5	R	-	R	-
	Hacking up/off and removing ceramic wall tile						
7	Tiles to walls	m ²	15	R	-	R	-
	Taking down and removing ceiling						
8	Rhino board ceilings including cornices, brandering, jointing strips, etc	m ²	150	R	-	R	-
	Taking out and removing glass from steel window frame						
9	clear glass from steel window frames including cleaning out rebates and preparing for new glass	m ²	25	R	-	R	-
	Taking out and removing Fascia and barge board						
10	Fascia and barge board not exceeding 300mm girth	m	60	R	-	R	-
	Clean down existing face brick façade, painted walls, etc with water and brush						

11	External face brick walls	m ²	150	R	-	R	-
12	Allow to remove roller shutter doors	no	2	R	-	R	-
						R	-
	<u>BILL NO 2</u>	<u>Unit</u>	<u>QTY</u>	<u>Rate</u>		<u>Amount</u>	
	<u>MASONRY</u>						
	Bricks shall have been obtained from an approved manufactured and shall be either general purpose (special) burn clay bricks or Engineering bricks that comply with the applicable requirements of SABS 285. The contractor shall submit to the project manager samples of the bricks that he/she intends using in the construction of the works. The sample of the bricks that are approved will be retained by the Project manager. See sub clause 3.1 of SABS 1200A or 1200AA as applicable						
	Bricks in Class II mortar						
1	One brick wall for storm water channel and catch basin	m ²	50	R	-	R	-
	BRICKWORK SUNDRIES						
	Brick reinforcement						
2	230mm wide reinforcement built in horizontal	m	150	R	-	R	-
	Face brick coping						
3	One face brick wall to match the existing.	m ²	50	R	-	R	-
						R	-
	<u>BILL NO 3</u>	<u>Unit</u>	<u>QTY</u>	<u>Rate</u>		<u>Amount</u>	
	<u>CARPENTRY AND JOINERY</u>						

DOORS

44mm thick interior grade flush solid core timber single door with 3 mm thick commercial ply on both sides with consolidated edges fitted and complying with SABS 545 in pressed steel frame. All painted in accordance with architects colour schedule.

1	813 x 2032 x 44mm single interior leaf solid core	No.	30	R	-	R	-
	44mm thick exterior grade flush solid core timber single door with 3mm thick commercial ply on both sides with consolidated edges fitted and complying with SABS 545 in pressed steel frame. All painted in accordance with architect's colour schedules						
2	813 x 2032 x 44mm single exterior leaf solid core	No.	5	R	-	R	-
3	1626 x 2032 x 44mm double exterior leaf solid core	No.	3	R	-	R	-

FITTINGS

The following in modular timber cupboards, counters, duty stations, desk etc. as per Cupboard Connections Specification

Carcasses of 16mm thick particle board with both faces white melamine with white Masonite backs. Shelving of 16mm particle board, both faces white melamine and front edge in white PVC. Doors of 16mm particle board with post formed vertical edges and laminated in Renolit. Tops of 32mm particle board with post formed leading edges and laminated in high pressure decorative laminate. All butt edges and edges against walls to be sealed with silicon sealant. Hinges to be "Hettich". Drawer runners to be metal 500mm series with nylon runners or similar. All units complete with door, handles, hinges, cupboards, door, locks, barrel bolts and shelves. Floor unit complete with kick plates. (Formica tops measured elsewhere)

Built in cupboards fittings

4	Kitchen sink floor cupboard 3000 x 600 x 900mm high with sides, bottom, back, 3 hinged doors and one drawer completely working including handles, etc. top	No.	3	R	-	R	-
---	--	-----	---	---	---	---	---

	and sink measured else where						
	Grocery cabinet						
5	2.1m high x 0.5m wide x 0.6m 3 lockable separated parking compartment including locks and handles	No.	3	R	-	R	-
	Interior type particle board with Formica veneer						
6	900 x30mm thick granite with all exposed edges large bevel edged, fixed to supports using dabs of 100% black silicone adhesive along all supports with all joints filled with matching polyester resin glue. Granite surface to be sealed using an approved stone sealer, all in accordance with the manufacturer's recommendations.	m	12	R	-	R	-
7	2mm thick edge strip 32mm wide	m	25	R	-	R	-
8	Cut 50mm work top to fit end bowl sink, measured else where	No.	3	R	-	R	-
	Nutec fibre cement						
9	3000 x 10 x 300mm fascia boards including PVC H-Profile fascia board joiner	m	40	R	-	R	-
10	3000 x 10 x 300mm barge boards including PVC H-Profile barge board joiner	m	20	R	-	R	-
	Glazed shower doors						
11	Tri-slider patterned obscure glazed shower door	No.	8	R	-	R	-
12	800 – 1020mm x 4mm tick obscure pivot shower door	No.	6	R	-	R	-
	Skirting						
17	20 x 120mm solid meranti skirting	m	200	R	-	R	-
						R	-
	<u>BILL NO 4</u>	<u>Unit</u>	<u>QTY</u>	<u>Rate</u>	<u>Amount</u>		
	<u>CEILING WORK</u>						
	<u>SUPPLEMENTARY PREAMBLES</u>						

	<u>Description</u> Items described as “nailed” shall be deemed to be fixed with hardened steel nails or pins or shot pinned to brickwork or concrete Items described as “plugged” shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 600mm centres, and where described as “bolted”, bolts priced elsewhere 6.4mm “Rhino” gypsum plaster board with H-Type pressed steel jointing strips or suspended ceilings					
1	Ceiling including 38 x 38mm sawn softwood branderling at 450mm centres,	m ²	600	R	-	R -
2	Extra over ceiling for 800 x 800mm trap door of 38 50mm wrought softwood rebated framing with one 38 x 38mm sawn softwood cross brander covered with ceiling board and fitted flush in opening	No.	10	R	-	R -
3	Supply and fit glass wool and make good.	m ²	600	R	-	R -
	“Rhino” gypsum plasterboard cornice					
4	75mm coved cornices	m	320	R	-	R -
						R -
	<u>BILL NO 5</u>	<u>Unit</u>	<u>QTY</u>	<u>Rate</u>	<u>Amount</u>	
	<u>IRONMONGERY</u>					
	<u>LOCKS</u>					
1	3 liver union lock with handles	No.	30	R	-	R -
2	Ultra-security heavy duty locks	No.	8	R	-	R -
3	Stainless Steel Toilet Cubicle Indicator bolt & lock set, Grade 304Stainless Steel indicator bolt fixed to surface with matching stainless-steel screws.	No.	12	R	-	R -

4	Satin stainless steel toilet roll holders for 2 rolls with central shaft system and cylinder lock, plugged and screwed to the wall with stainless steel screws. (vandal resistant)	No	12	R	-	R	-
	<u>SIGNAGE</u>						
	<u>External signage</u>						
5	500 x 150mm High double-sided ceiling mounted directional sign anodized aluminium female and male ablutions pictogram door sign, suspended from ceiling grids with brass chains. Minimum of 2,1m above finished floor level.	No.	8	R	-	R	-
						R	-
	<u>BILL NO 6</u>	<u>Unit</u>	<u>QTY</u>	<u>Rate</u>		<u>Amount</u>	
	<u>TILING</u>						
	<u>Prices:</u>						
	Prices are to include for all square cutting and waste, cleaning off on completion and protection from injury. Areas are measured net to face of brickwork and concrete. Any additional area caused by the thickness of tiling and screed are to be allowed for in prices						
	<u>FLOOR TILING</u>						
	600x600mm Full Bodied polished Porcelain tiles with 3mm grouting lines						
1	On floors	m ²	70	R	-	R	-
	300x300x6mm Full Bodied polished Porcelain mosaic tiles with 3mm grouting lines						
2	On floors	m ²	15	R	-	R	-
	<u>WALL TILING</u>						
	Matt Full Bodied Porcelain tiles, size 600 x 300mm x 12mm fixed to internal wall plaster backing with TAL tile adhesive mixed with TAL bonding liquid in lieu of water with joints continuous in both directions and grouted with TAL tile grout, excess						

	grout on the surface to be cleaned with water as work proceeds.					
3	On walls	m ²	80	R	-	R -
	300x300x6mm Full Bodied polished Porcelain mosaic tiles with 3mm grouting lines					
4	On walls	m ²	60	R	-	R -
						R -
	<u>BILL NO 7</u>	<u>Unit</u>	<u>QTY</u>	<u>Rate</u>	<u>Amount</u>	
	<u>PLUMBING WORK</u>					
	<u>SANITARY FITTINGS</u>					
1	Vaal Sanitary ware Hibiscus vitreous china close coupled suite colour White, comprising 90° outlet open rim pan with matching 9 litre front single flush cistern including lid and fitments and Jazz Thermoset seat.	No.	12	R	-	R -
2	Vaal Sanitary ware Hibiscus vitreous china lavatory basin colour White, size 510 x 405mm with two tap hole including integrated overflow and chain stay hole bolted to wall with two x 10mm bolts and including Classic floor mounted pedestal and sealed with silicone sealant where basin meets wall.	No.	7	R	-	R -
3	Top entry ceramic urinal basin with Junior flush master exposed chrome flush valve including flush pipe, spreader, etc	No.	6	R	-	R -
	WASTE UNINON ETC					
4	Bath and Basin waste, plug, chain, stay and backnut	No.	10	R	-	R -
	TRAPS ETC					
5	365/40 CP bottle trap 40 x 40 INC CP/PVC adaptor to 40mm	No.	3	R	-	R -
6	38mm sink “P” trap	No.	9	R	-	R -
7	Brass shower P trap with square ss grating	No.	7	R	-	R -
	SINK, BASIN, ETC					
8	Double bowls stainless steel double end bowl inset sink, overall size 1200 x 535mm wide with two 340 x	No.	6	R	-	R -

	370 x 150mm deep bowls, fitted onto cupboard (elsewhere specified) including 38mm waste fitting and PVC traps (traps elsewhere specified).						
	TAPS, VALVES, ETC						
9	15mm chrome plated deck mounted sink mixer with overarm swivel outlet and adjustable flanges, manufactured in accordance with SANS 226:2004 Type 1.	No.	4	R	-	R	-
10	Push button pillar tap for hot and cold water	No.	12	R	-	R	-
11	Flexi connector	No.	30	R	-	R	-
12	15 Mini Ball Valve	No.	30	R	-	R	-
13	Single function vandal resistant shower head including shower arm, stainless steel polished body	No.	7	R	-	R	-
14	Chrome plated Shower tap mixer	No.	7	R	-	R	-
15	22mm Brass Gate Valve	No.	5	R	-	R	-
16	600kpa pressure control valve	No.	3	R	-	R	-
17	Relieve/safety valve	No.	6	R	-	R	-
18	Vacuum breaker	No.	6	R	-	R	-
19	Drain cock	No.	3	R	-	R	-
	0.8mm galvanized sheet iron						
20	125 x 100mm eaves gutter	m	50	R	-	R	-
21	Extra over 125 x 100mm eaves gutter for stopped end	No.	8	R	-	R	-
22	Extra over 125 x 100 eaves gutter for angle	No.	10	R	-	R	-
23	Extra over 125 x 100mm eaves gutter for outlet for 100 x 75mm pipe	No.	10	R	-	R	-
24	100 x 75mm rainwater pipes	m	25	R	-	R	-
25	Extra over 100 x 75mm rainwater pipe for shoe	No.	10	R	-	R	-
	0.9mm galvanized sheet iron						
26	250 x 200mm industrial eaves gutter including heavy	m	40	R	-	R	-

	duty brackets fixed at 500mm centers						
27	Extra over 250 x 200mm eaves gutter for stopped end	No.	4	R	-	R	-
28	Extra over 250 x 200 eaves gutter for angle	No.	6	R	-	R	-
29	Extra over 125 x 100mm eaves gutter for outlet for 300mm pipe	No.	6	R	-	R	-
30	300mm rainwater pipes	m	25	R	-	R	-
31	Extra over 300mm rainwater pipe for shoe	No.	6	R	-	R	-
	Extra over PVC pipes for fittings						
32	110mm pan connector	No.	10	R	-	R	-
	WATER SUPPLIERS						
	Class “O” copper pipe						
33	15mm pipes chased into brick walls	m	50	R	-	R	-
34	22mm pipes	m	30	R	-	R	-
35	22mm pipes chased into brick walls and make good	m	50	R	-	R	-
	Extra over class “O” copper pipes for capillary fittings						
36	15mm fitting	No.	15	R	-	R	-
37	15mm Tee	No.	15	R	-	R	-
38	15mm bend	No.	5	R	-	R	-
39	22mm fitting	No.	20	R	-	R	-
40	22mm Tee	No.	15	R	-	R	-
41	22mm bend	No.	5	R	-	R	-
	Sundries						
42	110mm Upvc cleaning eye to end of 110 Upvc pipe	No.	3	R	-	R	-
43	350 x 350 x 50mm thick precast concrete inspection eye marker slab finished smooth on exposed surfaces	No.	3	R	-	R	-

	with letters “I.E” or “I.O” on top and placed flush in ground or paving					
	Manhole covers					
	Precast concrete manholes with medium duty concrete manhole cover and frame bedded in 1:3 cement mortar, spacers bedded in 1:6 cement mortar and precast concrete slab including excavation, backfilling, compaction, risk of collapse, cartaway surplus material, 300mm thick unreinforced 20MPa/19mm concrete base projection 75mm wide from walls, benching, junctions, channeling and step irons					
44	980mm diameter (internally) Precast concrete manhole not exceeding 1m deep	No.	2	R	-	R -
45	980mm diameter (internally) Precast concrete manhole exceeding 1m deep and not exceeding 2m deep	No.	2	R	-	R -
46	980mm diameter Precast concrete manhole cover including frame	No.	2	R	-	R -
	WATER RETICULATION					
	PREMBLES					
	The contractor is referred to the General Preambles for trades 2017 published by the Association of South Africa Quantity Surveyors before pricing					
	WATER PIPEWORK					
	HDPE PE 100PN 12.5 pipes including excavation, bedding, backfilling, and compaction and disposal of surplus material					
47	25mm pipes laid in and including trenches not exceeding 1m deep	m	50	R	-	R -
						R -
	<u>BILL NO. 8</u>	<u>Unit</u>	<u>QTY</u>	<u>Rate</u>	<u>Amount</u>	
	<u>GLAZING</u>					

	<u>GLAZING TO ALUMINIUM WITH CLIP ON BEADS</u>					
	4mm patterned glass					
1	Panes exceeding 0.1m ² and 0.5 m ²	m ²	10	R	-	R -
	4mm clear float glass					
2	Panes exceeding 0.1m ² and 0.5 m ²	m ²	25	R	-	R -
	<u>MIRROR</u>					
	6.5mm silvered float glass copper backed mirrors with polished edges holed for and fixed with chromium plated dome capped mirror screws with rubber buffers to plugs in brickwork					
3	Mirror 600 x 1200mm high with four screws	No.	12	R	-	R -
						R -
	<u>BILL NO.9</u>	<u>Unit</u>	<u>QTY</u>	<u>Rate</u>	<u>Amount</u>	
	<u>METAL WORK</u>					
	<u>PRESSED STEEL DOOR FRAMES, LOUVRE GRILLE FRAMES, ETC</u>					
	Preparation, supply and install 1.2mm Double rebated frames suitable for one brick work					
1	External Frame for door 813 x 2032mm high	No.	2	R	-	R -
	1.2mm Double rebated frames suitable for half brickwork					
2	Internal Frame for door 813 x 2032mm high	No.	3	R	-	R -
	SECURITY GATES					
	Supply and install Burglar door					

3	815 x 2100mm high Heavy duty Burglar door and frame with 16mm steel round bar and 40 x 40 x 2.5mm square tubing as per attached drawing for single door	No.	6	R	-	R	-
4.	2000 x 2100mm high Heavy duty Burglar door and frame with 16mm steel round bar and 40 x 40 x 2.5mm square tubing as per attached drawing for double door	No	2	R	-	R	-
STEEL ROLLER SHUTTERS							
Roll-Up solid galvanised, SABS 1461, & epoxy coated M/S manually hand chain operated push-up roller shutter for maximum opening 3000 x 3000mm high with standard bottom rail, 75 x 0.8mm thick end-locked slats, 120mm extra-wide tamper proof guides, 4.5mm end plates, closed shaft and 2 x slidebolts, extruded with Aluminium Tbar & Astragal rubber weather seal. Including galv. cover box and powder coated components incl. door curtain, end plates, cover box, guides & T-bar. Door fixed to brick, concrete or structural steel jambs and concrete or steel lintel over. Contractor to provide cavity of 160mm x 120mm for recessing guides							
4	Manual hand chain Push-up Roller Shutters, for openings not exceeding 3000mm x 2500mm high.	No.	2	R	-	R	-
Supply and install Burglar windows							
5	600mm W x 600mm H Box windows guard constructed with 5mm of expanded metal and 50 x 50 x 6mm equal angles.	No.	8	R	-	R	-
6	1600mm W x 1200mm H Box windows guard constructed with 5mm of expanded metal and 50 x 50 x 6mm equal angles.	No.	14	R	-	R	-
7	1200mm W x 900mm H Box windows guard constructed with 5mm of expanded metal and 50 x 50 x 6mm equal angles. Including window frame and windowpane.	No.	3	R	-	R	-
8	Supply and install heavy duty sliding steel gate , 6m x 2.5m high. Supply and fit and heavy duty industrial motor which allows to be operated manually also., allow tu supply electric cable, allow all necessary fittings to be installed to the total completion of the job.	No	1	R		R	

9	Allow to replace heavy duty load bearing industrial roof logs 300mm long 50mm thick. Make sure it matches with the existing. Make good.	m	200	R		R
10	Supply and fit IBR 0.6mm roof sheet to match the existing and make good.	m ²	40	R		R
11	Allow to seal IBR roof sheets with SABS approved roof seal and make good.	m ²	300	R		R
12	All to paint IBR roof sheets with SABS approved roof paint and make good.	m ²	300	R		R
						R -
	<u>BILL NO.10</u> <u>PLASTERING</u> <u>SUPPLEMENTARY PREAMBLES</u> <u>Preparatory work for textured finishes:</u> Textured finishes to be applied to plaster (plaster elsewhere) All surfaces are to be inspected and approved by Prasa representative before any work is commenced with <u>Price for texture finishes:</u> Prices are to include for all priming, preparatory work, etc INTERNAL PLASTER Preparation and Cement plaster on brick work	<u>Unit</u>	<u>QTY</u>	<u>Rate</u>		<u>Amount</u>
1	walls	m ²	40	R	-	R -
2	Narrow width	m ²	20	R	-	R -
						R -
	<u>BILL NO.11</u> <u>PAINTWORK</u>	<u>Unit</u>	<u>QTY</u>	<u>Rate</u>		<u>Amount</u>

For preambles see “Model Preambles for Trades” 2008 edition published by the Association of South African Quantity Surveyors

SUPPLEMENTARY PREAMBLES

Previously painted plastered surfaces

Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed, and cracks shall be opened, filled with a suitable filler and finished smooth

Previously painted metal surfaces

Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal

Previously painted wood surfaces

Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed, and cracks and crevices shall be primed, filled with a suitable filler and finished smooth

PAINTWORK, ETC TO NEW WORK

ON FLOATED PLASTER

One coat professional plaster primer and two coats acrylic paint

1	On ceiling and cornices	m ²	400	R	-	R	-
---	-------------------------	----------------	-----	---	---	---	---

One coat professional plaster primer and two coats contractors White Gloss Enamel

2	On gutters and downpipes	m	220	R	-	R	-
---	--------------------------	---	-----	---	---	---	---

3	On fascia and barge boards	m	180	R	-	R	-
---	----------------------------	---	-----	---	---	---	---

ON WOOD**One coat wood primer, one Universal Undercoat and two coats PRASA Brown**

4	On Doors	m ²	90	R	-	R	-
Sand with abrasive paper, leaving surface dry, clean and dust free. Wash knots and resinous areas with Lacquer Thinners (ILS 1) and coat with Woodcare Knot Seal (PK 2) and apply one coat of Dulux or Plascon Woodcare Pretreatment (WWP 1), overcoated within 48 hours with a moisture content of BD 2 scale (A1-A5) < 14% or less. Prime with one coat Varnish with an overcoating time of 6 hours and finish with two coats Varnish with 6 hours drying time between coats.							

5	On skirting	m	220	R	-	R	-
---	-------------	---	-----	---	---	---	---

ON METAL**One coat zinc chromate primer, one Undercoat and two coats Professional Gloss Enamel**

6	On rails, bars, handrails, steel work, window frames, door frames, burglar gates and window, gates, gutters and down pipes	m ²	150	R	-	R	-
---	--	----------------	-----	---	---	---	---

One coat zinc chromate primer, one Undercoat and two coats Chromadek Prasa Kingfisher Blue suitable for roof

7	On roofs	m ²	440	R	-	R	-
---	----------	----------------	-----	---	---	---	---

ON WOOD**Surface preparation and apply two coats PRASA Brown**

8	On Doors	m ²	80	R	-	R	-
---	----------	----------------	----	---	---	---	---

ON METAL**One coat zinc chromate primer, one Undercoat and two coats Professional Gloss Enamel**

9	On rails, bars, handrails, steel work, window frames, door frames, burglar gates and window, gates, gutters and down pipes	m ²	50	R	-	R	-
						R	-
		<u>Unit</u>	<u>QTY</u>	<u>Rate</u>		<u>Amount</u>	
	<u>BILL NO.12</u>						
	<u>ELECTRICAL</u>						
	Signal Equipment Room (SER)			R		R	
1	<u>Supply Cable:</u> Supply and fit 50mm ² 4 core copper armoured cable	m	50	R		R	
2	<u>Trenching for supply cable:</u> 300mm deep x 100 wide	m	50	R		R	
3	<u>Soft river sand for supply cable:</u> Cover cable with soft river sand	m ³	5	R		R	
4	<u>Concrete for supply cable:</u> Supply and cast concrete over supply cable	m ³	5	R		R	
5	<u>Circuit Breaker:</u> Supply and fit 150Amp three pole	Item	2	R		R	
	Signal Depot kitchen and changeroom			R		R	
6	<u>Supply Cable:</u> Supply and fit 50mm ² 4 core copper armoured cable	m	150	R		R	
7	<u>Trenching for supply cable:</u> 300mm deep x 100 wide	m	150				
8	<u>Soft river sand for supply cable:</u> Cover cable with soft river sand	m ³	15				
				R		R	
9	<u>Concrete for supply cable:</u> Supply and cast concrete over supply cable	m ³	15	R		R	
10	<u>Circuit Breaker:</u> Supply and fit 150Amp three pole	Item	2	R		R	
11	<u>Earth leakage single pole:</u> Supply and fit 63 Amp	Item	4	R		R	
12	Supply and fit light switches at 16 Amp	Item	12	R		R	
13	Supply and fit 4-foot double LED fitting IP65 rating	Item	38	R		R	
14	Supply and fit Double plug socket (surface mount)	Item	24	R		R	
15	Supply and fit Twin and Earth 2.5mm ²	m	400	R		R	
16	Supply and fit LED flood lights at min 2000 Lumens for outside	Item	6	R		R	

17	Supply and fit Circuit breakers single pole at 20 Amp	Item	12	R	R
18	Supply and fit Photo switch for flood lights	Item	2	R	R
19	Supply and fit Circuit breakers single pole at 10 Amp for contactor coil	Item	14	R	R
20	Supply and fit Contactor at 220Vac 18Amps 4 N/O contacts for flood lights	Item	2	R	R
21	<u>Test, certification and guarantee:</u> Ensure lights functioning correctly. Ensure workmanship is according to good engineering practice. Material to be SABS approved. Prasa Cres shall require a 12 month guarantee on all parts and workmanship	item	1	R	R
					R -

SUMMARY - SECTION A

UPGRADE OF ELSBURG SIGNAL DEPOT

		PAGE	AMOUNT
1	Alterations	1 to 3	R
2	Masonry	3	R
3	Carpentry and Joinery	3 to 5	R
4	Ceiling work	5 to 6	R
5	Ironmongery	6 to 7	R
6	Tiling work	7 to 8	R
7	Plumbing work	8 to 11	R
8	Glazing	11	R
9	Metal work	12 to 14	R
10	Plastering	14	R
11	Painting work	14 to 17	R
12	Electrical	17 to 18	R
SUB TOTAL			R
ADD VAT @ 15%			R
FINAL SUMMARY SECTION A			R

