

TMT-DBE-23/24-SAFEOS-ECCL49

BILLS OF QUANTITIES

INDEX TO BILLS OF QUANTITIES

<u>Bill No</u>	<u>Page No</u>
SECTION NO. 1: ST MICHAEL'S JUNIOR SECONDARY SCHOOL	1
1 PRELIMINARIES	2
Building Agreement And Preliminaries.	2
Section A: Jbcc Principal Building Agreement	3
Definitions	3
A1 Definitions And Interpretation.	3
Objective And Preparation	3
A2 Offer, Acceptance And Performance	3
A3 Documents	3
A4 Design Responsibility	3
A5 Employers Agents.	3
A6 Site Representative	3
A7 Compliance With Regulations	3
A8 Works Risk	3
A9 Indemnities	4
A10 Works Insurances.	4
A11 Liability Insurances	4
A12 Effecting Insurances	4
A14 Security	4
Execution	4
A15 Preperation For And Execution Of The Works.	4
A16 Access To The Works.	4
A17 Contract Instructions.	4
A18 Setting Out Of The Works.	5

A19 Assignment	5
A20 Nominated Sub-contractors	5
A21 Selected Subcontractors	5
A22 Employer's Direct Contractors	5
A23 Contractor's Domestic Subcontractors	5
Completion	5
A24 Practical Completion	5
A25 Work's Completion	5
A26 Final Completion	5
A27 Latent Defects Liability Period	6
A28 Sectional Completion	6
A29 Revision Of Date For Practical Completion	6
A30 Penalty For Non-completion	6
Payment	6
A31 Interim Payment To The Contractor	6
A32 Adjustment To The Contract Value	7
A33 Recovery Of Expense And Loss	7
A34 Final Account And Final Payment	7
A35 Payment To Other Parties	7
Cancellation	7
A36 Cancellation By Employer - Contractor's Default	7
A37 Cancellation By Employer - Loss And Damage	7
A38 Cancellation By Contractor - Employer's Default	7
A39 Cancellation - Cessation Of The Works	7
Dispute	7
A40 Dispute Settlement	7

Substitute Provisions	7
A41 State Clauses.....	7
Contract Variables.....	8
The Schedule (C1.2 Contract Data)	8
A42 Pre-tender Information	8
Section B: Jbcc Preliminaries.....	8
B1.0 Definitions And Interpretation.....	8
B2.0 Documents	8
B3.0 The Site.....	9
B4.0 Management Of Contract	9
B5.0 Samples, Shop Drawings And Manufacturers' Instructions.....	10
B6.0 Temporary Works And Plant	10
B7.0 Temporary Services	11
B8.0 Prime Cost Amounts.....	11
9.0 Attendance On N/s Subcontractors.....	11
B10.0 Financial Aspects	12
B11. General	12
Section C: Specific Preliminaries	13
C1 Contract Drawings	13
C2 General Preambles	13
C3 Proprietary Branded Products	13
C4 Contractor's Responsibility	14
C5 Overtime	14
C6 As Built Drawings.....	14
C7 Contract Instructions.....	14
C8 Labour Record.....	15

C9 Plant Record	15
C10 Encroachment	15
C11 Method Statement	15
C12 Unauthorised Persons/workmen On Premises	15
C13 Mode Of Procedure	15
C14 Location Of Temporary Buildings And Temporary Services	16
C15 Office Accommodation	16
C16 Storage Facilities	16
C17 Removal And Making Good Of Temporary Works, Etc, On Completion	16
2 HEALTH AND SAFETY.....	18
Model Preambles	18
Supplementary Preambles.....	18
Occupational Health And Safety.....	18
3 RENOVATIONS	21
Supplementary Preambles.....	21
Making Good Of Existing Work.....	21
Bathroom Fittings	22
Galvanised Steel Gates, Screens, Etc.....	22
Sanitary Fittings	22
Traps Etc	23
Tap Stands.....	23
Sanitary Plumbing.....	23
Preambles	23
4 GARDEN AND BALUSTRADE WALLS	25
Preambles	25
Earthworks (Provisional)	25

Concrete, Formwork & Reinforcement	26
Expansion Joints:	26
Test Cubes	26
Masonry	26
Facings Externally:	26
Painting	26
5 V-DRAINS	28
Preambles	28
Supplementary Preambles	28
Excavation Etc	29
Filling Etc Other Than Bulk	29
Dampproofing Of Walls And Floors	29
Stormwater Drainage (Provisional)	29
Test Cubes	30
Reinforcement (Cpap Work Group No. 114)	30
The Following In Earth Drains	30
6 CONCRETE WALKWAYS & RAMPS	32
Preambles	32
Earthworks (Provisional)	32
Concrete, Formwork & Reinforcement	32
Expansion Joints:	32
Test Cubes	32
Smooth Formwork (Degree Of Accuracy ii) (Cpap Work Group No. 111)	33
Reinforcement (Cpap Work Group No. 114)	33
Dampproofing Of Walls And Floors	33
7 SUBSOIL DRAINAGE	35

Preambles	35
Supplementary Preambles	35
The Following In Stormwater Soakaways	35
Subsoil Drainage (Cpap Work Group No. 146)	35
8 SOAKAWAYS & CULVERTS	38
The Following In Stormwater Soakaways	38
9 GRADE R FENCING	39
Preambles	39
The Following In Security Fencing	39
10 PROVISIONAL SUMS	43
Provisional Sums	43
Budgetary Allowances	43
SECTION SUMMARY	44
SECTION NO. 2: BAMBOESPRUIT JUNIOR SECONDARY SCHOOL	45
1 PRELIMINARIES	46
Building Agreement And Preliminaries.	46
Section A: Jbcc Principal Building Agreement	47
Definitions	47
A1 Definitions And Interpretation.	47
Objective And Preparation	47
A2 Offer, Acceptance And Performance	47
A3 Documents	47
A4 Design Responsibility	47
A5 Employers Agents.	47
A6 Site Representative	47
A7 Compliance With Regulations	47

A8 Works Risk	47
A9 Indemnities	48
A10 Works Insurances.....	48
A11 Liability Insurances.....	48
A12 Effecting Insurances.....	48
A14 Security	48
Execution	48
A15 Preperation For And Execution Of The Works.....	48
A16 Access To The Works.....	48
A17 Contract Instructions.....	48
A18 Setting Out Of The Works.....	49
A19 Assignment	49
A20 Nominated Sub-contractors.....	49
A21 Selected Subcontractors.....	49
A22 Employer's Direct Contractors	49
A23 Contractor's Domestic Subcontractors	49
Completion	49
A24 Practical Completion.....	49
A25 Work's Completion	49
A26 Final Completion.....	49
A27 Latent Defects Liability Period	50
A28 Sectional Completion	50
A29 Revision Of Date For Practical Completion.....	50
A30 Penalty For Non-completion.....	50
Payment.....	50
A31 Interim Payment To The Contractor	50

A32 Adjustment To The Contract Value	51
A33 Recovery Of Expense And Loss.	51
A34 Final Account And Final Payment.	51
A35 Payment To Other Parties.	51
Cancellation	51
A36 Cancellation By Employer - Contractor's Default	51
A37 Cancellation By Employer - Loss And Damage	51
A38 Cancellation By Contractor - Employer's Default	51
A39 Cancellation - Cessation Of The Works	51
Dispute	51
A40 Dispute Settlement	51
Substitute Provisions	51
A41 State Clauses.	51
Contract Variables.	52
The Schedule (C1.2 Contract Data)	52
A42 Pre-tender Information	52
Section B: Jbcc Preliminaries.	52
B1.0 Definitions And Interpretation.	52
B2.0 Documents	52
B3.0 The Site	53
B4.0 Management Of Contract	53
B5.0 Samples, Shop Drawings And Manufacturers' Instructions.	54
B6.0 Temporary Works And Plant	54
B7.0 Temporary Services	55
B8.0 Prime Cost Amounts.	55
9.0 Attendance On N/s Subcontractors.	55

B10.0 Financial Aspects	56
B11. General	56
Section C: Specific Preliminaries	57
C1 Contract Drawings	57
C2 General Preambles	57
C3 Proprietary Branded Products	57
C4 Contractor's Responsibility	58
C5 Overtime	58
C6 As Built Drawings	58
C7 Contract Instructions	58
C8 Labour Record	59
C9 Plant Record	59
C10 Encroachment	59
C11 Method Statement	59
C12 Unauthorised Persons/workmen On Premises	59
C13 Mode Of Procedure	59
C14 Location Of Temporary Buildings And Temporary Services	60
C15 Office Accommodation	60
C16 Storage Facilities	60
C17 Removal And Making Good Of Temporary Works, Etc, On Completion	60
2 HEALTH AND SAFETY	62
Model Preambles	62
Supplementary Preambles	62
Occupational Health And Safety	62
3 RENOVATIONS	65
Preambles	65

Supplementary Preambles	65
Making Good Of Existing Work	65
Bathroom Fittings	66
Sanitary Fittings	66
Traps Etc	66
Tap Stands	67
4 GARDEN AND BALUSTRADE WALLS	69
Preambles	69
Earthworks (Provisional)	69
Concrete, Formwork & Reinforcement	70
Expansion Joints:	70
Test Cubes	70
Masonry	70
Facings Externally:	70
Painting	70
5 V – DRAINS	72
Preambles	72
Supplementary Preambles	72
Excavation Etc	73
Filling Etc Other Than Bulk	73
Dampproofing Of Walls And Floors.	73
Culverts	73
Stormwater Drainage (Provisional)	74
Test Cubes	74
Reinforcement (Cpap Work Group No. 114)	74
6 CONCRETE APRONS, WALKWAYS & RAMPS.	76

Preambles	76
Earthworks (Provisional)	76
Concrete, Formwork & Reinforcement	77
Expansion Joints:	77
Test Cubes	77
Smooth Formwork (Degree Of Accuracy ii) (Cpap Work Group No. 111)	77
Reinforcement (Cpap Work Group No. 114)	77
Dampproofing Of Walls And Floors.	77
7 SUBSOIL DRAINAGE.	79
Preambles	79
Supplementary Preambles	79
Subsoil Drainage (Cpap Work Group No. 146)	79
The Following In Stormwater Soakaways	80
8 GRADE R FENCING.	83
Preambles	83
The Following In Security Fencing	83
9 PROVISIONAL SUMS.	87
Provisional Sums	87
Budgetary Allowances	87
SECTION SUMMARY.	88
SECTION NO. 3: KHIBA JUNIOR SECONDARY SCHOOL.	89
1 PRELIMINARIES	90
Building Agreement And Preliminaries.	90
Section A: Jbcc Principal Building Agreement	91
Definitions	91
A1 Definitions And Interpretation.	91

Objective And Preparation	91
A2 Offer, Acceptance And Performance	91
A3 Documents	91
A4 Design Responsibility	91
A5 Employers Agents.	91
A6 Site Representative	91
A7 Compliance With Regulations	91
A8 Works Risk	91
A9 Indemnities	92
A10 Works Insurances.	92
A11 Liability Insurances	92
A12 Effecting Insurances	92
A14 Security	92
Execution	92
A15 Preperation For And Execution Of The Works.	92
A16 Access To The Works.	92
A17 Contract Instructions.	92
A18 Setting Out Of The Works	93
A19 Assignment	93
A20 Nominated Sub-contractors.	93
A21 Selected Subcontractors	93
A22 Employer's Direct Contractors	93
A23 Contractor's Domestic Subcontractors	93
Completion	93
A24 Practical Completion.	93
A25 Work's Completion	93

A26 Final Completion.	93
A27 Latent Defects Liability Period	94
A28 Sectional Completion	94
A29 Revision Of Date For Practical Completion.	94
A30 Penalty For Non-completion.	94
Payment.	94
A31 Interim Payment To The Contractor	94
A32 Adjustment To The Contract Value.	95
A33 Recovery Of Expense And Loss.	95
A34 Final Account And Final Payment.	95
A35 Payment To Other Parties.	95
Cancellation	95
A36 Cancellation By Employer - Contractor's Default	95
A37 Cancellation By Employer - Loss And Damage	95
A38 Cancellation By Contractor - Employer's Default	95
A39 Cancellation - Cessation Of The Works	95
Dispute.	95
A40 Dispute Settlement	95
Substitute Provisions	95
A41 State Clauses.	95
Contract Variables.	96
The Schedule (C1.2 Contract Data)	96
A42 Pre-tender Information	96
Section B: Jbcc Preliminaries.	96
B1.0 Definitions And Interpretation.	96
B2.0 Documents	96

B3.0 The Site	97
B4.0 Management Of Contract	97
B5.0 Samples, Shop Drawings And Manufacturers' Instructions.....	98
B6.0 Temporary Works And Plant	98
B7.0 Temporary Services	99
B8.0 Prime Cost Amounts.....	99
9.0 Attendance On N/s Subcontractors.....	99
B10.0 Financial Aspects	100
B11. General	100
Section C: Specific Preliminaries	101
C1 Contract Drawings	101
C2 General Preambles	101
C3 Proprietary Branded Products	101
C4 Contractor's Responsibility	102
C5 Overtime	102
C6 As Built Drawings.....	102
C7 Contract Instructions.....	102
C8 Labour Record.....	103
C9 Plant Record	103
C10 Encroachment	103
C11 Method Statement	103
C12 Unauthorised Persons/workmen On Premises	103
C13 Mode Of Procedure	103
C14 Location Of Temporary Buildings And Temporary Services	104
C15 Office Accommodation	104
C16 Storage Facilities	104

C17 Removal And Making Good Of Temporary Works, Etc, On Completion	104
2 HEALTH AND SAFETY.	106
Model Preambles	106
Supplementary Preambles.	106
Occupational Health And Safety	106
3 RENOVATIONS	109
Preambles	109
Supplementary Preambles.	109
Making Good Of Existing Work.	109
Bathroom Fittings	110
Sanitary Plumbing	110
4 GARDEN AND BALUSTRADE WALLS	112
Preambles	112
Earthworks (Provisional)	112
Concrete, Formwork & Reinforcement	113
Expansion Joints:	113
Test Cubes.	113
Masonry	113
Facings Externally:	113
Painting	113
5 V – DRAINS	115
Preambles	115
Supplementary Preambles.	115
Excavation Etc	116
Filling Etc Other Than Bulk.	116
Dampproofing Of Walls And Floors.	116

Stormwater Drainage (Provisional)	116
Test Cubes	117
Reinforcement (Cpap Work Group No. 114)	117
6 SUBSOIL DRAINAGE.	119
Preambles	119
Supplementary Preambles	119
Subsoil Drainage (Cpap Work Group No. 146)	119
7 SOAKAWAYS & CULVERTS	122
Preambles	122
Supplementary Preambles	122
The Following In Stormwater Soakaways	122
8 PROVISIONAL SUMS.	125
Budgetary Allowances	125
Provisional Sums	125
SECTION SUMMARY.	126

SECTION NO. 1

ST MICHAEL'S JUNIOR SECONDARY SCHOOL

Amount

SECTION NO. 1

ST MICHAEL'S JUNIOR SECONDARY SCHOOL

BILL NO. 1

PRELIMINARIES

BUILDING AGREEMENT AND PRELIMINARIES

1. The Principal Building Agreement shall be the JBCC Series Edition 4.1, March 2005 as recommended by the Joint Building Contracts Committee and as amended by this Tender Enquiry.
2. The Preliminaries shall be JBCC Series 2000, May 2005 for use with the Principal Building Agreement as recommended by the joint Building Contracts Committee and as amended by this Tender Enquiry shall be deemed to be incorporated herein.
3. The tenderor is deemed to have referred to the abovementioned documents for the full intent and meaning of each clause. The clauses in the abovementioned documents are hereinafter referred to by clause number and heading only.
4. Where standard clauses or alternatives are not entirely applicable to this contract, such modifications, corrections or additions as are necessary, are given as far as possible under each relevant clause heading. Additional Preliminary clauses are contained in Section C hereof.
5. No claim whatsoever shall be entertained in respect of errors or omissions in pricing due to brevity of descriptions of items which are fully described when read in conjunction with the relevant clauses of the said Principal Building Agreement, Preliminaries and Preambles.
6. The Tenderers shall allow opposite each of the clauses whatever costs and charges he may consider necessary for the carrying out, complying with and due observance of the provisions, conditions and requirements set out herein. Only priced items will be considered in respect of any adjustment of this Section. Any items left unpriced will be understood to be provided free of charge and no claim for any extras arising out of the Tenderer's omission to price any item will be entertained.
7. Where modifications or amendments as described are made, such modifications and/or amendments shall supercede any conflicting provisions in the relevant clauses of the Standard Preliminaries or the Principal Building Agreement and the Tenderer shall make due allowance for whatever costs and charges he may consider necessary for the carrying out and observance of the provisions of the clauses as modified and/or amended.
8. Where any item is not relevant to this specific contract, such item is marked N/A.
9. If Alternative A as set out in clause B10.3 hereinafter is to be used for the adjustment of the preliminaries, each item priced is to be allocated to one or more of the three categories by insertion of "F","V","T" as the case may be against the price in the "rate" column immediately preceding the "amount" column, where "F" denotes a fixed amount (amount not to be varied), "V" denotes an amount variable in proportion to value, and "T" denotes an amount proportionate to time.

Carried to Collection

R

Section No. 1

Bill No. 1

Preliminaries

			Amount
<u>SECTION A: JBCC PRINCIPAL BUILDING AGREEMENT</u>			
<u>DEFINITIONS</u>			
<u>A1 DEFINITIONS AND INTERPRETATION</u>			
<u>Clause 1.0:</u>			
1	Fixed:_____ Value related:_____ Time related:_____0	Item	
<u>OBJECTIVE AND PREPARATION</u>			
<u>A2 OFFER, ACCEPTANCE AND PERFORMANCE</u>			
<u>Clause 2.0</u>			
2	Fixed:_____ Value related:_____ Time related:_____	Item	
<u>A3 DOCUMENTS</u>			
<u>Clause 3.0</u>			
Clause 3.1 is deleted and substituted with: 'This tender is for a Government Contract. No Payment Guarantee will be provided.'			
Clause 3.3 is deleted and substituted with:			
The principal agent shall complete the schedule and arrange for formal signing of the agreement once the priced bill of quantities/lump sum document, security, insurances and waiver of lien, where acceptable, have been provided and effected'			
3	Fixed:_____ Value related:_____ Time related:_____	Item	
<u>A4 DESIGN RESPONSIBILITY</u>			
<u>Clause 4.0</u>			
4	Fixed:_____ Value related:_____ Time related:_____	Item	
<u>A5 EMPLOYERS AGENTS</u>			
<u>Clause 5.0</u>			
5	Fixed:_____ Value related:_____ Time related:_____	Item	
<u>A6 SITE REPRESENTATIVE</u>			
<u>Clause 6.0</u>			
6	Fixed:_____ Value related:_____ Time related:_____	Item	
<u>A7 COMPLIANCE WITH REGULATIONS</u>			
7	Fixed:_____ Value related:_____ Time related:_____	Item	
<u>Clause 7.0</u>			
8	Fixed:_____ Value related:_____ Time related:_____	Item	
<u>A8 WORKS RISK</u>			
<u>Clause 8.0</u>			
9	Fixed:_____ Value related:_____ Time related:_____	Item	
Carried to Collection		R	
Section No. 1			
Bill No. 1			
Preliminaries			

			Amount
<u>A9 INDEMNITIES</u>			
<u>Clause 9.0</u>			
Clause 9.1.1 is deleted and substituted with:			
Claims from other parties consequent upon death of bodily injury or illness of any person or physical loss or damage to any property, other than the works, arising out or due to the execution of the works or occupation of the site by the contractor or his sub contractors'.			
10	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A10 WORKS INSURANCES</u>			
<u>Clause 10.0</u>			
11	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A11 LIABILITY INSURANCES</u>			
<u>Clause 11.0</u>			
12	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A12 EFFECTING INSURANCES</u>			
<u>Clause 12.0</u>			
13	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A13. No clause</u>			
14	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A14 SECURITY</u>			
<u>Clause 14.0</u>			
15	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>EXECUTION</u>			
<u>A15 PREPERATION FOR AND EXECUTION OF THE WORKS</u>			
<u>Clause 15.0</u>			
16	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A16 ACCESS TO THE WORKS</u>			
<u>Clause 16.0</u>			
17	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A17 CONTRACT INSTRUCTIONS</u>			
<u>Clause 17.0</u>			
18	Fixed: _____ Value related: _____ Time related: _____	Item	
Carried to Collection			
Section No. 1			
Bill No. 1			
Preliminaries			

			Amount
<u>A18 SETTING OUT OF THE WORKS</u>			
<u>Clause 18.0</u>			
The contractor shall notify the principal agent if any encroachments of adjoining foundations, buildings, structures, pavements, boundaries, etc., exist in order that the necessary arrangements may be made for the rectification of any such encroachments. Should incorrect information be given to the contractor in terms of 18.1 and 18.2, which causes the incorrect setting out of the works, the contractor shall not be liable for such incorrect setting out			
19	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A19 ASSIGNMENT</u>			
<u>Clause 19.0</u>			
20	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A20 NOMINATED SUB-CONTRACTORS</u>			
<u>Clause 20.0</u>			
21	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A21 SELECTED SUBCONTRACTORS</u>			
<u>Clause 21.0</u>			
22	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A22 EMPLOYER'S DIRECT CONTRACTORS</u>			
<u>Clause 22.0</u>			
23	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A23 CONTRACTOR'S DOMESTIC SUBCONTRACTORS</u>			
<u>Clause 23.0</u>			
24	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>COMPLETION</u>			
<u>A24 PRACTICAL COMPLETION</u>			
<u>Clause 24.0</u>			
25	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A25 WORK'S COMPLETION</u>			
<u>Clause 25.0</u>			
26	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A26 FINAL COMPLETION</u>			
<u>Clause 26.0</u>			
27	Fixed: _____ Value related: _____ Time related: _____	Item	
Carried to Collection		R	
Section No. 1			
Bill No. 1			
Preliminaries			

			Amount
<u>A27 LATENT DEFECTS LIABILITY PERIOD</u>			
<u>Clause 27.0</u>			
Clause 27.0 is amended by the addition of the following clauses:			
"27.3 Any water leakage into the building, whether in the roof, external wall or other element of the building susceptible to water leakage shall, unless proven to be a design defect, or as a result of obvious storm damage, be classified as a latent defect in terms of clause 1.0 Definitions and Interpretations".			
"27.4 The Contractor shall attend to defects during the Defects Liability Period on a progressive basis, to the satisfaction of the Principal Agent and will not be permitted to wait until the end of the Defect Liability Period or until the amount of defects accumulates in order to attend to a comprehensive list of defects"			
28	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A28 SECTIONAL COMPLETION</u>			
<u>Clause 28.0</u>			
29	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A29 REVISION OF DATE FOR PRACTICAL COMPLETION</u>			
<u>Clause 29.0</u>			
30	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A30 PENALTY FOR NON-COMPLETION</u>			
<u>Clause 30.0</u>			
31	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>PAYMENT</u>			
<u>A31 INTERIM PAYMENT TO THE CONTRACTOR</u>			
<u>Clause 31.0</u>			
The inclusion of materials and goods stored off site in the amount authorised for payment in terms of clause 31.3 shall be at the sole discretion of the principal agent and such inclusion shall only be considered upon the provision, by the contractor, of an approved guarantee issued by a registered commercial bank.			
Where prices are submitted by the contractor or nominated/selected sub-contractor during the progress of the works in respect of contract instructions or in regard to a claim under the terms of the contract and notwithstanding the fact that such prices may be used in an interim payment certificate, there is to be no presumption of acceptance. Should the principal agent wish to accept any such prices prior to the issue of the final certificate, it will be in writing.			
32	Fixed: _____ Value related: _____ Time related: _____	Item	
Carried to Collection			
Section No. 1			
Bill No. 1			
Preliminaries			

			Amount
<u>A32 ADJUSTMENT TO THE CONTRACT VALUE</u>			
<u>Clause 32.0</u>			
33	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A33 RECOVERY OF EXPENSE AND LOSS</u>			
<u>Clause 33.0</u>			
34	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A34 FINAL ACCOUNT AND FINAL PAYMENT</u>			
<u>Clause 34.0</u>			
35	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A35 PAYMENT TO OTHER PARTIES</u>			
<u>Clause 35.0</u>			
36	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>CANCELLATION</u>			
<u>A36 CANCELLATION BY EMPLOYER - CONTRACTOR'S DEFAULT</u>			
<u>Clause 36.0</u>			
37	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A37 CANCELLATION BY EMPLOYER - LOSS AND DAMAGE</u>			
<u>Clause 37.0</u>			
38	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A38 CANCELLATION BY CONTRACTOR - EMPLOYER'S DEFAULT</u>			
<u>Clause 38.0</u>			
39	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A39 CANCELLATION - CESSATION OF THE WORKS</u>			
<u>Clause 39.0</u>			
40	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>DISPUTE</u>			
<u>A40 DISPUTE SETTLEMENT</u>			
<u>Clause 40.0</u>			
41	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>SUBSTITUTE PROVISIONS</u>			
<u>A41 STATE CLAUSES</u>			
<u>Clause 41.0</u>			
42	Fixed: _____ Value related: _____ Time related: _____	Item	
Carried to Collection		R	
Section No. 1			
Bill No. 1			
Preliminaries			

			Amount
<u>CONTRACT VARIABLES</u>			
<u>THE SCHEDULE (C1.2 CONTRACT DATA)</u>			
<u>A42 PRE-TENDER INFORMATION</u>			
<u>Clause 42.0</u>			
Tenderers are referred to the document C1.2 Contract Data for variables pertaining to this contract.			
43	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>SECTION B: JBCC PRELIMINARIES</u>			
<u>B1.0 DEFINITIONS AND INTERPRETATION</u>			
<u>B1.1 Definitions and interpretation</u>			
44	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B2.0 DOCUMENTS</u>			
<u>B2.1 Checking of documents</u>			
Notwithstanding the issue of the tender drawings, it will remain the responsibility of the Tenderer to study all available drawings at the offices of the Principal Agent during normal working hours in order to acquaint himself with all the cost implications of the design, programming, phasing, etc.			
45	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B2.2 Provisional bills of quantities</u>			
Prime Cost Amounts, Budgetary Allowances, Provisional Amounts, etc., contained herein may be omitted or reduced at the Principal Agent's sole discretion and the Contractor shall not be entitled to claim for any loss by way of reduction or omission of any discount, or percentage relating to Prime Cost Amounts, Budgetary Allowances, Provisional Amounts, Provisional Quantities, etc., or loss of profit related thereto.			
46	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B2.3 Availability of construction documentation</u>			
47	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B2.4 Interests of agents</u>			
48	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B2.5 Priced documents</u>			
49	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B2.6 Tender submission</u>			
Notwithstanding anything contained in this clause, Tenders shall be valid for a period of 20 (Twenty) weeks from the closing date of tenders.			
50	Fixed: _____ Value related: _____ Time related: _____	Item	
Carried to Collection		R	
Section No. 1			
Bill No. 1			
Preliminaries			

			Amount
<u>B3.0 THE SITE</u>			
<u>B3.1 Defined works area</u>			
The area of the works to be occupied by the contractor, any restriction on the area and the limit of access or exit will be pointed out to the contractor by the principal agent on handing over of the site.			
Workmen employed on the site are to be restricted to the immediate area of the site and access thereto.			
The Tenderer shall make all necessary provision in all rates to take into account these requirements as no claims for extras arising from these matters will be subsequently entertained or admitted.			
51	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B3.2 Geotechnical investigation</u>			
52	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B3.3 Inspection of the site</u>			
53	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B3.4 Existing premises occupied</u>			
54	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B3.5 Previous work - dimensional accuracy</u>			
55	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B3.6 Previous work - defects</u>			
56	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B3.7 Services - known</u>			
57	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B3.8 Services - unknown</u>			
58	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B3.9 Protection of trees</u>			
59	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B3.10 Articles of value</u>			
60	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B3.11 Inspection of adjoining properties</u>			
61	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B4.0 MANAGEMENT OF CONTRACT</u>			
<u>B4.1 Management of the works</u>			
62	Fixed: _____ Value related: _____ Time related: _____	Item	
Carried to Collection		R	
Section No. 1			
Bill No. 1			
Preliminaries			

			Amount
<u>B4.2 Programme for the works</u>			
63	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B4.3 Progress meetings</u>			
64	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B4.4 Technical meetings</u>			
65	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B4.5 Labour and plant records</u>			
66	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B5.0 SAMPLES, SHOP DRAWINGS AND MANUFACTURERS' INSTRUCTIONS</u>			
<u>B5.1 Samples of materials</u>			
67	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B5.2 Workmanship samples</u>			
68	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B5.3 Shop drawings</u>			
69	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B5.4 Compliance with manufacturers instructions</u>			
70	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B6.0 TEMPORARY WORKS AND PLANT</u>			
<u>B6.1 Deposits and fees</u>			
71	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B6.2 Enclosure of the works</u>			
The contractor shall erect, maintain and remove at completion, hoardings, safety screens, barriers, access gates, covered gangways and the like as necessary for the enclosure of the works and elements thereof all for the protection of the public and others.			
72	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B6.3 Advertising</u>			
73	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B6.4 Plant, equipment, sheds and offices</u>			
74	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B6.5 Main notice board</u>			
75	Fixed: _____ Value related: _____ Time related: _____	Item	
Carried to Collection		R	
Section No. 1			
Bill No. 1			
Preliminaries			

			Amount
	<u>B6.6 Subcontractors' notice board</u>		
76	Fixed: _____ Value related: _____ Time related: _____	Item	
	<u>B7.0 TEMPORARY SERVICES</u>		
	<u>B7.1 Location</u>		
77	Fixed: _____ Value related: _____ Time related: _____	Item	
	<u>B7.2 Water</u>		
	The contractor shall provide water for the works in accordance with: Alternative A (i.e. to be provided for by the Contractor).		
78	Fixed: _____ Value related: _____ Time related: _____	Item	
	<u>B7.3 Electricity</u>		
	The contractor shall provide electricity for the works in accordance with: Alternative A (i.e. to be provided for by the Contractor).		
79	Fixed: _____ Value related: _____ Time related: _____	Item	
	<u>B7.4 Telecommunication facilities</u>		
	The contractor shall provide telephones on site for the works in accordance with: Alternative A (i.e. to be provided for by the Contractor).		
80	Fixed: _____ Value related: _____ Time related: _____	Item	
	<u>B7.5 Ablution facilities</u>		
	The contractor shall provide toilet facilities on site for the works in accordance with: Alternative A (i.e. to be provided for by the Contractor).		
81	Fixed: _____ Value related: _____ Time related: _____	Item	
	<u>B8.0 PRIME COST AMOUNTS</u>		
	<u>B8.1 Responsibility for prime cost amounts</u>		
82	Fixed: _____ Value related: _____ Time related: _____	Item	
	<u>9.0 ATTENDANCE ON N/S SUBCONTRACTORS</u>		
	<u>B9.1 General attendance</u>		
83	Fixed: _____ Value related: _____ Time related: _____	Item	
	<u>B9.2 Special attendance</u>		
84	Fixed: _____ Value related: _____ Time related: _____	Item	
	<u>B9.3 Commissioning - fuel, water and electricity</u>		
85	Fixed: _____ Value related: _____ Time related: _____	Item	
	Carried to Collection	R	
	Section No. 1		
	Bill No. 1		
	Preliminaries		

			Amount
<u>B10.0 FINANCIAL ASPECTS</u>			
<u>B10.1 Statutory taxes, duties and levies</u>			
86	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B10.2 Payment for preliminaries</u>			
87	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B10.3 Adjustment of preliminaries</u>			
88	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B10.4 Payment certificate cash flow</u>			
89	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B11. GENERAL</u>			
<u>B11.1 Protection of the works</u>			
90	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B11.2 Protection / isolation of existing / sectionally occupied works</u>			
91	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B11.3 Security of the works</u>			
92	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B11.4 Notice before covering work</u>			
93	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>11.5 Disturbance</u>			
94	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B11.6 Environmental disturbance</u>			
95	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B11.7 Works cleaning and clearing</u>			
96	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B11.8 Vermin</u>			
97	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B11.9 Overhand work</u>			
98	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B11.10 Instruction manuals and guarantees</u>			
99	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B11.11 As built information</u>			
100	Fixed: _____ Value related: _____ Time related: _____	Item	
		Carried to Collection	R
Section No. 1			
Bill No. 1			
Preliminaries			

			Amount
101	<u>B11.12 Tenant installations</u>		
	Fixed: _____ Value related: _____ Time related: _____	Item	
102	<u>SECTION C: SPECIFIC PRELIMINARIES</u>		
	Section C contains specific preliminary items which apply to this contract except where N/A (Not Applicable) appears against an item.		
103	<u>C1 CONTRACT DRAWINGS</u>		
	The drawings issued with the tender documents do not comprise the complete set but serve as a guide only for tendering purposes and for indicating the scope of the work to enable the tenderer to acquaint himself with the nature and extent of the works and the manner in which they are to be executed. Should any part of the drawings not be clearly intelligible to the tenderer he shall, before submitting his tender, obtain clarification in writing from the principal agent.	Item	
104	<u>C2 GENERAL PREAMBLES</u>		
	The document "Specification of Materials and Methods to be used (PW371)" is obtainable on request from the head office and all regional offices of the Department, and shall be read in conjunction with the bills of quantities / lump sum document and be referred to for the full descriptions of work to be done and materials to be used.	Item	
104	<u>C3 PROPRIETARY BRANDED PRODUCTS</u>		
	The contractor shall take delivery of, handle, store, use, apply and/or fix all proprietary branded products in strict accordance with the manufacturer's instructions after consultation with the manufacturer's authorised representative. All materials, fittings, finishings, etc., specified hereinafter under a trade name, catalogue number or reference, must be exactly as described. The Architect's approval in writing must be obtained for the use of any alternative to the specification before the submission of tenders otherwise the specified materials, fittings, finishings, etc., will be assumed to have been allowed for in the tender. The Contractor must take delivery of, handle, store, use, apply and/or fix all proprietary branded products in strict accordance with the manufacturer's instructions after consultation with the manufacturer's authorised representative.	Item	
Carried to Collection			
Section No. 1			
Bill No. 1			
Preliminaries			

			Amount
<u>C4 CONTRACTOR'S RESPONSIBILITY</u>			
The Employer, the Principal Agent and the other professional consultants shall not be responsible for any act or omission on the part of the Contractor which may result in any patent or latent defects, in materials or workmanship, breach or neglect of any local regulations. The Contractor shall at all times be responsible for any such neglect, deviation or wrong act, whether the same is discovered before or after the final certificate, or any other Certificate, has been approved			
105	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>C5 OVERTIME</u>			
Should overtime be required to be worked for any reason whatsoever, the costs of such overtime are to be borne by the contractor unless the principal agent has specifically authorised in writing, prior to the execution thereof, that costs for such overtime are to be borne by the employer.			
106	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>C6 AS BUILT DRAWINGS</u>			
The position of construction breaks and the extent of individual concrete pours are to be recorded by the contractor on the structural engineer's drawings and are to be submitted to the principal agent and the structural engineer for their records.			
Three full sets of as-built drawings shall be submitted to the Principal Agent no later than fourteen days after practical completion			
107	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>C7 CONTRACT INSTRUCTIONS</u>			
Contract instructions issued on site are to be recorded in triplicate in a site instruction book which is to be maintained on site by the Contractor. The Contractor shall supply and have available at the site of the works at all times, the following site books:			
a) Contract Instruction Book			
Receiving and recording instructions in a suitable A4 size triplicate book kept on site. Instructions issued shall be recorded by the Architect or other Employer's Agents to whom the Architect has delegated authority to in the book.			
Only instructions issued in such book shall be recognised.			
b) Daily Record Book			
The Contractor shall record in triplicate in a suitable A4 size triplicate book kept at the site, a daily record of work done, all site visits by the Principal Agent and other professional personnel and all events affecting the Works, such as progress, issue of plans, breakdown of machinery, etc. The labour, plant and material on site shall be recorded as well as work performed. Entries must be made by the Contractor and must be signed and forwarded to the Principal Agent for his counter-signature on a daily basis. Copies of these records shall be for the Architect, Quantity Surveyor and Contractor.			
Carried to Collection			
Section No. 1			R
Bill No. 1			
Preliminaries			

			Amount
108	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>C8 LABOUR RECORD</u>			
At the end of each week the contractor shall provide the principal agent with a written record, in schedule form, reflecting the number and description of tradesmen and labourers employed by him and all subcontractors on the works each day			
109	F: V: T:	Item	
<u>C9 PLANT RECORD</u>			
At the end of each week the contractor shall provide the principal agent with a written record, in schedule form, reflecting the number, type and capacity of all plant, excluding hand tools, currently used on the works.			
110	F: V: T:	Item	
<u>C10 ENCROACHMENT</u>			
During the course of the building operations, the Contractor shall be held entirely responsible for any encroachment onto any adjoining properties, buildings, etc., or servitudes and the cost of any remedial measures as required by the Principal Agent shall be borne by the Contractor			
111	F: V: T:	Item	
<u>C11 METHOD STATEMENT</u>			
The Tenderer shall produce, when required to do so by the Principal Agent, a Method Statement outlining the methods of construction and labour and plant resources that he proposes to use in the execution of the Works. Any approval given or observation made by the Principal Agent shall not relieve the Contractor of his sole responsibility to adopt the methods of construction and to provide the labour and plant resources necessary for the due and proper timeous execution of the Works.			
112	F: V: T:	Item	
<u>C12 UNAUTHORISED PERSONS/WORKMEN ON PREMISES</u>			
The Contractor shall at all times strictly exclude all unauthorised persons from the Works and the site and shall set up notice boards to that effect.			
No workmen or labourers (except security guards) are to be allowed under any circumstances to sleep or deposit any kit on the premises. The Contractor must provide any necessary independent shelter or shed required for any labour or watchmen on site, to the approval of the Employer.			
113	F: V: T:	Item	
<u>C13 MODE OF PROCEDURE</u>			
Notwithstanding anything to the contrary contained herein the Principal Agent at all times reserves the right to direct the order in which the various parts of the Contract are to be executed. The Contractor shall give priority to any individual section or portion of the Works that, in the opinion of the Principal Agent, requires to be expedited.			
Carried to Collection			
Section No. 1			
Bill No. 1			
Preliminaries			

			Amount
114	Should it appear, in the Principal Agent's opinion, that work in any area is not being executed in accordance with the requirements of the Contract Programme, the Contractor shall provide additional manpower and resources and shall work additional overtime and do everything else required to bring the work back to programme to the satisfaction of the Principal Agent and to the Contractor's cost F: V: T: <u>C14 LOCATION OF TEMPORARY BUILDINGS AND TEMPORARY SERVICES</u> The Contractor shall provide all necessary temporary works, including temporary roads, tracks, crossings, hardstanding and services, hoardings, dust screens, tunnelling, etc., required for his own and sub-contractors use during the construction and maintenance period There is no guarantee given or implied that Site conditions will be such that the Contractor will be able to erect such temporary works, roads, hardhats, offices, stores and temporary accommodation within the site boundaries and it shall be the Contractor's responsibility to adopt whatever measures he deems necessary in this regard and to obtain all necessary permission and pay all costs in connection therewith	Item	
115	F: V: T: <u>C15 OFFICE ACCOMMODATION</u> The contractor shall provide, maintain and remove on practical completion air conditioned office accommodation with suitable tables and chairs for meetings to be held on the site. Such offices shall be kept clean and fit for use at all times [12.2.18]	Item	
116	F: V: T: <u>C16 STORAGE FACILITIES</u> The Contractor shall provide a Container for storage of materials.	Item	
117	F: V: T: <u>C17 REMOVAL AND MAKING GOOD OF TEMPORARY WORKS, ETC, ON COMPLETION</u> The Contractor shall remove (except where specifically stated otherwise) all temporary works, roads, services and the like used for this contract and shall make good to the entire satisfaction of the Principal Agent any damage resulting therefrom.	Item	
118	F: V: T:	Item	
Carried to Collection			
Section No. 1			
Bill No. 1			
Preliminaries			

SECTION NO. 1
ST MICHAEL'S JUNIOR SECONDARY SCHOOL
BILL NO. 1
PRELIMINARIES
COLLECTION

Amount

Page No

Brought Forward from Page

- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13
- 14
- 15
- 16

Carried To Section Summary

R

Section No. 1
Bill No. 1
Preliminaries

	Unit	Quantity	Rate	Amount
<u>SECTION NO. 1</u> <u>ST MICHAEL'S JUNIOR SECONDARY SCHOOL</u> <u>BILL NO. 2</u> <u>HEALTH AND SAFETY</u> <u>MODEL PREAMBLES</u> The tenderer is referred to the "Model Preambles for Trades 2008" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates. <u>SUPPLEMENTARY PREAMBLES</u> Supplementary preambles and/or specifications are incorporated in these bills of quantities to satisfy the requirements of this project. Such supplementary preambles and/or specifications shall take precedence over the provisions of the General Preambles. The contractor's prices for all items throughout these bills of quantities shall take account of and include where applicable for all of the obligations, requirements and specifications given in the General Preambles and in any supplementary preambles and/or specifications. Prior to pricing the principal contractor must familiarize him/herself with the Occupational Health and Safety Act No. 85 Of 1993, Construction Regulations 2014, other relevant Regulations and Standards as well as project specific Health & Safety specifications. <u>OCCUPATIONAL HEALTH AND SAFETY</u> <u>General</u>				
1	Preparation of Contractor's site specific Health and Safety Plan	Item		
2	Submission of the Health and Safety File	Item		
3	Principal Contractor's initial obligations in respect of the OHS Act and Construction Regulations	Item		
4	Principal Contractor's time related obligations in respect of the OHS Act and Construction Regulations for the entire construction period	Item		
5	Provision of full time Health and Safety Officer for the entire construction period	Item		
6	Induction training of all personnel	Item		
7	Provision of first aid boxes	Item		
Carried to Collection			R	
Section No. 1				
Bill No. 2				
Health And Safety				

	Unit	Quantity	Rate	Amount
8 SANS approved weld mesh type temporary barrier fencing 1,8m high covered with a net fixed to and including 100mm diameter gum poles set securely min 300mm deep in ground at max 3m spacing including excavation, backfilling, etc	m	150		
9 Extra over mesh fence for pedestrian gate size 1.8 x 1,8m high	No	1		
<u>Provision for Personal Protective Equipment and</u>				
10 Reflective vests.	Item			
11 Hard hats	Item			
12 Protective footwear	Item			
13 Ear plugs	Item			
14 Dust masks	Item			
<u>Medical certificates and medical surveillance</u>				
15 Initial (baseline) medical examinations for all personnel	Item			
16 Exit Examinations for all personnel	Item			
<u>Noise Monitoring</u>				
17 Establishment of noise zones	Item			
18 Audiograms	Item			
<u>Covid-19 Compliance Measures</u>				
19 The Contractor is required to price for Covid 19 compliance and the pricing thereof shall be deemed to include all the mandatory requirements	Item			
Carried to Collection			R	
Section No. 1				
Bill No. 2				
Health And Safety				

19

Amount

SECTION NO. 1

ST MICHAEL'S JUNIOR SECONDARY SCHOOL

BILL NO. 2

HEALTH AND SAFETY

COLLECTION

Page No

Brought Forward from Page

18

19

Carried To Section Summary

R

Section No. 1

Bill No. 2

Health And Safety

	Unit	Quantity	Rate	Amount
<u>SECTION NO. 1</u> <u>ST MICHAEL'S JUNIOR SECONDARY SCHOOL</u> <u>BILL NO. 3</u> <u>RENOVATIONS</u> The Tenderer is referred to the relevant Clause in the separate document Model Preambles for Trades (1999 Edition) published by the Association of South African Quantity Surveyors, the document "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition July 2014) and the Supplementary Preambles which are incorporated in these Bills of Quantities <u>SUPPLEMENTARY PREAMBLES</u> <u>View site</u> Before submitting his tender the tenderer shall visit the site and satisfy himself as to the nature and extent of the work to be done and the value of the materials contained in the buildings or portions of the buildings to be demolished. No claim for any variations of the contract sum in respect of the nature and extent of the work or of inferior or damaged materials will be entertained <u>General</u> Water supply pipes and other piping in ground that may be encountered and found necessary to disconnect or cut, shall be effectually stopped off or grubbed up and removed, and any new connections that may be necessary shall be made with proper fittings to the satisfaction of the principal agent <u>MAKING GOOD OF EXISTING WORK</u> <u>Making good VIP pedestals</u>				
1	No	11		
<u>Taking out and removing piping, sanitary fittings, etc including disconnecting piping from fittings and making good floor and wall finishes (making good tiling and paintwork elsewhere)</u>				
2	No	3		
3	No	3		
Carried to Collection			R	
Section No. 1				
Bill No. 3				
Renovations				

		Unit	Quantity	Rate	Amount
4	PVC urinal traps	No	5		
5	Damaged 110mm vent pipes	m	4		
	<u>Making good existing security gates</u>				
6	Repair loose hanging or fallen gates by making good brick walls and then re-installing gates into position with new 13mm diameter x 90mm long expansion applied to existing gate hinges	No	3		
	<u>Making good existing timber doors and frames</u>				
7	Making good good falling doors where plugs to walls have failed by repositioning existing timber door frames and secure by installing new anchors/ plugs including refitting doors to hinges and frames.	No	3		
	<u>Making good existing pit latrine chambers</u>				
8	Allow for de-sludging of existing "long drop" pit latrines by means of "honey sucker". The pit latrines are to be completely empty before any other work is carried out	Litres	5 000		
	<u>BATHROOM FITTINGS</u>				
	<u>Stainless steel bathroom fittings</u>				
9	Free standing She Bin: manufactured from Grade 304 1,2mm Stainless Steel, satin finished with surface treatment. The container to have an approximately 20 litre capacity	No	7		
	<u>GALVANISED STEEL GATES, SCREENS, ETC</u>				
	<u>Welded screens and gates to walls</u>				
10	Entrance single gate size 1,040 x 2,125mm high formed of 25 x 25 x 1.6mm hollow square section framing to detail, with expanded metal mesh welded to inside frame, with 10 x 30mm flat bar shaped to detail and 12mm solid rods welded horizontally, with stainless steel shackle for locking mechanism, with 38 x 38 x 10mm thick plates as hinges with rounded ends to one side and hole for 18mm diameter pin hung on pair of socketted and pinned hinges with pin 18 mm in diameter and bolted to brick wall, with 200mm locking bolt welded on, or other Architect approved hinges	No	1		
	<u>SANITARY FITTINGS</u>				
	<u>Rust and corrosion resistant, UV-resistant polyethylene pedestals, urinals, basins, etc.</u>				
11	VIP 450 Pit pedestal complete with integral flap four times plugged to floor with and including 6 x 75mm masonry anchors.	No	3		
	Carried to Collection			R	
	Section No. 1				
	Bill No. 3				
	Renovations				

	Unit	Quantity	Rate	Amount
<u>TRAPS ETC</u>				
<u>Traps</u>				
12	40mm Chromium plated bottle trap	No	5	
<u>TAP STANDS</u>				
<u>Two 20mm brass bib-taps in tap stands formed of 110mm diameter PVC pipes encased in concrete and cast into the ground complete with connecting to existing tanks with 12m long 20mm HDPE pipes in and including trenches backfilled</u>				
13	700mm High tap stands complete	No	2	
<u>SANITARY PLUMBING</u>				
<u>PVC-U soil and vent pipes</u>				
14	110mm Pipes	m	4	
<u>Extra over PVC-U soil and vent pipes for fittings</u>				
15	Install new brackets/ holder bats anchored to brick walls around existing 110mm diameter vent pipes	No	8	
16	110mm Air vent whirlybird	No	2	
<u>PREAMBLES</u>				
Carried to Collection				R
Section No. 1				
Bill No. 3				
Renovations				

Amount

SECTION NO. 1

ST MICHAEL'S JUNIOR SECONDARY SCHOOL

BILL NO. 3

RENOVATIONS

COLLECTION

Page No

Brought Forward from Page

21

22

23

Carried To Section Summary

R

Section No. 1

Bill No. 3

Renovations

	Unit	Quantity	Rate	Amount
<u>SECTION NO. 1</u> <u>ST MICHAEL'S JUNIOR SECONDARY SCHOOL</u> <u>BILL NO. 4</u> <u>GARDEN AND BALUSTRADE WALLS</u> <u>PREAMBLES</u> The Tenderer is referred to the relevant Clause in the separate document Model Preambles for Trades (1999 Edition) published by the Association of South African Quantity Surveyors, the document "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition July 2014) and the Supplementary Preambles which are incorporated in these Bills of Quantities <u>EARTHWORKS (PROVISIONAL)</u> <u>Excavate in pickable material not exceeding 2m deep below natural or reduced ground level:</u>				
1	Surface trenches.	m ³	23	
	<u>Extra over excavation in pickable material for column bases, trenches, lift pits, sumps, etc for excavation:</u>			
2	Soft rock.	m ³	1	
3	Hard rock.	m ³	1	
4	Allow for risk of collapse to sides of excavations to column bases, trenches, etc. from ground level to not exceeding 1,5m deep.	m ²	92	
5	Allow for keeping excavations entirely free from water or mud.	Item		
	<u>Earth filling obtained from the excavations and/or prescribed stock piles on site, compacted to 98% Mod AASHTO density</u>			
6	Backfilling to trenches, holes, etc.	m ³	4	
7	Scarify in-situ material for a depth of 150mm and compact to obtain 98% modified AASHTO dry density.	m ²	39	
	<u>Earth filling supplied by the contractor, compacted to 98% Mod AASHTO density</u>			
8	Under floors, steps, pavings, etc.	m ³	4	
Carried to Collection			R	
Section No. 1				
Bill No. 4				
Garden And Balustrade Walls				

26

Amount

SECTION NO. 1

ST MICHAEL'S JUNIOR SECONDARY SCHOOL

BILL NO. 4

GARDEN AND BALUSTRADE WALLS

COLLECTION

Page No

Brought Forward from Page

25

26

Carried To Section Summary

R

Section No. 1

Bill No. 4

Garden And Balustrade Walls

	Unit	Quantity	Rate	Amount
<u>SECTION NO. 1</u> <u>ST MICHAEL'S JUNIOR SECONDARY SCHOOL</u> <u>BILL NO. 5</u> <u>V-DRAINS</u> <u>PREAMBLES</u> The Tenderer is referred to the relevant Clause in the separate document Model Preambles for Trades (1999 Edition) published by the Association of South African Quantity Surveyors, the document "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition July 2014) and the Supplementary Preambles which are incorporated in these Bills of Quantities <u>SUPPLEMENTARY PREAMBLES</u> <u>Nature of ground:</u> The nature of the ground is assumed to be loose sandy material, therefore 'earth', but possibly interspersed with 'soft rock' or 'hard rock' <u>Carting away of excavated material:</u> Descriptions of carting away of excavated material shall be deemed to include loading excavated material onto trucks directly from the excavations or, alternatively, from stock piles situated on the building site <u>Filling:</u> Notwithstanding the reference to prescribed multiple handling in clause 1 page 6 of the Standard System of Measuring Building Work, prices for filling and backfilling shall include for all selection and any necessary multiple handling of material <u>Testing:</u> Prices for filling are to include for all necessary density tests in accordance with SABS 1200D <u>Cost of tests:</u> The costs of making, storing and testing of concrete test cubes as required under clause 7 Tests of SABS 1200 G shall include the cost of providing cube moulds necessary for the purpose, for testing costs and for submitting reports on the tests to the principal agent. The testing shall be undertaken by an independent firm or institution nominated by the contractor to the approval of the principal agent. (Test cubes are measured separately)				
Carried to Collection			R	
Section No. 1				
Bill No. 5				
V-drains				

		Unit	Quantity	Rate	Amount
	<u>EXCAVATION ETC</u>				
	<u>Excavation in earth not exceeding 2m deep</u>				
1	Reduced levels under pavings	m ³	20		
	<u>Extra over all excavations for carting away</u>				
2	Surplus material from excavations and/or stock piles on site, to a dumping site to be located by the contractor	m ³	20		
	<u>FILLING ETC OTHER THAN BULK</u>				
	<u>Earth filling (G7 material) supplied by the contractor, compacted to 95% Mod AASHTO density</u>				
3	Under floors, steps, pavings, etc.	m ³	13		
	<u>Coarse river sand filling supplied by the contractor</u>				
4	Under pavings etc.	m ³	4		
	<u>Compaction of surfaces</u>				
5	Compaction of ground surface under floors etc. including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 98% Mod AASHTO density	m ²	88		
	<u>Prescribed density tests on filling</u>				
6	Modified AASHTO Density test	No	8		
	<u>DAMPPROOFING OF WALLS AND FLOORS</u>				
	<u>One layer 250 micron green polyethylene waterproof sheeting (SANS 952-1985 type C) sealed at laps with PVC self-adhesive tape</u>				
7	Under surface pavings etc.	m ²	88		
	<u>STORMWATER DRAINAGE (PROVISIONAL)</u>				
	<u>Precast or in-situ concrete (25 MPa) open stormwater channels having V-shaped waterway formed in top, finished smooth on all exposed surfaces in (3:1) untinted cement plaster trowelled smooth and with angles rounded, cast in maximum 3000mm lengths, and reinforced as necessary for handling if precast, including laying to falls, bedding and pointing in (3:1) cement mortar:</u>				
8	Channel size 700 x 230mm overall with 700 x 150mm deep v-channel waterway.	m	125		
9	Extra for angle.	No	3		
10	Extra for irregular T-intersection.	No	1		
11	Extra for fair end.	No	3		
	Carried to Collection			R	
	Section No. 1				
	Bill No. 5				
	V-drains				

		Unit	Quantity	Rate	Amount
12	Extra for 1000mm long x 2700mm wide outlet with 300mm deep x 300mm wide thickened edge and thirteen number 150 x 150 x 150mm concrete block energy dissipaters set into in-situ concrete draining off to and including a 2700 x 600 x 100mm thick bed formed of 19mm diameter stones	No	2		
13	Stormwater dish drain size 900 x 600 x 900mm wide (2400 wide overall) x 300mm deep with 2400 x 150mm deep waterway.	m	1		
<u>TEST CUBES</u>					
<u>Test Cubes</u>					
14	Making and testing 150 x 150 x 150mm concrete strength test cube (Provisional)	No	6		
<u>REINFORCEMENT (CPAP WORK GROUP NO. 114)</u>					
<u>Fabric reinforcement</u>					
15	Type 617 fabric reinforcement in concrete dish drains etc	m ²	85		
<u>THE FOLLOWING IN EARTH DRAINS</u>					
<u>Bulk excavation in earth</u>					
16	Earth drains/ channels not exceeding 2m deep	m ³	23		
17	On walls	m ²	2		
18	Carting away material arising from excavations	m ³	23		
Carried to Collection				R	
Section No. 1					
Bill No. 5					
V-drains					

Amount

SECTION NO. 1

ST MICHAEL'S JUNIOR SECONDARY SCHOOL

BILL NO. 5

V-DRAINS

COLLECTION

Page No

Brought Forward from Page

28

29

30

Carried To Section Summary

R

Section No. 1

Bill No. 5

V-drains

	Unit	Quantity	Rate	Amount
<u>SECTION NO. 1</u> <u>ST MICHAEL'S JUNIOR SECONDARY SCHOOL</u> <u>BILL NO. 6</u> <u>CONCRETE WALKWAYS & RAMPS</u> <u>PREAMBLES</u> The Tenderer is referred to the relevant Clause in the separate document Model Preambles for Trades (1999 Edition) published by the Association of South African Quantity Surveyors, the document "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition July 2014) and the Supplementary Preambles which are incorporated in these Bills of Quantities <u>EARTHWORKS (PROVISIONAL)</u> <u>Earth filling (G7 material) supplied by the contractor, compacted to 95% Mod AASHTO density</u> 1 Under floors, steps, pavings, etc. m ³ 4 <u>CONCRETE, FORMWORK & REINFORCEMENT</u> <u>25MPa Mass concrete in:</u> 2 Ramps m ³ 5 3 APRONS m ³ 1 <u>Sundries:</u> 4 Strike off and cure tops of surface beds laid in panels approximately 1000mm long x 1000mm wide to uniform levels including all necessary formwork to form toggle joints to temporary construction joints to falls. m ² 34 5 Extra for floating off smooth tops of surface beds laid in panels to brush finish including slightly rounded edges to panels. m ² 34 <u>Expansion Joints:</u> 6 12mm "Flexcell" or other approved cane fibre filler board in expansion joint between edge of concrete paving and walls in narrow widths not exceeding 150mm wide including tacking to face of wall. m 125 <u>TEST CUBES</u> <u>Test Cubes</u> 7 Making and testing 150 x 150 x 150mm concrete strength test cube (Provisional) No 3 Carried to Collection R Section No. 1 Bill No. 6 Concrete Walkways & Ramps				

		Unit	Quantity	Rate	Amount
<u>SMOOTH FORMWORK (DEGREE OF ACCURACY II)</u>					
<u>(CPAP WORK GROUP NO. 111)</u>					
<u>Smooth formwork to sides</u>					
8	Edges, risers, ends and reveals not exceeding 300mm high or wide	m	32		
<u>REINFORCEMENT (CPAP WORK GROUP NO. 114)</u>					
<u>Fabric reinforcement</u>					
9	Type 617 fabric reinforcement in concrete surface beds etc	m ²	188		
<u>DAMPPROOFING OF WALLS AND FLOORS</u>					
<u>One layer 250 micron green polyethylene waterproof sheeting (SANS 952-1985 type C) sealed at laps with PVC self-adhesive tape</u>					
10	Under surface pavings etc.	m ²	188		
				R	
Carried to Collection					
Section No. 1					
Bill No. 6					
Concrete Walkways & Ramps					

33

Amount

SECTION NO. 1

ST MICHAEL'S JUNIOR SECONDARY SCHOOL

BILL NO. 6

CONCRETE WALKWAYS & RAMPS

COLLECTION

Page No

Brought Forward from Page

32

33

Carried To Section Summary

R

Section No. 1

Bill No. 6

Concrete Walkways & Ramps

	Unit	Quantity	Rate	Amount
<u>SECTION NO. 1</u>				
<u>ST MICHAEL'S JUNIOR SECONDARY SCHOOL</u>				
<u>BILL NO. 7</u>				
<u>SUBSOIL DRAINAGE</u>				
<u>PREAMBLES</u>				
The Tenderer is referred to the relevant Clause in the separate document Model Preambles for Trades (1999 Edition) published by the Association of South African Quantity Surveyors, the document "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition July 2014) and the Supplementary Preambles which are incorporated in these Bills of Quantities				
<u>SUPPLEMENTARY PREAMBLES</u>				
<u>THE FOLLOWING IN STORMWATER SOAKAWAYS</u>				
<u>Site clearance</u>				
1 Digging up and removing rubbish, debris, vegetation, hedges, shrubs, bush, etc. and trees not exceeding 200mm girth	m ²	2		
<u>Subsoil drainage</u>				
<u>Laying, backfilling, bedding, etc. of pipes</u>				
2 Excavation in earth not exceeding 2m deep for pipe trenches and holes	m ³	2		
Pipes shall be laid and bedded in accordance with manufacturers' instructions and trenches shall be carefully backfilled				
<u>As-built drawings:</u>				
Where required, the contractor shall prepare an updated set of as-built drawings. At completion of the contract the contractor shall hand these drawings to the principal agent for reproducing onto the originals for handing over to the employer (provision for allowance of as-built drawings elsewhere)				
<u>SUBSOIL DRAINAGE (CPAP WORK GROUP NO. 146)</u>				
<u>Site clearance</u>				
3 Digging up and removing rubbish, debris, vegetation, hedges, shrubs, bush, etc. and trees not exceeding 200mm girth	m ²	122		
Carried to Collection			R	
Section No. 1 Bill No. 7 Subsoil Drainage				

		Unit	Quantity	Rate	Amount
<u>Subsoil drainage</u>					
4	Excavation in earth not exceeding 2m deep for pipe trenches	m³	73		
5	Extra over all excavations for carting away surplus material from excavations and/or stock piles on site, to a dumping site to be located by the contractor	m³	73		
6	Risk of collapse to sides of trench and hole excavation exceeding 1.5m but not exceeding 3.0m deep	m²	324		
7	Keeping excavations free of water	Item			
8	Filling in bedding under and filling around pipes with granular material supplied by the contractor and compacted to 98% Mod AASHTO density	m³	55		
9	19mm Crushed stone encasing to pipes	m³	18		
<u>Slotted uPVC flexible drainage pipes</u>					
10	160mm Pipes laid in stone encasing (encasing elsewhere)	m	180		
<u>Extra over slotted uPVC flexible drainage pipes for fittings</u>					
11	110mm Bend	No	9		
<u>Geotextle filter fabric blanket with stiched 300mm laps</u>					
12	Around stone filling in sub-soil drain trenches	m²	162		
Carried to Collection					R
Section No. 1					
Bill No. 7					
Subsoil Drainage					

Amount

SECTION NO. 1

ST MICHAEL'S JUNIOR SECONDARY SCHOOL

BILL NO. 7

SUBSOIL DRAINAGE

COLLECTION

Page No

Brought Forward from Page

35

36

Carried To Section Summary

R

Section No. 1

Bill No. 7

Subsoil Drainage

	Unit	Quantity	Rate	Amount
<u>SECTION NO. 1</u>				
<u>ST MICHAEL'S JUNIOR SECONDARY SCHOOL</u>				
<u>BILL NO. 8</u>				
<u>SOAKAWAYS & CULVERTS</u>				
<u>THE FOLLOWING IN STORMWATER SOAKAWAYS</u>				
<u>Site clearance</u>				
1 Digging up and removing rubbish, debris, vegetation, hedges, shrubs, bush, etc. and trees not exceeding 200mm girth	m ²	2		
<u>Subsoil drainage</u>				
2 Excavation in earth not exceeding 2m deep for pipe trenches and holes	m ³	2		
3 Extra over all excavations for carting away surplus material from excavations and/or stock piles on site, to a dumping site to be located by the contractor	m ³	2		
4 Risk of collapse to sides of trench and hole excavation not exceeding 1.5m deep	m ²	1		
5 Risk of collapse to sides of trench and hole excavation exceeding 1.5m but not exceeding 3.0m deep	m ²	7		
6 Keeping excavations free of water	Item			
7 Filling in bedding under and filling around pipes with granular material supplied by the contractor and compacted to 98% Mod AASHTO density	m ³	2		
8 63mm Stone beds	m ³	1		
<u>Geotextle filter fabric blanket with stiched 300mm laps</u>				
9 Around stone filling in sub-soil drain trenches	m ²	2		
Carried To Section Summary			R	
Section No. 1				
Bill No. 8				
Soakaways & Culverts				

39

		Unit	Quantity	Rate	Amount
6	150mm Ditto as straining or corner posts, but fitted with two 75mm diameter galvanised steel raking stays and with top ends flattened and bolted through post with post embedded in 600 x 600 x 700mm high mass concrete (15MPa) base and stays embedded in 700 x 700 x 450mm high mass concrete (15MPa) base	No	5		
7	150mm Ditto as end/ gate post, but fitted with one 75mm diameter galvanised steel stay set raking and with top end flattened and bolted through post, with post embedded in 600 x 600 x 700mm mass concrete (15MPa) base and stay embedded in 700 x 700 x 450mm high mass concrete (15MPa) base with all base tops set raking (sloping)	No	6		
	<u>Gates</u>				
8	Security fence single gate, size 900 mm wide x 1800 mm high, formed of 50 mm diameter nominal bore x 2,2 mm wall thickness hot dip galvanised mild steel pipe framing all round with mitred and welded angles and middle rail, with 20mm diameter x 300mm long locking bolt welded on and a pair of heavy duty gate hooks for a 16mm band hinge pin welded on to gate and including a pair of 16mm band hinge pins bolted to gate posts	No	1		
9	Security fence single gate, size 1500 mm wide x 1800 mm high, formed of 50 mm diameter nominal bore x 2,2 mm wall thickness hot dip galvanised mild steel pipe framing all round with mitred and welded angles and middle rail, hung on pair of socketted and pinned hinges with pin 18mm in diameter and bolted to brick wall and with 20mm diameter x 300mm long locking bolt welded on.	No	1		
10	Double gate, size 6 000 mm wide x 1 800 mm high overall in two leaves, formed of 50 mm diameter nominal bore x 2.5 mm wall thickness hot dip galvanised mild steel pipe framing all round with 25 mm diameter nominal bore x 2.0 mm wall thickness diagonal and centre braces, scribed and welded into angles and at cross intersections, gate filled with 50 x 50 x 2,0mm galvanised wire diamond mesh, with two 50 mm diameter nominal bore x 3,25 mm wall thickness security posts each 600 mm long with one end welded to top rail of gate and closure plate to other end, each leaf fitted with two 25 mm diameter x 300 mm long eyebolt hinges and stops including all holes, etc., welded or bolted to adjoining galvanised gatepost with and including 500 mm long approved chain spot welded to gate	No	1		
	Carried to Collection			R	
	Section No. 1				
	Bill No. 9				
	Grade R Fencing				

		Unit	Quantity	Rate	Amount
11	<u>Locks</u>				
	50mm "Viro" or other equally approved padlocks for external use.	No	3		
Carried to Collection				R	
Section No. 1					
Bill No. 9					
Grade R Fencing					
41					

Amount

SECTION NO. 1

ST MICHAEL'S JUNIOR SECONDARY SCHOOL

BILL NO. 9

GRADE R FENCING

COLLECTION

Page No

Brought Forward from Page

39

40

41

Carried To Section Summary

R

Section No. 1

Bill No. 9

Grade R Fencing

		Amount	
<u>SECTION NO. 1</u>			
<u>ST MICHAEL'S JUNIOR SECONDARY SCHOOL</u>			
<u>BILL NO. 10</u>			
<u>PROVISIONAL SUMS</u>			
<u>PROVISIONAL SUMS</u>			
<u>Supplementary Preambles</u>			
Tenderers are advised that no claim in respect of loss of profit or Preliminary charges based on the omission of these amounts will be considered and the said amounts will be omitted strictly without any financial compensation payable to the Contractor.			
Provisional sums and Budgetary allowances contained herein may be omitted or reduced at the Employer's discretion and the Contractor shall not be entitled to claim for any loss by way of reductions or omission of any discount, or percentage relating to Provisional amounts and Budgetary sums or any loss of profit related thereto.			
<u>BUDGETARY ALLOWANCES</u>			
<u>Sundry building work</u>			
1	Provide the sum of R22 500.00 for the employment of a Community Liaison Officer to be employed by the Main Contractor and be paid an allowance of R7 500.00 a month for the duration (3 months)	Item	22 500 00
2	Profit	Item	
3	Attendance	Item	
4	Provide the sum of R105 000. 00 for the hire, maintenance and servicing of temporary toilets for educators and learners during the entire constructions period	Item	105 000 00
5	Profit	Item	
6	Attendance	Item	
7	Provide the sum of R20 000. 00 for landscaping to be used as directed by the Principal Agent and deducted in whole or in part if not required	Item	20 000 00
8	Profit	Item	
9	Attendance	Item	
<u>Contingencies</u>			
10	Allow the Amount of R40 000.00 (Forty Thousand Rands) for contingencies, to be used by the Architect in terms of Clause 17 of the Principal Building Agreement.	Item	40 000 00
Carried To Section Summary		R	
Section No. 1			
Bill No. 10			
Provisional Sums			

Amount

SECTION NO. 1
ST MICHAEL'S JUNIOR SECONDARY SCHOOL
SECTION SUMMARY

Bill No.		Page
1	PRELIMINARIES	17
2	HEALTH AND SAFETY	20
3	RENOVATIONS	24
4	GARDEN AND BALUSTRADE WALLS	27
5	V-DRAINS	31
6	CONCRETE WALKWAYS & RAMPS	34
7	SUBSOIL DRAINAGE	37
8	SOAKAWAYS & CULVERTS	38
9	GRADE R FENCING	42
10	PROVISIONAL SUMS	43

Section No. 1
SECTION SUMMARY

Carried to Final Summary

R

SECTION NO. 2

BAMBOESPRUIT JUNIOR SECONDARY SCHOOL

Amount

SECTION NO. 2

BAMBOESPRUIT JUNIOR SECONDARY SCHOOL

BILL NO. 1

PRELIMINARIES

BUILDING AGREEMENT AND PRELIMINARIES

1. The Principal Building Agreement shall be the JBCC Series Edition 4.1, March 2005 as recommended by the Joint Building Contracts Committee and as amended by this Tender Enquiry.
2. The Preliminaries shall be JBCC Series 2000, May 2005 for use with the Principal Building Agreement as recommended by the joint Building Contracts Committee and as amended by this Tender Enquiry shall be deemed to be incorporated herein.
3. The tenderor is deemed to have referred to the abovementioned documents for the full intent and meaning of each clause. The clauses in the abovementioned documents are hereinafter referred to by clause number and heading only.
4. Where standard clauses or alternatives are not entirely applicable to this contract, such modifications, corrections or additions as are necessary, are given as far as possible under each relevant clause heading. Additional Preliminary clauses are contained in Section C hereof.
5. No claim whatsoever shall be entertained in respect of errors or omissions in pricing due to brevity of descriptions of items which are fully described when read in conjunction with the relevant clauses of the said Principal Building Agreement, Preliminaries and Preambles.
6. The Tenderers shall allow opposite each of the clauses whatever costs and charges he may consider necessary for the carrying out, complying with and due observance of the provisions, conditions and requirements set out herein. Only priced items will be considered in respect of any adjustment of this Section. Any items left unpriced will be understood to be provided free of charge and no claim for any extras arising out of the Tenderer's omission to price any item will be entertained.
7. Where modifications or amendments as described are made, such modifications and/or amendments shall supercede any conflicting provisions in the relevant clauses of the Standard Preliminaries or the Principal Building Agreement and the Tenderer shall make due allowance for whatever costs and charges he may consider necessary for the carrying out and observance of the provisions of the clauses as modified and/or amended.
8. Where any item is not relevant to this specific contract, such item is marked N/A.
9. If Alternative A as set out in clause B10.3 hereinafter is to be used for the adjustment of the preliminaries, each item priced is to be allocated to one or more of the three categories by insertion of "F", "V", "T" as the case may be against the price in the "rate" column immediately preceding the "amount" column, where "F" denotes a fixed amount (amount not to be varied), "V" denotes an amount variable in proportion to value, and "T" denotes an amount proportionate to time.

Carried to Collection

R

Section No. 2

Bill No. 1

Preliminaries

			Amount
<u>SECTION A: JBCC PRINCIPAL BUILDING AGREEMENT</u>			
<u>DEFINITIONS</u>			
<u>A1 DEFINITIONS AND INTERPRETATION</u>			
<u>Clause 1.0:</u>			
1	Fixed:_____ Value related:_____ Time related:_____0	Item	
<u>OBJECTIVE AND PREPARATION</u>			
<u>A2 OFFER, ACCEPTANCE AND PERFORMANCE</u>			
<u>Clause 2.0</u>			
2	Fixed:_____ Value related:_____ Time related:_____	Item	
<u>A3 DOCUMENTS</u>			
<u>Clause 3.0</u>			
Clause 3.1 is deleted and substituted with: 'This tender is for a Government Contract. No Payment Guarantee will be provided.'			
Clause 3.3 is deleted and substituted with:			
The principal agent shall complete the schedule and arrange for formal signing of the agreement once the priced bill of quantities/lump sum document, security, insurances and waiver of lien, where acceptable, have been provided and effected'			
3	Fixed:_____ Value related:_____ Time related:_____	Item	
<u>A4 DESIGN RESPONSIBILITY</u>			
<u>Clause 4.0</u>			
4	Fixed:_____ Value related:_____ Time related:_____	Item	
<u>A5 EMPLOYERS AGENTS</u>			
<u>Clause 5.0</u>			
5	Fixed:_____ Value related:_____ Time related:_____	Item	
<u>A6 SITE REPRESENTATIVE</u>			
<u>Clause 6.0</u>			
6	Fixed:_____ Value related:_____ Time related:_____	Item	
<u>A7 COMPLIANCE WITH REGULATIONS</u>			
7	Fixed:_____ Value related:_____ Time related:_____	Item	
<u>Clause 7.0</u>			
8	Fixed:_____ Value related:_____ Time related:_____	Item	
<u>A8 WORKS RISK</u>			
<u>Clause 8.0</u>			
9	Fixed:_____ Value related:_____ Time related:_____	Item	
Carried to Collection		R	
Section No. 2			
Bill No. 1			
Preliminaries			

			Amount
<u>A9 INDEMNITIES</u>			
<u>Clause 9.0</u>			
Clause 9.1.1 is deleted and substituted with:			
Claims from other parties consequent upon death of bodily injury or illness of any person or physical loss or damage to any property, other than the works, arising out or due to the execution of the works or occupation of the site by the contractor or his sub contractors'.			
10	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A10 WORKS INSURANCES</u>			
<u>Clause 10.0</u>			
11	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A11 LIABILITY INSURANCES</u>			
<u>Clause 11.0</u>			
12	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A12 EFFECTING INSURANCES</u>			
<u>Clause 12.0</u>			
13	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A13. No clause</u>			
14	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A14 SECURITY</u>			
<u>Clause 14.0</u>			
15	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>EXECUTION</u>			
<u>A15 PREPERATION FOR AND EXECUTION OF THE WORKS</u>			
<u>Clause 15.0</u>			
16	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A16 ACCESS TO THE WORKS</u>			
<u>Clause 16.0</u>			
17	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A17 CONTRACT INSTRUCTIONS</u>			
<u>Clause 17.0</u>			
18	Fixed: _____ Value related: _____ Time related: _____	Item	
Carried to Collection			
Section No. 2			
Bill No. 1			
Preliminaries			

			Amount
<u>A18 SETTING OUT OF THE WORKS</u>			
<u>Clause 18.0</u>			
The contractor shall notify the principal agent if any encroachments of adjoining foundations, buildings, structures, pavements, boundaries, etc., exist in order that the necessary arrangements may be made for the rectification of any such encroachments. Should incorrect information be given to the contractor in terms of 18.1 and 18.2, which causes the incorrect setting out of the works, the contractor shall not be liable for such incorrect setting out			
19	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A19 ASSIGNMENT</u>			
<u>Clause 19.0</u>			
20	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A20 NOMINATED SUB-CONTRACTORS</u>			
<u>Clause 20.0</u>			
21	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A21 SELECTED SUBCONTRACTORS</u>			
<u>Clause 21.0</u>			
22	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A22 EMPLOYER'S DIRECT CONTRACTORS</u>			
<u>Clause 22.0</u>			
23	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A23 CONTRACTOR'S DOMESTIC SUBCONTRACTORS</u>			
<u>Clause 23.0</u>			
24	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>COMPLETION</u>			
<u>A24 PRACTICAL COMPLETION</u>			
<u>Clause 24.0</u>			
25	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A25 WORK'S COMPLETION</u>			
<u>Clause 25.0</u>			
26	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A26 FINAL COMPLETION</u>			
<u>Clause 26.0</u>			
27	Fixed: _____ Value related: _____ Time related: _____	Item	
Carried to Collection		R	
Section No. 2			
Bill No. 1			
Preliminaries			

			Amount
<u>A27 LATENT DEFECTS LIABILITY PERIOD</u>			
<u>Clause 27.0</u>			
Clause 27.0 is amended by the addition of the following clauses:			
"27.3 Any water leakage into the building, whether in the roof, external wall or other element of the building susceptible to water leakage shall, unless proven to be a design defect, or as a result of obvious storm damage, be classified as a latent defect in terms of clause 1.0 Definitions and Interpretations".			
"27.4 The Contractor shall attend to defects during the Defects Liability Period on a progressive basis, to the satisfaction of the Principal Agent and will not be permitted to wait until the end of the Defect Liability Period or until the amount of defects accumulates in order to attend to a comprehensive list of defects"			
28	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A28 SECTIONAL COMPLETION</u>			
<u>Clause 28.0</u>			
29	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A29 REVISION OF DATE FOR PRACTICAL COMPLETION</u>			
<u>Clause 29.0</u>			
30	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A30 PENALTY FOR NON-COMPLETION</u>			
<u>Clause 30.0</u>			
31	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>PAYMENT</u>			
<u>A31 INTERIM PAYMENT TO THE CONTRACTOR</u>			
<u>Clause 31.0</u>			
The inclusion of materials and goods stored off site in the amount authorised for payment in terms of clause 31.3 shall be at the sole discretion of the principal agent and such inclusion shall only be considered upon the provision, by the contractor, of an approved guarantee issued by a registered commercial bank.			
Where prices are submitted by the contractor or nominated/selected sub-contractor during the progress of the works in respect of contract instructions or in regard to a claim under the terms of the contract and notwithstanding the fact that such prices may be used in an interim payment certificate, there is to be no presumption of acceptance. Should the principal agent wish to accept any such prices prior to the issue of the final certificate, it will be in writing.			
32	Fixed: _____ Value related: _____ Time related: _____	Item	
Carried to Collection			
Section No. 2			
Bill No. 1			
Preliminaries			

			Amount
<u>A32 ADJUSTMENT TO THE CONTRACT VALUE</u>			
<u>Clause 32.0</u>			
33	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A33 RECOVERY OF EXPENSE AND LOSS</u>			
<u>Clause 33.0</u>			
34	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A34 FINAL ACCOUNT AND FINAL PAYMENT</u>			
<u>Clause 34.0</u>			
35	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A35 PAYMENT TO OTHER PARTIES</u>			
<u>Clause 35.0</u>			
36	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>CANCELLATION</u>			
<u>A36 CANCELLATION BY EMPLOYER - CONTRACTOR'S DEFAULT</u>			
<u>Clause 36.0</u>			
37	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A37 CANCELLATION BY EMPLOYER - LOSS AND DAMAGE</u>			
<u>Clause 37.0</u>			
38	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A38 CANCELLATION BY CONTRACTOR - EMPLOYER'S DEFAULT</u>			
<u>Clause 38.0</u>			
39	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A39 CANCELLATION - CESSATION OF THE WORKS</u>			
<u>Clause 39.0</u>			
40	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>DISPUTE</u>			
<u>A40 DISPUTE SETTLEMENT</u>			
<u>Clause 40.0</u>			
41	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>SUBSTITUTE PROVISIONS</u>			
<u>A41 STATE CLAUSES</u>			
<u>Clause 41.0</u>			
42	Fixed: _____ Value related: _____ Time related: _____	Item	
Carried to Collection		R	
Section No. 2			
Bill No. 1			
Preliminaries			

			Amount
<u>CONTRACT VARIABLES</u>			
<u>THE SCHEDULE (C1.2 CONTRACT DATA)</u>			
<u>A42 PRE-TENDER INFORMATION</u>			
<u>Clause 42.0</u>			
Tenderers are referred to the document C1.2 Contract Data for variables pertaining to this contract.			
43	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>SECTION B: JBCC PRELIMINARIES</u>			
<u>B1.0 DEFINITIONS AND INTERPRETATION</u>			
<u>B1.1 Definitions and interpretation</u>			
44	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B2.0 DOCUMENTS</u>			
<u>B2.1 Checking of documents</u>			
Notwithstanding the issue of the tender drawings, it will remain the responsibility of the Tenderer to study all available drawings at the offices of the Principal Agent during normal working hours in order to acquaint himself with all the cost implications of the design, programming, phasing, etc.			
45	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B2.2 Provisional bills of quantities</u>			
Prime Cost Amounts, Budgetary Allowances, Provisional Amounts, etc., contained herein may be omitted or reduced at the Principal Agent's sole discretion and the Contractor shall not be entitled to claim for any loss by way of reduction or omission of any discount, or percentage relating to Prime Cost Amounts, Budgetary Allowances, Provisional Amounts, Provisional Quantities, etc., or loss of profit related thereto.			
46	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B2.3 Availability of construction documentation</u>			
47	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B2.4 Interests of agents</u>			
48	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B2.5 Priced documents</u>			
49	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B2.6 Tender submission</u>			
Notwithstanding anything contained in this clause, Tenders shall be valid for a period of 20 (Twenty) weeks from the closing date of tenders.			
50	Fixed: _____ Value related: _____ Time related: _____	Item	
Carried to Collection		R	
Section No. 2			
Bill No. 1			
Preliminaries			

			Amount
<u>B3.0 THE SITE</u>			
<u>B3.1 Defined works area</u>			
The area of the works to be occupied by the contractor, any restriction on the area and the limit of access or exit will be pointed out to the contractor by the principal agent on handing over of the site.			
Workmen employed on the site are to be restricted to the immediate area of the site and access thereto.			
The Tenderer shall make all necessary provision in all rates to take into account these requirements as no claims for extras arising from these matters will be subsequently entertained or admitted.			
51	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B3.2 Geotechnical investigation</u>			
52	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B3.3 Inspection of the site</u>			
53	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B3.4 Existing premises occupied</u>			
54	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B3.5 Previous work - dimensional accuracy</u>			
55	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B3.6 Previous work - defects</u>			
56	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B3.7 Services - known</u>			
57	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B3.8 Services - unknown</u>			
58	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B3.9 Protection of trees</u>			
59	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B3.10 Articles of value</u>			
60	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B3.11 Inspection of adjoining properties</u>			
61	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B4.0 MANAGEMENT OF CONTRACT</u>			
<u>B4.1 Management of the works</u>			
62	Fixed: _____ Value related: _____ Time related: _____	Item	
Carried to Collection		R	
Section No. 2			
Bill No. 1			
Preliminaries			

			Amount
<u>B4.2 Programme for the works</u>			
63	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B4.3 Progress meetings</u>			
64	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B4.4 Technical meetings</u>			
65	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B4.5 Labour and plant records</u>			
66	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B5.0 SAMPLES, SHOP DRAWINGS AND MANUFACTURERS' INSTRUCTIONS</u>			
<u>B5.1 Samples of materials</u>			
67	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B5.2 Workmanship samples</u>			
68	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B5.3 Shop drawings</u>			
69	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B5.4 Compliance with manufacturers instructions</u>			
70	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B6.0 TEMPORARY WORKS AND PLANT</u>			
<u>B6.1 Deposits and fees</u>			
71	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B6.2 Enclosure of the works</u>			
The contractor shall erect, maintain and remove at completion, hoardings, safety screens, barriers, access gates, covered gangways and the like as necessary for the enclosure of the works and elements thereof all for the protection of the public and others.			
72	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B6.3 Advertising</u>			
73	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B6.4 Plant, equipment, sheds and offices</u>			
74	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B6.5 Main notice board</u>			
75	Fixed: _____ Value related: _____ Time related: _____	Item	
Carried to Collection		R	
Section No. 2			
Bill No. 1			
Preliminaries			

			Amount
	<u>B6.6 Subcontractors' notice board</u>		
76	Fixed: _____ Value related: _____ Time related: _____	Item	
	<u>B7.0 TEMPORARY SERVICES</u>		
	<u>B7.1 Location</u>		
77	Fixed: _____ Value related: _____ Time related: _____	Item	
	<u>B7.2 Water</u>		
	The contractor shall provide water for the works in accordance with: Alternative A (i.e. to be provided for by the Contractor).		
78	Fixed: _____ Value related: _____ Time related: _____	Item	
	<u>B7.3 Electricity</u>		
	The contractor shall provide electricity for the works in accordance with: Alternative A (i.e. to be provided for by the Contractor).		
79	Fixed: _____ Value related: _____ Time related: _____	Item	
	<u>B7.4 Telecommunication facilities</u>		
	The contractor shall provide telephones on site for the works in accordance with: Alternative A (i.e. to be provided for by the Contractor).		
80	Fixed: _____ Value related: _____ Time related: _____	Item	
	<u>B7.5 Ablution facilities</u>		
	The contractor shall provide toilet facilities on site for the works in accordance with: Alternative A (i.e. to be provided for by the Contractor).		
81	Fixed: _____ Value related: _____ Time related: _____	Item	
	<u>B8.0 PRIME COST AMOUNTS</u>		
	<u>B8.1 Responsibility for prime cost amounts</u>		
82	Fixed: _____ Value related: _____ Time related: _____	Item	
	<u>9.0 ATTENDANCE ON N/S SUBCONTRACTORS</u>		
	<u>B9.1 General attendance</u>		
83	Fixed: _____ Value related: _____ Time related: _____	Item	
	<u>B9.2 Special attendance</u>		
84	Fixed: _____ Value related: _____ Time related: _____	Item	
	<u>B9.3 Commissioning - fuel, water and electricity</u>		
85	Fixed: _____ Value related: _____ Time related: _____	Item	
	Carried to Collection	R	
	Section No. 2		
	Bill No. 1		
	Preliminaries		

			Amount
<u>B10.0 FINANCIAL ASPECTS</u>			
<u>B10.1 Statutory taxes, duties and levies</u>			
86	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B10.2 Payment for preliminaries</u>			
87	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B10.3 Adjustment of preliminaries</u>			
88	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B10.4 Payment certificate cash flow</u>			
89	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B11. GENERAL</u>			
<u>B11.1 Protection of the works</u>			
90	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B11.2 Protection / isolation of existing / sectionally occupied works</u>			
91	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B11.3 Security of the works</u>			
92	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B11.4 Notice before covering work</u>			
93	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>11.5 Disturbance</u>			
94	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B11.6 Environmental disturbance</u>			
95	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B11.7 Works cleaning and clearing</u>			
96	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B11.8 Vermin</u>			
97	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B11.9 Overhand work</u>			
98	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B11.10 Instruction manuals and guarantees</u>			
99	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B11.11 As built information</u>			
100	Fixed: _____ Value related: _____ Time related: _____	Item	
		Carried to Collection	R
Section No. 2			
Bill No. 1			
Preliminaries			

			Amount
101	<u>B11.12 Tenant installations</u>		
	Fixed: _____ Value related: _____ Time related: _____	Item	
102	<u>SECTION C: SPECIFIC PRELIMINARIES</u>		
	Section C contains specific preliminary items which apply to this contract except where N/A (Not Applicable) appears against an item.		
103	<u>C1 CONTRACT DRAWINGS</u>		
	The drawings issued with the tender documents do not comprise the complete set but serve as a guide only for tendering purposes and for indicating the scope of the work to enable the tenderer to acquaint himself with the nature and extent of the works and the manner in which they are to be executed. Should any part of the drawings not be clearly intelligible to the tenderer he shall, before submitting his tender, obtain clarification in writing from the principal agent.	Item	
104	<u>C2 GENERAL PREAMBLES</u>		
	The document "Specification of Materials and Methods to be used (PW371)" is obtainable on request from the head office and all regional offices of the Department, and shall be read in conjunction with the bills of quantities / lump sum document and be referred to for the full descriptions of work to be done and materials to be used.	Item	
104	<u>C3 PROPRIETARY BRANDED PRODUCTS</u>		
	The contractor shall take delivery of, handle, store, use, apply and/or fix all proprietary branded products in strict accordance with the manufacturer's instructions after consultation with the manufacturer's authorised representative. All materials, fittings, finishings, etc., specified hereinafter under a trade name, catalogue number or reference, must be exactly as described. The Architect's approval in writing must be obtained for the use of any alternative to the specification before the submission of tenders otherwise the specified materials, fittings, finishings, etc., will be assumed to have been allowed for in the tender. The Contractor must take delivery of, handle, store, use, apply and/or fix all proprietary branded products in strict accordance with the manufacturer's instructions after consultation with the manufacturer's authorised representative.	Item	
Carried to Collection			R
Section No. 2			
Bill No. 1			
Preliminaries			

			Amount
<u>C4 CONTRACTOR'S RESPONSIBILITY</u>			
The Employer, the Principal Agent and the other professional consultants shall not be responsible for any act or omission on the part of the Contractor which may result in any patent or latent defects, in materials or workmanship, breach or neglect of any local regulations. The Contractor shall at all times be responsible for any such neglect, deviation or wrong act, whether the same is discovered before or after the final certificate, or any other Certificate, has been approved			
105	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>C5 OVERTIME</u>			
Should overtime be required to be worked for any reason whatsoever, the costs of such overtime are to be borne by the contractor unless the principal agent has specifically authorised in writing, prior to the execution thereof, that costs for such overtime are to be borne by the employer.			
106	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>C6 AS BUILT DRAWINGS</u>			
The position of construction breaks and the extent of individual concrete pours are to be recorded by the contractor on the structural engineer's drawings and are to be submitted to the principal agent and the structural engineer for their records.			
Three full sets of as-built drawings shall be submitted to the Principal Agent no later than fourteen days after practical completion			
107	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>C7 CONTRACT INSTRUCTIONS</u>			
Contract instructions issued on site are to be recorded in triplicate in a site instruction book which is to be maintained on site by the Contractor. The Contractor shall supply and have available at the site of the works at all times, the following site books:			
a) Contract Instruction Book			
Receiving and recording instructions in a suitable A4 size triplicate book kept on site. Instructions issued shall be recorded by the Architect or other Employer's Agents to whom the Architect has delegated authority to in the book.			
Only instructions issued in such book shall be recognised.			
b) Daily Record Book			
The Contractor shall record in triplicate in a suitable A4 size triplicate book kept at the site, a daily record of work done, all site visits by the Principal Agent and other professional personnel and all events affecting the Works, such as progress, issue of plans, breakdown of machinery, etc. The labour, plant and material on site shall be recorded as well as work performed. Entries must be made by the Contractor and must be signed and forwarded to the Principal Agent for his counter-signature on a daily basis. Copies of these records shall be for the Architect, Quantity Surveyor and Contractor.			
Carried to Collection			
Section No. 2			
Bill No. 1			
Preliminaries			

			Amount
108	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>C8 LABOUR RECORD</u>			
At the end of each week the contractor shall provide the principal agent with a written record, in schedule form, reflecting the number and description of tradesmen and labourers employed by him and all subcontractors on the works each day			
109	F: V: T:	Item	
<u>C9 PLANT RECORD</u>			
At the end of each week the contractor shall provide the principal agent with a written record, in schedule form, reflecting the number, type and capacity of all plant, excluding hand tools, currently used on the works.			
110	F: V: T:	Item	
<u>C10 ENCROACHMENT</u>			
During the course of the building operations, the Contractor shall be held entirely responsible for any encroachment onto any adjoining properties, buildings, etc., or servitudes and the cost of any remedial measures as required by the Principal Agent shall be borne by the Contractor			
111	F: V: T:	Item	
<u>C11 METHOD STATEMENT</u>			
The Tenderer shall produce, when required to do so by the Principal Agent, a Method Statement outlining the methods of construction and labour and plant resources that he proposes to use in the execution of the Works. Any approval given or observation made by the Principal Agent shall not relieve the Contractor of his sole responsibility to adopt the methods of construction and to provide the labour and plant resources necessary for the due and proper timeous execution of the Works.			
112	F: V: T:	Item	
<u>C12 UNAUTHORISED PERSONS/WORKMEN ON PREMISES</u>			
The Contractor shall at all times strictly exclude all unauthorised persons from the Works and the site and shall set up notice boards to that effect.			
No workmen or labourers (except security guards) are to be allowed under any circumstances to sleep or deposit any kit on the premises. The Contractor must provide any necessary independent shelter or shed required for any labour or watchmen on site, to the approval of the Employer.			
113	F: V: T:	Item	
<u>C13 MODE OF PROCEDURE</u>			
Notwithstanding anything to the contrary contained herein the Principal Agent at all times reserves the right to direct the order in which the various parts of the Contract are to be executed. The Contractor shall give priority to any individual section or portion of the Works that, in the opinion of the Principal Agent, requires to be expedited.			
Carried to Collection			
Section No. 2			
Bill No. 1			
Preliminaries			

			Amount
114	Should it appear, in the Principal Agent's opinion, that work in any area is not being executed in accordance with the requirements of the Contract Programme, the Contractor shall provide additional manpower and resources and shall work additional overtime and do everything else required to bring the work back to programme to the satisfaction of the Principal Agent and to the Contractor's cost F: V: T: <u>C14 LOCATION OF TEMPORARY BUILDINGS AND TEMPORARY SERVICES</u> The Contractor shall provide all necessary temporary works, including temporary roads, tracks, crossings, hardstanding and services, hoardings, dust screens, tunnelling, etc., required for his own and sub-contractors use during the construction and maintenance period There is no guarantee given or implied that Site conditions will be such that the Contractor will be able to erect such temporary works, roads, hardhats, offices, stores and temporary accommodation within the site boundaries and it shall be the Contractor's responsibility to adopt whatever measures he deems necessary in this regard and to obtain all necessary permission and pay all costs in connection therewith	Item	
115	F: V: T: <u>C15 OFFICE ACCOMMODATION</u> The contractor shall provide, maintain and remove on practical completion air conditioned office accommodation with suitable tables and chairs for meetings to be held on the site. Such offices shall be kept clean and fit for use at all times [12.2.18]	Item	
116	F: V: T: <u>C16 STORAGE FACILITIES</u> The Contractor shall provide a Container for storage of materials.	Item	
117	F: V: T: <u>C17 REMOVAL AND MAKING GOOD OF TEMPORARY WORKS, ETC, ON COMPLETION</u> The Contractor shall remove (except where specifically stated otherwise) all temporary works, roads, services and the like used for this contract and shall make good to the entire satisfaction of the Principal Agent any damage resulting therefrom.	Item	
118	F: V: T:	Item	
Carried to Collection			
Section No. 2			
Bill No. 1			
Preliminaries			

Amount

SECTION NO. 2

BAMBOESPRUIT JUNIOR SECONDARY SCHOOL

BILL NO. 1

PRELIMINARIES

COLLECTION

Page No

Brought Forward from Page

46

47

48

49

50

51

52

53

54

55

56

57

58

59

60

Carried To Section Summary

R

Section No. 2

Bill No. 1

Preliminaries

	Unit	Quantity	Rate	Amount
<u>SECTION NO. 2</u> <u>BAMBOESPRUIT JUNIOR SECONDARY SCHOOL</u> <u>BILL NO. 2</u> <u>HEALTH AND SAFETY</u> <u>MODEL PREAMBLES</u> The tenderer is referred to the "Model Preambles for Trades 2008" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates. <u>SUPPLEMENTARY PREAMBLES</u> Supplementary preambles and/or specifications are incorporated in these bills of quantities to satisfy the requirements of this project. Such supplementary preambles and/or specifications shall take precedence over the provisions of the General Preambles. The contractor's prices for all items throughout these bills of quantities shall take account of and include where applicable for all of the obligations, requirements and specifications given in the General Preambles and in any supplementary preambles and/or specifications. Prior to pricing the principal contractor must familiarize him/herself with the Occupational Health and Safety Act No. 85 Of 1993, Construction Regulations 2014, other relevant Regulations and Standards as well as project specific Health & Safety specifications. <u>OCCUPATIONAL HEALTH AND SAFETY</u> <u>General</u>				
1	Preparation of Contractor's site specific Health and Safety Plan	Item		
2	Submission of the Health and Safety File	Item		
3	Principal Contractor's initial obligations in respect of the OHS Act and Construction Regulations	Item		
4	Principal Contractor's time related obligations in respect of the OHS Act and Construction Regulations for the entire construction period	Item		
5	Provision of full time Health and Safety Officer for the entire construction period	Item		
6	Induction training of all personnel	Item		
7	Provision of first aid boxes	Item		
Carried to Collection			R	
Section No. 2				
Bill No. 2				
Health And Safety				

	Unit	Quantity	Rate	Amount
8 SANS approved weld mesh type temporary barrier fencing 1,8m high covered with a net fixed to and including 100mm diameter gum poles set securely min 300mm deep in ground at max 3m spacing including excavation, backfilling, etc	m	150		
9 Extra over mesh fence for pedestrian gate size 1.8 x 1,8m high	No	1		
<u>Provision for Personal Protective Equipment and</u>				
10 Reflective vests.	Item			
11 Hard hats	Item			
12 Protective footwear	Item			
13 Ear plugs	Item			
14 Dust masks	Item			
<u>Medical certificates and medical surveillance</u>				
15 Initial (baseline) medical examinations for all personnel	Item			
16 Exit Examinations for all personnel	Item			
<u>Noise Monitoring</u>				
17 Establishment of noise zones	Item			
18 Audiograms	Item			
<u>Covid-19 Compliance Measures</u>				
19 The Contractor is required to price for Covid 19 compliance and the pricing thereof shall be deemed to include all the mandatory requirements	Item			
Carried to Collection			R	
Section No. 2				
Bill No. 2				
Health And Safety				

Amount

SECTION NO. 2

BAMBOESPRUIT JUNIOR SECONDARY SCHOOL

BILL NO. 2

HEALTH AND SAFETY

COLLECTION

Page No

Brought Forward from Page

62

63

Carried To Section Summary

R

Section No. 2

Bill No. 2

Health And Safety

	Unit	Quantity	Rate	Amount
<u>SECTION NO. 2</u> <u>BAMBOESPRUIT JUNIOR SECONDARY SCHOOL</u> <u>BILL NO. 3</u> <u>RENOVATIONS</u> <u>PREAMBLES</u> The Tenderer is referred to the relevant Clause in the separate document Model Preambles for Trades (1999 Edition) published by the Association of South African Quantity Surveyors, the document "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition July 2014) and the Supplementary Preambles which are incorporated in these Bills of Quantities <u>SUPPLEMENTARY PREAMBLES</u> <u>View site</u> Before submitting his tender the tenderer shall visit the site and satisfy himself as to the nature and extent of the work to be done and the value of the materials contained in the buildings or portions of the buildings to be demolished. No claim for any variations of the contract sum in respect of the nature and extent of the work or of inferior or damaged materials will be entertained <u>General</u> Water supply pipes and other piping in ground that may be encountered and found necessary to disconnect or cut, shall be effectually stopped off or grubbed up and removed, and any new connections that may be necessary shall be made with proper fittings to the satisfaction of the principal agent <u>MAKING GOOD OF EXISTING WORK</u> <u>Taking out and removing piping, sanitary fittings, etc including disconnecting piping from fittings and making good floor and wall finishes (making good tiling and paintwork elsewhere)</u>				
1	No	3		
2	No	4		
3	No	4		
Carried to Collection			R	
Section No. 2				
Bill No. 3				
Renovations				

	Unit	Quantity	Rate	Amount
<u>Making good tie down straps to existing tanks</u>				
4	New 4mm diameter galvanised wire tank ties wrapped twice around centre of tank and secured to each corner of tank stand with a double strand of 4mm diameter galvanised wire bolted into concrete.	No	1	
<u>Making good falling VIP pedestal steel doors</u>				
5	Secure overhead timber beams to walls using expansion bolts, resecure and realign steel doors and make good plaster and paint	No	3	
<u>Making good existing security gates</u>				
6	Repair loose hanging or fallen gates by making good brick walls and then re-installing gates into position with new 13mm diameter x 90mm long expansion applied to existing gate hinges	No	1	
<u>Making good existing timber doors and frames</u>				
7	Making good good falling doors where plugs to walls have failed by repositioning existing timber door frames and secure by installing new anchors/ plugs including refitting doors to hinges and frames.	No	3	
<u>Making good existing pit latrine chambers</u>				
8	Allow for de-sludging of existing "long drop" pit latrines by means of "honey sucker". The pit latrines are to be completely empty before any other work is carried out	Litres	15 000	
<u>BATHROOM FITTINGS</u>				
<u>Stainless steel bathroom fittings</u>				
9	Free standing She Bin: manufactured from Grade 304 1,2mm Stainless Steel, satin finished with surface treatment. The container to have an approximately 20 litre capacity	No	9	
<u>SANITARY FITTINGS</u>				
<u>Rust and corrosion resistant, UV-resistant polyethylene pedestals, urinals, basins, etc.</u>				
10	VIP 450 Pit pedestal complete with integral flap four times plugged to floor with and including 6 x 75mm masonry anchors.	No	3	
<u>TRAPS ETC</u>				
<u>Traps</u>				
11	40mm Chromium plated bottle trap	No	4	
			R	
Carried to Collection				
Section No. 2				
Bill No. 3				
Renovations				

66

[illegible]

Amount

SECTION NO. 2

BAMBOESPRUIT JUNIOR SECONDARY SCHOOL

BILL NO. 3

RENOVATIONS

COLLECTION

Page No

Brought Forward from Page

65

66

67

Carried To Section Summary

R

Section No. 2

Bill No. 3

Renovations

	Unit	Quantity	Rate	Amount
<u>SECTION NO. 2</u> <u>BAMBOESPRUIT JUNIOR SECONDARY SCHOOL</u> <u>BILL NO. 4</u> <u>GARDEN AND BALUSTRADE WALLS</u> <u>PREAMBLES</u> The Tenderer is referred to the relevant Clause in the separate document Model Preambles for Trades (1999 Edition) published by the Association of South African Quantity Surveyors, the document "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition July 2014) and the Supplementary Preambles which are incorporated in these Bills of Quantities <u>EARTHWORKS (PROVISIONAL)</u> <u>Excavate in pickable material not exceeding 2m deep below natural or reduced ground level:</u>				
1	Surface trenches.	m ³	33	
	<u>Extra over excavation in pickable material for column bases, trenches, lift pits, sumps, etc for excavation:</u>			
2	Soft rock.	m ³	3	
3	Hard rock.	m ³	1	
4	Allow for risk of collapse to sides of excavations to column bases, trenches, etc. from ground level to not exceeding 1,5m deep.	m ²	131	
5	Allow for keeping excavations entirely free from water or mud.	Item		
	<u>Earth filling obtained from the excavations and/or prescribed stock piles on site, compacted to 98% Mod AASHTO density</u>			
6	Backfilling to trenches, holes, etc.	m ³	6	
7	Scarify in-situ material for a depth of 150mm and compact to obtain 98% modified AASHTO dry density.	m ²	55	
	<u>Earth filling supplied by the contractor, compacted to 98% Mod AASHTO density</u>			
8	Under floors, steps, pavings, etc.	m ³	6	
Carried to Collection			R	
Section No. 2				
Bill No. 4				
Garden And Balustrade Walls				

		Unit	Quantity	Rate	Amount
<u>CONCRETE, FORMWORK & REINFORCEMENT</u>					
<u>25MPa Mass concrete in:</u>					
9	Wall footings cast against excavated surfaces.	m ³	11		
<u>Expansion Joints:</u>					
10	12mm "Flexcell" or other approved cane fibre filler board in expansion joint between edge of concrete paving and walls in narrow widths not exceeding 150mm wide including tacking to face of wall.	m	109		
<u>TEST CUBES</u>					
<u>Test Cubes</u>					
11	Making and testing 150 x 150 x 150mm concrete strength test cube (Provisional)	No	5		
<u>MASONRY</u>					
<u>Brickwork of NFX bricks (14 MPa nominal compressive strength) in class II mortar</u>					
12	One brick wall.	m ²	87		
13	Leave or form 115 x 75mm high weep hole through one brick wall.	No	10		
<u>2,5mm Galvanised brick reinforcement</u>					
14	150mm Wide reinforcement built in horizontally	m	218		
<u>Facings Externally:</u>					
<u>"Rustgold FBS/Qunu Travertine" clay face brick or equal approved, size 222 x 106 x 73mm, bedded and jointed in Class II mortar and pointed with recessed vertical and recessed horizontal joints, suitable for exposure zones 1-2 (Cement to be 42.5N all-purpose cement):</u>					
15	Extra over ordinary brickwork for facing in stretcher bond and pointing as described.	m ²	87		
16	Brick on edge coping in header course to top of one brick wall bedded and jointed in cement mortar and pointed on top and both sides as described.	m	109		
<u>PAINTING</u>					
<u>Clean down with Spirits of Salts solution and apply two coats silicone-based brick dressing on:</u>					
17	Clinker brick facings (Externally).	m ²	87		
Carried to Collection				R	
Section No. 2					
Bill No. 4					
Garden And Balustrade Walls					

Amount

SECTION NO. 2

BAMBOESPRUIT JUNIOR SECONDARY SCHOOL

BILL NO. 4

GARDEN AND BALUSTRADE WALLS

COLLECTION

Page No

Brought Forward from Page

69

70

Carried To Section Summary

R

Section No. 2

Bill No. 4

Garden And Balustrade Walls

	Unit	Quantity	Rate	Amount
<u>SECTION NO. 2</u> <u>BAMBOESPRUIT JUNIOR SECONDARY SCHOOL</u> <u>BILL NO. 5</u> <u>V – DRAINS</u> <u>PREAMBLES</u> The Tenderer is referred to the relevant Clause in the separate document Model Preambles for Trades (1999 Edition) published by the Association of South African Quantity Surveyors, the document "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition July 2014) and the Supplementary Preambles which are incorporated in these Bills of Quantities <u>SUPPLEMENTARY PREAMBLES</u> <u>Nature of ground:</u> The nature of the ground is assumed to be loose sandy material, therefore 'earth', but possibly interspersed with 'soft rock' or 'hard rock' <u>Carting away of excavated material:</u> Descriptions of carting away of excavated material shall be deemed to include loading excavated material onto trucks directly from the excavations or, alternatively, from stock piles situated on the building site <u>Filling:</u> Notwithstanding the reference to prescribed multiple handling in clause 1 page 6 of the Standard System of Measuring Building Work, prices for filling and backfilling shall include for all selection and any necessary multiple handling of material <u>Testing:</u> Prices for filling are to include for all necessary density tests in accordance with SABS 1200D <u>Cost of tests:</u> The costs of making, storing and testing of concrete test cubes as required under clause 7 Tests of SABS 1200 G shall include the cost of providing cube moulds necessary for the purpose, for testing costs and for submitting reports on the tests to the principal agent. The testing shall be undertaken by an independent firm or institution nominated by the contractor to the approval of the principal agent. (Test cubes are measured separately)				
Carried to Collection			R	
Section No. 2				
Bill No. 5				
V – Drains				

[illegible]

[illegible]

Amount

SECTION NO. 2

BAMBOESPRUIT JUNIOR SECONDARY SCHOOL

BILL NO. 5

V – DRAINS

COLLECTION

Page No

Brought Forward from Page

72

73

74

Carried To Section Summary

R

Section No. 2

Bill No. 5

V – Drains

	Unit	Quantity	Rate	Amount
<u>SECTION NO. 2</u>				
<u>BAMBOESPRUIT JUNIOR SECONDARY SCHOOL</u>				
<u>BILL NO. 6</u>				
<u>CONCRETE APRONS, WALKWAYS & RAMPS</u>				
<u>PREAMBLES</u>				
The Tenderer is referred to the relevant Clause in the separate document Model Preambles for Trades (1999 Edition) published by the Association of South African Quantity Surveyors, the document "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition July 2014) and the Supplementary Preambles which are incorporated in these Bills of Quantities				
<u>EARTHWORKS (PROVISIONAL)</u>				
<u>Excavate in pickable material not exceeding 2m deep below natural or reduced ground level:</u>				
1 Reduce levels under pavings.	m ³	6		
<u>Extra over excavation in pickable material for column bases, trenches, lift pits, sumps, etc for excavation:</u>				
2 Soft rock.	m ³	1		
3 Hard rock.	m ³	1		
4 Unreinforced concrete	m ³	1		
<u>Extra over excavation in pickable material for column bases, trenches, lift pits, sumps, etc for breaking up:</u>				
5 Allow for risk of collapse to sides of excavations to column bases, trenches, etc. from ground level to not exceeding 1,5m deep.	m ²	6		
6 Allow for keeping excavations entirely free from water or mud.	Item			
<u>Earth filling obtained from the excavations and/or prescribed stock piles on site, compacted to 98% Mod AASHTO density</u>				
7 Scarify in-situ material for a depth of 150mm and compact to obtain 95% modified AASHTO dry density.	m ²	45		
<u>Earth filling (G7 material) supplied by the contractor, compacted to 95% Mod AASHTO density</u>				
8 Under floors, steps, pavings, etc.	m ³	7		
Carried to Collection			R	
Section No. 2				
Bill No. 6				
Concrete Aprons, Walkways & Ramps				

		Unit	Quantity	Rate	Amount
<u>CONCRETE, FORMWORK & REINFORCEMENT</u>					
<u>25MPa Mass concrete in:</u>					
9	Ramps	m ³	2		
10	Pavings.	m ³	4		
<u>Sundries:</u>					
11	Strike off and cure tops of surface beds laid in panels approximately 1000mm long x 1000mm wide to uniform levels including all necessary formwork to form toggle joints to temporary construction joints to falls.	m ²	45		
12	Extra for floating off smooth tops of surface beds laid in panels to brush finish including slightly rounded edges to panels.	m ²	45		
<u>Expansion Joints:</u>					
13	12mm "Flexcell" or other approved cane fibre filler board in expansion joint between edge of concrete paving and walls in narrow widths not exceeding 150mm wide including tacking to face of wall.	m	30		
<u>TEST CUBES</u>					
<u>Test Cubes</u>					
14	Making and testing 150 x 150 x 150mm concrete strength test cube (Provisional)	No	5		
<u>SMOOTH FORMWORK (DEGREE OF ACCURACY II) (CPAP WORK GROUP NO. 111)</u>					
<u>Smooth formwork to sides</u>					
15	Edges, risers, ends and reveals not exceeding 300mm high or wide	m	12		
<u>REINFORCEMENT (CPAP WORK GROUP NO. 114)</u>					
<u>Fabric reinforcement</u>					
16	Type 617 fabric reinforcement in concrete surface beds etc	m ²	45		
<u>DAMPPROOFING OF WALLS AND FLOORS</u>					
<u>One layer 250 micron green polyethylene waterproof sheeting (SANS 952-1985 type C) sealed at laps with PVC self-adhesive tape</u>					
17	Under surface pavings etc.	m ²	45		
Carried to Collection				R	
Section No. 2					
Bill No. 6					
Concrete Aprons, Walkways & Ramps					

Amount

SECTION NO. 2

BAMBOESPRUIT JUNIOR SECONDARY SCHOOL

BILL NO. 6

CONCRETE APRONS, WALKWAYS & RAMPS

COLLECTION

Page No

Brought Forward from Page

76

77

Carried To Section Summary

Section No. 2

Bill No. 6

Concrete Aprons, Walkways & Ramps

R

	Unit	Quantity	Rate	Amount
<u>SECTION NO. 2</u> <u>BAMBOESPRUIT JUNIOR SECONDARY SCHOOL</u> <u>BILL NO. 7</u> <u>SUBSOIL DRAINAGE</u> <u>PREAMBLES</u> The Tenderer is referred to the relevant Clause in the separate document Model Preambles for Trades (1999 Edition) published by the Association of South African Quantity Surveyors, the document "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition July 2014) and the Supplementary Preambles which are incorporated in these Bills of Quantities <u>SUPPLEMENTARY PREAMBLES</u> <u>Laying, backfilling, bedding, etc. of pipes</u> Pipes shall be laid and bedded in accordance with manufacturers' instructions and trenches shall be carefully backfilled <u>As-built drawings:</u> Where required, the contractor shall prepare an updated set of as-built drawings. At completion of the contract the contractor shall hand these drawings to the principal agent for reproducing onto the originals for handing over to the employer (provision for allowance of as-built drawings elsewhere) <u>SUBSOIL DRAINAGE (CPAP WORK GROUP NO. 146)</u> <u>Site clearance</u> 1 Digging up and removing rubbish, debris, vegetation, hedges, shrubs, bush, etc. and trees not exceeding 200mm girth <u>Subsoil drainage</u> 2 Excavation in earth not exceeding 2m deep for pipe trenches 3 Extra over all excavations for carting away surplus material from excavations and/or stock piles on site, to a dumping site to be located by the contractor 4 Risk of collapse to sides of trench and hole excavation exceeding 1.5m but not exceeding 3.0m deep 5 Keeping excavations free of water				
	m ²	105		
	m ³	63		
	m ³	1		
	m ²	281		
	Item			
Carried to Collection			R	
Section No. 2				
Bill No. 7				
Subsoil Drainage				

		Unit	Quantity	Rate	Amount
6	Filling in bedding under and filling around pipes with granular material supplied by the contractor and compacted to 98% Mod AASHTO density	m ³	47		
7	19mm Crushed stone encasing to pipes	m ³	16		
	<u>Slotted uPVC flexible drainage pipes</u>				
8	160mm Pipes laid in stone encasing (encasing elsewhere)	m	156		
	<u>Extra over slotted uPVC flexible drainage pipes for fittings</u>				
9	110mm Bend	No	5		
10	110mm Junction	No	2		
	<u>Geotextile filter fabric blanket with stiched 300mm laps</u>				
11	Around stone filling in sub-soil drain trenches	m ²	140		
	<u>THE FOLLOWING IN STORMWATER SOAKAWAYS</u>				
	<u>Site clearance</u>				
12	Digging up and removing rubbish, debris, vegetation, hedges, shrubs, bush, etc. and trees not exceeding 200mm girth	m ²	9		
	<u>Subsoil drainage</u>				
13	Excavation in earth not exceeding 2m deep for pipe trenches and holes	m ³	8		
14	Extra over all excavations for carting away surplus material from excavations and/or stock piles on site, to a dumping site to be located by the contractor	m ³	2		
15	Backfilling to trenches and holes with selected material compacted to 95% Mod AASHTO density	m ³	5		
16	Risk of collapse to sides of trench and hole excavation not exceeding 1.5m deep	m ²	5		
17	Risk of collapse to sides of trench and hole excavation exceeding 1.5m but not exceeding 3.0m deep	m ²	29		
18	Keeping excavations free of water	Item			
19	Filling in bedding under and filling around pipes with granular material supplied by the contractor and compacted to 98% Mod AASHTO density	m ³	6		
20	19mm Crushed stone beds	m ³	2		
	Carried to Collection			R	
	Section No. 2				
	Bill No. 7				
	Subsoil Drainage				

[illegible]

		Amount
<u>SECTION NO. 2</u>		
<u>BAMBOESPRUIT JUNIOR SECONDARY SCHOOL</u>		
<u>BILL NO. 7</u>		
<u>SUBSOIL DRAINAGE</u>		
<u>COLLECTION</u>		
		Page No
Brought Forward from Page		79
		80
		81
Carried To Section Summary		R
Section No. 2		
Bill No. 7		
Subsoil Drainage		

83

		Unit	Quantity	Rate	Amount
6	150mm Ditto as straining or corner posts, but fitted with two 75mm diameter galvanised steel raking stays and with top ends flattened and bolted through post with post embedded in 600 x 600 x 700mm high mass concrete (15MPa) base and stays embedded in 700 x 700 x 450mm high mass concrete (15MPa) base	No	5		
7	150mm Ditto as end/ gate post, but fitted with one 75mm diameter galvanised steel stay set raking and with top end flattened and bolted through post, with post embedded in 600 x 600 x 700mm mass concrete (15MPa) base and stay embedded in 700 x 700 x 450mm high mass concrete (15MPa) base with all base tops set raking (sloping)	No	6		
	Gates				
8	Security fence single gate, size 900 mm wide x 1800 mm high, formed of 50 mm diameter nominal bore x 2,2 mm wall thickness hot dip galvanised mild steel pipe framing all round with mitred and welded angles and middle rail, with 20mm diameter x 300mm long locking bolt welded on and a pair of heavy duty gate hooks for a 16mm band hinge pin welded on to gate and including a pair of 16mm band hinge pins bolted to gate posts	No	1		
9	Security fence single gate, size 1500 mm wide x 1800 mm high, formed of 50 mm diameter nominal bore x 2,2 mm wall thickness hot dip galvanised mild steel pipe framing all round with mitred and welded angles and middle rail, hung on pair of socketted and pinned hinges with pin 18mm in diameter and bolted to brick wall and with 20mm diameter x 300mm long locking bolt welded on.	No	1		
10	Double gate, size 6 000 mm wide x 1 800 mm high overall in two leaves, formed of 50 mm diameter nominal bore x 2.5 mm wall thickness hot dip galvanised mild steel pipe framing all round with 25 mm diameter nominal bore x 2.0 mm wall thickness diagonal and centre braces, scribed and welded into angles and at cross intersections, gate filled with 50 x 50 x 2,0mm galvanised wire diamond mesh, with two 50 mm diameter nominal bore x 3,25 mm wall thickness security posts each 600 mm long with one end welded to top rail of gate and closure plate to other end, each leaf fitted with two 25 mm diameter x 300 mm long eyebolt hinges and stops including all holes, etc., welded or bolted to adjoining galvanised gatepost with and including 500 mm long approved chain spot welded to gate	No	1		
	Carried to Collection			R	
	Section No. 2				
	Bill No. 8				
	Grade R Fencing				

85

Amount

SECTION NO. 2

BAMBOESPRUIT JUNIOR SECONDARY SCHOOL

BILL NO. 8

GRADE R FENCING

COLLECTION

Page No

Brought Forward from Page

83

84

85

Carried To Section Summary

R

Section No. 2

Bill No. 8

Grade R Fencing

Amount

SECTION NO. 2

BAMBOESPRUIT JUNIOR SECONDARY SCHOOL

BILL NO. 9

PROVISIONAL SUMS

PROVISIONAL SUMS

Supplementary Preambles

Tenderers are advised that no claim in respect of loss of profit or Preliminary charges based on the omission of these amounts will be considered and the said amounts will be omitted strictly without any financial compensation payable to the Contractor.

Provisional sums and Budgetary allowances contained herein may be omitted or reduced at the Employer's discretion and the Contractor shall not be entitled to claim for any loss by way of reductions or omission of any discount, or percentage relating to Provisional amounts and Budgetary sums or any loss of profit related thereto.

BUDGETARY ALLOWANCES

Sundry building work

- 1 Provide the sum of R22 500.00 for the employment of a Community Liaison Officer to be employed by the Main Contractor and be paid an allowance of R7 500.00 a month for the duration (3 months)

Item 22 500 00

- 2 Profit

Item

- 3 Attendance

Item

- 4 Provide the sum of R105 000. 00 for the hire, maintenance and servicing of temporary toilets for educators and learners during the entire constructions period

Item 105 000 00

- 5 Profit

Item

- 6 Attendance

Item

Contingencies

- 7 Allow the Amount of R30 000.00 (Thirty Thousand Rands) for contingencies, to be used by the Architect in terms of Clause 17 of the Principal Building Agreement.

Item 30 000 00

Carried To Section Summary

R

Section No. 2

Bill No. 9

Provisional Sums

Amount

SECTION NO. 2
BAMBOESPRUIT JUNIOR SECONDARY SCHOOL
SECTION SUMMARY

Bill No.		Page
1	PRELIMINARIES	61
2	HEALTH AND SAFETY	64
3	RENOVATIONS	68
4	GARDEN AND BALUSTRADE WALLS	71
5	V – DRAINS	75
6	CONCRETE APRONS, WALKWAYS & RAMPS	78
7	SUBSOIL DRAINAGE	82
8	GRADE R FENCING	86
9	PROVISIONAL SUMS	87

Section No. 2
SECTION SUMMARY

Carried to Final Summary

R

SECTION NO. 3

KHIBA JUNIOR SECONDARY SCHOOL

Amount

SECTION NO. 3

KHIBA JUNIOR SECONDARY SCHOOL

BILL NO. 1

PRELIMINARIES

BUILDING AGREEMENT AND PRELIMINARIES

1. The Principal Building Agreement shall be the JBCC Series Edition 4.1, March 2005 as recommended by the Joint Building Contracts Committee and as amended by this Tender Enquiry.
2. The Preliminaries shall be JBCC Series 2000, May 2005 for use with the Principal Building Agreement as recommended by the joint Building Contracts Committee and as amended by this Tender Enquiry shall be deemed to be incorporated herein.
3. The tenderor is deemed to have referred to the abovementioned documents for the full intent and meaning of each clause. The clauses in the abovementioned documents are hereinafter referred to by clause number and heading only.
4. Where standard clauses or alternatives are not entirely applicable to this contract, such modifications, corrections or additions as are necessary, are given as far as possible under each relevant clause heading. Additional Preliminary clauses are contained in Section C hereof.
5. No claim whatsoever shall be entertained in respect of errors or omissions in pricing due to brevity of descriptions of items which are fully described when read in conjunction with the relevant clauses of the said Principal Building Agreement, Preliminaries and Preambles.
6. The Tenderers shall allow opposite each of the clauses whatever costs and charges he may consider necessary for the carrying out, complying with and due observance of the provisions, conditions and requirements set out herein. Only priced items will be considered in respect of any adjustment of this Section. Any items left unpriced will be understood to be provided free of charge and no claim for any extras arising out of the Tenderer's omission to price any item will be entertained.
7. Where modifications or amendments as described are made, such modifications and/or amendments shall supercede any conflicting provisions in the relevant clauses of the Standard Preliminaries or the Principal Building Agreement and the Tenderer shall make due allowance for whatever costs and charges he may consider necessary for the carrying out and observance of the provisions of the clauses as modified and/or amended.
8. Where any item is not relevant to this specific contract, such item is marked N/A.
9. If Alternative A as set out in clause B10.3 hereinafter is to be used for the adjustment of the preliminaries, each item priced is to be allocated to one or more of the three categories by insertion of "F","V","T" as the case may be against the price in the "rate" column immediately preceding the "amount" column, where "F" denotes a fixed amount (amount not to be varied), "V" denotes an amount variable in proportion to value, and "T" denotes an amount proportionate to time.

Carried to Collection

R

Section No. 3

Bill No. 1

Preliminaries

			Amount
<u>SECTION A: JBCC PRINCIPAL BUILDING AGREEMENT</u>			
<u>DEFINITIONS</u>			
<u>A1 DEFINITIONS AND INTERPRETATION</u>			
<u>Clause 1.0:</u>			
1	Fixed:_____ Value related:_____ Time related:_____0	Item	
<u>OBJECTIVE AND PREPARATION</u>			
<u>A2 OFFER, ACCEPTANCE AND PERFORMANCE</u>			
<u>Clause 2.0</u>			
2	Fixed:_____ Value related:_____ Time related:_____	Item	
<u>A3 DOCUMENTS</u>			
<u>Clause 3.0</u>			
Clause 3.1 is deleted and substituted with: 'This tender is for a Government Contract. No Payment Guarantee will be provided.'			
Clause 3.3 is deleted and substituted with:			
The principal agent shall complete the schedule and arrange for formal signing of the agreement once the priced bill of quantities/lump sum document, security, insurances and waiver of lien, where acceptable, have been provided and effected'			
3	Fixed:_____ Value related:_____ Time related:_____	Item	
<u>A4 DESIGN RESPONSIBILITY</u>			
<u>Clause 4.0</u>			
4	Fixed:_____ Value related:_____ Time related:_____	Item	
<u>A5 EMPLOYERS AGENTS</u>			
<u>Clause 5.0</u>			
5	Fixed:_____ Value related:_____ Time related:_____	Item	
<u>A6 SITE REPRESENTATIVE</u>			
<u>Clause 6.0</u>			
6	Fixed:_____ Value related:_____ Time related:_____	Item	
<u>A7 COMPLIANCE WITH REGULATIONS</u>			
7	Fixed:_____ Value related:_____ Time related:_____	Item	
<u>Clause 7.0</u>			
8	Fixed:_____ Value related:_____ Time related:_____	Item	
<u>A8 WORKS RISK</u>			
<u>Clause 8.0</u>			
9	Fixed:_____ Value related:_____ Time related:_____	Item	
Carried to Collection		R	
Section No. 3			
Bill No. 1			
Preliminaries			

			Amount
<u>A9 INDEMNITIES</u>			
<u>Clause 9.0</u>			
Clause 9.1.1 is deleted and substituted with:			
Claims from other parties consequent upon death of bodily injury or illness of any person or physical loss or damage to any property, other than the works, arising out or due to the execution of the works or occupation of the site by the contractor or his sub contractors'.			
10	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A10 WORKS INSURANCES</u>			
<u>Clause 10.0</u>			
11	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A11 LIABILITY INSURANCES</u>			
<u>Clause 11.0</u>			
12	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A12 EFFECTING INSURANCES</u>			
<u>Clause 12.0</u>			
13	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A13. No clause</u>			
14	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A14 SECURITY</u>			
<u>Clause 14.0</u>			
15	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>EXECUTION</u>			
<u>A15 PREPERATION FOR AND EXECUTION OF THE WORKS</u>			
<u>Clause 15.0</u>			
16	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A16 ACCESS TO THE WORKS</u>			
<u>Clause 16.0</u>			
17	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A17 CONTRACT INSTRUCTIONS</u>			
<u>Clause 17.0</u>			
18	Fixed: _____ Value related: _____ Time related: _____	Item	
Carried to Collection		R	
Section No. 3			
Bill No. 1			
Preliminaries			

			Amount
<u>A18 SETTING OUT OF THE WORKS</u>			
<u>Clause 18.0</u>			
The contractor shall notify the principal agent if any encroachments of adjoining foundations, buildings, structures, pavements, boundaries, etc., exist in order that the necessary arrangements may be made for the rectification of any such encroachments. Should incorrect information be given to the contractor in terms of 18.1 and 18.2, which causes the incorrect setting out of the works, the contractor shall not be liable for such incorrect setting out			
19	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A19 ASSIGNMENT</u>			
<u>Clause 19.0</u>			
20	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A20 NOMINATED SUB-CONTRACTORS</u>			
<u>Clause 20.0</u>			
21	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A21 SELECTED SUBCONTRACTORS</u>			
<u>Clause 21.0</u>			
22	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A22 EMPLOYER'S DIRECT CONTRACTORS</u>			
<u>Clause 22.0</u>			
23	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A23 CONTRACTOR'S DOMESTIC SUBCONTRACTORS</u>			
<u>Clause 23.0</u>			
24	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>COMPLETION</u>			
<u>A24 PRACTICAL COMPLETION</u>			
<u>Clause 24.0</u>			
25	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A25 WORK'S COMPLETION</u>			
<u>Clause 25.0</u>			
26	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A26 FINAL COMPLETION</u>			
<u>Clause 26.0</u>			
27	Fixed: _____ Value related: _____ Time related: _____	Item	
Carried to Collection		R	
Section No. 3			
Bill No. 1			
Preliminaries			

			Amount
<u>A27 LATENT DEFECTS LIABILITY PERIOD</u>			
<u>Clause 27.0</u>			
Clause 27.0 is amended by the addition of the following clauses:			
"27.3 Any water leakage into the building, whether in the roof, external wall or other element of the building susceptible to water leakage shall, unless proven to be a design defect, or as a result of obvious storm damage, be classified as a latent defect in terms of clause 1.0 Definitions and Interpretations".			
"27.4 The Contractor shall attend to defects during the Defects Liability Period on a progressive basis, to the satisfaction of the Principal Agent and will not be permitted to wait until the end of the Defect Liability Period or until the amount of defects accumulates in order to attend to a comprehensive list of defects"			
28	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A28 SECTIONAL COMPLETION</u>			
<u>Clause 28.0</u>			
29	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A29 REVISION OF DATE FOR PRACTICAL COMPLETION</u>			
<u>Clause 29.0</u>			
30	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A30 PENALTY FOR NON-COMPLETION</u>			
<u>Clause 30.0</u>			
31	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>PAYMENT</u>			
<u>A31 INTERIM PAYMENT TO THE CONTRACTOR</u>			
<u>Clause 31.0</u>			
The inclusion of materials and goods stored off site in the amount authorised for payment in terms of clause 31.3 shall be at the sole discretion of the principal agent and such inclusion shall only be considered upon the provision, by the contractor, of an approved guarantee issued by a registered commercial bank.			
Where prices are submitted by the contractor or nominated/selected sub-contractor during the progress of the works in respect of contract instructions or in regard to a claim under the terms of the contract and notwithstanding the fact that such prices may be used in an interim payment certificate, there is to be no presumption of acceptance. Should the principal agent wish to accept any such prices prior to the issue of the final certificate, it will be in writing.			
32	Fixed: _____ Value related: _____ Time related: _____	Item	
Carried to Collection			
Section No. 3			
Bill No. 1			
Preliminaries			

			Amount
<u>A32 ADJUSTMENT TO THE CONTRACT VALUE</u>			
<u>Clause 32.0</u>			
33	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A33 RECOVERY OF EXPENSE AND LOSS</u>			
<u>Clause 33.0</u>			
34	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A34 FINAL ACCOUNT AND FINAL PAYMENT</u>			
<u>Clause 34.0</u>			
35	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A35 PAYMENT TO OTHER PARTIES</u>			
<u>Clause 35.0</u>			
36	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>CANCELLATION</u>			
<u>A36 CANCELLATION BY EMPLOYER - CONTRACTOR'S DEFAULT</u>			
<u>Clause 36.0</u>			
37	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A37 CANCELLATION BY EMPLOYER - LOSS AND DAMAGE</u>			
<u>Clause 37.0</u>			
38	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A38 CANCELLATION BY CONTRACTOR - EMPLOYER'S DEFAULT</u>			
<u>Clause 38.0</u>			
39	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>A39 CANCELLATION - CESSATION OF THE WORKS</u>			
<u>Clause 39.0</u>			
40	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>DISPUTE</u>			
<u>A40 DISPUTE SETTLEMENT</u>			
<u>Clause 40.0</u>			
41	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>SUBSTITUTE PROVISIONS</u>			
<u>A41 STATE CLAUSES</u>			
<u>Clause 41.0</u>			
42	Fixed: _____ Value related: _____ Time related: _____	Item	
Carried to Collection		R	
Section No. 3			
Bill No. 1			
Preliminaries			

			Amount
<u>CONTRACT VARIABLES</u>			
<u>THE SCHEDULE (C1.2 CONTRACT DATA)</u>			
<u>A42 PRE-TENDER INFORMATION</u>			
<u>Clause 42.0</u>			
Tenderers are referred to the document C1.2 Contract Data for variables pertaining to this contract.			
43	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>SECTION B: JBCC PRELIMINARIES</u>			
<u>B1.0 DEFINITIONS AND INTERPRETATION</u>			
<u>B1.1 Definitions and interpretation</u>			
44	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B2.0 DOCUMENTS</u>			
<u>B2.1 Checking of documents</u>			
Notwithstanding the issue of the tender drawings, it will remain the responsibility of the Tenderer to study all available drawings at the offices of the Principal Agent during normal working hours in order to acquaint himself with all the cost implications of the design, programming, phasing, etc.			
45	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B2.2 Provisional bills of quantities</u>			
Prime Cost Amounts, Budgetary Allowances, Provisional Amounts, etc., contained herein may be omitted or reduced at the Principal Agent's sole discretion and the Contractor shall not be entitled to claim for any loss by way of reduction or omission of any discount, or percentage relating to Prime Cost Amounts, Budgetary Allowances, Provisional Amounts, Provisional Quantities, etc., or loss of profit related thereto.			
46	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B2.3 Availability of construction documentation</u>			
47	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B2.4 Interests of agents</u>			
48	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B2.5 Priced documents</u>			
49	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B2.6 Tender submission</u>			
Notwithstanding anything contained in this clause, Tenders shall be valid for a period of 20 (Twenty) weeks from the closing date of tenders.			
50	Fixed: _____ Value related: _____ Time related: _____	Item	
Carried to Collection		R	
Section No. 3			
Bill No. 1			
Preliminaries			

			Amount
<u>B3.0 THE SITE</u>			
<u>B3.1 Defined works area</u>			
The area of the works to be occupied by the contractor, any restriction on the area and the limit of access or exit will be pointed out to the contractor by the principal agent on handing over of the site.			
Workmen employed on the site are to be restricted to the immediate area of the site and access thereto.			
The Tenderer shall make all necessary provision in all rates to take into account these requirements as no claims for extras arising from these matters will be subsequently entertained or admitted.			
51	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B3.2 Geotechnical investigation</u>			
52	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B3.3 Inspection of the site</u>			
53	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B3.4 Existing premises occupied</u>			
54	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B3.5 Previous work - dimensional accuracy</u>			
55	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B3.6 Previous work - defects</u>			
56	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B3.7 Services - known</u>			
57	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B3.8 Services - unknown</u>			
58	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B3.9 Protection of trees</u>			
59	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B3.10 Articles of value</u>			
60	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B3.11 Inspection of adjoining properties</u>			
61	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B4.0 MANAGEMENT OF CONTRACT</u>			
<u>B4.1 Management of the works</u>			
62	Fixed: _____ Value related: _____ Time related: _____	Item	
Carried to Collection		R	
Section No. 3			
Bill No. 1			
Preliminaries			

			Amount
<u>B4.2 Programme for the works</u>			
63	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B4.3 Progress meetings</u>			
64	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B4.4 Technical meetings</u>			
65	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B4.5 Labour and plant records</u>			
66	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B5.0 SAMPLES, SHOP DRAWINGS AND MANUFACTURERS' INSTRUCTIONS</u>			
<u>B5.1 Samples of materials</u>			
67	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B5.2 Workmanship samples</u>			
68	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B5.3 Shop drawings</u>			
69	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B5.4 Compliance with manufacturers instructions</u>			
70	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B6.0 TEMPORARY WORKS AND PLANT</u>			
<u>B6.1 Deposits and fees</u>			
71	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B6.2 Enclosure of the works</u>			
The contractor shall erect, maintain and remove at completion, hoardings, safety screens, barriers, access gates, covered gangways and the like as necessary for the enclosure of the works and elements thereof all for the protection of the public and others.			
72	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B6.3 Advertising</u>			
73	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B6.4 Plant, equipment, sheds and offices</u>			
74	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B6.5 Main notice board</u>			
75	Fixed: _____ Value related: _____ Time related: _____	Item	
Carried to Collection		R	
Section No. 3			
Bill No. 1			
Preliminaries			

			Amount
<u>B6.6 Subcontractors' notice board</u>			
76	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B7.0 TEMPORARY SERVICES</u>			
<u>B7.1 Location</u>			
77	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B7.2 Water</u>			
The contractor shall provide water for the works in accordance with: Alternative A (i.e. to be provided for by the Contractor).			
78	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B7.3 Electricity</u>			
The contractor shall provide electricity for the works in accordance with: Alternative A (i.e. to be provided for by the Contractor).			
79	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B7.4 Telecommunication facilities</u>			
The contractor shall provide telephones on site for the works in accordance with: Alternative A (i.e. to be provided for by the Contractor).			
80	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B7.5 Ablution facilities</u>			
The contractor shall provide toilet facilities on site for the works in accordance with: Alternative A (i.e. to be provided for by the Contractor).			
81	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B8.0 PRIME COST AMOUNTS</u>			
<u>B8.1 Responsibility for prime cost amounts</u>			
82	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>9.0 ATTENDANCE ON N/S SUBCONTRACTORS</u>			
<u>B9.1 General attendance</u>			
83	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B9.2 Special attendance</u>			
84	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B9.3 Commissioning - fuel, water and electricity</u>			
85	Fixed: _____ Value related: _____ Time related: _____	Item	
Carried to Collection		R	
Section No. 3			
Bill No. 1			
Preliminaries			

			Amount
<u>B10.0 FINANCIAL ASPECTS</u>			
<u>B10.1 Statutory taxes, duties and levies</u>			
86	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B10.2 Payment for preliminaries</u>			
87	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B10.3 Adjustment of preliminaries</u>			
88	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B10.4 Payment certificate cash flow</u>			
89	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B11. GENERAL</u>			
<u>B11.1 Protection of the works</u>			
90	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B11.2 Protection / isolation of existing / sectionally occupied works</u>			
91	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B11.3 Security of the works</u>			
92	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B11.4 Notice before covering work</u>			
93	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>11.5 Disturbance</u>			
94	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B11.6 Environmental disturbance</u>			
95	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B11.7 Works cleaning and clearing</u>			
96	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B11.8 Vermin</u>			
97	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B11.9 Overhand work</u>			
98	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B11.10 Instruction manuals and guarantees</u>			
99	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>B11.11 As built information</u>			
100	Fixed: _____ Value related: _____ Time related: _____	Item	
Carried to Collection		R	
Section No. 3			
Bill No. 1			
Preliminaries			

			Amount
101	<u>B11.12 Tenant installations</u>	Item	
	Fixed:_____ Value related:_____ Time related:_____		
102	<u>SECTION C: SPECIFIC PRELIMINARIES</u>	Item	
	Section C contains specific preliminary items which apply to this contract except where N/A (Not Applicable) appears against an item.		
103	<u>C1 CONTRACT DRAWINGS</u>	Item	
	The drawings issued with the tender documents do not comprise the complete set but serve as a guide only for tendering purposes and for indicating the scope of the work to enable the tenderer to acquaint himself with the nature and extent of the works and the manner in which they are to be executed. Should any part of the drawings not be clearly intelligible to the tenderer he shall, before submitting his tender, obtain clarification in writing from the principal agent.		
104	<u>C2 GENERAL PREAMBLES</u>	Item	
	The document "Specification of Materials and Methods to be used (PW371)" is obtainable on request from the head office and all regional offices of the Department, and shall be read in conjunction with the bills of quantities / lump sum document and be referred to for the full descriptions of work to be done and materials to be used.		
104	<u>C3 PROPRIETARY BRANDED PRODUCTS</u>	Item	
	The contractor shall take delivery of, handle, store, use, apply and/or fix all proprietary branded products in strict accordance with the manufacturer's instructions after consultation with the manufacturer's authorised representative. All materials, fittings, finishings, etc., specified hereinafter under a trade name, catalogue number or reference, must be exactly as described. The Architect's approval in writing must be obtained for the use of any alternative to the specification before the submission of tenders otherwise the specified materials, fittings, finishings, etc., will be assumed to have been allowed for in the tender. The Contractor must take delivery of, handle, store, use, apply and/or fix all proprietary branded products in strict accordance with the manufacturer's instructions after consultation with the manufacturer's authorised representative.		
104	Fixed:_____ Value related:_____ Time related:_____	Item	
Carried to Collection			R
Section No. 3			
Bill No. 1			
Preliminaries			

101

			Amount
<u>C4 CONTRACTOR'S RESPONSIBILITY</u>			
The Employer, the Principal Agent and the other professional consultants shall not be responsible for any act or omission on the part of the Contractor which may result in any patent or latent defects, in materials or workmanship, breach or neglect of any local regulations. The Contractor shall at all times be responsible for any such neglect, deviation or wrong act, whether the same is discovered before or after the final certificate, or any other Certificate, has been approved			
105	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>C5 OVERTIME</u>			
Should overtime be required to be worked for any reason whatsoever, the costs of such overtime are to be borne by the contractor unless the principal agent has specifically authorised in writing, prior to the execution thereof, that costs for such overtime are to be borne by the employer.			
106	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>C6 AS BUILT DRAWINGS</u>			
The position of construction breaks and the extent of individual concrete pours are to be recorded by the contractor on the structural engineer's drawings and are to be submitted to the principal agent and the structural engineer for their records.			
Three full sets of as-built drawings shall be submitted to the Principal Agent no later than fourteen days after practical completion			
107	Fixed: _____ Value related: _____ Time related: _____	Item	
<u>C7 CONTRACT INSTRUCTIONS</u>			
Contract instructions issued on site are to be recorded in triplicate in a site instruction book which is to be maintained on site by the Contractor. The Contractor shall supply and have available at the site of the works at all times, the following site books:			
a) Contract Instruction Book			
Receiving and recording instructions in a suitable A4 size triplicate book kept on site. Instructions issued shall be recorded by the Architect or other Employer's Agents to whom the Architect has delegated authority to in the book.			
Only instructions issued in such book shall be recognised.			
b) Daily Record Book			
The Contractor shall record in triplicate in a suitable A4 size triplicate book kept at the site, a daily record of work done, all site visits by the Principal Agent and other professional personnel and all events affecting the Works, such as progress, issue of plans, breakdown of machinery, etc. The labour, plant and material on site shall be recorded as well as work performed. Entries must be made by the Contractor and must be signed and forwarded to the Principal Agent for his counter-signature on a daily basis. Copies of these records shall be for the Architect, Quantity Surveyor and Contractor.			
Carried to Collection			
Section No. 3			R
Bill No. 1			
Preliminaries			

			Amount
108	Fixed: _____ Value related: _____ Time related: _____ <u>C8 LABOUR RECORD</u> At the end of each week the contractor shall provide the principal agent with a written record, in schedule form, reflecting the number and description of tradesmen and labourers employed by him and all subcontractors on the works each day	Item	
109	F: V: T: <u>C9 PLANT RECORD</u> At the end of each week the contractor shall provide the principal agent with a written record, in schedule form, reflecting the number, type and capacity of all plant, excluding hand tools, currently used on the works.	Item	
110	F: V: T: <u>C10 ENCROACHMENT</u> During the course of the building operations, the Contractor shall be held entirely responsible for any encroachment onto any adjoining properties, buildings, etc., or servitudes and the cost of any remedial measures as required by the Principal Agent shall be borne by the Contractor	Item	
111	F: V: T: <u>C11 METHOD STATEMENT</u> The Tenderer shall produce, when required to do so by the Principal Agent, a Method Statement outlining the methods of construction and labour and plant resources that he proposes to use in the execution of the Works. Any approval given or observation made by the Principal Agent shall not relieve the Contractor of his sole responsibility to adopt the methods of construction and to provide the labour and plant resources necessary for the due and proper timeous execution of the Works.	Item	
112	F: V: T: <u>C12 UNAUTHORISED PERSONS/WORKMEN ON PREMISES</u> The Contractor shall at all times strictly exclude all unauthorised persons from the Works and the site and shall set up notice boards to that effect. No workmen or labourers (except security guards) are to be allowed under any circumstances to sleep or deposit any kit on the premises. The Contractor must provide any necessary independent shelter or shed required for any labour or watchmen on site, to the approval of the Employer.	Item	
113	F: V: T: <u>C13 MODE OF PROCEDURE</u> Notwithstanding anything to the contrary contained herein the Principal Agent at all times reserves the right to direct the order in which the various parts of the Contract are to be executed. The Contractor shall give priority to any individual section or portion of the Works that, in the opinion of the Principal Agent, requires to be expedited.	Item	
Carried to Collection			
Section No. 3			
Bill No. 1			
Preliminaries			

			Amount
114	Should it appear, in the Principal Agent's opinion, that work in any area is not being executed in accordance with the requirements of the Contract Programme, the Contractor shall provide additional manpower and resources and shall work additional overtime and do everything else required to bring the work back to programme to the satisfaction of the Principal Agent and to the Contractor's cost F: V: T: <u>C14 LOCATION OF TEMPORARY BUILDINGS AND TEMPORARY SERVICES</u> The Contractor shall provide all necessary temporary works, including temporary roads, tracks, crossings, hardstanding and services, hoardings, dust screens, tunnelling, etc., required for his own and sub-contractors use during the construction and maintenance period There is no guarantee given or implied that Site conditions will be such that the Contractor will be able to erect such temporary works, roads, hardhats, offices, stores and temporary accommodation within the site boundaries and it shall be the Contractor's responsibility to adopt whatever measures he deems necessary in this regard and to obtain all necessary permission and pay all costs in connection therewith	Item	
115	F: V: T: <u>C15 OFFICE ACCOMMODATION</u> The contractor shall provide, maintain and remove on practical completion air conditioned office accommodation with suitable tables and chairs for meetings to be held on the site. Such offices shall be kept clean and fit for use at all times [12.2.18]	Item	
116	F: V: T: <u>C16 STORAGE FACILITIES</u> The Contractor shall provide a Container for storage of materials.	Item	
117	F: V: T: <u>C17 REMOVAL AND MAKING GOOD OF TEMPORARY WORKS, ETC, ON COMPLETION</u> The Contractor shall remove (except where specifically stated otherwise) all temporary works, roads, services and the like used for this contract and shall make good to the entire satisfaction of the Principal Agent any damage resulting therefrom.	Item	
118	F: V: T:	Item	
Carried to Collection			
Section No. 3			
Bill No. 1			
Preliminaries			

Amount

SECTION NO. 3

KHIBA JUNIOR SECONDARY SCHOOL

BILL NO. 1

PRELIMINARIES

COLLECTION

Page No

Brought Forward from Page

90

91

92

93

94

95

96

97

98

99

100

101

102

103

104

Carried To Section Summary

R

Section No. 3

Bill No. 1

Preliminaries

	Unit	Quantity	Rate	Amount
<u>SECTION NO. 3</u> <u>KHIBA JUNIOR SECONDARY SCHOOL</u> <u>BILL NO. 2</u> <u>HEALTH AND SAFETY</u> <u>MODEL PREAMBLES</u> The tenderer is referred to the "Model Preambles for Trades 2008" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates. <u>SUPPLEMENTARY PREAMBLES</u> Supplementary preambles and/or specifications are incorporated in these bills of quantities to satisfy the requirements of this project. Such supplementary preambles and/or specifications shall take precedence over the provisions of the General Preambles. The contractor's prices for all items throughout these bills of quantities shall take account of and include where applicable for all of the obligations, requirements and specifications given in the General Preambles and in any supplementary preambles and/or specifications. Prior to pricing the principal contractor must familiarize him/herself with the Occupational Health and Safety Act No. 85 Of 1993, Construction Regulations 2014, other relevant Regulations and Standards as well as project specific Health & Safety specifications. <u>OCCUPATIONAL HEALTH AND SAFETY</u> <u>General</u> 1 Preparation of Contractor's site specific Health and Safety Plan 2 Submission of the Health and Safety File 3 Principal Contractor's initial obligations in respect of the OHS Act and Construction Regulations 4 Principal Contractor's time related obligations in respect of the OHS Act and Construction Regulations for the entire construction period 5 Provision of full time Health and Safety Officer for the entire construction period 6 Induction training of all personnel 7 Provision of first aid boxes Carried to Collection Section No. 3 Bill No. 2 Health And Safety				
	Item			
	Item			
	Item			
	Item			
	Item			
	Item			
	Item			
			R	

		Unit	Quantity	Rate	Amount
8	SANS approved weld mesh type temporary barrier fencing 1,8m high covered with a net fixed to and including 100mm diameter gum poles set securely min 300mm deep in ground at max 3m spacing including excavation, backfilling, etc	m	150		
9	Extra over mesh fence for pedestrian gate size 1.8 x 1,8m high	No	1		
<u>Provision for Personal Protective Equipment and</u>					
10	Reflective vests.	Item			
11	Hard hats	Item			
12	Protective footwear	Item			
13	Ear plugs	Item			
14	Dust masks	Item			
<u>Medical certificates and medical surveillance</u>					
15	Initial (baseline) medical examinations for all personnel	Item			
16	Exit Examinations for all personnel	Item			
<u>Noise Monitoring</u>					
17	Establishment of noise zones	Item			
18	Audiograms	Item			
<u>Covid-19 Compliance Measures</u>					
19	The Contractor is required to price for Covid 19 compliance and the pricing thereof shall be deemed to include all the mandatory requirements	Item			
				R	
Carried to Collection					
Section No. 3					
Bill No. 2					
Health And Safety					

107

Amount

SECTION NO. 3

KHIBA JUNIOR SECONDARY SCHOOL

BILL NO. 2

HEALTH AND SAFETY

COLLECTION

Page No

Brought Forward from Page

106

107

Carried To Section Summary

R

Section No. 3

Bill No. 2

Health And Safety

	Unit	Quantity	Rate	Amount
<u>SECTION NO. 3</u> <u>KHIBA JUNIOR SECONDARY SCHOOL</u> <u>BILL NO. 3</u> <u>RENOVATIONS</u> <u>PREAMBLES</u> The Tenderer is referred to the relevant Clause in the separate document Model Preambles for Trades (1999 Edition) published by the Association of South African Quantity Surveyors, the document "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition July 2014) and the Supplementary Preambles which are incorporated in these Bills of Quantities <u>SUPPLEMENTARY PREAMBLES</u> <u>View site</u> Before submitting his tender the tenderer shall visit the site and satisfy himself as to the nature and extent of the work to be done and the value of the materials contained in the buildings or portions of the buildings to be demolished. No claim for any variations of the contract sum in respect of the nature and extent of the work or of inferior or damaged materials will be entertained <u>General</u> Water supply pipes and other piping in ground that may be encountered and found necessary to disconnect or cut, shall be effectually stopped off or grubbed up and removed, and any new connections that may be necessary shall be made with proper fittings to the satisfaction of the principal agent <u>MAKING GOOD OF EXISTING WORK</u> <u>Making good VIP pedestals</u> 1 Secure loosely fitted pit pedestals by bolting down securely or applying an cement/ epoxy based industrial adhesive <u>Taking out and removing piping, sanitary fittings, etc including disconnecting piping from fittings and making good floor and wall finishes (making good tiling and paintwork elsewhere)</u> 2 Damaged 110mm vent pipes				
	No	9		
	m	4		
Carried to Collection			R	
Section No. 3 Bill No. 3 Renovations				

	Unit	Quantity	Rate	Amount
<u>Making good leaking water pipe fittings by disassembling, cleanning, applying appropriate seal and reassembling</u>				
3	No	1		
<u>Making good existing pit latrine chambers</u>				
4	Litres	24 000		
<u>BATHROOM FITTINGS</u>				
<u>Stainless steel bathroom fittings</u>				
5	No	7		
<u>SANITARY PLUMBING</u>				
<u>PVC-U soil and vent pipes</u>				
6	m	4		
<u>Extra over PVC-U soil and vent pipes for fittings</u>				
7	No	12		
8	No	1		
Carried to Collection				R
Section No. 3				
Bill No. 3				
Renovations				

110

Amount

SECTION NO. 3

KHIBA JUNIOR SECONDARY SCHOOL

BILL NO. 3

RENOVATIONS

COLLECTION

Page No

Brought Forward from Page

109

110

Carried To Section Summary

R

Section No. 3

Bill No. 3

Renovations

	Unit	Quantity	Rate	Amount
<u>SECTION NO. 3</u> <u>KHIBA JUNIOR SECONDARY SCHOOL</u> <u>BILL NO. 4</u> <u>GARDEN AND BALUSTRADE WALLS</u> <u>PREAMBLES</u> The Tenderer is referred to the relevant Clause in the separate document Model Preambles for Trades (1999 Edition) published by the Association of South African Quantity Surveyors, the document "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition July 2014) and the Supplementary Preambles which are incorporated in these Bills of Quantities <u>EARTHWORKS (PROVISIONAL)</u> <u>Excavate in pickable material not exceeding 2m deep below natural or reduced ground level:</u>				
1	Surface trenches.	m ³	24	
	<u>Extra over excavation in pickable material for column bases, trenches, lift pits, sumps, etc for excavation:</u>			
2	Soft rock.	m ³	3	
3	Hard rock.	m ³	1	
4	Allow for risk of collapse to sides of excavations to column bases, trenches, etc. from ground level to not exceeding 1,5m deep.	m ²	96	
5	Allow for keeping excavations entirely free from water or mud.	Item		
	<u>Earth filling obtained from the excavations and/or prescribed stock piles on site, compacted to 98% Mod AASHTO density</u>			
6	Backfilling to trenches, holes, etc.	m ³	4	
7	Scarify in-situ material for a depth of 150mm and compact to obtain 98% modified AASHTO dry density.	m ²	40	
	<u>Earth filling supplied by the contractor, compacted to 98% Mod AASHTO density</u>			
8	Under floors, steps, pavings, etc.	m ³	4	
Carried to Collection			R	
Section No. 3				
Bill No. 4				
Garden And Balustrade Walls				

113

Amount

SECTION NO. 3

KHIBA JUNIOR SECONDARY SCHOOL

BILL NO. 4

GARDEN AND BALUSTRADE WALLS

COLLECTION

Page No

Brought Forward from Page

112

113

Carried To Section Summary

R

Section No. 3

Bill No. 4

Garden And Balustrade Walls

	Unit	Quantity	Rate	Amount
<u>SECTION NO. 3</u> <u>KHIBA JUNIOR SECONDARY SCHOOL</u> <u>BILL NO. 5</u> <u>V – DRAINS</u> <u>PREAMBLES</u> The Tenderer is referred to the relevant Clause in the separate document Model Preambles for Trades (1999 Edition) published by the Association of South African Quantity Surveyors, the document "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition July 2014) and the Supplementary Preambles which are incorporated in these Bills of Quantities <u>SUPPLEMENTARY PREAMBLES</u> <u>Nature of ground:</u> The nature of the ground is assumed to be loose sandy material, therefore 'earth', but possibly interspersed with 'soft rock' or 'hard rock' <u>Carting away of excavated material:</u> Descriptions of carting away of excavated material shall be deemed to include loading excavated material onto trucks directly from the excavations or, alternatively, from stock piles situated on the building site <u>Filling:</u> Notwithstanding the reference to prescribed multiple handling in clause 1 page 6 of the Standard System of Measuring Building Work, prices for filling and backfilling shall include for all selection and any necessary multiple handling of material <u>Testing:</u> Prices for filling are to include for all necessary density tests in accordance with SABS 1200D <u>Cost of tests:</u> The costs of making, storing and testing of concrete test cubes as required under clause 7 Tests of SABS 1200 G shall include the cost of providing cube moulds necessary for the purpose, for testing costs and for submitting reports on the tests to the principal agent. The testing shall be undertaken by an independent firm or institution nominated by the contractor to the approval of the principal agent. (Test cubes are measured separately)				
Carried to Collection				
Section No. 3 Bill No. 5 V – Drains			R	

		Unit	Quantity	Rate	Amount
	<u>EXCAVATION ETC</u>				
	<u>Excavation in earth not exceeding 2m deep</u>				
1	Reduced levels under pavings	m ³	9		
	<u>Extra over all excavations for carting away</u>				
2	Surplus material from excavations and/or stock piles on site, to a dumping site to be located by the contractor	m ³	9		
	<u>FILLING ETC OTHER THAN BULK</u>				
	<u>Earth filling (G7 material) supplied by the contractor, compacted to 95% Mod AASHTO density</u>				
3	Under floors, steps, pavings, etc.	m ³	6		
	<u>Coarse river sand filling supplied by the contractor</u>				
4	Under pavings etc.	m ³	2		
	<u>Compaction of surfaces</u>				
5	Compaction of ground surface under floors etc. including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 98% Mod AASHTO density	m ²	37		
	<u>Prescribed density tests on filling</u>				
6	Modified AASHTO Density test	No	3		
	<u>DAMPPROOFING OF WALLS AND FLOORS</u>				
	<u>One layer 250 micron green polyethylene waterproof sheeting (SANS 952-1985 type C) sealed at laps with PVC self-adhesive tape</u>				
7	Under surface pavings etc.	m ²	37		
	<u>STORMWATER DRAINAGE (PROVISIONAL)</u>				
	<u>Precast or in-situ concrete (25 MPa) open stormwater channels having V-shaped waterway formed in top, finished smooth on all exposed surfaces in (3:1) untinted cement plaster trowelled smooth and with angles rounded, cast in maximum 3000mm lengths, and reinforced as necessary for handling if precast, including laying to falls, bedding and pointing in (3:1) cement mortar:</u>				
8	Channel size 700 x 230mm overall with 700 x 150mm deep v-channel waterway.	m	53		
9	Extra for angle.	No	3		
10	Extra for fair end.	No	1		
	Carried to Collection			R	
	Section No. 3				
	Bill No. 5				
	V – Drains				

		Unit	Quantity	Rate	Amount
11	Extra for 1000mm long x 2700mm wide outlet with 300mm deep x 300mm wide thickened edge and thirteen number 150 x 150 x 150mm concrete block energy dissipaters set into in-situ concrete draining off to and including a 2700 x 600 x 100mm thick bed formed of 19mm diameter stones	No	1		
12	Stormwater dish drain size 900 x 600 x 900mm wide (2400 wide overall) x 300mm deep with 2400 x 150mm deep waterway.	m	3		
<u>TEST CUBES</u>					
<u>Test Cubes</u>					
13	Making and testing 150 x 150 x 150mm concrete strength test cube (Provisional)	No	3		
<u>REINFORCEMENT (CPAP WORK GROUP NO. 114)</u>					
<u>Fabric reinforcement</u>					
14	Type 617 fabric reinforcement in concrete dish drains etc	m ²	37		
Carried to Collection				R	
Section No. 3					
Bill No. 5					
V – Drains					

Amount

SECTION NO. 3

KHIBA JUNIOR SECONDARY SCHOOL

BILL NO. 5

V – DRAINS

COLLECTION

Page No

Brought Forward from Page

115

116

117

Carried To Section Summary

R

Section No. 3

Bill No. 5

V – Drains

	Unit	Quantity	Rate	Amount
<u>SECTION NO. 3</u> <u>KHIBA JUNIOR SECONDARY SCHOOL</u> <u>BILL NO. 6</u> <u>SUBSOIL DRAINAGE</u> <u>PREAMBLES</u> The Tenderer is referred to the relevant Clause in the separate document Model Preambles for Trades (1999 Edition) published by the Association of South African Quantity Surveyors, the document "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition July 2014) and the Supplementary Preambles which are incorporated in these Bills of Quantities <u>SUPPLEMENTARY PREAMBLES</u> <u>Laying, backfilling, bedding, etc. of pipes</u> Pipes shall be laid and bedded in accordance with manufacturers' instructions and trenches shall be carefully backfilled <u>As-built drawings:</u> Where required, the contractor shall prepare an updated set of as-built drawings. At completion of the contract the contractor shall hand these drawings to the principal agent for reproducing onto the originals for handing over to the employer (provision for allowance of as-built drawings elsewhere) <u>SUBSOIL DRAINAGE (CPAP WORK GROUP NO. 146)</u> <u>Site clearance</u> 1 Digging up and removing rubbish, debris, vegetation, hedges, shrubs, bush, etc. and trees not exceeding 200mm girth <u>Subsoil drainage</u> 2 Excavation in earth not exceeding 2m deep for pipe trenches 3 Extra over all excavations for carting away surplus material from excavations and/or stock piles on site, to a dumping site to be located by the contractor 4 Risk of collapse to sides of trench and hole excavation not exceeding 1.5m deep 5 Keeping excavations free of water				
	m ²	29		
	m ³	58		
	m ³	14		
	m ²	144		
	Item			
Carried to Collection			R	
Section No. 3				
Bill No. 6				
Subsoil Drainage				

		Unit	Quantity	Rate	Amount
6	Filling in bedding under and filling around pipes with granular material supplied by the contractor and compacted to 98% Mod AASHTO density	m ³	91		
7	19mm Crushed stone encasing to pipes	m ³	39		
	<u>Slotted uPVC flexible drainage pipes</u>				
8	110mm Pipes laid in stone encasing (encasing elsewhere)	m	108		
	<u>Extra over slotted uPVC flexible drainage pipes for fittings</u>				
9	110mm Bend	No	9		
10	110mm Junction	No	3		
	<u>Geotextile filter fabric blanket with stiched 300mm laps</u>				
11	Around stone filling in sub-soil drain trenches	m ²	259		
Carried to Collection				R	
Section No. 3					
Bill No. 6					
Subsoil Drainage					

Amount

SECTION NO. 3

KHIBA JUNIOR SECONDARY SCHOOL

BILL NO. 6

SUBSOIL DRAINAGE

COLLECTION

Page No

Brought Forward from Page

119

120

Carried To Section Summary

R

Section No. 3

Bill No. 6

Subsoil Drainage

	Unit	Quantity	Rate	Amount
<u>SECTION NO. 3</u> <u>KHIBA JUNIOR SECONDARY SCHOOL</u> <u>BILL NO. 7</u> <u>SOAKAWAYS & CULVERTS</u> <u>PREAMBLES</u> The Tenderer is referred to the relevant Clause in the separate document Model Preambles for Trades (1999 Edition) published by the Association of South African Quantity Surveyors, the document "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition July 2014) and the Supplementary Preambles which are incorporated in these Bills of Quantities <u>SUPPLEMENTARY PREAMBLES</u> <u>Filling:</u> Notwithstanding the reference to prescribed multiple handling in clause 1 page 6 of the Standard System of Measuring Building Work, prices for filling and backfilling shall include for all selection and any necessary multiple handling of material <u>Testing:</u> Prices for filling are to include for all necessary density tests in accordance with SABS 1200D <u>THE FOLLOWING IN STORMWATER SOAKAWAYS</u> <u>Site clearance</u> 1 Digging up and removing rubbish, debris, vegetation, hedges, shrubs, bush, etc. and trees not exceeding 200mm girth <u>Subsoil drainage</u> 2 Excavation in earth not exceeding 2m deep for pipe trenches 3 Extra over all excavations for carting away surplus material from excavations and/or stock piles on site, to a dumping site to be located by the contractor 4 Risk of collapse to sides of trench and hole excavation not exceeding 1.5m deep 5 Keeping excavations free of water 6 Filling in bedding under and filling around pipes with granular material supplied by the contractor and compacted to 98% Mod AASHTO density Carried to Collection Section No. 3 Bill No. 7 Soakaways & Culverts				
	m ²	2		
	m ³	1		
	m ³	1		
	m ²	5		
	Item			
	m ³	1		
			R	

	Unit	Quantity	Rate	Amount
7 63mm Stone beds	m³	2		
<u>Geotextle filter fabric blanket with stiched 300mm laps</u>				
8 Around stone filling in sub-soil drain trenches	m²	4		
Carried to Collection			R	
Section No. 3				
Bill No. 7				
Soakaways & Culverts				

123

Amount

SECTION NO. 3

KHIBA JUNIOR SECONDARY SCHOOL

BILL NO. 7

SOAKAWAYS & CULVERTS

COLLECTION

Page No

Brought Forward from Page

122

123

Carried To Section Summary

R

Section No. 3

Bill No. 7

Soakaways & Culverts

		Amount
<u>SECTION NO. 3</u>		
<u>KHIBA JUNIOR SECONDARY SCHOOL</u>		
<u>BILL NO. 8</u>		
<u>PROVISIONAL SUMS</u>		
<u>BUDGETARY ALLOWANCES</u>		
<u>PROVISIONAL SUMS</u>		
<u>Supplementary Preambles</u>		
Tenderers are advised that no claim in respect of loss of profit or Preliminary charges based on the omission of these amounts will be considered and the said amounts will be omitted strictly without any financial compensation payable to the Contractor.		
Provisional sums and Budgetary allowances contained herein may be omitted or reduced at the Employer's discretion and the Contractor shall not be entitled to claim for any loss by way of reductions or omission of any discount, or percentage relating to Provisional amounts and Budgetary sums or any loss of profit related thereto.		
<u>Sundry building work</u>		
1	Provide the sum of R22 500.00 for the employment of a Community Liaison Officer to be employed by the Main Contractor and be paid an allowance of R7 500.00 a month for the duration (3 months)	Item 22 500 00
2	Profit	Item
3	Attendance	Item
4	Provide the sum of R55 000. 00 for the hire, maintenance and servicing of temporary toilets for educators and learners during the entire constructions period	Item 55 000 00
5	Profit	Item
6	Attendance	Item
7	Provide the sum of R10 000. 00 for landscaping to be used as directed by the Principal Agent and deducted in whole or in part if not required	Item 10 000 00
8	Profit	Item
9	Attendance	Item
<u>Contingencies</u>		
10	Allow the Amount of R24 000.00 (Twenty Four Thousand Rands) for contingencies, to be used by the Architect in terms of Clause 17 of the Principal Building Agreement.	Item 24 000 00
Carried To Section Summary		R
Section No. 3		
Bill No. 8		
Provisional Sums		

Amount

SECTION NO. 3
KHIBA JUNIOR SECONDARY SCHOOL
SECTION SUMMARY

Bill No.		Page
1	PRELIMINARIES	105
2	HEALTH AND SAFETY	108
3	RENOVATIONS	111
4	GARDEN AND BALUSTRADE WALLS	114
5	V – DRAINS	118
6	SUBSOIL DRAINAGE	121
7	SOAKAWAYS & CULVERTS	124
8	PROVISIONAL SUMS	125

Section No. 3
SECTION SUMMARY

Carried to Final Summary

R

[illegible]