

## SCHEDULE B : ROAD WORKS

## SECTION 3300

ITEM NO	LIC	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
33,01		<b>MASS EARTHWORKS</b>				
		<b>Cut and borrow to fill with Commercial sourced material</b>				
		(a) Material in compacted layer thicknesses of 150 mm and less:				
		(i) Compacted to 90% of modified AASHTO density	m <sup>3</sup>	1 000		
33,03		(ii) Compacted to 93% of modified AASHTO density	m <sup>3</sup>	100		
		<b>Extra over item 33.01 for excavating and breaking down material in:</b>				
		(a) Intermediate excavation	m <sup>3</sup>	400,00		
		(b) Hard excavation	m <sup>3</sup>	200,00		
B33.03		(c) Boulder excavation class A	m <sup>3</sup>	10		
		(d) Boulder excavation class B	m <sup>3</sup>	10		
		<b>Extra over item 33.01 for importing material G7 of Better, from commercial sources:</b>				
		(a) (ii) Compacted to 90% of modified AASHTO	m <sup>3</sup>	450		
33,04		<b>Cut to spoil, including free-haul up to 0,5 km. Material obtained from:</b>				
		(a) Soft excavation	m <sup>3</sup>	1 400		
		(b) Intermediate excavation	m <sup>3</sup>	100,00		
		(c) Hard excavation	m <sup>3</sup>	35		
		(d) Boulder excavation class A	m <sup>3</sup>	5		
		(e) Boulder excavation class B	m <sup>3</sup>	5		
33,05		<b>Overbreak in hard and boulder class A excavation</b>	m <sup>2</sup>			
33,06		<b>Variations in the number of roller passes (applicable to subsubitems 33.01(a)(iii) and 33.01(b)(iii) and item 33.11):</b>				
		(a) Vibratory rollers	m <sup>2</sup> -pass	2,00		
		(b) Oscillatory rollers	m <sup>2</sup> -pass	2,00		
		(c) Grid rollers	m <sup>2</sup> -pass	2,00		
		(d) Tamping rollers	m <sup>2</sup> -pass	2,00		
		(e) Impact rollers	m <sup>2</sup> -pass	2,00		
		(f) Pneumatic-tyred rollers	m <sup>2</sup> -pass	2,00		
3300		<b>TOTAL CARRIED FORWARD</b>				

## SCHEDULE B : ROAD WORKS

## SECTION 3300

ITEM NO	LIC	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
33.07		<b><u>MASS EARTHWORKS</u></b> <b>Removal of unsuitable material (including free-haul of 0,5 km):</b> (a) In layer thicknesses of 150 mm and less: (i) Stable material (ii) Unstable material	m <sup>3</sup>  m <sup>3</sup>	10,00  10,00		
33,08		<b>Widening of cuts (extra over items 33.01, 33.02 and 33.04):</b> (a) In hard material (b) In boulder material class A or class B (c) In all other materials		10,00 10,00 10,00		
B33.09		<b>Material temporarily removed and placed in a windrow</b>	m <sup>3</sup>	1485,00		
33.10		<b>Roadbed preparation and the compaction of material:</b> (b) Compaction to 93% of modified AASHTO density (i) For roads and parking areas (iii) For walkways	  m <sup>3</sup> m <sup>3</sup>	  1800,00 10		
33.12		<b>In situ treatment of roadbed:</b> (a) In situ treatment by ripping	m <sup>3</sup>	1 800		
33,13		<b>Finishing-off cut and fill slopes</b> (a) Cut slopes (b) Fill slopes	m <sup>2</sup> m <sup>2</sup>	800 1500,00		
33.14		<b>Extra over item 33.01 for excavating material from the pavements and fills of existing roads:</b> (a) Non-cemented material (b) Cemented material	m <sup>3</sup> m <sup>3</sup>	5 5,00		
3300		<b>TOTAL CARRIED TO SUMMARY</b>				