

Item No	Quantity	Rate	Amount
<u>SECTION 1</u>			
<u>BILL NO. 1</u>			
<u>PRELIMINARIES</u>			
<u>BUILDING AGREEMENT AND PRELIMINARIES</u>			
<p>The JBCC Series 2000 Edition 4.1 Code 2101 March 2005 2005 edition prepared by the Joint Building Contracts Committee, shall be the agreement, amended as hereinafter described</p> <p>The Preliminaries for use with the JBCC Series 2000 Principal Building Agreement (May 2005 edition) prepared by the Joint Building Contracts Committee, shall be deemed to be incorporated in these bills of quantities</p> <p>Contractors are referred to the above-mentioned documents for the full intent and meaning of each clause thereof</p> <p>These clauses are hereinafter referred to by clause number and heading only. Where standard clauses or alternatives are not entirely applicable to this contract such modifications, corrections or supplements as will apply are given under each relevant clause heading and such modifications, corrections or supplements shall take precedence notwithstanding anything contrary contained in the above-mentioned documents</p> <p>Where any item is not relevant to this specific contract such item is marked N/A, signifying "not applicable"</p> <p>Notwithstanding anything to the contrary contained in any of the contract documents including the Principal Building Agreement and the Preliminaries, the provision of the "Preliminaries" as hereinafter set forth shall prevail and shall take precedence</p>			
Carried to Collection			R
Section 1 Bill No. 1 PRELIMINARIES			

PREAMBLES FOR TRADES

The Model Preambles for Trades (1999 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claim arising from brevity of description of items fully described in the said Model Preambles for Trades will be entertained

Supplementary preambles to the Model Preambles covering clauses of a general nature, clauses pertaining to specific materials and amendments to clauses in the Model Preambles are incorporated in these bills of quantities to satisfy the requirements of this project

The contractor's prices for all items throughout these bills of quantities must take account of and include for all of the obligations, requirements and specifications given in the Model Preambles and in any supplementary preambles

GENERAL

If Alternative A as set out in clause B10.3 hereinafter is to be used for the adjustment of the preliminaries each item priced is to be allocated to one or more of the three categories "F", "T" or "V" as the case may be below such item, where "F" denotes a fixed amount (amount not to be varied), "T" denotes an amount variable in proportion to time and "V" denotes an amount variable in proportion to value

SECTION A - PRINCIPAL BUILDING AGREEMENT

Definitions (A1)

- 1 Definitions and interpretation (clause 1)

F:..... V:.....
T:.....

Item

Carried to Collection

R

Section 1
Bill No. 1
PRELIMINARIES

Objective and Preparation (A2 to A14)

2 Offer acceptance and performance (clause 2)

F:..... V:.....
T:.....

Item

3 Documents (clause 3)

F:..... V:.....
T:.....

Item

4 Design responsibility (clause 4)

F:..... V:.....
T:.....

Item

5 Employer's agents (clause 5)

F:..... V:.....
T:.....

Item

The principal agent shall:

- monitor and control progress and scheduling
- monitor all contract conditions, and
- coordinate the efforts of the employer's agents, the contractor and subcontractors

The powers conferred on the principal agent in terms of this clause and/or the exercising of these powers shall not be construed as removing or diminishing any of the obligations of the Contractor in terms of the Principal Building Agreement, whether financial, contractual or otherwise, nor shall the exercising of these powers create any privity of contract as between the Employer or his agents on the one part and the Contractor or subcontractors or suppliers on the other part

Carried to Collection

R

Section 1
Bill No. 1
PRELIMINARIES

	The principal agent reserves the right to attend and participate in all contractor/subcontractor's meetings, to invite other employer's agents to attend such meetings at his discretion and to converse and chair any such meetings if the contractor is derelict in his duty in arranging such meetings to the degree of frequency and comprehensiveness dictated in the opinion of the project manager by the circumstances and exigencies of the construction process			
6	Site representative (clause 6)			
	F:..... V:..... T:.....	Item		
7	Compliance with regulations (clause 7)			
	F:..... V:..... T:.....	Item		
8	Works risk (clause 8)			
	F:..... V:..... T:.....	Item		
9	Indemnities (clause 9)			
	F:..... V:..... T:.....	Item		
10	Works insurances (clause 10)			
	F:..... V:..... T:.....	Item		
11	Liability insurances (clause 11)			
	F:..... V:..... T:.....	Item		
Carried to Collection				
Section 1 Bill No. 1 PRELIMINARIES				

12	Effecting insurance (clause 12)			
	F:..... V:..... T:.....	Item		
13	NO CLAUSE	N/A		
14	Security (clause 14)			
	F:..... V:..... T:.....	Item		
	<u>Execution (A15-A23)</u>			
15	Preparation for and execution of the works (clause 15)			
	F:..... V:..... T:.....	Item		
16	Access to the works (clause 16)			
	F:..... V:..... T:.....	Item		
17	Contract instructions (clause 17)			
	F:..... V:..... T:.....	Item		
18	Setting out of the works (clause 18)			
	F:..... V:..... T:.....	Item		
	The contractor shall notify the principal agent if any encroachments of adjoining foundations, buildings, structures, pavements, boundaries, etc exist in order that the necessary arrangements may be made for the rectification of any such encroachments			
	Carried to Collection		R	
	Section 1 Bill No. 1 PRELIMINARIES			

19	<p>Assignment (clause 19)</p> <p>F:..... V:..... T:.....</p> <p>The contractor shall not cede his rights or delegate his obligations in terms of this agreement unless specifically called for by the employer</p>	Item		
20	<p>Nominated subcontractors (clause 20)</p> <p>F:..... V:..... T:.....</p>	Item		
21	<p>Selected subcontractors (clause 21)</p> <p>F:..... V:..... T:.....</p> <p>Written proof is required from subcontract tenderers at tendering that they can meet the JBCC Selected Subcontract Agreement or other tender agreements and provide security in terms of the agreement. If the above is not provided the tender may not be accepted</p> <p>All amounts allowed under Provisional Amounts are intended to be awarded to Selected Subcontractors</p>	Item		
22	<p>Employer's Direct Contractors (clause 22)</p> <p>F:..... V:..... T:.....</p>	Item		
23	<p>Contractor's Domestic Sub-Contractors (Clause 23)</p> <p>F:..... V:..... T:.....</p> <p><u>Completion (A24-A30)</u></p>	Item		
24	<p>Practical completion (clause 24)</p> <p>F:..... V:..... T:.....</p>	Item		
Carried to Collection			R	
<p>Section 1 Bill No. 1 PRELIMINARIES</p>				

25	Works completion (clause 25)			
	F:..... V:..... T:.....	Item		
26	Final completion (clause 26)			
	F:..... V:..... T:.....	Item		
27	Latent defects liability period (clause 27)			
	F:..... V:..... T:.....	Item		
28	Sectional completion (clause 28)			
	F:..... V:..... T:.....	Item		
29	Revision of date of practical completion (clause 29)			
	F:..... V:..... T:.....	Item		
	The removal and replacement of materials and/or workmanship that do not conform to specification or drawings shall not constitute grounds for an extension of the construction period nor for an adjustment to the contract sum (clause 29.3)			
30	Penalty for non-completion (clause 30)			
	F:..... V:..... T:.....	Item		
Carried to Collection				
Section 1				
Bill No. 1				
PRELIMINARIES				

Payment (A31 - A35)

31 Interim payment to the contractor (clause 31)

F:..... V:.....
T:.....

Item

32 Adjustment to the contract value (clause 32)

F:..... V:.....
T:.....

Item

Where prices are submitted by the contractor or nominated/selected subcontractors during the progress of the works in respect of contract instructions or in regard to a claim under the terms of the contract and notwithstanding the fact that such prices may be used in an interim payment certificate, there is to be no presumption of acceptance. Should the principal agent wish to accept any such prices prior to the issue of the final certificate, it will be in writing

33 Recovery of expense and loss (clause 33)

F:..... V:.....
T:.....

Item

34 Final account and final payment (clause 34)

F:..... V:.....
T:.....

Item

The employer shall not pay any interest on amounts payable to the contractor for one hundred and forty two (142) days after the date of issue of the certificate of practical completion

Carried to Collection

R

Section 1
Bill No. 1
PRELIMINARIES

The employer shall, however, pay interest to the contractor at the rate stipulated in clause 34.11 on any amounts payable to the contractor more than one hundred and forty two (142) days after the date of issue of the certificate of practical completion but only for such period as the settlement of the final account is delayed by the non-performance of the principal agent or the employer or his agents. In evaluating non-performance for purposes of this clause a reasonable time shall be allowed to the employer or his agents to respond to any matter brought to his/their attention and which may affect the settlement of the final account

35 Payment to other parties (clause 35)

F:..... V:.....
T:.....

Item

Cancellation (A36-A39)

36 Cancellation by employer - contractor's default (clause 36)

F:..... V:.....
T:.....

Item

37 Cancellation by employer - loss and damage (clause 37)

F:..... V:.....
T:.....

Item

38 Cancellation by contractor - employer's default (clause 38)

F:..... V:.....
T:.....

Item

39 Cancellation - cessation of the works (clause 39)

F:..... V:.....
T:.....

Item

Carried to Collection

R

Section 1
Bill No. 1
PRELIMINARIES

	<u>Dispute (A40)</u>			
40	Dispute Settlement (clause 40) F:..... V:..... T:.....	Item		
	<u>Substitute Provisions (A41)</u>			
41	State clauses (Clause 41) F:..... V:..... T:..... Information necessary for the completion of those clauses contained in the schedule which are necessary for tender purposes is given hereunder <u>THE SCHEDULE</u> Information necessary for completion of those clauses contained in the schedule which are necessary for tender purposes is given hereunder	Item		
42	Pre-tender information (clause 42) F:..... V:..... T:.....	Item		
	<u>42.1 CONTRACTING AND OTHER PARTIES</u> 42.1.1 Employer: As per infomation on the tender data 42.1.2 Principal Agent: As per the infomation on the Tender data 42.1.3 Architect:			
	<div>Carried to Collection</div> <div>Section 1</div> <div>Bill No. 1</div> <div>PRELIMINARIES</div>		R	

42.1.4
Quantity Surveyor:

Structural :

42.1.5 Civil:

42.1.6
Electrical Engineer:

42.1.6
Mechanical Engineer:

42.2 CONTRACT DETAILS

42.2.1 Works Description: Construction of sanitation facilities

42.2.2 Site Description: as per the information on the tender data

42.2.3 Work or installations by direct contractors:

N/A

42.2.4 This agreement is for a government contract where there are specific options that are applicable to a **State** organ only

Yes

42.2.5 Date on which possession of the site is intended to be given:

UNKNOWN

Carried to Collection

Section 1
Bill No. 1
PRELIMINARIES

R

42.2.6 Period for the commencement of the works after the contractor takes posse

42.2.7 For the works **as a whole**. Intended date of practical completion and the penalty per calendar day

3 months after contractual commencement date *Date*

Penalty Amount
*The penalty shall be 7.5c per R100 per **calendar day** of the tendered amount (inclusive of value added tax)*

42.2.8 For the works in **sections**: Intended date of practical completion and the penalty per calendar day

Section 1

.N/A..... *Date*

R.N/A..... *Penalty Amount*

42.2.9 The **law** applicable to this **agreement** shall be that of

South Africa (country)

42.3 INSURANCES

42.3.1 Contract works insurance to be effected by:

Contractor:

For the Sum of R Contract Amount + 20.00 %

With a deductible of - to be determined by the contractor

42.3.2 Supplementary insurance is required

No

Carried to Collection

Section 1
Bill No. 1
PRELIMINARIES

R

42.3.3 Public liability insurance to be effected by:
Contractor:

For the Sum of R 2 500 000-00

With a deductible of - to be determined by the contractor

42.4 DOCUMENTS

42.4.1 Waivers of **contractors lien** or right of continuing possession is required

Yes

42.4.2 Number of construction document copies to be supplied to the **contractor** free of charge:

3 Number of

42.4.3 **Bills of Quantities/Lump sum document** schedule of rates drawn up in accordance with:

"Standard System of Measuring Builders' Work"

42.4.4 On acceptance of the tender the bills of quantities/lump sum document is to be submitted within **working days**

The priced bills of quantities must be handed in with the tender

42.4.5 JBCC Engineering General Conditions are to be included in the **contract documents**:

No

42.4.6 The contract value is to be adjusted using escalation adjustment indices

No

Where **JBCC CPAP** is to be used

Base Month **N/A**

42.4.7 Details of changes made to the provision of JBCC standard documentation:

SECTION B: PRELIMINARIES

Carried to Collection

Section 1
Bill No. 1
PRELIMINARIES

R

<u>Definitions and interpretation (B1)</u>				
43	Definition and interpretation (B1.1 - B1.4.6) F:..... V:..... T:.....	Item		
<u>Documents (B2)</u>				
44	Checking of documents (B2.1) F:..... V:..... T:.....	Item		
45	Provisional bills of quantities (B2.2) F:..... V:..... T:.....	N/A		
46	Availability of construction documentation (B2.3) F:..... V:..... T:.....	Item		
47	Interests of agents (B2.4) F:..... V:..... T:.....	Item		
48	Priced documents (B2.5) F:..... V:..... T:.....	Item		
49	Tender submission (B2.6) F:..... V:..... T:.....	Item		
Carried to Collection			R	
Section 1 Bill No. 1 PRELIMINARIES				

50 Defined works area (B3.1)

F:..... V:.....
T:.....

Item

The site (B3)

51 Geotechnical investigation (B3.2)

F:..... V:.....
T:.....

Item

52 Inspection of the site (B3.3)

F:..... V:.....
T:.....

Item

Existing premises occupied (B3.4)

F:..... V:.....
T:.....

Previous work - dimensional accuracy (B3.5)

F:..... V:.....
T:.....

Previous work - defects (B3.6)

F:..... V:.....
T:.....

53 Services - known (B3.7)

F:..... V:.....
T:.....

Item

Carried to Collection

R

Section 1
Bill No. 1
PRELIMINARIES

54	Services - unknown (B3.8)			
	F:..... V:..... T:.....	Item		
55	Protection of trees etc (B3.9)			
	F:..... V:..... T:.....	Item		
56	Articles of value (B3.10)			
	F:..... V:..... T:.....	Item		
	<u>Management of contract (B4)</u>			
57	Inspection of adjoining properties etc (B3.11)			
	F:..... V:..... T:.....	Item		
58	Management of the works (B4.1)			
	F:..... V:..... T:.....	Item		
59	Programme for the works (B4.2)			
	F:..... V:..... T:.....	Item		
60	Progress meetings (B4.3)			
	F:..... V:..... T:.....	Item		
61	Technical meetings (B4.4)			
	F:..... V:..... T:.....	Item		
	Carried to Collection		R	
	Section 1			
	Bill No. 1			
	PRELIMINARIES			

62 Labour and Plant records (B4.5)

F:..... V:.....
T:.....

Item

Samples, Shop Drawings and Manufacturer's Instructions (B5)

63 Samples of materials (B5.1)

F:..... V:.....
T:.....

Item

64 Workmanship samples (B5.2)

F:..... V:.....
T:.....

Item

65 Shop drawings (B5.3)

F:..... V:.....
T:.....

Item

66 Compliance with Manufacturer's Instructions (B5.4)

F:..... V:.....
T:.....

Item

Temporary works and plant (B6)

67 Deposits and fees (B6.1)

F:..... V:.....
T:.....

Item

68 Enclosure of the works (B6.2)

F:..... V:.....
T:.....

Item

Carried to Collection

R

Section 1
Bill No. 1
PRELIMINARIES

69	Advertising (B6.3)				
	F:..... V:..... T:.....	Item			
70	Plant, equipment, sheds and offices (B6.4)				
	F:..... V:..... T:.....	Item			
71	Main notice board (B6.5)				
	F:..... V:..... T:.....	Item			
72	Subcontractors' notice board (B6.6)				
	F:..... V:..... T:.....	N/A			
	<u>Temporary services (B7)</u>				
73	Location (B7.1)				
	F:..... V:..... T:.....	Item			
74	Water (B7.2)				
	Option [A] shall apply				
	F:..... V:..... T:.....	Item			
75	Electricity (B7.3)				
	Option [A] shall apply				
	F:..... V:..... T:.....	Item			
76	Telecommunication facilities (B7.4)				
	F:..... V:..... T:.....	Item			
	Carried to Collection				
	Section 1				
	Bill No. 1				
	PRELIMINARIES				

77 Ablution facilities (B7.5)
Option [A] shall apply

F:..... V:.....
T:.....

Item

Prime cost amounts (B8)

78 Responsibility for prime cost amounts (B8.1)

F:..... V:.....
T:.....

Item

Attendance on N/S Subcontractors (B9)

79 General attendance (B9.1)

F:..... V:.....
T:.....

Item

80 Special attendance (B9.2)

F:..... V:.....
T:.....

Item

81 Commissioning - Fuel, water and power (B9.3)

F:..... V:.....
T:.....

Item

Financial aspects (B10)

Statutory taxes, duties and levies (B10.1)

F:..... V:.....
T:.....

Item

82 Payment of preliminaries (B10.2)

Option [B] shall apply

F:..... V:.....
T:.....

Item

Carried to Collection

R

Section 1
Bill No. 1
PRELIMINARIES

83 Adjustment of preliminaries (B10.3)
Option [A] shall apply

F:..... V:.....
T:.....

Item

84 Payment certificate cash flow (B10.4)

F:..... V:.....
T:.....

Item

General (B11)

85 Protection of works (B11.1)

F:..... V:.....
T:.....

Item

86 Protection/isolation of existing/sectionally occupied works (B11.2)

F:..... V:.....
T:.....

Item

87 Security of the Works (B11.3)

F:..... V:.....
T:.....

Item

88 Notice before covering work (B11.4)

F:..... V:.....
T:.....

Item

89 Disturbance (B11.5)

F:..... V:.....
T:.....

Item

90 Environmental Disturbance (B11.6)

F:..... V:.....
T:.....

Item

Carried to Collection

R

Section 1
Bill No. 1
PRELIMINARIES

91	Works cleaning and clearing (B11.7) F:..... V:..... T:.....	Item		
92	Vermin (B11.8) F:..... V:..... T:.....	Item		
93	Overhand work (B11.9) F:..... V:..... T:.....	Item		
94	Instruction manuals and guarantees (B11.10) F:..... V:..... T:.....	Item		
95	As built information (B11.11) F:..... V:..... T:.....	Item		
96	Tenant Installations (B11.12) F:..... V:..... T:.....	Item		
	<u>Schedule of variables (B12)</u>			
97	Pre-tender information (B12.1) F:..... V:..... T:.....	Item		
	12.1.1 Provisional bills of quantities (B2.2) The quantities are provisional: <div style="text-align: right;">No</div>			
	12.1.2 Availability of construction documentation (B2.3) Construction documentation is not complete <div style="text-align: right;">No</div>			
	12.1.3 Interest of agents (B2.4)			
	Carried to Collection			
	Section 1 Bill No. 1 PRELIMINARIES		R	

[illegible]

[illegible]

SECTION C: SPECIFIC PRELIMINARIES

Any special items to meet the particular circumstances of a specific project are embodied in this section. Where required for an aspect of the works to be executed according to a design by a consulting engineer, a recital of the headings to the individual clauses of the JBCC Engineering General Conditions are included

98 Site instructions

Instructions issued on site are to be recorded in triplicate in a site instruction book which is to be maintained on site by the contractor

F: V:
T:

Item

99 Black economic empowerment and training

F: V:
T:

Item

100 Proprietary branded products

F: V:
T:

Item

101 Testing of flat roof waterproofing for watertightness

Flat roof waterproof areas shall be prepared with small sand dykes around them of a size and enclosing an area approved by the principal agent, flooded with water and kept "ponded" for at least 36 hours as a test to ensure the watertightness of the waterproofing and before any further construction work is carried out above the waterproofing

F: V: T:

Item

The contractor shall take delivery of, handle, store, use, apply and/or fix all proprietary branded products in strict accordance with the manufacturers' instructions after consultation with the manufacturer's authorised representative

Carried to Collection

R

Section 1
Bill No. 1
PRELIMINARIES

102	<p>Contract instructions</p> <p>F:..... V:..... T:.....</p> <p>Contract instructions issued on site are to be recorded in triplicate in a contract instruction book which is to be supplied and maintained on site by the contractor</p>	Item		
103	<p>Labour record</p> <p>F:..... V:..... T:.....</p> <p>At the end of each week the contractor shall provide the principal agent with a written record, in schedule form, reflecting the number and descriptions of tradesmen and labourers employed by him and all subcontractors on the works each day of that week</p>	Item		
104	<p>Plant record</p> <p>F:..... V:..... T:.....</p> <p>At the end of each week the contractor shall provide the principal agent with a written record, in schedule form, reflecting the number, type and capacity of all plant, excluding hand tools used on the works each day of that week</p>	Item		
105	<p>Guarantees</p> <p>F:..... V:..... T:.....</p>	Item		
<p style="text-align: right;">Carried to Collection</p> <p>Section 1 Bill No. 1 PRELIMINARIES</p>			R	

Where guarantees are called for, the contractor shall obtain a written guarantee, addressed to the employer, from the firm supplying the materials and/or doing the work and shall deliver same to the principal agent on the certified completion of the contract. The guarantee shall state that workmanship, materials and installation are guaranteed for a specified period from the date of certified completion of the contract, and that any defects that may arise during the specified period shall be made good at the expense of the firm supplying the materials and/or doing the work, upon written notice from the principal agent to do so. This guarantee will not be enforced if the work is damaged by defects in the construction of the building in which case the responsibility for replacement shall rest entirely with the contractor. The principal agent shall be the sole judge of the cause responsible for defects in the work and his decision shall be final and binding in terms of clause 40.2 of the agreement

106 Overtime

F:..... V:.....
T:.....

Item

Should overtime be required to be worked for any reason whatsoever, the costs of such overtime are to be borne by the contractor unless the principal agent has specifically authorised, in writing, prior to execution thereof, that costs for such overtime are to be borne by the employer

107 Co-operation of contractor for cost management

F:..... V:.....
T:.....

Item

Carried to Collection

R

Section 1
Bill No. 1
PRELIMINARIES

108	<p>It is specifically agreed that the contractor accepts the obligation of assisting the professional consultants in implementing proper cost management. The contractor will be advised by the principal agent of all cost management procedures which will be implemented to ensure that the final building cost does not exceed the budget. The quantity surveyor undertakes to make available to the contractor all budgetary allowances and cost assessments/reports to enable the proper procedures to be implemented and the contractor will attend all cost plan review and cost management meetings. The contractor undertakes to extend these procedures in regard to all subcontractors</p> <p>Occupational Health and Safety Specification</p> <p>F:..... V:..... T:.....</p> <p>Any Principal Contractor entering into a contract with The Developer must achieve an acceptable level of Occupational Health and Safety performance. Refer to "Project Specification" and "Safety, Health and Environmental Evaluation Questionnaire" The contractor to comply with all provisions of the above and to be enforced on all selected and or other sub-contractors, as no claim afterwards will be entertained</p> <p><u>SUMMARY OF CATEGORIES</u></p> <p>Category : Fixed R.....</p> <p>Category : Value R.....</p> <p>Category : Time R.....</p> <p>Carried to Collection</p> <p>Section 1 Bill No. 1 PRELIMINARIES</p>	Item		
-----	---	------	--	--

Section 1

Bill No. 1

PRELIMINARIES

COLLECTION

Total Brought Forward from Page No.

**Page
No**

Amount

1

2

3

4

5

6

7

8

9

10

11

12

13

14

15

16

17

18

19

20

Carried Forward

R

Section 1

Bill No. 1

PRELIMINARIES

Section 1

Bill No. 1

PRELIMINARIES

COLLECTION

Brought Forward

Total Brought Forward from Page No.

**Page
No**

Amount

R

21
22
23
24
25
26
27

Carried to Final Summary

R

Section 1
Bill No. 1
PRELIMINARIES

Item No	Quantity	Rate	Amount
<u>SECTION 2</u>			
<u>BILL No. 1</u>			
<u>ALTERATIONS</u>			
<u>MODEL PREAMBLES</u>			
The tenderer is referred to the "General Preambles for Trades 2017" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates.			
<u>SUPPLEMENTARY PREAMBLES</u>			
<u>View site</u>			
Before submitting his tender the tenderer shall visit the site and satisfy himself as to the nature and extent of the work to be done and the value of the materials contained in the buildings or portions of the buildings to be demolished. No claim for any variations of the contract sum in respect of the nature and extent of the work or of inferior or damaged materials will be entertained			
<u>Explosives</u>			
No explosives whatsoever may be used for demolition purposes unless otherwise stated.			
<u>General</u>			
Water supply pipes and other piping in ground that may be encountered and found necessary to disconnect or cut, shall be effectually stopped off or grubbed up and removed, and any new connections that may be necessary shall be made with proper fittings to the satisfaction of the principal agent.			
Unless otherwise described all materials are to become the property of the contractor and are to be removed from the site.			
Carried to Collection		R	
Section 2			
Bill No. 1			
Alterations			

Removal of asbestos material

All preparatory work, alterations, etc., to existing asbestos cement roof sheeting, gutters, rainwater pipes, etc., is to be carried out strictly by an approved and certified specialist company and in accordance with statutory requirements (Occupational Health and Safety Act, 1993 - Asbestos Regulations 2001) and all necessary precautions must be taken when working with and disposing of asbestos cement products and the disposal of waste water resulting from cleaning operations, etc.

The following shall apply in respect of asbestos removal

The removal of asbestos shall be carried out by a certified entity, registered in accordance with the Occupational Health and Safety Act, 1993 and the Asbestos Regulations 2001

Asbestos in all forms/building elements that is to be removed, shall be carried out in strict accordance with aforementioned regulation and a certificate issued by the entity as contemplated in the above, shall be provided per block for the removal thereof, where the term block shall in this context refer to any single, free standing building structure, regardless of size or purpose

Corresponding disposal certificates shall be issued by the facility at which the asbestos is disposed off, with said facility to, prior to the disposal of any asbestos material provide satisfactory proof that the facility is duly registered and fully compliant in terms of the act, to receive the asbestos material

Under no circumstances is the Contractor nor any of his duly authorised representatives to sell and/or give away asbestos material to any member/s of the school community, the community in general or the public at large. Should this be found to be occurring, the Contractor will be held responsible contractually and may further be prosecuted criminally

The cost for complying with the above, and all requirements of regulation as reflected above is to be priced for in terms for removal of asbestos material. No further claims in this regard will therefore be entertained

Carried to Collection

Section 2
Bill No. 1
Alterations

R

ALTERATIONS

1	Take out existing paving and set aside re-use.	m2	30
2	Re-lay existing paving	m2	30
3	Take out existing kerbs	m	20
4	Re-lay existing kerbs	m	20

Carried to Collection

R

Section 2
Bill No. 1
Alterations

Section 2

Bill No. 1

Alterations

COLLECTION

Total Brought Forward from Page No.

**Page
No**

Amount

30

31

32

Carried to Final Summary

R

Section 2
Bill No. 1
Alterations

Item No	Quantity	Rate	Amount
<u>SECTION No. 3</u>			
<u>BILL No. 1</u>			
<u>EXTERNAL WORKS (PROVISIONAL)</u>			
<u>MODEL PREAMBLES</u>			
The tenderer is referred to the "General Preambles for Trades 2017" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates.			
<u>THE FOLLOWING IN WALKWAYS</u>			
<u>Excavation not exceeding 2m deep</u>			
1	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	39
<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>			
2	Off site to a dumping site to be found by the Contractor.	m3	39
<u>Filling supplied by the contractor under walkways</u>			
3	G7 Base course material compacted to 98% Mod AASHTO density	m3	26
4	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	13
<u>Rip and Re - compact insitu material on site compacted to 93% Mod. AASHTO density:</u>			
5	Under floors,etc.	m2	87
Carried to Collection			R
Section 3			
Bill No. 1			
External Works			

	<u>Prescribed density tests on filling:</u>				
6	In-situ dry density test.	No	5		
	<u>Approved brand of anti-termite soil poison applied by a Registered Pest Control Company and guaranteed against termite infestation for ten years:</u>				
7	Treat filling under paving with 'Chlordane Heptachlor Aldrin' or equal approved.	m2	87		
	<u>Concrete Paving Blocks</u>				
	<u>Paving of 60mm thick 200x100mm 25MPa Bevel Bond paver blocks grey in colour in herringbone pattern on and including 20mm thick sand bed with dry filler sand swept and vibrated into joints all laid on subgrade (elsewhere measured) conforming to SABS 1200D degree of accuracy !:</u>				
8	Paving to walkway areas, etc laid to falls.	m2	87		
	<u>Kerbing</u>				
	<u>Precast or in situ mass concrete (25 MPa - 19 mm stone) kerbs cast in convenient lengths with exposed faces finished smooth from the mould and all salient angles rounded, jointed and pointed in 1:3 cement mortar, including excavations, formwork, etc.</u>				
9	Figure 8B (300 x 275 x 175mm) semi mountable kerb laid in lengths not exceeding 1000mm on a well rammed earth bottom or base course.	m	110		
10	Ditto but circular on plan.	m	10		
	<u>Welded balustrading to walkways</u>				
11	Horizontal welded balustrading 1000mm high of 70 x 70 x 2,5mm hollow section posts, at 1600mm centres, with 40 x 40 x 2,5mm hollow section top and bottom rails and 10mm diameter vertical uprights at 100mm centres	m	52		
12	Extra on last for closed end to 70 x 70mm posts	No	13		
13	150 x 150 x 6mm baseplate, four times holed and welded to soffit of posts	No	33		
	Carried to Collection			R	
	Section 3				
	Bill No. 1				
	External Works				

14	M16 x 100mm expansion bolt	No	130
	<u>CONCRETE CHUTES</u>		
	<u>Excavation not exceeding 2m deep</u>		
15	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	5
	<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>		
16	Off site to a dumping site to be found by the Contractor.	m3	5
	<u>Filling supplied by the contractor under channels</u>		
17	G7 Base course material compacted to 98% Mod AASHTO density	m3	2
18	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	3
	<u>Cast in-situ Ref 395 mesh reinforced concrete (25MPa) open stormwater channels having V-shaped waterway formed in top, finished smooth on all exposed surfaces in 3:1 cement plaster trowelled smooth and with angles rounded, cast in suitable lengths not exceeding 2m, including all formwork, moulds, shallow excavation, filling and ramming, laying to falls, bedding and pointing in 3:1 cement mortar. Concrete apron to be tinted, colour to be specified by the Engineer.</u>		
19	2000 x 150mm thick V' channel 150mm deep in centre laid in position in ground not exceeding 2000mm sections including all formwork, reinforcement, expansion joints, smooth finishing to top of concrete surface etc.	m	5
20	Extra for 2000mm angle	No	2
	Carried to Collection		
	Section 3 Bill No. 1 External Works		

21	Extra for forming 2000mm thick 700mm wide spreader with 200mm high edges fanning out to 3 000mm width at furthest end with hard burnt bricks pitching cast in ass diffusers including working off concrete to a smooth finish and draining onto natural ground with 150 - 200mm diameter loose stones.	No	1		
	<u>Sundries:</u>				
22	Create earth berm for stormwater control with in situ material 1,5m wide at base x 500mm high	m	122		
	<u>GABIONS</u>				
	<u>Gabions</u>				
	<u>Excavation in earth not exceeding 2m deep</u>				
23	Trenches	m3	284		
	<u>Risk of collapse of excavations</u>				
24	Sides of trench and hole excavations not exceeding 1,5m deep	m2	316		
	<u>FILLING ETC</u>				
	<u>Earth filling obtained from the excavations and/or prescribed stock piles on site compacted to 90% Mod AASHTO density</u>				
25	Backfilling to trenches, holes, etc	m3	79		
	<u>Filling with approved clean, hard, dry decomposed dolerite filling supplied and carted onto site by the Contractor, compacted to a density of at least 95% Mod. AASHTO maximum density:</u>				
26	Clean coarse sand with a fineness modulus of greater than 2,8	m3	47		
	<u>Gabions</u>				
Carried to Collection				R	
Section 3					
Bill No. 1					
External Works					

[illegible]

Section 3
Bill No. 1
External Works
COLLECTION

Total Brought Forward from Page No.

**Page
No** **Amount**

34
35
36
37
38

Carried to Final Summary

R

Section 3
Bill No. 1
External Works

[illegible]