

NKANGALA DISTRICT MUNICIPALITY



PROJECT NO: 185477 & 185478

SUPPLY, DELIVERY AND INSTALLATION OF ROOFSHELTER FOR MUNICIPAL HEALTH SERVICES OFFICES AT DR JS MOROKA AND THEMBISILE HANI LOCAL MUNICIPALITY WITHIN NKANGALA DISTRICT MUNICIPALITY

SCOPE OF WORK

Part C3: Scope of Work

C3 Scope of Work

NKANGALA DISTRICT MUNICIPALITY



PROJECT NO: 185477 & 185478

SUPPLY, DELIVERY AND INSTALLATION OF ROOFSHELTER FOR MUNICIPAL HEALTH SERVICES OFFICES AT DR JS MOROKA AND THEMBSILE HANI LOCAL MUNICIPALITY WITHIN NKANGALA DISTRICT MUNICIPALITY

The roof shelter is for MHS at Dr JS Moroka and Thembisile hani where there are MHS parkhome offices. The shelter shall be constructed of steel and IBR sheet that will cover the entire parkhome office.

The service provider must have CIDB grading 1GB, or higher.

- Chroma-dek IBR Roof sheeting, 0.5 mm thickness (colour green)
- 150 x 50 x 20 x 2 mm Lip channel – Outer steel frame
- 100 x 50 x 20 x 2 mm Lip channel – Inner frame
- 100 x 100 mm x 2mm Square tube columns which is concreted securely into the ground.
- Galvanized gutter with a downpipe.
- Quality primer to be used as an under coat to reduce the rust and metal fatigue rate.
- Quality metal final coat of a black colour paint.
- The standard height for a roof shelter must be 6 meter from the ground
- The measurement of shelter 23m (L) X 8m (W).
- The roof to be bolted on supporting beams
- The supporting steel frames to have concrete of 25MPa/19mm in a 600mm deep hole (400x600mm) for each beam.
- The bottom of each supporting beam must have flat steel welded and covering the bottom of each beam.