



MORETELE LOCAL MUNICIPALITY

CONTRACT NO.: MLM/IDS/WRYC/W16/23-24

FOR:

WATER RETICULATION AND YARD CONNECTIONS IN WARD 16: MORETELE LOCAL MUNICIPALITY – NORTH WEST PROVINCE

PROJECT DOCUMENT

TENDER DOCUMENT

THIS DOCUMENT IS COMPILED FOR:

MORETELE LOCAL MUNICIPALITY
PRIVATE BAG X367
MAKAPANSTAD
0404

Tel: +27 12 716 1300
Fax: +27 12 716 9999

TENDERER: _____

TENDER AMOUNT: _____

Prepared by:



Tshashu Consulting and Project Managers
The Village
Block C First Floor
Corner Oberon & Glenwood Roads
Pretoria, 0043
Tel: 012 348 1896
E-mail: admin@tsconsulting.co.za



**EXPANDED PUBLIC WORKS PROGRAMME
CONTRIBUTING TO A NATION AT WORK**

Contents

Number	Heading	Colour	Page
The Bid			
Part T1: Bidding procedures		<i>White & Pink</i>	
T1.1	Bid Notice and Invitation to Bid		3-4
T1.2	Bid Data		5-23
Part T2: Returnable documents		<i>Yellow</i>	
T2.1	List of Returnable Documents		24-25
T2.2	Returnable Schedules		25-64
The Contract			
Part C1: Agreement and Contract Data		<i>White</i>	
C1.1	Form of Offer and Acceptance		65-66
C1.2	Contract Data		67-86
C1.3	Form of Guarantee		87-88
C1.4	Occupational Health and Safety		89-91
Part C2: Special Conditions of Contract		<i>Orange</i>	
C2.1	Special Conditions of Contract		92-98
Part C3: Schedule of Quantities		<i>Yellow</i>	
C3.1	Preamble to Schedule of Quantities		99-118
C3.2	Schedule of Quantities		
Part C4: Scope of Work		<i>White</i>	
C4.1	Scope of work		119-120
C4.2	Drawing Descriptions		121
C4.3	Procurement		122
C4.4	Construction		123-126
C4.5	Management		127-129
Part C5: Project Specification		<i>Blue</i>	
C5.1	Project Specification		130-171
Part C6: OHS Specification for construction projects		<i>White</i>	
C6.1	Specification		172-183
Part C8: Site Information		<i>Green</i>	
C7.1	Site Information		184-185
Part C7: Drawings		<i>White</i>	
C8.1	Drawings		186-193



TENDER NOTICE AND INVITATION TO TENDER
MORETELE LOCAL MUNICIPALITY



MORETELE LOCAL MUNICIPALITY

T1.2 Bid Data

The conditions of Bid are the Standard Conditions of Bid as contained in Annex F of the CIDB Standard for Uniformity in Construction Procurement. (See www.cidb.org.za) which are reproduced without amendment or alteration for the convenience of Bidders as an Annex to this Bid Data

The Standard Conditions of Bid make several references to the Bid Data for details that apply specifically to this Bid. The Bid Data shall have precedence in the interpretation of any ambiguity or inconsistency between it and the standard conditions of Bid. Each item of data given below is cross-referenced to the clause in the Standard Conditions of Bid to which it mainly applies.

The additional conditions of Bid are:

Clause number	Bid Data
F.1.1	<p>The employer is: Name: Moretele Local Municipality Address: Private Bag x367, Makapanstad, 0404 Telephone: 012 716 1300 Fax: 012 716 9999</p>
F.1.2	<p>The Bid documents issued by the employer comprise:</p> <p>T1.1 Bid notice and invitation to Bid T1.2 Bid data T2.1 List of returnable documents T2.2 Returnable schedules</p> <p>Part 1: Agreements and contract data C1.1 Form of offer and acceptance C1.2 Contract data C1.3 Form of Guarantee C1.4 Occupational Health and Safety</p> <p>Part 2: Special Conditions of Contract C2.1 Special Conditions of Contract</p> <p>Part 3: Scope of work C3.1 Scope of work C3.2 Drawing Descriptions C3.3 Procurement C3.4 Construction C3.5 Management</p> <p>Part 4: Project Specification</p> <p>Part 5: Drawings</p> <p>Part 6: Site information</p> <p>Part 7: Schedule of Quantities C7.1 Preamble to Schedule of Quantities C7.2 Schedule of Quantities</p>

F.1.4	<p>The employer's agent is:</p> <p>Tshashu Consulting and Project Managers</p> <p>The Village</p> <p>Block C First Floor</p> <p>Corner Oberon & Glenwood Roads</p> <p>Pretoria,0043</p> <p>Tel: 012 348 1896</p> <p>Fax: 012 348 1896</p> <p>E-mail: admin@tsconsulting.co.za</p>
F.2.1	Only those Bidders who have in their employ management and supervisory staff satisfying the requirements of the Scope of Work for labour intensive competencies for supervisory and management staff are eligible to submit Bids.
F.2.1.1	Bidder must have at least a minimum of two (2) years' experience in related subject. Bidders are required to complete Schedule 3, Part 2 : Returnable with regard to similar work satisfactory out by the bidder.
F.2.1.2	<p>Only those Bidders who are registered with the CIDB, or are capable of being so prior to the evaluation of submissions, in a contractor grading designation equal to or higher than a contractor grading designation determined in accordance with the sum Bided for a 4 CEPE or higher class of construction work, are eligible to submit Bids.</p> <p>Joint ventures are eligible to submit Bids provided that:</p> <ol style="list-style-type: none"> 1. every member of the joint venture is registered with the CIDB; 2. the lead partner has a contractor grading designation in the 4 CEPE or higher class of construction work; and 3. the combined contractor grading designation calculated in accordance with the Construction Industry Development Regulations is equal to or higher than a contractor grading designation determined in accordance with the sum Bided for a 4 CEPE or higher class of construction work.
F.2.1	<p>The following Bidders who are registered with the CIDB, or are capable of being so registered prior to the evaluation of submissions, are eligible to submit Bids:</p> <ol style="list-style-type: none"> a) contractors who have a contractor grading designation equal to or higher than a contractor grading designation determined in accordance with the sum Bided for a 4 CEPE class of construction work; and b) contractors registered as potentially emerging enterprises with the CIDB who are registered in one contractor grading designation lower than that required in terms of a) above and who satisfy the following criteria: <ol style="list-style-type: none"> i) The Department, following an interview with the management of the enterprise, is satisfied that the enterprise has the potential to develop and qualify to be registered in a higher contractor grading designation; and ii) The Department, following a risk assessment, is able to provide the necessary supportive measures required to enable the enterprise to successfully execute the contract. <p>Joint ventures are eligible to submit Bids provided that:</p> <ol style="list-style-type: none"> 1. every member of the joint venture is registered with the CIDB; 2. the lead partner has a contractor grading designation in the 4 CEPE or higher class of construction work; and 3. the combined contractor grading designation calculated in accordance with the Construction Industry Development Regulations is equal to or higher than a contractor grading designation determined in accordance with the sum Bided for a 4 CEPE or higher class of construction work.
F2.2	In order to be considered for an appointment in terms of this bid, it will be beneficial if the bidder have an office in the Moretele Local Municipality area, through which all communication with the employer will flow, and where the majority of work in terms if this bid will be carried out. The address of the local office must be indicated on Schedule 1, Part T2: returnable documents and which will be regarded as the <i>domiciliumcitandi et executandi</i> for the purposes of any contract arising from this bid submission. The bidder must attach a certified copy of the certificate of incorporation and shareholders certificate of his/her company, close corporation or trust to Schedule 2, Part T2: Returnable document
F.2.3	The tenderer is required to complete his/ her tender in full using a black ink. The tenderer is required to initial all pages of the bid document. Failure to complete the form of offer in full is an automatic disqualification. Other contraventions also constitute an incomplete tender and may result in the bid being disqualified.

F.2.7	<p>The arrangements for a compulsory clarification meeting are as stated in the Bid Notice and Invitation to Bid.</p> <p>Bidders must sign the attendance list in the name of the Bidding entity. Addenda will be issued to and Bids will be received only from those Bidding entities appearing on the attendance list.</p>
F.2.11	Do not make any alterations or additions to the bid documents, except to comply with the instructions issued by employer, or necessary to correct errors made by the bidder. All signatories to the bid offer shall initial all alterations. Erasure and the use of masking fluid are prohibited.
F.2.12	<p>No alternative Bid offers will be considered</p> <p>If a Bidder wishes to submit an alternative Bid offer, the only criteria permitted for such alternative Bid offer is that it demonstrably satisfies the Employer's standards and requirements, the details of which may be obtained from the Employer's Agent.</p> <p>Calculations, drawings and all other pertinent technical information and characteristics as well as modified or proposed Pricing Data must be submitted with the alternative Bid offer to enable the Employer to evaluate the efficacy of the alternative and its principal elements, to take a view on the degree to which the alternative complies with the Employer's standards and requirements and to evaluate the acceptability of the pricing proposals. Calculations must be set out in a clear and logical sequence and must clearly reflect all design assumptions. Pricing Data must reflect all assumptions in the development of the pricing proposal.</p> <p>Acceptance of an alternative Bid offer will mean acceptance in principle of the offer. It will be an obligation of the contract for the Bidder, in the event that the alternative is accepted, to accept full responsibility and liability that the alternative offer complies in all respects with the Employer's standards and requirements.</p> <p>The modified Pricing Data must include an amount equal to 5% of the amount Bided for the alternative offer to cover the Employer's costs of confirming the acceptability of the detailed design before it is constructed.</p>
F.2.13.2	Return all returnable documents to the employer after completing them in their entirety, by hand in non-erasable black ink
F.2.13.3	Parts of each Bid offer communicated on paper shall be submitted as original, plus 2 copies.
F.2.13.5 F2.15.1	<p>The employer's address for delivery of Bid offers and identification details to be shown on each Bid offer package are:</p> <p>Location of Bid box: Tender Box</p> <p>Physical address: 4065B, Mathibestad</p> <p>Identification details: CONTRACT No.: WATER RETICULATION AND YARD CONNECTIONS IN WARD 16</p> <p>Postal address: Private Bag x367, Makapanstad, 0404</p>
F.2.13.6	A two-envelope procedure will not be followed.
F.2.15	The closing time for submission of Bid offers is as stated in the Bid Notice and Invitation to Bid.
F.2.15.1	Telephonic, telegraphic, telex, facsimile or e-mailed Bid offers will not be accepted.
F.2.16	The Bid offer validity period is 90 days; the municipality reserve the right to request an extension of the validity period if deemed necessary.
F.2.17	A bid may be rejected as non-responsive if the bidder fails to provide any clarification requested by the employer within the time for submission stated in the employer's written request.
F.2.18	The Bidder shall, when requested by the Employer to do so, submit the names of all management and supervisory staff that will be employed to supervise the labour-intensive portion of the works together with satisfactory evidence that such staff members satisfy the eligibility requirements.

F.2.19	Access shall be provided for inspections, tests and analysis.
F.2.23	The Bidder is required to submit with his Bid a Certificate of Contractor Registration issued by the Construction Industry Development Board and a copy of an original valid Tax Clearance Certificate issued by the South African Revenue Services. Where a Bidder satisfies CIDB contractor grading designation requirements through joint venture formation, such Bidders must submit the Certificates of Contractor Registration in respect of each partner.
F.3.4.1	Bids will be opened immediately after the closing time for Bids at Municipal Offices, at 4065B, Mathibestad.
	<p>The procedure for the evaluation of responsive Bids is Method 1</p> <p>The financial offer will be scored using Formula 2 (option 1) where the value of W_1 is:</p> <ol style="list-style-type: none"> 1) 90 where the financial value inclusive of VAT of all responsive Bids received have a value in excess of R 500 000; or 2) 80 where the financial value inclusive of VAT of one or more responsive Bid offers equals or is less than R 500 000. <p>Up to 100 minus W_1 Bid evaluation points will be awarded to Bidders who complete the preference schedule and who are found to be eligible for the preference claimed.</p>

F.3.11	<p>Evaluation of Bid offers</p> <p>Step 1 Bidders will firstly be evaluated on their responsiveness. This includes the following</p> <ol style="list-style-type: none"> 1. Municipal account for the business and directors not in arrears for more than 90 days or municipal account from private provider or statement of account from landlord with valid lease agreement. 2. Certified Company registration certificate 3. Valid CIDB Registration certificate 4. Original bid document and returnable must be duplicated into a disc or flash drive 5. Certified copy or Original certificate of BBBEE issued by SANAS/CIPC/Sworn Affidavit signed and stamped by commissioner of oath (For joint ventures the certificate must be consolidated) 6. Completed and signed Form of Offer and Acceptance 7. Certified I D Copies of Owners/Directors/Shareholders 8. All pages signed, initialled and completed 9. CSD summary report not older than one month 10. Authority for Signatory on company letter head 11. Letter of Good Standing with the Compensation for Occupational Injuries and Diseases 12. Proof of purchase of the tender document 13. Letter of intent from registered financial institution showing full details as guarantor in the amount of 10% as specified for surety purposes must be submitted 14. Joint venture (JV) agreement if applicable 15. Compulsory enterprise questionnaires (MBD Forms in the document) 16. Original compulsory briefing certificate 17. List of Returnable documents as listed T2.1 18. Addendum <p>NB. Failure to adhere to above conditions will lead to automatic disqualification.</p> <p>Step 2 According to the MFMA Circular No. 53 of the Municipal Finance Act No. 56 of 2003. Bidders will firstly be evaluated on Functionality. The minimum Score for functionality is 70%.</p> <p>Only the qualifying Tenderers will be evaluated on Method 2.</p> <p>The following is the criteria that the Bidders will be evaluated for Functionality:</p> <p>FUNCTIONALITY COMPETENCE ACHIEVEMENT SCHEDULES</p>																				
F.3.11.2	<p>Tenders will be evaluated using the following criteria</p> <table border="1" data-bbox="366 1477 1410 1956"> <thead> <tr> <th>Item no</th> <th>Criteria</th> <th>WEIGHTING</th> <th>Total Score</th> </tr> </thead> <tbody> <tr> <td>1.</td> <td>COMPANY EXPERIENCE</td> <td></td> <td></td> </tr> <tr> <td>1.1</td> <td>WATER PROJECTS (Tenderers to submit names with valid contact details and proof of appointment letters, referral letters and completion certificates (on completed projects) non-submission will result in loss of points.)</td> <td></td> <td></td> </tr> <tr> <td></td> <td>6 water projects with the value of 10 or more million (5 points each)</td> <td>30</td> <td></td> </tr> <tr> <td></td> <td>5 Water projects with the value of 10 or more million (5 points each)</td> <td>25</td> <td></td> </tr> </tbody> </table>	Item no	Criteria	WEIGHTING	Total Score	1.	COMPANY EXPERIENCE			1.1	WATER PROJECTS (Tenderers to submit names with valid contact details and proof of appointment letters, referral letters and completion certificates (on completed projects) non-submission will result in loss of points.)				6 water projects with the value of 10 or more million (5 points each)	30			5 Water projects with the value of 10 or more million (5 points each)	25	
Item no	Criteria	WEIGHTING	Total Score																		
1.	COMPANY EXPERIENCE																				
1.1	WATER PROJECTS (Tenderers to submit names with valid contact details and proof of appointment letters, referral letters and completion certificates (on completed projects) non-submission will result in loss of points.)																				
	6 water projects with the value of 10 or more million (5 points each)	30																			
	5 Water projects with the value of 10 or more million (5 points each)	25																			

	4 water projects with the value of 10 or more million (5 points each)	20		
	3 water projects with the value of 10 or more million (5 points each)	15		
	2 water projects with the value of 10 or more million (5 points each)	10		
	1 water projects with the value of 10 or more million (5 points each)	05		
	No project	0		
	CIVIL RELATED WORKS (Tenderers to submit names with valid contact details and proof of appointment letters, referral letters and completion certificates (on completed projects) non-submission will result in loss of points.)			
1.2	5 Civil related projects with the value of 10 or more million (2 points each)	10		
	4 Civil related projects with the value of 10 or more million (2 points each)	8		
	3 Civil related projects with the value of 10 or more million (2 points each)	6		
	2 Civil related projects with the value of 10 or more million (2 points each)	4		
	1 Civil related projects with the value of 10 or more million (2 points each)	2		
	No projects	0		
	N.B: TENDERERS TO SUBMIT NAMES COMPLETE WITH VALID CONTACT DETAILS AND PROOF (APPOINTMENT LETTERS, COMPLETION CERTIFICATE AND REFERRAL LETTERS), NON-SUBMISSION WILL RESULT IN LOSS OF POINTS.			
F.3.11.3	2. FINANCIAL REFERENCES			
	Tenderer submitted banking details, proof attached & bank rating of:			
2.1	Bank rating of "C" or better	5		
	Bank rating of "D"	3		
	Bank rating of "E"	2		
	Bank rating of "F" & below	1		
2.2	Audited Financial Statement	5		
	N.B: TENDERERS TO SUBMIT PROOF. NON-SUBMISSION WILL RESULT IN LOSS OF POINTS.			
F3.13.1	3. KEY PERSONNEL (Attach qualifications and CVs)			
	Project/Contract manager has B. Tech or higher in Civil Engineering and has 5 or more years of experience in civil related works	15		
3.1	Project/Contract manager has ND in Civil Engineering and has 5 or more years of experience in civil related works	10		
	Project/Contract manager has Certificate in Civil Engineering and has 5 or more years of experience in civil related works	5		

		Project/Contract manager has B. Tech, ND or Certificate in Civil Engineering and has less than 5 years of experience in civil related works	0		
		Site Agent has NQF Level 5/equivalent or higher and has 5 or more years of experience in civil related works	10		
		Site Agent has NQF Level 5/equivalent or higher and has 4 or less years of experience in civil related works	5		
		Site Agent has NQF Level 5/equivalent or higher and no experience in civil related works	2		
		Site Agent no qualification but years of experience in civil related works	0		
	3.3	Site Foreman has NQF level 2,3 or 4 and has 5 or more years of experience in civil related works	5		
		Site Foreman has NQF level 2,3 or 4 and has 4 or less years of experience in civil related works	3		
		Site Foreman has NQF level 2,3 or 4 and no experience in civil related works	2		
		Site Foreman no qualification but has 5 or more years of experience in civil related works	1		
		Site Foreman no qualification and no experience in civil related works	0		
		N.B: TENDERERS TO SUBMIT CURRICULUM VITAE & CERTIFICATES AND CERTIFIED COPIES OF QUALIFICATIONS. NON-SUBMISSION WILL RESULT IN LOSS OF POINTS.			
4.	PLANT AND EQUIPMENT (Attach vehicle/equipment ownership proof.)				
	Any 4 from the below list Excavator (5 points) TLB (5 points) Tipper trucks and 1 flatbed truck (5 points) Water tanker min 10000 l (5 points) 1 side bakkie (5 Points)	20			
	Any 3 from below list and letter to intent to hire Excavator (5 points) TLB (5 points) Tipper trucks and 1 flatbed truck (5 points) Water tanker min 10000 l (5 points) 1 side bakkie (5 Points)	15		20	
	Any 2 from below list and letter to intent to hire Excavator (5 points) TLB (5 points) Tipper trucks and 1 flatbed truck (5 points) Water tanker min 10000 l (5 points) 1 side bakkie (5 Points)	10			

	Any 1 from below list and letter to intent to hire Excavator (5 points) TLB (5 points) Tipper trucks and 1 flatbed truck (5 points) Water tanker min 10000 l (5 points) 1 side bakkie (5 Points)	5		
	Letter of intent to hire only	0		
		100	TOTAL	

N.B: TENDERERS TO SUBMIT VEHICLE/EQUIPMENT OWNERSHIP PROOF. TENDERERS TO SUBMIT CERTIFICATES & PROOF OF REGISTRATION FOR THE COURSE IN THE CASE I AND 3 AS MAY BE APPLICABLE. NON-SUBMISSION WILL RESULT IN LOSS OF POINTS.

N.B: BIDDERS MUST SCORE A MINIMUM OF 70 POINTS ON FUNCTIONALITY TO BE EVALUATED FURTHER ON 80/20 CRITERIA

Step 3

Price and BBBEE Contribution. Reduce each responsive Bid offer to a comparative offer and evaluate it using the Bid evaluation method that is indicated in the Bid Data and described below:

Method 2: Financial offer, and preferences	1) Score Bid evaluation points for financial offer.
	2) Confirm that Bidders are eligible for the preferences claimed, and if so, score Bid evaluation points for preferencing.
	3) Calculate total Bid evaluation points.
	4) Rank Bid offers from the highest number of Bid evaluation points to the lowest.
	5) Recommend Bidders with the highest number of Bid evaluation points for the award of the contract, unless there are compelling and justifiable reasons not to do so.

Score financial offers, preferences and quality, as relevant, to two decimal places.

Scoring Financial Offers

Score the financial offers of remaining responsive Bid offers using the following formula:

$$N_{FO} = W_1 \times A \text{ where:}$$

N_{FO} = the number of Bid evaluation points awarded for the financial offer.

W_1 = the maximum possible number of Bid evaluation points awarded for the financial offer as stated in the Bid Data.

A = a number calculated using either formulas 1 or 2 below as stated in the Bid Data.

Formula	Basis for comparison	Option 1	Option 2
1	Highest price or discount	$(1 + \frac{(P - P_m)}{P_m})$	P/P_m
2	Lowest price or percentage commission/fee	$(1 - \frac{(P - P_m)}{P_m})$	P_m/P

where:

P_m = the comparative offer of the most favourable Bid offer.

P = the comparative offer of Bid offer under consideration.

	<p>Scoring quality (functionality)</p> <p>Score quality in each of the categories stated in the Bid Data and calculate total score for quality.</p>
	<p>Bid offers will only be accepted if:</p> <ol style="list-style-type: none"> a) the Bidder has in his or her possession an original valid Tax Clearance Certificate issued by the South African Revenue Services or has made arrangements to meet outstanding tax obligations; b) the Bidder is registered with the Construction Industry Development Board in an appropriate contractor grading designation; c) the Bidder or any of its directors is not listed on the Register of Bid Defaulters in terms of the Prevention and Combating of Corrupt Activities Act of 2004 as a person prohibited from doing business with the public sector; d) the Bidder has not: <ul style="list-style-type: none"> i) abused the Employer's Supply Chain Management System; or ii) failed to perform on any previous contract and has been given a written notice to this effect; and e) Bidder has completed the Compulsory Enterprise Questionnaire and there are no conflicts of interest which may impact on the Bidder's ability to perform the contract in the best interests of the employer or potentially compromise the Bid process. f) the Bidder does not have arrears on municipal rates and levies exceeding 3 months.
	<p>If supply Chain Management bid adjudication committee, or the municipality manager, has resolved that a bid be accepted, the successful and unsuccessful bidders shall be notified in writing of this decision. Section 62 of the local municipality services Act 2000 (Act 32 of 2000) gives any person whose rights have been affected by such a decision, the rights to appeal such decision within 21 days of the notification of the decision.</p> <p>Any bidder wishing to exercise this right must submit their appeal to the Municipal manager, Private Bag x367, Makapanstad, 0404</p> <ul style="list-style-type: none"> • set out the reasons for the appeal • state in which way the appellant's rights have been affected by the decision of the supply Chain Management Bid Adjudication Committee or Municipal manager as applicable <p>Bidders are also hereby informed of their right to request reasons for the decision in terms of the Promotion of Administrative Justice Act (No 3 of 2000)</p> <p>The notification of decision sent to the bidder is not acceptance in terms of the form of offer and acceptance and no rights shall accrue to the successful bidder in terms of this notification.</p> <p>The consideration of appeals and if necessary, the invalidation of any decision made, shall be dealt with in terms of the Municipality's appeals process.</p>
F.3.18	The number of paper copies of the signed contract to be provided by the employer is one.
F.3.19	The tenderer must attach original or certified copies of BBEE certificate. In the event where tenderers entered into a JV agreement, they must submit original or certified (JV) combined BBEEE certificate
F.3.20	The tenderer must attach the proof of updated municipal rates and taxes. If the tenderer resides in a non-rateable municipal area, they must attach an affidavit for the company and its directors.

Annex: Standard Conditions of Tender

F.1 General

F.1.1 Actions

F.1.1.1 The employer and each tenderer submitting a tender offer shall comply with these conditions of tender. In their dealings with each other, they shall discharge their duties and obligations as set out in F.2 and F.3, timeously and with integrity, and behave equitably, honestly and transparently, comply with all legal obligations and not engage in anticompetitive practices.

F.1.1.2 The employer and the tenderer and all their agents and employees involved in the tender process shall avoid conflicts of interest and where a conflict of interest is perceived or known, declare any such conflict of interest, indicating the nature of such conflict. Tenderers shall declare any potential conflict of interest in their tender submissions. Employees, agents and advisors of the employer shall declare any conflict of interest to whoever is responsible for overseeing the procurement process at the start of any deliberations relating to the procurement process or as soon as they become aware of such conflict, and abstain from any decisions where such conflict exists or recuse themselves from the procurement process, as appropriate. Note: 1) A conflict of interest may arise due to a conflict of roles which might provide an incentive for improper acts in some circumstances. A conflict of interest can create an appearance of impropriety that can undermine confidence in the ability of that person to act properly in his or her position even if no improper acts result. 2) Conflicts of interest in respect of those engaged in the procurement process include direct, indirect or family interests in the tender or outcome of the procurement process and any personal bias, inclination, obligation, allegiance or loyalty which would in any way affect any decisions taken.

F.1.1.3 The employer shall not seek and a tenderer shall not submit a tender without having a firm intention and the capacity to proceed with the contract.

F.1.2 Tender Documents

The documents issued by the employer for the purpose of a tender offer are listed in the tender data.

F.1.3 Interpretation

F.1.3.1 The tender data and additional requirements contained in the tender schedules that are included in the returnable documents are deemed to be part of these conditions of tender.

F.1.3.2 These conditions of tender, the tender data and tender schedules which are only required for tender evaluation purposes, shall not form part of any contract arising from the invitation to tender.

F.1.3.3 For the purposes of these conditions of tender, the following definitions apply:

a) **Conflict of interest** means any situation in which:

- i) Someone in a position of trust has competing professional or personal interests which make it difficult to fulfil his or her duties impartially;
- ii) An individual or organisation is in a position to exploit a professional or official capacity in some way for their personal or corporate benefit; or
- iii) Incompatibility or contradictory interests exist between an employee and the organisation which employs that employee.

b) **Comparative offer** means the tenderer's financial offer after all tendered parameters that will affect the value of the financial offer have been taken into consideration in order to enable comparisons to be made between offers on a comparative basis.

c) **corrupt practice** means the offering, giving, receiving or soliciting of anything of value to influence the action of the employer or his staff or agents in the tender process; and

d) **Fraudulent practice** means the misrepresentation of the facts in order to influence the tender process or the award of a contract arising from a tender offer to the detriment of the employer, including collusive practices intended to establish prices at artificial levels

e) **Organization** means a company, firm, enterprise, association or other legal entity, whether incorporated or not, or a public body f) **Quality (functionality)** means the totality of features and characteristics of a product or service that bear on its ability to satisfy stated or implied needs

F.1.4 Communication and employer's agent

Each communication between the employer and a tenderer shall be to or from the employer's agent only, and in a form that can be readily read, copied and recorded. Communications shall be in the English language. The employer shall not take any responsibility for non-receipt of communications from or by a tenderer. The name and contact details of the employer's agent are stated in the tender data.

F.1.5 The employer's right to accept or reject any tender offer

F.1.5.1 The employer may accept or reject any variation, deviation, tender offer, or alternative tender offer, and may cancel the tender process and reject all tender offers at any time before the formation of a contract. The employer shall not accept or incur any liability to a tenderer for such cancellation and rejection, but will give written reasons for such action upon written request to do so.

F.1.5.2 The employer may not subsequent to the cancellation or abandonment of a tender process or the rejection of all responsive tender offers re-issue a tender covering substantially the same scope of work within a period of six months unless only one tender was received and such tender was returned unopened to the tenderer.

F.1.6 Procurement procedures

F.1.6.1 General

Unless otherwise stated in the tender data, a contract will, subject to F.3.13, be concluded with the tenderer who in terms of F.3.11 is the highest ranked or the tenderer scoring the highest number of tender evaluation points as relevant, based on the tender submissions that are received at the closing time for tenders.

F.1.6.2 Competitive negotiation procedure

F.1.6.2.1 Where the tender data require that the competitive negotiation procedure is to be followed, tenderers shall submit tender offers in response to the proposed contract in the first round of submissions. Notwithstanding the requirements of F.3.4, the employer shall announce only the names of the tenderers who make a submission. The requirements of F.3.8 relating to the material deviations or qualifications which affect the competitive position of tenderers shall not apply.

F.1.6.2.2 All responsive tenderers, or not less than three responsive tenderers that are highest ranked in terms of the evaluation method and evaluation criteria stated in the tender data, shall be invited in each round to enter into competitive negotiations, based on the principle of equal treatment and keeping confidential the proposed solutions and associated information. Notwithstanding the provisions of F.2.17, the employer may request that tenders be clarified, specified and fine-tuned in order to improve a tenderer's competitive position provided that such clarification, specification, fine-tuning or additional information does not alter any fundamental aspects of the offers or impose substantial new requirements which restrict or distort competition or have a discriminatory effect.

F.1.6.2.3 At the conclusion of each round of negotiations, tenderers shall be invited by the employer to make afresh tender offer, based on the same evaluation criteria, with or without adjusted weightings. Tenderers shall be advised when they are to submit their best and final offer.

F.1.6.2.4 The contract shall be awarded in accordance with the provisions of F.3.11 and F.3.13 after tenderers have been requested to submit their best and final offer.

F.1.6.3 Proposal procedure using the two stage-system

F.1.6.3.1 Option 1

Tenderers shall in the first stage submit technical proposals and, if required, cost parameters around which a contract may be negotiated. The employer shall evaluate each responsive submission in terms of the method of evaluation stated in the tender data, and in the second stage negotiate a contract with the tenderer scoring the highest number of evaluation points and award the contract in terms of these conditions of tender.

F.1.6.3.2 Option 2

F.1.6.3.2.1 Tenderers shall submit in the first stage only technical proposals. The employer shall invite all responsive tenderers to submit tender offers in the second stage, following the issuing of procurement documents.

F.1.6.3.2.2 The employer shall evaluate tenders received during the second stage in terms of the method of evaluation stated in the tender data, and award the contract in terms of these conditions of tender.

F.2 Tenderer's obligations

F.2.1 Eligibility

F.2.1.1 Submit a tender offer only if the tenderer satisfies the criteria stated in the tender data and the tenderer, or any of his principals, is not under any restriction to do business with employer.

F.2.1.2 Notify the employer of any proposed material change in the capabilities or formation of the tendering entity (or both) or any other criteria which formed part of the qualifying requirements used by the employer as the basis in a prior process to invite the tenderer to submit a tender offer and obtain the employer's written approval to do so prior to the closing time for tenders.

F.2.2 Cost of tendering

Accept that, unless otherwise stated in the tender data, the employer will not compensate the tenderer for any costs incurred in the preparation and submission of a tender offer, including the costs of any testing necessary to demonstrate that aspects of the offer comply with requirements.

F.2.3 Check documents

Check the tender documents on receipt for completeness and notify the employer of any discrepancy or omission.

F.2.4 Confidentiality and copyright of documents

Treat as confidential all matters arising in connection with the tender. Use and copy the documents issued by the employer only for the purpose of preparing and submitting a tender offer in response to the invitation.

F.2.5 Reference documents

Obtain, as necessary for submitting a tender offer, copies of the latest versions of standards, specifications, conditions of contract and other publications, which are not attached but which are incorporated into the tender documents by reference.

F.2.6 Acknowledge addenda

Acknowledge receipt of addenda to the tender documents, which the employer may issue, and if necessary, apply for an extension to the closing time stated in the tender data, in order to take the addenda into account.

F.2.7 Clarification meeting

Attend, where required, a clarification meeting at which tenderers may familiarize themselves with aspects of the proposed work, services or supply and raise questions. Details of the meeting(s) are stated in the tender data.

F.2.8 Seek clarification

Request clarification of the tender documents, if necessary, by notifying the employer at least five working days before the closing time stated in the tender data.

F.2.9 Insurance

Be aware that the extent of insurance to be provided by the employer (if any) might not be for the full cover required in terms of the conditions of contract identified in the contract data. The tenderer is advised to seek qualified advice regarding insurance.

F.2.10 pricing the tender offer

F.2.10.1 Include in the rates, prices, and the tendered total of the prices (if any) all duties, taxes (except Value-added Tax (VAT), and other levies payable by the successful tenderer, such duties, taxes and levies being those applicable 14 days before the closing time stated in the tender data.

F.2.10.2 Show VAT payable by the employer separately as an addition to the tendered total of the prices.

F.2.10.3 Provide rates and prices that are fixed for the duration of the contract and not subject to adjustment except as provided for in the conditions of contract identified in the contract data.

F.2.10.4 State the rates and prices in Rand unless instructed otherwise in the tender data. The conditions of contract identified in the contract data may provide for part payment in other currencies.

F.2.11 Alterations to documents

Do not make any alterations or additions to the tender documents, except to comply with instructions issued by the employer, or necessary to correct errors made by the tenderer. All signatories to the tender offer shall initial all such alterations. Erasures and the use of masking fluid are prohibited.

F.2.12 Alternative tender offers

F.2.12.1 Unless otherwise stated in the tender data, submit alternative tender offers only if a main tender offer, strictly in accordance with all the requirements of the tender documents, is also submitted as well as a schedule that compares the requirements of the tender documents with the alternative requirements that are proposed.

F.2.12.2 Accept that an alternative tender offer may be based only on the criteria stated in the tender data or criteria otherwise acceptable to the employer.

F.2.13 submitting a tender offer

F.2.13.1 Submit one tender offer only, either as a single tendering entity or as a member in a joint venture to provide the whole of the works, services or supply identified in the contract data and described in the scope of works, unless stated otherwise in the tender data.

F.2.13.2 Return all returnable documents to the employer after completing them in their entirety, either electronically (if they were issued in electronic format) or by writing legibly in non-erasable ink.

F.2.13.3 Submit the parts of the tender offer communicated on paper as an original plus the number of copies stated in the tender data, with an English translation of any documentation in a language other than English, and the parts communicated electronically in the same format as they were issued by the employer.

F.2.13.4 Sign the original and all copies of the tender offer where required in terms of the tender data. The employer will hold all authorized signatories liable on behalf of the tenderer. Signatories for tenderers proposing to contract as joint ventures shall state, which of the signatories is the lead partner whom the employer shall hold liable for the purpose of the tender offer

F.2.13.5 Seal the original and each copy of the tender offer as separate packages marking the packages as "ORIGINAL" and "COPY". Each package shall state on the outside the employer's address and identification details stated in the tender data, as well as the tenderer's name and contact address.

F.2.13.6 Where a two-envelope system is required in terms of the tender data, place and seal the returnable documents listed in the tender data in an envelope marked "financial proposal" and place the remaining returnable documents in an envelope marked "technical proposal". Each envelope shall state on the outside the employer's address and identification details stated in the tender data, as well as the tenderer's name and contact address.

F.2.13.7 Seal the original tender offer and copy packages together in an outer package that states on the outside only the employer's address and identification details as stated in the tender data.

F.2.13.8 Accept that the employer will not assume any responsibility for the misplacement or premature opening of the tender offer if the outer package is not sealed and marked as stated.

F.2.13.9 Accept that tender offers submitted by facsimile or e-mail will be rejected by the employer, unless stated otherwise in the tender data.

F.2.14 Information and data to be completed in all respects

Accept that tender offers, which do not provide all the data or information requested completely and in the required, may be regarded by the employer as non-responsive.

F.2.15 Closing time

F.2.15.1 Ensure that the employer receives the tender offer at the address specified in the tender data not later than the closing time stated in the tender data. Accept that proof of posting shall not be accepted as proof of delivery.

F.2.15.2 Accept that, if the employer extends the closing time stated in the tender data for any reason, the requirements of these conditions of tender apply equally to the extended deadline.

F.2.16 Tender offer validity

F.2.16.1 Hold the tender offer(s) valid for acceptance by the employer at any time during the validity period stated in the tender data after the closing time stated in the tender data.

F.2.16.2 If requested by the employer, consider extending the validity period stated in the tender data for an agreed additional period with or without any conditions attached to such extension.

F.2.16.3 Accept that a tender submission that has been submitted to the employer may only be withdrawn or substituted by giving the employer's agent written notice before the closing time for tenders that a tender is to be withdrawn or substituted.

F.2.16.4 Where a tender submission is to be substituted, submit a substitute tender in accordance with the requirements of F.2.13 with the packages clearly marked as "SUBSTITUTE".

F.2.17 Clarification of tender offer after submission

Provide clarification of a tender offer in response to a request to do so from the employer during the evaluation of tender offers. This may include providing a breakdown of rates or prices and correction of arithmetical errors by the adjustment of certain rates or item prices (or both). No change in the competitive position of tenderers or substance of the tender offer is sought, offered, or permitted.

Note: Sub-clause F.2.17 does not preclude the negotiation of the final terms of the contract with a preferred tenderer following a competitive selection process, should the Employer elect to do so.

F.2.18 Provide other material

F.2.18.1 Provide, on request by the employer, any other material that has a bearing on the tender offer, the tenderer's commercial position (including notarized joint venture agreements), referencing arrangements, or samples of materials, considered necessary by the employer for the purpose of a full and fair risk assessment. Should the tenderer not provide the material, or a satisfactory reason as to why it cannot be provided, by the time for submission stated in the employer's request, the employer may regard the tender offer as non-responsive.

F.2.18.2 Dispose of samples of materials provided for evaluation by the employer, where required.

F.2.19 Inspections, tests and analysis

Provide access during working hours to premises for inspections, tests and analysis as provided for in the tender data.

F.2.20 Submit securities, bonds, policies, etc

If requested, submit for the employer's acceptance before formation of the contract, all securities, bonds, guarantees, policies and certificates of insurance required in terms of the conditions of contract identified in the contract data.

F.2.21 Check final draft

Check the final draft of the contract provided by the employer within the time available for the employer to issue the contract.

F.2.22 Return of other tender documents

If so instructed by the employer, return all retained tender documents within 28 days after the expiry of the validity period stated in the tender data.

F.2.23 Certificates

Include in the tender submission or provide the employer with any certificates as stated in the tender data.

F.3 The employer's undertakings**F.3.1 Respond to requests from the tenderer**

F.3.1.1 Unless otherwise stated in the tender Data respond to a request for clarification received up to five working days before the tender closing time stated in the Tender Data and notify all tenderers who drew procurement documents.

F.3.1.2 Consider any request to make a material change in the capabilities or formation of the tendering entity (or both) or any other criteria which formed part of the qualifying requirements used to prequalify a tenderer to submit a tender offer in terms of a previous procurement process and deny any such request if as a consequence:

- a) An individual firm, or a joint venture as a whole, or any individual member of the joint venture fails to meet any of the collective or individual qualifying requirements;
- b) The new partners to a joint venture were not prequalified in the first instance, either as individual firms or as another joint venture; or
- c) In the opinion of the Employer, acceptance of the material change would compromise the outcome of the prequalification process.

F.3.2 Issue Addenda

If necessary, issue addenda that may amend or amplify the tender documents to each tenderer during the period from the date that tender documents are available until three days before the tender closing time stated in the Tender Data. If, as a result a tenderer applies for an extension to the closing time stated in the Tender Data, the Employer may grant such extension and, shall then notify all tenderers who drew documents.

F.3.3 Return late tender offers

Return tender offers received after the closing time stated in the Tender Data, unopened, (unless it is necessary to open a tender submission to obtain a forwarding address), to the tenderer concerned.

F.3.4 Opening of tender submissions

F.3.4.1 Unless the two-envelope system is to be followed, open valid tender submissions in the presence of tenderers' agents who choose to attend at the time and place stated in the tender data. Tender submissions for which acceptable reasons for withdrawal have been submitted will not be opened.

F.3.4.2 Announce at the meeting held immediately after the opening of tender submissions, at a venue indicated in the tender data, the name of each tenderer whose tender offer is opened and, where applicable, the total of his prices, preferences claimed and time for completion for the main tender offer only.

F.3.4.3 Make available the record outlined in F.3.4.2 to all interested persons upon request.

F.3.5 Two-envelope system

F.3.5.1 Where stated in the tender data that a two-envelope system is to be followed, open only the technical proposal of valid tenders in the presence of tenderers' agents who choose to attend at the time and place stated in the tender data and announce the name of each tenderer whose technical proposal is opened.

F.3.5.2 Evaluate the quality of the technical proposals offered by tenderers, then advise tenderers who remain in contention for the award of the contract of the time and place when the financial proposals will be opened. Open only the financial proposals of tenderers, who score in the quality evaluation more than the minimum number of points for quality stated in the tender data, and announce the score obtained for the technical proposals and the total price and any preferences claimed. Return unopened financial proposals to tenderers whose technical proposals failed to achieve the minimum number of points for quality.

F.3.6 Non-disclosure

Not disclose to tenderers, or to any other person not officially concerned with such processes, information relating to the evaluation and comparison of tender offers, the final evaluation price and recommendations for the award of a contract, until after the award of the contract to the successful tenderer.

F.3.7 Grounds for rejection and disqualification

Determine whether there has been any effort by a tenderer to influence the processing of tender offers and instantly disqualify a tenderer (and his tender offer) if it is established that he engaged in corrupt or fraudulent practices.

F.3.8 Test for responsiveness

F.3.8.1 Determine, after opening and before detailed evaluation, whether each tender offer properly received:

- a) complies with the requirements of these Conditions of Tender,
- b) Has been properly and fully completed and signed, and
- c) is responsive to the other requirements of the tender documents.

F.3.8.2 A responsive tender is one that conforms to all the terms, conditions, and specifications of the tender documents without material deviation or qualification. A material deviation or qualification is one which, in the Employer's opinion, would:

- a) Detrimentally affect the scope, quality, or performance of the works, services or supply identified in the Scope of Work,
- b) Significantly change the Employer's or the tenderer's risks and responsibilities under the contract, or
- c) Affect the competitive position of other tenderers presenting responsive tenders, if it were to be rectified. Reject a non-responsive tender offer, and not allow it to be subsequently made responsive by correction or withdrawal of the non-conforming deviation or reservation.

F.3.9 Arithmetical errors, omissions and discrepancies

F.3.9.1 Check responsive tenders for discrepancies between amounts in words and amounts in figures. Where there is a discrepancy between the amounts in figures and the amount in words, the amount in words shall govern.

F.3.9.2 Check the highest ranked tender or tenderer with the highest number of tender evaluation points after the evaluation of tender offers in accordance with F.3.11 for:

- a) The gross misplacement of the decimal point in any unit rate;
- b) Omissions made in completing the pricing schedule or bills of quantities; or
- c) Arithmetic errors in:
 - i) Line-item totals resulting from the product of a unit rate and a quantity in bills of quantities or schedules of prices; or
 - ii) The summation of the prices.

F.3.9.3 Notify the tenderer of all errors or omissions that are identified in the tender offer and either confirm the tender offer as tendered or accept the corrected total of prices.

F.3.9.4 Where the tenderer elects to confirm the tender offer as tendered, correct the errors as follows:

- a) If bills of quantities or pricing schedules apply and there is an error in the line-item total resulting from the product of the unit rate and the quantity, the line-item total shall govern and the rate shall be corrected. Where there is an obviously gross misplacement of the decimal point in the unit rate, the line-item total as quoted shall govern, and the unit rate shall be corrected.
- b) Where there is an error in the total of the prices either as a result of other corrections required by this checking process or in the tenderer's addition of prices, the total of the prices shall govern and the tenderer will be asked to revise selected item prices (and their rates if bills of quantities apply) to achieve the tendered total of the prices.

F.3.10 Clarification of a tender offer

Obtain clarification from a tenderer on any matter that could give rise to ambiguity in a contract arising from the tender offer.

F.3.11 Evaluation of tender offers

F.3.11.1 General

Appoint an evaluation panel of not less than three persons. Reduce each responsive tender offer to a comparative offer and evaluate them using the tender evaluation methods and associated evaluation criteria and weightings that are specified in the tender data.

F.3.11.2 Method 1: Financial offer

In the case of a financial offer:

- a) Rank tender offers from the most favourable to the least favourable comparative offer.
- b) Recommend the highest ranked tenderer for the award of the contract, unless there are compelling and justifiable reasons not to do so.
- c) Re-rank all tenderers should there be compelling and justifiable reasons not to recommend the highest ranked tenderer and recommend the highest ranked tenderer, unless there are compelling and justifiable reasons not to do so and the process set out in this sub clause is repeated.

F.3.11.3 Methods 2: Financial offer and preference

In the case of a financial offer and preferences:

- a) Score each tender in respect of the financial offer made and preferences claimed, if any, in accordance with the provisions of F.3.11.7 and F.3.11.8.
- b) Calculate the total number of tender evaluation points (TEV) in accordance with the following formula:

$$TEV = NFO + NP$$

Where: NFO is the number of tender evaluation points awarded for the financial offer made in accordance with F.3.11.7;

NP is the number of tender evaluation points awarded for preferences claimed in accordance with F.3.11.8.

- c) Rank tender offers from the highest number of tender evaluation points to the lowest.
- d) Recommend the tenderer with the highest number of tender evaluation points for the award of the contract, unless there are compelling and justifiable reasons not to do so.
- e) Rescore and re-rank all tenderers should there be compelling and justifiable reasons not to recommend the tenderer with the highest number of tender evaluation points, and recommend the tenderer with the highest number of tender evaluation points, unless there are compelling and justifiable reasons not to do so and the process set out in this sub clause is repeated

F.3.11.4 Method 3: Financial offer and quality

In the case of a financial offer and quality:

- a) Score each tender in respect of the financial offer made and the quality offered in accordance with the provisions of F.3.11.7 and F.3.11.9, rejecting all tender offers that fail to score the minimum number of points for quality stated in the tender data, if any.
- b) Calculate the total number of tender evaluation points (TEV) in accordance with the following formula:

$$TEV = NFO + NQ$$

Where: NFO is the number of tender evaluation points awarded for the financial offer made in accordance with F.3.11.7;

NQ is the number of tender evaluation points awarded for quality offered in accordance with F.3.11.9.

- c) Rank tender offers from the highest number of tender evaluation points to the lowest.
- d) Recommend tenderer with the highest number of tender evaluation points for the award of the contract, unless there are compelling and justifiable reasons not to do so.

e) Rescore and re-rank all tenderers should there be compelling and justifiable reasons not to recommend the tenderer with the highest number of tender evaluation points and recommend the tenderer with the highest number of tender evaluation points, unless there are compelling and justifiable reasons not to do so and the process set out in this sub clause is repeated.

F.3.11.5 Method 4: Financial offer, quality and preferences

In the case of a financial offer, quality and preferences:

a) Score each tender in respect of the financial offer made, preference claimed, if any, and the quality offered in accordance with the provisions of F.3.11.7 to F.3.11.9, rejecting all tender offers that fail to score the minimum number of points for quality stated in the tender data, if any.

b) Calculate the total number of tender evaluation points (TEV) in accordance with the following formula, unless otherwise stated in the Tender Data:

$$TEV = NFO + NP + NQ$$

Where: NFO is the number of tender evaluation points awarded for the financial offer made in accordance with F.3.11.7;

NP is the number of tender evaluation points awarded for preferences claimed in accordance with F.3.11.8.

NQ is the number of tender evaluation points awarded for quality offered in accordance with F.3.11.9.

c) Rank tender offers from the highest number of tender evaluation points to the lowest.

d) Recommend the tenderer with the highest number of tender evaluation points for the award of the contract, unless there are compelling and justifiable reasons not to do so.

e) Rescore and re-rank all tenderers should there be compelling and justifiable reasons not to recommend the tenderer with the highest number of tender evaluation points and recommend the tenderer with the highest number of tender evaluation points, unless there are compelling and justifiable reasons not to do so and the process set out in this sub clause is repeated.

F.3.11.6 Decimal places

Score price, preference and functionality, as relevant, to two decimal places.

F.3.11.7 Scoring Price

Score price of remaining responsive Bid offers using the following formula:

$$NFO = W_1 \times A$$

Where:

NFO = the number of Bid evaluation points awarded for price.

W₁ = the maximum possible number of Bid evaluation points awarded for price as stated in the Bid Data.

A = a number calculated using the formula and option described in Table F.1 as stated in the tender data.

Table F.1: formulae for calculating the value of A

Formula	Basis for comparison	Option 1	Option 2
1	Highest price or discount	$A = (1 + \frac{(P - P_m)}{P_m})$	$A = P/P_m$
2	Lowest price or percentage commission/fee	$A = (1 - \frac{(P - P_m)}{P_m})$	$A = P_m/P$
P _m is the comparative offer of the most favourable comparative offer. P is the comparative offer of the Bid offer under consideration.			

F.3.11.8 Scoring Preferences

Confirm that tenderers are eligible for the preferences claimed in accordance with provisions of the tender data and reject all claims for preferences where tenderers are not eligible for such preferences.

Calculate the total number of tender evaluation points for preferences claimed in accordance with provisions of the tender data.

F.3.11.9 Scoring Preferences

Score each of the criteria and sub criteria for quality in accordance with the provisions of the tender data. Calculate the total number of tender evaluation points for quality using the following formula:

$$N_{QO} = W_2 \times S_0 / M_S$$

Where

S_0 is the score for quality allocated to the submission under consideration

M_S is the maximum possible score for quality in respect of a submission; and

W_2 is the maximum possible number of tender evaluation points awarded for the quality as stated in the tender data.

F.3.12 Insurance provided by the employer

If requested by the proposed successful Bidder, submit for the Bidder's information the policies and / or certificates of insurance which the conditions of contract identified in the contract data, require the employer to provide.

F.3.13 Acceptance of Bid offer

F.3.13.1 Accept Bid offer only if the Bidder satisfies the legal requirements stated in the Bid Data.

F.3.13.2 Notify the successful Bidder of the employer's acceptance of his Bid offer by completing and returning one copy of the form of offer and acceptance before the expiry of the validity period stated in the Bid data, or agreed additional period. Providing the form of offer and acceptance does not contain any qualifying statements, it will constitute the formation of a contract between the employer and the successful Bidder as described in the form of offer and acceptance.

F.3.14 Notice to unsuccessful Bidders

Successful bidders will be on the website.

F.3.15. Prepare contract documents

If necessary, revise documents that shall form part of the contract and that were issued by the employer as part of the Bid documents to take account of:

- a) Addenda issued during the Bid period,
- b) Inclusion of some of the returnable documents,
- c) Other revisions agreed between the employer and the successful Bidder, and
- d) The schedule of deviations attached to the form of offer and acceptance, if any.

F.3.16 Issue final contract

Prepare and issue the final draft of contract documents to the successful Bidder for acceptance as soon as possible after the date of the employer's signing of the form of offer and acceptance (including the schedule of deviations, if any). Only those documents that the conditions of Bid require the Bidder to submit, after acceptance by the employer, shall be included.

F.3.17 Complete adjudicator's contract

Unless alternative arrangements have been agreed or otherwise provided for in the contract, arrange for both parties to complete formalities for appointing the selected adjudicator at the same time as the main contract is signed.

F.3.18 Provide copies of the contracts

Provide to the successful Bidder the number of copies stated in the Bid Data of the signed copy of the contract as soon as possible after completion and signing of the form of offer and acceptance.



MORETELE LOCAL MUNICIPALITY

T2.1 List of Returnable Documents

The Bidder must complete the following returnable documents:

1 Documents required for tender responsiveness (Mandatory)

- Municipal account for the business and directors not in arrears for more than 90 days or municipal account from private provider or statement of account from landlord with valid lease agreement.
- Certified Company registration certificate
- Valid CIDB Registration certificate
- Original bid document and returnable must be duplicated into a disc or flash drive
- Certified copy or Original certificate of BBBEE issued by SANAS/CIPC/Sworn Affidavit signed and stamped by commissioner of oath (For joint ventures the certificate must be consolidated)
- Completed and signed Form of Offer and Acceptance
- Certified I D Copies of Owners/Directors/Shareholders
- All pages signed, initialled and completed
- CSD summary report not older than one month
- Authority for Signatory on company letter head
- Letter of Good Standing with the Compensation for Occupational Injuries and Diseases
- Proof of purchase of the tender document
- Letter of intent from registered financial institution showing full details as guarantor in the amount of 10% as specified for surety purposes must be submitted
- Joint venture (JV) agreement if applicable
- Compulsory enterprise questionnaires (MBD Forms in the document)
- Original compulsory briefing certificate
- List of Returnable documents as listed T2.1
- Addendum

N.B: Failure to adhere to above conditions will lead to automatic disqualification.

2 Returnable Schedules that will be required for bid evaluation purpose

- Certificate of Contractor Registration issued by the Construction Industry Development Board **4 CEPE**
- MBD 1: Invitation to Bid
- MBD 3.1: Pricing Schedule – Firm Prices
- MBD 3.2: Pricing Schedule – Non-Firm prices
- MBD 4: Declaration of interest
- MBD 5: Declaration for Procurement above R10 Million (All applicable taxes included)
- MBD 6.1: Preference Points Claim Form In Terms Of The Preferential Procurement Regulations 2001
- MBD 7.2: Contract Form – Rendering of services
- MBD 8: Declaration of Bidder's Past Supply Chain Management Practices
- MBD 9: Certificate of Independent Bid Determination

3 Other Returnable Schedules required for tender evaluation purposes (included hereafter for completion)

- Declaration affidavit
- Proposed amendments and qualifications

- Proposed nominated Subcontractors
- Plant and Equipment
- Schedule of work satisfactorily carried out by tenderer
- Personnel Schedule
- Declaration regarding fulfillment of construction regulations, 2003
- Estimated monthly cashflow
- Preliminary
- Financial rating
- Latest audited financial statements
- Preliminary Health and Safety Plan

4 Returnable Schedules that will be incorporated into the contract (to be attached with submission)

- Record of Addenda
- Amendments and qualifications
- Form of Offer and Acceptance*
- Contract Data
- Form of guarantee
- Occupational Health and Safety Agreement
- Daywork Schedule
- Schedule of Price

5 Form of Offer

6 C1.2 Contract Data (Part 2)

7 C6.2 Bills of quantities

Record of Addenda to Bid documents

We confirm that the following communications received from the Employer before the submission of this Bid offer, amending the Bid documents, have been taken into account in this Bid offer:

	Date	Title or Details
1.		
2.		
3.		
4.		
5.		
6.		
7.		
8.		

Attach additional pages if more space is required.

Signed		Date	
Name		Position	
Bidder			

EXAMPLE FOR USE BY THE TENDERER WHEN COMPILING THE AUTHORITY CERTIFICATE

Certificate of Authority for Power of Attorney (TO BE PRINTED ON COMPANY'S LETTER HEAD)

Indicate the status of the tenderer by ticking the appropriate box hereunder. The tenderer must complete the certificate set out below for the relevant category.

A Company	B Partnership	C Joint Venture	D Sole Proprietor	E Close Corporation

A. Certificate for company

I,....., chairperson of the board of directors of....., hereby confirm that by resolution of the board (copy attached) taken on20...., Mr/Mrs.....acting in the capacity of....., was authorised to sign all documents in connection with this tender and any contract resulting from it on behalf of the company.

As witness

1.....
Chairman

2.....
Date

B. Certificate of partnership

We, the undersigned, being the key partners in the business trading as

hereby authorise Mr/Mrs....., acting in the capacity of....., to sign all documents in connection with the tender for Contract.....and any contract resulting from it on our behalf.

NAME	ADDRESS	SIGNATURE	DATE

NOTE: This certificate is to be completed and signed by all of the key partners upon whom rests the direction of the affairs of the Partnership as a whole.

C. Certificate for Joint Venture

We, the undersigned, are submitting this tender offer in Joint Venture and hereby authorise Mr/Mrs....., authorised signatory of the company, acting in the capacity of lead partner, to sign all documents in connection with the tender offer for Contract.....and any other contract resulting from it on our behalf. This authorisation is evidenced by the attached power of attorney signed by legally authorised signatories of all the partners to the Joint Venture.

NAME OF FIRM	ADDRESS	AUTHORISING SIGNATURE, NAME & CAPACITY
Lead partner		

D. Certificate for sole proprietor

I,, hereby confirm that I am the sole owner of the business trading as.....

As Witness:

1.....
Signature: Sole owner

2.....
Date

E. Certificate for Close Corporation

We, the undersigned, being the key members in the business trading as.....hereby authorise Mr/Mrs.....

Acting in the capacity of....., to sign all documents in connection with the tender for Contract.....and any contract resulting from it on our behalf.

NAME	ADDRESS	SIGNATURE	DATE

NOTE: These certificates are only Examples. Bidding Entities are requested to submit in their own company letter heads.

Schedule of Proposed Subcontractors

		<p>We notify you that it is our intention to employ the following Subcontractors for work in this contract.</p> <p>If we are awarded a contract, we agree that this notification does not change the requirement for us to submit the names of proposed Subcontractors in accordance with requirements in the contract for such appointments. If there are no such requirements in the contract, then your written acceptance of this list shall be binding between us.</p>		
	Name and address of proposed Subcontractor	Nature and extent of work	CIDB grading of the sub-contractor	Previous experience with Subcontractor.
1.				
2.				
3.				
4.				
5.				
Signed			Date	
Name			Position	
Bidder				

Schedule of Plant and Equipment

The following are lists of major items of relevant equipment that I/we presently own or lease and will have available for this contract or will acquire or hire for this contract if my/our Bid is accepted.

(a) Details of major equipment that is owned by and immediately available for this contract.

Quantity	Description, size, capacity, etc.

Attach additional pages if more space is required.

(b) Details of major equipment that will be hired, or acquired for this contract if my/our Bid is acceptable.

Quantity	Description, size, capacity, etc.

Attach additional pages if more space is required.

Signed		Date	
Name		Position	
Bidder			

N.B: Bidders to submit certified proof of ownership from the relevant Authority. If hiring proof of certified ownership documents from the plant hire to be submitted with the tender.

Schedule of the Bidder's Experience

The following is a statement of similar work successfully executed by myself/ourselves:

Employer, contact person and telephone number.	Description of contract	Value of work inclusive of VAT (Rand)	Date completed
Signed		Date	
Name		Position	
Bidder			

N.B: Evaluation will be based on the first four projects only. Certificates of practical completion for completed projects. Appointment letters for projects not completed.

Proposed amendments and qualifications

The Bidder should record any deviations or qualifications he may wish to make to the Bid documents in this Returnable Schedule. Alternatively, a Bidder may state such deviations and qualifications in a covering letter to his Bid and reference such letter in this schedule.

The Bidder's attention is drawn to clause F.3.8 of the Standard Conditions of Bid referenced in the Bid Data regarding the employer's handling of material deviations and qualifications.

Page	Clause or item	Proposal	
Signed		Date	
Name		Position	
Bidder			

Schedule of Personnel and Employees

The Tenderer shall state below the number of Personnel and Employees to be employed on the Works.

PERSONNEL AND EMPLOYEES	TENDER			
	FULL TIME	PART TIME	FULL TIME	PART TIME
1. Technical staff				
2. Clerical staff				
3. Artisans				
4. Semi-skilled				
5. Unskilled labour				
Total				

State the name, qualifications (Certified proof not older than three months) and experience of proposed Site agent:

Date:

SIGNATURE OF TENDERER:

Preliminary Programme

The Tenderer shall detail below or attach a preliminary programme reflecting the proposed order and rate of progress for each portion of the work comprising this Contract. The programme shall be consistent with and in support of his time required for completion and shall be in accordance with the requirements of this tender.

SIGNATURE OF TENDERER:

Signatories Authority (Power Of Attorney)

1. INFORMATION TO BE PROVIDED

1.1 If the Tenderer is a COMPANY

- (a) Affix a certificate copy of the Certificate of Incorporation to this page.
- (b) Affix a copy of the relevant resolution of the Board of Directors, duly signed and dated
- (c) List the Directors

.....
.....

1.2 If the Tenderer is a CLOSE CORPORATION

- (a) Affix a certificate copy of the Founding Statement to this page
- (b) Affix a copy of the relevant resolution of the Members, duly signed and dated
- (c) List the Members

.....
.....

1.3 If the Tenderer is a PARTNERSHIP

- (a) Affix a copy of the relevant resolution on the Partners, duly signed and dated
- (b) List the Partners

.....
.....

1.2 If the Tenderer is a ONE-MAN-CONCERN.

Provide the full name, identity number and qualifications of the person

.....

1.3 If the Tenderer is a JOINT VENTURE

- a) Affix a copy of the original document of information defining the conditions under which the joint venture will function, its period of duration and the participating persons, companies and/or firms
- b) Affix a certificate signed for or on behalf of each participating person, company and/or firm authorizing the person who signed the tender to do so.

1.4 If the Tenderer is a CONCERN OTHER than these listed above

Provide full details of the CONCERN submitting the tender:

.....

Site Inspection Certificate

This is to certify that I,.....

representing and duly authorized by (Tenderer)

attended the site inspection on

Having prior to this site visit carefully examined the tender document, technical information and drawings supplied, I confirm that I was given unrestricted access to inspect those sections of the Site necessary for the execution of the Works.

I further confirm that I am completely satisfied with the scope of work as explained by the Engineer, and am fully aware of all Site conditions and regulations of whatsoever nature that could influence the preparation of our tender.

I therefore append my signature below in agreement that we will not institute any claim against the Employer after submission of our tender based on lack of knowledge of site conditions or regulations appertaining to the execution of this Contract.

Signature of Tenderer's Representative

Date

Signature of Engineer's Representative

Date

NB: THE PERSON WHO ATTENDED THE BRIEFING SESSION TO SIGN ON THIS PAGE, INFORMATION TO BE THE SAME AS THE ONE ON THE ATTENDANCE REGISTER. ANY DEVIATION WILL LEAD TO DISQUALIFICATION.

COMPLIANCE WITH OCCUPATIONAL HEALTH AND SAFETY ACT, 1993 AND CONSTRUCTION REGULATIONS, 2003

The tenderer shall attach to this Form evidence that he is registered and in good standing with a compensation insurer who is approved by Department of Labour in terms of section 80 of the Compensation for Injury and Disease Act (COID)(Act 130 of 1993).

The tenderer is required to disclose, by also attaching documentary evidence to this form, all inspections, investigations and their outcomes conducted by the Department of Labour into the conduct of the tenderer at any time during the 36 months preceding the date of this tender.

SIGNED ON BEHALF OF THE TENDERER:

Note to tenderer:

Discovery that the tenderer has failed to make proper disclosure may result in MLM terminating a contract that flows from this tender on the ground that it has been rendered invalid by the tenderer's misrepresentation.

CONSTRUCTION INDUSTRIES DEVELOPMENT BOARD REGISTRATION

The tenderer is to affix to this page either:

- Written proof of his registration with the CIDB as a Category **4 CEPE or higher** (as Minimum)

Or

- Written proof of his application to the CIDB for registration as a contractor in the category listed above.

Note:

1. Failure to affix such documentation as prescribed to this page shall result in this tender not being further considered for the award of the contract.
2. Should this tender be considered for award of the contract, based on proof of submission of application for registration in the appropriate category with the CIDB, and should proof of such subsequent registration not be forthcoming to the employer by the time of award of the contract, then this tender will no longer be considered for the award of the contract.

INVITATION TO BID

YOU ARE HEREBY INVITED TO BID FOR REQUIREMENTS OF THE (NAME OF MUNICIPALITY/ENTITY)

BID NUMBER: MLM/IDS/WRYC/W16/23-24 CLOSING DATE: 03 NOVEMBER 2023 CLOSING TIME:12:00

DESCRIPTION: WATER RETICULATION AND YARD CONNECTIONS IN WARD 16

The successful bidder will be required to fill in and sign a written Contract Form (MBD 7).

BID DOCUMENTS SHOULD BE DEPOSITED IN THE BID BOX SITUATED AT (STREET ADDRESS)

Municipal Offices

4065 B

Mathibestad

0404

Bidders should ensure that bids are delivered timeously to the correct address. If the bid is late, it will not be accepted for consideration.

The bid box is generally open 24 hours a day, 7 days a week.

ALL BIDS MUST BE SUBMITTED ON THE OFFICIAL FORMS – (NOT TO BE RE-TYPED)

THIS BID IS SUBJECT TO THE PREFERENTIAL PROCUREMENT POLICY FRAMEWORK ACT AND THE PREFERENTIAL PROCUREMENT REGULATIONS, 2011, THE GENERAL CONDITIONS OF CONTRACT (GCC) AND, IF APPLICABLE, ANY OTHER SPECIAL CONDITIONS OF CONTRACT

NB: NO BIDS WILL BE CONSIDERED FROM PERSONS IN THE SERVICE OF THE STATE (as defined in Regulation 1 of the Local Government: Municipal Supply Chain Management Regulations)

**THE FOLLOWING PARTICULARS MUST BE FURNISHED
(FAILURE TO DO SO MAY RESULT IN YOUR BID BEING DISQUALIFIED)**

NAME OF BIDDER

POSTAL ADDRESS

STREET ADDRESS

TELEPHONE NUMBER CODE.....NUMBER.....

CELLPHONE NUMBER

FACSIMILE NUMBER CODE NUMBER.....

E-MAIL ADDRESS

VAT REGISTRATION NUMBER.....

HAS AN ORIGINAL AND VALID TAX CLEARANCE CERTIFICATE BEEN ATTACHED? (MBD 2) YES/NO

HAS A B-BBEE STATUS LEVEL VERIFICATION CERTIFICATE BEEN SUBMITTED? (MBD 6.1) YES/NO

IF YES, WHO WAS THE CERTIFICATE ISSUED BY?

AN ACCOUNTING OFFICER AS CONTEMPLATED IN THE CLOSE CORPORATION ACT (CCA)
A VERIFICATION AGENCY ACCREDITED BY THE SOUTH AFRICAN NATIONAL ACCREDITATION SYSTEM (SANAS)
A REGISTERED AUDITOR
(Tick applicable box)

(A B-BBEE STATUS LEVEL VERIFICATION CERTIFICATE MUST BE SUBMITTED IN ORDER TO QUALIFY FOR PREFERENCE POINTS FOR B-BBEE)

I. ARE YOU THE ACCREDITED REPRESENTATIVE IN SOUTH AFRICA FOR THE GOODS/SERVICES/WORKS OFFERED?

YES/NO (IF YES ENCLOSURE PROOF)

SIGNATURE OF BIDDER

DATE

CAPACITY UNDER WHICH THIS BID IS SIGNED.....

TOTAL BID PRICE.....TOTAL NUMBER OF ITEMS OFFERED

ANY ENQUIRIES REGARDING THE BIDDING PROCEDURE MAY BE DIRECTED TO:

Municipality / Municipal Entity:

Department:

Contact Person:

Tel:

Fax:

ANY ENQUIRIES REGARDING TECHNICAL INFORMATION MAY BE DIRECTED TO:

Contact Person:

Tel:

Fax:

TAX CLEARANCE CERTIFICATE REQUIREMENTS

It is a condition of bid that the taxes of the successful bidder must be in order, or that satisfactory arrangements have been made with South African Revenue Service (SARS) to meet the bidder's tax obligations.

1. In order to meet this requirement bidders are required to complete in full the attached form TCC 001 "Application for a Tax Clearance Certificate" and submit it to any SARS branch office nationally. The Tax Clearance Certificate Requirements are also applicable to foreign bidders / individuals who wish to submit bids.
2. SARS will then furnish the bidder with a Tax Clearance Certificate that will be valid for a period of 1 (one) year from the date of approval.
3. The original Tax Clearance Certificate must be submitted together with the bid. Failure to submit the original and valid Tax Clearance Certificate will result in the invalidation of the bid. Certified copies of the Tax Clearance Certificate will not be acceptable.
4. In bids where Consortia / Joint Ventures / Sub-contractors are involved, each party must submit a separate Tax Clearance Certificate.
5. Copies of the TCC 001 "Application for a Tax Clearance Certificate" form are available from any SARS branch office nationally or on the website www.sars.gov.za.
6. Applications for the Tax Clearance Certificates may also be made via eFiling. In order to use this provision, taxpayers will need to register with SARS as eFilers through the website www.sars.gov.za.

Application for a Tax Clearance Certificate**Purpose**Select the applicable option Tenders Good standing If "Good standing", please state the purpose of this application

Particulars of applicant

Name/Legal name (Initials & Surname or registered name)	<input type="text"/>	
Trading name (if applicable)	<input type="text"/>	
ID/Passport no	<input type="text"/>	Company/Close Corp. registered no
Income Tax ref no	<input type="text"/> PAYE ref no 7	
VAT registration no	4	SDL ref no L
Customs code	<input type="text"/> UIF ref no U	
Telephone no	CODE - NUMBER	<input type="text"/> Fax no CODE - NUMBER
E-mail address	<input type="text"/>	
Physical address	<input type="text"/> <input type="text"/> <input type="text"/>	
Postal address	<input type="text"/> <input type="text"/> <input type="text"/>	

Particulars of representative (Public Officer/Trustee/Partner)

Surname	<input type="text"/>	
First names	<input type="text"/>	
ID/Passport no	<input type="text"/>	Income Tax ref no <input type="text"/>
Telephone no	CODE - NUMBER	<input type="text"/> Fax no CODE - NUMBER
E-mail address	<input type="text"/>	
Physical address	<input type="text"/> <input type="text"/> <input type="text"/>	

Particulars of tender (If applicable)Tender number Estimated Tender amount R , Expected duration year(s)**Particulars of the 3 largest contracts previously awarded**

Date started	Date finalised	Principal	Contact person	Telephone number	Amount
<input type="text"/>					
<input type="text"/>					

AuditAre you currently aware of any Audit investigation against you/the company?..... YES NO
If "YES" provide details

Appointment of representative/agent (Power of Attorney)I the undersigned confirm that I require a Tax Clearance Certificate in respect of Tenders or Goodstanding.I hereby authorise and instruct to apply to and receive from SARS the applicable Tax Clearance Certificate on my/our behalf.

C C Y Y - M M - D D

Date

Signature of representative/agent

Name of representative/

agent

Declaration

I declare that the information furnished in this application as well as any supporting documents is true and correct in every respect.

C C Y Y - M M - D D

Date

Signature of applicant/Public Officer

Name of applicant/
Public Officer
Notes:

1. It is a serious offence to make a false declaration.
2. Section 75 of the Income Tax Act, 1962, states: Any person who
 - (a) fails or neglects to furnish, file or submit any return or document as and when required by or under this Act; or
 - (b) without just cause shown by him, refuses or neglects to-
 - (i) furnish, produce or make available any information, documents or things;
 - (ii) reply to or answer truly and fully, any questions put to him ...

As and when required in terms of this Act ... shall be guilty of an offence ...
3. **SARS will, under no circumstances, issue a Tax Clearance Certificate unless this form is completed in full.**
4. Your Tax Clearance Certificate will only be issued on presentation of your South African Identity Document or Passport (Foreigners only) as applicable.

PRICING SCHEDULE – FIRM PRICES (PURCHASES)

NOTE: ONLY FIRM PRICES WILL BE ACCEPTED. NON-FIRM PRICES (INCLUDING PRICES SUBJECT TO RATES OF EXCHANGE VARIATIONS) WILL NOT BE CONSIDERED

IN CASES WHERE DIFFERENT DELIVERY POINTS INFLUENCE THE PRICING, A SEPARATE PRICING SCHEDULE MUST BE SUBMITTED FOR EACH DELIVERY POINT

Name of Bidder..... Bid Number.....

Closing Time Closing Date

OFFER TO BE VALID FOR.....DAYS FROM THE CLOSING DATE OF BID.

ITEM NO.	QUANTITY	DESCRIPTION	BID PRICE IN RSA CURRENCY **(ALL APPLICABLE TAXES INCLUDED)
-------------	----------	-------------	--

- Required by:
- At:
- Brand and Model
- Country of Origin
- Does the offer comply with the specification(s)? *YES/NO
- If not to specification, indicate deviation(s)
- Period required for delivery
- *Delivery: Firm/Not firm
- Delivery basis

Note: All delivery costs must be included in the bid price, for delivery at the prescribed destination.

** "all applicable taxes" includes value- added tax, pay as you earn, income tax, unemployment insurance fund contributions and skills development levies.

*Delete if not applicable

PRICE ADJUSTMENTS

A NON-FIRM PRICES SUBJECT TO ESCALATION

1. IN CASES OF PERIOD CONTRACTS, NON-FIRM PRICES WILL BE ADJUSTED (LOADED) WITH THE ASSESSED CONTRACT PRICE ADJUSTMENTS IMPLICIT IN NON-FIRM PRICES WHEN CALCULATING THE COMPARATIVE PRICES
2. IN THIS CATEGORY PRICE ESCALATIONS WILL ONLY BE CONSIDERED IN TERMS OF THE FOLLOWING FORMULA:

$$Pa = (1 - V)Pt \left(D1 \frac{R1t}{R1o} + D2 \frac{R2t}{R2o} + D3 \frac{R3t}{R3o} + D4 \frac{R4t}{R4o} \right) + VPt$$

Where:

Pa	=	The new escalated price to be calculated.
(1-V) Pt	=	85% of the original bid price. Note that Pt must always be the original bid price and not an escalated price.
D1, D2.	=	Each factor of the bid price e.g. labour, transport, clothing, footwear, etc. The total of the various factors D1, D2...etc. must add up to 100%.
R1t, R2t.....	=	Index figure obtained from new index (depends on the number of factors used).
R1o, R2o	=	Index figure at time of bidding.
VPt	=	15% of the original bid price. This portion of the bid price remains firm i.e. it is not subject to any price escalations.

3. The following index/indices must be used to calculate your bid price:

Index..... Dated.....	Index..... Dated.....	Index..... Dated.....
Index..... Dated.....	Index..... Dated.....	Index..... Dated.....

4. FURNISH A BREAKDOWN OF YOUR PRICE IN TERMS OF ABOVE-MENTIONED FORMULA. THE TOTAL OF THE VARIOUS FACTORS MUST ADD UP TO 100%.

FACTOR (D1, D2 etc. e.g. Labour, transport etc.)	P	PERCENTAGE OF BID PRICE

B PRICES SUBJECT TO RATE OF EXCHANGE VARIATIONS

1. Please furnish full particulars of your financial institution, state the currencies used in the conversion of the prices of the items to South African currency, which portion of the price is subject to rate of exchange variations and the amounts remitted abroad.

PARTICULARS OF FINANCIAL INSTITUTION	ITEM NO	PRICE	CURRENCY	RATE	PORTION OF PRICE SUBJECT TO ROE	AMOUNT IN FOREIGN CURRENCY REMITTED ABROAD
				ZAR=		
				ZAR=		
				ZAR=		
				ZAR=		
				ZAR=		
				ZAR=		

2. Adjustments for rate of exchange variations during the contract period will be calculated by using the average monthly exchange rates as issued by your commercial bank for the periods indicated hereunder: (Proof from bank required)

AVERAGE MONTHLY EXCHANGE RATES FOR THE PERIOD:	DATE DOCUMENTATION MUST BE SUBMITTED TO THIS OFFICE	DATE FROM WHICH NEW CALCULATED PRICES WILL BECOME EFFECTIVE	DATE UNTIL WHICH NEW CALCULATED PRICE WILL BE EFFECTIVE

DECLARATION OF INTEREST

1. No bid will be accepted from persons in the service of the state*.
2. Any person, having a kinship with persons in the service of the state, including a blood relationship, may make an offer or offers in terms of this invitation to bid. In view of possible allegations of favouritism, should the resulting bid, or part thereof, be awarded to persons connected with or related to persons in service of the state, it is required that the bidder or their authorised representative declare their position in relation to the evaluating/adjudicating authority and/or take an oath declaring his/her interest.

- 3 In order to give effect to the above, the following questionnaire must be completed and submitted with the bid.

3.1 Full Name:

3.2 Identity Number:

3.3 Company Registration Number:

3.4 Tax Reference Number:

3.5 VAT Registration Number:

3.6 Are you presently in the service of the state* YES / NO

3.6.1 If so, furnish particulars.

.....
.....

3.7 Have you been in the service of the state for the past twelve months? YES / NO

3.7.1 If so, furnish particulars.

*MSCM Regulations: "in the service of the state" means to be –

- (a) a member of –
 - (i) any municipal council;
 - (ii) any provincial legislature; or
 - (iii) the national Assembly or the national Council of provinces;
- (b) a member of the board of directors of any municipal entity;
- (c) an official of any municipality or municipal entity;
- (d) an employee of any national or provincial department, national or provincial public entity or constitutional institution within the meaning of the Public Finance Management Act, 1999 (Act No.1 of 1999);
- (e) a member of the accounting authority of any national or provincial public entity; or
- (f) an employee of Parliament or a provincial legislature.

3.8 Do you, have any relationship (family, friend, other) with persons in the service of the state and who may be involved with the evaluation and or adjudication of this bid? **YES / NO**

3.8.1 If so, furnish particulars.

3.9 Are you, aware of any relationship (family, friend, other),
between a bidder and any persons in the service of the state who
may be involved with the evaluation and or adjudication of this
bid? YES / NO

3.9.1 If so, furnish particulars

3.10 Are any of the company's directors, managers, principal shareholders or stakeholders in service of the state? **YES / NO**

3.10.1 If so, furnish particulars.

3.11 Are any spouse, child or parent of the company's directors, managers, principal shareholders or stakeholders in service of the state? **YES / NO**

3.11.1 If so, furnish particulars.

CERTIFICATION

I, THE UNDERSIGNED (NAME).....

CERTIFY THAT THE INFORMATION FURNISHED ON THIS DECLARATION FORM IS CORRECT.

I ACCEPT THAT THE STATE MAY ACT AGAINST ME SHOULD THIS DECLARATION PROVE TO BE FALSE.

.....
Signature

.....
Date

.....
Position

.....
Name of Bidder

DECLARATION FOR PROCUREMENT ABOVE R10 MILLION (ALL APPLICABLE TAXES INCLUDED)

For all procurement expected to exceed R10 million (all applicable taxes included), bidders must complete the following questionnaire:

1 Are you by law required to prepare annual financial statements for auditing?

1.1 If yes, submit audited annual financial statements for the past three years or since the date of establishment if established during the past three years. YES / NO

.....

.....

2 Do you have any outstanding undisputed commitments for municipal services towards any municipality for more than three months or any other service provider in respect of which payment is overdue for more than 30 days?

2.1 If no, this serves to certify that the bidder has no undisputed commitments for municipal services towards any municipality for more than three months or other service provider in respect of which payment is overdue for more than 30 days.

2.2 If yes, provide particulars.

.....

.....

3 Has any contract been awarded to you by an organ of state during the past five years, including particulars of any material non-compliance or dispute concerning the execution of such contract? YES / NO

3.1 If yes, furnish particulars

.....

.....

4. Will any portion of goods or services be sourced from outside the Republic, and, if so, what portion and whether any portion of payment from the municipality / municipal entity is expected to be transferred out of the Republic? *YES / NO

4.1 If yes, furnish particulars

.....

.....

CERTIFICATION

I, THE UNDERSIGNED (NAME).....

CERTIFY THAT THE INFORMATION FURNISHED ON THIS DECLARATION FORM IS CORRECT.

I ACCEPT THAT THE STATE MAY ACT AGAINST ME SHOULD THIS DECLARATION PROVE TO BE FALSE.

.....

Signature

.....

Date

.....

Position

.....

Name of Bidder

PREFERENCE POINTS CLAIM FORM IN TERMS OF THE PREFERENTIAL PROCUREMENT REGULATIONS 2011

(1)

This preference form must form part of all bids invited. It contains general information and serves as a claim form for preference points for Broad-Based Black Economic Empowerment (B-BBEE) Status Level of Contribution

NB: BEFORE COMPLETING THIS FORM, BIDDERS MUST STUDY THE GENERAL CONDITIONS, DEFINITIONS AND DIRECTIVES APPLICABLE IN RESPECT OF B-BBEE, AS PRESCRIBED IN THE PREFERENTIAL PROCUREMENT REGULATIONS, 2011.

1. GENERAL CONDITIONS

1.1 The following preference point systems are applicable to all bids:

- the 80/20 system for requirements with a Rand value of up to R 50 000 000 (all applicable taxes included); and
- the 90/10 system for requirements with a Rand value above R 50 000 000 (all applicable taxes included).

1.2 The value of this bid is estimated to exceed/not exceed R 50 000 000 (all applicable taxes included) and therefore the 80/20 system shall be applicable.

1.3 Preference points for this bid shall be awarded for:

- (a) Price; and
- (b) B-BBEE Status Level of Contribution.

1.3.1 The maximum points for this bid are allocated as follows:

	POINTS
1.3.1.1 PRICE
1.3.1.2 B-BBEE STATUS LEVEL OF CONTRIBUTION
Total points for Price and B-BBEE must not exceed	100
1.4 Failure on the part of a bidder to fill in and/or to sign this form and submit a B-BBEE Verification Certificate from a Verification Agency accredited by the South African Accreditation System (SANAS) or a Registered Auditor approved by the Independent Regulatory Board of Auditors (IRBA) or an Accounting Officer as contemplated in the Close Corporation Act (CCA) together with the bid, will be interpreted to mean that preference points for B-BBEE status level of contribution are not claimed.	
1.5. The purchaser reserves the right to require of a bidder, either before a bid is adjudicated or at any time subsequently, to substantiate any claim in regard to preferences, in any manner required by the purchaser.	

2. DEFINITIONS

2.1 “**all applicable taxes**” includes value-added tax, pay as you earn, income tax, unemployment insurance fund contributions and skills development levies;

2.2 “**B-BBEE**” means broad-based black economic empowerment as defined in section 1 of the Broad Based

2.3 Black Economic Empowerment Act;

2.4 “**bid**” means a written offer in a prescribed or stipulated form in response to an invitation by an organ of state for the provision of services, works or goods, through price quotations, advertised competitive bidding processes or proposals;

2.5 “**Broad-Based Black Economic Empowerment Act**” means the Broad-Based Black Economic Empowerment Act, 2003 (Act No. 53 of 2003);

2.6 “**comparative price**” means the price after the factors of a non-firm price and all unconditional discounts that can be utilized have been taken into consideration;

2.7 “**consortium or joint venture**” means an association of persons for the purpose of combining their expertise, property, capital, efforts, skill and knowledge in an activity for the execution of a contract;

2.8 “**contract**” means the agreement that results from the acceptance of a bid by an organ of state;

2.9 “**EME**” means any enterprise with annual total revenue of R5 million or less.

2.10 “**Firm price**” means the price that is only subject to adjustments in accordance with the actual increase or decrease resulting from the change, imposition, or abolition of customs or excise duty and any other duty, levy, or tax, which, in terms of the law or regulation, is binding on the contractor and demonstrably has an influence on the price of any supplies, or the rendering costs of any service, for the execution of the contract;

2.11 “**functionality**” means the measurement according to predetermined norms, as set out in the bid documents, of a service or commodity that is designed to be practical and useful, working or operating, taking into account, among other factors, the quality, reliability, viability and durability of a service and the technical capacity and ability of a bidder;

2.12 “**non-firm prices**” means all prices other than “firm” prices;

2.13 “**person**” includes a juristic person;

2.14 “**rand value**” means the total estimated value of a contract in South African currency, calculated at the time of bid invitations, and includes all applicable taxes and excise duties;

(2) 2.15 “**sub-contract**” means the primary contractor’s assigning, leasing, making out work to, or employing, another person to support such primary contractor in the execution of part of a project in terms of the contract;

2.16 “**total revenue**” bears the same meaning assigned to this expression in the Codes of Good Practice on Black Economic Empowerment, issued in terms of section 9(1) of the Broad-Based Black Economic Empowerment Act and promulgated in the *Government Gazette* on 9 February 2007;

2.17 “**trust**” means the arrangement through which the property of one person is made over or bequeathed to a trustee to administer such property for the benefit of another person; and

2.18 “**trustee**” means any person, including the founder of a trust, to whom property is bequeathed in order for such property to be administered for the benefit of another person.

3. ADJUDICATION USING A POINT SYSTEM

3.1 The bidder obtaining the highest number of total points will be awarded the contract.

3.2 Preference points shall be calculated after prices have been brought to a comparative basis taking into

account all factors of non-firm prices and all unconditional discounts;

3.2 Points scored must be rounded off to the nearest 2 decimal places.

3.4 In the event that two or more bids have scored equal total points, the successful bid must be the one scoring the highest number of preference points for B-BBEE.

3.5 However, when functionality is part of the evaluation process and two or more bids have scored equal points including equal preference points for B-BBEE, the successful bid must be the one scoring the highest score for functionality.

3.6 Should two or more bids be equal in all respects; the award shall be decided by the drawing of lots.

4. POINTS AWARDED FOR PRICE

4.1 THE 80/20 OR 90/10 PREFERENCE POINT SYSTEMS

A maximum of 80 or 90 points is allocated for price on the following basis:

$$P_S = 80 \left(1 - \frac{P_t - P_{\min}}{P_{\min}} \right) \quad \text{or} \quad P_S = 90 \left(1 - \frac{P_t - P_{\min}}{P_{\min}} \right)$$

Where

Ps = Points scored for comparative price of bid under consideration

P_t = Comparative price of bid under consideration

P_{min} = Comparative price of lowest acceptable bid

5. Points awarded for B-BBEE Status Level of Contribution

5.1 In terms of Regulation 5 (2) and 6 (2) of the Preferential Procurement Regulations, preference points must be awarded to a bidder for attaining the B-BBEE status level of contribution in accordance with the table below:

B-BBEE Status Level of Contributor	Number of points (90/10 system)	Number of points (80/20 system)
1	10	20
2	9	18
3	8	16
4	5	12
5	4	8
6	3	6
7	2	4
8	1	2
Non-compliant contributor	0	0

5.2 Bidders who qualify as EMEs in terms of the B-BBEE Act must submit a certificate issued by an Accounting Officer as contemplated in the CCA or a Verification Agency accredited by SANAS or a Registered Auditor. Registered auditors do not need to meet the prerequisite for IRBA's approval for the purpose of conducting verification and issuing EMEs with B-BBEE Status Level Certificates.

5.3 Bidders other than EMEs must submit their original and valid B-BBEE status level verification certificate or a certified copy thereof, substantiating their B-BBEE rating issued by a Registered Auditor approved by IRBA or a Verification Agency accredited by SANAS.

5.4 A trust, consortium or joint venture, will qualify for points for their B-BBEE status level as a legal entity, provided that the entity submits their B-BBEE status level certificate.

5.5 A trust, consortium or joint venture will qualify for points for their B-BBEE status level as an unincorporated entity, provided that the entity submits their consolidated B-BBEE scorecard as if they were a group structure and that such a consolidated B-BBEE scorecard is prepared for every separate bid.

5.6 Tertiary institutions and public entities will be required to submit their B-BBEE status level certificates in terms of the specialized scorecard contained in the B-BBEE Codes of Good Practice.

5.7 A person will not be awarded points for B-BBEE status level if it is indicated in the bid documents that such a bidder intends sub-contracting more than 25% of the value of the contract to any other enterprise that does not qualify for at least the points that such a bidder qualifies for, unless the intended sub-contractor is an EME that has the capability and ability to execute the sub-contract.

5.8 A person awarded a contract may not sub-contract more than 25% of the value of the contract to any other enterprise that does not have an equal or higher B-BBEE status level than the person concerned, unless the contract is sub-contracted to an EME that has the capability and ability to execute the sub-contract.

5.2.1 Moretele Local Municipality Specific Goals

Women	5
Youth	5
Locality	5

6. BID DECLARATION

6.1 Bidders who claim points in respect of B-BBEE Status Level of Contribution must complete the following:

6. B-BBEE STATUS LEVEL OF CONTRIBUTION CLAIMED IN TERMS OF PARAGRAPHS 1.3.1.2 AND 5.1

7.1 B-BBEE Status Level of Contribution : =(maximum of 10 or 20 points)

(Points claimed in respect of paragraph 7.1 must be in accordance with the table reflected in paragraph 5.1 and must be substantiated by means of a B-BBEE certificate issued by a Verification Agency accredited by SANAS or a Registered Auditor approved by IRBA or an Accounting Officer as contemplated in the CCA).

8 SUB-CONTRACTING

8.1 Will any portion of the contract be sub-contracted? YES / NO (delete which is not applicable)

8.1.1 If yes, indicate:

(i) what percentage of the contract will be subcontracted?%
 (ii) the name of the sub-contractor?
 (iii) the B-BBEE status level of the sub-contractor?
 (iv) whether the sub-contractor is an EME? YES / NO (delete which is not applicable)

9 DECLARATION WITH REGARD TO COMPANY/FIRM

9.1 Name of firm :

9.2 VAT registration number :

9.3 Company registration number

9.4 TYPE OF COMPANY/ FIRM

- Partnership/Joint Venture / Consortium
- One-person business/sole property
- Close corporation
- Company
- (Pty) Limited

[TICK APPLICABLE BOX]

9.5 DESCRIBE PRINCIPAL BUSINESS ACTIVITIES

.....
.....
.....

9.6 COMPANY CLASSIFICATION

- Manufacturer
- Supplier
- Professional service provider
- Other service providers, e.g. transporter, etc.

[TICK APPLICABLE BOX]

9.7 MUNICIPAL INFORMATION

Municipality where business is situated

Registered Account Number

Stand Number

9.8 TOTAL NUMBER OF YEARS THE COMPANY/FIRM HAS BEEN IN BUSINESS?

9.9 I/we, the undersigned, who is / are duly authorised to do so on behalf of the company/firm, certify that the points claimed, based on the B-BBE status level of contribution indicated in paragraph 7 of the foregoing certificate, qualifies the company/ firm for the preference(s) shown and I / we acknowledge that:

- (i) The information furnished is true and correct;
- (ii) The preference points claimed are in accordance with the General Conditions as indicated in paragraph 1 of this form.
- (iii) In the event of a contract being awarded as a result of points claimed as shown in paragraph 7, the contractor may be required to furnish documentary proof to the satisfaction of the purchaser that the claims are correct;
- (iv) If the B-BBEE status level of contribution has been claimed or obtained on a fraudulent basis or any of the conditions of contract have not been fulfilled, the purchaser may, in addition to any other remedy it may have –
 - (a) disqualify the person from the bidding process;
 - (b) recover costs, losses or damages it has incurred or suffered as a result of that person's conduct;
 - (c) cancel the contract and claim any damages which it has suffered as a result of having to make less favourable arrangements due to such cancellation;
 - (d) restrict the bidder or contractor, its shareholders and directors, or only the

shareholders and directors who acted on a fraudulent basis, from obtaining business from any organ of state for a period not exceeding 10 years, after the *audialterampartem* (hear the other side) rule has been applied; and
(e) forward the matter for criminal prosecution

WITNESSES:

1.

SIGNATURE(S)OF BIDDER(S)

2.

DATE:.....

ADDRESS:.....

.....

.....

CONTRACT FORM - RENDERING OF SERVICES

THIS FORM MUST BE FILLED IN DUPLICATE BY BOTH THE SERVICE PROVIDER (PART 1) AND THE PURCHASER (PART 2). BOTH FORMS MUST BE SIGNED IN THE ORIGINAL SO THAT THE SERVICE PROVIDER AND THE PURCHASER WOULD BE IN POSSESSION OF ORIGINALLY SIGNED CONTRACTS FOR THEIR RESPECTIVE RECORDS.

PART 1 (TO BE FILLED IN BY THE SERVICE PROVIDER)

1. I hereby undertake to render services described in the attached bidding documents to (name of the institution) in accordance with the requirements and task directives / proposals specifications stipulated in Bid Number at the price/s quoted. My offer/s remain binding upon me and open for acceptance by the Purchaser during the validity period indicated and calculated from the closing date of the bid.
2. The following documents shall be deemed to form and be read and construed as part of this agreement:
 - (i) Bidding documents, *viz*
 - Invitation to bid;
 - Tax clearance certificate;
 - Pricing schedule(s);
 - Filled in task directive/proposal;
 - Preference claims for Broad Based Black Economic Empowerment Status Level of Contribution in terms of the Preferential Procurement Regulations 2011;
 - Declaration of interest;
 - Declaration of Bidder's past SCM practices;
 - Certificate of Independent Bid Determination;
 - Special Conditions of Contract;
 - (ii) General Conditions of Contract; and
 - (iii) Other (specify)
3. I confirm that I have satisfied myself as to the correctness and validity of my bid; that the price(s) and rate(s) quoted cover all the services specified in the bidding documents; that the price(s) and rate(s) cover all my obligations and I accept that any mistakes regarding price(s) and rate(s) and calculations will be at my own risk.
4. I accept full responsibility for the proper execution and fulfilment of all obligations and conditions devolving on me under this agreement as the principal liable for the due fulfilment of this contract.
5. I declare that I have no participation in any collusive practices with any bidder or any other person regarding this or any other bid.
6. I confirm that I am duly authorised to sign this contract.

NAME (PRINT)

CAPACITY

WITNESSES	
1
2
DATE:	

SIGNATURE

NAME OF FIRM

DATE

MBD 7.2

CONTRACT FORM - RENDERING OF SERVICES

PART 2 (TO BE FILLED IN BY THE PURCHASER)

1. I..... in my capacity as..... accept your bid under reference numberdated.....for the rendering of services indicated hereunder and/or further specified in the annexure(s).
2. An official order indicating service delivery instructions is forthcoming.
3. I undertake to make payment for the services rendered in accordance with the terms and conditions of the contract, within 30 (thirty) days after receipt of an invoice.

DESCRIPTION OF SERVICE	PRICE (ALL APPLICABLE TAXES INCLUDED)	COMPLETION DATE	B-BBEE STATUS LEVEL OF CONTRIBUTION	MINIMUM THRESHOLD FOR LOCAL PRODUCTION AND CONTENT (if applicable)

4. I confirm that I am duly authorized to sign this contract.

SIGNED AT ON

NAME (PRINT)

SIGNATURE

OFFICIAL STAMP

WITNESSES

1
2

DATE:

DECLARATION OF BIDDER'S PAST SUPPLY CHAIN MANAGEMENT PRACTICES

- 1 This Municipal Bidding Document must form part of all bids invited.
- 2 It serves as a declaration to be used by municipalities and municipal entities in ensuring that when goods and services are being procured, all reasonable steps are taken to combat the abuse of the supply chain management system.
- 3 The bid of any bidder may be rejected if that bidder, or any of its directors have:
 - a. abused the municipality's / municipal entity's supply chain management system or committed any improper conduct in relation to such system;
 - b. been convicted for fraud or corruption during the past five years;
 - c. willfully neglected, reneged on or failed to comply with any government, municipal or other public sector contract during the past five years; or
 - d. been listed in the Register for Tender Defaulters in terms of section 29 of the Prevention and Combating of Corrupt Activities Act (No 12 of 2004).
- 4 **In order to give effect to the above, the following questionnaire must be completed and submitted with the bid.**

Item	Question	Yes	No
4.1	<p>Is the bidder or any of its directors listed on the National Treasury's Database of Restricted Suppliers as companies or persons prohibited from doing business with the public sector?</p> <p>(Companies or persons who are listed on this Database were informed in writing of this restriction by the Accounting Officer/Authority of the institution that imposed the restriction after the <i>audialteram partem</i> rule was applied).</p> <p>The Database of Restricted Suppliers now resides on the National Treasury's website (www.treasury.gov.za) and can be accessed by clicking on its link at the bottom of the home page.</p>	<input type="checkbox"/>	<input type="checkbox"/>
4.1.1	If so, furnish particulars:		
4.2	<p>Is the bidder or any of its directors listed on the Register for Tender Defaulters in terms of section 29 of the Prevention and Combating of Corrupt Activities Act (No 12 of 2004)?</p> <p>The Register for Tender Defaulters can be accessed on the National Treasury's website (www.treasury.gov.za) by clicking on its link at the bottom of the home page.</p>	<input type="checkbox"/>	<input type="checkbox"/>
4.2.1	If so, furnish particulars:		
4.3	Was the bidder or any of its directors convicted by a court of law (including a court of law outside the Republic of South Africa) for fraud or corruption during the past five years?	<input type="checkbox"/>	<input type="checkbox"/>

4.3.1	If so, furnish particulars:	Yes	No
4.4	Does the bidder or any of its directors owe any municipal rates and taxes or municipal charges to the municipality / municipal entity, or to any other municipality / municipal entity, that is in arrears for more than three months?	Yes <input type="checkbox"/>	No <input type="checkbox"/>
4.4.1	If so, furnish particulars:		
4.5	Was any contract between the bidder and the municipality / municipal entity or any other organ of state terminated during the past five years on account of failure to perform on or comply with the contract?	Yes <input type="checkbox"/>	No <input type="checkbox"/>
4.7.1	If so, furnish particulars:		

CERTIFICATION

I, THE UNDERSIGNED (FULL NAME)
CERTIFY THAT THE INFORMATION FURNISHED ON THIS
DECLARATION FORM TRUE AND CORRECT.

I ACCEPT THAT, IN ADDITION TO CANCELLATION OF A CONTRACT, ACTION MAY BE TAKEN AGAINST ME SHOULD THIS DECLARATION PROVE TO BE FALSE.

.....
Signature

.....
Date

.....
Position

.....
Name of Bidder

CERTIFICATE OF INDEPENDENT BID DETERMINATION

- 1 This Municipal Bidding Document (MBD) must form part of all bids¹ invited.
- 2 Section 4 (1) (b) (iii) of the Competition Act No. 89 of 1998, as amended, prohibits an agreement between, or concerted practice by, firms, or a decision by an association of firms, if it is between parties in a horizontal relationship and if it involves collusive bidding (or bid rigging).² Collusive bidding is a *per se* prohibition meaning that it cannot be justified under any grounds.
- 3 Municipal Supply Regulation 38 (1) prescribes that a supply chain management policy must provide measures for the combating of abuse of the supply chain management system, and must enable the accounting officer, among others, to:
 - a. takes all reasonable steps to prevent such abuse;
 - b. rejects the bid of any bidder if that bidder or any of its directors has abused the supply chain management system of the municipality or municipal entity or has committed any improper conduct in relation to such system; and
 - c. cancels a contract awarded to a person if the person committed any corrupt or fraudulent act during the bidding process or the execution of the contract.
- 4 This MBD serves as a certificate of declaration that would be used by institutions to ensure that, when bids are considered, reasonable steps are taken to prevent any form of bid-rigging.
- 5 In order to give effect to the above, the attached Certificate of Bid Determination (MBD 9) must be completed and submitted with the bid:

¹ Includes price quotations, advertised competitive bids, limited bids and proposals.

² Bid rigging (or collusive bidding) occurs when businesses, that would otherwise be expected to compete, secretly conspire to raise prices or lower the quality of goods and / or services for purchasers who wish to acquire goods and / or services through a bidding process. Bid rigging is, therefore, an agreement between competitors not to compete.

CERTIFICATE OF INDEPENDENT BID DETERMINATION

I, the undersigned, in submitting the accompanying bid:

(Bid Number and Description)

in response to the invitation for the bid made by:

(Name of Municipality / Municipal Entity)

do hereby make the following statements that I certify to be true and complete in every respect:

I certify, on behalf of: _____ that:

(Name of Bidder)

1. I have read and I understand the contents of this Certificate;
2. I understand that the accompanying bid will be disqualified if this Certificate is found not to be true and complete in every respect;
3. I am authorized by the bidder to sign this Certificate, and to submit the accompanying bid, on behalf of the bidder;
4. Each person whose signature appears on the accompanying bid has been authorized by the bidder to determine the terms of, and to sign, the bid, on behalf of the bidder;
5. For the purposes of this Certificate and the accompanying bid, I understand that the word "competitor" shall include any individual or organization, other than the bidder, whether or not affiliated with the bidder, who:
 - (a) has been requested to submit a bid in response to this bid invitation;
 - (b) could potentially submit a bid in response to this bid invitation, based on their qualifications, abilities or experience; and
 - (c) provides the same goods and services as the bidder and/or is in the same line of business as the bidder
6. The bidder has arrived at the accompanying bid independently from, and without consultation, communication, agreement or arrangement with any competitor. However, communication between partners in a joint venture or consortium³ will not be construed as collusive bidding

7. In particular, without limiting the generality of paragraphs 6 above, there has been no consultation, communication, agreement or arrangement with any competitor regarding:
 - (a) prices;
 - (b) geographical area where product or service will be rendered (market allocation)
 - (c) methods, factors or formulas used to calculate prices;
 - (d) the intention or decision to submit or not to submit, a bid;
 - (e) the submission of a bid which does not meet the specifications and conditions of the bid; or
 - (f) bidding with the intention not to win the bid.
8. In addition, there have been no consultations, communications, agreements or arrangements with any competitor regarding the quality, quantity, specifications and conditions or delivery particulars of the products or services to which this bid invitation relates.
9. The terms of the accompanying bid have not been, and will not be, disclosed by the bidder, directly or indirectly, to any competitor, prior to the date and time of the official bid opening or of the awarding of the contract.
10. I am aware that, in addition and without prejudice to any other remedy provided to combat any restrictive practices related to bids and contracts, bids that are suspicious will be reported to the Competition Commission for investigation and possible imposition of administrative penalties in terms of section 59 of the Competition Act No 89 of 1998 and or may be reported to the National Prosecuting Authority (NPA) for criminal investigation and or may be restricted from conducting business with the public sector for a period not exceeding ten (10) years in terms of the Prevention and Combating of Corrupt Activities Act No 12 of 2004 or any other applicable legislation.

.....
.....
.....
.....
.....
.....

Signature

.....
.....
.....
.....
.....
.....

Date

.....
.....
.....
.....
.....
.....

Position

.....
.....
.....
.....
.....
.....

Name of Bidder

³ Joint venture or Consortium means an association of persons for the purpose of combining their expertise, property, capital, efforts, skill and knowledge in an activity for the execution of a contract.



MORETELE LOCAL MUNICIPALITY

C1.1 Form of Offer and Acceptance

C1.1 FORM OF OFFER AND ACCEPTANCE

Offer

The Employer, identified in the Acceptance signature block, has solicited offers to enter into a contract in respect of the following works:

Contract Number: MLM/IDS/WRYC/W16/23-24

WATER RETICULATION AND YARD CONNECTIONS IN WARD 16

The Tenderer, identified in the Offer signature block, has examined the documents listed in the Tender Data and addenda thereto as listed in the Tender Schedules, and by submitting this Offer has accepted the conditions of tender.

By the representative of the Tenderer, deemed to be duly authorized, signing this part of this Form of Offer and Acceptance, the Tenderer offers to perform all of the obligations and liabilities of the Contractor under the Contract including compliance with all its terms and conditions according to their true intent and meaning for an amount to be determined in accordance with the Conditions of Contract identified in the Contract Data.

THE OFFERED TOTAL OF THE PRICE INCLUSIVE OF VALUE ADDED TAX IS (CONTRACT PRICE)

..... Rand (in words); (in figures)

This offer may be accepted by the Employer by signing the Acceptance part of this Form of Offer and Acceptance and returning one copy of this document to the Tenderer before the end of the period of validity stated in the Tender Data, whereupon the Tenderer becomes the party named as the Contractor in the Conditions of Contract identified in the Contract Data.

For the Tenderer:

Signature(s)

Name(s)

Capacity

Name and address of organization

Signature and name of witness:

Signature

Name

Date

Acceptance

By signing this part of this Form of Offer and Acceptance, the Employer identified below accepts the tenderer's Offer. In consideration thereof, the Employer shall pay the Contractor the amount due in accordance with the Conditions of Contract identified in the Contract Data. Acceptance of the Tenderer's Offer shall form an agreement between the Employer and the Tenderer upon the terms and conditions contained in this Agreement and in the Contract that is the subject of this Agreement.

The terms of the contract are contained in:

- PART 1 Agreements and Contract Data, (which includes this Agreement)
- PART 2 Pricing Data
- PART 3 Scope of Work
- PART 4 Site Information

and drawings and documents or parts thereof, which may be incorporated by reference into Parts 1 to 4 above.

Deviations from and amendments to the documents listed in the Tender Data and any addenda thereto as listed in the Tender Schedules as well as any changes to the terms of the Offer agreed by the Tenderer and the Employer during this process of offer and acceptance, are contained in the Schedule of Deviations attached to and forming part of this Agreement. No amendments to or deviations from said documents are valid unless contained in this schedule, which must be signed by the authorised representative(s) of both parties.

The Tenderer shall within two weeks after receiving a completed copy of this Agreement, including the Schedule of Deviations (if any), contact the Employer's agent (whose details are given in the Contract Data) to arrange the delivery of any bonds, guarantees, proof of insurance and any other documentation to be provided in terms of the Conditions of Contract identified in the Contract Data at, or just after, the date this Agreement comes into effect. Failure to fulfil any of these obligations in accordance with those terms shall constitute a repudiation of this Agreement.

Notwithstanding anything contained herein, this Agreement comes into effect on the date when the Tenderer receives one fully completed original copy of this document, including the Schedule of deviations (if any). Unless the Tenderer (now Contractor) within five days of the date of such receipt notifies the Employer in writing of any reason why he cannot accept the contents of this Agreement, this Agreement shall constitute a binding contract between the parties.

Signature(s).....

Name(s).....

Capacity

for the Employer

..... (Name and address or organization)

Name of witness

Signature

Date:

*****For official use only*



MORETELE LOCAL MUNICIPALITY

C1.2 Contract Data

The General Conditions of Contract for Construction Works (2015) published by the South African Institution of Civil Engineering, are applicable to this contract and forms Volume 1 of the Contract Document. Volume 2 is the Contract Drawings. Copies of these conditions of contract may be obtained from the South African Institution of Civil Engineering (Tel: 011-805 5947).

The General Conditions of Contract for Construction Works make several references to the Contract Data for specific data, which together with these conditions collectively describe the risks, liabilities and obligations of the contracting parties and the procedures for the administration of the Contract. The Contract Data shall have precedence in the interpretation of any ambiguity or inconsistency between it and the general conditions of contract.

Each item of data given below is cross-referenced to the clause in the General Conditions of Contract for Construction Works to which it mainly applies.

The additional clauses to the General Conditions of Contract are:	
	<p>Payment for the labour-intensive component of the works</p> <p>Payment for works identified in the Scope of Work as being labour-intensive shall only be made in accordance with the provisions of the Contract if the works are constructed strictly in accordance with the provisions of the scope of work. Any non-payment for such works shall not relieve the Contractor in any way from his obligations either in contract or in delict.</p> <p>Applicable labour laws</p> <p>The Ministerial Determination, Special Public Works Programmes, issued in terms of the Basic Conditions of Employment Act of 1997 by the Minister of Labour in Government Notice N° R63 of 25 January 2002, as reproduced below, shall apply to works described in the scope of work as being labour intensive and which are undertaken by unskilled or semi-skilled workers.</p> <p>1 Introduction</p> <p>1.1 This document contains the standard terms and conditions for workers employed in elementary occupations on a Special Public Works Programme (SPWP). These terms and conditions do NOT apply to persons employed in the supervision and management of a SPWP.</p> <p>2.2 In this document –</p> <ul style="list-style-type: none">(a) “department” means any department of the State, implementing agent or contractor;(b) “employer” means any department, implementing agency or contractor that hires workers to work in elementary occupations on a SPWP;(c) “worker” means any person working in an elementary occupation on a SPWP;(d) “elementary occupation” means any occupation involving unskilled or semi-skilled work;(e) “management” means any person employed by a department or implementing agency to administer or execute an SPWP;(f) “task” means a fixed quantity of work;(g) “task-based work” means work in which a worker is paid a fixed rate for performing a task;(h) “task-rated worker” means a worker paid on the basis of the number of tasks completed;(i) “time-rated worker” means a worker paid on the basis of the length of time worked.

	<p>2 Terms of Work</p> <p>2.1 Workers on a SPWP are employed on a temporary basis.</p> <p>2.2 A worker may NOT be employed for longer than 24 months in any five-year cycle on a SPWP.</p> <p>2.3 Employment on a SPWP does not qualify as employment as a contributor for the purposes of the Unemployment Insurance Act 30 of 1966.</p> <p>3 Normal Hours of Work</p> <p>3.1 An employer may not set tasks or hours of work that require a worker to work–</p> <ul style="list-style-type: none"> (a) more than forty hours in any week (b) on more than five days in any week; and (c) for more than eight hours on any day. <p>3.2 An employer and worker may agree that a worker will work four days per week. The worker may then work up to ten hours per day.</p> <p>3.3 A task-rated worker may not work more than a total of 55 hours in any week to complete the tasks allocated (based on a 40-hour week) to that worker.</p> <p>4 Meal Breaks</p> <p>4.1 A worker may not work for more than five hours without taking a meal break of at least thirty minutes duration.</p> <p>4.2 An employer and worker may agree on longer meal breaks.</p> <p>4.3 A worker may not work during a meal break. However, an employer may require a worker to perform duties during a meal break if those duties cannot be left unattended and cannot be performed by another worker. An employer must take reasonable steps to ensure that a worker is relieved of his or her duties during the meal break.</p> <p>4.4 A worker is not entitled to payment for the period of a meal break. However, a worker who is paid on the basis of time worked must be paid if the worker is required to work or to be available for work during the meal break.</p> <p>5 Special Conditions for Security Guards</p> <p>5.1 A security guard may work up to 55 hours per week and up to eleven hours per day.</p> <p>5.2 A security guard who works more than ten hours per day must have a meal break of at least one hour or two breaks of at least 30 minutes each.</p> <p>6 Daily Rest Period</p> <p>Every worker is entitled to a daily rest period of at least eight consecutive hours. The daily rest period is measured from the time the worker ends work on one day until the time the worker starts work on the next day.</p> <p>7 Weekly Rest Period</p> <p>Every worker must have two days off every week. A worker may only work on their day off to perform work which must be done without delay and cannot be performed by workers during their ordinary hours of work ("emergency work").</p> <p>8 Work on Sundays and Public Holidays</p> <p>8.1 A worker may only work on a Sunday or public holiday to perform emergency or security work.</p> <p>8.2 Work on Sundays is paid at the ordinary rate of pay.</p> <p>8.3 A task-rated worker who works on a public holiday must be paid –</p> <ul style="list-style-type: none"> (a) the worker's daily task rate, if the worker works for less than four hours; (b) double the worker's daily task rate, if the worker works for more than four hours. <p>8.4 A time-rated worker who works on a public holiday must be paid –</p> <ul style="list-style-type: none"> (a) the worker's daily rate of pay, if the worker works for less than four hours on the public holiday; (b) double the worker's daily rate of pay, if the worker works for more than four hours on the public holiday.
--	--

9 Sick Leave

9.1 Only workers who work four or more days per week have the right to claim sick-pay in terms of this clause.

9.2 A worker who is unable to work on account of illness or injury is entitled to claim one day's paid sick leave for every full month that the worker has worked in terms of a contract.

9.3 A worker may accumulate a maximum of twelve days' sick leave in a year.

9.4 Accumulated sick-leave may not be transferred from one contract to another contract.

9.5 An employer must pay a task-rated worker the worker's daily task rate for a day's sick leave.

9.6 An employer must pay a time-rated worker the worker's daily rate of pay for a day's sick leave.

9.7 An employer must pay a worker sick pay on the worker's usual payday.

9.8 Before paying sick-pay, an employer may require a worker to produce a certificate stating that the worker was unable to work on account of sickness or injury if the worker is –

- (a) absent from work for more than two consecutive days; or
- (b) absent from work on more than two occasions in any eight-week period.

9.9 A medical certificate must be issued and signed by a medical practitioner, a qualified nurse or a clinic staff member authorised to issue medical certificates indicating the duration and reason for incapacity.

9.10 A worker is not entitled to paid sick-leave for a work-related injury or occupational disease for which the worker can claim compensation under the Compensation for Occupational Injuries and Diseases Act.

10 Maternity Leave

10.1 A worker may take up to four consecutive months' unpaid maternity leave.

10.2 A worker is not entitled to any payment or employment-related benefits during maternity leave.

10.3 A worker must give her employer reasonable notice of when she will start maternity leave and when she will return to work.

10.4 A worker is not required to take the full period of maternity leave. However, a worker may not work for four weeks before the expected date of birth of her child or for six weeks after the birth of her child, unless a medical practitioner, midwife or qualified nurse certifies that she is fit to do so.

10.5 A worker may begin maternity leave –

- (a) four weeks before the expected date of birth; or
- (b) on an earlier date –
 - (i) if a medical practitioner, midwife or certified nurse certifies that it is necessary for the health of the worker or that of her unborn child; or
 - (ii) if agreed to between employer and worker; or
- (c) on a later date, if a medical practitioner, midwife or certified nurse has certified that the worker is able to continue to work without endangering her health.

10.6 A worker who has a miscarriage during the third trimester of pregnancy or bears a stillborn child may take maternity leave for up to six weeks after the miscarriage or stillbirth.

10.7 A worker who returns to work after maternity leave, has the right to start a new cycle of twenty-four months employment, unless the SPWP on which she was employed has ended.

11 Family responsibility leave

11.1 Workers, who work for at least four days per week, are entitled to three days paid family responsibility leave each year in the following circumstances -

- (a) when the employee's child is born;
- (b) when the employee's child is sick;
- (c) in the event of a death of –
 - (i) the employee's spouse or life partner;
 - (ii) the employee's parent, adoptive parent, grandparent, child, adopted child, grandchild or sibling.

12 Statement of Conditions

12.1 An employer must give a worker a statement containing the following details at the start of employment –

- (a) the employer's name and address and the name of the SPWP;
- (b) the tasks or job that the worker is to perform; and
- (c) the period for which the worker is hired or, if this is not certain, the expected duration of the contract;
- (d) the worker's rate of pay and how this is to be calculated;
- (e) the training that the worker will receive during the SPWP.

	<p>12.2 An employer must ensure that these terms are explained in a suitable language to any employee who is unable to read the statement.</p> <p>12.3 An employer must supply each worker with a copy of these conditions of employment.</p>
	<p>13 Keeping Records</p> <p>13.1 Every employer must keep a written record of at least the following –</p> <ul style="list-style-type: none"> (a) the worker's name and position; (b) in the case of a task-rated worker, the number of tasks completed by the worker; (c) in the case of a time-rated worker, the time worked by the worker; (d) payments made to each worker. <p>13.2 The employer must keep this record for a period of at least three years after the completion of the SPWP.</p>
	<p>14 Payment</p> <p>14.1 An employer must pay all wages at least monthly in cash or by cheque or into a bank account.</p> <p>14.2 A task-rated worker will only be paid for tasks that have been completed.</p> <p>14.3 An employer must pay a task-rated worker within five weeks of the work being completed and the work having been approved by the manager or the contractor having submitted an invoice to the employer.</p> <p>14.4 A time-rated worker will be paid at the end of each month.</p> <p>14.5 Payment must be made in cash, by cheque or by direct deposit into a bank account designated by the worker.</p> <p>14.6 Payment in cash or by cheque must take place –</p> <ul style="list-style-type: none"> (a) at the workplace or at a place agreed to by the worker; (b) during the worker's working hours or within fifteen minutes of the start or finish of work; (c) in a sealed envelope which becomes the property of the worker. <p>14.7 An employer must give a worker the following information in writing –</p> <ul style="list-style-type: none"> (a) the period for which payment is made; (b) the numbers of tasks completed or hours worked; (c) the worker's earnings; (d) any money deducted from the payment; (e) the actual amount paid to the worker. <p>14.8 If the worker is paid in cash or by cheque, this information must be recorded on the envelope and the worker must acknowledge receipt of payment by signing for it</p> <p>14.9 If a worker's employment is terminated, the employer must pay all monies owing to that worker within one month of the termination of employment.</p>
	<p>15 Deductions</p> <p>15.1 An employer may not deduct money from a worker's payment unless the deduction is required in terms of a law.</p> <p>15.2 An employer must deduct and pay to the SA Revenue Services any income tax that the worker is required to pay.</p> <p>15.3 An employer who deducts money from a worker's pay for payment to another person must pay the money to that person within the time period and other requirements specified in the agreement law, court order or arbitration award concerned.</p> <p>15.4 An employer may not require or allow a worker to –</p> <ul style="list-style-type: none"> (a) repay any payment except an overpayment previously made by the employer by mistake; (b) state that the worker received a greater amount of money than the employer actually paid to the worker; or (f) pay the employer or any other person for having been employed.
	<p>16 Health and Safety</p> <p>16.1 Employers must take all reasonable steps to ensure that the working environment is healthy and safe.</p> <p>16.2 A worker must –</p> <ul style="list-style-type: none"> (a) work in a way that does not endanger his/her health and safety or that of any other person;

	<ul style="list-style-type: none"> (b) obey any health and safety instruction; (c) obey all health and safety rules of the SPWP; (d) use any personal protective equipment or clothing issued by the employer; (e) report any accident, near-miss incident or dangerous behaviour by another person to their employer or manager.
	<p>17 Compensation for Injuries and Diseases</p> <p>17.1 It is the responsibility of the employers (other than a contractor) to arrange for all persons employed on a SPWP to be covered in terms of the Compensation for Occupational Injuries and Diseases Act, 130 of 1993.</p> <p>17.2 A worker must report any work-related injury or occupational disease to their employer or manager.</p> <p>17.3 The employer must report the accident or disease to the Compensation Commissioner.</p> <p>17.4 An employer must pay a worker who is unable to work because of an injury caused by an accident at work 75% of their earnings for up to three months. The employer will be refunded this amount by the Compensation Commissioner. This does NOT apply to injuries caused by accidents outside the workplace such as road accidents or accidents at home.</p>
	<p>18 Termination</p> <p>18.1 The employer may terminate the employment of a worker for good cause after following a fair procedure.</p> <p>18.2 A worker will not receive severance pay on termination.</p> <p>18.3 A worker is not required to give notice to terminate employment. However, a worker who wishes to resign should advise the employer in advance to allow the employer to find a replacement.</p> <p>18.4 A worker who is absent for more than three consecutive days without informing the employer of an intention to return to work will have terminated the contract. However, the worker may be re-engaged if a position becomes available for the balance of the 24-month period.</p> <p>18.5 A worker who does not attend required training events, without good reason, will have terminated the contract. However, the worker may be re-engaged if a position becomes available for the balance of the 24-month period.</p>
	<p>19 Certificate of Service</p> <p>19.1 On termination of employment, a worker is entitled to a certificate stating –</p> <ul style="list-style-type: none"> (a) the worker's full name; (b) the name and address of the employer; (c) the SPWP on which the worker worked; (d) the work performed by the worker; (e) any training received by the worker as part of the SPWP; (f) the period for which the worker worked on the SPWP; (g) any other information agreed on by the employer and worker.

Part 1: Contract Data completed by the Employer

Clause	Data								
1.1.1.13	The Defects Liability Period is 12 months								
1.1.1.14	The time for achieving Practical Completion is 4 months								
1.1.1.15	The name of the Employer is Moretele Local Municipality								
1.1.1.26	The Pricing Strategy of a Re-measurement Contract shall apply								
1.2.1.2	<p>The address of the Employer is:</p> <p>Moretele Local Municipality Physical Address 4065 Mathibestad</p> <p>Postal address Private Bag X 367 0404</p> <p>Contact numbers: Tel: 012 716 1300 Fax: 012 716 9999</p>								
1.1.1.16	The name of the Employers Agent is: Tshashu Consulting and Project Managers								
1.2.1.2	<p>The address of the Employers Agent is:</p> <p><u>Physical address:</u></p> <p>The Village Block C First Floor Corner Oberon & Glenwood Roads Pretoria,0043</p> <p>e-mail address: admin@tsconsulting.co.za</p> <p>Tel/Fax: 012 348 1896 Cell: 072 180 7396</p>								
3.3.1	<p>The Employers Agent shall obtain the specific approval of the Employer before executing any of his functions or duties according to the following table:</p> <table border="1"> <thead> <tr> <th>GCC Clause No</th> <th>Description</th> <th>Requires EWA*</th> <th>Delegated to ER*</th> </tr> </thead> <tbody> <tr> <td>3.3.1</td> <td>Employers Representative Agent's appointment and termination</td> <td>Y</td> <td></td> </tr> </tbody> </table>	GCC Clause No	Description	Requires EWA*	Delegated to ER*	3.3.1	Employers Representative Agent's appointment and termination	Y	
GCC Clause No	Description	Requires EWA*	Delegated to ER*						
3.3.1	Employers Representative Agent's appointment and termination	Y							

Clause	Data			
	3.3.4	Employers Agent's Representative acting on Engineer's behalf	Y	
	4.5.4	Payment for notices and fees	Y	
	4.7.1	Fossils, etc on Site	Y	
	5.7.2	Work at night	Y	
	5.7.3	Acceleration of rate of progress	Y	
	5.7.3	Payment for acceleration	Y	
	5.9.1	Instructions and drawings on Commencement Date		Y
	5.11.1	Suspension of the Works		Y
	5.11.3	Proceeding with Works after suspension	Y	
	5.12.4	Acceleration instead of extension of time	Y	
	5.13.2	Reduction in penalty		Y
	6.3.1	Variation orders	Y	
	6.3.2.1	Confirmation of a Variation Order	Y	
	6.4.1.4	Day works as a Variation Order	Y	
	6.5.2	Materials for day works	Y	
	6.8.2	Contract Prise Adjustment to apply	Y	
	6.8.3	Price adjustment for special material	Y	
	6.8.4	Costs due to changes in legislation	Y	
	6.11.1	Variations exceeding 20%		Y
	8.2.2.2	Damage due to excepted risks		Y
	10.1.5	Consultation on Contractor's claim	Y	Y
	10.1.5	Ruling on Contractor's claim	Y	N
	<p>*The following abbreviations apply:</p> <p>EAR Employers Agent's Representative</p> <p>EAWA Employers Agent's Written Action</p> <p>N No</p> <p>NA Not Applicable</p> <p>Y Yes</p>			
4.9.1	<p>The Contractor shall deliver to the Employers Agent's, on a monthly basis, a detailed inventory of Construction Equipment kept on Site, full particulars given for each day of the month. Distinction shall be made between Owned Equipment and Hired Equipment as well as Equipment in working order and Equipment out of order. Such inventory shall be submitted by the seventh day of the month following the month to be reported.</p>			

Clause	Data
4.10.2	The Contractor shall deliver to the Employers Agent's, on a monthly basis, a return in detail of supervisory staff and the number of categorized classes of labour employed each day for the said period by the Contractor for execution of the Contract. Such return shall be submitted by the seventh day of the month following the month to be reported.
5.3.1	<p>The documentation required before commencement with Works execution are:</p> <p>Health and Safety Plan (Refer to Clause 4.3)</p> <p>A signed Agreement between the Employer and the Contractor for the Works to be completed by the Contractor in terms of the provisions of Section 37(2) of the Occupational Health and Safety Act (Act No.85 of 1993) and the Construction Regulations promulgated thereunder (Refer to Clause 4.3).</p> <p>Proof of payment to the Employer, that the Contractor has paid all contributions required in terms of the Compensation for Occupational Injuries and Diseases Act, No 130 of 1993 (Refer to Clause 4.3).</p> <p>Initial programme (Refer to Clause 5.6).</p> <p>Security (Refer to Clause 6.2).</p> <p>Insurance (Refer to Clause 8.6).</p>
5.3.2	The time to submit the documentation required before commencement with Works execution is 14 Days .
5.4.2	The access and possession of Site shall not be exclusive to the Contractor but shall be as set out elsewhere in the Contract.
5.8.1	<p>The non-working Days are Sundays.</p> <p>The special non-working Days are:</p> <p>Statutory public holidays; and</p> <p>All annual year-end shutdown periods as recommended by the South African Federation of Civil Engineering Contractors (SAFCEC),</p> <p>and which commence after the Commencement Date and which commence before the Due Completion Date.</p>
5.13.1	The penalty for failing to complete the Works is 0,1 percent of contract price per calendar day.
5.16.3	The latent defect period is 10 years, commencing on the Day after the date of certification of Practical Completion.
6.5.1.2.3	<p>The percentage allowance to cover overhead charges is:</p> <p>50 per cent for labour; and</p> <p>15 per cent for materials.</p>

Clause	Data
6.8.2	<p>Contract Price Adjustment: The contract shall be subject to Contract Price Adjustment.</p> <p>The value of the certificates issued shall be adjusted in accordance with the Contract Price Adjustment Schedule included in the General Conditions of Contract.</p> <p>The value of "x" is 0.15</p> <p>The values of the coefficients are:</p> <p>a = 0.25 Labour b = 0.3 Contractor's equipment c = 0.35 Material d = 0.1 Fuel</p> <p>The Province wherein the larger part of the Site is located is Hamanskraal.</p> <p>The applicable industry for the Producer Price Index for material is Diesel</p> <p>The area for the Producer Price Index for fuel is Example Fuel index area</p> <p>The base month is OCTOBER 2023.</p>
6.8.3	
6.10.1.5	The percentage advance on materials not yet built into the Permanent Works is 80%. Proof of ownership is required.
6.10.3	<p>The limit of retention money is 10% of the value of the Contract Price.</p> <p>A Retention Money Guarantee is compulsory.</p> <p>A penalty will be applied for non-delivery of the Retention Money Guarantee as required. The penalty will be 10% of the value of the completion Retention Money Amount per calendar month for late delivery of the said Retention Money Guarantee.</p>
8.6.1.1.2	The value of Plant and materials supplied by the Employer to be included in the insurance sum is nil .
8.6.1.1.3	The amount to cover professional fees for repairing damage and loss to be included in the insurance sum is a maximum of 0% of the Contract Sum.
8.6.1.3	The limit of indemnity for liability insurance is equal to the contract amount.
10.5.1	Dispute resolution shall be by standing adjudication, use GCC 2015, Appendix 5.
10.7.1	The determination of disputes shall be by arbitration.
	<p>Payment for labour-intensive component of the works</p> <p><i>Payment for works identified in the Scope of Works as being labour-intensive shall only be made in accordance with the provisions of the Contract if the works are constructed strictly in accordance with the provisions of the Scope of Work. Any payment for such works shall not relieve the Contractor in any way from his obligations either in contract or in delict.</i></p>

Clause	Data
	<p>Linkage of payment for labour-intensive component of works to submission of project data</p> <p><i>The Contractor's payment invoices shall be accompanied by labour information for the corresponding period in a format specified by the employer. If the contractor chooses to delay submitting payment invoices, labour returns shall still be submitted as per frequency and timeframe stipulated by the Employer. The contractor's invoices shall not be paid until all pending labour information has been submitted.</i></p>
	<p>Applicable Labour Laws</p> <p><i>The current Ministerial Determination (also downloadable at www.epwp.gov.za), Expanded Public Works Programmes, issued in terms of the Basic Condition of Employment Act of 1997 by the Minister of Labour in Government Notice, shall apply to works described in the scope of work as being labour-intensive and which are undertaken by unskilled workers.</i></p>

C.1.2.1.2.2 Variations to the General Conditions of Contract

Clause	Data
2.5.1	<p>Cession <i>Amend Clause 2.5.1 as follows:</i></p> <p><i>Delete the words "without the written consent of the other"</i></p>
5.14.5.1	<p>Consequences of Completion <i>Amend Clause 5.14.5.1 as follows:</i></p> <p><i>In the second line, substitute the word 'Guarantor' with 'Contractor'.</i></p>
6.2	<p>Security <i>Replace Sub-Clauses 6.2.1 and 6.2.2 with:</i></p> <p>"The Contractor shall deliver to the Employer within such time as may be stated in the Contract Data, a Demand Guarantee, of an Insurance Company registered in terms of the Short-term Insurance Act (Act 53 of 1998) or of a registered Commercial Bank, in a sum equal to the amount stated in the Contract Data. The Demand Guarantee shall be issued by an entity subject to the approved of the Employer, and shall conform in all respects to the format contained in the Contract Data.</p> <p>The security to be provided by the Contractor shall be a Demand Guarantee of 10% of the Contract Sum.</p> <p>Wherever a joint venture constitutes the contracting party, the Demand Guarantee shall be issued on behalf of the joint venture.</p> <p>Failure to produce an acceptable Demand Guarantee within the period stated in the Contract Data, is a fundamental breach of Contract, entitling the Employer to cancel the Contract by due notice in terms of Clause 9.2 with specific reference to Sub-clause 9.2.2.5 as amended in the Contract Data."</p>
6.3	<p>Variations <i>Amend Clause 6.3, as follows:</i></p> <p><i>In the first paragraph, third line, after the words "or for any reason appropriate", add the phrase</i></p> <p><i>", including the limiting of contract expenditure so as not to exceed the Employer's budgeted project funding, "</i></p> <p><i>Add the following phrase to the last paragraph of Clause 6.3.1.6, after the words "ascertaining the amount of the Contract Price":</i></p> <p><i>", and no such variation shall give reason for consideration of any claim in terms of Clause 6.11."</i></p>
6.3.2	<p>Orders for Variations to be in writing <i>Omit the words "Provided that" under Clause 6.3.2 and omit Clause 6.3.2.1.</i></p>

Clause	Data
6.9.2	<p>Definition of “materials” <i>Amend Clause 6.9.2, as follows:</i> <i>Substitute the word ‘plant’ with ‘Plant’.</i></p>
6.10.1	<p>Interim Payments <i>Amend Clause 6.10.1.5 as follows:</i> <i>In the third line, add the words ‘not yet’ before the words ‘built into’</i></p>
6.10.5	<p>Payment of retention money <i>Amend Clause 6.10.5 as follows:</i> <i>In the second line, add the words ‘, if any,’ after the words ‘Defects Liability Period’</i></p>
6.10.6	<p>Set-off and delayed payments <i>Amend Clause 6.10.6.2 as follows:</i> <i>Delete the words ‘Contractor’s Bank’ and substitute with the words ‘Employer’s Bank’</i></p>
6.11	<p>Variations exceeding 15 per cent <i>Replace the marginal heading with:</i> “Variations exceeding 20 per cent” <i>Replace “15 per cent” with “20 per cent” in the text of this Sub-Clause</i></p>
7.8.2	<p>Cost of making good of defects <i>Amend Clause 7.8.2.1 as follows:</i> <i>In the first line, correct the spelling of ‘therefore’.</i></p>
8.3.1	<p>Excepted risks <i>Amend Clause 8.3.1.12 as follows:</i> <i>In the second line, delete the words ‘Employer or any of their’ and substitute with ‘or any of its’.</i></p>
8.6.6	<p>Contractor to produce proof of payment “<i>The Contractor shall before commencement of the Works produce to the Employer’s Agent:</i></p> <p class="list-item-l1">8.6.6.1 <i>The policies by which the insurances are effected,</i></p> <p class="list-item-l1">8.6.6.2 <i>Proof that due payment of all premiums there under, covering the full required period has been made, and</i></p> <p class="list-item-l1">8.6.6.3 <i>Proof of continuity of the policies for the required period.</i></p>

Clause	Data
	<p>Should, during the currency of the Contract, the required period of insurance be extended for any reason, the Contractor shall timeously extend (so as to maintain) the said insurances for the full extended duration.</p> <p>The Employer's Agent shall be empowered to withhold all payment certificates until the Contractor has complied with his obligations in terms of this Clause 8.6.6."</p>
8.6.7	<p>Remedy on Contractor's failure to insure</p>
	<p><i>Delete sub-clause 8.6.7 and substitute with:</i></p> <p>"Failure on the part of the Contractor to effect and keep in force any of the insurances referred to in Clause 8.6.1 and its sub-clauses, is a fundamental breach of Contract, entitling the Employer to cancel the Contract by due notice in terms of Clause 9.2 and with specific reference to sub-clause 9.2.2, as amended in the Contract Data."</p>
9.1.2	<p>State of emergency</p> <p><i>In the fourth line, delete the words 'supply of' and substitute with 'availability of'.</i></p>
9.2	<p>Termination by Employer</p> <p><i>Delete the contents of Clause 9.2 and substitute with:</i></p> <p>"9.2.1 The Employer may terminate the Contract by written notice to the Contractor if:</p> <p>9.2.1.1 Sequestration of the Contractor's estate is ordered by a Court with due jurisdiction, or</p> <p>9.2.1.2 The Contractor publishes a notice of surrender or presents a petition for the surrender of his estate as insolvent, or makes a compromise with his creditors, or assigns in favour of his creditors, or agrees to carry out the Contract under the supervision of a committee representing his creditors, or (being a company) goes into liquidation, whether provisionally or finally (other than a voluntary liquidation for the purpose of amalgamation or reconstruction), or if the Contractor assigns the Contract without having first obtained the Employer's consent in writing, or if execution is levied on his goods, or</p> <p>9.2.1.3 The Contractor, or anyone on his behalf, or in his employ, offers to any person in the employ of the Employer or the Engineer, a gratuity or reward or commission, or</p>

Clause	Data
	<p>9.2.1.4 The Contractor furnished materially inaccurate information in his Tender, which had a bearing on the award of the Contract, or</p> <p>9.2.1.5 The Contractor has abandoned the Contract.</p> <p>9.2.2 If the Contractor:</p> <p>9.2.2.1 Has failed to commence the Works in terms of Clause 10 hereof, or has suspended the progress of the Works for fourteen (14) days after receiving from the Engineer written notice to proceed, or</p> <p>9.2.2.2 Has failed to provide the Guarantee in terms of Clause 7 within the time stipulated in the Contract Data, or</p>
	<p>9.2.2.3 Has failed to proceed with the Works with due diligence, or</p> <p>9.2.2.4 Has failed to remove materials from the Site or to pull down and replace work within fourteen (14) days after receiving from the Engineer written notice that the said materials or work have been condemned and rejected by the Engineer in terms of these conditions, or</p> <p>9.2.2.5 Is not executing the Works in accordance with the Contract, or is neglecting to carry out his obligations under the Contract, or</p>
	<p>9.2.2.6 Has, to the detriment of good workmanship or in defiance of the Engineer's instructions to the contrary, sublet any part of the Contract, or</p> <p>9.2.2.7 Has assigned the Contract or any part thereof without the Employer's consent in writing,</p> <p>then the Employer may give the Contractor 14 days' notice to rectify the default, and if the Contractor fails to rectify the default in said 14 days, then, without further notice, notify the Contractor in writing of the termination of the Contract and expel the Contractor and order the Contractor to vacate the site within 24 hours of issue of the Notice of Termination and to hand the Site over to the Employer, and the Employer</p>

Clause	Data
	<p>may then enter upon the Site and the Works without affecting the rights and powers conferred on the Employer or the Engineer by the Contract and the Employer may himself complete the Works or may employ another contractor to complete the Works, and the Employer or such other contractor may use for such completion so much of the Construction Equipment, Temporary Works and materials brought onto the Site by the Contractor as the Employer may think proper, and the Employer may at any time sell any of the said Construction Equipment, Temporary Works and unused materials and apply the proceeds of sale towards payment of any sums that may be due or become due to the Employer by the Contractor under the Contract. In such circumstances the Contractor shall forthwith vacate the Site and shall not be entitled to remain on the Site on the grounds that he is entitled to do so on a right of retention until amounts due to him have been paid, neither will the Contractor be entitled to any further payments in terms of this Contract.</p>
	<p>9.2.3 If the Contractor, having been given notice to rectify a default in terms of 9.2.2 above, rectifies said default, but later repeats the same or substantially the same default, then the Employer may notify the Contractor of the immediate termination of the Contract, and proceed as stated in the paragraph following the word 'writing' in Clause 9.2.2.7 above.</p> <p>9.2.4 Should the amounts that the Employer must pay to complete the Works, exceed the sum that would have been payable to the Contractor on due completion by him, then the Contractor shall upon demand pay to the Employer the difference, and it shall be deemed a debt due by the Contractor to the Employer and shall be recoverable accordingly. Provided that should the Contractor on demand not pay the amount of such excess to the Employer, such sum may be determined and deducted by the Employer from any sum due to or that may become due to the Contractor under this or any previous or subsequent contract between the Contractor and the Employer."</p>

C.1.2.1.2.3 Additional clauses to the General Conditions of Contract:

Clause	Data
1.1	<p>Definitions</p> <p><i>Add the following at the end of Sub-Clause 1.1.1:</i></p> <p>1.1.1.35 “Client”, as used in the Occupational Health and Safety Act - Construction Regulations, means Employer.</p> <p>1.1.1.36 “Principal Contractor”, as used in the Occupational Health and Safety Act - Construction Regulations, means Contractor.</p>
4.12	<p>Contractor's superintendence</p> <p><i>Add the following sub-clause 4.12.4 to Clause 4.12:</i></p> <p>“Where a form is included in the Contract Data for this purpose, the Tenderer shall fill in the name of the person he proposes to entrust with the post of Construction Manager on this Contract in the space provided therefore. Previous experience of this person on work of a similar nature during the past five (5) years is to be entered on the form.</p> <p>The Contractor's Construction Manager shall be on Site at all times when work is being performed.</p> <p>The person shall be subject to approval of the Employers Agent's in writing and shall not be replaced or removed from Site without the written approval of the Employers Agent”.</p>
5.6	<p>Programme</p> <p><i>Add the following sub-clause 5.6.6 to Clause 5.6:</i></p> <p>“Failure on the part of the Contractor to deliver to the Employers Agent, the</p> <ul style="list-style-type: none"> • programme of the Works in terms of Clause 5.6.1 and • supporting documents in terms of Clause 5.6.2 <p>Within the period stated in the Contract Data, shall be sufficient cause for the Engineer to retain 25 per centum of the value of the Fixed Charge and Value-related items in assessment of amounts due to the Contractor, until the Contractor has submitted aforementioned first Programme of the Works and Supporting Documents”.</p>
5.9.7	<p>Employers Agent's to approve Contractor's Designs and Drawings</p> <p><i>Add the following at the end of Sub-Clause 5.9.7</i></p> <p>“All designs, calculations, drawings and operation and maintenance manuals shall be fully endorsed by a third party registered engineer, accomplished in such specific field of practice and the cost thereof shall be borne solely by the Contractor.</p> <p>Once the alternative design has been approved, the Contractor shall indemnify and hold harmless the Employers Agent's, the Employer, their agents and assigns, against all claims howsoever arising out of the said design, whether in contract or delict”.</p>

Clause	Data
5.11	<p>Suspension of the Works</p> <p><i>Add the following sub-clause 5.11.7 to Clause 5.11:</i></p> <p>“If the Contractor does not receive from the Employer the amount due under an Interim Payment Certificate within 28 days after expiry of the time stated in sub-clause 6.10.4 within which payment is to be made (except for deductions in accordance with sub-clauses 6.10.1.6 and 6.10.1.7), the Contractor may, after giving 14 days’ notice to the Employer, suspend the progress of the Works.</p> <p>The Contractor’s action shall not prejudice his entitlements to a claim in terms of Clause 10.1 and to cancellation of the Contract in terms of Clause 9.3.</p> <p>If the Contractor subsequently receives full payment of the amount due under such Interim Payment Certificate before giving a notice of cancellation of the Contract, the Contractor shall resume normal working as soon as is reasonably practicable.”</p>
5.12	<p>Extension of Time for Practical Completion</p> <p><i>Add the following at the end of Sub-Clause 5.12.2.2:</i></p> <p>“The extension of time to be allowed due to abnormal rainfall shall be calculated separately for each calendar month or part thereof in accordance with the following formula:</p> $V = (Nw - Nn) + \left(\frac{Rw - Rn}{X} \right)$ <p>where</p> <p>V = Extension of time in calendar days for the calendar month under consideration</p> <p>Nw = Actual number of days during the calendar month on which a rainfall of 10 mm or more has been recorded</p> <p>Rw = Actual recorded rainfall for the calendar month</p> <p>Rn = Average rainfall for the calendar month, as derived from existing rainfall records</p> <p>X = 20</p>
	<p>The rainfall records which shall provisionally be accepted for calculation purposes are:</p> <p>Based on records taken at: Rainfall Station : Moretele Years of record: 2006 – 2016</p>

Clause	Data																																																																																																																																																																																																																																									
<p>Table 1 – RAINFALL RECORDS FOR PERIOD: 2006– 2016</p> <p>RAINFALL STATION: HAMASKRAAL Lat: 23.8570 Lon: 29.451 Height 1226 m</p> <p>Average No of Days with Rainfall exceeding 10mm: 9.8 days/year</p> <p>Average Rainfall: 488.6 mm/year station no: 0677802BX</p> <table border="1"> <thead> <tr> <th>MON</th><th>AVE</th><th>ST</th><th>N DAY</th><th>NUM</th><th>1</th><th>5.1</th><th>10.1</th><th>20.1</th><th>50.1</th><th>100.1</th><th>MAX R</th><th>MAX RAIN</th></tr> <tr> <th>MON</th><th></th><th>DEV</th><th>RAIN</th><th>MON</th><th>5</th><th>10</th><th>20</th><th>50</th><th>100</th><th>900</th><th>DAY</th><th>DATE</th></tr> </thead> <tbody> <tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr> <tr><td>MON</td><td>AVE</td><td>ST</td><td>N DAY</td><td>NUM</td><td>1</td><td>5.1</td><td>10.1</td><td>20.1</td><td>50.1</td><td>100.1</td><td>MAX R</td><td>MAX RAIN</td></tr> <tr><td>MON</td><td></td><td>DEV</td><td>RAIN</td><td>MON</td><td>5</td><td>10</td><td>20</td><td>50</td><td>100</td><td>900</td><td>DAY</td><td>DATE</td></tr> <tr><td>JAN</td><td>65.9</td><td>39.3</td><td>65.9</td><td>11</td><td>3.4</td><td>2.1</td><td>1.3</td><td>0.7</td><td>0</td><td>0</td><td>38</td><td>1/18/2013</td></tr> <tr><td>FEB</td><td>47.3</td><td>49.7</td><td>47.3</td><td>11</td><td>1.6</td><td>0.9</td><td>1.1</td><td>0.6</td><td>0</td><td>0</td><td>49</td><td>2/26/2006</td></tr> <tr><td>MAR</td><td>58.4</td><td>33.2</td><td>58.4</td><td>11</td><td>3</td><td>1.3</td><td>1.1</td><td>0.7</td><td>0.1</td><td>0</td><td>51.5</td><td>3/27/2006</td></tr> <tr><td>APR</td><td>43.3</td><td>46.6</td><td>43.3</td><td>11</td><td>1.5</td><td>1</td><td>0.7</td><td>0.5</td><td>0.1</td><td>0</td><td>68</td><td>4/4/2011</td></tr> <tr><td>MAY</td><td>10.4</td><td>14</td><td>10.4</td><td>11</td><td>0.5</td><td>0.4</td><td>0.3</td><td>0.1</td><td>0</td><td>0</td><td>29.2</td><td>5/8/2009</td></tr> <tr><td>JUN</td><td>1.7</td><td>3.6</td><td>1.7</td><td>11</td><td>0.3</td><td>0</td><td>0.1</td><td>0</td><td>0</td><td>0</td><td>12</td><td>6/10/2009</td></tr> <tr><td>JUL</td><td>2.4</td><td>4.3</td><td>2.4</td><td>11</td><td>0.3</td><td>0.1</td><td>0.1</td><td>0</td><td>0</td><td>0</td><td>12.1</td><td>7/4/2007</td></tr> <tr><td>AUG</td><td>2.3</td><td>5.6</td><td>2.3</td><td>11</td><td>0.2</td><td>0</td><td>0.1</td><td>0</td><td>0</td><td>0</td><td>19.2</td><td>8/15/2011</td></tr> <tr><td>SEP</td><td>6.6</td><td>8.2</td><td>6.6</td><td>11</td><td>0.4</td><td>0.4</td><td>0.1</td><td>0.1</td><td>0</td><td>0</td><td>22.5</td><td>9/4/2015</td></tr> <tr><td>OCT</td><td>48.1</td><td>29.5</td><td>48.1</td><td>11</td><td>1.5</td><td>0.7</td><td>1.4</td><td>0.6</td><td>0</td><td>0</td><td>38.2</td><td>10/29/2009</td></tr> <tr><td>NOV</td><td>97.7</td><td>40.5</td><td>97.7</td><td>11</td><td>3.1</td><td>2</td><td>1.3</td><td>1.5</td><td>0.2</td><td>0</td><td>65.5</td><td>11/12/2008</td></tr> <tr><td>DEC</td><td>104.6</td><td>56.3</td><td>104.6</td><td>11</td><td>3.8</td><td>1</td><td>1.7</td><td>1.9</td><td>0.1</td><td>0</td><td>55</td><td>12/16/2014</td></tr> <tr><td>YR</td><td>488.6</td><td></td><td>67.9</td><td></td><td>19.5</td><td>9.8</td><td>9.2</td><td>6.8</td><td>0.5</td><td>0</td><td>488.6</td><td></td></tr> </tbody> </table>	MON	AVE	ST	N DAY	NUM	1	5.1	10.1	20.1	50.1	100.1	MAX R	MAX RAIN	MON		DEV	RAIN	MON	5	10	20	50	100	900	DAY	DATE														MON	AVE	ST	N DAY	NUM	1	5.1	10.1	20.1	50.1	100.1	MAX R	MAX RAIN	MON		DEV	RAIN	MON	5	10	20	50	100	900	DAY	DATE	JAN	65.9	39.3	65.9	11	3.4	2.1	1.3	0.7	0	0	38	1/18/2013	FEB	47.3	49.7	47.3	11	1.6	0.9	1.1	0.6	0	0	49	2/26/2006	MAR	58.4	33.2	58.4	11	3	1.3	1.1	0.7	0.1	0	51.5	3/27/2006	APR	43.3	46.6	43.3	11	1.5	1	0.7	0.5	0.1	0	68	4/4/2011	MAY	10.4	14	10.4	11	0.5	0.4	0.3	0.1	0	0	29.2	5/8/2009	JUN	1.7	3.6	1.7	11	0.3	0	0.1	0	0	0	12	6/10/2009	JUL	2.4	4.3	2.4	11	0.3	0.1	0.1	0	0	0	12.1	7/4/2007	AUG	2.3	5.6	2.3	11	0.2	0	0.1	0	0	0	19.2	8/15/2011	SEP	6.6	8.2	6.6	11	0.4	0.4	0.1	0.1	0	0	22.5	9/4/2015	OCT	48.1	29.5	48.1	11	1.5	0.7	1.4	0.6	0	0	38.2	10/29/2009	NOV	97.7	40.5	97.7	11	3.1	2	1.3	1.5	0.2	0	65.5	11/12/2008	DEC	104.6	56.3	104.6	11	3.8	1	1.7	1.9	0.1	0	55	12/16/2014	YR	488.6		67.9		19.5	9.8	9.2	6.8	0.5	0	488.6	
MON	AVE	ST	N DAY	NUM	1	5.1	10.1	20.1	50.1	100.1	MAX R	MAX RAIN																																																																																																																																																																																																																														
MON		DEV	RAIN	MON	5	10	20	50	100	900	DAY	DATE																																																																																																																																																																																																																														
MON	AVE	ST	N DAY	NUM	1	5.1	10.1	20.1	50.1	100.1	MAX R	MAX RAIN																																																																																																																																																																																																																														
MON		DEV	RAIN	MON	5	10	20	50	100	900	DAY	DATE																																																																																																																																																																																																																														
JAN	65.9	39.3	65.9	11	3.4	2.1	1.3	0.7	0	0	38	1/18/2013																																																																																																																																																																																																																														
FEB	47.3	49.7	47.3	11	1.6	0.9	1.1	0.6	0	0	49	2/26/2006																																																																																																																																																																																																																														
MAR	58.4	33.2	58.4	11	3	1.3	1.1	0.7	0.1	0	51.5	3/27/2006																																																																																																																																																																																																																														
APR	43.3	46.6	43.3	11	1.5	1	0.7	0.5	0.1	0	68	4/4/2011																																																																																																																																																																																																																														
MAY	10.4	14	10.4	11	0.5	0.4	0.3	0.1	0	0	29.2	5/8/2009																																																																																																																																																																																																																														
JUN	1.7	3.6	1.7	11	0.3	0	0.1	0	0	0	12	6/10/2009																																																																																																																																																																																																																														
JUL	2.4	4.3	2.4	11	0.3	0.1	0.1	0	0	0	12.1	7/4/2007																																																																																																																																																																																																																														
AUG	2.3	5.6	2.3	11	0.2	0	0.1	0	0	0	19.2	8/15/2011																																																																																																																																																																																																																														
SEP	6.6	8.2	6.6	11	0.4	0.4	0.1	0.1	0	0	22.5	9/4/2015																																																																																																																																																																																																																														
OCT	48.1	29.5	48.1	11	1.5	0.7	1.4	0.6	0	0	38.2	10/29/2009																																																																																																																																																																																																																														
NOV	97.7	40.5	97.7	11	3.1	2	1.3	1.5	0.2	0	65.5	11/12/2008																																																																																																																																																																																																																														
DEC	104.6	56.3	104.6	11	3.8	1	1.7	1.9	0.1	0	55	12/16/2014																																																																																																																																																																																																																														
YR	488.6		67.9		19.5	9.8	9.2	6.8	0.5	0	488.6																																																																																																																																																																																																																															

The factor (Nw - Nn) shall be considered to represent a fair allowance for days during which rainfall exceeds 10 mm and the factor (Rw - Rn)/x shall be considered to represent a fair allowance for those days when rainfall does not exceed 10 mm but wet conditions prevent or disrupt work.

The total extension of time shall be the algebraic sum of all monthly totals for the contract period, but if the algebraic sum is negative the time for completion shall not be reduced due to subnormal rainfall. Extensions of time for a part of a month shall be calculated using pro rata values of Nn and Rn."

For this project the rainfall formula will only apply as background information, or dispute resolution. Extension of time for rainfall will only be granted on Actual Delays experienced; noted and agreed upon by the engineer.

Clause	Data
6.10	<p>Payments</p>
	<p><i>Add the following at the end of Sub-Clause 6.10.1:</i></p> <p>“The Contractor shall complete the ‘Contractor’s Monthly Report Schedule’, which pro forma documentation is obtainable from the Employer’s Agent. Pursuant to Sub-Clause (1), these, duly signed by all concerned, together with the Contractor’s statement and a VAT invoice in original format are to be submitted to the Employer’s Agent. Issue by the Employer’s Agent to the Employer and Contractor of any signed payment certificate is conditional to this information being fully endorsed, accurately and timeously submitted to the Employer’s Agent r”.</p> <p><i>Add the following at the end of Sub-Clause 6.10.1.5:</i></p>
9.3	<p>“All documentary evidence of such materials shall be unambiguous with respect to ownership having fully passed to the Contractor on or before the date of submittal of the Contractor’s monthly statement.</p> <p>Should the Contractor fail to supply unambiguous documentary evidence, he shall, prior to submittal of his monthly statement, deliver to the Employer a Guarantor Guarantee in the form contained in the Appendices to the Contract Data.”</p> <p>Termination by the Contractor</p> <p><i>Add the following at the end of Sub-Clause 9.3:</i></p> <p>9.3.5“In addition to, or as an alternative to the rights to termination contained in this Clause 9.3, the Contractor may notify the default to the Employer, with a copy to the Employer’s Agent, and if the default is not rectified within 10 days the Contractor may suspend progress of the works until a date 7 days after the default is rectified. The Contractor shall be entitled to extension of time to the extent of delay caused by or resulting from such suspension, and to payment of additional costs caused by or resulting from the suspension. Such extension of time and additional costs shall be promptly ascertained by the Employer’s Agent, who shall then grant the extension of time and include the additional costs in all future payment certificates. Such suspension, extension of time and/or payment of additional costs, shall not prejudice the Contractor’s rights to cancel the contract.”</p>

C.1.2.2 Part 2: Data provided by the Contractor

The General Conditions of Contract, as specified in Part 1, shall be used as a basis for this Data which is required to be completed.

Each item of data given below is cross-referenced to the clause in the Conditions of Contract to which it mainly applies.

Clause	Data
1.1.1.9	<p>The Name of the Contractor is:</p> <p>.....</p> <p>.....</p>
1.2.1.2	<p>The address of the Contractor is:</p> <p>Physical address:</p> <p>.....</p> <p>.....</p> <p>.....</p> <p>Postal address:</p> <p>.....</p> <p>.....</p> <p>.....</p> <p>e-mail address:</p> <p>Contact numbers:</p> <p>Corporate:</p> <p>Direct:</p> <p>Mobile:</p> <p>Fax:</p>
1.2.1.2	



MORETELE LOCAL MUNICIPALITY

C1.3 Form of Guarantee

Contract No. MLM/IDS/WRYC/W16/23-24

WHEREAS The **MORETELE LOCAL MUNICIPALITY** (hereinafter referred to as the Employer") entered into, a Contract with:

.....
(hereinafter called "the Contactor") on the day of 20.....
for the construction of **WATER RETICULATION AND YARD CONNECTIONS IN WARD 16**

AND WHEREAS it is provided by such Contract that the Contractor shall provide the Employer with security by way of a guarantee for the due and faithful fulfilment of such Contract by the Contractor;

AND WHEREAS has / have at the

request of the Contractor, agreed to give such guarantee;

NOW THEREFORE WE do hereby
guarantee and bind ourselves jointly and severally as Guarantor and Co-principal Debtors to the Employer
under renunciation of the benefits of division and execution for the due and faithful performance by the
Contractor of all the terms and conditions of the said Contract, subject to the following conditions:

1. The Employer shall, without reference and / or notice to us, have complete liberty of action to act in any manner authorized and/or contemplated by the terms of the said Contract, and/or to agree to any modifications, variations, alterations, directions or extensions of the completion date of the works under the said Contract, and that its rights under this guarantee shall in no way be prejudiced nor our liability hereunder be affected by reason of any steps which the Employer may take under such Contract, or of any modification, variation, alterations of the completion date which the Employer may make, give, concede or agree to under the said Contract.
2. This guarantee shall be limited to the payment of a sum of money.
3. The Employer shall be entitled, without reference to us, to release any guarantee held by it, and to give time to or compound or make any other arrangement with the Contractor.
4. This guarantee shall remain in full force and effect until the issue of the Certificate of Completion in terms of the Contract, unless we are advised in writing by the Employer before the issue of the said Certificate of his intention to institute claims, and the particulars thereof, in which event this guarantee shall remain in full force and effect until all such claims have been paid or liquidated.
5. Our totally hereunder all not exceed the Guaranteed Sum of liability. Rand (in words); R (in figures)

6. The Guarantor reserves the right to withdraw from this guarantee by depositing the Guaranteed Sum with the beneficiary, whereupon our liability hereunder shall cease.
7. We hereby choose our address for the serving of all notices for all purposes arising here from as
.....
.....
.....
.....
.....
.....

IN WITNESS WHEREOF this guarantee has been executed by us at
on this day of 20

Signature

Duly authorized to sign on behalf of

Address

As witnesses:

1

2



MORETELE LOCAL MUNICIPALITY

C1.4 Occupational Health and Safety

AGREEMENT IN TERMS OF THE OCCUPATIONAL HEALTH AND SAFETY ACT, 1993 (ACT NO 85 OF 1993)

THIS AGREEMENT IS made at

on the day of in the year

Between MORETELE LOCAL MUNICIPALITY (hereinafter called "the Employer") of the one part, herein represented by

In his capacity as

and delegate of the Employer in terms of the Employer's standard powers of delegation pursuant to the provisions of Act No 7 of 1998,

and

(hereinafter called "the Mandatory") of the other part, herein represented by

.....

In his capacity as

and being duly authorized by virtue of a resolution appended hereto as Annexure A;

WHEREAS the Employer requires certain works be constructed, viz **WATER RETICULATION AND YARD CONNECTIONS IN WARD 16** and has accepted a Tender by the Mandatory for the construction, completion and maintenance of such Works and whereas the Employer and the Mandatory have agreed to certain arrangements and procedures to be followed in order to ensure compliance by the Mandatory with the provisions of the Occupational Health and Safety Act, 1993 (Act 85 of 1993).

NOW THEREFORE THIS AGREEMENT WITNESSES AS FOLLOWS:

- 1 The Mandatory shall execute the work in accordance with the Contract Documents pertaining to this Contract.
- 2 This Agreement shall hold good from its Commencement Date, which shall be the date of a written notice from the Employer or engineer requiring him to commence the execution of the Works, to either -
 - (a) the date of the Final Certificate issued in terms of Clause 5.16.1 of the South African Institution of Civil Engineering General Conditions of Contract for construction work, 3rd Edition 2015 (hereinafter referred to as "the GCC"), or
 - (b) The date of termination of the Contract in terms of Clause 09 of the GCC.

3 The Mandatory declares himself to be conversant with the following:

- (a) All the requirements, regulations and standards of the Occupational Health and Safety Act (Act 85 of 1993), hereinafter referred to as "The Act", together with its amendments and with special reference to the following Sections of The Act:
 - (i) Section 8 : General duties of Employers to their employees
 - (ii) Section 9 : General duties of Employers and self-employed persons to persons other than employees
 - (iii) Section 37 : Acts or omissions by employees or mandatories
 - (iv) Sub-section 37(2) relating to the purpose and meaning of this Agreement
- (b) The procedures and safety rules of the Employer as pertaining to the Mandatory and to all his subcontractors.

4 In addition to the requirements of the ruling GCC (as amended by Special Condition of Contract section contained in this Contract Documents) and all relevant requirements of the above-mentioned document/s, the Mandatory agrees to execute all the Works forming part of this Contract and to operate and utilize all machinery, Plant and equipment in accordance with the Act.

5 The Mandatory is responsible for the compliance with the Act by all his subcontractors, whether or not selected and/or approved by the Employer.

6. The Mandatory warrants that all his and his subcontractors' workmen are covered in terms of the Compensation for Occupational Injuries and Diseases Act, 1993 (Act No 130 of 1993), which cover, shall remain in force whilst any such workmen are present on site. A letter of good standing from the Compensation Commissioner to this effect must be produced to the Employer upon signature of the agreement.

7. The Mandatory undertakes to ensure that he and/or subcontractors and/or their respective employers will at all times comply with the following conditions:

- a) The Mandatory shall assume the responsibility in terms of Section 16.1 of the Act. The Mandatory shall not delegate any duty in terms of Section 16.2 of this Act without the prior written approval of the Employer. If the Mandatory obtains such approval and delegates any duty in terms of section 16.2 a copy of such written delegation shall immediately be forwarded to the Employer.
- b) All incidents referred to in the Act shall be reported by the Mandatory to the Department of Labour as well as to the Employer. The Employer will further be provided with copies of all written documentation relating to any incident.
- c) The Employer hereby obtains an interest in the issue of any formal enquiry conducted in terms of section 32 of the Act into any incident involving the Mandatory and/or his employees and/or his subcontractors.

In witness thereof the parties hereto have set their signatures hereon in the presence of the subscribing witnesses:

<u>SIGNED FOR AND ON BEHALF OF THE EMPLOYER</u>	:
Witness	Witness
(Name)	(Name)
(Print)	(Print)
<u>SIGNED FOR AND ON BEHALF OF THE MANDATORY</u>	
Witness	Witness
(Name)	(Name)
(Print)	(Print)

ANNEXURE A

CERTIFICATE OF AUTHORITY FOR SIGNATORY TO AGREEMENT IN TERMS OF OCCUPATIONAL HEALTH AND SAFETY ACT, 1993 (ACT NO 85 OF 1993)

The signatory for the company that is the Contractor in terms of the above-mentioned Contract and the Mandatory in terms of the above-mentioned Act shall confirm his or her authority thereto by attaching to this page a duly signed and dated copy of the relevant resolution of the board of directors.

By resolution of the board of directors passed at a meeting held on 20.....,

Mr//Ms whose signature
appears below, has been duly authorised to sign the AGREEMENT IN TERMS OF THE
OCCUPATIONAL HEALTH AND SAFETY ACT, 1993 (ACT 85 OF 1993) on behalf of

SIGNED ON BEHALF OF THE COMPANY :

IN HIS/HER CAPACITY AS :

DATE :

SIGNATURE OF SIGNATORY :

WITNESS : WITNESS :

NAME (in capitals):..... NAME :



MORETELE LOCAL MUNICIPALITY

C2.1 Special Conditions of Contract

The following special conditions of contract, which include amendments to, omissions of or additions to certain clauses of the "General Conditions of Contract for Construction Works, Third Edition (2015)", shall be applicable to the works. In the case of conflict with the mentioned general conditions of contract, these special conditions of contract shall be binding and applicable to the contract.

Each clause with the prefix SCC shall refer to the concurrent clause in the general conditions of contract. Such clause shall substitute, supplement or amend the clause with the same number in the general conditions of contract. Where there is no such concurrent clause in the general conditions of contract the SCC clause shall be numbered as a new clause in the special conditions of contract.

1. DEFINITIONS, INTERPRETATIONS AND GENERAL PROVISIONS

SCC 1.1.1.15 EMPLOYER

Add the following to GCC 1.1.1.15:

The employer is the **Moretele Local Municipality**, and includes any persons appointed by the Employer. The official address is:

Moretele Local Municipality
4065B, Mathibestad
Private bag x367
MAKAPANSTAD
0404

SCC 1.1.1.16 ENGINEER

Add the following to GCC 1.1.1.16:

The Engineer means Tshashu Consulting Engineers and Project Manager's, and includes any persons appointed by the Engineer. The official address is:

Address (physical): The Village
Block C First Floor
Corner Oberon & Glenwood Roads
Pretoria 0043
Cell: 082 778 0876
Tel/ fax: 012 348 1896
e-mail: admin@tsconsulting.co.za

2. AMBIGUITY IN DOCUMENTS

Add the following to GCC 2.4:

2.4.1 The several documents forming the contract shall rank in the following order of precedence:

- a) contract agreement;
- b) tender form and appendix;
- c) special conditions of contract;
- d) project specifications;
- e) general conditions of contract;
- f) drawings;
- g) standardised specifications (SANS 1200) and particular specifications;
- h) schedule of quantities and summary;
- i) statutory regulations and requirements;
- j) standard SANS specifications (not SANS 1200);
- k) other standard specifications.

If the requirements of any part of the tender document contradict any other part, the document in the highest position on the above order of precedence, shall have preference and apply.

3. PROGRAMME OF THE WORKS

SCC 5.6.1 PROGRAMM

Add the following to GCC 5.6.1

The critical path of the works shall also be stipulated clearly in the programme.

4. INSTRUCTIONS AND DRAWINGS

SCC 5.9.1 DRAWINGS AND INSTRUCTIONS

Add the following to GCC 5.9.1

The Contractor is entitled to three (3) free sets of paper plans for normal use and one (1) free set of paper plans on which to enter "as built" information. He shall also be supplied with one (1) free copy of the contract document. These drawings and contract document shall be issued to the Contractor, at the time of commencement of the contract, by the Engineer.

SCC 5.9.7 ENGINEER TO APPROVE CONTRACTOR'S DESIGNS AND DRAWINGS

Add the following to GCC 5.9.7:

Although the Engineer may approve plans and designs of the Contractor, this does not exempt the Contractor from his responsibility. The professional responsibility for such designs shall be that of the Contractor and his Engineer.

5. CLEARANCE OF SITE

SCC 5.15.1 CLEARANCE OF SITE ON COMPLETION

Add the following to GCC 5.15.1:

After completion of the works, the Contractor shall obtain certificates from all concerned land owners on whose property works have been executed, stating that they are satisfied with the condition of their property, which will normally include finishing of pipe trenches and structures, clearance and finishing of all stone quarries, borrow pits, diversions, private or tertiary or haulage roads that have been used for the transport of material, waste material, fencing, gates, etc on their properties. These certificates shall all be handed to the Engineer before he issues the certificate of completion.

Notwithstanding a certificate of completion will not be issued if the work is not to the satisfaction of the Engineer.

6. CONTRACTOR'S EMPLOYEES

SCC 4.10 ENGAGEMENT OF EMPLOYEES

Add the following to clause 4.10.1:

In the event that the Contractor does not pay local labour or any outside agency employed on a monthly basis, the Employer has the automatic right to deduct such wages from the Contractor's next payment certificate. This will be deducted from either monies due to the Contractor or from retention already retained on the project. Payments to the local labour or outside agency will be made by cession.

7. MATERIALS, WORKMANSHIP AND CONSTRUCTIONAL PLANT

SCC 7.1 QUALITY OF PLANT, MATERIALS AND WORKMANSHIP

Add the following to GCC 7.2.1:

No second-hand or reject material shall be used without written permission from the Engineer.

SCC 7.4.4 COST OF TEST SPECIMENS AND TESTS

Substitute GCC 7.4.4 with the following:

(a) It is deemed that the Contractor has made provision in his tender for all such services and tests that are required from him. It is the duty of the Contractor to, at his own cost and by means of the necessary tests, prove to the Engineer that the works and compaction prescribed, comply with the specification.

8. EXAMINATION OF THE WORKS

SCC 7.5.1 EXAMINATION OF WORK BEFORE COVERING UP

Add the following to GCC 7.5.1:

The Contractor shall give the Engineer a reasonable time to accommodate examinations in his programme, in which case a time for inspection can be agreed upon.

SCC 7.5.3 NOTICE TO BE GIVEN WHEN READY FOR TESTING

Add the following to paragraph 2 of GCC 7.5.3:

If the Engineer attends with the purpose of examining any part or materials of the works at any time and date as agreed upon with the Contractor, and it is found that the works or materials are not yet ready for inspection, the Contractor shall be responsible for the costs of such a visit by the Engineer.

9. INDEMNIFICATIONS

SCC 8.4.2 INDEMNITY BY EMPLOYER

Add the following to GCC 8.4.2:

The Contractor indemnifies the Employer against any liability in respect of damage to or physical loss of the property of any person or injury to or death of any person due to not complying with the Occupational Health and Safety Act No 85 of 1993. Attached in the tender document is the form "Contract between Employer and Contractor" to be completed by the successful Contractor.

SCC 8.6.1 INSURANCES

Add the following to GCC 8.6.1:

The amount shall be per occurrence. The number of occurrences is unlimited.

Add the following to GCC 8.6.6:

Within 14 days of receipt of the letter of acceptance of his tender, the Contractor shall submit proof of payment to the Engineer.

10. VARIATIONS**SCC 6.5 DAYWORK**

Add the following to GCC 6.5:

"Total remuneration" shall include the following:

- Basic wage
- Holiday fund stamp
- Unemployment insurance
- Employee's compensation
- Service bonus

Add the following to GCC 6.5.4:

The percentage allowance stated in the appendix shall also include travelling cost or travelling allowance (transport of workmen with the Contractor's transport vehicles or transport vehicles hired by the Contractor or for which the Contractor paid), and residence allowance and other wages that are payable to the workmen on the date for submission of tenders.

11. SUSPENSION OF THE WORKS**SCC 5.11.1 SUSPENSION OF THE WORKS**

Add the following to GCC 5.11.1:

No payment shall be made for costs incurred by recompiling a construction programme. In the case of suspension of work, either for a change in sequence or as a result of GCC 5.11.2 to 5.11.3, no payment shall be made for such costs resulting from this.

12. EXTENSION OF TIME FOR COMPLETION**SCC 1.1.1.14 TIME FOR ACHIEVING PRACTICAL COMPLETION**

Add the following to GCC 5.12.1:

The time for achieving practical completion shall exclude the period of builder's holidays from 16 December 2021 till 5 January 2022, as well as other special non-working days and public holidays.

SCC 5.12.1 EXTENSION OF TIME FOR COMPLETION

Add the following to GCC 5.12.1:

Extension of the time for completion as a result of extra or additional work and unfavourable physical conditions shall only be granted if such work or conditions influence work on the critical path of the programme. If no definitive method for extension of time due to weather conditions and rain is specified, extension of time as a result of this shall also only be applicable if it influences the critical path of activities.

SCC 5.12.2 SOME REASONS FOR EXTENSIONS OF TIME

Add the following to GCC 5.12.2:

Abnormal climatic conditions.

No extension of the time for completion shall be granted on the grounds of normal rainfall conditions, but extension of time in terms of relevant clause of the general conditions of contract on the grounds of abnormal rainfall or wet conditions shall be calculated separately for each calendar month or part thereof, according to the following formula. It shall be calculated as follows for the time for completion, including any extension thereof:

$$V = (Nw - Nn) + \left(\frac{Rw + Rn}{X} \right)$$

V = Extension of time for calendar days of the calendar month concerned. If the value of V is negative and the absolute value thereof is greater than Nn, V is taken as negative Nn.

Nw = Actual number of days during calendar month on which a rainfall of Y mm or more is recorded.

Nn = Average number of days in the calendar month concerned on which a rainfall of Y mm or more is recorded in terms of existing rainfall data.

Rw = Actual rainfall for the calendar month concerned in mm.

Rn = Average rainfall for the calendar month in mm deduced from existing rainfall data.

The total extension of time is the algebraic sum of the monthly totals for the period concerned. Extension of time for parts of a month shall be calculated by using pro rata values of Nn and Rn. If the algebraic sum of the monthly totals is negative, no reduction of the time for completion as a result of rainfall shall be applicable.

This formula does not take any delays as a result of flood damage, which may cause further or simultaneous delays; into consideration and flood damage shall be treated separately for purposes of extension of time for completion.

The factor (Nw - Nn) is considered as a fair allowance for deviation from the normal for the number of days on which the rainfall exceeds Y mm. The factor (Rw - Rn)/X is considered as a fair allowance for deviation from the normal for the number of days on which the rainfall does not exceed Y mm, but on which wet conditions will hamper or disrupt work.

For the purpose of this contract the values of Nn, Rn, X and Y will be the relevant values of the nearest weather station to the site as supplied by the South African Weather Bureau. It is the sole responsibility of the Tenderer to acquaint himself with the relevant values. These values shall, at the start of the contract be submitted to the Engineer for scrutiny and approval.

SCC 5.12.2.3 AVAILABILITY OF PETROLEUM PRODUCTS

The tender shall be based on the available supply of petroleum products required for the completion of the works. If, during the contract period, for reasons outside the control of the Contractor, a restriction or breakdown in the supply of petroleum products may occur, which has an actual influence on the execution of the works for a period of at least thirty (30) days, the Contractor shall make all reasonable efforts to complete the works and he shall be entitled to an extension of the time for completion and he shall also be entitled to such an adjustment of the contract price as deemed reasonable by the Engineer, with consideration of all materials and relevant factors directly responsible or having a direct effect on such restriction or breakdown, with the inclusion of the Contractor's site and overhead costs relevant to the contract.

SCC 5.12.2.3 EXTENSION OF TIME DUE TO SHORTAGE OF MATERIAL

If, during the preparation of his tender or during construction, the Contractor bases his unit prices on prices obtained from specific material or specific suppliers, it will be accepted that the Contractor

has ascertained that such material shall be available on a continuous basis for the execution of the contract.

No extension of time shall be granted if material cannot be obtained locally, but is available from other sources in the country, and no additional remuneration shall be granted for increased costs due to obtaining material from sources in other parts of the country.

If suppliers cannot adhere to the quoted delivery dates, any delays resulting from this shall be considered as a matter between the supplier and the Contractor. Extension of time could be granted under such conditions after complete proofs have been submitted to and accepted by the Engineer, but without any financial implications for the Employer.

13. INTERIM PAYMENTS

SCC 6.10.2 VALUATION OF MATERIAL BROUGHT ONTO SITE

Add the following to GCC 6.10.2:

Material or goods for which payment is made in terms of this clause, shall be identified uniquely and be stored in a space approved by the Engineer, and which will only be used for the purposes of the Employer.

SCC 6.10.3 RETENTION MONEY

Add the following to GCC 6.10.3:

No limit of retention money will be applicable only the 10 % as stated in the Contract Data will be applicable on the contract.

SCC 6.10.5 EMPLOYER'S OBLIGATION TO PAY

Replace GCC 6.10.5 with the following:

The Engineer shall deliver to the Employer the Contractor the payment certificate referred to in clause 6.10.3 within 07 (seven) days after the receipt by the Engineer of the Contractor's said statement, and the Employer shall pay the amount due to the Contractor within 65 (sixty five) days after receipt by the Employer of the payment certificate signed by the Engineer.

SCC 6.10.1 VALUE ADDED TAX

Add the following to GCC 6.10.1:

Value added tax (VAT) shall be calculated on each payment certificate, but it shall remain the responsibility of the Contractor to issue a tax invoice for the certified amount. The Contractor is responsible for the payment of VAT.

14. DEFECTS

SCC 7.8.1 MAKING GOOD OF DEFECTS

Add the following to GCC7.8.1:

If it is deemed necessary in the opinion of the Engineer, the defects liability period after repairs can be extended for a further period of twelve months or for a period to the discretion of the Engineer, as regards the relevant part of the works that is made good.

15. LEGAL PROVISIONS

SCC 4.3.1 COMPLIANCE WITH APPLICABLE LAWS

The Contractor shall be conversant with all the requirements, regulations, and standards of the Occupational Health and Safety Act, 1993 (Act No. 85 of 1993), hereinafter referred to as "the Act" and undertakes to execute all the works forming part of this Contract and to operate and utilise all machinery, plant, and equipment in accordance with the Act.

The Contractor shall, from the commencement date of the Contract up to completion or termination thereof, be the Employer's mandatory regarding occupational health and safety for all activities on the site but without derogating from his status in his own right as an employer or a user in accordance with the Act.

The Contractor is responsible for the compliance with the Act by all his subcontractors, whether or not nominated and/or approved by the Employer.

The Contractor shall, when called upon to do so, enter into and execute an Agreement, as provided for under Section 37(2) of the Act, with the Employer. The Agreement in the relevant form shall be prepared at the expense of the Employer.

16. LATENT DEFECT PERIOD

SCC 5.16.3 LATENT DEFECT PERIOD

The latent defect period is 10 years.

17. ADJUDICATION

SCC 10.5.3 ADJUDICATION BOARD MEMBERS

The number of Adjudication Board Members to be appointed is three.



MORETELE LOCAL MUNICIPALITY

C3. Schedule of Quantities

C3.1 Preamble to Schedule of Quantities

1. The general conditions of contract, the special conditions of contract (if any), the specifications (including the project specification) and the drawings are to be read in conjunction with the schedule of quantities.
2.
 - a) The schedule comprises items covering the Contractor's profit and costs of general liabilities and of the construction of temporary and permanent works.
 - b) The Contractor is at liberty to insert a rate of his own choosing for each item in the schedule and his attention is drawn to the fact that the Contractor has the right, under various circumstances, to payment for additional works carried out and that the Engineer is obliged to base his assessment of the rates to be paid for such additional work on the rates inserted in the schedule by the Contractor.
 - c) Clause 8 of each standardised specification and the measurement and payment clause of each particular specification, read together with the relevant clauses of the project specification, set out what ancillary or associated activities are included in the rates for the operations specified.
3. Descriptions in the schedule of quantities are abbreviated and the schedule has been drawn up generally in accordance with the latest issue of Civil Engineering Quantities¹. Should any requirement of the measurement and payment clause of the applicable standardised specification², or the project specification², or the particular specification(s)² conflict with the terms of the schedule or, when relevant, Civil Engineering Quantities¹, the requirement of the standardised, project or particular specification, as applicable, shall prevail.
4. Unless otherwise stated, items are measured net in accordance with the drawings, and no allowance has been made for waste.
5. The prices and rates to be inserted in the schedule of quantities are to be the full inclusive prices to the Employer for the work described under the several items, value added tax excluded. Such prices shall cover all costs and expenses that may be required in and for the construction of the work described, and shall cover the cost of all general risks, liabilities and obligations set forth or implied in the documents on which the quotation is based.
6. A price or rate is to be entered against each item in the schedule of quantities, whether the quantities are stated or not. An item against which no price is entered will be considered to be covered by the other prices or rates in the schedule.
7. The Contractor must price each item in the schedule of quantities in **BLACK INK**.
8. **All prices and rates shall exclude value added tax (VAT)**. The Contractor shall calculate value added tax and enter it at the end of the summary of the schedule of quantities.

9. For the purposes of this Schedule of Quantities, the following words shall have the meanings hereby assigned to them:

Unit	: The unit of measurement for each item of work as defined in the Specifications.
Quantity	: The number of units of work for each item
Rate	: The payment per unit of measurement at which the Tenderer tenders to do the work.
Amount	: The product of the quantity and the rate tendered for an item
Sum	: An amount tendered for an item, the extent of which is described in the Schedule of Quantities, the specifications or elsewhere but the quantity of work of which is not measured in any units.
Prime Cost (or PC item)	: A sum fixed by the Engineer and entered in the Schedule of Quantities as the net sum provided to cover the cost of specific goods or materials to be supplied under the contract, or the net sum to be paid by the Contractor to merchants or others for such articles or materials. ¹
Provisional Sum	: A sum of money fixed by the Engineer and entered in the Schedule of Quantities to provide for work not defined at the tender stage and includes any allowance specifically made for unforeseen contingencies. ¹
Extra Over (or EO)	: Qualifies an operation (or combination of operations) which is common in a varying degree to a number of other operations and which is scheduled once as "extra over" those other operations in order to avoid a multiplicity of items each reflecting the degree to which the common operations applies. The term "extra over" invariably denotes double measurement, no deduction being made from one on account of the other. ¹

10. The units of measurements indicated in the Schedule of Quantities are metric units.

The following abbreviations are used in the Schedule of Quantities:

mm	= millimetre
m	= metre
km	= kilometre
km-pass	= kilometre-pass
m^2	= square metre
m^2 -pass	= square metre-pass
ha	= hectare
m^3	= cubic metre
m^3 -km	= cubic metre-kilometre
/	= litre
kl	= kilolitre
kg	= kilogramme
t	= ton (1 000 kg)
no	= number
%	= percentage
kW	= kilowatt
PC Sum	= prime cost sum
Prov. Sum	= provisional sum
kPa	= kilopascal
R/only	= Rate only
W/day	= Work day

1) The standard system of measurement of Civil Engineering Quantities of South Africa published by the South African Institution of Civil Engineers.

2) See definition in sub clause 2.1 of Part 1 of SANS 0120: Format and Contents.

DAY WORK LIST

GENERAL

Contractors must complete this list, which will be used to assess the value of work that the Engineer instructs in writing to be done on a day work basis, all in agreement with clause 37.2 of the General Conditions of Contract for Construction Works, Third Edition, 2015 and coupled Special Conditions of Contract. All the rates are fixed and shall be binding till the issuing of the final certificate, except for statutory increases that are announced from time to time.

LABOUR COSTS

Rates for labour as listed below shall include all the allowances as specified in the General Conditions of Contract for Construction Works, Third Edition, 2015 and Special Conditions of Contract. The extra allowance, applicable on Labour costs listed below, is given in the tender appendix and must not be taken into account in this list.

Overtime costs incurred by this contract shall be paid in the same proportion as the amounts actually paid to the employees.

DESCRIPTION	UNIT	RATE
Unschooled labour	Hour	R
Half- Schooled labour	Hour	R
Pipe layer	Hour	R
Ganger	Hour	R
Foreman / Section leader	Hour	R
Brick layer	Hour	R
Plumber	Hour	R

EQUIPMENT COSTS

Full comprehensive hourly rates, which also include the cost of operators, must be listed below. Rates must also include all the costs of consumable items, maintenance, depreciation, tools, and all other coincidences that shall be necessary to operate the equipment for the purpose it is designed for. The rates must also include all the overhead costs, profits, site supervision, insurance, holidays with payment, travelling costs (or travelling allowances) and residence allowances of operators and any other allowances that are applicable on equipment. The Tenderer must list under each heading the make and specification of the equipment available.

DESCRIPTION	UNIT	RATE
1. Excavators		
.....	Hour
.....	Hour
.....	Hour
2. Front-end loaders		
.....	Hour
.....	Hour
.....	Hour
3. Trucks (m ³ specified)		
.....	Hour
.....	Hour
.....	Hour
4. Water truck (litres specified)		
.....	Hour
5. Tractor & Trailer		
.....	Hour
.....	Hour
.....	Hour
6. Compressor		
.....	Hour
.....	Hour
.....	Hour
DESCRIPTION	UNIT	RATE

7. Concrete mixer (litres specified)	Hour
.....	Hour
.....	Hour
.....	Hour
8. "Dumper" (m ³ specified)	Hour
.....	Hour
.....	Hour
.....	Hour
9. Water pumps		
75mm.....	Hour
100mm.....	Hour
150mm.....	Hour
10. Compactors	Plate	
.....	Hour
11. Other equipment		
.....	Hour

SUMMARY SCHEDULE OF QUANTITIES			TENDER NO.
WATER RETICULATION AND YARD CONNECTIONS-WARD-16			
SCHEDULE	SECTION	DESCRIPTION	AMOUNT
A	1	PRELIMINARY AND GENERAL - FIXED CHARGE AND VALUE RELATED OBLIGATIONS	
	2	PRELIMINARY AND GENERAL - TIME RELATED OBLIGATIONS	
	3	PRELIMINARY AND GENERAL - PROVISIONAL SUMS	
	4	PRELIMINARY AND GENERAL - PRIME COST SUMS	
	5	PRELIMINARY AND GENERAL - DAYWORK	
C	1	SITE CLEARANCE	
DB	1	EARTHWORKS FOR PIPE TRENCHES	
L	1	MEDIUM PRESSURE PIPELINES	
LB	1	PIPE BEDDING	
LF	1	ERF CONNECTIONS (WATER)	
TOTAL SCHEDULE OF QUANTITIES AMOUNT:			
CALCULATION OF TENDER SUM			
TOTAL SCHEDULE OF QUANTITIES AMOUNT BROUGHT FORWARD:			
CONTINGENCIES@05%:			
SUB-TOTAL:			
ADD 15% VAT:			
TOTAL TENDER AMOUNT CARRIED TO FORM OF OFFER:			

MORETELE LOCAL MUNICIPALITY - NORTH WEST PROVINCE
SCHEDULE OF QUANTITIES:
WATER RETICULATION AND YARD CONNECTIONS-WARD-16

SCHEDULE A: PRELIMINARY AND GENERAL OBLIGATIONS						
SECTION 1: PRELIMINARY AND GENERAL - FIXED CHARGE AND VALUE RELATED OBLIGATIONS						
ITEM NUMBER	PAYMENT CLAUSE	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
A1	PSA 8.3	FIXED CHARGE AND VALUE RELATED ITEMS: <i>(As specified in SABS 1200 A, SABS 1200 AB and the Project Specifications.)</i>				
1,1		Contractual Requirements:				
1.1.1	PSA 8.3.1	Fixed charge contractual requirements.	Sum	1,00		
1.1.2	PSA 8.3.1	Value related contractual requirements.	Sum	1,00		
1,2		Facilities for Engineer:				
1.2.1	PSA 8.3.2.1 a	Furnished office	Sum	1,00		
1.2.2	PSA 8.3.2.1 b	Telephone	Sum	1,00		
1.2.3	PSA 8.3.2.1 c	Name board(1 No)	Sum	1,00		
1,3		Facilities for Contractor:				
1.3.1	PSA 8.3.2.2 a	Offices and storage sheds	Sum	1,00		
1.3.2	PSA 8.3.2.2 b	Workshops	Sum	1,00		
1.3.4	PSA 8.3.2.2 d	Living accommodation	Sum	1,00		
1.3.5	PSA 8.3.2.2 e	Ablution and latrine facilities	Sum	1,00		
1.3.6	PSA 8.3.2.2 f	Tools and equipment	Sum	1,00		
1.3.7	PSA 8.3.2.2 g	Water supplies, electric power and communications	Sum	1,00		
1.3.8	PSA 8.3.2.2 h	Dealing with water	Sum	1,00		
1.3.9	PSA 8.3.2.2 i	Access	Sum	1,00		
1.3.10	PSA 8.3.2.2 j	Plant	Sum	1,00		
1.3.11	PSA 14.2 a	Materials on site storage and protection.	Sum	1,00		
1.3.12	PSA 14.2 b	Accommodation of traffic.	Sum	1,00		
1,4	PSA 8.3.3	Other Fixed Charge Obligations:	Sum	1,00		
1,5	PSA 8.3.4	Removal of Site Establishment:	Sum	1,00		
1,6	PSA 8.5	Sum Stated Provisionally by Engineer Occupation Health and Safety				
1.6.1	PSA 8.3.5.1	Contractor's initial obligations in respect of the Occupational Health and Safety Act contractual	Prov. Sum			R 15 000,00
1.6.2	PSA 8.3.5.2	Occupational, health and Safety act	sum	1,00		
TOTAL SCHEDULE A - SECTION 1 CARRIED TO SUMMARY:						

MORETELE LOCAL MUNICIPALITY - NORTH WEST PROVINCE
SCHEDULE OF QUANTITIES:
WATER RETICULATION AND YARD CONNECTIONS-WARD-16

SCHEDULE A: PRELIMINARY AND GENERAL OBLIGATIONS						
SECTION 2: PRELIMINARY AND GENERAL - TIME RELATED OBLIGATIONS						
ITEM NUMBER	PAYMENT CLAUSE	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
A.2		TIME RELATED ITEMS: <i>(As specified in SABS 1200 A, SABS 1200 AB and the Project Specifications.)</i>				
2,1	8,4	Scheduled Tie-Related Items:				
2.1.1	8.4.1	Contractual Requirements	Month	4		
2,2		Facilities for Engineer:				
2.2.1	PS A 8.4.2.1 a	Furnished offices	Month	4		
2.2.2	PS A 8.4.2.1 a	Telephone for engineer's Representative	Month	4		
2.2.3	PS A 8.4.2.1 c	Name boards (1 No)	Month	4		
2,3		Facilities for Contractor:				
2.3.1	PS A 8.4.2.2 a	Offices and storage sheds.	Month	4		
2.3.2	PS A 8.4.2.2 b	Workshops.	Month	4		
2.3.4	PS A 8.4.2.2 d	Living accommodation.	Month	4		
2.3.5	PS A 8.4.2.2 e	Ablution and latrine facilities.	Month	4		
2.3.6	PS A 8.4.2.2 f	Tools and equipment.	Month	4		
2.3.7	PS A 8.4.2.2 g	Water supplies, electric power and communications.	Month	4		
2.3.8	PS A 8.4.2.2 h	Dealing with water.	Month	4		
2.3.9	PS A 8.4.2.2 i	Access.	Month	4		
2.3.10	PS A 8.4.2.2 j	Plant.	Month	4		
2,4	PS A 8.4.3	Supervision for Duration of the Contract:	Month	4		
2,5	PS A 8.4.4	Company and Head Office Overhead Costs's for the Duration of the Contract:	Month	4		
2,6	PS A 8.4.5	Other Time Related Obligations:	Month	4		
2,7	PSA 8.5	Environmental Management:	Month	4		
2,8	PSA 8.5	Occupational Health and Safety	Month	4		
TOTAL SCHEDULE A - SECTION 2 CARRIED TO SUMMARY:						

MORETELE LOCAL MUNICIPALITY - NORTH WEST PROVINCE
SCHEDULE OF QUANTITIES:
WATER RETICULATION AND YARD CONNECTIONS-WARD-16

SCHEDULE A: PRELIMINARY AND GENERAL OBLIGATIONS						
SECTION 3: PRELIMINARY AND GENERAL - PROVISIONAL SUMS						
ITEM NUMBER	PAYMENT CLAUSE	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
A.3		PROVISIONAL SUMS: <i>(As specified in SABS 1200 A and the Project Specifications.)</i>				
3,1	PS A 8.5 (a)1	Community Liaison Officer: Provision for the employment of CLO. @ R4500/m Overheads, charges and profit on item 3.1.1.	Prov. Sum %	27000,00		R 27 000,00
3,2	PS A 8.5 (a)2	PSC Meetings Attendance Provision for the payment of PSC members @ R140/sitting Overheads, charges and profit on item 3.2.1.	Prov. Sum %	8400,00		R 8 400,00
3,3	PS A 8.5 b.1	Basic Skills and Construction Training: Provision for basic skills and construction site safety training. Overheads, charges and profit on item 3.3.1.	Prov Sum %	60000,00		R 60 000,00
3.3.1	PS A 8.5 b.1	Payment for labourers undergoing training	Prov Sum %	15000,00		R 15 000,00
3.3.2	PS A 8.5 b.2	Overheads, charges and profit on item 3.3.1.				
3.3.3	PS A 8.5 b.3	Overheads, charges and profit on item 3.3.3.				
3.3.4	PS A 8.5 b.4	Overheads, charges and profit on item 3.3.3.				
		Temporary Works				
3,4	PS A 8.8.2	Accommodation of Traffic a) Provision for relocation/protection of existing services.	Prov. Sum %	50000,00		R 50 000,00
3.4.1	PS A 8.8.2	b) Overheads, charges and profit on item 3.4.1.				
3,5	8.5 b	Routine Tests required by Engineer: Provision for routine tests.	Prov. Sum %	25000,00		R 25 000,00
3.5.1	PSA 14.5 i	Overheads, charges and profit on item 3.5.1.				
3,6		Safety Rep Provision for Safety Rep Services.	Prov. Sum %	22500,00		R 22 500,00
3.6.1		Overheads, charges and profit on item 3.6.1.				
3.6.2						
TOTAL SCHEDULE A - SECTION 3 CARRIED TO SUMMARY:						

MORETELE LOCAL MUNICIPALITY - NORTH WEST PROVINCE
SCHEDULE OF QUANTITIES:
WATER RETICULATION AND YARD CONNECTIONS-WARD-16

SCHEDULE A: PRELIMINARY AND GENERAL OBLIGATIONS

SECTION 4: PRELIMINARY AND GENERAL - PRIME COST SUMS

ITEM NUMBER	PAYMENT CLAUSE	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
A.4		PRIME COST ITEMS: <i>(As specified in SABS 1200 AB and the Project Specifications.)</i>				
4,1	PSA 8.6	Phone for Engineer's Site Staff: a) Provision for a phone and call charges.	PC Sum			R 14 000,00
4.1.1	PSA 8.6	b) Overheads, charges and profit on item 4.1.1.	%	14000,00		
4,2		Protective Clothing: a) Provision for PPE	PC Sum			R 17 250,00
4.2.1		b) Overheads, charges and profit on item 4.1.1.	%	17250		
TOTAL SCHEDULE A - SECTION 4 CARRIED TO SUMMARY:						

MORETELE LOCAL MUNICIPALITY - NORTH WEST PROVINCE
SCHEDULE OF QUANTITIES:
WATER RETICULATION AND YARD CONNECTIONS-WARD-16

SCHEDULE A: PRELIMINARY AND GENERAL OBLIGATIONS

SECTION 5: PRELIMINARY AND GENERAL - DAYWORKS

ITEM NUMBER	PAYMENT CLAUSE	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
A.5		DAYWORK: <i>(As specified in SABS 1200 A and the Project Specifications.)</i>				
5.1	PS A8.7	Labour - Normal Working Hours: [Provisional]				
5.1.1		Skilled Labour (Artisan).	hr	1		
5.1.2		Semi-skilled Labour.	hr	1		
5.1.3		Unskilled Labour.	hr	1		
5.1.4		Foreman.	hr	1		
5.1.5		Extra-over rate for items 5.1.1 to 5.1.4 for work during non working hours.	hr	1		
5.2	8,7	Materials: [Provisional]				
5.2.1		Allowance for Materials used under Dayworks.	Prov Sum			R1 500,00
5.2.2		Overheads, Handling and all Charges on Item 5.2.1.	%	1500		
5.3	8,7	Plant - Heavy Equipment: [Provisional] <i>(Plant shall not be more than 3 years old or have more than 3000 hrs logged. Operator to be qualified and competency certified.)</i>				
5.3.1		Excavator - Size Cat 225.	hr	1		
5.3.2		Excavator - TLB.	hr	1		
5.3.3		Grader 140G or similar.	hr	1		
5.3.4		Front end loader - bucket capacity $\leq 1.5 \text{ m}^3$.	hr	1		
5.3.5		Front end loader - bucket capacity $\leq 1.5 \text{ m}^3$.	hr	1		
5.3.6		Tip truck - 5 m^3 capacity.	hr	1		
5.3.7		Tip truck - 10 m^3 capacity.	hr	1		
5.3.8		Vibratory compaction roller - 13.5 ton.	hr	1		
5.4	8,7	Plant - Small Equipment: [Provisional]				
5.4.1		Pedestrian roller - BW90 or similar.	hr	1		
5.4.2		Vibratory plate compactor.	hr	1		
5.4.3		Vibratory rammer.	hr	1		
5.4.4		Transport cost per any unit of plant to deliver to site and remove from site for items 5.4.1 to 5.4.3.	Sum	1		
TOTAL SCHEDULE A - SECTION 5 CARRIED TO SUMMARY:						

MORETELE LOCAL MUNICIPALITY - NORTH WEST PROVINCE
SCHEDULE OF QUANTITIES:
WATER RETICULATION AND YARD CONNECTIONS-WARD-16

SCHEDULE C: BULK SUPPLY AND NETWORK DISTRIBUTION WORKS

SECTION 1: EARTHWORKS FOR PIPE TRENCHES

ITEM NUMBER	PAYMENT CLAUSE	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
C.1		SITE CLEARANCE <i>(As specified in SABS 1200 C and the Project Specifications.)</i>				
1.1		Site Clearance:				
1.1.1	PSC 8.2.1	Clear vegetation, 800 mm wide. (Provisional)	m	3200		
1.1.2	PSC 8.2.2	Clear trees of girth over 1.0 m.	No.	4		
1.1.3	PSC 8.2.5	Take down existing fence and reinstate to original position	m	20		
SUB-TOTAL SCHEDULE C - SECTION 1 CARRIED SUMMARY:						

MORETELE LOCAL MUNICIPALITY - NORTH WEST PROVINCE
SCHEDULE OF QUANTITIES:
WATER RETICULATION AND YARD CONNECTIONS-WARD-16

SCHEDULE DB: BULK SUPPLY AND NETWORK DISTRIBUTION WORKS

SECTION 1: EARTHWORKS FOR PIPE TRENCHES

ITEM NUMBER	PAYMENT CLAUSE	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
DB.1		EARTHWORKS: PIPE TRANCHES <i>(As specified in SABS 1200 DB and the Project Specifications.)</i>				
1.1	PSDB 8.3.2	Excavation				
1.1.1		a) Excavate in all materials for trenches, backfill, compact and dispose of surplus material.	m	3200		
1.1.2		b) 1. Extra-over items (a) for excavation in intermediate material.	m ³	1280		
1.1.3		c) 2. Extra-over items (a) for hard rock excavation.	m ³	512		
1.1.4		d) 3. Extra-over items (a) for hand excavation and backfill where ordered by engineer.	m ³	100		
1.1.5		e) Soilcrete backfilling where ordered by Engineer.	m ³	30		
TOTAL SCHEDULE DB - SECTION 1 CARRIED FORWARD:						

MORETELE LOCAL MUNICIPALITY - NORTH WEST PROVINCE
SCHEDULE OF QUANTITIES:
WATER RETICULATION AND YARD CONNECTIONS-WARD-16

SCHEDULE DB: BULK SUPPLY AND NETWORK DISTRIBUTION WORKS						
SECTION 1: EARTHWORKS FOR PIPE TRENCHES						
ITEM NUMBER	PAYMENT CLAUSE	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
SUB-TOTAL SCHEDULE DB - SECTION 1 BROUGHT FORWARD:						
DB.1		EARTHWORKS: (Continues) <i>(As specified in SABS 1200 DB and the Project Specifications.)</i>				
1,2	DB 8.3.2.(a)	Backfill and Compaction: Backfill and Compaction trenches	m^3	2048		
1.2.1.1		Dispose of surplus material	m^3	102		
1,3	PSDB 8.3.3 PSDB 8.3.3.1	Excavation Ancillaries; Make up deficiency in backfill material (Provisional) a) from other necessary excavations on site	m^3	102		
1.3.1.2		(b) importing from commercial or off-site source selected by the contractor.	m^3			
1.3.2	DB 8.3.3.3	Compaction within road reserve to 90 % of Modified AASHTO density clause 5.7.1.	m^3	10		
1,4	DB 8.3.3.4	Overhaul: b) Overhaul in excess of the free-haul of 3.0 km.	m^3	102		
1,5	PSDB 8.3.5	Existing Services: a) Services that intersect a trench.	No.	20		
TOTAL SCHEDULE DB - SECTION 1 CARRIED TO SUMMARY:						

MORETELE LOCAL MUNICIPALITY - NORTH WEST PROVINCE
SCHEDULE OF QUANTITIES:
WATER RETICULATION AND YARD CONNECTIONS-WARD-16

SCHEDULE L: BULK SUPPLY AND NETWORK DISTRIBUTION WORKS

SECTION 1: MEDIUM PRESSURE PIPELINES AND ANCILLARIES

ITEM NUMBER	PAYMENT CLAUSE	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
L 1		MEDIUM PRESSURE PIPES: <i>(As specified in SABS 1200 L, SABS 1200 GA and the Project Specifications.)</i>				
1.1	PSL 8.2.1	Supply, Lay and Bed uPVC Pipes Complete with Couplings <i>(The rates shall include disinfecting of pipes after completion of hydraulic pipe test.)</i>				
1.1.1		63 mm uPVC medium pressure pipes - Class 09.	m	3200	95,00	
1.2	PSL 8.2.2	Fittings and Specials - uPVC Laying Bends: <i>(Extra-over rate to Items 3.1.1 to 3.1.6.)</i>				
1.2.2		63 mm uPVC:				
1.2.2.1		uPVC bends less than 90 degree angle.	No.	25	550,00	
1.2.2.2		uPVC bends less than 45 degree angle.	No.	10	550,00	
1.2.2.3		uPVC bends with 22,5 degree angle.	No.	10	550,00	
1.2.2.4		uPVC bends with 11,5 degree angle.	No.	10	550,00	
1.2.3	8.2.2	Specials and Fittings - uPVC Equal Tees: <i>(Bitumen dipped and LAYING sockets on all sides all to SABS 546 and SABS 966.)</i>				
1.2.3.1		90 mm dia.	No.	6	650,00	
1.2.3.2		63 mm dia.	No.	4	650,00	
SUB-TOTAL SCHEDULE L - SECTION 1 CARRIED FORWARD:						

MORETELE LOCAL MUNICIPALITY - NORTH WEST PROVINCE
SCHEDULE OF QUANTITIES:
WATER RETICULATION AND YARD CONNECTIONS-WARD-16

SCHEDULE L: BULK SUPPLY AND NETWORK DISTRIBUTION WORKS						
SECTION 1: MEDIUM PRESSURE PIPELINES AND ANCILLARIES						
ITEM NUMBER	PAYMENT CLAUSE	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
SUB-TOTAL SCHEDULE L - SECTION 1 BROUGHT FORWARD:						
L 2		MEDIUM PRESSURE PIPES: (continues) <i>(As specified in SABS 1200 L, SABS 1200 GA and the Project Specifications.)</i>				
1.2.5	PSL 8.2.2	Specials and Fittings - uPVC End Caps: 63 mm dia.	No.	2		
1.2.6	PSL 8.2.2	Specials and Fittings - uPVC Reducers: <i>(Bitumen dipped, spigot and socket and socketed cast iron reducers all to SABS 546 and SABS 966.)</i>				
1.2.6.1		90 mm x 63 mm dia. [S]	No.	5		
1.2.6.1		75 mm x 63 mm dia. [S]	No.	5		
1.2.7	8.2.2	Specials and Fittings - uPVC Equal Crosses: <i>(Bitumen dipped and LAYING sockets on all sides all to SABS 546 and SABS 966.)</i>				
1.2.7.1		63 mm x 63 mm	No	5		
1.2.8	8.2.3	Specials and Fittings - uPVC Reducing Crosses: <i>(Bitumen dipped, spigot and socket and socketed cast iron reducers all to SABS 546 and SABS 966.)</i>				
1.2.8.1		75 mm x 63mm dia. [S]	No.	3		
1.2.9	8.2.4	Specials and Fittings - uPVC Reducing Tee: <i>(Bitumen dipped, spigot and socket and socketed cast iron reducers all to SABS 546 and SABS 966.)</i>				
1.2.9.1		90 mm x 75 mm dia. [S]	No.	5		
SUB-TOTAL SCHEDULE L - SECTION 1 CARRIED FORWARD:						

MORETELE LOCAL MUNICIPALITY - NORTH WEST PROVINCE
SCHEDULE OF QUANTITIES:
WATER RETICULATION AND YARD CONNECTIONS-WARD-16

SCHEDULE L: BULK SUPPLY AND NETWORK DISTRIBUTION WORKS

SECTION 1: MEDIUM PRESSURE PIPELINES AND ANCILLARIES

ITEM NUMBER	PAYMENT CLAUSE	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
SUB-TOTAL SCHEDULE L - SECTION 1 BROUGHT FORWARD:						
L 3		MEDIUM PRESSURE PIPES: (continues) <i>(As specified in SABS 1200 L, SABS 1200 GA and the Project Specifications.)</i>				
1.2.10	PSL 8.2.3	Specials and Fittings - Isolating Valve: All isolating valves to be Double orifice type. Rate shall include all accessories required as per tender drawing. 63 mm Isolating Valve	No.	15		
SUB-TOTAL SCHEDULE L - SECTION 1 CARRIED FORWARD:						

MORETELE LOCAL MUNICIPALITY - NORTH WEST PROVINCE
SCHEDULE OF QUANTITIES:
WATER RETICULATION AND YARD CONNECTIONS-WARD-16

SCHEDULE L: BULK SUPPLY AND NETWORK DISTRIBUTION WORKS						
SECTION 1: MEDIUM PRESSURE PIPELINES AND ANCILLARIES						
ITEM NUMBER	PAYMENT CLAUSE	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
SUB-TOTAL SCHEDULE L - SECTION 5 BROUGHT FORWARD:						
L 1		MEDIUM PRESSURE PIPES: (continues) (As specified in SABS 1200 L, SABS 1200 GA and the Project Specifications.)				
1.2.12	PSL 8.2.11	Thrust Blocks: Concrete volume < 0,5m ³	No.	75		
1.2.13	PSL 8.2.13	Valve Chambers: Valve chamber - As per detail complete including excavation, materials, plant, labour and incidentals, as per detail drawings.	No.	10		
1.2.13.2		Extra-over Item 8.2.13 for depth increments of 250 mm.	No.	2		
SUB-TOTAL SCHEDULE L - SECTION 1 CARRIED TO SUMMARY:						

MORETELE LOCAL MUNICIPALITY - NORTH WEST PROVINCE
SCHEDULE OF QUANTITIES:
WATER RETICULATION AND YARD CONNECTIONS-WARD-16

SCHEDULE LB: BULK SUPPLY AND NETWORK DISTRIBUTION WORKS

SECTION 1: PIPE BEDDING

ITEM NUMBER	PAYMENT CLAUSE	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
LB 1		BEDDING: <i>(As specified in SABS 1200 LB and the Project Specifications.)</i>				
1,1	PSLB 8.1.1	Provision of Bedding and Blanket from Trench Excavations: <i>(Bedding to be Class C for flexible pipes as indicated in the contract drawings)</i>				
1.1.1		b) Provision of bedding from pipe trench excavation within 1.0 km, using selected fill material.	m ³	512		
1,2	PSLB 8.2.5	Overhaul				
1.2.1		a) Limited overhaul (0,5 km to 1,0 km)	m ³ .km	20		
1.2.2		b) Long overhaul	m ³ .km	30		
TOTAL SCHEDULE LB - SECTION 1 CARRIED TO SUMMARY:						

MORETELE LOCAL MUNICIPALITY - NORTH WEST PROVINCE
SCHEDULE OF QUANTITIES:
WATER RETICULATION AND YARD CONNECTIONS-WARD-16

SCHEDULE B: BULK SUPPLY AND NETWORK DISTRIBUTION WORKS

SECTION 1: MEDIUM PRESSURE PIPELINES AND ANCILLARIES

ITEM NUMBER	PAYMENT CLAUSE	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
LF 1	PSLF 8.2.1	ERF CONNECTIONS (WATER): <i>(As specified in SABS 1200 L, SABS 1200 LF.)</i> Provide Communal Taps complete as per drawing 1.1.1 Metered yard connections(Short connections) 1.1.1.2 Metered yard connections(Long connections)	No.	50		
1.2.1			No.	50		
TOTAL SCHEDULE LF - SECTION 1 CARRIED TO SUMMARY:						



MORETELE LOCAL MUNICIPALITY

C4.1 Scope of Work

4.1.1 Employer's objectives

The employer's objectives are to deliver public infrastructure using labour intensive method, whereby the local community benefit throughout the entire project and also in doing so provide work place training opportunities to learners who have a Learner ship Agreements with the Construction Education and Training Authority.

The employer's objective is to improve the existing water reticulation system, socio economic development of the community, satisfy the needs of the community, and upgrading the system based on future socio-economic developments.

4.1.2 Overview of the works

On this Contract the aim is to provide a basic level of services, with regards to improve aspects of the current conditions. The Contract will entail a provision of the services as listed in the Project Specification. Also, with regards to EPWP requirements, labour-intensive works comprise the activities described in SANS 1921-5, Earthworks activities which are to be performed by hand, and its associated specification data. Such works shall be constructed using local workers who are temporarily employed in terms of this Scope of Work. Time is of the essence for this contract. The Tenderer shall state the time in calendar months required by him/her to complete the Works. Tenderers offering early completion dates will generally be more favourably received, other things being equal.

The following activities are to be carried out:

Maubane (Hani View)

- Supply and installation of water lines as follows:
 - 63 mm Ø diameter class 12 uPVC reticulation pipeline for 1.6 km
 - Supply and installation of 100 metered yard connections.
- Pipe line ancillaries (valves and meters).

Dihibidung

- Supply and installation of water lines as follows:
 - 63 mm Ø diameter class 9 uPVC reticulation pipeline for 1.6 km
 - Pipe line ancillaries (valves and meters).

4.1.3 Labour-Intensive Works

All the relevant tasks/works shall be constructed using Labour-Intensive Construction Methods only.

4.1.4 Location of the works

The project areas are in ward 16 of the Moretele Local Municipality. The villages for the project are namely;

Village name	Ward	Latitude	Longitude
Maubane	16	25°17'28.08"S	28°16'45.44"E
Dihibidung	16	25°16'58.17"S	28°16'05.11"E

Locality Details

- Province : North West Province
- District : Bojanala District Municipality
- Municipality: Moretele Local Municipality

4.1.5 Temporary works

The Contractor shall provide, erect, maintain and remove on completion of the Contract, temporary offices and sheds for the storage of perishable materials and for the use of his workmen.



MORETELE LOCAL MUNICIPALITY

C4.2 Drawing Descriptions

The following drawings are applicable to the contract:

4.2.1 Key plans

All key plans for this type of project are included in the tender document as "Part C.8 Drawings".

4.2.2 Typical details

All typical details for this type of project are included in the tender document as "Part C.8 Drawings".

4.2.3 Civil engineering drawings

The drawings used for setting up the Bills of Quantities are as indicated above in paragraph 4.2.1 and 4.2.2.



MORETELE LOCAL MUNICIPALITY

C4.3 Procurement

3.4.1 Preferential procurement procedures

The works shall be executed in accordance with the conditions attached to preferences granted in accordance with the referencing schedule.

3.4.2 Scope of mandatory subcontract work

The following portions of the works shall be subcontracted to CIDB registered contractors in accordance with the subcontracting procedures described hereunder:

Competitive Bids shall be invited in respect of each of the above portions of the works in accordance with the relevant provisions of the latest edition of the CIDB Standard for Uniformity in Construction Procurement. The Contract Data in the associated procurement documents shall be based on the use of BIFSA Non-Nominated Subcontract for use with the JBCC Series 2000 Principal Building Agreement / CIDB Standard subcontract (labour only) / JBCC series 2000 Nominated / Selected Subcontract Agreement / SAFCEC General conditions of subcontract (2003 edition) (select appropriate option) / NEC Engineering and Construction Subcontract / NEC Engineering and Construction Short Subcontract with minimal project specific variations and amendments that do not change their intended usage.

The Employer together with the Contractor shall evaluate the Bids received in accordance with the provisions of the Standard Conditions of Bid contained in Annex F of Standard for Uniformity in Construction Procurement. The evaluation panel shall comprise equal representatives from the Employer and from the Contractor.

The Contractor shall without delay enter into contract with the successful Bidding subcontractor based on their accepted Bid submission. The Contractor shall remain responsible for providing the subcontracted portion of the works as if the work had not been subcontracted.



MORETELE LOCAL MUNICIPALITY

C4.4 Construction

4.4.1 Setting out of Works (Sub clause 5.1.1)

The Employer shall arrange for the Contractor to be given sufficient reference pegs from which to work. The value of all bench marks shall be given in writing. The Contractor shall bear the cost of any re-survey and the cost of re-establishment or checking of any pegs, bench marks, etc. disturbed, destroyed or interfered with in any way and the cost of any survey to prove the accuracy of the setting out after any disturbance of or interference with any peg or bench mark. All surveys or re-survey shall be by Surveyors appointed by the Employer."

4.4.2 Applicable national and international standards

SANS 1200

4.4.3 Particular / generic specifications

The relevant provisions of the SANS 1200 (1981edition) shall apply to the contract with the following amendments:

1115 Replace clause with the following:

The general conditions of contract are the General Conditions of Contract for Construction Works (2015) as published by the South African Institution of Civil Engineering read in conjunction with the Contract Data.

1202 Replace "Clause 15" with "Clause 12".

1206 Replace the first sentence with the following:

The contractor shall comply with all legal provisions in regard to surveying and setting out work.

1209(e) Replace "Clause 52" with "Clauses 29 and 49.2".

1210 Replace "Clause 54" with "Clause 51".

1212(1) Replace "Clause 49" with "Clause 46".

1215 Replace "Clause 45" with "Clause 42".

1217 Replace "Clause 35" with "Clause 31".

1303 Replace "Clauses 49 and 53" with "Clause 50".

13.01(3) Replace "Clauses 12 and 45" with "Clauses 1.1.4 and 42".

14.03(c) Replace "Clause 40(1)" with "Clause 37".

1505 Replace "Clauses 40 and 53" with "Clause 37".

3204(b) (iii) Replace "Clauses 40 and 53" with "Clause 37".

4.4.4 EPWP labour intensive specification

4.4.4.1 Labour intensive competencies of supervisory and management staff

Contractors having a CIDB contractor grading designation of **4 CEPE or higher**, shall only engage supervisory and management staff in labour intensive works who have either completed, or for the period 1 September 2020 to 31 July 2021, are registered for training towards, the skills programme outlined in Table 1.

The managing principal of the contractor, namely, a sole proprietor, the senior partner, the managing director or managing member of a close corporation, as relevant, having a contractor grading designation of **4 CEPE or higher** shall have personally completed, or for the period 1 September 2020 to 31 July 2021 be registered on a skills programme for the NQF level 2. All other site supervisory staff in the employ of such contractors must have completed, or for the 1 September 2020 to 31 July 2021 be registered on a skills programme for, the NQF level 2 unit standards or NQF level 4 unit standards.

Table 1: Skills programme for supervisory and management staff

Personnel	NQF level	Unit standard titles	Skills programme description
Team leader / supervisor	2	Apply Labour Intensive Construction Systems and Techniques to Work Activities Use Labour Intensive Construction Methods to Construct and Maintain the Pump Station Use Labour Intensive Construction Methods to Construct and Maintain Water and Sanitation Services Use Labour Intensive Construction Methods to Construct, Repair and Maintain Structures	This unit standard must be completed, and } any one of these 3 unit standards
Foreman/ supervisor	4	Implement labour Intensive Construction Systems and Techniques Use Labour Intensive Construction Methods to Construct and Maintain the Pump Station Use Labour Intensive Construction Methods to Construct and Maintain Water and Sanitation Services Use Labour Intensive Construction Methods to Construct, Repair and Maintain Structures	This unit standard must be completed, and } any one of these 3 unit standards
Site Agent / Manager (i.e. the contractor's most senior representative that is resident on the site)	5	Manage Labour Intensive Construction Processes	Skills Programme against this single unit standard

4.4.4.2 Employment of unskilled and semi-skilled workers in labour-intensive works

4.4.4.2.1 Requirements for the sourcing and engagement of labour.

4.4.4.2.1.1 Unskilled and semi-skilled labour required for the execution of all labour-intensive works shall be engaged strictly in accordance with prevailing legislation and SANS 1914-5, Participation of Targeted Labour.

4.4.4.2.1.2 The rate of pay set for the SPWP is **R 170 per task or per day**. Rate to be confirmed with client during construction stage.

4.4.4.2.1.3 Tasks established by the contractor must be such that:

- a) the average worker completes 5 tasks per week in 40 hours or less; and
- b) the weakest worker completes 5 tasks per week in 55 hours or less.

4.4.4.2.1.4 The contractor must revise the time taken to complete a task whenever it is established that the time taken to complete a weekly task is not within the requirements of 3.4.4.2.1.3.

4.4.4.2.1.5 The Contractor shall, through all available community structures, inform the local community of the labour-intensive works and the employment opportunities presented thereby. Preference must be given to people with previous practical experience in construction and / or who come from households:

- a) where the head of the household has less than a primary school education;
- b) that have less than one full time person earning an income;
- c) where subsistence agriculture is the source of income.
- d) those who are not in receipt of any social security pension income

4.4.4.2.1.6 The Contractor shall endeavour to ensure that the expenditure on the employment of temporary workers is in the following proportions:

- a) 60 % women;
- b) 20% youth who are between the ages of 18 and 35; and
- c) 2% on persons with disabilities.

4.4.4.2.2 Specific provisions pertaining to SANS 1914-5

4.4.4.2.2.1 Definitions

Targeted labour: Unemployed persons who are employed as local labour on the project.

4.4.4.2.2.2 Contract participation goals

4.4.4.2.2.2.1 There is no specified contract participation goal for the contract. The contract participation goal shall be measured in the performance of the contract to enable the employment provided to targeted labour to be quantified.

4.4.4.2.2.2.2 The wages and allowances used to calculate the contract participation goal shall, with respect to both time-rated and task rated workers, comprise all wages paid and any training allowance paid in respect of agreed training programmes.

4.4.4.2.2.3 Terms and conditions for the engagement of targeted labour

Further to the provisions of clause 3.3.2 of SANS 1914-5, written contracts shall be entered into with targeted labour.

4.4.4.2.2.4 Variations to SANS 1914-5

4.4.4.2.2.4.1 The definition for net amount shall be amended as follows:

Financial value of the contract upon completion, exclusive of any value added tax or sales tax which the law requires the employer to pay the contractor.

4.4.4.2.2.2.4.2 The schedule referred to in 5.2 shall in addition reflect the status of targeted labour as women, youth and persons with disabilities and the number of days of formal training provided to targeted labour.

4.4.4.2.2.5 Training of targeted labour

4.4.4.2.2.2.5.1 The contractor shall provide all the necessary on-the-job training to targeted labour to enable such labour to master the basic work techniques required to undertake the work in

accordance with the requirements of the contract in a manner that does not compromise worker health and safety.

- 4.4.4.2.2.2.5.2 The cost of the formal training of targeted labour, will be funded by the provincial office of the Department of Labour. This training should take place as close to the project site as practically possible. The contractor, must access this training by informing the relevant provincial office of the Department of Labour in writing, within 14 days of being awarded the contract, of the likely number of persons that will undergo training and when such training is required. The employer must be furnished with a copy of this request.
- 4.4.4.2.2.2.5.3 A copy of this training request made by the contractor to the DOL provincial office must also be faxed to the EPWP Training Director in the Department of Public Works, Fax Number 012 328 6820 or email cinderella.makunike@dpw.gov.za Tel: 083 677 4026.
- 4.4.4.2.2.2.5.4 The contractor shall be responsible for scheduling the training of workers and shall take all reasonable steps to ensure that each beneficiary is provided with a minimum of six (6) days of formal training if he/she is employed for 3 months or less and a minimum of ten (10) days if he she is employed for 4 months or more.
- 4.4.4.2.2.2.5.5 The contractor shall do nothing to dissuade targeted labour from participating in training programmes.

4.2.2.5.4 An allowance equal to 100% of the task rate or daily rate shall be paid by the contractor to workers who attend formal training, in terms of 4.4.4.2.2.2.5.4 above.

4.4.4.2.2.2.5.5 Proof of compliance with the requirements of 4.4.4.2.2.2.5.2 to 4.4.4.2.2.2.5.6 must be provided by the Contractor to the Employer prior to submission of the final payment certificate.

4.4.5 Plant and equipment

Add Sub-clause 4.4.5: Restriction on the use of plant.

"Except for the type of plant, and to the extent permitted in terms of the project specification or approved by the Engineer, in writing, the Contractor shall use only hand tools and equipment in the construction of the Works, or portion(s) of the Works, that are required in terms of the project specification to be constructed using labour intensive methods.

Failure by the Contractor to adhere to this clause will put him in breach of contract. The provisions contained in this contract with regard to labour content and labour-intensive construction, are binding, and will be enforced accordingly."

The plant and equipment used on the site shall not be inferior to that described in the Schedule of Plant and Equipment.



MORETELE LOCAL MUNICIPALITY

C4.5 Management

4.5.1 Applicable SANS 1921 standards

The following parts of SANS 1921 Construction works standards and associated specification data are applicable to the works:

- 1) SANS 1921-1:2004
- 2) SANS 1921-2:2004
- 3) SANS 1921-6:2004

The abovementioned South African National Standards make several references to the Specification Data for data, provisions and variations that make these standards applicable to this contract. The Specification Data shall have precedence in the interpretation of any ambiguity or inconsistency between it and these standards.

Each item of Specification Data given below is cross-referenced to the clause in the standard to which it mainly applies.

The associated Specification Data is as follows:

SANS 1921-1, Construction and management requirements for works contracts – Part 1: General engineering and construction works	
Clause	Specification data
Essential data	
4.1.7	There are no requirements for drawings, information and calculations for which the contractor is responsible
4.2.1	The responsibility strategy assigned to the contractor for the works is A.
4.3.1	The planning, programme and method statements are to comply with the following: <ul style="list-style-type: none">• format of programme,• critical path activities and their dependencies,• frequency of updating,
4.3.3	The notice period for inspection is 5 Days
4.7.3	The over break allowances for blasting are provided for in the scope of work.
4.9.3	The trees and shrubs which are not to be disturbed are identified in the scope of work.
4.12.2	The samples of materials, workmanship and finishes that the contractor is to provide and deliver to the employer are: <ol style="list-style-type: none">1) concrete works2) Pressure testing results done.
4.14.3	The office accommodation, equipment, accommodation for site meetings and other facilities for use by the employer and his agents are:

	1) Site office which shall be used for site meetings and for the contractor's use. Such an office shall comprise a minimum of 20m ² in area and 3 m high, be ventilated, have good lamination, must be reasonably sound proof, and have a hard floor construction. It shall be furnished with a desk on which drawings can be rolled open and on which there is sufficient writing space and sufficient temporary chairs or benches to accommodate all persons present at site meetings.
4.14.5	The Contractor is required to provide latrine and ablution facilities.
4.14.6	<p>The requirements for the provision and erection of separate sign boards for consultants and subcontractors are:</p> <ol style="list-style-type: none"> 1) The boards must comply with the official standard type signboard of the Employer and be at least 2750 x 1800 mm high. 2) The boards must be constructed with a firm flat exposed face using suitable material of firm construction, painted and lettered according to the standard drawings available from the Employer on request and mounted on sturdy pipe-standards at a height of 1800 mm above natural ground level.
4.17.1	<p>The requirements for the termination, diversion or maintenance of existing services are:</p> <ol style="list-style-type: none"> 1) Water 2) Electricity 3) Sanitation
4.17.3	<p>Services which are known to exist on the site are:</p> <ol style="list-style-type: none"> 1) Water 2) Sanitation 3) Electricity
Additional clauses	
<p>1 Site meetings and procedures</p> <p>The Employer's Representative and the Contractor shall hold meetings relating to the progress of the works at regular intervals and at other such times as may be necessary. The Contractor shall attend all site meetings and shall ensure that all persons under his jurisdiction are notified timeously of all site meetings should the Employer's Representative require their attendance at such meetings.</p> <p>The Contractor shall keep on site a set of minutes of all site meetings, daily records of resources (people and equipment employed), a site instruction book, a complete set of contract working drawings and a copy of the procurement document and make these available at all reasonable times to all persons concerned with the contract.</p> <p>2 Water</p> <p>The Contractor is to provide, and remove and make good upon completion, all the necessary temporary plumbing connections and purchase water from the local authority for the works at his own cost.</p> <p>3 Electricity</p> <p>The Contractor is to provide, and remove and make good upon completion, all the necessary temporary electrical connections and installations and purchase electricity from the local authority / ESKOM for the works at his own cost.</p>	

4.5.2 Particular / generic specifications

The management of the site shall be in accordance with the provisions of the SANS Standard Specification, obtainable from the South African Institution of Civil Engineering.

4.5.3 Recording of weather

The Contractor shall erect an effective rainfall gauge on the site and record the daily rainfall figures in a book. Such book shall be handed to the employer's representative for his signature no later than 12 days after rain that is considered to justify an extension of time occurs.

4.5.4 Unauthorised persons

The Contractor shall keep unauthorized persons from the works at all times Under no circumstances may any person except guards be allowed to sleep on the building site.

4.5.5 Management meetings

Site meetings will be held on monthly basis. The following parties are required to attend these meetings: the Employer's Representative, the Engineer and/or Representative, the Contractor and/or Representative, the Community Liaison Officer, the Health and Safety Officer and all members of the Project Steering Committee.

4.5.6 Forms for contract administration

These forms will be issued to the Contractor as required.

4.5.7 Electronic payments

Proof of all electronic payments must on request be supplied to the Employer.

4.5.8 Daily records

All accidents and incidents shall be recorded daily in a site diary. Apart from the site diary the Contractor shall provide a site instruction notebook for use by the Engineer. The notebook shall be signed by both the Engineer and the Contractor whenever a site instruction is issued by the Engineer.

4.5.9 Payment certificates

Contractor to submit claims for the work done. All claims are subjected to verification by the Engineer.

4.5.10 Permits

Contractor to ensure that no unauthorised persons are permitted to site

4.5.11 Proof of compliance with the law

Contractor to submit copies of the CIDB Registration and the Company Registration Certificates



MORETELE LOCAL MUNICIPALITY

C5. Project Specification

SCOPE

This project specification is set out in two parts. Portion 1 cover a general description of the project, the facilities available, and the requirements to be met. Portion 2 covers variations and additions to standardised or particular specifications that are applicable to the contract.

The numbering method in portion 2 of this project specification deviates as follows from the method suggested in Code of Practice SANS 1200.

Each clause with the prefix PS shall refer to the concurrent clause in the appropriate section of the standardised or particular specification. Such clause shall either substitute, or supplement, or amend the clause with the same number. Where there is no such concurrent clause in the standardised or particular specification, the PS clause shall be a new clause in the project specification. Any clause that is referred to in the standardised specification will also include the appropriate project specification

PORTION 1: THE WORKS

PS 1 GENERAL DESCRIPTION OF WORKS

Maubane (Hani View)

- Supply and installation of water lines as follows:
 - 63 mm Ø diameter class 12 uPVC reticulation pipeline for 1.6 km
 - Supply and installation of 100 metered yard connections.
- Pipe line ancillaries (valves and meters).

Dihibidung

- Supply and installation of water lines as follows:
 - 63 mm Ø diameter class 9 uPVC reticulation pipeline for 1.6 km
- Pipe line ancillaries (valves and meters).

Tenderers must note that certain rates in this tender are fixed and based on prices that the successful Tenderer shall undertake the complete construction of such installations. Tenderers are also to take note of the fact that the bulk of the work is to be executed by means of labour-intensive construction (LIC) methods, where feasible. The execution of the work will be done using the two following methods:

- (i) Established contractor to employ people from the communities where the work is to be done.
- (ii) Nominated emerging sub-contractors, which are to be employed and trained by the established contractor with the assistance of an approved training institution.

The tenderers must take note of the fact that it will be expected of the successful Tenderer to enter into a formal agreement with the Nominated Emerging Contractors (NEC) and all local labour to be employed on the project. The established/main contractor (MC) will be responsible for the quantity and progress of the work of the nominated emerging contractors.

The work to be carried out during the contract period may be given as separate tasks. Each task to be undertaken will be issued as a written instruction by the Engineer and will consist of a detail scope of work and relevant drawings for each particular task.

PS 2 DESCRIPTION OF THE SITE AND ACCESS

Refer to the "PART C.7 Site Information".

PS 3 DOCUMENTATION

PS 3.1 The Provisional Bill of Quantities is included in this document and *must be completed and handed in with the tender.*

PS 3.2 The drawings, for tender purposes, listed under part C3.2 are applicable to this contract

PS 3.3 The Tenderer shall check the Bills of Quantities for missing or duplicated pages and or drawings and should any be missing or duplicated, or the reproduction be indistinct, or if any doubt exists as to the full intent or meaning of any particulars or description, or this Bills of Quantities contain any obvious errors, the Tenderer shall notify the Engineer at once who shall promptly give a written directive. No liability whatsoever will be admitted in respect of errors in any tender due to the abovementioned causes.

No alteration, erasure, omission or addition is to be made in the text and conditions of these Bills of Quantities or other documents. Should any such alterations, amendment, note or addition is made, it will not be recognised and the text of the Bills of Quantities or other documents as prepared by the Representative must be adhered to.

PS 3.4 The Tenderer shall examine all project documents and shall thoroughly acquaint himself with the nature and extent of the Works and the manner in which they are to be executed as no claim for extra payment will be entertained.

PS 4 NATURE OF GROUND AND SUBSOIL CONDITIONS ON SITE

No bore tests or investigation of the in-situ material were done, over and above the provided information if any.

The water table may be relatively high during the summer months and provision must be made for effective draining of excavations.

It is the Contractor's responsibility to supply and deliver all material that complies with the minimum standards as well as for the building and maintaining of access roads to the works on site, haul areas or dumping sites. No additional payment will be applicable to the abovementioned, other than the relevant items in the schedule of quantities.

No trial holes were dug along the network layout. Note that the prospective tenderers shall acquaint themselves with the nature of materials on site.

PS 5 DETAILS OF THE CONTRACT

PS 5.1 MAIN CONTRACTS

Work included in this contract involves the scope of work as per paragraph PS1.

The other main components of the work under this contract are:

- a) Establishment of the Contractor's camp.
- b) Site clearance and earthworks.
- c) Provision of all materials, special fittings and accessories as required, to complete the work as prescribed.
- d) Excavation and backfill compacted as specified, of pipe trenches and the removal of all excess material.
- e) Laying, bedding and installation of all pipes and accessories.
- f) Concrete work associated with the abovementioned equipment.
- g) Construction of concrete anchor blocks associated with the above.
- h) Commissioning of the works.
- i) Maintenance on the works for a twelve-month period.

PS 6 CONSTRUCTION PROGRAM AND METHODS

The construction site is situated in a built-up area; the Contractor shall ensure the least possible disruption of movement of the public during construction.

Construction methods must be of such a nature that no property or life is endangered. The Employer accepts no responsibility for work that is done without consent by the Engineer outside the site boundaries. The Contractor himself is responsible for liaison and arrangements with the Local Authority in connection with the finalisation and approval of the construction program.

The Contractor is responsible for liaison and the necessary arrangements with the relevant water authorities in respect of the finalisation and approval of the works programme.

Sufficient photos of existing structures, walls, and areas that have to be crossed must be taken by the Contractor and handed over to the Engineer before such operations commence. No payment will be made in this regard and it shall be deemed to be covered in the Preliminary and General items.

Local labourers must do the trench preparation, bedding, handling, laying and backfilling of pipes and fittings. The contractor is responsible to liaise with the Labour Desk for labourers.

No separate payment shall be made for any arrangements with relative local authorities for closing off the current water supply or for the distribution of notices to the public.

The compilation of the construction programme and any amendments thereto during the course of construction shall be at the cost of the Contractor and shall not be measured elsewhere in this contract. The contract has to be completed within the time specified in the "Contract Data" of this document, excluding the builder and public holidays.

PS 7 SITE FACILITIES AVAILABLE

PS 7.1 SOURCES OF WATER SUPPLY, POWER SUPPLY, SANITATION, AND COMMUNICATION

Water for construction purposes will be for the account of the contractor at the ruling tariff and will be supplied at a suitable point, from where the contractor will be responsible to convey the water to the point of usage. Water for human consumption will be from the existing reticulation at the ruling tariff. Electrical power is available from the existing network at ruling tariffs. The Contractor shall make his own arrangement for any water or power he may require. Any extension of time due to delays resulting from these facilities will not be granted.

The Contractor must supply and maintain at his own cost a sufficient number of portable chemical toilets, one of which must be situated at the campsite and the rest in the area of the site.

No waste or sludge must be left uncovered until it is removed. The contractor must operate an efficient solid waste removal system to the satisfaction of the engineer for the duration of the contract.

The Contractor must make his own arrangement for communication and a telephone service.

PS 7.2 LOCATION OF CAMP AND DEPOT

The contractor is responsible for establishment of their own site camp and depot. No trees may be removed and the Contractor must provide his own firewood.

PS 7.3 HOUSING FOR CONTRACTOR'S EMPLOYEES

No housing is made available for the Contractor's employees, and the Contractor shall make his own arrangements for housing his employees or transporting them to and from the site. The Contractor is in all respects responsible for the housing and transporting of his employees, and for the arrangement thereof, and no extension of time due to any delays resulting from this, will be granted.

PS 8 SITE FACILITIES REQUIRED

No housing is required for the Engineer. Other facilities such as an office, telephone, name board, survey equipment, etc. required for the Engineer, are described under the relevant sections.

PS 9 FEATURES REQUIRING SPECIAL ATTENTION

PS 9.1 CONTROL OF WATER

The Contractor is in all respects responsible for the handling of storm water from higher-laying areas, adjacent to the works for the handling of possible sub-surface water and for the handling of spoiled water when disconnecting existing connections or valves. No separate payment shall be made for this, as all costs related thereto shall be deemed to be included elsewhere in the tendered rates.

PS 9.2 "AS BUILT" DRAWINGS

As the work progresses, the Contractor shall keep full records of all amendments to and deviations from the drawings as issued to the Contractor at the start of the contract. The true positions, invert levels and ground levels of all services shall be indicated on the drawings, for which purpose the Contractor shall receive a separate complete set of drawings from the Engineer, at no cost.

The completion certificate shall only be issued after the Engineer has received a properly completed set of "AS-BUILT" drawings from the Contractor. No separate payment shall be made for this service, as all costs related thereto shall be deemed to be included in the related items.

PS 9.3 FINISHING AND TIDYING

Progressive and systematic finishing and tidying will form an essential part of this contract. Under no circumstances shall spoil, rubble, materials, equipment or unfinished operations be allowed to accumulate unnecessarily and in the event of this occurring the Engineer shall have the right to withhold payment for as long as necessary in respect of the relevant works in the area(s) concerned.

PS 9.4 SURVEY BEACONS

No separate payment shall be made for this, as all costs related thereto shall be deemed to be included elsewhere in the tendered rates.

PS 9.5 CONSTRUCTION MODUS OPERANDI

Labour-based or labour-intensive construction may be defined as the economically efficient employment of as much labour as is technically feasible to produce as high a standard of construction as demanded by the specification and allowed by the funding available. In other words, projects based on labour-intensive principles aim at devoting the highest feasible proportion of projects costs to unskilled, semi-skilled and skilled labour without jeopardising the technical quality of the product demanded by the specification.

The following regulations must be adhered to so as to ensure that the construction methods used are labour intensive.

- i) If not scheduled elsewhere otherwise the remuneration to local labour for hourly-rated employees and/or daily-based work shall be in accordance with the terms and conditions of Proclamation R1841 of Government Gazette 16833 dated 24 November 1995 or its latest amendment.
- ii) The name, identification number, task performed, and hours worked per day for each labourer shall be recorded by the Contractor. These records shall be submitted to the secretary of the Project Steering Committee on the second working day of each week following the recounted week.

The employment of local labour must be at least **30%**, if at all possible, of the total contract amount. The 30% must be divided as follows:

Percentage of labour	Description
50%	Women
15%	Youth (Above school, but under 36)
1.5%	Disabled persons

PS 9.6 LOCALLY BASED SUB-CONTRACTORS

Tenderers are encouraged to utilise the services of locally based sub-contractors.

PS 10 TRAINING

PS 10.1 General

A suitably capable Training consultant is to be employed on this project.

Their duty is to train the identified suitable persons for the following:

- i) Employee Training – community-based labour
- ii) Employer Training – community-based contractors
- iii) Committee Training – maintenance and operation of the Works (this however falls outside the scope of this Contract)

This project is a project using community-based labour and community-based contractors as far as possible.

The Contractor using the necessary plant and labour as he sees fit shall carry out conventional construction. However, the Contractor may only bring in key staff from outside the area that has the necessary skills not available among the local community. Other than key staff, all other labour must be employed from the local communities. As a guideline, key staff would include general foreman, foreman, site managers, buyers, quantity surveyors, etc.

The Training Consultant will provide the necessary training so that the local labourers will have the necessary skills to carry out this work. In this respect, the contractor and the Training Consultant will have to work closely together to identify what skills are required, how many labourers in each trade are required and when this labour will be required, so that the necessary training can be given timeously.

Typical training that is envisaged at this stage includes shuttering, concrete work, reinforcing, team leaders, etc.

The other part of the Contract is work that will be carried out by community-based contractors.

The Training Consultant will identify persons, with the assistance of the Project Steering Committee, and train these persons to establish small community based contracting firms, who will employ local labour. These firms will tender to carry out this work and successful Tenderers will be appointed by the Contractor as nominated sub-contractors to execute this work.

Typical training that will be given by the Training Consultant is:

- i) Community based contractors
 - Preparation phase – using a calculator, numeracy, using a scale ruler, reading a building plan, handling administrative tasks in the building industry.
 - Estimating and tendering – marketing the services of a company, seeking, selecting, collecting and studying tender documents, investigating and assessing a site, developing a bill of quantities from building plants, calculating the cost of a project, finalizing tender prices, completing and submitting a tender.
 - Project planning – introducing to planning techniques, pre-tender planning, planning contract activities, contract planning, executing a contract programme.
 - Executing the project – managing the finances of the company, managing materials, administering record systems, managing manpower, completion and handover.
- ii) Community based labour
Local labour will be taught the following skills:
 - Excavation if possible, bedding, selected backfill and backfill
 - Pipe laying, valves and fittings
 - Valve boxes, manholes, anchor blocks etc.

Again, the Contractor and Training Consultant will have to work closely together to identify what their requirements are and when this labour is needed.

Community based labour training will take place on site before actual production starts. No allowance needs to be made for wages, food or travelling during training.

Training of community-based contractors will take place at a central point. The Provincial Sum allowed in the Schedule of Quantities, makes allowance for travelling and meals for the training of community-based contractors.

PS 10.2 Construction and Materials Management

This section applies only to work to be carried out by community-based contractors.

The contractor shall provide construction and material management to the community-based contractors. In this respect, each party has the following responsibilities.

i) Community Based Contractors

- To tender on the labour-based sub contract work and enter into a contract with the Contractor.
- To carry out the work according to specification and on time using community-based labour.
- To liaise and co-operate with the contractor regarding specifications, programme, progress, delivery of material, quality of work etc.
- To provide wheelbarrows, hand tools, clothing, safety equipment, etc. to enable his labourers to carry out the work. All material (pipes, fittings, valves, etc.) to be provided by the Contractor.
- To receive material required for the task, store it and provide the necessary security until the material is built into the works.
- To provide the necessary transport for this labour force.
- To carry out a task in its entirety until final approval and acceptance. In other words, there will be no split responsibility. For example, a community-based contractor will excavate, provide the bedding, selected backfill, backfill, lay pipes, valves and fittings, build valve boxes, manholes, anchor blocks etc. and test the pipes in conjunction with the Contractor.
- To pay his labourers. VAT etc. and finalize the final account.

ii) Contractor

- In conjunction with the Training Consultant, establish the needs, training and programming of the work.
- To assist the Training Consultant in drawing up the agreements of association between the Contractor and the community-based contractors where applicable.
- To enter into nominated sub contracts with the community-based contractors.
- To provide the necessary skills transfer and construction management for the community-based contractors to successfully complete this work. This includes setting out of the work, quality control over the work, programming of the work, progress, testing and acceptance thereof.
- To provide the necessary materials to execute the work. This includes purchasing the required materials, transporting them to the camp site, storage at the campsite, transporting of materials as required from camp site to the sites of the various community-based contractors, handling over of the materials.
- To pay the community-based contractors as the work progresses and the Contractor must make allowance in his Tender for this. Retention monies will be as for this Contract. No sureties will be required from the community-based contractors.
- To measure the work and finalize the final account.
- Complete copies of the emerging contractor's contracts to be given to the Engineer for endorsement prior to the contract being signed.

Candidate selection would be according to the requirements for a particular discipline. A Certificate of Achievement should be awarded to a student who has attained a prescribed level of competency.

A provisional amount for training has been recorded in both sections under the Item "Training", in the Preliminary and General portions in the Schedule of Quantities.

PS 11 APPLICABLE STANDARDISED SPECIFICATIONS

Although not bound in nor issued with this document, the following standardised specifications shall form part of the contract and, notwithstanding the provisions of sub clause 2.2 of SANS 1200 A, the editions specified below shall apply:

SANS 1200 A	- 1986	General
SANS 1200 C	- 1980	Site Clearance
SANS 1200 DB	- 1989	Earthworks (Pipe Trenches)
SANS 1200 L	- 1983	Medium pressure pipe lines
SANS 1200 LB	- 1983	Bedding (Pipes)
SANS 1200 LF	- 1990	Erf Connection (Water)

The newest additions of above specifications up to and including the month of this tender will prevail.

PROJECT SPECIFICATION

PORTION 2: VARIATIONS AND ADDITIONS TO STANDARDISED SPECIFICATIONS

SANS 1200 A: GENERAL

PS A 3 MATERIALS

PS A 3.1 QUALITY

Substitute the second sentence of the first paragraph of A 3.1 with the following:

Materials shall bear the official mark of the appropriate standard.

Substitute the second paragraph with the following:

The Contractor is responsible for the cost of all testing to ascertain that the materials do comply with the relevant minimum requirements and all such costs shall be deemed to be included in the tendered rates. The cost of control tests done by the Engineer and of which the results do not comply with the minimum requirements shall be for the Contractor's account.

The Contractor shall inform the Engineer of any control testing to be done at least 48 hours before such tests are required and must allow in his program for the time necessary for the tests and the processing of the results thereof.

The handling, storage, transport, and erection of equipment, machinery, and materials shall be strictly in accordance with the requirements of the supplier and/or manufacturer.

All materials shall be new and of the best quality available unless otherwise specified. They must function satisfactorily under prevailing climate and weather conditions at the place of installations.

PS A 4 PLANT

PS A 4.2 Contractor's Offices, Stores and Resources

Add the following to A 4.2:

No housing is available for the contractor's employees and the contractor must make his own arrangements for accommodation and transport of his employees.

PS A 4.3 Hand Tools

The contractor shall provide and maintain all hand tools required for the execution of the Works.

PS A 5 CONSTRUCTION

PS A 5.1 SURVEY

PS A 5.1.1 Setting out of the Works

Substitute the first sentence in A 5.1.1 with the following:

Setting out of the works is the sole responsibility of the Contractor and shall be done from the layouts given to him. The proposed network pipes must be placed 2,0m away from the erf boundaries in the road reserve. Any discrepancy shall immediately be reported in writing to the Engineer. Any costs or subsequent costs arising from discrepancies, which had not been reported to the Engineer, shall be the sole responsibility of the Contractor. *The exact position*

of the network pipes shall be determined on site in conjunction with the Engineer and must be approved before construction of the specific section starts.

The Engineer may alter any part of the works to suit local conditions. The Contractor must therefore contact the Engineer immediately after the preliminary setting out of any part of the works before starting with detail setting out, or construction. Only after the Engineer has approved a specific site or part of the works, may the detail setting out and construction commence.

PS A 5.2 WATCHING, BARRICADING, LIGHTING AND TRAFFIC CROSSINGS

Add the following to A 5.2:

The crossing of existing tar and dirt roads must be done in half widths, while the total traffic is accommodated on the other lane.

Road traffic signs shall comply with the requirements of the "South African Road Traffic Signs Manual" and shall be approved by the Engineer before construction commences.

PSA 7 TESTING

PS A 7.4 STATISTICAL ANALYSIS OF CONTROL TESTS

Substitute A 7.4 with the following:

Test results shall not be evaluated by statistical methods. All results shall comply with the specified minimum requirements of the materials concerned.

PS A 8 MEASUREMENT AND PAYMENT

PS A 8.2 PAYMENT

PS A 8.3 Fixed-charge and Value-Related Items

PSA 8.3.1 Contractual Requirements..... Unit: Sum

The sum shall cover the Contractor's initial costs of providing sureties, insurance of the works and plant, third party or public liability insurance and unemployment insurance to cover his compliance with the requirements of the Workmen's Compensation Act, 1941 (Act NO. 30 of 1941) and any other initial financing obligations of a preliminary and general nature, such as contributions to the CEITB..

The tendered amounts for fixed-charge and value-related items will not be increased, if extension of time for the completion of the works is awarded.

PSA 8.3.2 Establishment of Facilities on the Site

PSA 8.3.2.1 Facilities for Engineer

- a) Furnished office (No) Unit: Sum
- b) Telephone (No) Unit: Sum
- c) Name board (1 No.) Unit: Sum

SA 8.3.2.2 Facilities for Contractor

a)	Offices, and storage sheds	Unit: Sum
b)	Workshops.....	Unit: Sum
c)	Laboratories.....	Unit: Sum
d)	Living Accommodation.....	Unit: Sum
e)	Ablution and Latrine Facility.....	Unit: Sum
f)	Tools and Equipment.....	Unit: Sum
g)	Water Supplies, Electrical power and Communication.....	Unit: Sum
h)	Dealing with water.....	Unit: Sum
i)	Access	Unit: Sum
j)	Plant	Unit: Sum

PSA 8.3.3 Other Fixed-Charge Obligations..... Unit: Sum

This item as listed under Schedule A of the bill of quantities is as specified in the standardised specification SANS 1200 A.

PSA 8.3.4 Removal of Site Establishment..... Unit: Sum

The sum shall cover the cost of the demolition on and the removal from the surface of the site of all items established in terms of 8.3.2 and 8.3.3, and shall provide for the making good and the restoring of the Site to the satisfaction of the Engineer

PSA B.8.3.5 OCCUPATIONAL HEALTH AND SAFETY

PSA B.8.3.5.1 Contractor's initial obligations in respect of the Occupation Health and Safety Act and Contractual Regulations..... Unit: P/Sum

The full amount will be paid on the scheduled rate on condition that:

- (a) The contractor has notified the Provincial Director of the Department of Labour in writing of the project.
- (b) The contractor has made the required initial appointment of Employees and sub- contractors
- (c) The client has approved the contractor's Health and safety plan
- (d) The contractor has set up his Health and safety File and Safety Plan.
- (e) The Contractor has appointed a Health and Safety officer.

The provincial sum shall represent full compensation for that part of the contractor's general obligations in terms of Occupational Health and Safety Act and the Construction Regulation which are mainly a function of time. The sum for the supply of all safety equipment, safety clothing, first aid kit, etc. in order to adhere to the Occupational, Health and Safety Act specifications. The Contractor must familiarise himself with the conditions as per Occupational, Health and Safety Act and adhere thereto. The rate shall cover the Contractor's overheads, charges, and profit on payments for the Service Provider. Contractor to note that this item covers the costs for the preparation and submission of Health and Safety plan and file.

Payment shall be as specified for item 1.3 in the standard specifications

PSA B.8.3.5.2 Occupational, Health and Safety Act..... Unit: %

Handling cost in respect of sub-item 8.3.5.1 A percentage of the payment made to the Occupational health and safety act will be paid to the Contractor under this section. The rate shall cover the Contractor's overheads, charges, and profit on payments for the Occupational health and safety act.

(a) Provision for safety officer

The Contractor should appoint the safety officer who will be full time responsible for all safety issuers on site, and he or she should be full time on site.

The tendered rates include the full compensation for that part of the provision of safety officer in terms of the Occupational Health and Safety Act and the construction regulation which are mainly a function of time. Payment shall be made monthly.

(b) Handling cost in respect of sub-item 8.3.5.2 (a). A percentage of the payment made to the Safety Officer will be paid to the Contractor. The rate shall cover the Contractor's overheads, charges, and profit on payments for the Safety Officer.

PSA B.8.3.5.3 Contractor's time related obligation in respect of the OH&S Act and Construction regulation

The tendered lump sum shall represent full compensation for that part of the contractor's general obligations in terms of Occupational Health and Safety Act and the Construction Regulations which are mainly a function of time. The lump sum will be paid monthly only after payment for item 1.3.3 and item 1.1.5 has been made. Payment of the lump sum shall be made monthly (calculated by the division of the lump sum by the number of months remaining)

PS A 8.2.2 Time-Related Items

The tendered amount for a time-related item will be increased; if an extension of time for the completion of the works is awarded on the condition that the activity related to the item tendered for must be sustained during the extended period.

The ratio between the increased amount for a time-related item and the tendered amount must be the same as the ratio between the extension of the time period for the completion of the works and the original time period allowed for completion of the works.

If the works is completed before the end of the original time period allowed for completion of the works, the tendered amount of a time related item that is influenced by the earlier completion would be reduced similarly.

PS A 8.4 SCHEDULED TIME RELATED ITEMS

PSA 8.4.2.1 Facilities for Engineer

a) Furnished offices Unit: Month
b) Telephone for engineer's representative..... Unit: P/Sum

PSA 8.4.2.2 Facilities for Contractor.....Unit: Month

The sum shall cover the Contractor's initial costs of providing sureties, insurance of the works and plant, third party or public liability insurance and unemployment insurance to cover his compliance with the requirements of the Workmen's Compensation Act, 1941 (Act NO. 30 of 1941) and any other initial financing obligations of a preliminary and general nature, such as contributions to the CEITB. Establishment of Facilities on the Site Facilities for Engineer

a) Offices, and storage sheds Unit: Month
b) Workshops..... Unit: Month
c) Laboratories..... Unit: Month
d) Living Accommodation..... Unit: Month
e) Ablution and Latrine Facility..... Unit: Month
f) Tools and Equipment..... Unit: Month
g) Water Supplies, Electrical power and Communication..... Unit: Month
h) Dealing with water..... Unit: Month
i) Access Unit: Month
j) Plant Unit: Month

PSA 8.4.3 Supervision for Duration of Construction..... Unit: Month

The sum shall cover the costs of on-site supervision and such local administration as the Contractor considers necessary for the proper completion of the Works, and shall cover the cost of the salaries, wages and allowances paid to the site agent, general foreman, section foremen (where applicable), site surveyors, timekeepers, assistants and other site supervisory staff, and of transport incurred in connection with such staff. Plant (designated plant or plant for designated operations or plant for use during Supervision for Duration of Construction

PSA 8.4.4 Company and Head Office Overhead Cost/s for the Duration of the Contract.... Unit: Month

The sum shall cover the Contractor's company and head office overhead costs.

PS A 8.5 SUMS STATED PROVISIONALLY BY ENGINEER

PS A 8.5(a)1 Community Liaison Officer

Unit : P/Sum

The Contractor must pay a salary to a person appointed as the Community Liaison Officer for the project. The amount of payment and payment dates will be determined as soon as the Community Liaison Officer is appointed. Proof of payment has to be submitted to Engineer before claim can be certified

PSA 8.5 (a) 2 PSC Meetings Attendance

Unit: P/Sum

The tendered rate shall cover the compensation of all members of Project Steering Committee for attending meetings. The amount of payment and payment dates will be determined on the commencement date of the project. The Engineer should authorise payment before it is made. Proof of payment has to be submitted to Engineer before claim can be certified.

PS A 8.5(a)3 Overheads, charges and profit on (a)1 & 2 above

Unit : %

Handling cost and profit in respect of sub-item 8.5(a)1&2. A percentage of the payment made to the Community Liaison Officer and PSC Meeting attendance will be paid to the contractor. The rate shall cover the Contractor's overheads, charges, and profit on payments for the Community Liaison Officer and PSC members. No payment will be made under this item before payment to the Community Liaison Officer and PSC members is made.

PS A 8.5(b)1 Training

Unit : P/Sum

Provisional sum for training services supplied by the Training Company. The name and contact details of the Training Company, to be appointed by the Contractor, will be supplied to the Contractor by the Employer or Engineer.

PS A 8.5(b)2 Overheads, changes and profit on (b)1 above

Unit : %

Handling cost and profit in respect of sub-item 8.5(b)1. A percentage of the payment made to the Training Company will be paid to the Contractor. The rate shall cover the Contractor's overheads, charges, and profit on payments for the Training Company. No payment will be made under this item before any payment is made to the Training Company.

PS C 8.5 EXISTING SERVICES

The services parallel to the pipeline routes must only be removed, repaired if damaged in a process and relocated to the positions as indicated and approved by the Engineer. When the pipeline routes cross fencing or gates temporary wire gates must be provided that must be kept closed. After completion of the work these fences or gates must be repaired to the same condition as before commencement of the work.

PS A 8.5(c)2 Overheads, changes and profit on (1) above**Unit : %**

Handling cost in respect of sub-item 8.5(c)1. A percentage of the payment made to the Service Provider will be paid to the Contractor. The rate shall cover the contractor's overheads, charges, and profit on payments for the Service Provider.

PS A 8.7 DAYWORK

Replace A 8.7 with the following:

Daywork will be paid according to the percentage allowance method. For calculating the total remuneration, the General Conditions of Contract for Construction Works, Third Edition, 2015 shall apply, with the amendments as in the appropriate special conditions of contract, which is bound into this document. A daywork schedule will be provided for filling in the necessary information.

A 8.8 TEMPORARY WORKS**PS A 8.8.2 Accommodation Of Traffic****Unit: Sum**

Add the following to A 8.8.2:

The rate shall cover all costs pertaining to the provision, erection, moving, re-erection and maintenance of all temporary barricades, road signs, lights, flagmen, etc. as required, for the guarding and protection of the works, for the construction, gravelling and maintenance of access roads and detours to the site of the works, borrow pits or spoil sites, as well as for the later removal or the cleaning and tidying up thereof.

PROJECT SPECIFICATION

PORTION 2: VARIATIONS AND ADDITIONS TO STANDARDISED SPECIFICATIONS

SANS 1200 AB: ENGINEER'S OFFICE

PS AB 3 MATERIALS

PS AB 3.1 NAME BOARDS

Substitute "South African Institution of Civil Engineers" in the first paragraph of AB 3.1 with "South African Association of Consulting Engineers".

PS AB 3.2 OFFICE BUILDING

Replace AB 3.2 with the following:

Prior to commencing with work, the contractor shall provide and furnish for the use of the engineer's representative and his staff one office (3.0 x 4.5m Wendy House Type with veranda) in an approved position. The Engineer will indicate the position. All plans shall be submitted to the engineer for approval, before the commencement of erection.

The office with a minimum floor area of 13.50m² (the smaller dimension at least 3.0m) with a ceiling height of minimum 2.1m, shall also have one toilet apart from the office building for the exclusive use of the engineer's representative.

The office shall be provided with lined walls and boarded ceilings and floor and suitable door with secure locks. The office shall be ventilated, weather proof and waterproof and shall have windows with an area to at least 20% of the floor area. The office shall be insulated to provide comfortable working conditions.

Internal furnishings shall include:

- One desk (1,5m long x 1,0m wide x 0,9m high) with lockable drawers with keys
- One drawing table
- Eight desk chairs
- One table (2,0m long x 1,0m wide x 0,9m high) with smooth top.

PS AB 4 PLANT

PS AB 4.1 TELEPHONE AND FAX

Replace AB 4.1 with the following:

The Contractor shall supply the Engineer with a cellular telephone service for the exclusive use of the Engineer and Engineers Representative for official purposes for the duration of the contract.

PS AB 5 CONSTRUCTION

PS AB 5.1 NAME BOARDS

Add the following to AB 5.1:

The name boards shall be erected within a month of the commencement date of the contract and shall be placed at the position indicated by the Engineer. Any damage to these boards shall be repaired within seven days of a written instruction issued by the Engineer. No payment shall be made in terms of the contract prior to the erection of the name boards.

The Contractor will be permitted to erect a maximum of two of his own name boards, in positions approved by the Engineer. The Engineer reserves the right to order the removal of these boards if they are not kept in good repair.

PS AB 5.5 SURVEY ASSISTANTS

Substitute "two or more suitably educated survey labourers" in the first sentence of PS 5.5 with "two semi-skilled labourers."

PS AB 5.6 SURVEY EQUIPMENT

The Contractor shall provide the following tested and approved survey equipment on site for the duration of the contract and for the use of the Engineer whenever needed:

- a) one tachometer capable of reading to minimum 20 seconds and maximum 6 seconds of arc, plus tripod;
- b) one automatic level plus tripod;
- c) two tachometer staffs and one level staff, all graduated metrically;
- d) one 5m and one 100 m tape measure; and
- e) diverse surveyors' necessities like paint, pegs, etc.

The above-mentioned equipment may by arrangement be shared between the Contractor and the Engineer's representative.

The Contractor shall keep the equipment continuously insured against any loss, damage, or breakage, and he shall indemnify the Engineer and the Employer against any claims in this regard.

The Contractor shall maintain the equipment in good working order and keep it clean throughout the contract period.

PS AB 8 MEASUREMENT AND PAYMENT

PS AB 8.2 PAYMENT

PSAB 8.2.2(a) Office buildings Unit: Sum

The rate shall cover all time-related costs pertaining to the office building as prescribed in PS AB 3.2.

PSAB 8.2.2(b) Telephone and fax Unit: Sum

The rate shall cover all time-related costs pertaining to the telephone and fax as prescribed in PS AB 4.1.

PS AB 8.2.2(c) Name board (1 off) Unit: Sum

The rate shall cover all time-related costs pertaining to the name board/s as prescribed in PS AB 5.1.

PSAB 8.2.2(d) Survey assistance and equipment Unit: Sum

The rate shall cover all time-related costs pertaining to the survey assistants and equipment as prescribed in PS AB 5.6.

PROJECT SPECIFICATION

PORTION 2: VARIATIONS AND ADDITIONS TO STANDARDISED SPECIFICATIONS

SANS 1200 C: SITE CLEARANCE

PS C 3 MATERIAL

PS C 3.1 DISPOSAL OF MATERIAL

Substitute the first sentence of C 3.1 with the following:

Material obtained from clearing and grubbing shall be disposed of at the site indicated at the site inspection. If such a site is indicated at tender stage, the cost of transporting material and debris will be included under 8.2.1.

Loading and off-loading should be done by hand and the contractor must price accordingly under item 8.2.1.

PS C 5 CONSTRUCTION

PS C 5.1 AREAS TO BE CLEARED AND GRUBBED

Substitute the first sentence of C 5.1 with the following:

Unless otherwise indicated by the Engineer, clearing and grubbing are limited to a 2,5m wide strip along the pipe route. Measurement and payment for clearing and grubbing shall only occur for areas as required in writing by the Engineer.

The Contractor may proceed with clearing and grubbing after the handing over of the site.

PS C 5.2 CUTTING OF TREES

PS C 5.2.3 Preservation of Trees

PS C 5.2.3.2 Individual trees

Add the following to C 5.2.3.2:

Trees outside pipeline routes must be left standing and undamaged, except where otherwise ordered in writing by the Engineer.

A penalty of **R15 000,00** per tree for trees damaged and/or removed will be charged.

PSC 5.3 EXISTING FENCING

The fencing parallel to the pipeline routes must only be removed and re-erected at the positions as indicated and approved by the Engineer and repaired where it was damaged. When the pipeline routes cross fencing or gates temporary wire gates must be provided that must be kept closed. After completion of the work these fences or gates must be repaired to the same condition as before commencement of the work.

PS C 8 MEASUREMENT AND PAYMENT

PS C 8.2 SCHEDULED ITEMS

PS C 8.2.1 Clear and grub (1.0m wide)

Unit: m

The removal of all rocks and boulders on site over 0,15 m³ will be paid under sub clause D 8.3.2(b). The removal of hard rock other than boulders will be paid under sub clause PS DB 8.3.2(b).

PSC 8.2.2 Remove and grub large trees and tree stumps of girth

a) over 1 m and up to and including 2 m Unit: No
b) over 2 m and up to and including 3 m Unit: No

The girth of a tree or stump will be measured at the narrowest point of the tree or stump in the first metre of its height above ground level. Trees and stumps of girth exceeding 1 m will be measured individually and classified according to site in increments of 1 m as indicated above.

The rate shall cover the cost of clearing and grubbing trees and stumps of all sizes, cutting branches, backfilling holes, and removing, transporting, and disposing of all such trees, stumps, and branches and associated material.

PSC 8.2.3 Remove and grub all trees and tree stumps regardless of girth Unit: No

In exceptional circumstances, where construction is carried out through plantations or where the quantity of trees or girth exceeding 1 m renders individual measurement impracticable the project specification may provide that the clearing and grubbing of trees be measured in hectares. If this method of measurement is used the areas to which it is applicable will be defined clearly on the drawings and the reason for adopting the method of measurement will be stated in the project specification.

The rate shall cover the cost of all operations specified in .8.2.2.

PSC 8.2.5 Take down existing fence..... Unit: m

The rate shall cover the cost of taking down the fences, coiling wire, sorting and stacking all material at sites indicated by the Engineer and the cost of loading, transporting and offloading such material.

The rate shall cover the cost of reinstating fence to original condition on completion of all scheduled work

PROJECT SPECIFICATION

PORTION 2: VARIATIONS AND ADDITIONS TO STANDARDISED SPECIFICATIONS

SANS 1200 DB: EARTHWORKS (PIPE TRENCHES)

PSDB 1 SCOPE

This specification covers earthworks for trenches for all types and sizes of pipes. It covers excavation, the preparation of a trench bottom, backfilling and the reinstatement of surfaces.

PS DB 3 MATERIALS

PS DB 3.1 CLASSIFICATION FOR EXCAVATION PURPOSES

PS DB 3.1.1 Method of Classifying

Substitute DB 3.1.1 and DB 3.1.2(a), (b) and (c) with the following:

The Engineer shall classify excavated materials as Soft Class and Rock. Rock will be measured individually as extra-over items.

TABLE 1: CLASSIFICATION OF MATERIALS

CLASSIFICATION	DESCRIPTION
Soft	All material other than rock
Rock	Material which cannot be economically fragmented and loosened for removal by hand implements and pneumatic tools, except by drilling and blasting or the use of rock breaking equipment.

In the first instance, the classification shall be based on the descriptions given in Table 1. In the event of disagreement between the Contractor and the Engineer, the Engineer shall reclassify the material in accordance with relevant specifications and without being unreasonable to the Contractor. The decision of the Engineer on the classification shall then, subject to the provisions of the Contract, be final and binding.

The Contractor shall notify the Engineer of the presence of what he considers to be rock immediately upon discovery thereof. The Engineer will inspect the material and decide whether or not it warrants the use of pneumatic tools or rock breaking equipment. In the case of isolated boulders set in a soil matrix, the Engineer may order the Contractor to either widen the excavation or roll the boulders sideways or lift the boulders out from the trenches.

In the event that the Engineer decides that the use of pneumatic tools, rock breaking equipment, or blasting is necessary, he will classify the material accordingly and arrange for the quantity thereof to be measured. The Construction Manager will supply necessary pneumatic equipment and arrange for others to break up rock into manageable pieces.

PS DB 3.5**BACKFILL MATERIALS**

a) Substitute "from trenches" in DB 3.5(a) with "from trenches and street excavations".

Add the following to DB 3.5(b):

c) Road crossings, access to services, farms and camps and any section that fall within the road reserve shall be classified as areas subject to loads from road traffic and must be compacted accordingly to the top of the trench (natural ground level).

PS DB 3.7**SELECTION OF MATERIAL FOR REPAIR WORK**

If the excavation of a pipeline damages an existing road surface, the Contractor must stockpile material from the top 200mm of such a road surface in order to reuse it as sub base for the repairing of the road crossing.

If necessary, gravel material that is suitable for the reparation of road surfaces must be imported.

The Contractor must make provision in his tariffs for compaction in road reserves for the selection of excavated material as specified above.

PS DB 4 PLANT**PS DB 4.1****EXCAVATION EQUIPMENT**

Add the following to DB 4.1:

An adequate number of suitable tools, including hand stampers, wheelbarrows and hosepipes shall be provided by the Contractor. The Contractor will supply mechanical compaction equipment and when required pneumatic and rock breaking equipment.

All excavations exceeding the specified widths shall be backfilled with approved selected material. No payment shall be made for this and all relevant costs shall be deemed to be included in the tendered rates.

PSDB 5 CONSTRUCTION**PSDB 5.1****PRECAUTIONS****PS DB 5.1.1.1 Water in Trenches**

Water in pipe trenches may cause movement of the pipes as a result of flotation and backfilling must therefore be executed as quickly as possible. If movement of the pipes does occur the contractor must, unless otherwise instructed by the Engineer, remove the pipes from the trench and reinstall it at his own expense.

PS DB 5.4**EXCAVATION**

Add the following to DB 5.4:

"Excavation and backfilling of pipe trenches on sidewalks in the residential area shall be done in such a manner as to ensure the least possible disruption to the public and access to the properties. No additional payment shall be made for this and all relevant costs shall be deemed to be included in the tendered rates.

PS DB 5.5 TRENCH BOTTOM

Substitute "90 %" in the second paragraph of DB 5.5 with "93 %".

PS DB 5.5.1 Over Excavation of Trenches

Where pipe trenches are excavated deeper than specified or shown on the drawings, these excavations must be backfilled with suitable approved selected material in layers of not more than 150mm uncompacted thickness and must be compacted to the thickness of the adjoining in-situ material or as prescribed by the Engineer.

PS DB 5.6 BACKFILLING**PS DB 5.6.1 General**

Backfilling in road reserves must be compacted in 100mm layers up to natural ground level.

Where prescribed by the Engineer all surplus material must be neatly piled over the real trench width to a height not more than 150mm higher than the adjoining level.

PS DB 5.6.3 Disposal of Soft Excavation Material

Add the following to DB 5.6.3:

All surplus and unsuitable material as described in DB 5.6.3 shall be disposed of at the spoil site, (as described in PS D 5.2.2.3) and levelled.

PS DB 5.7 COMPACTION**PS DB 5.7.2 Areas Subject To Traffic Loads**

Add the following to DB 5.7.2:

All pipe trenches within road crossings, accesses to services, farms and camps that fall within the road reserve, will be regarded as areas subject to traffic loads. Backfilling of trenches that are subject to traffic loads will be executed in layers of 100mm as follows:

Item	% mod AASHTO	Final Layer Thickness
Approved Backfill	93%	200mm
Main Backfill up to road layers	96%	200mm
Sub-base	97%	200mm
Base	98%	175mm

PS DB 5.9 REINSTATEMENT OF SURFACE**PS DB 5.9.2 Private Property and Commonage**

Add the following to DB 5.9.2:

Gardens and lawns shall be repaired to the original standard where they were crossed. Grass and plants shall be taken out of the ground, temporarily stocked, watered during construction, and replanted after backfilling.

PSDB 8 MEASUREMENT AND PAYMENT

PSDB 8.2 COMPUTATION OF QUANTITIES

PS DB 8.2.4 Shoring

Add the following to DB 8.2.4:

Shoring will only be measured and paid for, if the Engineer gives written approval before it is installed.

PSDB 8.3.2 Excavation

(a) Excavation in all material for trenches, backfill, compact and dispose of surplus material..... Unit (m)

Item will be provided for various pipe diameters in steps not greater than those specified in 5.2 and various depths in increments of 1.0 m measured to the bottom of the bedding layer (see Drawing DB 2, DB 3, and DB 4). Where measured volumetrically in terms of 8.1.2 (a), the volume of excavation will be computed in accordance with 8.2.2 and 8.2.3

The rate shall cover the cost of the same operation in heading where the Contractor elects to use such a method of excavation. The volume or length will be measured for payment on the assumption that normal trench excavation has been carried out. The volume or length in the undisturbed prism of material between the top of the tunnel and ground level will be classified as soft excavation in terms of 3.1. No additional payment will be made for such headings and no deductions will be made for reduced excavation quantities.

(b) Extra-over item (a) above for:

1. Intermediate excavation Unit: m³
2. Hard rock excavation..... Unit: m³
3. Hand excavation and backfill where ordered by the engineer. Unit: m³
4. Soil Crete backfilling where directed by the engineer. Unit: m³

Separate items will not be provided for depth increment, volume will be computed from the trench width determined in accordance with 8.2.3 and the depth from the top of the intermediate or hard rock excavation, as the case may be, either to the bottom of the same material or to the bottom of the trench as specified in (a) above, whichever is the lesser (see Drawing DB 5)

The rates shall cover the additional cost of the excavation and hauling of the more difficult material of unsuitable material.

c) Excavate and dispose of unsuitable material from trench bottom (provisional)... Unit: m³

The volume will be computed from the trench width determined in accordance with 8.2.3 and m³ the additional depth ordered.

The rate shall cover the cost of the excavation of the additional depth in any material, the disposal of the unsuitable material as specified for soft: excavation in 5.6.3 within free haul distance and the backfilling of the additional depth with suitable material from the side of the trench.

PSLF 8.17 GENERIC LABOUR-INTENSIVE SPECIFICATION

The Generic Labour-intensive specification below is the same as SANS 1921-5,
Construction and management requirement for works contracts- Part 5:

PSDB 8.3.3 EXCAVATION ANCILLARIES

PSDB 8.3.3.1 Make up deficiency in backfill material

- a) from other necessary excavations on site Unit: m³
- b) by importation from-designated borrow pits Unit: m³
- c) by importation from commercial or off-site sources selected by the Contractor Unit: m³

Items (b) and (c) above will not be measured for payment unless importation has been ordered in writing. The volume will be computed from the trench width determined in accordance with 8.2.3 and the depth from the top of the backfill to the top of the bedding as shown on Drawing DB-1 or the actual depth of backfill used to make up the deficiency or the depth of additional excavation ordered in terms of B.3.2(c), as applicable.

The rate for material from other necessary excavations on site shall cover the cost of selection of suitable material, the moving of the material to points alongside the trench spaced to suit the Contractor's method of working, and the disposal of the material that is replaced, all within free haul distance.

The rate for material from designated borrow pits shall cover the cost of royalties, if applicable, excavation and selection of suitable material, the moving of the material to points alongside the trench spaced to suit the Contractor's methods of working, and the disposal of the material that becomes surplus as a result of the importation, all within free haul distance.

The rate for material from commercial or off-site sources selected by the Contractor shall cover the cost of the acquisition of the material (including royalties, if applicable), the moving of the material to points alongside the trench spaced to suit the Contractor's methods of working, and the disposal of the material that becomes surplus as a result of the importation, all within free haul distance (see Sub clause 5.2.5.1 of SANS 1200 D or Sub clause 5.2.6.1 of SANS 1200 DA, as applicable).

PSDB 8.3.3.2 Opening up and closing down of designated borrow pit Unit: Sum

This item will only be scheduled when a new borrow pit has to be established or when access to an existing borrow pit has to be established.

With the exception of the cost of the removal and spreading back of the topsoil (if scheduled), the sum shall cover the cost of opening up and of restoring the Site as specified in Subclause 5.2.2.2 of SANS 1200 D or Subclause 5.2.2(f) of SANS 1200 DA, as applicable.

PSDB 8.3.5 Existing Services

Existing Services-that Intersect or Adjoin a Pipe Trench (see Sub-clauses 5.1.2 and 8.3.8 of SANS 1200 D or Sub-clauses 5.1.3 and 8.3.5 of SANS 1200 DA, as applicable.)
(See Subclauses 5.1.2 as applicable.)

- (a) Services that intersect a trench (angles between centre-lines in plan of 45-90°)..unit (No)

Except where water pipes are to be recovered, existing water pipes, sewers, stormwater pipes, concrete-lined channels and drains, box culverts, electric cables, ducts, kerbs, channels, erf connections and various sizes of pipes and services that intersect a trench of specified width and require various degrees of care, whether or not their presence is known before they are uncovered, will be measured separately. The unit refers to one service, but services that are so

grouped that they can be contained within a horizontal dimension of 200 mm measured at right angles to the axis of the services will be measured as one unit.

(b) Services that adjoin a trench (parallel to or at an angle between centre-lines in plan of less than 45°)..... Unit. (No)

In a case where a trench of specified width

1 runs parallel to or at an angle (in plan) of less than 45° to an existing service, and is such that the nearer side of the bottom of the trench lies at least partly between a vertical plane and a plane that lies at an angle of 45° below the horizontal, both planes passing through the axis of the service, the length of service within the minimum base width of the trench, determined in accordance with 5.2, will be measured for payment under this item and the remaining length, the side of the trench which, in the opinion of the Engineer, is rendered liable to collapse because of the existence of such service, will be measured for shoring (see 8.3.4(a)). The rate for an item scheduled in terms of (a) and (b) above shall cover the additional cost of

- i) care in excavation necessitated by the presence of such service in or across the trench;
- ii) protecting and maintaining such service in operation by means of temporary supports or shoring, as necessary;
- iii) delays and disruption of the progress of the work due to the existence of the service1 and
- iv) repairs necessitated by damage caused by the Contractor.

PS DB 8.3.6 Finishing

PS DB 8.3.6.1 Reinstate road surfaces complete with all courses

Unit: m²

Replace DB 8.3.6.1 with the following:

a) Gravel

Unit: m²

The area will be calculated from the length of finished road or paved surfaces as applicable and with the trench width taken as 0,8m. Payment for finishing will be additional to that for excavation covered by 8.3.2.

The rate shall cover the cost, selective excavation (including the equipment that is required to break up, remove and, if necessary, stockpile the original surface material), and subsequently of reinstating and compaction and shall include the cost of delays and the cost of any risk of having to repair damage as specified in DB 5.10. Compaction to be according to PS DB 5.7.2

PROJECT SPECIFICATIONS

PSGA 4 PLANT

PSGA 4.4 Formwork

PSGA 4.3.3 Ties

Add the following to G 4.4.3:

No ties will be allowed in vertical walls and permanent metal ties shall have a minimum concrete cover of 40 mm. Tie holes shall be filled with an approved non-shrink epoxy grout.

PSGA 5 CONSTRUCTION

PSGA 5.1 REINFORCEMENT

PSGA 5.1.3 Cover

Substitute G 5.1.3 with the following:

The cover of concrete over reinforcement, unless otherwise indicated on the drawings, shall be not less than 40 mm.

PSGA 5.2 FORMWORK

PSGA 5.2.1 Classification of Finishes

Add the following to G 5.2.1:

The following surface conditions are required in the various portions of the finished concrete:

(a) **Rough**

Concealed surfaces and surfaces lower than 100 mm below finished ground level.

(b) **Smooth**

All surface finishes not classified as "rough" in paragraph (a) shall be classified as "smooth". All exposed edges unless otherwise indicated on the drawings, shall be chamfered 20 mm x 20 mm by means of triangular fillets fixed to the formwork

PSGA 5.4 CONCRETE

PSGA 5.4.1 Quality

PSGA 5.4.1.2 Consistency

Add the following to sub clause G 5.5.1.2(a):

The slump of concrete used in water retaining structures may not be less than 30mm and not more than 60mm.

PSGA 5.4.1.5 Strength concrete

Add the following to G 5.5.1.7:

The grade of strength concrete and the maximum nominal size of coarse aggregate for each portion of the works, unless otherwise indicated on the drawings, shall be as follows:

(a) Blinding layers and encasing of pipes	20 MPa/50 mm
(b) Benching	20 MPa/19 mm
(c) Screeds	20 MPa/13.5 mm
(d) Reinforced concrete	30 MPa/19 mm

PSGA 5.4.1.7 Durability

Concrete shall be so proportioned to ensure that the water/cement ratio does not exceed 0,5 and, to ensure workability, water-reducing admixtures of approved manufacture shall be used in preference to increasing the cement content.

PSGA 5.4.8 Concrete Surfaces

Add the following to GA 5.4.8.1:

Concrete surfaces under screeds, granolithic finishes or benching shall be brought up to a plane, uniform surface with a suitable screed board.

PSGA 5.4.11 Construction Joints

The use of construction joints must be minimised and may only be placed as shown on the drawings or at positions as approved by the Engineer.

At all construction joints in walls a PVC water stop without a centre bulb must be placed as shown on the drawings.

Alternative materials with similar properties may be proposed but may only be installed after approval of the Engineer.

PSGA 5.5.10.4 Wood-floated finish

Where wood floating is specified or scheduled, the surface shall first be given a finish as specified in G 5.5.10.1 and after the concrete has hardened sufficiently; it shall be floated to a uniform surface free from trowel marks. The screed surface shall be wood-floated, either by hand or machine, only sufficiently to produce a uniform surface free from screed marks.

PSGA 5.5.10.5 Steel-floated finish

Where steel floating is specified or scheduled, the surface shall be treated as specified in PS G 5.5.10.4 except that, when the moisture film has disappeared and the concrete has hardened sufficiently to prevent laitance from being worked to the surface, the screed surface shall be steel-trowelled under firm pressure to produce a dense, smooth, uniform surface free from trowel marks.

PSGA 8 Measurements and Payment

PSGA 8.1.1 Formwork

Formwork, other than formwork covered by 8.1.1.2 and 8.1.4, will be measured as the net area of the face of the concrete to be supported during the deposition of concrete. No deduction will be made for fillets and splays of size up to 50 mm x 50 mm or for openings of diameter up to 0,7 m or of area up to 0.5 m².

Formwork in continuous lengths of narrow widths and of fillets or splays over 20 mm x 20 mm will be measured by length, the width or range of widths being stated in the schedule. Boxing-out, the forming of holes, and other such operations will be measured by number, basic dimensions, perimeters, or drawing references, as stated in the schedule.

The unit rate shall cover the cost of all parts of formwork in contact with the concrete, and the necessary bearers, struts, and other supports, plus the labour and plant necessary to erect and strike such formwork.

PSGA 8.1.2 Reinforcement

Steel for normal reinforced concrete will be measured net by mass of all bars, including supporting steel detailed on the reinforcing schedules. The mass will be computed from the nominal bar size and nominal mass per unit length. No allowance will be made for cutting, waste, spacer devices (materials other than steel bars), or binding wire.

Steel reinforcement for precast concrete units will not be measured unless so scheduled (see 8.6).

Welded mesh will be measured by area as shown on the drawings. No allowance being made for cutting, waste, laps, or deductions for end cover. The areas measured will be those of the concrete floor or slab being reinforced by means of mesh. In the case of continuous unit partly reinforced by mesh, the area will be computed from the outside dimensions of the area covered by mesh regardless of whether or not additional reinforcing steel is present in the same area.

Steel off cuts resulting from the cutting and bending of reinforcement in accordance with the bending schedules shall be deemed to be the property of the Contractor.

PSGA 8.1.3 Concrete

a) Concrete will be measured net to the dimensions shown on the drawings or to the dimensions cast, whichever are the smaller. Structural elements that are undersized will be measured for payment only if they are accepted by the Engineer

b) No allowance will be made for concrete required to make up over break in soft excavation, but payment will be made for additional concrete or formwork, or both, ordered in writing by the Engineer to replace unsuitable material or over break in hard rock or in intermediate excavation.

The unit rates shall cover the cost of the provision of concrete (made with ordinary Portland cement unless otherwise scheduled), mixing, testing, placing, compacting, the forming of stop-ends and unforeseen construction joints, striking off for levelling as applicable, and curing and repairing where necessary, together with the cost of all parts of formwork in contact with the concrete and the necessary bearers, struts, and other supports, plus the layout and plant necessary to erect and strike such formwork.

PROJECT SPECIFICATION

PORTION 2: VARIATIONS AND ADDITIONS TO STANDARDISED SPECIFICATIONS

SANS 1200 LB: BEDDING (PIPES)

PS LB 1 SCOPE

PS LB 1.1 SCOPE

Add the following to LB 1.1:

This specification also covers the bedding required for sleeve pipes.

PS LB 3 MATERIALS

PS LB 3.1 SELECTED GRANULAR MATERIAL

Substitute LB 3.1 with the following:

Selected granular material shall be an aggregate, sand or granular material, all of a non-cohesive nature and free from any organic material, of which the grading analysis shows 100 % passing a 13, 2 mm sieve and not more than 5 % passing a 0,075 mm sieve.

Only if approved by the Engineer may sand from the trench excavations be used as selected material.

PS LB 3.2 SELECTED FILL MATERIAL

Substitute LB 3.2 with the following:

The requirements of PS LB 3.1 shall apply *mutatis mutandis*.

PS LB 3.3 BEDDING

Add the following to LB 3.3:

All pipes shall be classified as flexible pipes and shall have a bedding of selected granular material and selected fill material.

PS LB 3.4 SELECTION

PS LB 3.4.1 Suitable Material from Trench Excavation Available

Replace the first sentence of LB 3.4.1 with the following:

Notwithstanding the requirements DB 3.7 and LB 3.4.1 relating selected excavation methods, the Contractor must follow selected excavation methods and provide or use plant that will prevent material that is suitable and necessary for bedding being contaminated.

PS LB 5 CONSTRUCTION

PS LB 5.1 GENERAL

PS LB 5.1.4 Compacting

Substitute "90 % of Mod. AASHTO" in LB 5.1.4 with "93 % of Mod. AASHTO.

If sand is used the compaction grade must be 100% Mod. AASHTO

PS LB 8 MEASUREMENT AND PAYMENT

PS LB 8.1 PRINCIPLES

PSLB 8.1.1 Provision of Bedding from Trench Excavation

- a) Selected granular materialUnit: m³
- b) Selected fill material Unit: m

The rates shall cover the cost of acquiring, from within 1 km, bedding that complies with the relevant requirements of the specification, of delivering it to points alongside the trench spaced to suit the Contractor's methods of working, and of disposing of displaced material within a free haul distance of 1 km.

In terms of the standardized specifications covering pipelines, the rate for the supply and laying of pipelines covers the cost of handling bedding material from alongside the trench and placing it under and around the pipeline.

PSLB 8.1.2 Supply only of Bedding by Importation

From other necessary excavations

- a) Selected granular materialUnit: m³
- b) Selected fill material Unit: m³

PSLB 8.1.4 From commercial sources

- a) Selected granular material Unit: m³
- b) Selected fill material Unit: m³

The rate shall cover the cost of acquiring, regardless of distance, the required bedding from commercial sources (see Sub clause 8.3.4 of SANS 1200 D or Sub clause 8.3.4 of SANS 1200 DA, as relevant), of delivering it to points alongside the trench spaced to suit the Contractor's methods of working, and of delivering it to points alongside the trench spaced to suit the Contractor's methods of working, and of disposing of material displaced by such importation, within a free haul distance of 0,5 km.

PSLB 8.1.6 Encasing of Pipes in Concrete Unit: m³

Separate items will be scheduled for each size of pipe and for each grade of concrete specified.

The volume will be computed from the dimensions of the concrete as given on the drawing.

The rate shall cover the cost of dealing with any excavation (in all materials including disposal of surplus) that is additional to that measured under the item for pipe trench excavation, the

cost of encasing the pipe in concrete including the cost of formwork (if any), etc., and the cost of formwork to form flexible joints at 4 m centres.

The rate shall cover encasement of pipe through stream crossings, Rate shall include formwork, mixing and placing of concrete (5m³) and Gabions (10m³).

PS LB 8.2.5 Overhaul of material for Bedding cradle and selected fill blanket

Unit: m³.km

Substitute LB 8.2.5 with the following:

- a) Limited overhaul (0,5 km to 1,0 km) Unit: m³
- b) Long overhaul Unit: m³.km

Except that the volume is calculated according to LB 8.1.3, the requirements of D 8.3.6 or DA 8.3.3, as applicable, shall apply for overhaul.

PROJECT SPECIFICATION

PORTION 2: VARIATIONS AND ADDITIONS TO STANDARDISED SPECIFICATIONS

SANS 1200 L: MEDIUM PRESSURE PIPELINES

PSL 1 SCOPE

This specification covers the supply and installation of pipelines of diameter up to 1 000 mm, Complete with ancillary works, for transporting water and sewage under working pressures of up to 2.5 MPa.

PSL 3 MATERIAL

PSL 3.1 GENERAL

Replace the first sentence of L 3.1 with the following:

Dura flown PVC and uPVC pipes, where relevant, will be used in the water pipelines.

Pipes and fittings shall be of the types specified in the schedule or in the project specification and, unless otherwise required in terms of the project specification, they and their couplings shall be capable of withstanding the applicable test pressure specified in 7.3.1. All pipes and fittings shall be supplied complete with couplings and jointing material.

Satisfactory temporary end covers shall be provided for the protection of threads, flanges, and prepared ends of plain-ended pipes and fittings, and to prevent damage to internal lining during transportation and during handling on Site.

Pipeline materials shall be so transported, stored, and handled that pipes are not overstressed at any time and fittings are not damaged in any way. PVC pipes to be stored under shade for the period between delivery to site and pipe laying and backfilling. All thin-walled, flexible, and soft-coated pipes shall be handled with particular care and shall be so stored that they are not subject to concentrated pressure from stones or other objects. Pipes damaged or cracked in any way shall be removed from the Site.

PSL 3.9 CORROSION PROTECTION

PSL 3.9.2 Protection of Steel Pipes and Accessories

All the pipe items of steel with diameters from 100mm and more must, unless otherwise specified be provided of three coats of epoxy paint (KSIR 88 or similar) to provide a final film of 300 micron dried thickness. Application must be according to the suppliers' prescription and must be on the inside and outside. Steel pipe items with diameters smaller than 100mm must be protected using galvanising or epoxy paint.

PSL 3.10 VALVES

All valves must be painted according to an approved method with epoxy paint (KSIR 88 or similar), to provide a final film of 300 micron dried thickness, after manufacturing and testing. Complete technical information of all valves must be submitted to the Engineer for approval before purchase.

PSL 3.10.1 Gate Valves

All gate valves shall be of the AVK type, shall comply with the requirements of SANS 664 and shall be suitable for a working pressure of 1,6 MPa (Class 16), or as indicated on the detail drawings. All gate valves must be supplied with a square spindle nut, suitable to be

used with a valve key, or with a hand wheel as indicated on the detailed drawings. One valve key per nut size must be provided and will be included in the rate for valves.

All gate valves shall be flanged and drilled according to SANS 1123 or B.S. 4504 Table 16, unless shown differently on the drawings, and shall be right hand closing. The direction for opening and closing shall be permanently displayed on the valves. Valves shall have non-rising spindles.

Compression shut-off valves with rubber protected gate and smooth finish without recess inside, may be used.

The spindle seal shall consist of at least two O-rings located in a corrosion resistant housing. A wiper ring to prevent ingress of dirt shall be provided. The spindle nut may be loose or fixed in the gate.

The valves shall be provided with a straight, unobstructed body passage without any pocket and the gate shall be completely clear of the waterway in the fully open position. The sealing and gate guide areas shall be designed to eliminate deposits in the valve body. The gate guides shall be of substantial design to support the gate until the point of closure.

All components shall be interchangeable between valves of one size.

The rated working pressure shall be as detailed on the drawings. The valves are required to seal drop tight from zero to a test pressure of 1,1 times the rated working pressure under test and field conditions.

The valve shall be capable of being opened and closed under an unbalanced pressure equal to the rated working pressure.

Pipes shall not be tested against a closed valve. Thrust blocks for test sections shall be approved by the Engineer prior to testing of pipes.

PSL 3.10.2 Air Valves

All air valves to be Double orifice type. Rate shall include all accessories required as per tender drawing.

PSL 5 CONSTRUCTION

PSL 5.1 LAYING

PSL 5.1.1 General

Where connecting to the existing pipeline the position of the existing pipeline must be established by excavating test holes (hand excavation) before any trench excavation to the planned connection point is undertaken. The Contractor will not be compensated for excavation and any other work that is executed and proves to be unnecessary because this specification was not followed.

PSL 5.4 CONCRETE ENCASING

Replace the first sentence of L 5.4 with the following:

Concrete encasing with concrete with strength of 20 MPa/19mm, must be provided at positions indicated by the Engineer. Provision must be made to keep the pipe in position during the placement of the concrete encasing. The length of concrete encasing will be determined by means of site instructions from the Engineer.

PSL 5.4.1 Soil Crete Encasing

Add the following:

A mixture of Portland cement and gravel of base quality that is mixed in a ratio of 1:10 must be provided at positions indicated by the Engineer. Provision must be made to keep the pipe in position during the placement of the soilcrete encasing. The length of soilcrete encasing will be determined by means of a site instruction from the Engineer.

PSL 5.5 ANCHOR BLOCKS

Delete “15 Mpa/37,5mm” in the second sentence and replace with “20Mpa/19mm”

PSL 5.6 VALVE CHAMBERS

PSL 5.6.1 General

Substitute the first sentence of L 5.6.1 with the following:

The drawings of valve chambers, which are bound into the document, shall supersede the corresponding drawings in the standard specification.

Valve chambers, to the relevant specified sizes and specifications, shall be installed at all the new positions as indicated on the detailed drawings.

PSL 5.10 CLEANING OF PIPE

Sub clauses (a), (b) and (c) must be adhered to.

PSL 5.11 PIPE MARKERS

Pipe markers shall be installed at 50m intervals on the pipeline route, at all the newly installed isolation and scour valves as indicated on the detailed drawings as well as at all positions where the pipeline route deviates from the horizontal.

PSL 7 TESTING

PSL 7.3 STANDARD HYDRAULIC PIPE TEST

PSL 7.3.1 Test pressure and time of test

Add the following to L 7.3.1.1:

Pipes shall not be tested against isolating valves. Special blank flanges or end caps, fully anchored, shall be provided for testing.

PSL 8 MEASUREMENT AND PAYMENT

PSL 8.2 SCHEDULED ITEMS

PSL 8.2.1 Supply, Lay and Bed Pipes complete with couplingsUnit: m

PSL 8.2.1.1 uPVC Class 9, 12 and 16 Pipes

The pipes should be the type with a spigot at one end and a socket with lying rubber at the other. Contractor has an option to supply mPVC piping of same class and diameter if he so wishes, on condition the rate of cost used is that of uPVC. All pipes to have the class and diameter clearly marked, in addition to Manufacturer's details.

PSL 8.2.1.2 Steel Pipes

The pipes should be threaded at both ends and supplied fitted with one threaded socket. The pipes will thus be jointed using threaded sockets except on advice of Engineer or where drawings details indicate otherwise.

PSL 8.2.2 Extra-over 8.2.1 for the Supplying, Laying, and Bedding of Specials Complete with CouplingsUnit: No

These shall be measured and paid for per installation, complete with the inclusion of the cutting of pipes, couplings, extra excavation and all extra material and labour that is required, including tees, fittings complete as shown on the drawings.

PSL 8.2.2.1 Extra-over 8.2.1.1 for the Supplying, Laying, and Bedding of Specials Complete with Couplings for Steel pipes and adaptors to PVC

Bends, Tees and Reducers shall be steel, be flanged and drilled to Table 16 at all ends. End caps to be flanged at the open end. Bends to be long radius. Steel - uPVC Adaptors to be flanged at end linking to the steel pipe and spigot ended at end linking the PVC pipe. The spigot end to match the diameter of PVC piping. Separate flanges to be drilled to Table 16 with threading to match the steel pipe threading.

PSL 8.2.2.2 Extra-over 8.2.1.2 for the Supplying, Laying, and Bedding of Specials Complete with Couplings for uPVC pipes

All bends, reducers, tees, end caps etc for uPVC sections to be uPVC, unless indicated on the drawings. All bends to be long radius with one end socketed and the other spigot end. The rest of the fittings/ specials to be socketed at all ends, unless the drawings or Engineer suggests otherwise.

PSL 8.2.3 Extra-over 8.2.1 for the Supply, Fixing and Bedding of Valves

Unit: No

Add the following to L 8.2.3:

Valves are measured and paid for per installation, complete with the inclusion of the cutting of pipes, couplings, extra excavation and all extra material and labour that is required, including tees, fittings complete as shown on the drawings.

PSL 8.2.4 Cut Into and Connect To Existing Mains

Unit: No

The number of each type and diameter of pipe cut into shall measure the cutting into existing mains.

The Tendered rate shall include full compensation for all arrangements with the relevant authorities, isolating the main, cutting into the main to accommodate the connecting fitting, dewatering, excavating, removing of excess material, taking steps to prevent the ingress of soil, stones and other material into the main as well as all material and labour to connect the pipe.

PS L 3.10 VALVES

PS L 3.10.1 Gate Valves

(a) 200mm isolation valve..... unit (No.)

All gate valves shall comply with the requirements of SANS 664 – Figure 2 and shall be suitable for a working pressure of 1.0 MPa. All gate valves shall be supplied with hand wheels, unless shown otherwise on the drawings.

Gate valves shall have flanged ends unless shown otherwise on the drawings and shall open clockwise. The direction for opening and closing shall be permanently displayed on the valves. Valves shall have non-rising spindles.

Spindles, spindle nuts, gate rings and body rings shall all be of bronze.

All flanged gate valves shall be drilled according to SANS 1123 Table 1600/3.

PSL8.2.10 Temporary Valves,

Payment for the supply or loan of temporary valves, end caps, blank flanges, or other isolating devices ordered by the Engineer in terms of 7.3.1.1 will be made at daywork rates or at a price to be agreed by the Engineer, unless the method of payment for the work has been dealt with in the project specification and a suitable item included in the schedule.

PSL 8.2.11 Anchor/Thrust Blocks

Unit: m³

Substitute L 8.2.11 with the following:

Anchor and thrust blocks shall be measured per cubic metre concrete and the Tendered rate shall include for all formwork and reinforcement (where specified) for the required dimensions.

“The concrete will be measured net by volume to the specified width and depth in excess of the external volume of the pipe (i.e. the volume of the pipe will be deducted).

The rate shall cover the cost of formwork and concrete.”

PSL 8.2.13 VALVE CHAMBERS

Valve and hydrant chambers, manholes, etc., will be measured as complete units.

The rate shall cover additional excavation (see Subclauses 8.2.2 and 8.2.3 of SANS 1200 LIB), materials, plant, and labour necessary for the complete construction including the installation of the surface boxes or covers.

Valve chambers will be measured and paid for by number and the tariff must include all excavation, installation, finishing and numbering of the chamber, all materials as well as labour as described in PS L 5.12.

PSL 8.2.17 Soil Crete Casing**Unit: m³**

The soilcrete (1:10 ratio) is measured by volume according to the specified width and depth that exceeds the outside volume of the pipe (the volume of the pipe detracted).

The tariff includes the cost of shuttering and soilcrete mixture.

PSL 8.2.18 Pipe Markers**Unit: No**

Pipe markers will be measured and paid for by number and the tariff must include all excavation, installation, and paint and numbering of marker, concrete as well as labour as described in PS L 5.11.

**PROJECT SPECIFICATION
PORTION 2: VARIATIONS AND ADDITIONS TO
STANDARDISED SPECIFICATIONS**

SANS 1200 VC: WATER PUMPS PROJECT SPECIFICATIONS

PSVC WATER PUMPS

CONTENTS

- PSVC 1: SCOPE
- PSVC 2: GENERAL
- PSVC 3: MATERIALS AND WORKMANSHIP
- PSVC 4: INSTALLATION

PSVC 1: SCOPE

This specification covers the design, manufacture, supply, delivery and testing of water pumps such as used for pumping water from dams and reservoirs, and as in line booster pumps.

PSVC 2: GENERAL

Pumps shall be of the maker's standard and approved design, capable of performing the required duty at a preferred speed of 1500 RPM. Pumps shall be supplied complete with motor, drives, couplings and base plate or frame. Pipes, pipe fittings, valves etc are specified and scheduled elsewhere. All electrical switchgear, cabling etc shall be supplied as stated in the project specification. The design of the pump/motor set shall be of the non-overloading type to prevent failure of the motor should the delivery pipeline fail.

The duty required of the pump is described in terms of the system curves in this document and pumps supplied shall be capable of successfully performing under all conditions so indicated. As far as possible, standard component parts shall be used.

PSVC 3: MATERIALS AND WORKMANSHIP

The Contractor shall ensure that materials, seals, bearings and couplings are correctly chosen in compliance with the original design requirements. Where substitution to suit local (as opposed to overseas) conditions and availability of materials is required, the Engineer shall be advised in writing, together with the motivation for the substitution. The calculations and specifications for the original design and the proposed substitutions shall be made available to the Engineer.

PSVC 3.1: CASINGS:

Pump casings shall be of high-grade cast iron designed to be capable of pressures 40% greater than the shut off head of the pump.

PSVC 3.2: BEARINGS:

All bearings shall have a minimum design life given by a B10 rating of 30,000 hrs. Adequate attention to choose of bearings shall be made in respect of loading, thrust, mounting, thermal expansion and contraction, lubrication and the conditions under which the bearings will be operating.

PSVC 3.3: IMPELLERS:

Impellers shall be made of cast iron, cast steel zinc free bronze or stainless steel. For fractional kW pumps other materials may be considered but used only with the Engineer's approval. The impeller shall be securely fixed to the shaft with a key and keyway and blind nut.

PSVC 3.4: WEARING RINGS:

Where pumps are fitted with wearing rings to limit recirculation losses, they shall be machined to tolerances compatible with the solids content of the water to be pumped.

PSVC 3.5: SEALS:

Pumps shall be fitted with stuffing boxes rather than mechanical seals under most conditions for ease and simplicity of maintenance.

Seals shall be effective over the normal working range ie no flow static head to shut off head of pump. Leakage from glands shall be openly collected and suitably piped out of the pump station.

a). Stuffing Boxes:

Stuffing boxes shall be sized as to accommodate not less than four rings of packing plus the lantern ring and a portion of the gland. The lantern ring shall be served by both inlet and outlet connections. A renewable sleeve shall be fitted to the shaft where it passes through the stuffing box. A slinger shall be incorporated between the stuffing box and the bearings. The stuffing box shall be easily tightened, and removed for repacking.

b). Mechanical Seals:

Particular attention shall be paid to the selection of materials and design of the seal in relation to the conditions under which the pump is to operate.

PSVC 3.6: MOUNTINGS AND BASEPLATE:

The pump shall be suitably equipped with mounting points to facilitate location and fixing in position the pump to a baseplate or flange mounting. In mounting to the baseplate or frame, which shall also serve the prime mover and gearbox, facility shall be provided for setting up and alignment.

The baseplate shall be manufactured from steel and be of sufficient stiffness to ensure location and alignment within acceptable tolerances.

The baseplate shall be securely bolted to the floor or foundation block with at least M20 bolts, before final alignment and setting up of the pump/drive/motor.

PSVC 3.7: PIPE WORK AND FITTINGS:

PSVC 3.7.1: General:

The pipework associated with the pumps shall be supplied and installed by the Contractor to ensure the proper functioning of the installation.

Where specified, all pipework, reflux valves, puddle flanges, bends and specials shall conform to the following:

SANS 509 and 546:	Cast iron and cast steel fittings.
SANS 719 and 720:	Mild steel pipes and fittings.
SANS 286, 721 and 946:	Asbestos cement pipes and fittings.
SANS 121:	Galvanized iron pipes and fittings.
SANS 966:	Un-plasticized polyvinyl chloride pipes and fittings.
SANS 533:	High density Polyethylene pipes and fittings.
BS 3605:	Stainless Steel.
SANS 664:	Sluice Valves.

The pipework shall be designed by the Contractor to suit the characteristics of the pumps supplied, and in addition shall be sized so that the velocity in the suction pipework shall not exceed 1,5 m/sec whilst the velocity in the delivery pipework shall not exceed 2,5 m/sec.

PSVC 3.7.2: Pipes:

The class of pipe selected shall be such as to provide a working pressure equal to the greater of:

- a). Maximum shut off head of the pumps, or
- b). The pressure given in the project specifications which allows for working head and pressure surges, or

- c). For cast iron pipes Class B - BS 2035.
- d). For spun cast iron Class B - BS 1211.
- e). For steel, Grade A, SANS 719/71, manufactured to dimensions given in BS 534/1966, minimum test pressure of 1,5 x a) or b) above, whichever is the greater, subject to a minimum wall thickness of 6 mm.

PSVC 3.7.3: Pipe Joints:

Generally, flanged joints are required. Where required for movement or assembly and maintenance requirements Viking Johnson couplings shall be used.

Flanges shall be manufactured in accordance with SANS 1123 as amended, and the pressure requirements of the adjacent pipework. Each joint shall be completely watertight under test and working conditions.

PSVC 3.7.4: Valves:

Each pump shall be fitted with an isolating valve on both the suction and delivery pipes, and a non-return valve shall be installed adjacent to the pump on the delivery side.

PSVC 3.7.5: Gate Valves:

Gate valves shall be manufactured to the requirements of SANS 665. All valves shall close on clockwise rotation of the hand-wheel. The hand-wheel shall be clearly and permanently marked with "open" and "shut" with arrows indicating the direction of rotation. All valves shall be capable of being opened and closed by one man against the maximum differential pressure.

PSVC 3.7.6: Butterfly Valves:

Butterfly valves may be used only on "clear water" ie water containing no particles or stringy matter which would affect the operation of the valves.

All valves shall be capable of being opened and closed by one man against maximum differential pressure.

PSVC 3.7.7: Non-return valves:

Non-return valves shall be suitable for use in either horizontal or vertical mounting. They shall be so designed and manufactured so as to provide satisfactory operation under the conditions of service envisaged and under zero flow conditions. Access to moving parts shall be possible without the need to remove the body from the line.

PSVC 3.8: PRESSURE GAUGES:

Each pump shall be fitted with suitable pressure gauges on both the suction side and the delivery side of the pump. The gauges shall be permanently mounted in position and provided with an isolation valve.

Gauges shall be a diameter of not less than 100 mm and shall be calibrated to indicate at least 5%. An accuracy of within 1% or better is required.

PSVC 3.9: MOTOR-PUMP COUPLINGS AND TRANSMISSIONS:

Generally, the pump shall run at the same speed as the prime mover and be directly coupled by means of a flexible coupling. Where such a layout is not desirable vee-belt drives are preferred, and only under exceptional circumstances will the use of a gearbox be approved.

The flexible coupling or vee-belt drive, where used, shall be designed to accept the full load torque at design speed, and also the start and stop loads, with due allowance being made for shock loading.

The couplings or drive shall also be designed to accommodate under all the above loading conditions, thermal expansion and contraction movements of the shafts, the effects of end float, vibrations and a practical amount of misalignment of the shafts.

PSVC 3.10: SHAFTS:

The installation shall comply with the requirements of the Machinery and Occupational Safety Act NO 6 of 1983 as amended.

All rotating or moving parts shall be enclosed by moveable guards.

PSVC 3.11: PAINTING AND CORROSION PROTECTION:

Where possible, materials of manufacture shall be selected for corrosion resistant properties.

Detailed requirements for painting and corrosion protection are specified in a separate section.

PSVC 3.12: NAMEPLATES:

A corrosion resistant nameplate shall be fixed to the pump with the following information punched or engraved thereon;

- Manufacturer's name.
- Serial number of the pump.
- Model number and type.
- Impeller type/diameter installed.
- Normal operating head and flow.

- Rotational speed.
- Bearing numbers.
- Lubricant type.

PSVC 3.13: MOTORS:

The electric motor shall be a direct coupled 220/380 V 50 Hz 3 phase motor which is capable of operating continuously under the load requirements specified without stalling or being overloaded.

The motor shall comply with the relevant section of BS 2613 or BS 170 where applicable. The motor shall be so sealed from the pump as to prevent the ingress of moisture and shall have a completely moisture proof terminal block into which the power supply cable is to be brought.



MORETELE LOCAL MUNICIPALITY

C6. OHS Specifications for construction projects

5.1 Specification

1. PREAMBLE

In terms of Construction Regulation 4(1)(a) of the Occupational Health and Safety Act, 1993 (Act 85 of 1993), the Moretele Local Municipality, as the Client, shall be responsible to prepare Health & Safety Specifications for any intended construction project and provide any Principal Contractor who is making a bid or appointed to perform construction work for the Client on its behalf with the same.

The Client's further duties are as described in The Act and the Regulations made there-under. The Principal Contractor shall be responsible for the Health & Safety Policy for the site in terms of Section 7 of the Act and in line with Construction Regulation 5 as well as the Health and Safety Plan for the project.

This 'Health and Safety Specifications' document is governed by the "Occupational Health and Safety Act, 1993 (Act No. 85 of 1993), hereinafter referred to as 'The Act'. Notwithstanding this, cognisance should be taken of the fact that no single Act or its set of Regulations can be read in isolation. Furthermore, although the definition of Health and Safety Specifications stipulates 'a documented specification of all health and safety requirements pertaining to associated works on a construction site, so as to ensure the health and safety of persons', it is required that the entire scope of the Labour legislation, including the Basic Conditions of Employment Act be considered as part of the legal compliance system. With reference to this specification document this requirement is limited to all health, safety and environmental issues pertaining to the site of the project as referred to here-in. Despite the foregoing it is reiterated that environmental management shall receive due attention.

Due to the wide scope and definition of construction work, every construction activity and site will be different, and circumstances and conditions may change even on a daily basis. Therefore, due caution is to be taken by the Principal Contractor when drafting the Health and Safety Plan based on these Health and Safety Specifications. Prior to drafting the Health and Safety Plan, and in consideration of the information contained here-in, the contractor shall set up a Risk Assessment Program to identify and determine the scope and details of any risk associated with any hazard at the construction site, in order to identify the steps needed to be taken to remove, reduce or control such hazard. *This Risk Assessment and the steps identified will be the basis or point of departure for the Health and Safety Plan.* The Health and Safety Plan shall include documented 'Methods of Statement' (see definitions under Construction Regulations) detailing the key activities to be performed in order to reduce as far as practicable, the hazards identified in the Risk Assessment.

2. SCOPE OF HEALTH AND SAFETY SPECIFICATION

The Health and Safety Specifications pertaining to this project; cover the subjects contained in the index and is intended to outline the normal as well as any special requirements of the Client pertaining to the health and safety matters (including the environment) applicable to the project in question. These Specifications should be read in conjunction with the Act, the Construction Regulations and all other Regulations and Safety Standards which were or will be promulgated under the Act or incorporated into the Act and be in force or

come into force during the effective duration of the project. The stipulations in this specification, as well as those contained in all other documentation pertaining to the project, including contract documentation and technical specifications shall not be interpreted, in any way whatsoever, to countermand or nullify any stipulation of the Act, Regulations and Safety Standards which are promulgated under, or incorporated into the Act.

3. PURPOSE

The Client is obligated to implement measures to ensure the health and safety of all people and properties affected under its custodianship or contractual commitments, and is further obligated to monitor that these measures are structured and applied according to the requirements of these Health and Safety Specifications.

The purpose of this specification document is to provide the relevant Principal Contractor with any information other than the standard conditions pertaining to construction sites which might affect the health and safety of persons at work and the health and safety of persons in connection with the use of plant and machinery; and to protect persons other than persons at work against hazards to health and safety arising out of or in connection with the activities of persons at work during the carrying out of construction work for the Moretele Local Municipality. The Principal Contractor is to be briefed on the significant health and safety aspects of the project and to be provided with information and requirements on *inter alia*:

- a) Safety considerations affecting the site of the project and its environment;
- b) Health and safety aspects of the associated structures and equipment;
- c) Submissions on health and safety matters required from the Principal Contractor and,
- d) The Principal Contractor's health & safety plan.

To serve to ensure that the Principal Contractor is fully aware of what is expected from him/her with regard to the Occupational Health and Safety Act, 1993 (Act No. 85 of 1993) and the Regulations made there-under including the applicable safety standards, and in particular in terms of Section 8 of the Act.

To inform the Principal Contractor that the Occupational Health and Safety Act, 1993 (Act 85 of 1993) in its entirety shall apply to the contract to which this specification document applies. The Construction Regulations shall apply to any person involved in construction work pertaining to this project, as will the Act.

4. DEFINITIONS

“Purpose of the Act” –

To provide for the health and safety of persons at work and the health and safety of persons in connection with the use of plant and machinery; the protection of persons other than persons at work against hazards to health and safety arising out of or in connection with the activities of persons at work; to establish an advisory council for occupational health and safety; and to provide for matters connected therewith.

“Agent” –

means any person who acts as a representative for a client;

“Client” –

means any person for whom construction work is performed;

“Construction Work” is defined as any work in connection with –

- (a) the erection, maintenance, alteration, renovation, repair, demolition or dismantling of or addition to a building or any similar structure;
- (b) the installation, erection, dismantling or maintenance of a fixed plant where such work includes the risk of a person falling;
- (c) the construction, maintenance, demolition or dismantling of any bridge, dam, canal, road, railway, runway, sewer or water reticulation system or any similar civil engineering structure; or
- (d) the moving of earth, clearing of land, the making of an excavation, piling, or any similar type of work;

“Contractor” –

means an employer, as defined in Section 1 of the Act, who performs construction work and includes Principal Contractors;

“Health and Safety File” –

means a file, or other record in permanent form, containing the information required a contemplated in the regulations;

“Health and Safety Plan” –

means a documented plan which addresses hazards identified and includes safe work procedures to mitigate, reduce or control the hazards identified;

“Health and Safety Specification” –

means a documented specification of all health and safety requirements pertaining to the associated works on a construction site, so as to ensure the health and safety of persons;

“Method Statement” –

means a document detailing the key activities to be performed in order to reduce as reasonably as practicable the hazards identified in any risk assessment;

“Principal Contractor” –

means an employer, as defined in section 1 of the Act who performs construction work and is appointed by the client to be in overall control and management of a part of or the whole of a construction site;

“Risk Assessment” –

means a program to determine any risk associated with any hazard at a construction site, in order to identify the steps needed to be taken to remove, reduce or control such hazard.

5. OCCUPATIONAL HEALTH & SAFETY MANAGEMENT

5.1 Structure and Organisation of OH&S Responsibilities

5.1.1. *Overall Supervision and Responsibility for OH&S*

- The Client and/or its Agent on its behalf to ensure that the Principal Contractor, appointed in terms of Construction Regulation 4(1)(c), implements and maintains the agreed and approved H&S Plan. Failure on the part of the Client or Agent to comply with this requirement will not relieve the Principal Contractor from any one or more of his/her duties under the Act and Regulations.
- The Chief Executive Officer of the Principal Contractor in terms of Section 16 (1) of the Act to ensure that the Employer (as defined in the Act) complies with the Act.
- All OH&S Act (85 /1993), Section 16 (2) appointee/s as detailed in his/her/their respective appointment forms to regularly, in writing, report to their principals on matters of health and safety per routine and ad hoc inspections and on any deviations as soon as observed, regardless of whether the observation was made during any routine or ad hoc inspection and to ensure that the reports are made available to the principal Contractor to become part of site records (Health & Safety File).
- The Construction Supervisor and Assistant Construction Supervisor/s appointed in terms of Construction Regulation 6 to regularly, in writing, report to their principals on matters of health and safety per routine and ad hoc inspections and on any deviations as soon as observed, regardless of whether the observation was made during any routine or ad hoc inspection and to ensure that the reports are made available to the principal Contractor to become part of site records (Health & Safety File).
- All Health and Safety Representatives (SHE-Rep)s shall act and report as per Section 18 of the Act.

5.1.2. *Legal Appointments*

Several appointments or designations of responsible and /or competent people in specific areas of construction work are required by the Act and Regulations. The following competent appointments, where applicable, in terms of the Construction Regulations are required to ensure compliance to the Act, Regulations and Safety Standards.

Required appointments as per the Construction Regulations: -

Item	Regulation	Appointment	Responsible Person
1.	4(1)(c)	Principal contractor for each phase or project	Client
2.	5.(3)(b)	Contractor	Principal Contractor
3.	5(11)	Contractor	Contractor
4.	6(1)	Construction supervisor	Contractor

Item	Regulation	Appointment	Responsible Person
5.	6(2)	Construction supervisor sub-ordinates	Contractor
6.	6(6)	Construction Safety Officer	Contractor
7.	7(1)	Person to carry out risk assessment	Contractor
8.	7(4)	Trainer/Instructor	Contractor
9.	8(1)(a)	Fall protection planner	Contractor
10.	10 (a)	Formwork & support work supervisor	Contractor
11.	10(e) + (f)	Formwork & support work examiner	Contractor
12.	11(1)	Excavation supervisor	Contractor
13.	11(3)(b)(ii)(b)	Professional engineer or technologist	Contractor
14.	11(3)(k)	Explosives expert	Contractor
15.	12(1)	Supervisor demolition work	Contractor
16.	12(2) + (3)	Demolition expert	Contractor
17.	12(11)	Explosives expert	Contractor
18.	14(2)	Scaffold supervisor	Contractor
19.	15(1)	Suspended platform supervisor	Contractor
20.	15(2)(c)	Compliance plan developer	Contractor
21.	15(8)(c)	Suspended platform expert	Contractor
22.	15(13)	Outrigger expert	Contractor
23.	17(8)(a)	Material hoist inspector	Contractor
24.	18(1)	Batch plant supervisor	Contractor
25.	18(7)	Batch plant operator	Contractor
26.	19(2)(b)	Power tool expert	Contractor
27.	19.2 (g) (i)	Power tool controller	Contractor
28.	20(f)	Tower crane operator	Contractor
29.	21(1)(d)(i)	Construction vehicle and mobile plant operator	Contractor
30.	21(1)(j)	Construction vehicle and mobile plant inspector	Contractor
31.	22(d)	Temporary electrical installations inspector	Contractor
32.	22 (e)	Temporary electrical installations controller	Contractor
33.	26 (a)	Stacking and storage supervisor	Contractor
34.	27 (h)	Fire equipment inspector	Contractor

This list may be used as a reference or tool to determine which components of the Act and Regulations would be applicable to a particular site. This list must not be assumed to be exclusive or comprehensive.

5.2 Communication & Liaison

5.2.1 OH&S Liaison between the Employer, the Principal Contractor, the other Contractors, the Designer and other concerned parties shall be through the project Committee as per the procedures determined by the project Committee.

- 5.2.2 In addition to the above, communication may be directly to the Client or his appointed Agent, verbally or in writing, as and when the need arises.
- 5.2.3 Consultation with the workforce on OH&S matters will be through their Supervisors and H&S Representatives ('SHE – Reps')
- 5.2.4 The Principal Contractor will be responsible for the dissemination of all relevant OH&S information to the other Contractors e.g. design changes agreed with the Client and/or its Agent on its behalf and the Designer, instructions by the Client and/or his/her agent, exchange of information between Contractors, the reporting of hazardous/dangerous conditions/situations etc.

6. RESPONSIBILITIES

6.1 Client

- 6.1.1 The Client or his appointed Agent on his behalf will appoint each Principal Contractor for this project in writing for assuming the role of Principal Contractor as intended by the Construction Regulations and determined by the Bills of Quantities.
- 6.1.2 The Client or his appointed Agent on his behalf shall discuss and negotiate with the Principal Contractor the contents of the health and safety plan of the both Principal Contractor and Contractor for approval.
- 6.1.3 The Client or his appointed Agent on his behalf, will take reasonable steps to ensure that the health and safety plan of both the Principal Contractor and Contractor is implemented and maintained. The steps taken will include periodic audits at intervals of at least once every month.
- 6.1.4 The Client or his appointed Agent on his behalf, will prevent the Principal Contractor and/or the Contractor from commencing or continuing with construction work should the Principal Contractor and/or the Contractor at any stage in the execution of the works be found to:
 - have failed to have complied with any of the administrative measures required by the Construction Regulations in preparation for the construction project or any physical preparations necessary in terms of the Act;
 - have failed to implement or maintain their health and safety plan;
 - have executed construction work which is not in accordance with their health and safety plan; or
 - act in any way which may pose a threat to the health and safety of any person(s) present on the site of the works or in its vicinity, irrespective of him/them being employed or legitimately on the site of the works or in its vicinity.

6.2 Principal Contractor

- 6.2.1 The Principal Contractor shall accept the appointment under the terms and Conditions of Contract. The Principal Contractor shall sign and agree to those terms and conditions and shall, before commencing work, notify the Department of Labour of the intended construction work in terms of

Regulation 3 of the Construction. The Principal Contractor shall submit the notification in writing prior to commencement of work and inform the Client or his Agent accordingly.

- 6.2.2 The Principal Contractor shall ensure that he is fully conversant with the requirements of this Specification and all relevant health and safety legislation. *This Specification is not intended to supersede the Act nor the Construction Regulations or any part of either.* Those sections of the Act and the Construction Regulations which apply to the scope of work to be performed by the Principal Contractor in terms of this contract will continue to be legally required of the Principal Contractor to comply with. The Principal Contractor will in no manner or means be absolved from the responsibility to comply with all applicable sections of the Act, the Construction Regulations or any Regulations proclaimed under the Act or which may perceiveable be applicable to this contract.
- 6.2.3 The Principal Contractor shall provide and demonstrate to the Client a suitable and sufficiently documented health and safety plan based on this Specification, the Act and the Construction Regulations, which shall be applied from the date of commencement of and for the duration of execution of the works. This plan shall, as appendices, include the health and safety plans of all Sub-contractors for which he has to take responsibility in terms of this contract.
- 6.2.4 The Principal Contractor shall provide proof of his registration and good standing with the Compensation Fund or with a licensed compensation insurer prior to commencement with the works.
- 6.2.5 The Potential Principal Contractor shall, in submitting his tender, demonstrate that he has made provision for the cost of compliance with the specified health and safety requirements, the Act and Construction Regulations.
- 6.2.6 The Principal Contractor shall consistently demonstrate his competence and the adequacy of his resources to perform the duties imposed on the Principal Contractor in terms of this Specification, the Act and the Construction Regulations.
- 6.2.7 The Principal Contractor shall ensure that a copy of his health and safety plan is available on site and is presented upon request to the Client, an Inspector, Employee or Sub-contractor.
- 6.2.8 The Principal Contractor shall ensure that a health and safety file, which shall include all documentation required in terms of the provisions of this Specification, the Act and the Construction Regulations, is opened and kept on site and made available to the Client or Inspector upon request. Upon completion of the works, the Principal Contractor shall hand over a consolidated health and safety file to the Client.
- 6.2.9 The Principal Contractor shall, throughout execution of the contract, ensure that all conditions imposed on his Sub-contractors in terms of the Act and the Construction Regulations are complied with as if they were the Principal Contractor.
- 6.2.10 The Principal Contractor shall from time to time evaluate the relevance of the Health and Safety Plan and revise the same as required, following which revised plan shall be submitted to the Client and/or his/her Agent for approval.

7. SCOPE OF WORK

These specifications are applicable to the specific scope of work pertaining to the project as detailed in the tender documents. **Refer to Project specification.**

8. HEALTH AND SAFETY FILE

The Principal Contractor must, in terms of Construction Regulation 5(7), keep a Health & Safety File on site at all times that must include all documentation required in terms of the Act and Regulations and must also include a list of all Contractors on site that are accountable to the Principal Contractor and the agreements between the parties and details of work being done.

The Health and Safety File will remain the property of the Client and/or its Agent on its behalf throughout the period of the project and shall be consolidated and handed over to the Client and/or its Agent on its behalf at the time of completion of the project.

The safety file shall contain the following documentations:

- Safety reports,
- Notification documents,
- Appointment letters,
- Records of incidents,
- Records of training,
- Records of safety meetings,
- Records of PPE provision,
- And any other document related to safety issues on site.

9. MONITORING AND REVIEWING OH&S PERFORMANCE

The Principal Contractor is required to maintain acceptable incident rate and report on this to the Client and/or its Agent on its behalf on a monthly basis. The frequency rates must reflect permanent disability, lost workdays, restricted workdays, medical treatment and first aid treatment.

10. HAZARD IDENTIFICATION AND RISK ASSESSMENT

The Principal Contractor is required to develop Risk Assessments, Standard Working Procedures (SWP) and Method Statements for each activity executed in the contract or project. The identification of hazards is over and above the hazards identification program and those hazards identified during the drafting of the Health and Safety Plan. Hazard identification should be conducted continuously over and above the baseline risk assessment.

11. ARRANGEMENTS FOR MONITORING AND REVIEW

11.1 Monthly Audit by Client

The Client and/or its Agent on its behalf will be conducting Periodic Audits at times agreed with the Principal Contractor Audit to comply with Construction Regulation 4(1)(d) to ensure that the principal Contractor has implemented, is adhering to and is maintaining the agreed and approved OH&S Plan.

11.2 Other audits and inspections

The Client and/or its Agent on its behalf reserves the right to conduct any other ad hoc audits and inspections as it and/or its Agent on its behalf deem necessary.

A representative of the Principal Contractor and the relevant Health and Safety Representative(s) (SHE-Reps) must accompany the Client and/or its Agent on its behalf on all Audits and Inspections and may conduct their own audit/inspection at the same time. Each party will, however, take responsibility for the results of his/her own audit/inspection results. The Client and/or its Agent on its behalf may require to be handed a copy of the minutes of the previous Health and Safety Committee meeting reflecting possible recommendations made by that committee to the Employer for reference purposes and any other health and safety related issues.

11.3 Reports

- 11.3.1 The Principal Contractor shall report all incidents where an employee is injured on duty to the extent that he/she dies, becomes unconscious, loses a limb or part of a limb, is injured or becomes ill to such a degree that he/she is likely either to die or to suffer a permanent physical defect or likely to be unable for a period of at least 14 days either to work or continue with the activity for which he/she was usually employed, or where a major incident occurred, the health or safety of any person was endangered, where a dangerous substance was spilled, the uncontrolled release of any substance under pressure took place, machinery or any part of machinery fractured or failed resulting in flying, falling or uncontrolled moving objects, machinery ran out of control, to the Provincial Director of the Department of Labour within seven days and at the same time to the Client and/or its Agent on its behalf.
- 11.3.2 The Principal Contractor is required to provide the Client and/or its Agent on its behalf with copies of all statutory reports required in terms of the Act and the Regulations.
- 11.3.3 The Principal Contractor is required to provide the Client and/or its Agent on its behalf with a monthly "SHE Risk Management Report".
- 11.3.4 The Principal Contractor is required to provide the Client and/or its Agent on its behalf with copies of all internal and external accident/incident investigation reports. As soon as the occurrence of any accident/incident of whatever nature comes to the notice of the Principal Contractor, it shall be reported immediately to any of the following:

11.4 Review

The Principal Contractor is to review the Hazard Identification, Risk Assessments and Standard Work Processes at each Production Planning and Progress Report meeting as the construction work develops and progresses and each time changes are made to the designs, plans and construction methods and processes. The Principal Contractor must provide the Client and/or its Agent on its behalf, and all other concerned parties with copies of any changes, alterations or amendments

11.5 Site Safety Rules

11.5.1 Site OH&S Rules

The Principal Contractor must develop a set of site-specific OH&S rules that will be applied to regulate the Health and Safety Plan and associated aspects of the construction. When required for a site by law, visitors and non-employees upon entering the site shall be issued with the proper Personal Protective Equipment (PPE) as and when necessary.

11.5.2 Security Arrangements

The Principal Contractor must establish site access rules and implement and maintain these throughout the construction period. Access control must include the rule that non-employees shall at all times be provided with fulltime supervision while on site. The Principal Contractor must develop a set of Security rules and procedures and maintain these throughout the construction period.

If not already tasked to the H&S Officer appointed in terms of Construction Regulation 6(6), the Principal Contractor must appoint a competent Emergency Controller who must develop contingency plans for any emergency that may arise on site as indicated by the risk assessments. These must include a monthly practice/testing program for the plans

11.6 Training

The Principal Contractor shall ensure that all employees under his or her control are informed, instructed and trained by a competent person regarding any hazard and the related work procedures before any work commences, and thereafter at such times as may be determined in the risk assessment.

The Principal Contractor shall ensure that all labourers are informed regarding any hazard as stipulated in the risk assessment before any work commences, and thereafter at such times as may be determined in the risk assessment.

The Principal Contractor shall ensure that as far as is reasonably practicable, ergonomic related hazards are analysed, evaluated and addressed in the risk assessment.

No Principal Contractor shall allow or permit any employee to enter any site, unless such person has undergone health and safety induction training pertaining to the hazards prevalent on the site at the time of entry.

The Principal Contractor shall ensure that all visitors to a construction site undergoes health and safety instruction pertaining to the hazards prevalent on the site and shall be provided with the necessary personal protective equipment: Provided that where visits are made only to the site office which is not in direct contact with the construction work activities, those health and safety instructions and the provision of personal protective equipment may not apply.

The contents and syllabi of all training required by the Act and Regulations including any other related or relevant training as required must be included in the Principal Contractor's Health and Safety Plan and Health and Safety File.

11.6.1 General Induction Training

The Principal contractor must ensure that the employees on site are conversant with the general health and safety requirements on site. All employees of the Principal and other Contractors must be in possession of proof of General Induction training.

11.6.2 Site Specific Induction Training

All employees of the Principal and other Contractors must be in possession of Site-Specific Occupational Health and Safety Induction or other qualifying training.

11.6.3 Other Training

All operators, drivers and users of construction vehicles, mobile plant and other equipment must be in possession of valid proof of training. All employees in jobs requiring training in terms of the Act and Regulations must be in possession of valid proof of training as follows:

- General Induction (Section 8 of the Act)
- Site/Job Specific Induction (also visitors) (Sections 8 & 9 of the Act)

- Site/Project Manager
- Construction Supervisor
- OH&S Representatives (Section 18 (3) of the Act)
- Training of the Appointees indicated in 12.6.1 & 12.6.2 above
- Operation of Cranes (Driven Machinery Regulations 18 (11))
- Operators & Drivers of Construction Vehicles & Mobile Plant (Construction Regulation 21)
- Basic Fire Prevention & Protection (Environmental Regulations 9 and Construction Regulation 27)
- As a minimum basic First Aid to be upgraded when necessary (General Safety Regulations 3)
- Storekeeping Methods & Safe Stacking (Construction Regulation 26)
- Emergency, Security and Fire Coordinator

11.7 Accident and Incident Investigation

The Principal Contractor is responsible to oversee the investigation of all accidents/incidents where employees and non-employees were injured to the extent that he/she/they had to receive first aid or be referred for medical treatment by a doctor, hospital or clinic, (General Administrative Regulation 9). The Principal Contractor is responsible for the investigation of all non-injury incidents as described in Section 24 (1) (b) & (c) of the Act and keeping a record of the results of such investigations including the steps taken to prevent similar incidents in future.

The Principal Contractor is responsible for the investigation of all road traffic accidents relating to the construction site and keeping a record of the results of such investigations including the steps taken to prevent similar accidents in future. Notwithstanding the requirements of Section 24 of the Act, ALL incidents shall be investigated and reported on in writing, irrespective of whether such incident gave rise to injury or damage.

11.8 H&S Representatives and H&S Committees

11.8.1 Designation of H&S Representatives

Where the Principal Contractor employs more than 20 persons (including the employees of other Contractors (sub-contractors) he has to appoint one H&S Representatives for every 20 employees or part thereof. (Section 17 of the Act and General Administrative Regulation 6. & 7.) H&S Representatives have to be designated in writing and the designation shall be in accordance with the Collective Agreement as concluded between the parties as is required in terms of General Administration Regulation 6.

11.8.2 Duties and Functions of the H&S Representatives

The Principal Contractor must ensure that the designated H&S Representatives conduct at least a weekly inspection of their respective areas of responsibility using a checklist and report thereon to the Principal Contractor, after which these reports shall be consolidated for submission to the Health and Safety Committee. H&S Representatives must be included in and be part of accident/incident investigations. H&S Representatives shall be members of at least one H&S Committee and must attend all meetings of that H&S committee.

11.8.3 Establishment of H&S Committee(s)

The Principal Contractor must establish H&S Committees consisting of designated H&S Representatives together with a number of Employers Representatives appointed as per Section 19(3) that are not allowed to exceed the number of H&S Representatives on the committee. The persons nominated by the employer on an H&S Committee must be designated in writing for such period as may be determined by the project

period. The H&S Committee shall co-opt advisory (temporary) members and determine the procedures of the meetings including the chairmanship.

12. HOUSE KEEPING

Good housekeeping will be maintained at all times as per Construction Regulation No. 25. Poor housekeeping contributes to three major problems, namely, costly or increased accidents, fire or fire hazards and reduction in production. Good housekeeping will enhance production time.

Particular emphasis is to be placed on the following crucial elements of a construction site:

- Phase priorities and production/plant layout
- Enclosures
- Pits, openings and shoring
- Storage facilities
- Effective, sufficient and maintained lighting or illumination
- Principal sources of injuries e.g. stairways, runways, ramps, loose building material
- Oil, grease, water, waste, rubble, glass, storm water
- Colour coding
- Demarcations
- Pollution
- Waste disposal
- Ablution and hygiene facilities
- First aid disposals
- Hazardous chemical substances

This list must not be taken to be exclusive or exhaustive.

In promotion of environmental control all waste, rubble, scrap etc, will be disposed of at a registered dumping site and records will be maintained. Where it is found to be impractical to use a registered dump site or it is not available, the Principal Contractor will ensure that the matter is brought to record with the client or his representative, after which suitable, acceptable alternatives will be sought and applied. Dross and refuse from metals, and waste matters or by-products whose nature is such that they are poisonous or capable of fermentation, putrefaction or constituting a nuisance shall be treated or disposed of by methods approved of by an inspector.

13. OPERATIONAL CONTROL

The Principal Contractor shall take reasonable steps to ensure that necessary control measures are taken to promote safe working environment during all operational works. Routine safety inspections shall be carried out to ensure plant; machinery and tools are safe enough for employees to work with. Operational control measures shall be taken for the following activities and plant or machinery where applicable:

- Fall protection;
- Excavation work;
- Scaffolding;
- Mobile plants;
- Electrical installation and machinery; and
- Other associated activities.

14. SUB CONTRACTORS

The Principal Contractor shall ensure that agreements are entered into by all sub-contractors on site, and ensure that all sub-contractors are in compliance with the health and safety standards on site. Particulars of sub-contractors involved in specialised work such as blasting, concrete works and electrical installations must be submitted to the designers for approval and their safety plans submitted to the Client for approval.

15. OFFENCES AND PENALTIES

Any contractor, who does not comply with the requirements of the Act, will be penalised or punished as per Section 38 of the Act. The principal contractor must also note that the Client may stop the execution of construction work if it is not in accordance with the health and safety plan or if it poses a threat on the health and safety of employees and the public.



MORETELE LOCAL MUNICIPALITY

C7. Site Information

7.1 General

This section describes the site at the time of the tender in order to enable the tenderer to price his tender accordingly and to decide upon his method of working, programming and risks.

The tenderer shall inform him / herself on the nature of the site and inspect the site.

The Employer will consider a tender only if the site inspection and/or tenderer's meeting arranged by the Engineer has been attended by a representative who must:

- Be suitably qualified to comprehend the implications of the work involved, and
- Be the tenderer him/herself or a person in the direct employ of the tenderer

7.2 Site location

The project is located in the North West Province, approximately 60 km from Tshwane and is part of Moretele Local Municipality in the jurisdiction of Moretele Local Municipality.

The project areas are in ward 16 of the Moretele Local Municipality. The villages for the project are namely;

Village name	Ward	Latitude	Longitude
Maubane	16	25°17'28.08"S	28°16'45.44"E
Dihibidung	16	25°16'58.17"S	28°16'05.11"E

Locality Details

- Province : North West Province
- District : Bojanala District Municipality
- Municipality : Moretele Local Municipality

The climate is very dry with an average annual rainfall between 600mm and 800mm. General vegetation cover consists of sparse grasses and thorn trees scattered over the site. The site is generally flat, falling gently towards the south.

The area is within the Molten, Elliot and Clarens formations. The Group comprises of materials such as Andesite, Basalt, Dolomite, Chert, Quartzite, Conglomerate and Calcrete.

The site has isolated hard rock outcrops of calcretes which needs to be blasted. It is anticipated that 25% to 30% of the trench excavations between depths of 0.8 to 2.0m deep will need to be blasted and will be classified as hard rock excavation.

7.3 Access to site and restrictions

The construction sites are situated in the existing villages as mentioned in 6.2. These sites can be reached via existing streets/roads and Provincial Roads

The operation of construction vehicles on existing roads or streets, or on streets which have been completed on the level of sub-base or base or bituminous surface treatment, shall be limited to traffic with an axle load not exceeding that allowed by the Road Traffic Ordinance of the authority concerned, or any amendment thereof. Hauling is strictly forbidden on sections of streets that have been completed as described above. The Contractor shall make use of temporary haul roads, or where not practically possible, program his work in such a manner that the haulage of materials shall be restricted to that required for the particular section of street. No additional payment shall be made for the use of temporary haul roads and all relevant costs shall be deemed to be covered by the appropriate rates.

The Contractor must note that no additional payment will be made for the construction of temporary access roads to the construction site, borrow-areas or to the spoil sites, except for payment made under payment item A.8.3.2.2 of SANS 1200 A.

If the Contractor does not make use of existing streets for the hauling of materials to or from the site, he shall be held responsible to clear any spillage caused by his activities on or near the roads by whatever means necessary, within two (2) days after such spillage has occurred. No additional payment will be made for the clearance of spillage and all relevant costs will be deemed to be covered under the relevant items.

7.4 Existing services, servitudes and way leaves

All the known existing services are indicated on the drawings.

7.5 Security

The security of the Contractor's plant, employers, materials and site camp will be the Contractor's responsibility.

7.6 Nature of ground and subsoil conditions

The Contractor shall familiarize himself with the conditions on site.

The materials on site mainly consist of soft and hard material. The majority of excavation will be in weathered and hard granite.

Also refer to the Project Specification "PS 4 : NATURE OF GROUND AND SUBSOIL CONDITIONS ON SITE".




MORETELE LOCAL MUNICIPALITY


C.8 Drawings

The following drawings, for tender purposes only, form part of this contract.

MORETELE DRAWINGS

1. GENERAL LAYOUT TS-001
2. DIHIBIDUNG LAYOUT TS-002
3. MAUBANE LAYOUT TS-003
4. WATER PIPES TS – 004
5. YARD CONNECTIONS TS – 005
6. ISOLATING VALVES TS – 006
7. CONTRACT NAMEBOARD TS – 007





A			REMARKS	REMARKS
No	DATE	REVISION	COMMIT	RE

**FOR TENDER
PURPOSES**

SCALE ON REDUCED DRAWING

SCALE ON REDUCED DRAWING

ISSUED BY	PK MOLE
REISSUED BY	PK MOLE
DRAINED BY	PK MOLE
REMOVED BY	PK MOLE



MORITSETTE LOCAL MUNICIPALITY
 PRINCE ALBERT
 MANGAPOE
 3406
 TEL (012) 711 1000
 FAX (012) 711 1001



PROJECT TITLE


WARD RETICULATION AND YARD

CONTRACT NUMBER:
DRAWING NAME
WARD 16 (OBEDDUNG, MAJBANE AND SOSPLAAS) LAYOUT

ON IN WARD 16	PROJEC 610-104	84001-101
	100-104-101	AS BROWN
	CONCRETE CROWN NUMBER TICKET	BLK ENHANCED COLOR

WATER RETICULATION & YARD CONNECTIONS IN WARD 16

CONTRACT NO. MLM/IDS/WRYC/W16/23-



FOR TENDER
PURPOSES
DO NOT SCALE DRAWING
SCALE ON REDUCED DRAWING



PRIBANTE SAG. X30
MANUFACTURADA
0464
TEL: (512) 716-1333
FAX: (512) 716-4881


TS Consulting
08 Hans van Rensburg Street, Suite No 11
P.O. Box 6817
Pretoria/ North
012 396 2886
E-mail: admin@tsconsulting.co.za

ANSWER

PROJECT TITLE
WARD RETICULATION AND YARD CONNECTION IN WARD 16
CONTRACT NUMBER:
DRAWING NAME
WARD 16 (DEENDING, MAURIAH AND BOGPLAAS) LAYOUT



WATER RETICULATION & YARD CONNECTIONS IN WARD 16




D = Depth of block
B = Width of block
W = Trench width
1. Half of the depth of the block shall be symmetrical about the pipe axis.
2. Keep couplings and flanges 25mm clear of concrete.
3. Diameter given is the nominal diameter of a pipe.

D _n (mm)	X (mm)	Y (mm)	Z (mm)	B (mm)	W (mm)
61	50	200	200	100	700
75	50	200	200	100	700
100	50	200	200	100	700
125	75	200	200	100	700
150	75	200	200	100	700
150	100	200	400	100	800
200	100	300	300	100	800
200	100	300	300	100	800
200	100	400	400	100	800
200	200	400	200	100	800

THRUST BLOCK FOR REDUCERS

Block cast symmetrically about plane containing axes of fitting and against undisturbed excavation




D = Depth of block
B = Width of block
W = Trench width
1. Half of the depth of the block shall be below the pipe axis.
2. Keep couplings and flanges 25mm clear of concrete.
3. Diameter given is the nominal diameter of a pipe.

D _n (mm)	X (mm)	Y (mm)	Z (mm)	B (mm)	W (mm)
61	400	300	100	800	700
75	400	400	100	800	700
100	400	400	200	800	700
125	400	400	300	800	700
150	400	400	300	800	700
200	400	400	300	800	700
200	1000	1000	300	800	700


THRUST BLOCKS FOR 90 DEG. BENDS

Block cast symmetrically about plane containing axes of fitting and against undisturbed excavation




D = Depth of block
B = Width of block
W = Trench width
1. Half of the depth of the block shall be below the pipe axis.
2. Keep couplings and flanges 25mm clear of concrete.
3. Diameter given is the nominal diameter of a pipe.

D _n (mm)	11 1/2"				
	X (mm)	Y (mm)	Z (mm)	W (mm)	W (mm)
61	—	—	—	—	—
75	100	150	80	400	700
100	100	200	80	475	700
125	100	200	100	500	800
150	100	200	100	500	800
200	100	300	100	525	800
200	400	400	200	525	800
200	1000	1000	300	525	800
200	1000	1000	400	525	800
200	1000	1000	500	525	800
200	1000	1000	600	525	800
200	1000	1000	700	525	800
200	1000	1000	800	525	800
200	1000	1000	900	525	800
200	1000	1000	1000	525	800
200	1000	1000	1100	525	800
200	1000	1000	1200	525	800
200	1000	1000	1300	525	800
200	1000	1000	1400	525	800
200	1000	1000	1500	525	800
200	1000	1000	1600	525	800
200	1000	1000	1700	525	800
200	1000	1000	1800	525	800
200	1000	1000	1900	525	800
200	1000	1000	2000	525	800
200	1000	1000	2100	525	800
200	1000	1000	2200	525	800
200	1000	1000	2300	525	800
200	1000	1000	2400	525	800
200	1000	1000	2500	525	800
200	1000	1000	2600	525	800
200	1000	1000	2700	525	800
200	1000	1000	2800	525	800
200	1000	1000	2900	525	800
200	1000	1000	3000	525	800
200	1000	1000	3100	525	800
200	1000	1000	3200	525	800
200	1000	1000	3300	525	800
200	1000	1000	3400	525	800
200	1000	1000	3500	525	800
200	1000	1000	3600	525	800
200	1000	1000	3700	525	800
200	1000	1000	3800	525	800
200	1000	1000	3900	525	800
200	1000	1000	4000	525	800
200	1000	1000	4100	525	800
200	1000	1000	4200	525	800
200	1000	1000	4300	525	800
200	1000	1000	4400	525	800
200	1000	1000	4500	525	800
200	1000	1000	4600	525	800
200	1000	1000	4700	525	800
200	1000	1000	4800	525	800
200	1000	1000	4900	525	800
200	1000	1000	5000	525	800
200	1000	1000	5100	525	800
200	1000	1000	5200	525	800
200	1000	1000	5300	525	800
200	1000	1000	5400	525	800
200	1000	1000	5500	525	800
200	1000	1000	5600	525	800
200	1000	1000	5700	525	800
200	1000	1000	5800	525	800
200	1000	1000	5900	525	800
200	1000	1000	6000	525	800
200	1000	1000	6100	525	800
200	1000	1000	6200	525	800
200	1000	1000	6300	525	800
200	1000	1000	6400	525	800
200	1000	1000	6500	525	800
200	1000	1000	6600	525	800
200	1000	1000	6700	525	800
200	1000	1000	6800	525	800
200	1000	1000	6900	525	800
200	1000	1000	7000	525	800
200	1000	1000	7100	525	800
200	1000	1000	7200	525	800
200	1000	1000	7300	525	800
200	1000	1000	7400	525	800
200	1000	1000	7500	525	800
200	1000	1000	7600	525	800
200	1000	1000	7700	525	800
200	1000	1000	7800	525	800
200	1000	1000	7900	525	800
200	1000	1000	8000	525	800
200	1000	1000	8100	525	800
200	1000	1000	8200	525	800
200	1000	1000	8300	525	800
200	1000	1000	8400	525	800
200	1000	1000	8500	525	800
200	1000	1000	8600	525	800
200	1000	1000	8700	525	800
200	1000	1000	8800	525	800
200	1000	1000	8900	525	800
200	1000	1000	9000	525	800
200	1000	1000	9100	525	800
200	1000	1000	9200	525	800
200	1000	1000	9300	525	800
200	1000	1000	9400	525	800
200	1000	1000	9500	525	800
200	1000	1000	9600	525	800
200	1000	1000	9700	525	800
200	1000	1000	9800	525	800
200	1000	1000	9900	525	800
200	1000	1000	10000	525	800
200	1000	1000	10100	525	800
200	1000	1000	10200	525	800
200	1000	1000	10300	525	800
200	1000	1000	10400	525	800
200	1000	1000	10500	525	800
200	1000	1000	10600	525	800
200	1000	1000	10700	525	800
200	1000	1000	10800	525	800
200	1000	1000	10900	525	800
200	1000	1000	11000	525	800
200	1000	1000	11100	525	800
200	1000	1000	11200	525	800
200	1000	1000	11300	525	800
200	1000	1000	11400	525	800
200	1000	1000	11500	525	800
200	1000	1000	11600	525	800
200	1000	1000	11700	525	800
200	1000	1000	11800	525	800
200	1000	1000	11900	525	800
200	1000	1000	12000	525	800
200	1000	1000	12100	525	800
200	1000	1000	12200	525	800
200	1000	1000	12300	525	800
200	1000	1000	12400	525	800
200	1000	1000	12500	525	800
200	1000	1000	12600	525	800
200	1000	1000	12700	525	800
200	1000	1000	12800	525	800
200	1000	1000	12900	525	800
200	1000	1000	13000	525	800
200	1000	1000	13100	525	800
200	1000	1000	13200	525	800
200	1000	1000	13300	525	800
200	1000	1000	13400	525	800
200	1000	1000	13500	525	800
200	1000	1000	13600	525	800
200	1000	1000	13700	525	800
200	1000	1000	13800	525	800
200	1000	1000	13900	525	800
200	1000	1000	14000	525	800
200	1000	1000	14100	525	800
200	1000	1000	14200	525	800
200	1000	1000	14300	525	800
200	1000	1000	14400	525	800
200	1000	1000	14500	525	800
200	1000	1000	14600	525	800
200	1000	1000	14700	525	800
200	1000	1000	14800	525	800




PLAN OF PLASTIC METER BOX
SCALE 1:50

ROAD RESERVE




OLD TYPE METER
N.B.
ONLY FOR MAINTENANCE OR
IF DIRECTED BY ENGINEER

ERF



SECTION ELEVATION OF PLASTIC METER BOX
SCALE 1:5

FOR USE WITH 20mm² PIPES FOR ALL
NEW DOMESTIC CONNECTIONS



LONG SHORT COMBINATION
DETAIL

TYPICAL SECTION



PLAN SINGLE CONNECTION



PLAN DOUBLE CONNECTION



LONG ERF CONNECTIONS
SCALE 1:50

DIMENSION MAY VARY
BETWEEN 380-400mm
DEPENDING ON THE TYPE
METER TO BE USED



PLAN SINGLE CONNECTION



PLAN DOUBLE CONNECTION



SHORT ERF CONNECTIONS
SCALE 1:50

DIMENSION MAY VARY
BETWEEN 380-400mm
DEPENDING ON THE TYPE
METER TO BE USED

FOR TENDER PURPOSES	DESPENDED BY	IN MSA
MADE IN PLASTIC 20mm ²	CHIEF ENGINEER	
SCALE ON REDUCED DRAWING	DESIGNED BY	IN MSA
	CHIEF ENGINEER	

MADE IN PLASTIC 20mm²
SCALE ON REDUCED DRAWING



MORELELE LOCAL MUNICIPALITY
PRIVATE BAG X907
MAMKANANE 8400
TEL: (012) 7110000
FAX: (012) 7110000
E-mail: admin@morelele.org.za



TS Consulting
SARL
100 Main Street, Suite N1
PO Box 1011
0100-00111
TEL: (011) 2671200
FAX: (011) 2671200
E-mail: admin@tsconsulting.co.za

PROJECT TITLE:
WARD RETICULATION AND YARD CONNECTION IN WARD 16


WORK
ITEM
NO.
1
AS DRAWN

CONTRACT NUMBER:


DRAWING NAME:
TYPICAL DETAILS METER BOXES AND WATER COMMUNICATING PIPES

WORK
ITEM
NO.
2
AS DRAWN



CONTRACT NO. MLM/IDS/WRYC/W16/23-



BACK ELEVATION



TOP ELEVATION






RULES

1. Typeface to be used shall be helvetica medium.
2. Size of lettering and dimensions are indicated on the diagram and shall be strictly adhered to.
3. Height of Board depends on number of professional services displayed. Note all professional services are to be shown.
4. Project name and owner shall be white lettering on middle blue background.
5. surrounding border shall be in middle blue.
6. professional crests and company names shall be in black on white.
7. The board shall conform to the diagram subject to rule 4

NOTE

Paint colours are based on
plascon-evans.White vlo 1:Tequila
vlo 10 (Velvaglo polyurethane velvet
enamel) black ref.266,middle
blue ref 290 (acrylic road sign paints)



HELVETICA MEDIUM 100mm WHITE CAPITAL AND SMALL

FOR TENDER
PURPOSES

DESIGNED BY
CHIEF DESIGNER
DRAWN BY



PRIVATE EAG
MAKAN/PANESTA
5404
TEL: (012) 716-
FAX: (012) 716-



ing
TEL: (318) 287-3388
FAX: (318) 291-5202

卷之三

PROJECT TITLE
WARD RETICULATION AND YARD CONNECTION IN WARD 16
CONTRACT NUMBER:
DRAWING NAME

	WIRELESS STATUS	WIRELESS
	WIRELESS	WIRELESS
	AS IS SHOWN	AS IS SHOWN

WATER RETICULATION & YARD CONNECTIONS IN WARD 16

CONTRACT NO. MI M/IDS/WB/YC/W16/23-