

BILL NO	102	SITE CLEARANCE	PHASE 0 - 3 + 13			
PAYMENT REF	ITEM NO	DESCRIPTION	UNIT	RATE	QUANTITY	AMOUNT
1200 C		<u>Site Clearance</u>				
		<u>SITE CLEARANCE</u>				
8.2.1	102.01	Clear and grub (spoil to a site provided by: the Contractor):				
		a) General landscaped/grassed areas	m²		109384	
8.2.2	102.02	Remove and grub large trees and tree stumps of girth:				
		a) Over 1,0 m and up to and including 2,0 m	No		10	
		b) Over 2,0 m and up to and including 3,0 m	No		6	
8.2.5	102.03	Take down existing fences	km		9	
8.2.7	102.04	Dismantle and remove:				
		a) Pipelines not encased in concrete: (pipes found in road reserve to be decommissioned and closed)				
		.01 Up to 500 mm dia	m		500	
		b) Electricity transmission lines:				
		.01 Low voltage cables	m		250	
		.02 Medium voltage cables	m		5358	
PS C 8.2.4	102.05	Remove existing asphalt and spoil off-site to approved dump sites as identified by the Contractor				
		a) Existing roads asphalt removal	m³		842	
PS C 8.2.11	102.06	Dismantle and relocate existing households to a new selected site:				
		a) Individual housing units	No		1457	
8.2.9	102.07	Transport materials and debris to unspecified sites and dump				
		a) Select and remove all domestic waste	m³		13736	
		b) Load and cart contaminated material to a licenced waste facility	m³		13736	
		c) Dumping Ticket costs	Prov. Sum	R 5 000 000	1	R 5 000 000
		d) Overheads, charges and profit for Contractor on above	%			
8.2.10	102.08	Remove topsoil to nominal depth of 150 mm and stockpile	m³		29650	
PHASE 1 - 3 + PHASE 0 - 3 + 13 SITE CLEARANCE SUBTOTAL CARRIED TO TOTAL						