

Item No	Quantity	Rate	Amount
<p><u>SECTION NO 1</u></p> <p><u>BILL NO. 1</u></p> <p><u>PRELIMINARIES</u></p> <p>1. The Principal Building Agreement shall be the JBCC Series Edition 4.1, March 2005 as recommended by the Joint Building Contract Committee and as amended by this Tender Enquiry.</p> <p>2. The Preliminaries shall be JBCC Series 2000, May 2005 for use with the Principal Building Agreement as recommended by the Joint Building Contracts Committee and as amended by this Tender Enquiry shall be deemed to be incorporated herein.</p> <p>3. Tenderers are referred to the above mentioned documents for the full intent and meaning of each clause thereof. These clauses are hereinafter referred to by clause number and heading only.</p> <p>4. Where standard clauses or alternatives are not entirely applicable to this contract, such modifications, corrections or additions as are necessary, are given as far as possible under each relevant clause heading. Additional Preliminary clauses are contained in Section C hereof.</p> <p>5. No claim whatsoever shall be entertained in respect of errors or omissions in pricing due to brevity of descriptions of items which are fully described when read in conjunction with the relevant clauses of the said Principal Building Agreement, Preliminaries and Preambles.</p>			
<p>Carried to Collection</p>			<p>R</p>
<p>Section No. 1 PRELIMINARIES Bill No. 1 PRELIMINARIES & GENERAL</p>			

6. The Tenderers shall allow opposite each of the clauses whatever costs and charges he may consider necessary for the carrying out, complying with and due observance of the provisions, conditions and requirements set out herein. Only priced items will be considered in respect of any adjustment of this Section. Any items left unpriced will be understood to be provided free of charge and no claim for any extras arising out of the Tenderer's omission to price any item will be entertained.

7. Where modifications or amendments as described are made, such modifications and/or amendments shall supercede any conflicting provisions in the relevant clauses of the Standard Preliminaries or the Principal Building Agreement and the Tenderer shall make due allowance for whatever costs and charges he may consider necessary for the carrying out and observance of the provisions of the clauses as modified and/or amended.

8. Where any item is not relevant to this specific contract, such item is marked N/A.

9. If Alternative A as set out in clause B10.3 hereinafter is to be used for the adjustment of the preliminaries, each item priced is to be allocated to one or more of the three categories by insertion of "F", "V", "T" as the case may be against the price in the "rate" column immediately preceding the "amount" column, where "F" denotes a fixed amount (amount not to be varied), "V" denotes an amount variable in proportion to value, and "T" denotes an amount proportionate to time.

SECTION A: PRINCIPAL BUILDING AGREEMENT

Definitions (A1)

1 Definitions and interpretation (clause 1)

F:..... V:..... T:.....

Item

Objective and Preparation (A2 to A14)

2 Offer acceptance and performance (clause 2)

F:..... V:..... T:.....

Item

Carried to Collection

R

Section No. 1
PRELIMINARIES
Bill No. 1
PRELIMINARIES & GENERAL

3	<p>Documents (clause 3)</p> <p>F:..... V:..... T:.....</p> <p>.Clause 3.1 is deleted and substituted with: 'This tender is for a Government Contract. No Payment Guarantee will be provided.'</p> <p>Clause 3.3 is deleted and substituted with:</p> <p>The principal agent shall complete the schedule and arrange for formal signing of the agreement once the priced bill of quantities/lump sum document, security, insurances and waiver of lien, where acceptable, have been provided and effected'.</p>	Item			
4	<p>Design responsibility (clause 4)</p> <p>F:..... V:..... T:.....</p>	Item			
<p>Section No. 1 PRELIMINARIES Bill No. 1 PRELIMINARIES & GENERAL</p>		Carried to Collection	R		

5 Employer's agents (clause 5)

F:..... V:..... T:.....

The principal agent shall:

- monitor and control progress and scheduling
- monitor all contract conditions, and
- coordinate the efforts of the employer's agents, the contractor and subcontractors

The powers conferred on the principal agent in terms of this clause and/or the exercising of these powers shall not be construed as removing or diminishing any of the obligations of the Contractor in terms of the Principal Building Agreement, whether financial, contractual or otherwise, nor shall the exercising of these powers create any privity of contract as between the Employer or his agents on the one part and the Contractor or subcontractors or suppliers on the other part

The principal agent reserves the right to attend and participate in all contractor/subcontractor's meetings, to invite other employer's agents to attend such meetings at his discretion and to converse and chair any such meetings if the contractor is derelict in his duty in arranging such meetings to the degree of frequency and comprehensiveness dictated in the opinion of the project manager by the circumstances and exigencies of the construction process

Item

6 Site representative (clause 6)

F:..... V:..... T:.....

Item

Carried to Collection

R

Section No. 1
PRELIMINARIES
Bill No. 1
PRELIMINARIES & GENERAL

7 Compliance with regulations (clause 7)

F:..... V:..... T:.....

Sub-clause 7.3 added:

The Occupational Health and Safety Act No. 85 of 1993 and the Construction Regulations 2014 will in all respects be applicable to this contract. All obligations in respect of health and safety requirements of the Contractor are set out in the Scope of Work.

Sub-clause 7.3.1 is added:

Notwithstanding any actions which the employer may take, the contractor accepts sole liability for due compliance with the relevant duties, obligations, prohibitions, arrangements and procedures imposed by the Occupational Health and Safety Act, 1993 (Act 85 of 1993), and all its regulations, including the Construction Regulations, 2014, for which the contractor is liable as mandatory. By entering into this agreement it shall be deemed that the parties have agreed in writing to the above provisions in terms of Section 37 (2) of the Act and will enter into the mandatory agreement as set out in the Scope of Work. This clause will be sufficient to establish the mandatory obligations of the contractor in the event the parties fail to execute the aforesaid mandatory agreement."

Note: A separate clause has been included in Section C: Specific Preliminaries of the bills of quantities / lump sum document for the contractor to have the opportunity to price for all the requirements of the Occupational Health and Safety Act, Construction Regulations and Health and Safety Specification.

The contractor shall also comply with the additional requirements with regard to the Coronavirus pandemic in terms of all Covid-19 legislation, regulations and guidelines.

Item

8 Works risk (clause 8)

F:..... V:..... T:.....

Item

Carried to Collection

R

Section No. 1
PRELIMINARIES
Bill No. 1
PRELIMINARIES & GENERAL

9	<p>Indemnities (clause 9)</p> <p>F:..... V:..... T:.....</p> <p>Clause 9.1.1 is deleted and substituted with:</p> <p>Claims from other parties consequent upon death of bodily injury or illness of any person or physical loss or damage to any property, other than the works, arising out or due to the execution of the works or occupation of the site by the contractor or his sub contractors'.</p>				
		Item			
10	<p>Works insurances (clause 10)</p> <p>F:..... V:..... T:.....</p>				
		Item			
11	<p>Liability insurances (clause 11)</p> <p>F:..... V:..... T:.....</p>				
		Item			
12	<p>Effecting insurance (clause 12)</p> <p>F:..... V:..... T:.....</p>				
		Item			
13	<p>State Provisions (Clause 13).</p> <p>F: V: T:</p>				
		Item			
14	<p>Security (clause 14)</p> <p>The security to be submitted by the contractor to the employer will be as a payment reduction of ten per cent (10%) of the value certified in the payment certificate (excluding VAT)</p> <p>F:..... V:..... T:.....</p>				
		Item			
<p style="text-align: right;">Carried to Collection</p> <p>Section No. 1 PRELIMINARIES Bill No. 1 PRELIMINARIES & GENERAL</p>					
				R	

Execution (A15-A23)

15 Preparation for and execution of the works (clause 15)

F:..... V:..... T:.....

Item

16 Access to the works (clause 16)

F:..... V:..... T:.....

Item

17 Contract instructions (clause 17)

F:..... V:..... T:.....

Item

18 Setting out of the works (clause 18)

F:..... V:..... T:.....

The contractor shall notify the principal agent if any encroachments of adjoining foundations, buildings, structures, pavements, boundaries, etc exist in order that the necessary arrangements may be made for the rectification of any such encroachments

Item

19 Assignment (clause 19)

F:..... V:..... T:.....

The contractor shall not cede his rights or delegate his obligations in terms of this agreement unless specifically called for by the employer

Item

20 Nominated subcontractors (clause 20)

F:..... V:..... T:.....

Item

Carried to Collection

R

Section No. 1
PRELIMINARIES
Bill No. 1
PRELIMINARIES & GENERAL

27	<p>Latent defects liability period (clause 27)</p> <p>F:..... V:..... T:.....</p> <p>Clause 27.0 is amended by the addition of the following clauses: "27.3 Any water leakage into the building, whether in the roof, external wall or other element of the building susceptible to water leakage shall, unless proven to be a design defect, or as a result of obvious storm damage, be classified as a latent defect in terms of clause 1.0 Definitions and Interpretations". "27.4 The Contractor shall attend to defects during the Defects Liability Period on a progressive basis, to the satisfaction of the Principal Agent and will not be permitted to wait until the end of the Defect Liability Period or until the amount of defects accumulates in order to attend to a comprehensive list of defects"</p>	Item		
28	<p>Sectional completion (clause 28)</p> <p>F:..... V:..... T:.....</p>	Item		
29	<p>Revision of date of practical completion (clause 29)</p> <p>F:..... V:..... T:.....</p> <p>The removal and replacement of materials and/or workmanship that do not conform to specification or drawings shall not constitute grounds for an extension of the construction period nor for an adjustment to the contract sum (clause 29.3)</p>	Item		
30	<p>Penalty for non-completion (clause 30)</p> <p>F:..... V:..... T:.....</p>	Item		
Carried to Collection			R	
Section No. 1 PRELIMINARIES Bill No. 1 PRELIMINARIES & GENERAL				

Payment (A31 - A35)

31 Interim payment to the contractor (clause 31)

F:..... V:..... T:.....

The inclusion of materials and goods stored off site in the amount authorised for payment in terms of clause 31.3 shall be at the sole discretion of the principal agent and such inclusion shall only be considered upon the provision, by the contractor, of an approved guarantee issued by a registered commercial bank.

Where prices are submitted by the contractor or nominated/selected sub contractor during the progress of the works in respect of contract instructions or in regard to a claim under the terms of the contract and notwithstanding the fact that such prices may be used in an interim payment certificate, there is to be no presumption of acceptance. Should the principal agent wish to accept any such prices prior to the issue of the final certificate, it will be in writing.

Item

32 Adjustment to the contract value (clause 32)

F:..... V:..... T:.....

Where prices are submitted by the contractor or nominated/selected subcontractors during the progress of the works in respect of contract instructions or in regard to a claim under the terms of the contract and notwithstanding the fact that such prices may be used in an interim payment certificate, there is to be no presumption of acceptance. Should the principal agent wish to accept any such prices prior to the issue of the final certificate, it will be in writing

Item

33 Recovery of expense and loss (clause 33)

F:..... V:..... T:.....

Item

Carried to Collection

R

Section No. 1
PRELIMINARIES
Bill No. 1
PRELIMINARIES & GENERAL

35	Payment to other parties (clause 35)
	F:..... V:..... T:.....

Cancellation (A36-A39)

36	Cancellation by employer - contractor's default (clause 36)
----	---

F:..... V:..... T:.....

37 Cancellation by employer - loss and damage (clause 37)

F: V: T:

38	Cancellation by contractor - employer's default (clause 38)
----	---

F: V: T:

Item

R

-11-

39 Cancellation - cessation of the works (clause 39)
F:..... V:..... T:.....

Item

Dispute (A40)

40 Dispute Settlement (clause 40)
F:..... V:..... T:.....

Item

Substitute Provisions (A41)

41 State clauses (Clause 41)
F:..... V:..... T:.....

Item

Contract variables

42 State clauses (Clause 42)
F:..... V:..... T:.....

Item

Carried to Collection

R

Section No. 1
PRELIMINARIES
Bill No. 1
PRELIMINARIES & GENERAL

42.1 CONTRACTING AND OTHER PARTIES

42.1.1 Employer: The Mvula Trust

Postal Address: 67 Devereux Avenue, Vincent, East

London

Telephone: 043 726 2255

Facsimile: 043 726 5967

Physical address: 67 Devereux Avenue, Vincent, East
London

Principal Agent: The Mvula Trust

Postal Address: 67 Devereux Avenue, Vincent, East
London

Telephone: 043 726 2255

Facsimile: 043 726 5967

Physical address: 67 Devereux Avenue, Vincent, East
London

42.2 CONTRACT DETAILS

42.2.1 Works Description: Construction of new
ablutions facilities

42.2.2 Site Description: the site is an existing school.

42.2.3 Work or installations by Others: NIL

Carried to Collection

Section No. 1
PRELIMINARIES
Bill No. 1
PRELIMINARIES & GENERAL

R

42.2.4 This agreement is for a government contract where there are specific options that are applicable to a **State** organ only

Yes

Payment will be made for materials and goods:- Yes

Dispute resolution :- Mediation (in terms of clause 40) followed by litigation.

Arbitration rules as recommended by the Association of Arbitrators (SA) :- N/A

42.2.5 Date on which possession of the site is intended to be given:

To be advised

42.2.6 Period for the commencement of the works after the contractor takes possession of site:

5 working days

Period for the commencement of the works after the contractor takes possession of the site :- 5 Working days.

Completion in Sections are required : NO

42.2.7 Intended date of practical completion and the penalty per calendar day for the works as a whole :-

To be advised.

Penalty amount will be 5,75c/R100 of Contract Sum.

Carried to Collection

Section No. 1
PRELIMINARIES
Bill No. 1
PRELIMINARIES & GENERAL

R

42.2.8 Intended date of practical completion and the penalty per calendar day

N/A..... Date

N/A..... Penalty Amount

42.2.9 The **law** applicable to this **agreement** shall be that of:

South Africa (Country)

42.3 INSURANCES

42.3.1 Contract works insurance to be effected by:

Contractor:

For the Sum of R Contract Amount + 10.00 %

With a deductible amount of: Not exceeding 5% of each and every claim.

Supplementary insurance is required : Yes

42.3.2 Supplementary insurance is required:

Yes

SASRIA insurance required to be effected by the Contractor for the amount of: Contract Sum plus 20% (with a deductible to be determined by the Insurance company issuing the policy).

42.3.3 Public liability insurance to be effected by:

Contractor:

For the Sum of R 5 000 000-00

With a deductible amount of: Not exceeding 5% of each and every claim

Carried to Collection

Section No. 1
PRELIMINARIES
Bill No. 1
PRELIMINARIES & GENERAL

R

42.4 DOCUMENTS

42.4.1 Waivers of **contractors lien** or right of continuing possession is required

Yes

42.4.2 Number of construction document copies to be supplied to the **contractor** free of charge:

3 Number of

42.4.3 **Bills of Quantities/Lump sum document** schedule of rates drawn up in accordance with:

"Standard System of Measuring Builders' Work"

42.4.4 On acceptance of the tender the bills of quantities/lump sum document is to be submitted within:

5 Working days

The priced bills of quantities must be handed in with the tender

42.4.5 JBCC Engineering General Conditions are to be included in the **contract documents**:

No

42.4.6 The contract value is to be adjusted using escalation adjustment indices

No

Where **JBCC CPAP** is to be used

Base Month N/A

SECTION B: PRELIMINARIES

Definitions and interpretation (B1)

43 Definition and interpretation (B1.1 - B1.4.6)

F:..... V:..... T:.....

Item

Carried to Collection

R

Section No. 1
PRELIMINARIES
Bill No. 1
PRELIMINARIES & GENERAL

<u>Documents (B2)</u>				
44	Checking of documents (B2.1) F:..... V:..... T:.....	Item		
45	Provisional bills of quantities (B2.2) F:..... V:..... T:.....	N/A		
46	Availability of construction documentation (B2.3) F:..... V:..... T:.....	Item		
47	Interests of agents (B2.4) F:..... V:..... T:.....	Item		
48	Priced documents (B2.5) F:..... V:..... T:.....	Item		
49	Tender submission (B2.6) F:..... V:..... T:.....	Item		
<u>The site (B3)</u>				
50	Defined works area (B3.1) F:..... V:..... T:.....	Item		
51	Geotechnical investigation (B3.2) F:..... V:..... T:.....	Item		
52	Inspection of the site (B3.3) F:..... V:..... T:.....	Item		
Carried to Collection			R	
Section No. 1 PRELIMINARIES Bill No. 1 PRELIMINARIES & GENERAL				

	Existing premises occupied (B3.4)				
	F:..... V:..... T:.....				
	Specific requirements: The contractor shall also comply with the additional requirements with regard to the Coronavirus pandemic in terms of all Covid-19 legislation, regulations and guidelines.				
	Previous work - dimensional accuracy (B3.5)				
	F:..... V:..... T:.....				
	Previous work - defects (B3.6)				
	F:..... V:..... T:.....				
53	Services - known (B3.7)				
	F:..... V:..... T:.....		Item		
54	Services - unknown (B3.8)				
	F:..... V:..... T:.....		Item		
55	Protection of trees etc (B3.9)				
	F:..... V:..... T:.....		Item		
56	Articles of value (B3.10)				
	F:..... V:..... T:.....		Item		
57	Inspection of adjoining properties etc (B3.11)				
	F:..... V:..... T:.....		Item		
Carried to Collection				R	
Section No. 1					
PRELIMINARIES					
Bill No. 1					
PRELIMINARIES & GENERAL					

Management of contract (B4)

58 Management of the works (B4.1)

F:..... V:..... T:.....

Item

59 Programme for the works (B4.2)

F:..... V:..... T:.....

Item

60 Progress meetings (B4.3)

F:..... V:..... T:.....

Item

61 Technical meetings (B4.4)

F:..... V:..... T:.....

Item

62 Labour and Plant records (B4.5)

F:..... V:..... T:.....

Item

Samples, Shop Drawings and Manufacturer's Instructions (B5)

63 Samples of materials (B5.1)

F:..... V:..... T:.....

Item

64 Workmanship samples (B5.2)

F:..... V:..... T:.....

Item

65 Shop drawings (B5.3)

F:..... V:..... T:.....

Item

Carried to Collection

R

Section No. 1
PRELIMINARIES
Bill No. 1
PRELIMINARIES & GENERAL

66	Compliance with Manufacturer's Instructions (B5.4) F:..... V:..... T:.....	Item		
	<u>Temporary works and plant (B6)</u>			
67	Deposits and fees (B6.1) F:..... V:..... T:.....	Item		
68	Enclosure of the works (B6.2) F:..... V:..... T:.....	Item		
69	Advertising (B6.3) F:..... V:..... T:.....	Item		
70	Plant, equipment, sheds and offices (B6.4) F:..... V:..... T:.....	Item		
71	Main notice board (B6.5) F:..... V:..... T:.....	Item		
72	Subcontractors' notice board (B6.6) F:..... V:..... T:.....	N/A		
	<u>Temporary services (B7)</u>			
73	Location (B7.1) F:..... V:..... T:.....	Item		
Carried to Collection			R	
Section No. 1 PRELIMINARIES Bill No. 1 PRELIMINARIES & GENERAL				

[illegible]

Financial aspects (B10)

Statutory taxes, duties and levies (B10.1)

F:..... V:..... T:.....

Provision is made in the Final Summary of these
Bills of
Quantities for the inclusion of Value Added Tax
(VAT).

Item

82 Payment of preliminaries (B10.2)

Option [B] shall apply

F:..... V:..... T:.....

Item

83 Adjustment of preliminaries (B10.3)

Option [A] shall apply

F:..... V:..... T:.....

Item

84 Payment certificate cash flow (B10.4)

F:..... V:..... T:.....

Item

85 Contractor information supply (B10.5)

F:..... V:..... T:.....

Item

General (B11)

86 Protection of works (B11.1)

F:..... V:..... T:.....

Item

87 Protection/isolation of existing/sectionally occupied
works (B11.2)

F:..... V:..... T:.....

Item

Carried to Collection

R

Section No. 1
PRELIMINARIES
Bill No. 1
PRELIMINARIES & GENERAL

88	<p>Security of the Works (B11.3)</p> <p>The security to be submitted by the contractor to the employer will be as a payment reduction of ten per cent (10%) of the value certified in the payment certificate (excluding VAT)</p> <p>F:..... V:..... T:.....</p>	Item		
89	<p>Notice before covering work (B11.4)</p> <p>F:..... V:..... T:.....</p>	Item		
90	<p>Disturbance (B11.5)</p> <p>F:..... V:..... T:.....</p>	Item		
91	<p>Environmental Disturbance (B11.6)</p> <p>F:..... V:..... T:.....</p>	Item		
92	<p>Works cleaning and clearing (B11.7)</p> <p>F:..... V:..... T:.....</p>	Item		
93	<p>Vermin (B11.8)</p> <p>F:..... V:..... T:.....</p>	Item		
94	<p>Overhand work (B11.9)</p> <p>F:..... V:..... T:.....</p>	Item		
95	<p>Instruction manuals and guarantees (B11.10)</p> <p>F:..... V:..... T:.....</p>	Item		
Carried to Collection			R	
<p>Section No. 1 PRELIMINARIES Bill No. 1 PRELIMINARIES & GENERAL</p>				

96	As built information (B11.11) F:..... V:..... T:.....	Item		
97	Tenant Installations (B11.12) F:..... V:..... T:.....	Item		
<u>Schedule of variables (B12)</u>				
98	Pre-tender information (B12.1) F:..... V:..... T:.....	Item		
	12.1.1 Provisional bills of quantities (B2.2) The quantities are provisional: No			
	12.1.2 Availability of construction documentation (B2.3) Construction documentation is not complete No			
	12.1.3 Interest of agents (B2.4)			
	12.1.4 Defined works area (B3.1)			
	12.1.5 Geotechnical investigation (B3.2) N/A			
	12.1.6 Existing premises occupied (B3.4)			
	12.1.7 Previous work - dimensional accuracy (B3.4)			
	12.1.8 Previous work - defects (B3.5)			
Carried to Collection			R	
Section No. 1 PRELIMINARIES Bill No. 1 PRELIMINARIES & GENERAL				

[illegible]

SECTION C: SPECIFIC PRELIMINARIES

Any special items to meet the particular circumstances of a specific project are embodied in this section. Where required for an aspect of the works to be executed according to a design by a consulting engineer, a recital of the headings to the individual clauses of the JBCC Engineering General Conditions are included

99 Site instructions

Instructions issued on site are to be recorded in triplicate in a site instruction book which is to be maintained on site by the contractor

F: V:
T:

Item

100 Black economic empowerment and training

F: V: T:

Item

101 Proprietary branded products

F: V: T:

Item

102 Testing of flat roof waterproofing for watertightness

Flat roof waterproof areas shall be prepared with small sand dykes around them of a size and enclosing an area approved by the principal agent, flooded with water and kept "ponded" for at least 36 hours as a test to ensure the watertightness of the waterproofing and before any further construction work is carried out above the waterproofing

F: V: T:

Item

The contractor shall take delivery of, handle, store, use, apply and/or fix all proprietary branded products in strict accordance with the manufacturers' instructions after consultation with the manufacturer's authorised representative

Carried to Collection

R

Section No. 1
PRELIMINARIES
Bill No. 1
PRELIMINARIES & GENERAL

103	<p>Contract instructions</p> <p>F:..... V:..... T:.....</p> <p>Contract instructions issued on site are to be recorded in triplicate in a contract instruction book which is to be supplied and maintained on site by the contractor</p>	Item		
104	<p>Labour record</p> <p>F:..... V:..... T:.....</p> <p>At the end of each week the contractor shall provide the principal agent with a written record, in schedule form, reflecting the number and descriptions of tradesmen and labourers employed by him and all subcontractors on the works each day of that week</p>	Item		
105	<p>Plant record</p> <p>F:..... V:..... T:.....</p> <p>At the end of each week the contractor shall provide the principal agent with a written record, in schedule form, reflecting the number, type and capacity of all plant, excluding hand tools used on the works each day of that week</p>	Item		
106	<p>Guarantees</p> <p>F:..... V:..... T:.....</p>	Item		
Carried to Collection			R	
<p>Section No. 1 PRELIMINARIES Bill No. 1 PRELIMINARIES & GENERAL</p>				

Where guarantees are called for, the contractor shall obtain a written guarantee, addressed to the employer, from the firm supplying the materials and/or doing the work and shall deliver same to the principal agent on the certified completion of the contract. The guarantee shall state that workmanship, materials and installation are guaranteed for a specified period from the date of certified completion of the contract, and that any defects that may arise during the specified period shall be made good at the expense of the firm supplying the materials and/or doing the work, upon written notice from the principal agent to do so. This guarantee will not be enforced if the work is damaged by defects in the construction of the building in which case the responsibility for replacement shall rest entirely with the contractor. The principal agent shall be the sole judge of the cause responsible for defects in the work and his decision shall be final and binding in terms of clause 40.2 of the agreement

107 Overtime

F:..... V:..... T:.....

Item

Should overtime be required to be worked for any reason whatsoever, the costs of such overtime are to be borne by the contractor unless the principal agent has specifically authorised, in writing, prior to execution thereof, that costs for such overtime are to be borne by the employer

108 Co-operation of contractor for cost management

F:..... V:..... T:.....

Item

Carried to Collection

R

Section No. 1
PRELIMINARIES
Bill No. 1
PRELIMINARIES & GENERAL

It is specifically agreed that the contractor accepts the obligation of assisting the professional consultants in implementing proper cost management. The contractor will be advised by the principal agent of all cost management procedures which will be implemented to ensure that the final building cost does not exceed the budget. The quantity surveyor undertakes to make available to the contractor all budgetary allowances and cost assessments/reports to enable the proper procedures to be implemented and the contractor will attend all cost plan review and cost management meetings. The contractor undertakes to extend these procedures in regard to all subcontractors

Carried to Collection

Section No. 1
PRELIMINARIES
Bill No. 1
PRELIMINARIES & GENERAL

R

109	Occupational Health and Safety Specification		
F:..... V:..... T:.....	<p>The contractor shall comply with all the requirements set out in the Construction Regulations, 2014 issued under the Occupational Health and Safety Act, 1993 (Act No 85 of 1993)</p> <p>It is required of the contractor to thoroughly study the Health and Safety Specification that must be read together with and is deemed to be incorporated under this Section of the bills of quantities / lump sum document</p> <p>The contractor must take note that compliance with the Occupational Health and Safety Act, Construction Regulations and Health and Safety Specification is compulsory. In the event of partial or total non-compliance, the principal agent, notwithstanding the provisions of clause A31.0 of Section A or any other clause to the contrary, reserves the right to delay issuing any progress payment certificate until the contractor provides satisfactory proof of compliance. The contractor shall not be entitled to any compensation of whatsoever nature, including interest, due to such delay of payment</p> <p>Provision for pricing of the Occupational Health and Safety Act, Construction Regulations and Health and Safety Specification is made under this clause, as well as the clauses that follow hereafter and it is explicitly pointed out that all requirements of the aforementioned are deemed to be priced under these clauses and no additional claims in this regard shall be entertained</p> <p>The contractor shall also comply with the additional requirements with regard to the Coronavirus pandemic in terms of all Covid-19 legislation, regulations and guidelines. It is explicitly pointed out that all requirements of the aforementioned are deemed to be priced under this clause and the specific related clauses hereafter and no additional claims in this regard shall be entertained</p>	Item	R
Carried to Collection			
Section No. 1 PRELIMINARIES Bill No. 1 PRELIMINARIES & GENERAL			

110 HIV/AIDS Awareness

F:..... V:..... T:.....

It is required of the contractor to thoroughly study the HIV/AIDS Specification (PW 1544) of the Department that must be read together with and is deemed to be incorporated under this Section of the bills of quantities / lump sum document. Provision for pricing of HIV/AIDS awareness is made under items C11.1 to C11.5 hereafter and it is explicitly pointed out that all requirements of the aforementioned specification are deemed to be priced hereunder, as the said items represent the only method of measurement and no additional items or extras to the contract in this regard shall be entertained.

The contractor must take note that compliance with the HIV/AIDS Specification is compulsory. In the event of partial or total non-compliance, the principal agent, notwithstanding the provisions of clause A 31.0 of Section A or any other clause to the contrary, reserves the right to delay issuing any progress payment certificate until the contractor provides satisfactory proof of compliance. The contractor shall not be entitled to any compensation of whatsoever nature, including interest, due to such delay of payment

Any Principal Contractor entering into a contract with The Developer must achieve an acceptable level of Occupational Health and Safety performance. Refer to "Project Specification" and "Safety, Health and Environmental Evaluation Questionnaire" The contractor to comply with all provisions of the above and to be enforced on all selected and or other sub-contractors, as no claim afterwards will be entertained

SUMMARY OF CATEGORIES

Category : Fixed R.....

Category : Value R.....

Category : Time R.....

Item

Carried to Collection

R

Section No. 1
PRELIMINARIES
Bill No. 1
PRELIMINARIES & GENERAL

Item No	Quantity	Rate	Amount
<u>SECTION NO 1</u>			
<u>BILL NO. 2</u>			
<u>HEALTH AND SAFETY</u>			
<u>MODEL PREAMBLES</u>			
The tenderer is referred to the "Model Preambles for Trades 2008" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates.			
<u>SUPPLEMENTARY PREAMBLES</u>			
Supplementary preambles and/or specifications are incorporated in these bills of quantities to satisfy the requirements of this project. Such supplementary preambles and/or specifications shall take precedence over the provisions of the General Preambles.			
The contractor's prices for all items throughout these bills of quantities shall take account of and include where applicable for all of the obligations, requirements and specifications given in the General Preambles and in any supplementary preambles and/or specifications.			
Prior to pricing the principal contractor must familiarize him/herself with the Occupational Health and Safety Act No. 85 Of 1993, Construction Regulations 2014, other relevant Regulations and Standards as well as project specific Health & Safety specifications.			
The items in this Bill do not contain quantities hence the Contractor must insert his own quantities based on his individual requirements to comply with the Health and Safety obligations and demands of the Occupational Health and Safety Act No. 85 of 1993, Construction Regulations 2014, other relevant Regulations and Standards as well as project specific Health & Safety Specifications.			
The costs included herein must incorporate Community Liaison Officer (CLO).			
Carried to Collection			R
Section No. 1 PRELIMINARIES Bill No. 2 HEALTH AND SAFETY			

<u>OCCUPATIONAL HEALTH AND SAFETY</u>					
<u>General:</u>					
1	Preparation of Contractor's site specific Health and Safety Plan.		Item		
2	Submission of the Health and Safety File.		Item		
3	Principal Contractor's initial obligations in respect of the OHS Act and Construction Regulations.		Item		
4	Principal Contractor's time related obligations in respect of the OHS Act and Construction Regulations for the entire construction period.		Item		
5	Provision of full time Health and Safety Officer for the entire construction period.		Item		
6	Induction training of all personnel.	No			
7	Provision of first aid boxes.	No			
8	SANS approved weld mesh type temporary barrier fencing 1,8m high covered with a net fixed to and including 100mm diameter gum poles set securely min 300mm deep in ground at max 3m spacing including excavation, backfilling, etc	m			
9	Extra over mesh fence for pedestrian gate size 1.8 x 1,8m high.	No			
<u>Provision for Personal Protective Equipment and Protective Clothing:</u>					
10	Reflective vests.	No			
11	Hard hats.	No			
12	Protective foot wear.	No			
13	Ear Plugs.	No			
14	Dust Masks.	No			
Carried to Collection					
Section No. 1 PRELIMINARIES Bill No. 2 HEALTH AND SAFETY				R	

[illegible]

[illegible]

Item No		Quantity	Rate	Amount
	<u>SECTION NO.2</u>			
	<u>BILL NO.1</u>			
	<u>SUNDRY BUILDERS WORK - ALL TRADES</u>			
	<u>Quantity Split:</u>			
	Note that the total quantity per each item is split into the various buildings and appears below each description as follows:			
	<u>ALTERATIONS</u>			
	<u>REMOVAL OF EXISTING WORK</u>			
	<u>Breaking up and removing mass concrete</u>			
1	85mm Thick surface bed	m2	20	
	<u>Taking out and removing piping, sanitary fittings, etc including disconnecting piping from fittings and preparing pipes for new fittings (e/m) making good floor and wall finishes (making good good and wall finishes elsewhere)</u>			
2	50mm Waste pipe	m	5	
3	Remove VIP 200 Pit pedestal and prepare surface to receive new VIP 450 pedestal (VIP pedestal elsewhere).	No	3	
	<u>IRONMONGERY</u>			
	<u>BATHROOM FITTINGS</u>			
	<u>Stainless steel bathroom fittings</u>			
4	Free standing She Bin; manufactured from Grade 304 1,2/1,5mm Stainless Steel, satin finished with surface treatment. The container to have an approximately 20 litre capacity.	No	8	
	Carried to Collection			
	Section No. 2			
	ALTERATIONS			
	Bill No. 1			
	ALTERATIONS			

PLUMBING AND DRAINAGE
(PROVISIONAL)

MODEL PREAMBLES

The tenderer is referred to the "Model Preambles for Trades 2008" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates

SANITARY FITTINGS

Rust and corrosion resistant, UV-resistant polyethylene pedestals, urinals, basins, etc. Product and colour to Principal Agent's approval:

5	VIP 450 Pit pedestal complete with integral flap four times plugged to floor with and including 6 x 75mm masonry anchors.	No	3
---	---	----	---

SANITARY PLUMBING

PVC waste or vent pipes and fittings:

6	50mm waste pipe	m	4
	<u>Extra for:</u>		
7	50mm Bend	No	3
8	50mm Access bend	No	2

Carried to Collection

R

Section No. 2
ALTERATIONS
Bill No. 1
ALTERATIONS

Item No	Quantity	Rate	Amount
<u>SECTION NO.3</u>			
<u>BILL NO.1</u>			
<u>BARRIER WALLS</u>			
<u>EARTHWORKS</u>			
For preambles see "Model Preambles for Trades (2008 Edition)" and Supplementary preambles as specified in the Trades as well as Engineering Specifications attached to these documents.			
<u>EXCAVATIONS</u>			
<u>Excavation in earth not exceeding 2m deep</u>			
1	Trenches	m3	40
<u>Extra over trench and hole excavations in earth for excavation in</u>			
2	Soft rock	m3	3
3	Hard rock	m3	7
<u>Extra over all excavations for carting away</u>			
4	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the contractor	m3	27
<u>Risk of collapse of excavations</u>			
5	Sides of trench and hole excavations not exceeding 1,5m deep	m2	132
Carried to Collection			R
Section No. 3 EXTERNAL WORKS Bill No. 1 BARRIER WALL			

[illegible]

	<u>Weedkiller mixed in accordance to supplier's specifications</u>		
13	To bottoms and sides of trenches etc	m2	198
	<u>CONCRETE, FORMWORK & REINFORCEMENT</u>		
	<u>UNREINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES</u>		
	<u>30MPa/19mm concrete</u>		
14	Strip footings	m3	17
	<u>MASONRY</u>		
	<u>Brickwork of NFP bricks in class II mortar</u>		
15	One brick walls in foundations	m2	62
16	One brick wall	m2	29
	<u>BRICKWORK SUNDRIES</u>		
	<u>Brickwork reinforcement</u>		
17	150mm Brick reinforcement built in horizontally in foundations	m	331
18	150mm Wide reinforcement built in horizontally	m	331
	<u>FACE BRICKWORK</u>		
	<u>Face brick, size 222 x 106 x 73mm, manufactured in accordance with SANS 227:2007, bedded and jointed in Class II mortar and pointed with flush vertical and flush horizontal joints, suitable for exposure zones 1-2. (PC Amount R6 000-00/thousand Vat excl supplied and delivered to site)</u>		
19	Extra over brickwork for face brickwork	m2	57
	Carried to Collection		
	Section No. 3 EXTERNAL WORKS Bill No. 1 BARRIER WALL		

R

Brick-on-edge header course copings, sills, etc of clay face brick, size 222 x 106 x 73mm, bedded and jointed in Class II mortar and pointed with recessed vertical and recessed horizontal joints, suitable for exposure zone 1-2 (PC Amount R6 000-00/thousand Vat excl supplied and delivered to site)

20	Coping on top of one and a half brick wall	m	110
----	--	---	-----

Carried to Collection

R

Section No. 3
EXTERNAL WORKS
Bill No. 1
BARRIER WALL

Item No		Quantity	Rate	Amount
	<u>SECTION NO.3</u>			
	<u>BILL NO.2</u>			
	<u>V-DRAINS</u>			
	<u>STORMWATER APRONS</u>			
	<u>Excavation not exceeding 2m deep</u>			
1	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	23	
	<u>Extra over all excavations for loading, carting and dumping surplus material (no allowance made for increase in bulk)</u>			
2	Offsite to a dumping site to be found by contractor	m3	23	
	<u>Compaction of surfaces</u>			
3	G7 Base course material compacted to 97% Mod AASHTO density	m3	14	
4	Over site of selected subgrade G5 material in accordance with SABS 1200DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density	m3	5	
	<u>Compaction of surfaces</u>			
5	Compaction of ground surface under floors etc including scarifying for a depth of 100mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density	m2	175	
	Carried to Collection			R
	Section No. 3			
	EXTERNAL WORKS			
	Bill No. 2			
	V-DRAINS			

<u>Prescribed density tests on filling</u>				
6	In-situ dry "density" test	No	20	
<u>Reinforced 30MPa/19mm concrete</u>				
7	Surface beds cast in panels on waterproofing.	m3	23	
8	Edge Thickening	m3	5	
<u>Finishing top surfaces of concrete smooth with a wood float</u>				
9	Surface beds, slabs, etc to falls and currents	m2	175	
<u>Test Blocks;</u>				
10	Making and testing a set of three 150 x 150 x 150mm concrete strength test cube (Provisional)	No	18	
<u>Expansion joints with Bitumen impregnated softboard between vertical concrete or brick surfaces</u>				
11	12mm Joints not exceeding 300mm high	m	175	
<u>Two-part grey polysulphide sealing compound including backing cord, bond breaker, primer, etc</u>				
12	10 x 12mm In movement joints in floors or walls including raking out expansion joint filler as necessary	m	175	
<u>Fabric Reinforcement</u>				
13	REF. 395 fabric reinforcement in concrete surface beds, slabs, etc.	m2	175	
Carried to Collection				
Section No. 3 EXTERNAL WORKS Bill No. 2 V-DRAINS				R

Waterproofing under surface beds

14	350 Micron USB orange Polythylene dampproof membrane in accordance with SABS 952 Type C laid on sand bed(elsewhere measured)	m2	175
----	--	----	-----

Taps

15	Stand taps including excavation and plumbing etc.	No	2
----	---	----	---

Carried to Collection

Section No. 3
EXTERNAL WORKS
Bill No. 2
V-DRAINS

R

[illegible]

Item No		Quantity	Rate	Amount
	<u>SECTION NO.3</u>			
	<u>BILL NO.3</u>			
	<u>APRONS AROUND BUILDINGS</u>			
	For preambles see "Model Preambles for Trades (2008 Edition)" and Supplementary preambles as specified in the Trades			
	<u>EARTHWORKS</u>			
	<u>Excavation not exceeding 2m deep</u>			
1	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	25	
	<u>Extra over all excavations for loading, carting and dumping surplus material (no allowance made for increase in bulk)</u>			
2	Offsite to a dumping site to be found by contractor	m3	19	
	<u>Compaction of surfaces</u>			
3	G7 Base course material compacted to 97% Mod AASHTO density	m3	19	
4	Over site of selected subgrade G5 material in accordance with SABS 1200DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density	m3	9	
	Carried to Collection			
	Section No. 3			
	EXTERNAL WORKS			
	Bill No. 3			
	APRONS ETC.			

	<u>Waterproofing under surface beds</u>				
5	350 Micron USB orange Polythylene dampproof membrane in accordance with SABS 952 Type C laid on sand bed(elsewhere measured)	m2	146		
	<u>Compaction of surfaces</u>				
6	Compaction of ground surface under aprons including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density	m2	146		
	<u>CONCRETE, FORMWORK AND REINFORCEMENT</u>				
	<u>REINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES</u>				
	<u>30MPa/20 mm concrete</u>				
7	Aprons cast in panels to falls	m3	19		
	<u>Grooves, channels, mortices, sinkings, etc. in concrete</u>				
8	Segmental channel with radius 290mm and minimum depth of 100mm on top of concrete, incl. all excavations, cart away etc.	m	122		
	<u>Finishing top surfaces of concrete smooth with a wood float</u>				
9	Aprons to falls	m2	146		
	<u>Smooth formwork to sides</u>				
10	Edges, risers, ends and reveals not exceeding 300mm high or wide	m	122		
	<u>Prescribed density tests on filling</u>				
11	"Mod. AASHTO Density" test	No	12		
	Carried to Collection			R	
	Section No. 3				
	EXTERNAL WORKS				
	Bill No. 3				
	APRONS ETC.				

TEST CUBES

12	Allow for preparing a set of three concrete strength test cubes, each size 150 x 150 x 150mm, sending them to an approved Testing Laboratory for testing and paying all charges in connection therewith. (Provisional)	Sets	12.0
----	--	------	------

REINFORCEMENT (PROVISIONAL)

Fabric reinforcement

13	REF. 395 fabric reinforcement in concrete surface beds, slabs, etc.	m	122
----	---	---	-----

MOVEMENT JOINTS ETC

Expansion joints with Bitumen impregnated softboard between vertical concrete or brick surfaces

14	12mm Joints not exceeding 300mm high	m	122
----	--------------------------------------	---	-----

Two-part grey polysulphide sealing compound including backing cord, bond breaker, primer, etc

15	10 x 12mm In movement joints in floors or walls including raking out expansion joint filler as necessary	m	122
----	--	---	-----

Carried to Collection

R

Section No. 3
EXTERNAL WORKS
Bill No. 3
APRONS ETC.

[illegible]

Item No		Quantity	Rate	Amount
	<u>SECTION NO.3</u>			
	<u>BILL NO.4</u>			
	<u>WALKWAYS</u>			
	<u>EARTHWORKS</u>			
	<u>Site clearance</u>			
1	Digging up and removing rubbish, debris, vegetation, hedges, shrubs and trees not exceeding 200mm girth, bush, etc	m2	126	
	<u>Earthworks</u>			
2	Rip and scarify ground level to a depth of 150mm and consolidate to 93% mod. AASHTO density (minimum CBR 3)	m2	126	
3	Excavate in pickable earth to reduce ground level below paving and set aside for later use	m3	19	
4	Ditto, but cart away excavated material to a dumping place to be found by the contractor (cut to spoil)	m3	13	
5	Extra over excavation for excavation in soft rock	m3	2	
6	Ditto, but in hard rock	m3	2	
	<u>Prescribed density tests on filling</u>			
7	"Mod. AASHTO Density" test	No	12	
	<u>TEST CUBES</u>			
8	Allow for preparing a set of three concrete strength test cubes, each size 150 x 150 x 150mm, sending them to an approved Testing Laboratory for testing and paying all charges in connection therewith. (Provisional)	Sets	18.0	
	Carried to Collection			
	Section No. 3			
	EXTERNAL WORKS			
	Bill No. 4			
	WALKWAYS, ETC.			

	The following to be natural selected gravel layers evenly spread and consolidated in layers and dimensions as specified and on the drawings. All thicknesses to be consolidated thicknesses.				
	Where described as "imported" the gravel to be supplied and carted on by the contractor from an approved borrow pit				
9	125mm Imported G7 material compacted to 95% mod. AASHTO density	m3	13		
10	Weed-killing treatment of surface under paving	m2	88		
	<u>Compaction of surfaces</u>				
11	Compaction of ground surface under aprons including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density	m2	88		
	<u>30 MPa/20 mm concrete</u>				
12	Aprons cast in panels to falls	m3	22		
	<u>Grooves, channels, mortices, sinkings, etc. in concrete</u>				
13	Segmental channel with radius 290mm and minimum depth of 100mm on top of concrete, incl. all excavations, cart away etc.	m	59		
	<u>Finishing top surfaces of concrete smooth with a wood float</u>				
14	Aprons to falls	m2	88		
	<u>Smooth formwork to sides</u>				
15	Edges, risers, ends and reveals not exceeding 300mm high or wide	m	59		
Carried to Collection				R	
Section No. 3 EXTERNAL WORKS Bill No. 4 WALKWAYS, ETC.					

Item No	Quantity	Rate	Amount
<p><u>SECTION NO.3</u></p> <p><u>BILL NO.5</u></p> <p><u>SOIL DRAINAGE</u></p> <p>For Preambles refer to "Department of Public Works: Specification of material and methods to be used - PW371"</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>uPVC pipes and fittings:</u></p> <p>Soil, waste and vent pipes and fittings shall be solvent weld jointed</p> <p><u>uPVC pressure pipes and fittings:</u></p> <p>Pipes for water supply shall be of the class stated</p> <p>Pipes of 40mm diameter and smaller shall be plain ended with solvent welded uPVC loose sockets and fittings</p> <p>Pipes of 50mm diameter and greater shall have sockets and spigots with push in type integral rubber ring joints. Bends shall be uPVC and all other fittings shall be cast iron, all with similar push-in type joints</p> <p><u>Laying, backfilling, bedding, etc. of pipes</u></p> <p>Pipes shall be laid and bedded and trenches shall be carefully backfilled in accordance with manufacturers' instructions</p>			
<p>Carried to Collection</p>			<p>R</p>
<p>Section No. 3 EXTERNAL WORKS Bill No. 5 SOIL DRAINAGE</p>			

Where no manufacturers' instructions exist pipes shall be laid in accordance with clauses 5.1 and 5.2 of each of the following: SABS 1200 L : Medium-pressure pipelines LD : Sewers LE : Stormwater drainage Pipe trenches etc shall be backfilled in accordance with clauses 3, 5.5, 5.6, 5.7 and 7 of SABS 1200 DB : Earthworks (Pipe trenches) Pipes shall be bedded in accordance with clauses 3.1 to 3.4.1, 5.1 to 5.3 and 7 of SABS 1200 LB : Bedding (Pipes). Unless otherwise described bedding of rigid pipes shall be class B bedding

SOIL DRAINAGE

Site clearance

- | | | | |
|---|--|----|-----|
| 1 | Digging up and removing rubbish, debris, vegetation, hedges, shrubs and trees not exceeding 200mm girth, bush, etc | m2 | 428 |
|---|--|----|-----|

Excavation in earth not exceeding 2m deep

- | | | | |
|---|----------|----|-----|
| 2 | Trenches | m3 | 171 |
|---|----------|----|-----|

Extra over all excavations for carting away

- | | | | |
|---|---|----|-----|
| 3 | Surplus material from excavations on site to a dumping site to be located by the contractor | m3 | 171 |
|---|---|----|-----|

Risk of collapse of excavations

- | | | | |
|---|--|----|-----|
| 4 | Sides of trench and hole excavations not exceeding 1,5m deep | m2 | 570 |
| 5 | Ditto, but from ground level to exceeding 1,5m. | m2 | 856 |

Earth filling obtained from the excavations and /or prescribed stock piles on site including compacted to 93% Mod AASHTO density

- | | | | |
|---|-------------------------------------|----|-----|
| 6 | Backfilling to trenches, holes, etc | m3 | 171 |
|---|-------------------------------------|----|-----|

Carried to Collection

R

Section No. 3
EXTERNAL WORKS
Bill No. 5
SOIL DRAINAGE

Earth filling 300 x 300mm section of 19mm thick stone material surrounding 110mm uPVC pipe, supplied by the contractor compacted to 98% Mod AASHTO density

7	19mm Stone	m3	34
---	------------	----	----

Membrane

8	"Geofabric filter blanket wrapped around stone with 150mm side and 300mm end laps, including stitching	m2	285
---	--	----	-----

Keeping excavations free of water

9	Keeping excavations free from mud and all water including subterranean sources.		
---	---	--	--

Item

Compaction of surfaces

10	Compaction of ground surface under floors etc including scarifying for a depth of 100mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density	m2	171
----	---	----	-----

11	160mm uPVC pipe.	m	285
----	------------------	---	-----

12	160mm Tee	No	3
----	-----------	----	---

13	160mm Bend	No	5
----	------------	----	---

THE FOLLOWING IN SOAKAWAY

Site clearance

14	Digging up and removing rubbish, debris, vegetation, hedges, shrubs and trees not exceeding 200mm girth, bush, etc	m2	3
----	--	----	---

Carried to Collection

R

Section No. 3
EXTERNAL WORKS
Bill No. 5
SOIL DRAINAGE

	<u>Excavation in earth not exceeding 2m deep</u>				
15	Holes	m3	2		
	<u>Extra over all excavations for carting away</u>				
16	Surplus material from excavations on site to a dumping site to be located by the contractor	m3	2		
	<u>Risk of collapse of excavations</u>				
17	Sides of trench and hole excavations not exceeding 1,5m deep	m2	2		
	<u>Earth filling obtained from the excavations and /or prescribed stock piles on site including compacted to 93% Mod AASHTO density</u>				
18	Backfilling to holes, etc	m3	0.2		
	<u>Earth filling with stone material supplied by contractor.</u>				
19	Stone(>53mm).	m3	0.1		
	<u>Membrane</u>				
20	"BidimGeotextile or equal approved, lined on all sides including the top and bottom faces	m2	2		
	<u>Keeping excavations free of water</u>				
21	Keeping excavations free from mud and all water including subterranean sources.			Item	
	<u>THE FOLLOWING IN CULVERTS</u>				
	<u>Class 50D concrete pipes:</u>				
22	450mm Diameter concrete pipe laid in trenches not exceeding 1m deep including excavation,backfill,bedding,cartaway and compaction.	m	3		
	Carried to Collection				R
	Section No. 3 EXTERNAL WORKS Bill No. 5 SOIL DRAINAGE				

Item No		Quantity	Rate	Amount
	<u>SECTION NO.3</u>			
	<u>BILL NO.6</u>			
	<u>FENCING</u>			
	<u>EXCAVATIONS</u>			
	<u>SITE CLEARANCE</u>			
	<u>Site clearance</u>			
1	Digging up and removing rubbish, debris, vegetation, hedges, shrubs and trees not exceeding 200mm girth, bush, etc <u>Excavate in pickable material not exceeding 2m deep below reduced or natural ground level and set aside for use as filling (backfilling elsewhere)</u>	m2	54	
	<u>EXCAVATION, FILLING, ETC</u>			
	<u>Excavation in earth not exceeding 2m deep</u>			
2	Holes <u>Extra over trench and hole excavations in earth for excavation in</u>	m3	2	
3	Soft rock	m3	0.1	
4	Hard rock <u>Extra over all excavations for carting away</u>	m3	0.1	
5	Surplus material from excavations on site to a dumping site to be located by the contractor	m3	2	
	Carried to Collection		R	
	Section No. 3 EXTERNAL WORKS Bill No. 6 FENCING ETC.			

	<u>Risk of collapse of excavations</u>			
6	Sides of trench and hole excavations not exceeding 1,5m deep	m2	18	
	<u>Keeping excavations free of water</u>			
7	Keeping excavations free of all water other than subterranean water		Item	
	<u>Prescribed density tests on filling</u>			
8	"Mod. AASHTO Density" test	No	12	
	<u>TEST CUBES</u>			
9	Allow for preparing a set of three concrete strength test cubes, each size 150 x 150 x 150mm, sending them to an approved Testing Laboratory for testing and paying all charges in connection therewith. (Provisional)	Sets	9.0	
	<u>UNREINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES</u>			
	<u>30MPa/19mm concrete</u>			
10	Bases	m3	2	
	<u>FENCING</u>			
	<u>Straining wires,fencing and razor wire</u>			
11	Four strands of 4mm Class'A' galvanised straining wires secured to fencing posts with doubled 2 mm galvanised wire inserted through hole in post and turned a minimum of four turns around straining wire and attached to straining frame at one end with not less than four turns at the other end to straining bolts (elsewhere measured).	m	54	
12	3 Strands of galvanised barbed wire tied to standards, posts and eye bolts	m	54	
	Carried to Collection			
	Section No. 3 EXTERNAL WORKS Bill No. 6 FENCING ETC.			

	<u>50 x 50mm Galvanized welded mesh fencing erected in strict accordance to the manufacturer's instructions</u>				
13	1800mm Galvanised 50 x 50mm welded mesh fixed to posts etc.	m	54		
14	Corner post size 2,4m high x 101mm diameter x 2mm thick with cap and baseplate and finished with silver bitumen primer with 600mm long bottom end fixed in concrete base (e/m)	No	6		
15	Gate post size 2,4m high x 101mm diameter x 2mm thick with cap and baseplate and finished with silver bitumen primer with 600mm long bottom end fixed in concrete base (e/m)	No	2		
16	Immediate post size 2,4m high x 101mm diameter x 2mm thick with cap and base plate and finished with silver bitumen primer with 600mm long bottom end fixed in concrete base (e/m)	No	18		
17	Inclined stay size 2400mm x 48mm x 2mm thick with steel base plate fixed and 600mm long bottom end fixed in concrete base (e/m)	No	44		
18	Pedestrian gate 1000 x 1200mm high (PC Amount R2000-00 each VAT excl. supplied and delivered to site)	No	1		
19	Supply 50 mm "Viro" Padlocks and Keys (or equal approved)	No	1		
Carried to Collection				R	
Section No. 3 EXTERNAL WORKS Bill No. 6 FENCING ETC.					

[illegible]

[illegible]

Item No	Quantity	Rate	Amount
<u>SECTION NO. 4</u>			
<u>BILL No.1</u>			
<u>PROVISIONAL SUMS</u>			
<u>SUPPLEMENTARY PREAMBLES</u>			
Tenderers are advised that no claim in respect of loss of profit or preliminary charges based on the omission of these amounts will be considered and the said amounts will be omitted strictly without any financial compensation payable to the Contractor			
Provisional Sums and Budgetary Allowances contained herein may be omitted or reduced at the Employer's discretion and the Contractor shall be entitled to claim for any loss of profit related thereto.			
<u>BUDGETARY ALLOWANCES</u>			
<u>The following budgetary allowances are for work to be executed at rates in the bills of quantities or to be agreed by Principal Agent.</u>			
1			
Provide the sum of R 22 500.00 for the employment of a Community Liason Officer to be employed by the main Contractor and be paid an allowance of R 7500.00 a month for the duration (3 months)	Item		
2			
Add Mark-up	Item		
3			
Provide the sum of R 105 000.00 for the hire,maintenance and servicing of temporary toilets for educators and learners during the entire construction period.	Item		
4			
Add Mark-up	Item		
5			
Provide the sum of R 50 000.00 for landscaping to be used as directed by the Principal Agent and deducted in a whole or in part if not required.	Item		
Carried to Collection			R
Section No. 4			
PROVISIONAL SUMS			
Bill No. 1			
PROVISIONAL SUMS			

[illegible]

[illegible]