

C2.2. PRICING SCHEDULES / BILLS OF QUANTITIES (BoQ)

Section 2.2 1: PRELIMINARY & GENERAL

DESCRIPTION	UNIT	QTY	RATE	AMOUNT R
Safety file	Sum	1.0		
TOTAL CARRIED TO SUMMARY				

SECTION 2.2.2 LABOUR COMPONENT

ITEM NO	DESCRIPTION	UNIT	QTY	RATE	AMOUNT R
1	<u>INSTALLATION OF CEILINGS</u>				
	Items described as "nailed" shall be deemed to be fixed with hardened steel nails or pins or shot pinned to brickwork or concrete Items described as "plugged" shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 600mm centres,				
1.1	<u>SUSPENDED CEILINGS</u>				
1.1.2	Supply all labour and equipment for installation of 600 x 600 ceiling tiles, including cutting to existing frame	m2	2000		
1.1.3	Circular cutting	no	150		
1.1.4	Opening for sprinkler head	no	950		
1.1.5	Extra over ceiling for opening for 75mm diameter downlighter	no	1000		
1.1.6	Extra over ceiling for opening for 180mm diameter downlighter	no	300		
1.1.7	Vacuum cleaning of ceiling voids	m2	350		
2	<u>FLOOR COVERINGS, WALL LININGS, ETC.</u>				

2.1	FLOOR COVERINGS				
	<u>CARPET TILES</u>				
2.1.1	Removal of old damaged carpet tiles and prepare floor to receive new carpet tiles	m2	2000		
	INSTALLATION OF CARPET TILES				
	<u>Provide labour only to install new carpet tiles</u>				
2.1.2	Supply carpet glue where required	m2	2000		
2.1.3	On floors	m2	2000		
2.1.4	On treads and risers of steps	m2	300		
2.1.5	Circular cutting	m	150		
2.1.6	75mm Skirting	m	1500		
3	<u>PAPERHANGING</u>				
3.1	<u>PAPERHANGING TO EXISTING WALL</u>				
	<u>Preparatory work to previously painted surfaces</u>				
3.1.1	Surfaces shall be thoroughly washed down and allowed to dry completely before paperhanging is commenced. Blistered and peeling paint shall be completely removed, and cracks shall be opened, filled with a suitable filler and finished smooth. All surfaces shall be painted with a single coat of interior quality PVA emulsion paint.	m2	2000		
	<u>INSTALLATION</u>				
3.1.2	Supply all labour and equipment to install wall paper to existing dry walling, including narrow widths	m2	2000		
	TOTAL CARRIED TO SUMMARY				

2.2.3 LABOUR

ITEM NO.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT R
	ALLOW LABOUR ONLY RATES FOR ADDITIONAL ITEMS NOT SPECIFIED.				
	Artisan Carpenter	P/Hour	100		
	Artisan Painter	P/Hour	100		
	Artisan Floor fitter	P/Hour	100		
	General Assistant for moving of furniture and office equipment	P/Hour	100		
	TOTAL CARRIED TO SUMMARY				

SUMMARY OF SECTIONS

DESCRIPTION	AMOUNT R
Section 2.2.1: Preliminary & General	R
SECTION 2.2.2 INSTALLATIONS	R
SECTION 2.2.3 LABOUR	R
SUBTOTAL	R
	R
SUBTOTAL	R
Add 15% VAT	R



BID DESCRIPTION: INSTALLATION OF FINISHES ON AN AS AND WHEN REQUIRED BASIS FOR A PERIOD
OF TWELVE MONTHS IN VARIOUS RAND WATER SITES
BID NUMBER. 10406709

Total Carried Forward to Summary of Schedules	