




	MATLA POWER STATION SCOPE OF WORK	Document Identifier	14593	Rev	7	
		Effective Date	October 2024			
		Review Date	October 2027			

PLANT AREA: Matla Power Station					
TITLE: Scope of Work for supply and delivery of scale and corrosion prevention chemicals for Matla Power Station Ash water systems, Auxiliary Cooling water systems and Main Cooling Water systems on an as and when required basis for a period of 5 years					
REF: MEP - 051318		Reference Rev No:1		MULTIDISCIPLINARY: No	
				Plant Level: All	
COMPILED BY	Name: Maria Majake Contract Manager	Signature: 	Date	2026-02-20	
REVIEWED	Name: Yatish Ramkalawan Water Treatment Plant Chemical Engineer	Signature: 	Date	2026-02-20	
REVIEWED	Name: Themba Kubheka Senior Supervisor Water Treatment Plant	Signature: 	Date	2026-02-20	
REVIEWED	Name: Thabiso Khumalo Ash Water System Engineer	Signature: 	Date	23/02/2026	
REVIEWED	Name: Isaack Maredi Demin Axillary Cooling System Engineer	Signature: 	Date	25/02/2026	
APPROVED	Name: Lindokuhle Ngobese Group Manager	Signature: 	Date	26/02/2026	
REVIEWED	Name: Bontle Mahura Quality Department	Signature: 	Date	26/02/2026	
REVIEWED	Name: Bethuel Moeng Environmental Department	Signature: 	Date	26/02/2026	

Reference No MEP - 051318	Reference Rev No:	Date. 2026/02/17	Page 1 of 29
---------------------------	-------------------	------------------	--------------

Controlled Disclosure

This document is the property of Eskom and is to be controlled and managed accordingly. It is not to be distributed outside Eskom without the written consent of the Eskom Group Manager. It is to be stored in the Eskom Group Manager's secure system. It is to be destroyed when it is no longer required for control purposes. It is to be stored in the Eskom Group Manager's secure system.

	MATLA POWER STATION SCOPE OF WORK	Document Identifier	14593	Rev	7
		Effective Date	October 2024		
		Review Date	October 2027		

ACCEPTED	Name: Nthabiseng Selowa Manager Chemistry	Signature:	Date
----------	--	------------	------

NB: Do not tamper with the template.

GENERAL

- Data books, reviews, reports, and diagrams/drawings shall be submitted to Engineering after the completion of the work Engineering to forward the data books to Quality Department (Document Control)
- All QCP's to be submitted to Engineering and Quality for approval prior to outage/project or maintenance work commencement.

	SCOPE OF WORK DESCRIPTION / ACTIVITY	PROCEDURE, SPECIFICATION, ENG. REQUIREMENTS / DOCUMENTATION	HOLD POINTS, WITNESS, REPORTS	RESPONSIBLE PARTY
1 1	Occupational Health and Safety	<ul style="list-style-type: none"> • Health and safety file should be approved by Safety risk management department prior to any work commences on site • All work is to be done in accordance with OHS Act 85 of 1993, Matla plant procedures and Plant Safety Regulations. (240-150642762). • Matla power station SHEQ induction must be done before access to site can be granted • The contractor should ensure that all employees have acquired the required competency for the task they are performing. 	Eskom to witness	Contractor

Reference No: MEP - 051318	Reference Rev No.	Date: 2026/02/17	Page 2 of 29
----------------------------	-------------------	------------------	--------------

Controlled Disclosure

(Faint, illegible text, likely bleed-through from the reverse side of the page)

	MATLA POWER STATION SCOPE OF WORK	Document Identifier 14593	Rev 7
		Effective Date October 2024	
		Review Date October 2027	

		<ul style="list-style-type: none"> The contractor to ensure compliance to updated legal requirements and other requirements. BUY QUIET: All stakeholders are encouraged to purchase or rent quieter machinery, equipment, and tools to reduce worker noise exposure, contribute towards compliance to OHS noise exposure limits and ultimately reduce the risk of noise induced hearing loss 		
1.2	Environmental Management.	<ul style="list-style-type: none"> All activities listed in the National Environmental Act 107 of 1998, EIA Regulations as amended, must have environmental AUTHORISATION before commencement of work The contractor shall comply with all applicable legal and other requirements The polluter pays principle will be applied. The contractor manager shall ensure compliance with Eskom Matla Environmental procedures to ensure the prevention of pollution (refer OMOP 4090 and 4402) The last payment will be processed based on the status of the last housekeeping check sheet (Annexure C- OMOP 4402) of designated area. EMS file based on ISO14001 will be required 	Eskom to witness	Contractor
1.3	Quality Management	<ul style="list-style-type: none"> The contractor/executioner of work will be responsible for drawing up all QCP documentation and this must be approved by engineering and authorised by the Quality Department before commencing with the work. 	Hold point	Contractor

Reference No: MEP - 051318	Reference Rev No	Date: 2026/02/17	Page 3 of 29
----------------------------	------------------	------------------	--------------

Controlled Disclosure

Faint, illegible text, likely a watermark or bleed-through from the reverse side of the page.

	MATLA POWER STATION SCOPE OF WORK	Document Identifier	14593	Rev	7	
		Effective Date	October 2024			
		Review Date	October 2027			

		<ul style="list-style-type: none"> Contractors/executioner to adhere to QM 58 and OMOP4497 requirements Number of NCR issued can affect your next tendering process. The QCP shall be signed progressively by the Engineer/Supervisor, Eskom QC Inspector, Contractor QC Inspector and/or AIA. No procuring of outage items without the approval of scopes by quality All outage scopes creep and scopes addition should be approved by quality No contractor should be in the possession of scopes for execution without the scopes approved by quality The contractor is subjected to quality auditing at any point in time during execution of scope 		
1.4	Inputs from other departments			
1.5	Commissioning reference			

Reference No. MEP - 051318	Reference Rev No	Date 2026/02/17	Page 4 of 29
----------------------------	------------------	-----------------	--------------

Controlled Disclosure

This document is the property of Eskom. It is to be used for the purpose intended and is not to be distributed, copied, or otherwise used without the written consent of Eskom. It is to be returned to Eskom when no longer required. It is to be destroyed when it is no longer required. It is to be kept confidential and its contents are not to be disclosed to the public or other persons without the written consent of Eskom.

	MATLA POWER STATION SCOPE OF WORK	Document Identifier	14593	Rev	7	
		Effective Date	October 2024			
		Review Date	October 2027			

	SCOPE OF WORK DESCRIPTION / ACTIVITY	PROCEDURE, SPECIFICATION, ENG. REQUIREMENTS / DOCUMENTATION	HOLD POINTS, WITNESS, REPORTS	RESPONSIBLE PARTY
1	SYSTEMS DESCRIPTION			
1.1	<u>SYSTEM INFORMATION</u>			
1.1.1	<u>ASH WATER SYSTEMS</u> REQUIREMENT: SCALE INHIBITOR Scale inhibitors are used in the prevention of CaCO ₃ scale are the polymeric inorganic phosphates. This class of compounds includes the salts of pyrophosphates, tri-polyphosphates and hexametaphosphate. At dosage levels of 1,0 mg.kg ⁻¹ these products inhibit the crystallisation of CaCO ₃ crystallites by suppressing both nucleation and crystal growth The number of pumps and estimated system flow rates where dosing should occur on the suction side of the pumps are as follow Final Cut · 2 X 700m ³ /hr (1016.4ml/month) SWR 2 X 2000m ³ /hr (2904.4ml/month) 3 X 1000m ³ /hr (2178ml/month) Slurry Plant 5 X 480m ³ /hr (1742.40ml/month) Seal Water 2 X 280m ³ /hr (406.56ml/month)			

Reference No. MEP - 051318	Reference Rev No	Date: 2026/02/17	Page 5 of 29
----------------------------	------------------	------------------	--------------

Controlled Disclosure

(Faint, illegible text, likely a watermark or bleed-through from the reverse side of the page)

	MATLA POWER STATION SCOPE OF WORK	Document Identifier	14593	Rev	7
		Effective Date	October 2024		
		Review Date	October 2027		

<p>AWR - 2 X 720m³/hr (500 ml/month)</p> <p>Note: Dosing rates must be based on this volume</p> <p>The dosing infrastructure available for the specified systems are as follow</p> <p>Final Cut 1 x Dosing Tank 3000 Litres 2 x Dosing Pumps</p> <p>SWR 1 x Dosing Tank 3000 Litres 5 x Dosing Pumps</p> <p>AWR 1 x Dosing Tank 2500 Litres 4 x Dosing Pumps</p> <p>Note: All dosing and other monitoring equipment are to be supplied on loan and maintained by the supplier for the duration of the contract if needed</p> <p>The Ash water quality is provided in Appendix A</p>			
---	--	--	--

Reference No. MEP - 051318	Reference Rev No	Date: 2026/02/17	Page 6 of 29
----------------------------	------------------	------------------	--------------

Controlled Disclosure

This document is the property of Eskom and is intended for the use of the recipient only. It is not to be distributed, copied, or otherwise used without the prior written consent of Eskom. If you have received this document in error, please contact the sender immediately. Eskom is not responsible for any loss or damage arising from the use of this document.

	MATLA POWER STATION SCOPE OF WORK	Document Identifier	14593	Rev	7	
		Effective Date	October 2024			
		Review Date	October 2027			

1.1.2	<p>AUXILIARY COOLING WATER SYSTEMS</p> <p>CLOSED SYSTEMS INFORMATION: DEMIN WATER COOLING</p> <p>REQUIREMENT: BIOCIDES AND CORROSION INHIBITOR</p> <p>Closed recirculating systems should have very little water loss and continuously recirculates the same water. The heat absorbed from the heat transfer equipment is dissipated to another heat sink. Because there are no evaporative losses and provided that the system is operated correctly, make-up water is minimal and the mineral content remains essentially constant. However, corrosion by-products can easily accumulate and foul heat transfer equipment.</p> <p>Biocides not compatible with closed systems</p> <p>Dodecylguanidine hydrochloride contributes 3 mg kg⁻¹ to 7 mg.kg⁻¹ chlorine at typical application rates of 25 mg kg⁻¹ to 50 mg kg⁻¹ Carbamates can attack copper alloys and precipitate iron. Carbamates are more applicable to open recirculating cooling water systems Quaternary ammonium salts (Quats) contribute to the chloride concentration of the system. No specific contribution can be listed as a result of the extent of formulations available. Chlorine cannot be applied to close cooling water system (with demineralised water makeup) as result of the chloride contamination Chlorine, however, remains a good biocide</p>			
-------	---	--	--	--

Reference No MEP - 051318	Reference Rev No	Date. 2026/02/17	Page 7 of 29
---------------------------	------------------	------------------	--------------

Controlled Disclosure

This document is the property of Eskom and is controlled and managed in accordance with the Eskom Information Management Policy. It is to be used for the purpose for which it was issued and is not to be distributed outside the Eskom Group of Companies. It is to be destroyed when it is no longer required. Eskom is not responsible for the content of any external links. Eskom is not responsible for the content of any external links.

	MATLA POWER STATION SCOPE OF WORK	Document Identifier 14593	Rev 7
		Effective Date October 2024	
		Review Date October 2027	

<p>for open evaporative systems provided the system pH is within the most effective range for chlorine. But safety issues have limited its use.</p> <p>Corrosion control requires knowledge of the metallurgy of the system, an understanding of the susceptibility of the metals to corrode under the operating conditions encountered, and an understanding of the limitations of the specific corrosion inhibitors applied. Principal economic advantages for the use of corrosion inhibitors in cooling water stem from two sources, namely</p> <ul style="list-style-type: none"> a they reduce the frequency of maintenance and inspection shutdowns, and b they permit more extensive use of iron and carbon or low alloy steels <p>The systems volumes are as follow</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="text-align: left;">Systems</th> <th style="text-align: center;">Volume (m³) approx. volumes</th> <th style="text-align: center;">Number of Units</th> </tr> </thead> <tbody> <tr> <td>Auxiliary Cooling</td> <td style="text-align: center;">30</td> <td style="text-align: center;">6</td> </tr> <tr> <td>Chiller Plant</td> <td style="text-align: center;">1</td> <td style="text-align: center;">6</td> </tr> <tr> <td>Aircon Chiller - Head tank</td> <td style="text-align: center;">10</td> <td style="text-align: center;">1</td> </tr> <tr> <td>Compressor (Slurry Plant)</td> <td style="text-align: center;">1</td> <td style="text-align: center;">1</td> </tr> </tbody> </table>	Systems	Volume (m ³) approx. volumes	Number of Units	Auxiliary Cooling	30	6	Chiller Plant	1	6	Aircon Chiller - Head tank	10	1	Compressor (Slurry Plant)	1	1				
Systems	Volume (m ³) approx. volumes	Number of Units																	
Auxiliary Cooling	30	6																	
Chiller Plant	1	6																	
Aircon Chiller - Head tank	10	1																	
Compressor (Slurry Plant)	1	1																	

Reference No: MEP - 051318	Reference Rev No:	Date: 2026/02/17	Page 8 of 29
----------------------------	-------------------	------------------	--------------

Controlled Disclosure

This document is the property of Eskom and is intended for the use of the recipient only. It is not to be distributed, copied, or otherwise used without the prior written consent of Eskom. If you are not the intended recipient, you should not disseminate, distribute or copy this e-mail. If you have received this e-mail by mistake, please notify the sender immediately by e-mail. You should not disseminate, distribute or copy this e-mail. If you have received this e-mail by mistake, please notify the sender immediately by e-mail. You should not disseminate, distribute or copy this e-mail.

	MATLA POWER STATION SCOPE OF WORK	Document Identifier 14593	Rev 7
		Effective Date October 2024	
		Review Date October 2027	

<p>polymaleates, and their copolymers. Dose rates are in the order of 2,0 mg.kg⁻¹ to 4,0 mg.kg⁻¹. The polymers adsorb on to the CaCO₃ crystal structure, limiting the growth of CaCO₃ and ultimately limiting scale formation. These polymers are more frequently considered dispersants. They retard CaCO₃ scale by maintaining small particles of distorted crystalline material in suspension</p> <p>South system volume = 47 ML North system volume = 47 ML Blowdown volume = 4 ML/D per system (at MCR) Average raw water make-up = 60 ML/D per system (at MCR) CoC (based on K) = 16 Cooling water Temperature range 0 – 45 °C</p> <p>The cooling water is circulated at a maximum flowrate of 14.36 m³/s (South CW system) or 13 m³/s (North CW system), through the condensers and back to the cooling towers. The flowrate is dependent on the number of CW pumps running (max 6 pumps per system), which is dependent on the number of operating units on load.</p> <p><u>The system has the following materials of construction</u></p> <p>Deformed H.T. reinforced concrete (Class A, B & C), Carbon steel, Mild steel, Cast iron, Titanium condenser tubes, Brass condenser tubes, Polygrid splash on South Cooling Towers and flat asbestos-cement sheets on North System</p>				
---	--	--	--	--

Reference No: MEP - 051318	Reference Rev No:	Date 2026/02/17	Page 10 of 29
----------------------------	-------------------	-----------------	---------------

Controlled Disclosure

This document is the property of Eskom and is to be used only for the purpose for which it is issued. It is not to be distributed, copied, reproduced, stored in a retrieval system, or transmitted in any form or by any means, electronic, mechanical, photocopying, recording, or by any information storage and retrieval system, without the prior written permission of Eskom. Eskom does not accept any liability for the accuracy or completeness of the information contained herein.

	MATLA POWER STATION SCOPE OF WORK	Document Identifier	14593	Rev	7	
		Effective Date	October 2024			
		Review Date	October 2027			

	<u>Other chemicals dosed in system:</u> Lime (Calcium hydroxide), Flocculent & Coagulant The chemical constituents of all dosing chemicals will be communicated during contract phase. The Main Cooling Water specifications are included in Appendix C.			
2	DETAILED REQUIREMENTS			
2.1	Supply and delivery of chemicals to scale/corrosion prevention chemicals for all the 3 mentioned systems. The contractor is to supply and maintain their own dosing system on site (Pumps, tanks, pipelines, etc.) where needed			
2.2	Supply and delivery of the best suited biocide for the Auxiliary Cooling Water Systems Biocides to be used as little as possible in the system. Caution must be taken against excessive foaming at the air extraction zones An anti-foam chemical should be available and dosed in order to prevent excessive foaming.	Biocide efficacy test of dosing for the biocides should be provided, an acceptable kill rate will be 99.99% of total planktonic bacteria within the system, after optimal time for the biocide used. The minimum efficacy is 99.99% kill at the optimal kill time for the biocide. These results must be reported to the PS regularly Bacterial counts to be constant / decreasing – (to be done on a monthly basis) Visual inspections: algae growth to be minimized – (to be done on a two weekly basis and a report generated) Legionella counts 10 ¹ - 10 ² / Litre – (to be done quarterly).		

Reference No: MEP - 051318	Reference Rev No:	Date 2026/02/17	Page 11 of 29
----------------------------	-------------------	-----------------	---------------

Controlled Disclosure

[Faint, illegible text, likely a watermark or bleed-through from the reverse side of the page]

	MATLA POWER STATION SCOPE OF WORK	Document Identifier	14593	Rev	7	
		Effective Date	October 2024			
		Review Date	October 2027			

2.3	<p>The supplier should recommend and install appropriate online monitoring systems, where applicable, for the monitoring of scale formation (main cooling water system and open auxiliary cooling water system), corrosion rate (closed auxiliary cooling water system) and monitoring of sessile bacteria proliferation and biofilm formation (open and closed auxiliary cooling water systems) The online monitoring systems will provide valuable feedback on the effectiveness of the suppliers proposed treatment regimes.</p>			
2.4	<p>Water samples from the station should be taken on all the mentioned systems and laboratory tests should be conducted to establish which chemical (based on the active ingredient) is most suitable for Matla Power Station water system type/chemistry and a feedback report must be generated and included in the enquiry document The chemicals must be effective to improve and / or keep system in stable condition complying with the applicable Eskom Standard's specification values as per the Appendix's</p>	<p>The tender documents must contain an analysis of the existing chemistry conditions of the systems with a predictive dosing model which will demonstrate the best suited chemical and optimal dosing rate in order to prevent scale formation/prevent corrosion and prevent microbiological fouling on the mentioned systems The result must indicate the proposed chemical/s together with the active ingredient and the concentration of the active ingredient. The recommended dosing rate, concentration to be dosed and the treatment price as Rand per Mega Litre (R/ML) of ash water treated Additionally, a method in which the dosage will be monitored and controlled should be outlined as well as a method by which residual chemical in the system can be determined</p>		

Reference No. MEP - 051318	Reference Rev No	Date. 2026/02/17	Page 12 of 29
----------------------------	------------------	------------------	---------------

Controlled Disclosure

This document is the property of Eskom and is intended for the use of the recipient only. It is not to be distributed, copied, or otherwise used without the prior written consent of Eskom. If you have received this document in error, please contact the sender immediately and delete this document from your system. Eskom is not responsible for any loss or damage arising from the use of this document.

	MATLA POWER STATION SCOPE OF WORK	Document Identifier 14593	Rev 7
		Effective Date October 2024	
		Review Date October 2027	

2.5	The supplier should submit a report outlining the optimal treatment regime for all the mentioned systems to meet the specified scaling limits, corrosion prevention limits and bio-control limits	The proposed chemicals should not cause any damage or blockages in any parts of the water systems and should be compatible with the chemicals already dosed in these systems. The supplier will ensure that the chemicals supplied do not affect the materials of construction for any of the mentioned systems		
2.6	The supplier service must compile a monthly report on the effectiveness of the proposed dosing regimes. Changes to the dosing regimes should be implemented during seasonal changes or in any event where the water quality of a system has changed. The supplier should sample the water from the different systems on a frequent basis to determine if there are any changes to the water quality	The monthly reports should include the following <ul style="list-style-type: none"> • Quantity of chemicals used • Concentration dosed (ppm) • R/ML for the month • Performance Results • Comments on deviations if any 		
2.7	The supplier should provide a detailed 16 points Material Safety Data Sheet (MSDS) with a South African contact number for each chemical to be used. The MSDS must state the main active ingredient and the concentration thereof.	All chemical deliveries to Matla must be accompanied by a Certificate of Analysis (COA) for each chemical together with a 16-point MDSD/PDS for each chemical		
2.8	All chemical containers shall have an identifying label that includes as a minimum the substance name, shelf life or expiry date, appropriate hazard warnings and identification of manufacturer or distributor			

Reference No MEP - 051318	Reference Rev No:	Date 2026/02/17	Page 13 of 29
---------------------------	-------------------	-----------------	---------------

Controlled Disclosure

This document is the property of Eskom and is controlled and its disclosure is restricted to the intended recipients only. It is not to be distributed outside the intended recipients. If you are not an intended recipient, you should not disseminate, distribute or copy this e-mail. If you have received this e-mail by mistake, please notify the sender immediately by e-mail. This e-mail and any files transmitted with it are confidential and intended only for the individual named. If you are not the named addressee you should not disseminate, distribute or copy this e-mail. Please notify the sender immediately by e-mail if you have received this e-mail by mistake and delete this e-mail from your system. If you are not the named addressee you should not disseminate, distribute or copy this e-mail. Please notify the sender immediately by e-mail if you have received this e-mail by mistake and delete this e-mail from your system. If you are not the named addressee you should not disseminate, distribute or copy this e-mail. Please notify the sender immediately by e-mail if you have received this e-mail by mistake and delete this e-mail from your system.

	MATLA POWER STATION SCOPE OF WORK	Document Identifier 14593	Rev 7
		Effective Date October 2024	
		Review Date October 2027	

2.9	Chemicals to be delivered in Original Equipment Manufacturer (OEM) containers, no repackaging allowed			
2.10	All storage tanks of chemicals must be labelled with the name, use and safety information of the chemical. Contact names must be available in the event of a chemical spill			
2.11	The supplier must conduct periodic site visits to ensure that the specified chemicals are being dosed optimally, and the desired treatment outcome is achieved. The supplier is expected to give technical backup on the products and their correct application.			
2.12	The supplier must carry out plant inspections during outage opportunities and compile a report with the effectiveness of chemicals being dosed as well as suggestions/ recommendations.			
2.13	Lead time delivery of chemicals must be within reasonable time period (three days maximum)			
2.14	The supplier should mention all previous work conducted with similar SOW requirements and plant equipment as per Matla Power Station.			
2.15	A company and / or supplier's audit to be done quarterly on all installations and / or dosing systems covering all aspects of safety			

Reference No. MEP - 051318	Reference Rev No	Date: 2026/02/17	Page 14 of 29
----------------------------	------------------	------------------	---------------

Controlled Disclosure

This document is the property of Eskom and is controlled information. It is to be used only for the purposes for which it was issued. It is not to be distributed outside the Eskom group of companies without the prior written approval of Eskom. If you are not an intended recipient, you should not disseminate, distribute or copy this document. If you have received this document by mistake, please notify the sender immediately by e-mail. Eskom is not liable for any loss or damage arising from the use of this document.

	MATLA POWER STATION SCOPE OF WORK	Document Identifier	14593	Rev	7	
		Effective Date	October 2024			
		Review Date	October 2027			

2.16	and operational procedural compliance and a report of all findings to be submitted to Matla Power Station. The Contractor must provide training / awareness to Matla Power Station's personnel if needed			
------	---	--	--	--

Reference No: MEP - 051318	Reference Rev No:	Date: 2026/02/17	Page 15 of 29
----------------------------	-------------------	------------------	---------------

Controlled Disclosure

This document is the property of Eskom and is to be used only for the purposes for which it is issued. It is not to be distributed, copied, or otherwise used without the prior written consent of Eskom. If you are not an intended recipient, you should not disseminate, distribute or take any action in reliance on the contents of this information. If you have received this document in error, please notify the sender immediately by e-mail at eskomp@eskom.co.za or by telephone at 011 630 0100.

	MATLA POWER STATION SCOPE OF WORK	Document Identifier	14593	Rev	7	
		Effective Date	October 2024			
		Review Date	October 2027			

BILL OF MATERIAL

	Full description of Material/Spares/Equipment	Specifications of Matenal/Spares/Equipment	Stock No	Part Number	Required Quantity
1	1 x scale inhibitor chemical for the mentioned Ash Water Systems				As per supplier specifications
2	1 x corrosion inhibitor chemical for the mentioned Closed Demin Water Auxiliary Cooling Water Systems				As per supplier specifications
3	1 x scale inhibitor chemical for the mentioned Open Potable Water Auxiliary Cooling Water Systems				As per supplier specifications
4	1 x Biocide chemical for the mentioned Closed Demin Water Auxiliary Cooling Water Systems				As per supplier specifications
5	1 x Biocide chemical for the mentioned Open Potable Water Auxiliary Cooling Water Systems				As per supplier specifications
6	1 x anti-foam chemical to prevent foaming in the Auxiliary Cooling Water Systems after biocide dosing				As per supplier specifications
7	1 x crystal modifier chemical for the mentioned Main Cooling Water Systems				As per supplier specifications
8	All required dosing equipment (tanks, pumps, piping, valves, monitoring equipment)				As per supplier specifications
9	Online monitoring systems, where applicable				As per supplier specifications

Reference No MEP - 051318	Reference Rev No	Date. 2026/02/17	Page 16 of 29
---------------------------	------------------	------------------	---------------

Controlled Disclosure

(This document is the property of Eskom. It is to be used for the purpose for which it is issued and is not to be distributed, copied, or otherwise used without the written consent of Eskom. It is to be returned to Eskom when it is no longer required.)

	MATLA POWER STATION SCOPE OF WORK	Document Identifier	14593	Rev	7	
		Effective Date	October 2024			
		Review Date	October 2027			

APPENDIX A: ASH WATER SYSTEMS

Ash water quality based on 5 years 95th percentile data.

Final out Chemical Parameter	Value	Unit
Aluminium (Al)	0.092	ppm
Ammonium (NH4) as N	0.047	ppm
Antimony (Sb)	<0.005	ppm
Arsenic (As)	<1	ppb
Barium (Ba)	0.079	ppb
Beryllium (Be)	<0.005	ppm
Boron (B)	2.182	ppm
Cadmium (Cd)	<0.005	ppm
CaH	1005.2	ppm
Calcium (Ca)	359	ppm
Chloride (Cl)	209.3	ppm
Chromium (Cr)	0.020	ppm
Cobalt (Co)	<0.005	ppm
Copper (Cu)	<0.005	ppm
Cyanide (CN)	<0.025	ppm
F coli	36	CFU/100 ml
Electric conductivity (EC) @ 25 degrees C	3199.0	uS/cm
EMA	2465.5	ppm
Faecal coliform	39	CFU/100 ml
Fluoride (F)	0.596	ppm
Hexavalent chromium (Cr6+)	0.008	ppm
Iron (Fe)	0.044	ppm

Reference No: MEP - 051318	Reference Rev No:	Date 2026/02/17	Page 17 of 29
----------------------------	-------------------	-----------------	---------------

Controlled Disclosure

This document is the property of Eskom and is intended for the use of the person to whom it is issued. It is not to be distributed, copied, or otherwise used without the prior written consent of Eskom. If you are not the intended recipient, you should not disseminate, distribute or take any action in reliance on the contents of this information. If you have received this document by mistake, please notify us immediately by e-mail at information@eskom.co.za or by telephone at 011 630 0100. Eskom is not liable for any loss or damage arising from the use of this information.

	MATLA POWER STATION SCOPE OF WORK	Document Identifier	14593	Rev	7	
		Effective Date	October 2024			
		Review Date	October 2027			

Lead (Pb)	<0.01	ppm
Magnesium (Mg)	49.1	ppm
M-alkalinity	233.4	ppm
Manganese (Mn)	0.169	ppm
Mercury (Hg)	<1	ppb
MgH	673.5	ppm
Molybdenum (Mo)	0.154	ppm
Nickel (Ni)	<0.005	ppm
Nitrate (NO3) as N	0.242	ppm
Orthophosphate (PO4) as P	<0.005	ppm
P-alkalinity	6.8	ppm
pH @ 25 degrees C	8.8	
Phosphorus (P)	<0.005	ppm
Potassium (K)	71.0	ppm
Selenium (Se)	<2	ppb
Silica (SiO2)	15.3	ppm
Silicon (Si)	3.450	ppm
Sodium (Na)	346.2	ppm
Strontium (Sr)	7.210	ppm
Sulphate (SO4)	2209.8	ppm
Total Chromium (Cr)	0.019	ppm
Total coliform	45	CFU/100 ml
Total Dissolved solids @ 180 degrees C	1462.0	ppm
Total Hardness	1541.5	ppm
Turbidity	3.6	NTU
Vanadium (V)	0.073	ppm
Zinc	<0.005	ppm

Reference No: MEP - 051318	Reference Rev No	Date: 2026/02/17	Page 18 of 29
----------------------------	------------------	------------------	---------------

Controlled Disclosure

Faint, illegible text, possibly a signature or stamp.

	MATLA POWER STATION SCOPE OF WORK	Document Identifier	14593	Rev	7	
		Effective Date	October 2024			
		Review Date	October 2027			

APPENDIX B: AUXILIARY COOLING WATER SYSTEMS

Cooling water specification for closed systems with demineralised water make-up as per Eskom Chemistry Standard for Auxiliary Cooling Water 240-106192541 Revision 1

Parameter	Units	Limit or range
Turbidity	NTU	<1
pH		In accordance with correct chemical additives concentration
Conductivity	$\mu\text{S.cm}^{-1}$	In accordance with correct chemical additives concentration
Inhibitor(s)*	mg kg^{-1}	In accordance with vendor and or Eskom recommendation
Copper	$\mu\text{g.kg}^{-1}$	< 50
Iron	$\mu\text{g.kg}^{-1}$	< 200
Oil	mg kg^{-1}	< 5
System water losses	% loss	< 2 % per week
Total hardness as CaCO_3	mg kg^{-1}	< 5
Dissolved oxygen	mg kg^{-1}	In accordance with inhibitor requirements

Reference No: MEP - 051318	Reference Rev No	Date: 2026/02/17	Page 19 of 29
----------------------------	------------------	------------------	---------------

Controlled Disclosure

This document is the property of Eskom and is controlled and disseminated in accordance with Eskom's Information Management Policy. It is intended for the use of the recipient only and is not to be distributed outside the intended audience. It is to be stored, controlled and disposed of in accordance with Eskom's Information Management Policy. It is to be destroyed when it is no longer required for the intended purpose.

	MATLA POWER STATION SCOPE OF WORK	Document Identifier	14593	Rev	7
		Effective Date	October 2024		
		Review Date	October 2027		

Planktonic bacteriological counts for closed systems with demineralised water make-up as per Eskom Chemistry Standard for

Auxiliary Cooling Water 240-106192541 Revision 1

Parameter	Units	Limit or range
Total aerobic bacteria	CFUs/ml	<10 000
Total anaerobic bacteria	CFUs/ml	<1000
H ₂ S producers	CFUs/ml	<10

Reference No. MEP - 051318	Reference Rev No:	Date 2026/02/17	Page 20 of 29
----------------------------	-------------------	-----------------	---------------

Controlled Disclosure

This document is the property of Eskom and is to be used only for the purpose for which it is issued. It is not to be distributed, copied, or otherwise used without the written permission of Eskom. It is to be kept confidential and its use is restricted to the specific project for which it is issued. (Page 5 of 5)

	MATLA POWER STATION SCOPE OF WORK	Document Identifier	14593	Rev	7	
		Effective Date	October 2024			
		Review Date	October 2027			

Cooling water specification for open systems with potable water make-up as per Eskom Chemistry Standard for Auxiliary Cooling Water 240-106192541 Revision 1

Turbidity	NTU	< 15
pH		8.3 to 8.9
Conductivity	$\mu S\ cm^{-1}$	< 4500
Corrosion inhibitors	$mg\ kg^{-1}$	In accordance with vendor and/or Eskom technical specifications
Sodium	$mg\ kg^{-1}$	< 500
Potassium	$mg\ kg^{-1}$	< 500
Cl	$mg\ kg^{-1}$	< 5 / Negotiable
Water losses	% loss	In accordance with evaporation and blow down requirements
M Alkalinity	$mg\ kg^{-1}$	50 to 150
Total hardness as $CaCO_3$	$mg\ kg^{-1}$	< 500
Calcium carbonate precipitation potential Using Stroz 4	$mg\ kg^{-1}$	< 30 With scale control program < 5 Without scale control program
Copper	$mg\ kg^{-1}$	< 500
Iron	$mg\ kg^{-1}$	< 500
Chlorides	$mg\ kg^{-1}$	< 400
Sulphates	$mg\ kg^{-1}$	Poor quality concrete – Stations < 1000 $mg\ kg^{-1}$ if Na^+ < 250 $mg\ kg^{-1}$ < 750 $mg\ kg^{-1}$ if Na^+ = 250 $mg\ kg^{-1}$ High quality concrete – Stations < 1500 $mg\ kg^{-1}$ if Na^+ < 500 $mg\ kg^{-1}$ < 1000 $mg\ kg^{-1}$ if Na^+ = 500 $mg\ kg^{-1}$ Note Mg^{2+} to be < 150 $mg\ kg^{-1}$ as $CaCO_3$
Magnesium	Mg (as $CaCO_3$) - SiO_2	Mg (as $CaCO_3$) - SiO_2 < 25 000
Silica	As SiO_2	< 150 $mg\ kg^{-1}$ as SiO_2 , while also taking cognisance of Mg + SiO_2 limitation

Reference No: MEP - 051318	Reference Rev No	Date: 2026/02/17	Page 21 of 29
----------------------------	------------------	------------------	---------------

Controlled Disclosure

This document is the property of Eskom and is intended for use only by the person to whom it is issued. It is not to be distributed, copied, or otherwise used without the prior written consent of Eskom. If you are not the intended recipient, you should not disseminate, distribute or take any action in reliance on the contents of this information. If you have received this document in error, please notify the sender immediately by e-mail. Eskom is not responsible for any actions taken in reliance on the contents of this information.

	MATLA POWER STATION SCOPE OF WORK	Document Identifier	14593	Rev	7
		Effective Date	October 2024		
		Review Date	October 2027		

The target/specification of the scaling rate is 0.01mg/dm²/day.

Bacteriological counts for open evaporative systems with potable and raw water makeup as per Eskom Chemistry Standard for Auxiliary Cooling Water 240-106192541 Revision 1

Parameter	Units	Limit or range
Total aerobic bacteria	CFUs per ml	< 10 000
Total anaerobic bacteria	CFUs per ml	< 1000
H ₂ S producers	CFUs per ml	< 10
Legionella	CFU per litre	<100

Reference No. MEP - 051318	Reference Rev No.	Date 2026/02/17	Page 22 of 29
----------------------------	-------------------	-----------------	---------------

Controlled Disclosure

[Faint, illegible text, likely bleed-through from the reverse side of the page]

	MATLA POWER STATION SCOPE OF WORK	Document Identifier	14593	Rev	7
		Effective Date	October 2024		
		Review Date	October 2027		

APPENDIX C: MAIN COOLING WATER SYSTEM

Raw water quality (95th percentile data from Jan 2023 – Feb 2021)

Parameter	Unit	Value
Turbidity	NTU	28
pH		8.09
Conductivity	uS/cm	255
M-alkalinity	mg/kg CaCO ₃	83
Calcium hardness	mg/kg CaCO ₃	44
Magnesium hardness	mg/kg CaCO ₃	50
Total hardness	mg/kg CaCO ₃	94
Sodium, Na	mg/kg	17
Potassium, K	mg/kg	3.94
Reactive Silica, SiO ₂	mg/kg	23
Chloride, Cl	mg/kg	14
Sulphate, SO ₄	mg/kg	42
EMA		60
Organic Acid, OA		
Langelier Index, LI		-0.17
Total Organic Carbon (TOC)	mg/kg	8.09

Reference No: MEP - 051318	Reference Rev No	Date: 2026/02/17	Page 23 of 29
----------------------------	------------------	------------------	---------------

Controlled Disclosure

This document is the property of Eskom and contains confidential information. It is to be used only for the purpose for which it is issued. It is not to be distributed, copied, or otherwise used without the prior written consent of Eskom. If you are not an intended recipient, please contact the sender immediately. Eskom is not responsible for any loss or damage arising from the use of this document.

	MATLA POWER STATION SCOPE OF WORK	Document Identifier	14593	Rev	7	
		Effective Date	October 2024			
		Review Date	October 2027			

Cooling Water quality (95th percentile data from Jan 2023 – December 2025)

Parameter	Unit	Value	South CW	North CW
CW Turb	NTU	<100	58	54
CW pH		8.1 - 8.6	8.70	8.70
CW K25	uS/cm	<4000	2335	2233
CW P-alk	mg/kg	<7.5	14.2	12.3
CW M-alk	mg/kg	120 - 160	166	154
CW CaH	mg/kg	200 - 500	268	246
CW MgH	mg/kg		220	205
CW TH	mg/kg		488	452
CW Na	mg/kg	<500	322	339
CW K	mg/kg		76.1	78.9
CW Cl	mg/kg	<400	214	229
CW SiO2	mg/kg	<150	46	46
CW SO4	mg/kg	<1000	695	678
CW Mg*SiO2		<25 000	8829	9771
CW CCPP		10 - 45	50.3	45.0

Reference No: MEP - 051318	Reference Rev No	Date: 2026/02/17	Page 24 of 29
----------------------------	------------------	------------------	---------------

Controlled Disclosure

(Faint, illegible text, likely bleed-through from the reverse side of the page)

	MATLA POWER STATION SCOPE OF WORK	Document Identifier	14593	Rev	7
		Effective Date	October 2024		
		Review Date	October 2027		

Cooling water specification as per Eskom Chemistry and Microbiology Standard for Cooling Water 240-55864767 Revision 4

Parameter	Unit	Spec	Target
pH @ 25°C		8.1 – 8.6	8.1 – 8.5
Conductivity	µS/cm	< 4000	2800 – 3000
Turbidity	NTU	< 100	< 50
P-alkalinity	mg/kg CaCO ₃	< 7.5	< 5
M-alkalinity (with crystal modifier)	mg/kg CaCO ₃	120 – 160	120 – 160 *
Calcium hardness	mg/kg CaCO ₃	200 – 500	200 – 400
Permanent hardness	mg/kg as CaCO ₃	< 400	
PO ₄ ³⁻	mg/kg as P	< 0.5	< 0.5
NO ₃ ⁻	mg/kg as N	1	< 1
SO ₄ ²⁻	mg/kg CaCO ₃	< 1000 if Na ⁺ > 250 < 750 if Na ⁺ < 250	< 1000 < 750
Cl	mg/kg	< 400	< 400
Sodium	mg/kg as Na	< 500	
Reactive Silica	Mg/kg as SiO ₂	< 150	
Mg X SiO ₂	mg/kg	< 25000	< 23000
OA	mg/kg	< 20	
COD	mg/kg	< 200	

Reference No: MEP - 051318	Reference Rev No	Date: 2026/02/17	Page 25 of 29
----------------------------	------------------	------------------	---------------

Controlled Disclosure

[Faint, illegible text, likely bleed-through from the reverse side of the page]

	MATLA POWER STATION SCOPE OF WORK	Document Identifier	14593	Rev	7
		Effective Date	October 2024		
		Review Date	October 2027		

Ammonia	mg/kg as NH ₄	< 40	
Scaling Potential Calcium Carbonate precipitation potential (CCPP) at 38°C	mg/kg as CaCO ₃ with a crystal modifier	10 - 45	<40

* with the use of a crystal modifier

Reference No MEP - 051318	Reference Rev No	Date 2026/02/17	Page 26 of 29
---------------------------	------------------	-----------------	---------------

Controlled Disclosure

This document is the property of Eskom and is to be used only for the purpose intended. It is to be kept confidential and its disclosure to any other person without the written authority of Eskom is prohibited. It is to be destroyed when it is no longer required for the purpose intended.

	MATLA POWER STATION SCOPE OF WORK	Document Identifier	14593	Rev	7
		Effective Date	October 2024		
		Review Date	October 2027		

SCOPE COMPILATION REFERENCES				
SOURCE & Ref No.	Yes	No	N/A	Comments
Previous outage service reports				
Return to service data packages				
Maintenance Strategy with Rev number				
SAP defects (attach list as appendix)				
GHRMS (STEP) reports (Generation Heat Rate Management System)				
Online Condition Monitoring				
Pre-outage performance test results				
Post outage performance test results				
GPSS/ Plant Performance data on UCLF incurred				
OMS / IIRMS recommendations (Audits Reports)				
Risk controls (IRM system)				
Previous audits and reviews (e.g. ERAP)				
Engineering Change Requests (Projects)				
LOPP strategy reports				

Reference No: MEP - 051318	Reference Rev No:	Date: 2026/02/17	Page 27 of 29
----------------------------	-------------------	------------------	---------------

Controlled Disclosure

Faint, illegible text, likely bleed-through from the reverse side of the page.

	MATLA POWER STATION SCOPE OF WORK	Document Identifier	14593	Rev	7
		Effective Date	October 2024		
		Review Date	October 2027		

URS				
Philosophy (Outage)				
Condition Monitoring Report				
VA/PHD Viewer trends				
Corrective Actions				
CARAB reports				
Statutory Requirements				
Grid code requirements				
Waivers and Exemptions				
Calibration requirements				
Previous Outage SOW variations				
Post Mortems Actions from previous outages				
Pre-Outage plant walks				
Risk based inspection (RBI) report				
Simulation, TOIs, OON, SI				

Reference No MEP - 051318	Reference Rev No	Date 2026/02/17	Page 28 of 29
---------------------------	------------------	-----------------	---------------

Controlled Disclosure

This document is the property of Eskom and is controlled and managed in accordance with the Eskom Information Management Policy. It is intended for internal use only and is not to be distributed outside Eskom. It is not to be used for any other purpose without the prior written consent of Eskom. It is not to be used for any other purpose without the prior written consent of Eskom.

