

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	TENDER AMOUNT
1200	GENERAL REQUIREMENTS AND PROVISIONS				
12.01	Community Liaison:				
	(a) Community Liaison Officer cost	Prov. Sum	1,00	27000,00	27000,00
	(c) Handling costs and charges for Contractor on items 12.01 (a) to (b)	%	27000		
12.02	Remedial Work				
	(a) Rehabilitation of borrow pits and quarry	Lump Sum	1		
	(b) Removal of site establishment	Sum			
CARRIED FORWARD TO SUMMARY :					

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
1300	CONTRACTOR'S ESTABLISHMENT ON SITE AND GENERAL OBLIGATIONS				
13,01	The contractor's general obligations:				
	(a) <u>Fixed obligations</u>	Lump sum	1		
	(b) <u>Value-related obligations</u>	Lump sum	1		
	(c) <u>Time-related obligations</u>	Month	6		
13,02	Occupational Health & Safety:	lump sum	1		
	(a) - Preparation of Contractor's site specific Health and Safety Plan				
	(b) - Principal Contractor's initial obligations in respect of the OHS Act and Construction Regulations				
	(c) - Principal Contractor's time related obligations in respect of the OHS Act and Construction Regulations				
	(d) - Provision for Personal Protective Equipment & Protective Clothing including the following items				
	(i) Reflective vests (15)				
	(ii) Work Suits(15)				
	(iii) Hard hats(15)				
	(iv) Protective foot wear(15)				
	(v) Earplugs and Goggles (15)				
	(vi) Dust masks (15)				
	(e) - Provision of full time Construction Health and Safety Officer for project duration				
	(f) - Induction Training				
	(g) - Provision of First Aid Boxes				
	(h) - Submission of the Health and Safety File				
	(i) Contractors Obligations for OHS COVID 19 & Construction Regulations				
	(j) Costs of Medical Certificates for all employees				

CARRIED FORWARD TO SUMMARY :

-

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
1400	HOUSING, OFFICES AND LABORATORIES FOR THE ENGINEER'S PERSONNEL				
14,08	Services: The provision of water, electricity, sewerage, septic tanks, sewage and rubbish removal, cleaning services, maintenance and repairs, all as specified in Clause 14.04, including the construction and maintenance of the access roads, footpaths, etc: (a) Services at office and laboratories (i) Fixed costs (ii) Running costs	Lump sum Month	1 6		
14,09	Combined office and laboratory accommodation: Office and laboratory accommodation, including fittings, furniture and equipment, car ports and housing in accordance with the details given in the project specification and on the drawings and airconditioning	Lump sum	1		
CARRIED FORWARD TO SUMMARY :					

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
1500	ACCOMODATION OF TRAFFIC				
15,01	Accomodation of traffic	km	0,350		
CARRIED FORWARD TO SUMMARY :					0

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
2100	DRAINS				
21,01	Excavation of open drains				
	(a) Excavating soft material situated within the following depth ranges below the surface level				
	(i) 0m up to 1,5m	m ³	18,00		
	(b) Extra over subitem B21.01(a) for excavation in hard material irrespective of depth	m ³	Rate only		
21,02	Clearing and shaping existing open drains	m ³	22,00		
21,14	Repairing or replacing of existing drainage systems	Prov Sum	1,00		
21,20	Clearing and shaping side and mitre drains by grader	m	38,00		
CARRIED FORWARD TO SUMMARY :					

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
3400	PAVEMENT LAYERS OF GRAVEL MATERIAL				
34,01	Pavement layers constructed from gravel taken from cut or borrow including free haul up to 1,0km				
	(h) Gravel wearing course compacted to				
	(ii) 95% Mod AASHTO density: 150mm layer thickness	m³	270,00		
CARRIED FORWARD TO SUMMARY :					-

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
6200	FALSEWORK, FORMWORK AND CONCRETE FINISH				
62,01	Formwork to provide class F2 surface finish to concrete	m²			
62,02	Vertical formwork to provide class F2 surface finish to concrete	m²	2260,00		
CARRIED FORWARD TO SUMMARY :					-

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
6300	STEEL REINFORCING FOR STRUCTURES				
63,01	Steel reinforcement for:				
	(a) Concrete				
	(3) Welded steel fabric mesh (ref 395)	kg	1 235		
CARRIED FORWARD TO SUMMARY :					-

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
6400	CONCRETE FOR STRUCTURES				
64,01	Cast in situ concrete				
LIC	(a) Class 25 /19	m³	432,00		
CARRIED FORWARD TO SUMMARY :					-

SUMMARY OF SCHEDULE OF QUANTITIES

SECTION	DESCRIPTION	AMOUNT
1200	General Requirements and Provisions	
1300	Contractors Establishment and General Obligations	
1400	House, Offices and Laboratory for Engineer's Personnel	
1500	Accommodation of Traffic	
2100	Drains	
3400	Pavement Layers of Gravel Material	
6200	Falsework, Formwork and Concrete Finish	
6300	Steel reinforcing of Structures	
6400	Concrete for Structures	
Subtotal A		
Add 15% VAT		
Total Tender Amount		

Signed :

Date:

Name of Tenderer :