

## SECTION 2.1: SPECIFICATIONS

Purchase of 12 (Twelve) two (2) Cubic meter metal Skip bins:

SPECIFICATIONS		COMPLY YES/NO	PAGE TO REFERENCE
<b>2.1.1</b>	<b>2 Cubic Meter Skip Bin: (Metal)</b>		
2.1.1.1	Size: 2280mm x 1319mm x 1000mm.		
2.1.1.2	Made of 2 mm hot rolled mild steel sheets.		
2.1.1.3	Double welded at all seams (inner and outer)		
2.1.1.4	Bended seams to the floor panel (modification)		
2.1.1.5	Four dia.30mm hooking pins.		
2.1.1.6	Four, bended hooking handles, made of 16mm round bar, welded to each corner with 50mm insert into bin to strengthen.		
2.1.1.7	Triangular stiffener welded to centre of floor (modification)		
2.1.1.8	Two coats of Red Oxide Primer		
2.1.1.9	Two coats of QD Enamel Paint (Yellow)		

All skips must be delivered at Municipal workshop at Riversdale at Mulder street, Riversdale.

SPECIFICATIONS		COMPLY YES/NO	PAGE TO REFERENCE
<b>2.1.2</b>	<b>1 x 3.0 Ton Double Axle Universal Loader Trailer UL2000C</b>		
2.1.2.1	<b>Dimensions and Weight:</b>		
2.1.2.1.1	Outside Dimensions (l,b,h): 4 100mm x 2 100mm x 2 500mm		
2.1.2.1.2	Payload: 2 000kg		
2.1.2.2	<b>Components:</b>		
2.1.2.2.1	Axles: 1 600kg Each (Braked) (x2)		
2.1.2.2.2	Coupler: 3 000kg (Braked)		

2.1.2.2.3	Leaf springs: 10 Ply Leaf Springs 1 800kg/set (x2)		
2.1.2.2.4	Wheels: 195.14" (Spare wheel included)		
2.1.2.2.5	Jockey Wheel: 60mm Double Wheel		
2.1.2.3	<b>Built Type:</b>		
2.1.2.3.1	Floor: Galvanized Lip Channel 2mm thick with Galvanized wear strips.		
2.1.2.3.2	Chassis: 100 x 50 x 3 mm Rectangular Tubing		
2.1.2.3.3	A – Frame: 100 x 50 Channel		
2.1.2.3.4	Control Compartment: Galvanized Steel - Spray Painted, Lockable		
2.1.2.3.5	Engine: 16HP, Electric and Recoil start petrol engine		
2.1.2.3.6	Finish: Galvanized		
2.1.2.3.7	Operation: Loading and offloading: Hydraulically operated.		
2.1.2.3.8	Controls in lockable cabinet		
2.1.2.3.9	Hydraulics: High quality hydraulic pump and controls (Imported from Italy)		
2.1.2.3.10	All cylinders with Teflon seals and double O – rings.		
2.1.2.3.11	Plastic molded Hydraulic Tank.		
2.1.2.3.12	2 x stabilizing supports at back included (hydraulically operated)		
2.1.2.4	<b>Included Items:</b>		
2.1.2.4.1	4.5kg Fire extinguisher		
2.1.2.4.2	Micro Dotting		
2.1.2.4.3	Certified lifting chains. (Certificates included)		
2.1.2.4.4	Chain shortenings included stacking bins into one another.		
2.1.2.4.5	SABS Registered Builder providing registration papers.		
2.1.2.4.6	12 Months warrantee on <b>Universal Loader Trailer</b>		

Failure to adhere to the above, will result in your tender being declared non-responsive.

DECLARATION,

I, THE UNDERSIGNED (NAME) .....  
CERTIFY THAT THE INFORMATION FURNISHED ABOVE IS CORRECT. I ACCEPT THAT THE MUNICIPALITY MAY ACT  
AGAINST ME SHOULD THIS DECLARATION PROVE TO BE FALSE.

AUTHORISED SIGNATURE: .....

NAME: .....

CAPACITY: ..... DATE: .....

Initials of Service Provider's Authority: .....