



NEC3 Engineering and Construction Contract

QUESTIONS & ANSWERS (4) KZN171

The design, manufacture, supply, construction, installation and commissioning of 2x 3mvar, 22kv Shunt Capacitors and C-Type Filters at Makhathini Substation in the Empangeni Area of the KZN Operating Unit, for a period of twenty-four (24) months.

ENQUIRY NUMBER : KZN171

**TENDER CLOSING
DATE : Friday,
28 March 2025
AT 10H00**

QUESTIONS & ANSWERS (4) - KZN171

QUESTIONS		ANSWERS
1	With reference to Eskom specifications issued with this enquiry, please take note of the following: “No type tests are specified in “<i>SPECIFICATION FOR MAKHATHINI CAPACITOR REV 1 SIGNED</i> “ for the main capacitors. In specification “ <i>240-76429758 SPECIFICATION FOR CAPACITOR UNITS</i> “, a general specification for capacitors, all type test are listed but none are marked (specified) as required”. “Please advise which type test are required and included in our offer”.	The Type Testing of each Capacitor Unit, Damping Resistor and Filter Reactor type and rating offered will be required as part of the main offer. The type tests <u>rates</u> are required only. Should the cost of the type testing not be financially justifiable, type test certificates of similar equipment that are less than 5 years old and within the same ratings as specified may be accepted.