Project Title

Supply and deliver security cameras for the following Sentech sites: Klerksdorp, Heldekruin, Heidelberg, Mondeor, Mulbarton, Menlo park and Pretoria North.

Scope of Works

The successful applicant will:

Supply and deliver of cctv cameras and access control systems at Sentech Johannesburg operations centre that match mandatory criteria below:

Mandatory Criteria		Proof Required
DESCRIPTION:	**QTY**	
System must be compatible with the ONVIF standard		Attach spec sheet
ITEMS MUST BE DELIVERED AT JOHANNESBURG OPERATIONS OFFICE		
Delivery address: 1 Octave Road Radiokop Honeydew		
CCTV/ACCESS CONTROL SYSTEM		
16 Port Smart Gigabit PoE Managed Switch 10/100/1000Mbps	5	Attach spec sheet
24 Port Smart Gigabit PoE Managed Switch 10/100/1000Mbps	2	Attach spec sheet
NVR - similar to Uniview 8channel NVR, ONVIF, Smart Analytics, 2x HDD Slots - UN-NVR302-16S2	5	Attach spec sheet
NVR - similar to Uniview 16channel NVR, ONVIF, Smart Analytics, 2x HDD Slots - UN-NVR302-16S2	2	Attach spec sheet
Hard drive - similar to Seagate SkyHawk 4TB Surveillance Drive - ST8000VX0022	5	Attach spec sheet
Hard drive - similar to Seagate SkyHawk 8TB Surveillance Drive - ST8000VX0022	2	Attach spec sheet
5 MP True WDR fixed lens 4mm and Lighthunter AI **Dome Camera**. Day/Night, IR, IK10 vandal resistant, IP67 protection Support PoE power supply	11	Attach spec sheet
5 MP True WDR Vari-Focal 2.7-13.5mm Motorised and Lighthunter AI **Dome Camera**. Day/Night, IR, IK10 vandal resistant, IP67 protection Support PoE power supply, waterproof kit.	17	Attach spec sheet
5 MP True WDR Vari-Focal 2.7-13.5mm Motorised and Lighthunter AI **Bullet Camera**. Day/Night, IR, IP67 protection Support PoE power supply, waterproof kit.	5	Attach spec sheet
4G/5G LTE cat 6 industrial router, 2x LAN ports 10/100/1000, 1x WAN port 10/100/1000	7	Attach spec sheet

Outdoor Biometric Fingerprint/RFID cards/Password Access Control System Kit+ magnetic door Lock, Power Supply + Exit Button. Alarm output, IP65, TCP/IP, RS485. Similar to ZK-F17	4	Attach spec sheet
30W siren	7	Attach data sheet
INSTALLATION MATERIAL		
CCTV warning signs	20	
19" rack shelf	7	
19" Brush Panel	14	
100-meter black UV protected CAT6 POE network cable	10	Attach spec sheet
8mm Cable clips 100 pack	14	
RJ45 CAT6 connectors	100	
Outdoor vertical Pole mount bracket for cameras	7	
L arm mount for cameras	7	
Junction Box for dome/bullet camera	18	

NOTE:

On submission of your quote please attach

➢ your company's CSD Report; Valid Tax & BEE Certificates