



**Groblersdal Post Office**

**Supply and installation of burglarproofing, gates  
including certain work**

**NAME OF CONTRACTOR**

# INDEX

#REF!					
Groblersdal Post Office					
		DOORS	Page 3		
		PLUMBING	Page 4		
		GLAZING	Page 5		
		TRIM TREES CLEAN YARD	Page 6		
		METALWORK	Page 7		

## DOORS

	Groblersdal Post Office	No	units	Rate	Amount
	NOTE 1: The rates of all items in this bill shall include manufacturing-, delivery- and installation costs, excluding VAT.				
	NOTE 2: The rates of all items in this bill shall include all paint and varnish finishes .				
	NOTE 3 : Doors must be finished all in accordance with SAPO standard specifications				
1	<b>Store Room outside.</b> Provide and weld brackets securely on to gate and frame suitable to fit a ABUS Discus 70mm lock. Prepare and paint brackets and where welded.	1	no	R	R
2	Supply ABUS Discus 70mm lock with keys.	1	no	R	R
	DOORS carried to summary				

DOORS


## PLUMBING

	Groblersdal Post Office	No	units	Rate	Amount
	NOTE: The rates of all items in this bill shall include manufacturing-, delivery- and installation costs, excluding VAT.				
1	Excavate and replace burst pipe underground with new. Do all the connections and leave watertight on completion. Refill area and leave level and compact on completion.	4	lm	R	R
2	<b>External wall.</b> Replace faulty PVC valve with new. Leave perfect and watertight on completion.	1	no	R	R

---

PLUMBING carried to summary

---

# GLAZING

	Groblersdal Post Office	No	Units	Rate	Amount
	NOTE 1: The rates of all items in this bill shall include manufacturing-, delivery- and installation costs, excluding VAT.				
1	Replace all broken pane with new to match the existing.All panes to be well back puttied. Measurement to be confirmed by supplier on site. Correct mearements to be taken on site by the supplier. Sizes				
1.1	500 x 950mm	2	no	R	R
1.2	500 x 100mm	7	no	R	R
1.3	950 x 450mm (ladies toilets)	1	no	R	R
2	Replace missing window handle with new including new brackets. When welding and grinding protect window panes from damages.	4	no	R	R

---

GLAZING carried to summary

---

TRIM TREES CEAN YARD AND OFFICE

	<b>Groblersdal Post Office</b>	<b>No</b>	<b>units</b>	<b>Rate</b>	<b>Amount</b>
	NOTE: The rates of all items in this bill shall include all manufacturing-, delivery- and installation costs, excluding VAT.				
1	Cut trees down completely and cart away from site. Trees trange in different sizes. Treat stumps with an approved chemical to stop growing further.	7	no	R	R
2	Entire yard to be cleaned. All grass, veld grass to be neatly cut. All edges to be trimmed. All rubble, garden refuse to be cart away from site. On completion entire yard to be left neat and clean.	1	item	R	R

---

TRIM REES, CLEAN YARD carried to  
summary

---

# METALWORK

#REF!					
Groblersdal Post Office		No	Units	Rate	Amount
	NOTE 1: Before commencing with work measurements must be taken on site by the successful contractor.				
	NOTE 2: The rates of all items in this bill shall include manufacturing-, delivery- and installation costs, excluding VAT				
1	<b>PO Entrance Door.</b> Build and installed a double security gate 2000 x 2100mm with frame to doorframe at the entrance door. Constructed of 32 x 32 x2mm square tubing, strongly braced and filled with 25 x 25 x 2mm square tubing securely and neatly welded to frame complete with lock etc. The door to be provided with a four-lever mortice lock, designed for trellis doors, with two keys. On completion paint one undercoat and two coats Plascon Double Velvet: Colour Fresh Drop C14-6. Measurement to be confirmed by supplier on site	2	no	R	R
2	<b>Service Hatch</b> Build and install a 1320 x 700mm sliding gate to close off the serving hatch when not in use. Constructed of 25 x 25 x 2.5mm square tubing and covered from the outside with flatex 352 securely welded. Gate to be provided with brackets suitable for a padlock. The sliding gate to be painted one undercoat and two coats Plascon Double Velvet: Colour Fresh Drop C14-6. Provide 60mm Viro padlock with keys. Measurement to be confirmed by supplier on site	1	item	R	R
3	<b>Post Office Building.</b> Build and install burglar proofing (boxed) constructed of 40 x 40 x 3mm angle iron and covered from the inside with flatex 352 securely welded. The burglar-proofing to be painted one undercoat and two coats Plascon Double Velvet: Colour Fresh Drop C14-6. The burglar proofing to be fasten to the outside of the specific windows with M10 rawllbolts. On completion the rawllbolts to be welded to prevent them from loosening. Measurement to be confirmed by supplier on site			R	R



## METALWORK

3.1	1600 x 1300 x 300mm (Branch Manager, Boxes)	3	no	R	R
3.2	1100 x 1300 x 300mm Kitchen, Branch Manager)	2	no	R	R
3.3	2100 x 1100 x 300mm (Public area, Boxes)	8	no	R	R
4	<b>Post Office (Above Private Boxes)</b> Build and install burglar proofing (boxed) constructed of 40 x 40 x 3mm angle iron and covered from the inside with flatex 352 securely welded. The burglar-proofing to be painted one undercoat and two coats Plascon Double Velvet: Colour Fresh Drop C14-6. The burglar proofing to be fasten to the outside of the specific windows with M10 rawllbolts. On completion the rawllbolts to be welded to prevent them from loosening. Measurement to be confirmed by supplier on site			R	R
4.1	2300 x 500 x 100mm	3	no	R	R
4.2	3000 x 500 x 100mm	3	no	R	R
5	Provide and install 500mm razor flat wrap wire on part of the existing fence and vehicle gate. Leave secure on completion	30	L/m	R	R

---

METALWORK carried to summary

---

## SUMMARY

	Groblersdal Post Office				
		Page		Amount R.c	
1	DOORS	3		R	
2	PLUMBING	4		R	
3	GLAZING	5		R	
4	TRIM TREES, CLEAN YARD AND OFFICE	6		R	
5	METALWORK	7		R	
6	SUMMARY	8		R	
7	CONTINGENCIES Provision of 5% of tender amount for contingencies to be used at the discretion of the SAPO and deducted from the contract amount if not required			R	
	SUB-TOTAL			R	
	Add: V.A.T. @ 15 %			R	
	<b>TOTAL</b>	<b>Carried to tender form</b>		R	