

# SCOPE OF WORK

## Supply and installation of HVAC / Aircon Split unit

- Removal and disposing of old existing faulty aircons
- Installation of new air conditioning units which include, assembling of old aircons
- Re-gasing of aircons
- Electrical work- wiring and pulling of cables from ducting and trenching
- Welding
- Wall drilling

## **SCAFFOLDING:**

Erection and dismantling for all types of scaffolds higher than 2 meters. Scaffolding shall be erected, altered or dismantled under the supervision of a competent person who has been appointed in writing for this purpose.

Scaffolding for use of internal and external building, contractor to also note some building exceed 6m high.

## **FAS**

Contractor to refer to Eskom standard no:240-100979499 (attached as part of tender documents) for Fall Arrest System and working at heights specifications and safety requirements.

**Name : Tom Hlatshwayo**

**Signature :**

