

Item No	Quantity	Rate	Amount
<u>SECTION NO. 1</u>			
<u>BILL NO. 1</u>			
<u>PRELIMINARIES</u>			
<u>BUILDING AGREEMENT AND PRELIMINARIES</u>			
<u>Principal Building Agreement Code 2101 Edition 4.1 March 2005 (including State Provisions)</u>			
<u>AND PRELIMINARIES Code 2103 May 2005</u>			
<u>PRELIMINARIES NOTES</u>			
i)	The agreement is to be the JBCC Series 2000 Principal Building Agreement, Edition 4.1 May 2005, and other contract documents that together form the contract between the employer and contractor		
ii)	The preliminaries are to be the JBCC Series 2000 Code 2103 Preliminaries prepared by the Joint Building Contracts Committee, May 2005 edition and shall be deemed to be incorporated herein		
iii)	Tenderers are referred to the abovementioned documents for the full intent and meaning of each clause thereof (hereinafter referred to by heading and clause number only) for which such allowance must be made as may be considered necessary		
iv)	Where standard clauses or alternatives are not entirely applicable to this contract such modifications, corrections or supplements as will apply are given under each relevant clause heading		
Carried Forward			R
Section No. 1 Section 1 - Preliminaries and General Bill No. 1 Preliminaries Re-Solve Consulting			

	Brought Forward		R
<p>v) Where any item is not relevant to this specific contract such item is marked N/A (signifying "not applicable")</p> <p>vi) If Alternative A as set out in clause B10.3 hereinafter is to be used for the adjustment of the preliminaries each item priced is to be allocated to one or more of the three categories, where "F" denotes a fixed amount (amount not to be varied), "V" denotes an amount variable in proportion to value and "T" denotes an amount in proportion to time</p> <p style="text-align: center;">-----</p>			
<p>Section No. 1 Section 1 - Preliminaries and General Bill No. 1 Preliminaries Re-Solve Consulting</p>	Carried Forward		R

Brought Forward		R
<u>SECTION A: PRINCIPAL BUILDING AGREEMENT</u>		
<u>Definitions (A1)</u>		
1/1/1	Definitions and interpretation (clause 1)	Item
<u>Objective and Preparation (A2 to A14)</u>		
1/1/2	Offer acceptance and performance (clause 2)	Item
1/1/3	Documents (clause 3)	Item
1/1/4	Design responsibility (clause 4)	Item
1/1/5	Employer's agents (clause 5)	Item
1/1/6	Site representative (clause 6)	Item
1/1/7	Compliance with regulations (clause 7)	Item
1/1/8	Works risk (clause 8)	Item
1/1/9	Indemnities (clause 9)	Item
1/1/10	Works insurances (clause 10)	Item
1/1/11	Liability insurances (clause 11)	Item
1/1/12	Effecting insurance (clause 12)	Item
1/1/13	NO CLAUSE 13.	N/A
1/1/14	Security (clause 14)	Item
<u>Execution (A15-A23)</u>		
1/1/15	Preparation for and execution of the works (clause 15)	Item
1/1/16	Access to the works (clause 16)	Item
1/1/17	Contract instructions (clause 17)	Item
Carried Forward		R
Section No. 1 Section 1 - Preliminaries and General Bill No. 1 Preliminaries Re-Solve Consulting		

Brought Forward		R
1/1/18	Setting out of the works (clause 18)	Item
1/1/19	Assignment (clause 19)	Item
1/1/20	Nominated subcontractors (clause 20)	Item
1/1/21	Selected subcontractors (clause 21)	Item
1/1/22	Employer's Direct Contractors (clause 22)	Item
1/1/23	Contractor's Domestic Sub-Contractors (Clause 23)	Item
<u>Completion (A24-A30)</u>		
1/1/24	Practical completion (clause 24)	Item
1/1/25	Works completion (clause 25)	Item
1/1/26	Final completion (clause 26)	Item
1/1/27	Latent defects liability period (clause 27)	Item
1/1/28	Sectional completion (clause 28)	Item
1/1/29	Revision of date of practical completion (clause 29)	Item
1/1/30	Penalty for non-completion (clause 30)	Item
<u>Payment (A31 - A35)</u>		
1/1/31	Interim payment to the contractor (clause 31)	Item
1/1/32	Adjustment to the contract value (clause 32)	Item
1/1/33	Recovery of expense and loss (clause 33)	Item
1/1/34	Final account and final payment (clause 34)	Item
1/1/35	Payment to other parties (clause 35)	Item
Carried Forward		R
Section No. 1 Section 1 - Preliminaries and General Bill No. 1 Preliminaries Re-Solve Consulting		

	Brought Forward		R	
	<u>Cancellation (A36-A39)</u>			
1/1/36	Cancellation by employer - contractor's default (clause 36)	Item		
1/1/37	Cancellation by employer - loss and damage (clause 37)	Item		
1/1/38	Cancellation by contractor - employer's default (clause 38)	Item		
1/1/39	Cancellation - cessation of the works (clause 39)	Item		
	<u>Dispute (A40)</u>			
1/1/40	Dispute Settlement (clause 40)	Item		
	<u>Substitute Provisions (A41)</u>			
1/1/41	State clauses (Clause 41)	Item		
	<u>THE SCHEDULE</u>			
	Information necessary for completion of those clauses contained in the schedule which are necessary for tender purposes is given hereunder			
1/1/42	Pre-tender information (clause 42)	Item		
	<u>42.1 CONTRACTING AND OTHER PARTIES</u>			
	42.1.1 Employer:			
	THE MVULA TRUST			
	42.1.2 Principal Agent:			
	RE-SOLVE CONSULTING			
	Carried Forward			
	Section No. 1 Section 1 - Preliminaries and General Bill No. 1 Preliminaries Re-Solve Consulting		R	

	Brought Forward		R	
42.2 CONTRACT DETAILS				
42.2.1 Works Description:				
Construction of sanitation facilities				
42.2.2 Site Description:				
as per the information on the tender data				
42.2.3 Work or installations by direct contractors:				
N/a				
42.2.4 This agreement is for a government contract where there are specific options that are applicable to a State organ only				
				Yes
42.2.5 Date on which possession of the site is intended to be given:				
As per the information provided in the Tender Data				
42.2.6 Period for the commencement of the works after the contractor takes possession of the site				
				7 DAYS
42.2.7 For the works as a whole. Intended date of practical completion and the penalty per calendar day				
Intended Date of Practical Completion: As per the information provided in the Tender Data				
Penalty Amount:				
The penalty per calendar day shall be 7.5 cents per R100 of the Tendered Amount (inclusive of value added tax)				
Carried Forward				
Section No. 1				
Section 1 - Preliminaries and General				
Bill No. 1				
Preliminaries				
Re-Solve Consulting				
				R

	Brought Forward		R
42.2.8 For the works in sections : Intended date of practical completion and the penalty per calender day	N/a		
42.2.9 The law applicable to this agreement shall be that of	<i>South Africa (country)</i>		
<u>42.3 INSURANCES</u>			
42.3.1 Contract works insurance to be effected by: Contractor: For the Sum of R Contract Amount + 10.00 % With a deductible of - to be determined by the contractor			
42.3.2 Supplementary insurance is required	No		
42.3.3 Public liability insurance to be effected by:Contractor: For the Sum of R 5 000 000-00 With a deductible of - to be determined by the contractor			
<u>42.4 DOCUMENTS</u>			
42.4.1 Waivers of contractors lien or right of continuing possession is required	Yes		
42.4.2 Number of construction document copies to be supplied to the contractor free of charge:	<i>3 Number of</i>		
42.4.3 Bills of Quantities/Lump sum document schedule of rates drawn up in accordance with: "Standard System of Measuring Builders' Work"			
Carried Forward			
Section No. 1 Section 1 - Preliminaries and General Bill No. 1 Preliminaries Re-Solve Consulting			R

Brought Forward			R	
42.4.4 On acceptance of the tender the bills of quantities/lump sum document is to be submitted within working days				
5 working days				
42.4.5 JBCC Engineering General Conditions are to be included in the contract documents:				
<i>No</i>				
42.4.6 The contract value is to be adjusted using escalation adjustment indices				
<i>No</i>				
42.4.7 Details of changes made to the provision of JBCC standard documentation: [An addendum is to be attached should the space provided be insufficient]				
Part 1 -Contract Data completed by Employer				
Carried Forward			R	
Section No. 1 Section 1 - Preliminaries and General Bill No. 1 Preliminaries Re-Solve Consulting				

Brought Forward

R

SECTION B: PRELIMINARIES

Definitions and interpretation (B1)

1/1/43	Definition and interpretation (B1.1 - B1.4.6)	Item		
--------	---	------	--	--

Documents (B2)

1/1/44	Checking of documents (B2.1)	Item		
--------	------------------------------	------	--	--

1/1/45	Provisional bills of quantities (B2.2)	Item		
--------	--	------	--	--

1/1/46	Availability of construction documentation (B2.3)	Item		
--------	---	------	--	--

1/1/47	Interests of agents (B2.4)	Item		
--------	----------------------------	------	--	--

1/1/48	Priced documents (B2.5)	Item		
--------	-------------------------	------	--	--

1/1/49	Tender submission (B2.6)	Item		
--------	--------------------------	------	--	--

The site (B3)

1/1/50	Defined works area (B3.1)	Item		
--------	---------------------------	------	--	--

1/1/51	Geotechnical investigation (B3.2)	Item		
--------	-----------------------------------	------	--	--

1/1/52	Inspection of the site (B3.3)	Item		
--------	-------------------------------	------	--	--

1/1/53	Existing premises occupied (B3.4)	Item		
--------	-----------------------------------	------	--	--

1/1/54	Previous work - dimensional accuracy (B3.5)	Item		
--------	---	------	--	--

1/1/55	Previous work - defects (B3.6)	Item		
--------	--------------------------------	------	--	--

1/1/56	Services - known (B3.7)	Item		
--------	-------------------------	------	--	--

1/1/57	Services - unknown (B3.8)	Item		
--------	---------------------------	------	--	--

1/1/58	Protection of trees etc (B3.9)	Item		
--------	--------------------------------	------	--	--

1/1/59	Articles of value (B3.10)	Item		
--------	---------------------------	------	--	--

1/1/60	Inspection of adjoining properties etc (B3.11)	Item		
--------	--	------	--	--

Carried Forward

R

Section No. 1
Section 1 - Preliminaries and General
Bill No. 1
Preliminaries
Re-Solve Consulting

	Brought Forward		R	
	<u>Management of contract (B4)</u>			
1/1/61	Management of the works (B4.1)	Item		
1/1/62	Programme for the works (B4.2)	Item		
1/1/63	Progress meetings (B4.3)	Item		
1/1/64	Technical meetings (B4.4)	Item		
1/1/65	Labour and Plant records (B4.5)	Item		
	<u>Samples, Shop Drawings and Manufacturer's Instructions (B5)</u>			
1/1/66	Samples of materials (B5.1)	Item		
1/1/67	Workmanship samples (B5.2)	Item		
1/1/68	Shop drawings (B5.3)	Item		
1/1/69	Compliance with Manufacturer's Instructions (B5.4)	Item		
	<u>Temporary works and plant (B6)</u>			
1/1/70	Deposits and fees (B6.1)	Item		
1/1/71	Enclosure of the works (B6.2)	Item		
1/1/72	Advertising (B6.3)	Item		
1/1/73	Plant, equipment, sheds and offices (B6.4)	Item		
1/1/74	Main notice board (B6.5)	Item		
1/1/75	Subcontractors' notice board (B6.6)	Item		
	<u>Temporary services (B7)</u>			
1/1/76	Location (B7.1)	Item		
1/1/77	Water (B7.2)	Item		
	Option [A] shall apply			
	Carried Forward		R	
	Section No. 1 Section 1 - Preliminaries and General Bill No. 1 Preliminaries Re-Solve Consulting			

Brought Forward

R

1/1/78	Electricity (B7.3)	Option [A] shall apply	Item
1/1/79	Telecommunication facilities (B7.4)		Item
1/1/80	Ablution facilities (B7.5)	Option [A] shall apply	Item
<u>Prime cost amounts (B8)</u>			
1/1/81	Responsibility for prime cost amounts (B8.1)		Item
<u>Attendance on N/S Subcontractors (B9)</u>			
1/1/82	General attendance (B9.1)		Item
1/1/83	Special attendance (B9.2)		Item
1/1/84	Commissioning - Fuel, water and power (B9.3)		Item
<u>Financial aspects (B10)</u>			
	Statutory taxes, duties and levies (B10.1)		Item
1/1/85	Payment of preliminaries (B10.2)	Option [B] shall apply	Item
1/1/86	Adjustment of preliminaries (B10.3)	Option [A] shall apply	Item
1/1/87	Payment certificate cash flow (B10.4)		Item
<u>General (B11)</u>			
1/1/88	Protection of works (B11.1)		Item
1/1/89	Protection/isolation of existing/sectionally occupied works (B11.2)		Item
1/1/90	Security of the Works (B11.3)		Item
1/1/91	Notice before covering work (B11.4)		Item

Carried Forward

R

Section No. 1
Section 1 - Preliminaries and General
Bill No. 1
Preliminaries
Re-Solve Consulting

	Brought Forward		R
1/1/92	Disturbance (B11.5)	Item	
1/1/93	Environmental Disturbance (B11.6)	Item	
1/1/94	Works cleaning and clearing (B11.7)	Item	
1/1/95	Vermin (B11.8)	Item	
1/1/96	Overhand work (B11.9)	Item	
1/1/97	Instruction manuals and guarantees (B11.10)	Item	
1/1/98	As built information (B11.11)	Item	
1/1/99	Tenant Installations (B11.12)	Item	
	<u>Schedule of variables (B12)</u>		
1/1/100	Pre-tender information (B12.1)	Item	
	12.1.1 Provisional bills of quantities (B2.2) The quantities are provisional:		
	<i>No</i>		
	12.1.2 Availability of construction documentation (B2.3) Construction documentation is not complete		
	<i>No</i>		
	12.1.3 Interest of agents (B2.4)		
	.		
	12.1.4 Defined works area (B3.1)		
		
	12.1.5 Geotechnical investigation (B3.2)		
	N/a		
	Carried Forward		
	Section No. 1 Section 1 - Preliminaries and General Bill No. 1 Preliminaries Re-Solve Consulting		R

Brought Forward	R
12.1.6 Existing premises occupied (B3.4) ??	
12.1.7 Previous work - dimensional accuracy (B3.4) ??	
12.1.8 Previous work - defects (B3.5) ??	
12.1.9 Services - known (B3.7) ??	
12.1.10 Protection of trees (B3.9) All trees should be protected and only on instruction of the Principal Agent may any trees be removed	
Carried Forward	R
Section No. 1 Section 1 - Preliminaries and General Bill No. 1 Preliminaries Re-Solve Consulting	

	Brought Forward		R
12.1.11 Inspection of adjoining properties (B3.11)			
??			
.....			
.....			
12.1.12 Enclosure of the works (B6.2)			
??			
.....			
.....			
12.1.13 Offices (B6.4.3)			
Specific requirements: The contractor shall provide, maintain and remove, on completion of the works, an office for the exclusive use of the principal agent, minimum size 4 x 3 x 3m high internally, suitably insulated and ventilated, provided with electric lighting and fitted with boarded floor, desk, chair, drawing stool, drawing board and lock-up drawers for drawings. The office shall be kept clean and fit for use at all times			
12.1.14 Main notice board (B6.5)			
Yes			
12.1.15 Subcontractors notice board (B6.6)			
A notice board is required		Yes	
12.1.16 Water (B7.2)			
Alternative Selected: A			
12.1.17 Electricity (B7.3)			
Alternative selected: A			
	Carried Forward		R
Section No. 1 Section 1 - Preliminaries and General Bill No. 1 Preliminaries Re-Solve Consulting			

	Brought Forward		R
12.1.18 Telecommunications (B7.4)			
12.1.19 Ablution facilities (B7.5) Alternative selected: A			
12.1.20 Protection of existing/sectionally occupied works (B11.2)			
12.1.21 Special attendance (B9.2) Subcontractor (1) details: N/a			
12.1.22 Protection of the works (B11.1)			
12.1.23 Disturbance (B11.5)			
12.1.24 Environmental Disturbance (B11.6)			
<u>Post tender information (B12.2)</u>			
12.2.1 Payment of preliminaries Alternative selected: B			
12.2.2 Adjustment of preliminaries Alternative selected: A			
12.2.3 Additional agreed preliminaries items N/a			
	Carried Forward		R
Section No. 1 Section 1 - Preliminaries and General Bill No. 1 Preliminaries Re-Solve Consulting			

Brought Forward

R

SECTION C: SPECIFIC PRELIMINARIES??

Any special items to meet the parrtcular circumstances of a specific project are embodied in this section. Where required for an aspect of the works to be executed according to a design by a consulting engineer, a recital of the headings to the individual clauses of the JBCC Engineering General Conditions are included

1/1/101 **Site instructions**

Instructions issued on site are to be recorded in triplicate in a site instruction book which is to be maintained on site by the contractor

F:..... V:..... T:.....

Item

1/1/102 **Black economic empowerment and training**

F:..... V:..... T:.....

Item

1/1/103 **Proprietary branded products**

F:..... V:..... T:.....

Item

Carried Forward

R

Section No. 1
 Section 1 - Preliminaries and General
 Bill No. 1
 Preliminaries
Re-Solve Consulting

Brought Forward

1/1/104 **Testing of flat roof waterproofing for watertightness**

Flat roof waterproof areas shall be prepared with small sand dykes around them of a size and enclosing an area approved by the principal agent, flooded with water and kept "ponded" for at least 36 hours as a test to ensure the watertightness of the waterproofing and before any further construction work is carried out above the waterproofing

F:.....V:.....T:.....
 The contractor shall take delivery of, handle, store, use, apply and/or fix all proprietary branded products in strict accordance with the manufacturers' instructions after consultation with the manufacturer's authorised representative

Item

1/1/105 **Contract instructions**

F:..... V:..... T:.....

Contract instructions issued on site are to be recorded in triplicate in a contract instruction book which is to be supplied and maintained on site by the contractor

Item

1/1/106 **Labour record**

F:..... V:..... T:.....

At the end of each week the contractor shall provide the principal agent with a written record, in schedule form, reflecting the number and descriptions of tradesmen and labourers employed by him and all subcontractors on the works each day of that week

Item

Carried Forward

Section No. 1
 Section 1 - Preliminaries and General
 Bill No. 1
 Preliminaries
Re-Solve Consulting

R

R

Brought Forward

R

1/1/107 **Plant record**

F:..... V:..... T:.....

At the end of each week the contractor shall provide the principal agent with a written record, in schedule form, reflecting the number, type and capacity of all plant, excluding hand tools used on the works each day of that week

Item

1/1/108 **Guarantees**

F:..... V:..... T:.....

Where guarantees are called for, the contractor shall obtain a written guarantee, addressed to the employer, from the firm supplying the materials and/or doing the work and shall deliver same to the principal agent on the certified completion of the contract. The guarantee shall state that workmanship, materials and installation are guaranteed for a specified period from the date of certified completion of the contract, and that any defects that may arise during the specified period shall be made good at the expense of the firm supplying the materials and/or doing the work, upon written notice from the principal agent to do so. This guarantee will not be enforced if the work is damaged by defects in the construction of the building in which case the responsibility for replacement shall rest entirely with the contractor. The principal agent shall be the sole judge of the cause responsible for defects in the work and his decision shall be final and binding in terms of clause 40.2 of the agreement

Item

Carried Forward

R

Section No. 1
 Section 1 - Preliminaries and General
 Bill No. 1
 Preliminaries
Re-Solve Consulting

Brought Forward

R

1/1/109 **Overtime**

F:..... V:..... T:.....

Should overtime be required to be worked for any reason whatsoever, the costs of such overtime are to be borne by the contractor unless the principal agent has specifically authorised, in writing, prior to execution thereof, that costs for such overtime are to be borne by the employer

Item

1/1/110 **Co-operation of contractor for cost management**

F:..... V:..... T:.....

It is specifically agreed that the contractor accepts the obligation of assisting the professional consultants in implementing proper cost management. The contractor will be advised by the principal agent of all cost management procedures which will be implemented to ensure that the final building cost does not exceed the budget. The quantity surveyor undertakes to make available to the contractor all budgetary allowances and cost assessments/reports to enable the proper procedures to be implemented and the contractor will attend all cost plan review and cost management meetings. The contractor undertakes to extend these procedures in regard to all subcontractors

Item

Carried Forward

R

Section No. 1
 Section 1 - Preliminaries and General
 Bill No. 1
 Preliminaries
Re-Solve Consulting

Brought Forward

R

1/1/111

Occupational Health and Safety Specification

F:..... V:..... T:.....

The contractor shall comply with all the requirements set out in the Construction Regulations, 2003 issued under the Occupational Health and Safety Act, 1993 (Act No 85 of 1993)

It is required of the contractor to thoroughly study the Health and Safety Specification that must be read together with and is deemed to be incorporated under this Section of the bills of quantities / lump sum document.

The contractor must take note that compliance with the Occupational Health and Safety Act, Construction Regulations and Health and Safety Specification is compulsory. In the event of partial or total non-compliance, the principal agent, notwithstanding the provisions of clause A31.0 of Section A or any other clause to the contrary, reserves the right to delay issuing any progress payment certificate until the contractor provides satisfactory proof of compliance.

The contractor shall not be entitled to any compensation of whatsoever nature, including interest, due to such delay of payment.

Provision for pricing of the Occupational Health and Safety Act, Construction Regulations and Health and Safety Specification is made under this clause, as well as the clauses that follow hereafter and it is explicitly pointed out that all requirements of the aforementioned are deemed to be priced under these clauses and no additional claims in this regard shall be entertained.

The contractor shall also comply with the additional requirements with regard to the Coronavirus pandemic in terms of all Covid-19 legislation, regulations and guidelines. It is explicitly pointed out that all requirements of the aforementioned are deemed to be priced under this clause and the specific related clauses hereafter and no additional claims in this regard shall be entertained.

Item

Carried Forward

R

Section No. 1
 Section 1 - Preliminaries and General
 Bill No. 1
 Preliminaries
Re-Solve Consulting

Brought Forward

R

1/1/112 **Occupational Health and Safety Specification**
 F:..... V:..... T:.....

Preparation of contractor's site specific health and safety plan, including compliance with Covid-19 legislation, regulations and guidelines

Item

1/1/113 **Occupational Health and Safety Specification**
 F:..... V:..... T:.....

Principal contractor's initial obligations in respect of the Health and Safety Act, Construction Regulations and Covid-19 regulations, etc

Item

1/1/114 **Occupational Health and Safety Specification**
 F:..... V:..... T:.....

Principal contractor's time related obligations in respect of the Health and Safety Act, Construction Regulations and Covid-19 regulations, etc

Item

1/1/115 **Provision of personal protective equipment (PPE)**
 F:..... V:..... T:.....

Provision of reflective vests

Item

1/1/116 **Provision of personal protective equipment (PPE)**
 F:..... V:..... T:.....

Provision of hard hats

Item

Carried Forward

R

Section No. 1
 Section 1 - Preliminaries and General
 Bill No. 1
 Preliminaries
Re-Solve Consulting

	Brought Forward		R	
1/1/117	Provision of personal protective equipment (PPE) F:..... V:..... T:..... Provision of protective footwear	Item		
1/1/118	Provision of personal protective equipment (PPE) F:..... V:..... T:..... Provision of earplugs	Item		
1/1/119	Provision of personal protective equipment (PPE) F:..... V:..... T:..... Provision of dust masks	Item		
1/1/120	Provision of personal protective equipment (PPE) F:..... V:..... T:..... Provision of gloves	Item		
1/1/121	Provision of personal protective equipment (PPE) F:..... V:..... T:..... Provision of high visibility overalls to SARTSM Chapter 13 Level 3	Item		
1/1/122	Provision of personal protective equipment (PPE) F:..... V:..... T:..... Provision of SANS approved ear defenders	Item		
	Carried Forward		R	
	Section No. 1 Section 1 - Preliminaries and General Bill No. 1 Preliminaries Re-Solve Consulting			

	Brought Forward		R
1/1/123	Provision of personal protective equipment (PPE) F:..... V:..... T:..... Provision of face masks (Covid -19)	Item	
1/1/124	Provision of personal protective equipment (PPE) F:..... V:..... T:..... Provision of face shields (Covid -19)	Item	
1/1/125	Provision of personal protective equipment (PPE) F:..... V:..... T:..... Provision of gloves (Covid -19)	Item	
1/1/126	Provision of personal protective equipment (PPE) F:..... V:..... T:..... Provision of hand sanitiser (min 70% alcohol), foot press stands and paper towels (Covid -19)	Item	
1/1/127	Provision of personal protective equipment (PPE) F:..... V:..... T:..... Provision of covered refuse bins and refuse bags and waste (including hazardous) management (Covid -19)	Item	
	Carried Forward		R
	Section No. 1 Section 1 - Preliminaries and General Bill No. 1 Preliminaries Re-Solve Consulting		

	Brought Forward		R	
1/1/128	Provision of personal protective equipment (PPE) F:..... V:..... T:..... Provision of digital infrared non-contact body thermometer (Covid -19, minimum of two per site entrance)	Item		
1/1/129	Provision of personal protective equipment (PPE) F:..... V:..... T:..... Provision of perspex screens for office staff (Covid -19, minimum size 600 x 500mm)	Item		
1/1/130	Provision of personal protective equipment (PPE) F:..... V:..... T:..... Provision of signage, including Covid -19 related signage	Item		
1/1/131	Provision of personal protective equipment (PPE) F:..... V:..... T:..... Provision of full time construction health and safety officer (SACPCMP Registered)	Item		
1/1/132	Provision of personal protective equipment (PPE) F:..... V:..... T:..... Medical certificates and medical surveillance including initial (baseline) medical examinations, periodic examinations, and exit examinations	Item		
	Carried Forward		R	
	Section No. 1 Section 1 - Preliminaries and General Bill No. 1 Preliminaries Re-Solve Consulting			

Brought Forward

R

1/1/133 **Provision of personal protective equipment (PPE)**

F:..... V:..... T:.....

Medical screenings, examinations, etc in terms of Covid-19 regulations

Item

1/1/134 **Provision of personal protective equipment (PPE)**

F:..... V:..... T:.....

Induction training, including Covid-19 training

Item

1/1/135 **Provision of personal protective equipment (PPE)**

F:..... V:..... T:.....

Provision of first aid boxes to GSR requirements

Item

1/1/136 **Provision of personal protective equipment (PPE)**

F:..... V:..... T:.....

Noise monitoring including establishment of noise zones (plant), audiograms (personnel), etc

Item

1/1/137 **Provision of personal protective equipment (PPE)**

F:..... V:..... T:.....

Submission of health and safety file

Item

Carried Forward

R

Section No. 1
 Section 1 - Preliminaries and General
 Bill No. 1
 Preliminaries
Re-Solve Consulting

Brought Forward

R

1/1/138

HIV/AIDS Awareness

F:..... V:..... T:.....

It is required of the contractor to thoroughly study the HIV/AIDS Specification (PW 1544) of the Department that must be read together with and is deemed to be incorporated under this Section of the bills of quantities / lump sum document. Provision for pricing of HIV/AIDS awareness is made under items C11.1 to C11.5 hereafter and it is explicitly pointed out that all requirements of the aforementioned specification are deemed to be priced hereunder, as the said items represent the only method of measurement and no additional items or extras to the contract in this regard shall be entertained.

The contractor must take note that compliance with the HIV/AIDS Specification is compulsory. In the event of partial or total non-compliance, the principal agent, notwithstanding the provisions of clause A 31.0 of Section A or any other clause to the contrary, reserves the right to delay issuing any progress payment certificate until the contractor provides satisfactory proof of compliance. The contractor shall not be entitled to any compensation of whatsoever nature, including interest, due to such delay of payment.

Item

SUMMARY OF CATEGORIES

Category : Fixed R.....

Category : Value R.....

Category : Time R.....

Carried to Final Summary

R

Section No. 1
Section 1 - Preliminaries and General
Bill No. 1
Preliminaries
Re-Solve Consulting

Item No	Quantity	Rate	Amount
<p><u>SECTION 2</u></p> <p><u>BILL NO. 1</u></p> <p><u>ALTERATIONS</u></p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>View site</u></p> <p>Before submitting his tender the contractor shall visit the site and satisfy himself as to the nature and extent of the work to be done and the value of the materials contained in the buildings or portions of the buildings to be demolished. No claim for any variations of the contract sum in respect of the nature and extent of the work or of inferior or damaged materials will be entertained.</p> <p><u>Explosives</u></p> <p>No explosives whatsoever may be used for demolition.</p> <p><u>General</u></p> <p>The contractor shall carry out the whole of the works with as little mess and noise as possible and with a minimum of disturbance to adjoining premises and their tenants. He shall provide proper protection and provide, erect and remove when directed, any temporary tarpaulins that may be necessary during the progress of the works, all to the satisfaction of the principal agent. Water supply pipes and other piping that may be encountered and found necessary to disconnect or cut, shall be effectually stopped off or grubbed up and removed, and any new connections that may be necessary shall be made with proper fittings, to the satisfaction of the principal agent. Doors, fanlights, fittings, frames, linings, etc which are to be re-used shall be thoroughly overhauled before refixing including taking off, easing and rehanging, cramping up, re-wedging as required and making good cramps, dowels, etc, and easing, oiling, adjusting and repairing</p>			
			R
		Carried Forward	
<p>Section No. 2 Section 2 - Demolitions and Alterations Bill No. 1 ALTERATIONS Re-Solve Consulting</p>			

Brought Forward

R

DEMOLITIONS AND ALTERATIONS

DEMOLITIONS OF EXISTING TOILET STRUCTURES

2/1/1	Demolish existing pit toilet structures including hacking up and removing foundations and surface beds, doors, windows and door frames, ironmongery and plumbing fittings complete. All pits are to be filled with soil.	No	8
-------	--	----	---

2/1/2	Demolish existing ground slab (max strength and size, 25MPa and 10m2 respectively) with mesh reinforcement for pit toilets that have been abandoned. All pits are to be filled with soil.	No	8
-------	---	----	---

Refurbishment of existing 'Enviro Loo' toilet seats

2/1/3	Refurbish existing seats including fixing and/or replacement of seats, connector pans, toilet bowls, etc.	No	8
-------	---	----	---

Carried to Final Summary

R

Section No. 2
 Section 2 - Demolitions and Alterations
 Bill No. 1
 ALTERATIONS
Re-Solve Consulting

Item No		Quantity	Rate	Amount
	<p><u>SECTION 3</u></p> <p><u>BILL NO. 1</u></p> <p><u>EARTHWORKS (PROVISIONAL)</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Nature of ground</u></p> <p><u>Use "assumed to be" if no trial holes, soils investigations, etc have been carried out - discuss with engineer. Use "Trial holes indicate that" where the ground has been investigated by means of trial holes</u></p> <p><u>Nature of ground</u></p> <p><u>A soils investigation has been carried out on site by the engineer and the report is annexed to these bills of quantities. Descriptions of excavations shall be deemed to include all ground conditions classifiable as "earth" described in the above report and where conditions of a more difficult character are indicated these are separately measured</u></p> <p><u>Carting away of excavated material</u></p> <p><u>Descriptions of carting away of excavated material shall be deemed to include loading excavated material onto trucks directly from the excavations or, alternatively, from stock piles situated on the building site</u></p> <p><u>Filling</u></p>			
	Carried Forward		R	
	<p>Section No. 3 Section 3 - Staff Ablutions Bill No. 1 EARTHWORKS(PROVISIONAL) Re-Solve Consulting</p>			

Brought Forward				R
<u>Notwithstanding the reference to prescribed multiple handling in clause 1 page 6 of the Standard System of Measuring Building Work, prices for filling and backfilling shall include for all selection and any multiple handling of material</u>				
<u>Soil poisoning</u>				
<u>Ant and weed poisoning will be applied in accordance to SABS specifications by Registered and Approved Specialists who will issue a five (5) year guarantee. The contractor will only be paid for this items once they have produced the said certificate to the Principal Agent</u>				
<u>SITE CLEARANCE ETC</u>				
<u>Site clearance</u>				
3/1/1	Digging up and removing rubbish, debris, vegetation, hedges, shrubs and trees not exceeding 200mm girth, bush, etc	m2	86	
3/1/2	Stripping average 100mm thick layer of top soil and stockpiling on site	m2	86	
<u>EXCAVATION, FILLING, ETC</u>				
<u>Excavation in earth not exceeding 2m deep</u>				
3/1/3	Trenches	m3	41	
3/1/4	Pits	m3	40	
3/1/5	Thickening under aprons	m3	0.4	
<u>Extra over trench and hole excavations in earth for excavation in</u>				
3/1/6	Soft rock	m3	6	
3/1/7	Hard rock	m3	3	
Carried Forward				R
Section No. 3 Section 3 - Staff Ablutions Bill No. 1 EARTHWORKS(PROVISIONAL) Re-Solve Consulting				

Brought Forward			R
<u>Extra over all excavations for carting away</u>			
3/1/8	Surplus material from excavations on site to a dumping site to be located by the contractor	m3	63
<u>Risk of collapse of excavations</u>			
3/1/9	Sides of trench and hole excavations not exceeding 1,5m deep	m2	242
<u>Keeping excavations free of water</u>			
3/1/10	Keeping excavations free of all water other than subterranean water		Item
<u>Earth filling obtained from the excavations and /or prescribed stock piles on site including compacted to 93% Mod AASHTO density</u>			
3/1/11	Under floors, steps, paving, etc	m3	12
3/1/12	Backfilling to trenches, holes, etc	m3	18
<u>Compaction of surfaces</u>			
3/1/13	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density	m2	58
3/1/14	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density (Enviro Loo Tanks Pit)	m2	28
3/1/15	Ditto but to bottom of trenches and bases	m2	42
<u>Prescribed density tests on filling</u>			
3/1/16	Modified AASHTO Density	No	4
<u>SOIL POISONING</u>			
Carried Forward			R
Section No. 3 Section 3 - Staff Ablutions Bill No. 1 EARTHWORKS(PROVISIONAL) Re-Solve Consulting			

Brought Forward					
	<u>Weedkiller mixed in accordance to supplier's specifications</u>				R
3/1/17	To bottoms and sides of trenches, etc.	m2	198		
3/1/18	Under floors etc including forming and poisoning shallow furrows against foundation walls etc, filling in furrows and ramming(pits)	m2	113		
	<u>Soil insecticide</u>				
3/1/19	To bottoms and sides of trenches etc	m2	198		
3/1/20	Under floors etc including forming and poisoning shallow furrows against foundation walls etc, filling in furrows and ramming(pits)	m2	93		
Carried Forward to Summary of Section No. 3					R
Section No. 3					
Section 3 - Staff Ablutions					
Bill No. 1					
EARTHWORKS(PROVISIONAL)					
Re-Solve Consulting					

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 3</u>			
	<u>BILL NO. 2</u>			
	<u>CONCRETE, FORMWORK AND REINFORCEMENT</u>			
	For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades			
	<u>UNREINFORCED CONCRETE, ETC.</u>			
	<u>15MPa/19mm concrete</u>			
3/2/1	Surface blinding under footings and bases	m3	3	
3/2/2	Aprons cast in panels to falls	m3	2	
3/2/3	Extra over concrete in surface beds for thickening 85mm deep the bottom including all excavation, backfilling etc	m	26	
3/2/4	Extra over for concrete thickening in aprons size approximately 100mm deep, 400mm at top and tapering one side to 200mm at bottom, including all excavations, cart away, etc.	m	20	
	<u>25MPa/19mm concrete</u>			
3/2/5	Strip footings	m3	9	
3/2/6	Ramps	m3	2	
	<u>REINFORCED CONCRETE</u>			
	<u>25MPa/19mm concrete</u>			
3/2/7	Surface beds cast in panels on waterproofing.	m3	4	
3/2/8	Slabs (pits)	m3	4	
	Carried Forward			R
	Section No. 3 Section 3 - Staff Ablutions Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT Re-Solve Consulting			

Brought Forward

R

TEST CUBES

3/2/9	Allow for preparing a set of three concrete strength test cubes, each size 150 x 150 x 150mm, sending them to an approved Testing Laboratory for testing and paying all charges in connection therewith	Sets	4.0
-------	---	------	-----

CONCRETE SUNDRIES

Finishing top surfaces of concrete smooth with a wood float/steel trowel

3/2/10	Surface beds, slabs, etc	m2	67
3/2/11	Surface beds, slabs, etc (pits)	m2	25
3/2/12	Aprons to falls	m2	20

SMOOTH FORMWORK (DEGREE OF ACCURACY I)

Rough formwork to sides

3/2/13	Edges, risers, ends and reveals not exceeding 300mm high or wide	m	26
--------	--	---	----

REINFORCEMENT (PROVISIONAL)

Fabric Reinforcement

3/2/14	Mesh ref. No. 395 fabric reinforcement fixed horizontalt in surface beds etc.	m2	83
--------	---	----	----

Carried Forward to Summary of Section No. 3

R

Section No. 3
Section 3 - Staff Ablutions
Bill No. 2
CONCRETE, FORMWORK AND REINFORCEMENT
Re-Solve Consulting

Item No		Quantity	Rate	Amount
	<p><u>SECTION NO.3</u></p> <p><u>BILL NO.3</u></p> <p><u>MASONRY</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>BRICKWORK</u></p> <p><u>Sizes in descriptions</u></p> <p><u>Where sizes in descriptions are given in brick units, "one brick" shall represent the length and "half brick" the width of a brick</u></p> <p><u>Face bricks</u></p> <p><u>Bricks shall be ordered timeously to obtain uniformity in size and colour</u></p> <p><u>Pointing</u></p> <p><u>Descriptions of recessed pointing to fair face brickwork and face brickwork shall be deemed to include square recessed, hollow recessed, weathered pointing, etc</u></p> <p><u>FOUNDATIONS (PROVISIONAL)</u></p> <p><u>Brickwork of NFP bricks in class II mortar</u></p>			
3/3/1	One brick walls	m2	61	
	<p><u>FACE BRICKWORK</u></p>			
	Carried Forward			R
	<p>Section No. 3 Section 3 - Staff Ablutions Bill No. 3 MASONRY Re-Solve Consulting</p>			

Brought Forward

R

Face bricks (purchase price of R5 000.00/1000 delivered to site excluding VAT) pointed with flush horizontal and vertical joints

3/3/2	Extra over brickwork for face brickwork in foundations	m2	7
-------	--	----	---

SUPERSTRUCTURE

Brickwork of NFP bricks in class II mortar

3/3/3	Half brick walls	m2	8
-------	------------------	----	---

3/3/4	Half brick walls in beamfilling	m2	6
-------	---------------------------------	----	---

3/3/5	One brick walls	m2	77
-------	-----------------	----	----

FACE BRICKWORK

3/3/6	Extra over brickwork for face brickwork	m2	69
-------	---	----	----

3/3/7	Extra over brickwork for brick-on-edge header course lintel	m	10
-------	---	---	----

3/3/8	220mm Wide sill set sloping and slightly protecting outside	m	10
-------	---	---	----

3/3/9	Fair cutting fitting around pipe not exceeding 100mm	No	3
-------	--	----	---

3/3/10	Fair cutting fitting around pipe exceeding 100mm and not exceeding 200mm diameter	No	7
--------	---	----	---

BRICKWORK SUNDRIES

Brickwork reinforcement

3/3/11	75mm Wide reinforcement built in horizontally	m	8
--------	---	---	---

3/3/12	150mm Wide reinforcement built in horizontally	m	146
--------	--	---	-----

Galvanised wire ties etc

3/3/13	6mm Diameter roof tie 2m long with one end fixed to timber and other end built into brickwork	No	28
--------	---	----	----

Carried Forward

R

Section No. 3
Section 3 - Staff Ablutions
Bill No. 3
MASONRY
Re-Solve Consulting

Brought Forward

R

Turning pieces to lintels etc.

3/3/14	230mm Wide turning pieces	m	7	
--------	---------------------------	---	---	--

Prestressed fabricated lintels

3/3/15	110 x 75mm Lintels in lengths exceeding 3m and not exceeding 6m	m	23	
--------	---	---	----	--

Air bricks etc.

3/3/16	230 x 152mm terra-cotta vermin proofed louvered air brick	No	4	
--------	---	----	---	--

Carried Forward to Summary of Section No. 3

R

Section No. 3
 Section 3 - Staff Ablutions
 Bill No. 3
 MASONRY
Re-Solve Consulting

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 3</u>			
	<u>BILL NO.4</u>			
	<u>WATERPROOFING</u>			
	For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades			
	<u>DAMP-PROOFING OF WALLS AND FLOORS</u>			
	<u>One layer of 375 micron Consol Plastic Brikgrip DPC" embossed damp proof course</u>			
3/4/1	In walls	m2	78	
	<u>One layer of 250 micron "Consol Plastic USB Green" waterproof sheeting sealed at laps with "Gunplas Pressure Sensitive Tape"</u>			
3/4/2	Under surface beds	m2	110	
3/4/3	Under aprons and ramps	m2	2	
	<u>FLOOR AND WALL SEALERS</u>			
	<u>Secomastic non setting mastic sealant applied cold with a hand pressure caulking gun and leave perfectly watertight</u>			
3/4/4	Around steel windows and door frames	m	16	
	Carried Forward to Summary of Section No. 3			R
	Section No. 3			
	Section 3 - Staff Ablutions			
	Bill No. 4			
	WATERPROOFING			
	Re-Solve Consulting			

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 3</u>			
	<u>BILL NO.5</u>			
	<u>ROOF COVERINGS ETC</u>			
	For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades			
	<u>PROFILED METAL SHEETING AND ACCESSORIES</u>			
	<u>0,6mm "Kliplok" roof sheeting in chromadek finish fixed to timber purlins (elsewhere)</u>			
3/5/1	Roof covering with pitch not exceeding 25 degrees	m2	38	
	<u>ROOF AND WALL INSULATION</u>			
3/5/2	12" Thermal resistance sisalition laid on purlins	m2	38	
	<u>RAINWATER DISPOSAL</u>			
	<u>For preambles see "Model Preambles for Trades (2008 Edition)" and Supplementary preambles as specified in the Trades</u>			
	<u>Aluminium Zinc Seamless Gutters</u>			
3/5/3	100 x 100mm sandard rainwater gutters fixed with gutter brackets	m	9	
3/5/4	Extra over eaves gutter for stopped end	No	2	
3/5/5	75 x 100mm Diameter rainwater down pipes fixed to wall	m	6	
3/5/6	Extra over eaves gutter for outlet for 75 x 100mm down pipe	No	2	
3/5/7	Ditto .for shoe	No	2	
	Carried Forward to Summary of Section No. 3			R
	Section No. 3 Section 3 - Staff Ablutions Bill No. 5 ROOF COVERINGS ETC Re-Solve Consulting			

Item No		Quantity	Rate	Amount
	<p><u>SECTION NO. 3</u></p> <p><u>BILL NO. 6</u></p> <p><u>CARPENTRY AND JOINERY</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>ROOFS, ETC.</u></p> <p><u>Plate nailed timber roof truss construction</u></p>			
3/6/1	<p>Design manufacture and deliver on site plate nailed roof truss construction to Ablutions Block size 8 9000 x 3 964 mm overall on plan consisting of mono pitched trusses to suit with 350mm eaves overhang projecting including all necessary purlins runners bracing and cross bracing (wall plates elsewhere) all in accordance with suppliers and manufacturer's recommendations: Trusses are at maximum 110m centres. Roof covering is galvanised "IBR" roof sheeting (measured elsewhere) on 50 x 75mm purlins at 11m maximum centres. All timber to be sawn softwood in accordance with V4 or M4 as defined in SABS 563 or SABS 1245. Metal connector plates shall have a minimum yield strength of 228 MPa and a minimum ultimate tensile strength of 330 Mpa with hot-dip galvanised finish. All joints to be close fitted butt joints. Trusses shall be designed by a registered supplier of prefabricated trusses who shall issue an Engineers Certificate upon completion of the installation. The dimensions in the descriptions of the trusses are nominal and actual measurements are to be obtained on site before design or fabrication commences. Tenderers must study the roof plan and sections as attached to the back of these bills of quantities and must obtain prices from a qualified and registered roof truss supplier as no claims in this regard will be entertained.</p>	No	1	
3/6/2	Profit (As per rate build build up)		Item	
	Carried Forward			R
	<p>Section No. 3 Section 3 - Staff Ablutions Bill No. 6 CARPENTRY AND JOINERY Re-Solve Consulting</p>			

Brought Forward			R
3/6/3	Take delivery temporary store hoist in position and erect plate nailed timber roof trusses purlins gangboarding temporary and permanent bracing etc (measured on slope of roof)	Item	
<u>Sawn softwood</u>			
3/6/4	38 x 114mm Wall plates	m	28
<u>Sundries</u>			
3/6/5	Two coats creosote on sawn timbers	m2	35
3/6/6	6mm Diameter galvanised wire tie 3000mm girth wrapped around rafter and purlin with ends tied together	No	28
3/6/7	Hurricane clips	No	28
<u>EAVES, VERGES, ETC</u>			
<u>Pressed fibre-cement:</u>			
3/6/8	15 x 230mm Nutec Fascias and barge boards including galvanised steel H-profile jointing strips	m	26
<u>DOORS, ETC</u>			
<u>Wrought meranti doors hung to steel frames</u>			
3/6/9	44mm framed, ledged and braced door 877 x 2064mm high including external weather bar (D1)	No	2
3/6/10	44mm framed, ledged and braced door 813 x 1914mm high (door raised by 150mm from bottom) (D2)	No	4
3/6/11	44mm framed, ledged and braced door 915 x 2032mm high including external weather bar (disabled)	No	1
Carried Forward to Summary of Section No. 3			R
Section No. 3			
Section 3 - Staff Ablutions			
Bill No. 6			
CARPENTRY AND JOINERY			
Re-Solve Consulting			

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 3</u>			
	<u>BILL NO. 7</u>			
	<u>IRONMONGERY</u>			
	For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades			
	<u>HINGES, BOLTS, ETC</u>			
	<u>100mm Chrome plated "D" type handle 3 by solid brace hinges</u>			
	<u>CATCHES,CABIN HOOKS, ETC</u>			
3/7/1	100mm brace Cabin hook and eye including 70 x 70 x 20mm chamfered hardwood block twice oiled and plugged	No	2	
	<u>LOCKS</u>			
	<u>Approved</u>			
3/7/2	Three lever mortice lock set	No	3	
3/7/3	Indicator lock set	No	4	
3/7/4	Security double throw dead lock (no latch)	No	1	
	<u>HANDLES, ETC.</u>			
	<u>Aluminium Pull Handle</u>			
3/7/5	ASSA ABLOY Anodised Silver straight pull handle (Code: AL5515-300BBAS) with 300mm fixing centres.	No	6	
	<u>SUNDRIES</u>			
	Carried Forward			R
	Section No. 3 Section 3 - Staff Ablutions Bill No. 7 IRONMONGERY Re-Solve Consulting			

Brought Forward			R
<u>ASSA ABLOY</u>			
3/7/6	38mm Diameter rubber door stop plugged	No	6
<u>Vaal Paragon</u>			
3/7/7	32mm Type 9 back grab rail 800mm long plugged	No	1
3/7/8	32mm Type 8 side grab rail 900mm girth plugged	No	1
<u>LETTERS, NAMEPLATES, ETC</u>			
<u>Dorma:</u>			
3/7/9	DSS-130 Engraved "Male" information sign, plugged	No	1
3/7/10	DSS-130 Engraved "Female" information sign, plugged	No	1
3/7/11	DSS-133 Engraved "Disabled" information sign, plugged	No	1
<u>BATHROOM FITTINGS</u>			
<u>Sundries</u>			
<u>Kimberley-Clark or Similar</u>			
3/7/12	SQ2 code 405607B white none lockable toilet roll holder	No	5
<u>stainless Steel</u>			
3/7/13	Stainless steel mirror size: 350 x 400mm plugged to wall with chrome plated screws.	No	1
3/7/14	Brushed stainless steel body, rust resistant, she bin, approximately 330 x 280 x 180mm etc	No	4
Carried Forward to Summary of Section No. 3			R
Section No. 3			
Section 3 - Staff Ablutions			
Bill No. 7			
IRONMONGERY			
Re-Solve Consulting			

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 3</u>			
	<u>BILL NO. 8</u>			
	<u>METALWORK</u>			
	For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades			
	<u>WELDED SCREENS, GATES, ETC</u>			
	<u>Gates to external doors</u>			
3/8/1	Purpose made square hollow section mild steel single security gate and frame size to fit standard door, size 813 x 2032mm high	No	3	
3/8/2	Single gate and frame size to fit none standard door, size approximately 915 x 2032mm high (disable)	No	3	
	<u>PRESSED STEEL DOOR FRAMES</u>			
	<u>1,2mm Double rebated frames suitable for half brick walls</u>			
3/8/3	Frame for door size 813 x 1914mm high	No	4	
	<u>1,2mm Double rebated frames suitable for one brick walls</u>			
3/8/4	Frame for door size 914 x 2032mm high	No	1	
	<u>1,2mm Single rebate steel frame suitable for one brick wall</u>			
3/8/5	Frame for door size 813 x 2032mm high	No	2	
	<u>STEEL WINDOWS, DOORS, ETC</u>			
	Carried Forward			R
	Section No. 3 Section 3 - Staff Ablutions Bill No. 8 METALWORK Re-Solve Consulting			

	Brought Forward			R
	<u>Nty steel or similar approved school windows with standard burglar bars formed of 20 x 5mm thick flat bars to all sashes</u>			
3/8/6	Window type NE1, size 533 x 654mm high	No	7	
3/8/7	Window type NE7, size 1022 x 654mm high	No	3	
	<u>Sundries</u>			
	<u>Cage, etc</u>			
3/8/8	She bin cages, to fit 330 x 280 x 180mm width, she bin to be able to open, including pad lock and locking mechanism, complete, etc	No	4	
Carried Forward to Summary of Section No. 3				
Section No. 3 Section 3 - Staff Ablutions Bill No. 8 METALWORK Re-Solve Consulting				R

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 3</u>			
	<u>BILL NO.9</u>			
	<u>PLASTERING</u>			
	For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades			
	<u>GRANOLITHIC</u>			
	<u>Untinted granolithic on concrete</u>			
3/9/1	20mm Thick on floors	m2	35	
	<u>INTERNAL PLASTER</u>			
	<u>Cement plaster on brickwork or blockwork</u>			
3/9/2	On internal plastered walls(pits)	m2	75	
	<u>FLOOR AND WALLS SEALERS</u>			
	<u>Minimum two coats approved epoxy coat:</u>			
3/9/3	On floors in pits	m2	1	
3/9/4	On internal plastered walls in pits	m2	75	
	Carried Forward to Summary of Section No. 3			
	Section No. 3			
	Section 3 - Staff Ablutions			
	Bill No. 9			
	PLASTERING			
	Re-Solve Consulting			
			R	

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 3</u>			
	<u>BILL NO. 10</u>			
	<u>PLUMBING AND DRAINAGE(PROVISIONAL)</u>			
	For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades			
	<u>SANITARY FITTINGS</u>			
	<u>"Vaal" or similar and approved</u>			
3/10/1	Ceramic wall mounted wash hand basin, complete with all fittings and accesseries including cutting & making good wall & floor wherever required for disable toilets.	No	1	
	<u>SUPPLY AND INSTALL "ENVIRO-LOO" TOILET SYSTEMS</u>			
3/10/2	Supply and Install "Enviro-Loo" Industrial 1040 Model complete,installed strictly in accordance with manufacturers instructions, unit comprising of top unit and two x louvred inlets , drying plate , two x air inlets, standard toilet pan, seat and lid, 3500mm long outlet vent pipe, ventilation extraction unit fixed to wall with vent wall bracket, 1 bag mounting screws and organic starter, enzyme and toilet cleaner including all necessary inter connector piping between multiple tanks, emergency outlet piping,etc	No	4	
3/10/3	Supply and Erect disabled "Enviro-loo"Industrial 1040 Model set up and fixed complete as per manufacturers instructions, unit comprising of top unit and two x louvred inlets , drying plate , two x air inlets, paraplegic toilet pan, seat and lid, 3500mm long outlet vent pipe, ventilation extraction unit fixed to wall with vent wall bracket, 1 bag mounting screws and organic starter, enzyme and toilet cleaner including all necessary inter connector piping between multiple tanks, emergency outlet piping,etc	No	1	
	Carried Forward			R
	Section No. 3 Section 3 - Staff Ablutions Bill No. 10 PLUMBING AND DRAINAGE(PROVISIONAL) Re-Solve Consulting			

Brought Forward

R

3/10/4	Supply and Erect "Enviro-loo" Urinal Evaporative Tank system fixed complete as per manufacturers specification unit comprising of urinal evaporative tank , urinal bowls including brackets , 3500mm long outlet vent pipe , ventilation extraction unit fixed to wall with vent wall bracket, 1 bag mounting screws and organic starter, enzyme and toilet cleaner including all necessary piping, traps, etc	No	1
--------	--	----	---

PRECAST CONCRETE WASH HAND TROUGH

3/10/5	Standard SABS approved Pre-Cast Concrete Double Wash Trough, 1080 x 650 x 850mm high with support legs fitted with standard 3/4 Brass Garden Taps, fixed complete to berick wall, including all necessary pipework, including soak away as per 'Engineers detail'.	No	2
--------	--	----	---

SOIL DRAINAGE

uPVC pipes

3/10/6	110mm Pipes laid in and including trenches not exceeding 1m deep	m	25
--------	--	---	----

Extra over uPVC pipes for fittings

3/10/7	110mm Bend	No	5
--------	------------	----	---

3/10/8	110mm Junction	No	5
--------	----------------	----	---

uPVC gulleys

3/10/9	110mm Gulley not exceeding 750mm deep, including excavations, pre-cast concrete sorround etc.	No	3
--------	---	----	---

TRAPS ETC

Marley

3/10/10	40 x 300mm Sink combination for double bowl with deepseal "P" trap	No	3
---------	--	----	---

TAPS, VALVES, ETC

3/10/11	Cobra Watertech 15mm gate valve plugged	No	1
---------	---	----	---

Carried Forward

R

Section No. 3
Section 3 - Staff Ablutions
Bill No. 10
PLUMBING AND DRAINAGE(PROVISIONAL)
Re-Solve Consulting

Brought Forward			R
3/10/12	Cobra Watertech 15mm Elbow action pillar tap	No	2
<u>SANITARY PLUMBING</u>			
<u>uPVC pipes</u>			
3/10/13	50mm Pipes	m	30
<u>Extra over uPVC pipes for fittings</u>			
3/10/14	50mm Bend	No	3
3/10/15	50mm Access bend	No	3
3/10/16	50mm Junction	No	3
<u>WATER SUPPLIES</u>			
<u>Class 0 copper pipes</u>			
3/10/17	15mm Pipes	m	20
3/10/18	22mm Pipes	m	15
<u>Extra over class 0 copper pipes for capillary fittings</u>			
3/10/19	15mm Fittings	No	5
3/10/20	22mm Pipes	No	5
<u>TESTING</u>			
3/10/21	Allow for testing all drains, sanitary plumbing, water supplies and installation to the satisfaction of the Principle Agent.		Item
Carried Forward to Summary of Section No. 3			R
Section No. 3			
Section 3 - Staff Ablutions			
Bill No. 10			
PLUMBING AND DRAINAGE(PROVISIONAL)			
Re-Solve Consulting			

Item No	<u>SECTION NO. 3</u>	Quantity	Rate	Amount
	<u>BILL NO. 11</u>			
	<u>GLAZING</u>			
	For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades			
	<u>GLAZING TO STEEL WITH PUTTY</u>			
	<u>6.28mm Obscure safety glass</u>			
3/11/1	Panes not exceeding 0,1 m2	m2	4	
	Carried Forward to Summary of Section No. 3			R
	Section No. 3 Section 3 - Staff Ablutions Bill No. 11 GLAZING Re-Solve Consulting			

Item No		Quantity	Rate	Amount
	<p><u>SECTION NO.3</u></p> <p><u>BILL NO. 12</u></p> <p><u>PAINTWORK</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>PAINTWORK ETC TO NEW WORK</u></p> <p><u>PREPARATORY WORK TO EXISTING WORK</u></p> <p><u>Previously painted plastered surfaces</u></p> <p><u>Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and cracks shall be opened, filled with a suitable filler and finished smooth</u></p> <p><u>Previously painted metal surfaces</u></p> <p><u>Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal</u></p> <p><u>Previously painted wood surfaces</u></p> <p><u>Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth</u></p> <p><u>ON FIBRE-CEMENT</u></p> <p><u>Prepare and brush to remove all loose contaminations, apply one coat primer and two coats PVA emulsion paint</u></p>			
3/12/1	On fascias and barge boards	m2	28	
	Carried Forward			R
	<p>Section No. 3 Section 3 - Staff Ablutions Bill No. 12 PAINTWORK Re-Solve Consulting</p>			

Brought Forward

R

ON METAL

Prime and paint undercoat and 2 finishing coats in gloss enamel, colour TBC.

3/12/2 On door frames m2 20

Spot prining defects in pre-prime surface with zinc chromate primer and apply one universal undercoat and two coats EPWP. golden brown gloss enamel paint on steel

3/12/3 On windows with burglar bars m2 4

1 coat zinc chromate primer minimum and 2 coats gloss enamel (Exterior Quality)

3/12/4 On gates (Measured over the full flat area of both sides) m2 10

ON WOOD

Under coat and minimum 2 coats gloss enamel, colour TBC

3/12/5 On doors (External) m2 4

3/12/6 On doors (Internal) m2 6

Carried Forward to Summary of Section No. 3

R

Section No. 3
Section 3 - Staff Ablutions
Bill No. 12
PAINTWORK
Re-Solve Consulting

Section No. 3

Section 3 - Staff Ablutions

SECTION SUMMARY - Section 3 - Staff Ablutions

Bill No		Page No	Amount
3/1	EARTHWORKS(PROVISIONAL)	32	
3/2	CONCRETE, FORMWORK AND REINFORCEMENT	34	
3/3	MASONRY	37	
3/4	WATERPROOFING	38	
3/5	ROOF COVERINGS ETC	39	
3/6	CARPENTRY AND JOINERY	41	
3/7	IRONMONGERY	43	
3/8	METALWORK	45	
3/9	PLASTERING	46	
3/10	PLUMBING AND DRAINAGE(PROVISIONAL)	49	
3/11	GLAZING	50	
3/12	PAINTWORK	52	

Carried to Final Summary

R

Section No. 3
 Section 3 - Staff Ablutions
Re-Solve Consulting

Item No		Quantity	Rate	Amount
	<p><u>SECTION 4</u></p> <p><u>BILL NO. 1</u></p> <p><u>EARTHWORKS (PROVISIONAL)</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Nature of ground</u></p> <p><u>Use "assumed to be" if no trial holes, soils investigations, etc have been carried out - discuss with engineer. Use "Trial holes indicate that" where the ground has been investigated by means of trial holes</u></p> <p><u>Nature of ground</u></p> <p><u>A soils investigation has been carried out on site by the engineer and the report is annexed to these bills of quantities. Descriptions of excavations shall be deemed to include all ground conditions classifiable as "earth" described in the above report and where conditions of a more difficult character are indicated these are separately measured</u></p> <p><u>Carting away of excavated material</u></p> <p><u>Descriptions of carting away of excavated material shall be deemed to include loading excavated material onto trucks directly from the excavations or, alternatively, from stock piles situated on the building site</u></p> <p><u>Filling</u></p>			
	Carried Forward		R	
	<p>Section No. 4 Section 4 - Girls Block of 5 Bill No. 1 EARTHWORKS(PROVISIONAL) Re-Solve Consulting</p>			

Brought Forward				R
<u>Notwithstanding the reference to prescribed multiple handling in clause 1 page 6 of the Standard System of Measuring Building Work, prices for filling and backfilling shall include for all selection and any multiple handling of material</u>				
<u>Soil poisoning</u>				
<u>Ant and weed poisoning will be applied in accordance to SABS specifications by Registered and Approved Specialists who will issue a five (5) year guarantee. The contractor will only be paid for this items once they have produced the said certificate to the Principal Agent</u>				
<u>SITE CLEARANCE ETC</u>				
<u>Site clearance</u>				
4/1/1	Digging up and removing rubbish, debris, vegetation, hedges, shrubs and trees not exceeding 200mm girth, bush, etc	m2	79	
4/1/2	Stripping average 100mm thick layer of top soil and stockpiling on site	m2	79	
<u>EXCAVATION, FILLING, ETC</u>				
<u>Excavation in earth not exceeding 2m deep</u>				
4/1/3	Trenches	m3	39	
4/1/4	Pits	m3	40	
4/1/5	Thickening under aprons	m3	0.4	
<u>Extra over trench and hole excavations in earth for excavation in</u>				
4/1/6	Soft rock	m3	5	
4/1/7	Hard rock	m3	3	
Carried Forward				R
Section No. 4 Section 4 - Girls Block of 5 Bill No. 1 EARTHWORKS(PROVISIONAL) Re-Solve Consulting				

Brought Forward			R
<u>Extra over all excavations for carting away</u>			
4/1/8	Surplus material from excavations on site to a dumping site to be located by the contractor	m3	62
<u>Risk of collapse of excavations</u>			
4/1/9	Sides of trench and hole excavations not exceeding 1,5m deep	m2	245
<u>Keeping excavations free of water</u>			
4/1/10	Keeping excavations free of all water other than subterranean water		Item
<u>Earth filling obtained from the excavations and /or prescribed stock piles on site including compacted to 93% Mod AASHTO density</u>			
4/1/11	Under floors, steps, paving, etc	m3	12
4/1/12	Backfilling to trenches, holes, etc	m3	17
<u>Compaction of surfaces</u>			
4/1/13	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density	m2	52
4/1/14	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density (Enviro Loo Tanks Pit)	m2	28
4/1/15	Ditto but to bottom of trenches and bases	m2	38
<u>Prescribed density tests on filling</u>			
4/1/16	Modified AASHTO Density	No	
<u>SOIL POISONING</u>			
Carried Forward			R
Section No. 4 Section 4 - Girls Block of 5 Bill No. 1 EARTHWORKS(PROVISIONAL) Re-Solve Consulting			

Brought Forward					
	<u>Weedkiller mixed in accordance to supplier's specifications</u>				R
4/1/17	To bottoms and sides of trenches, etc.	m2	197		
4/1/18	Under floors etc including forming and poisoning shallow furrows against foundation walls etc, filling in furrows and ramming(pits)	m2	103		
	<u>Soil insecticide</u>				
4/1/19	To bottoms and sides of trenches etc	m2	197		
4/1/20	Under floors etc including forming and poisoning shallow furrows against foundation walls etc, filling in furrows and ramming(pits)	m2	84		
Carried Forward to Summary of Section No. 4					R
Section No. 4 Section 4 - Girls Block of 5 Bill No. 1 EARTHWORKS(PROVISIONAL) Re-Solve Consulting					

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 4</u>			
	<u>BILL NO. 2</u>			
	<u>CONCRETE, FORMWORK AND REINFORCEMENT</u>			
	For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades			
	<u>UNREINFORCED CONCRETE, ETC.</u>			
	<u>15MPa/19mm concrete</u>			
4/2/1	Surface blinding under footings and bases	m3	3	
4/2/2	Aprons cast in panels to falls	m3	2	
4/2/3	Extra over concrete in surface beds for thickening 85mm deep the bottom including all excavation, backfilling etc	m	23	
4/2/4	Extra over for concrete thickening in aprons size approximately 100mm deep, 400mm at top and tapering one side to 200mm at bottom, including all excavations, cart away, etc.	m	20	
	<u>25MPa/19mm concrete</u>			
4/2/5	Strip footings	m3	8	
4/2/6	Ramps	m3	2	
	<u>REINFORCED CONCRETE</u>			
	<u>25MPa/19mm concrete</u>			
4/2/7	Surface beds cast in panels on waterproofing.	m3	3	
4/2/8	Slabs (pits)	m3	4	
	Carried Forward			R
	Section No. 4 Section 4 - Girls Block of 5 Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT Re-Solve Consulting			

Brought Forward

R

TEST CUBES

4/2/9	Allow for preparing a set of three concrete strength test cubes, each size 150 x 150 x 150mm, sending them to an approved Testing Laboratory for testing and paying all charges in connection therewith	Sets	4.0
-------	---	------	-----

CONCRETE SUNDRIES

Finishing top surfaces of concrete smooth with a wood float/steel trowel

4/2/10	Surface beds, slabs, etc	m2	59
4/2/11	Surface beds, slabs, etc (pits)	m2	25
4/2/12	Aprons to falls	m2	19

SMOOTH FORMWORK (DEGREE OF ACCURACY I)

Rough formwork to sides

4/2/13	Edges, risers, ends and reveals not exceeding 300mm high or wide	m	23
--------	--	---	----

REINFORCEMENT (PROVISIONAL)

Fabric Reinforcement

4/2/14	Mesh ref. No. 395 fabric reinforcement fixed horizontalt in surface beds etc.	m2	77
--------	---	----	----

Carried Forward to Summary of Section No. 4

R

Section No. 4
Section 4 - Girls Block of 5
Bill No. 2
CONCRETE, FORMWORK AND REINFORCEMENT
Re-Solve Consulting

Item No		Quantity	Rate	Amount
	<p><u>SECTION NO.4</u></p> <p><u>BILL NO.3</u></p> <p><u>MASONRY</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>BRICKWORK</u></p> <p><u>Sizes in descriptions</u></p> <p><u>Where sizes in descriptions are given in brick units, "one brick" shall represent the length and "half brick" the width of a brick</u></p> <p><u>Face bricks</u></p> <p><u>Bricks shall be ordered timeously to obtain uniformity in size and colour</u></p> <p><u>Pointing</u></p> <p><u>Descriptions of recessed pointing to fair face brickwork and face brickwork shall be deemed to include square recessed, hollow recessed, weathered pointing, etc</u></p> <p><u>FOUNDATIONS (PROVISIONAL)</u></p> <p><u>Brickwork of NFP bricks in class II mortar</u></p>			
4/3/1	One brick walls	m2	64	
	<p><u>FACE BRICKWORK</u></p>			
	Carried Forward			R
	<p>Section No. 4 Section 4 - Girls Block of 5 Bill No. 3 MASONRY Re-Solve Consulting</p>			

Brought Forward			R
<u>Face bricks (purchase price of R5 000.00/1000 delivered to site excluding VAT) pointed with flush horizontal and vertical joints</u>			
4/3/2	Extra over brickwork for face brickwork in foundations	m2	5
<u>SUPERSTRUCTURE</u>			
<u>Brickwork of NFP bricks in class II mortar</u>			
4/3/3	Half brick walls	m2	11
4/3/4	Half brick walls in beamfilling	m2	6
4/3/5	One brick walls	m2	72
<u>FACE BRICKWORK</u>			
4/3/6	Extra over brickwork for face brickwork	m2	69
4/3/7	Extra over brickwork for brick-on-edge header course lintel	m	9
4/3/8	110mm Wide sill set level and slightly projecting	m	
4/3/9	220mm Wide sill set sloping and slightly protecting outside	m	9
4/3/10	Fair cutting fitting around pipe not exceeding 100mm	No	
4/3/11	Fair cutting fitting around pipe exceeding 100mm and not exceeding 200mm diameter	No	
<u>BRICKWORK SUNDRIES</u>			
<u>Brickwork reinforcement</u>			
4/3/12	75mm Wide reinforcement built in horizontally	m	11
4/3/13	150mm Wide reinforcement built in horizontally	m	139
Carried Forward			R
Section No. 4 Section 4 - Girls Block of 5 Bill No. 3 MASONRY Re-Solve Consulting			

Brought Forward					
				R	
<u>Galvanised wire ties etc</u>					
4/3/14	6mm Diameter roof tie 2m long with one end fixed to timber and other end built into brickwork	No	28		
<u>Turning pieces to lintels etc.</u>					
4/3/15	115mm Wide turning pieces	m			
4/3/16	230mm Wide turning pieces	m	6		
<u>Prestressed fabricated lintels</u>					
4/3/17	110 x 75mm Lintels in lengths exceeding 3m and not exceeding 6m	m	22		
<u>Air bricks etc.</u>					
4/3/18	230 x 152mm terra-cotta vermin proofed louvered air brick	No	2		
Carried Forward to Summary of Section No. 4				R	
Section No. 4					
Section 4 - Girls Block of 5					
Bill No. 3					
MASONRY					
Re-Solve Consulting					

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 4</u>			
	<u>BILL NO.4</u>			
	<u>WATERPROOFING</u>			
	For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades			
	<u>DAMP-PROOFING OF WALLS AND FLOORS</u>			
	<u>One layer of 375 micron Consol Plastic Brikgrip DPC" embossed damp proof course</u>			
4/4/1	In walls	m2	80	
	<u>One layer of 250 micron "Consol Plastic USB Green" waterproof sheeting sealed at laps with "Gunplas Pressure Sensitive Tape"</u>			
4/4/2	Under surface beds	m2	100	
4/4/3	Under aprons and ramps	m2	2	
	<u>FLOOR AND WALL SEALERS</u>			
	<u>Secomastic non setting mastic sealant applied cold with a hand pressure caulking gun and leave perfectly watertight</u>			
4/4/4	Around steel windows and door frames	m	15	
	Carried Forward to Summary of Section No. 4			
	Section No. 4			
	Section 4 - Girls Block of 5			
	Bill No. 4			
	WATERPROOFING			
	Re-Solve Consulting			
				R

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 4</u>			
	<u>BILL NO.5</u>			
	<u>ROOF COVERINGS ETC</u>			
	For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades			
	<u>PROFILED METAL SHEETING AND ACCESSORIES</u>			
	<u>0,6mm "Kliplok" roof sheeting in chromadek finish fixed to timber purlins (elsewhere)</u>			
4/5/1	Roof covering with pitch not exceeding 25 degrees	m2	34	
	<u>ROOF AND WALL INSULATION</u>			
4/5/2	12" Thermal resistance sisalition laid on purlins	m2	34	
	<u>RAINWATER DISPOSAL</u>			
	<u>For preambles see "Model Preambles for Trades (2008 Edition)" and Supplementary preambles as specified in the Trades</u>			
	<u>Aluminium Zinc Seamless Gutters</u>			
4/5/3	100 x 100mm sandard rainwater gutters fixed with gutter brackets	m	8	
4/5/4	Extra over eaves gutter for stopped end	No	2	
4/5/5	75 x 100mm Diameter rainwater down pipes fixed to wall	m	6	
4/5/6	Extra over eaves gutter for outlet for 75 x 100mm down pipe	No	2	
4/5/7	Ditto .for shoe	No	2	
	Carried Forward to Summary of Section No. 4			R
	Section No. 4			
	Section 4 - Girls Block of 5			
	Bill No. 5			
	ROOF COVERINGS ETC			
	Re-Solve Consulting			

Item No		Quantity	Rate	Amount
	<p><u>SECTION NO. 4</u></p> <p><u>BILL NO. 6</u></p> <p><u>CARPENTRY AND JOINERY</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>ROOFS, ETC.</u></p> <p><u>Plate nailed timber roof truss construction</u></p>			
4/6/1	<p>Design manufacture and deliver on site plate nailed roof truss construction to Ablutions Block size 7 750 x 3 964 mm overall on plan consisting of mono pitched trusses to suit with 350mm eaves overhang projecting including all necessary purlins runners bracing and cross bracing (wall plates elsewhere) all in accordance with suppliers and manufacturer's recommendations: Trusses are at maximum 110m centres. Roof covering is galvanised "IBR" roof sheeting (measured elsewhere) on 50 x 75mm purlins at 11m maximum centres. All timber to be sawn softwood in accordance with V4 or M4 as defined in SABS 563 or SABS 1245. Metal connector plates shall have a minimum yield strength of 228 MPa and a minimum ultimate tensile strength of 330 Mpa with hot-dip galvanised finish. All joints to be close fitted butt joints. Trusses shall be designed by a registered supplier of prefabricated trusses who shall issue an Engineers Certificate upon completion of the installation. The dimensions in the descriptions of the trusses are nominal and actual measurements are to be obtained on site before design or fabrication commences. Tenderers must study the roof plan and sections as attached to the back of these bills of quantities and must obtain prices from a qualified and registered roof truss supplier as no claims in this regard will be entertained.</p>	No	1	
4/6/2	<p>Profit (As per rate build build up)</p>	Item		
	Carried Forward			R
	<p>Section No. 4 Section 4 - Girls Block of 5 Bill No. 6 CARPENTRY AND JOINERY Re-Solve Consulting</p>			

Brought Forward			R
4/6/3	Take delivery temporary store hoist in position and erect plate nailed timber roof trusses purlins gangboarding temporary and permanent bracing etc (measured on slope of roof)	Item	
<u>Sawn softwood</u>			
4/6/4	38 x 114mm Wall plates	m	28
<u>Sundries</u>			
4/6/5	Two coats creosote on sawn timbers	m2	31
4/6/6	6mm Diameter galvanised wire tie 3000mm girth wrapped around rafter and purlin with ends tied together	No	28
4/6/7	Hurricane clips	No	28
<u>EAVES, VERGES, ETC</u>			
<u>Pressed fibre-cement:</u>			
4/6/8	15 x 230mm Nutec Fascias and barge boards including galvanised steel H-profile jointing strips	m	23
<u>DOORS, ETC</u>			
<u>Wrought meranti doors hung to steel frames</u>			
4/6/9	44mm framed, ledged and braced door 877 x 2064mm high including external weather bar (D1)	No	1
4/6/10	44mm framed, ledged and braced door 813 x 1914mm high (door raised by 150mm from bottom) (D2)	No	5
4/6/11	44mm framed, ledged and braced door 915 x 2032mm high including external weather bar (disabled)	No	1
Carried Forward to Summary of Section No. 4			R
Section No. 4			
Section 4 - Girls Block of 5			
Bill No. 6			
CARPENTRY AND JOINERY			
Re-Solve Consulting			

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 4</u>			
	<u>BILL NO. 7</u>			
	<u>IRONMONGERY</u>			
	For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades			
	<u>HINGES, BOLTS, ETC</u>			
	<u>100mm Chrome plated "D" type handle 3 by solid brace hinges</u>			
	<u>CATCHES,CABIN HOOKS, ETC</u>			
4/7/1	100mm brace Cabin hook and eye including 70 x 70 x 20mm chamfered hardwood block twice oiled and plugged	No	1	
	<u>LOCKS</u>			
	<u>Approved</u>			
4/7/2	Three lever mortice lock set	No	2	
4/7/3	Indicator lock set	No	5	
4/7/4	Security double throw dead lock (no latch)	No	2	
	<u>HANDLES, ETC.</u>			
	<u>Aluminium Pull Handle</u>			
4/7/5	ASSA ABLOY Anodised Silver straight pull handle (Code: AL5515-300BBAS) with 300mm fixing centres.	No	6	
	<u>SUNDRIES</u>			
	Carried Forward			R
	Section No. 4 Section 4 - Girls Block of 5 Bill No. 7 IRONMONGERY Re-Solve Consulting			

Brought Forward

R

ASSA ABLOY

4/7/6	38mm Diameter rubber door stop plugged	No	6	
-------	--	----	---	--

Vaal Paragon

4/7/7	32mm Type 9 back grab rail 800mm long plugged	No	1	
-------	---	----	---	--

4/7/8	32mm Type 8 side grab rail 900mm girth plugged	No	1	
-------	--	----	---	--

LETTERS, NAMEPLATES, ETC

Dorma:

4/7/9	DSS-130 Engraved "Female" information sign, plugged	No	1	
-------	---	----	---	--

4/7/10	DSS-133 Engraved "Disabled" information sign, plugged	No	1	
--------	---	----	---	--

BATHROOM FITTINGS

Sundries

Kimberley-Clark or Similar

4/7/11	SQ2 code 405607B white none lockable toilet roll holder	No	6	
--------	---	----	---	--

stainless Steel

4/7/12	Stainless steel mirror size: 350 x 400mm plugged to wall with chrome plated screws.	No	1	
--------	---	----	---	--

4/7/13	Brushed stainless steel body, rust resistant, she bin, approximately 330 x 280 x 180mm etc	No	6	
--------	--	----	---	--

Carried Forward to Summary of Section No. 4

R

Section No. 4
Section 4 - Girls Block of 5
Bill No. 7
IRONMONGERY
Re-Solve Consulting

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 4</u>			
	<u>BILL NO. 8</u>			
	<u>METALWORK</u>			
	For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades			
	<u>WELDED SCREENS, GATES, ETC</u>			
	<u>Gates to external doors</u>			
4/8/1	Purpose made square hollow section mild steel single security gate and frame size to fit standard door, size 813 x 2032mm high	No	2	
4/8/2	Single gate and frame size to fit none standard door, size approximately 915 x 2032mm high (disable)	No	2	
	<u>PRESSED STEEL DOOR FRAMES</u>			
	<u>1,2mm Double rebated frames suitable for half brick walls</u>			
4/8/3	Frame for door size 813 x 1914mm high	No	5	
	<u>1,2mm Double rebated frames suitable for one brick walls</u>			
4/8/4	Frame for door size 914 x 2032mm high	No	1	
	<u>1,2mm Single rebate steel frame suitable for one brick wall</u>			
4/8/5	Frame for door size 813 x 2032mm high	No	1	
	<u>STEEL WINDOWS, DOORS, ETC</u>			
	Carried Forward			R
	Section No. 4 Section 4 - Girls Block of 5 Bill No. 8 METALWORK Re-Solve Consulting			

	Brought Forward				
	<u>Nty steel or similar approved school windows with standard burglar bars formed of 20 x 5mm thick flat bars to all sashes</u>				R
4/8/6	Window type NE1, size 533 x 654mm high	No	6		
4/8/7	Window type NE7, size 1022 x 654mm high	No	3		
	<u>Sundries</u>				
	<u>Cage, etc</u>				
4/8/8	She bin cages, to fit 330 x 280 x 180mm width, she bin to be able to open, including pad lock and locking mechanism, complete, etc	No	6		
	Carried Forward to Summary of Section No. 4				R
	Section No. 4				
	Section 4 - Girls Block of 5				
	Bill No. 8				
	METALWORK				
	Re-Solve Consulting				

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 4</u>			
	<u>BILL NO.9</u>			
	<u>PLASTERING</u>			
	For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades			
	<u>GRANOLITHIC</u>			
	<u>Untinted granolithic on concrete</u>			
4/9/1	20mm Thick on floors	m2	31	
	<u>INTERNAL PLASTER</u>			
	<u>Cement plaster on brickwork or blockwork</u>			
4/9/2	On internal plastered walls(pits)	m2	75	
	<u>FLOOR AND WALLS SEALERS</u>			
	<u>Minimum two coats approved epoxy coat:</u>			
4/9/3	On floors in pits	m2	1	
4/9/4	On internal plastered walls in pits	m2	75	
	Carried Forward to Summary of Section No. 4			R
	Section No. 4			
	Section 4 - Girls Block of 5			
	Bill No. 9			
	PLASTERING			
	Re-Solve Consulting			

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 4</u>			
	<u>BILL NO. 10</u>			
	<u>PLUMBING AND DRAINAGE(PROVISIONAL)</u>			
	For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades			
	<u>SANITARY FITTINGS</u>			
	<u>"Vaal" or similar and approved</u>			
4/10/1	Ceramic wall mounted wash hand basin, complete with all fittings and accesseries including cutting & making good wall & floor wherever required for disable toilets.	No	1	
	<u>SUPPLY AND INSTALL "ENVIRO-LOO" TOILET SYSTEMS</u>			
4/10/2	Supply and Install "Enviro-Loo" Industrial 1040 Model complete,installed strictly in accordance with manufacturers instructions, unit comprising of top unit and two x louvred inlets , drying plate , two x air inlets, standard toilet pan, seat and lid, 3500mm long outlet vent pipe, ventilation extraction unit fixed to wall with vent wall bracket, 1 bag mounting screws and organic starter, enzyme and toilet cleaner including all necessary inter connector piping between multiple tanks, emergency outlet piping,etc	No	5	
4/10/3	Supply and Erect disabled "Enviro-loo"Industrial 1040 Model set up and fixed complete as per manufacturers instructions, unit comprising of top unit and two x louvred inlets , drying plate , two x air inlets, paraplegic toilet pan, seat and lid, 3500mm long outlet vent pipe, ventilation extraction unit fixed to wall with vent wall bracket, 1 bag mounting screws and organic starter, enzyme and toilet cleaner including all necessary inter connector piping between multiple tanks, emergency outlet piping,etc	No	1	
	Carried Forward			R
	Section No. 4 Section 4 - Girls Block of 5 Bill No. 10 PLUMBING AND DRAINAGE(PROVISIONAL) Re-Solve Consulting			

Brought Forward

R

PRECAST CONCRETE WASH HAND TROUGH

4/10/4	Standard SABS approved Pre-Cast Concrete Double Wash Trough, 1080 x 650 x 850mm high with support legs fitted with standard 3/4 Brass Garden Taps, fixed complete to berick wall, including all necessary pipework, including soak away as per 'Engineers detail'.	No	1
--------	--	----	---

SOIL DRAINAGE

uPVC pipes

4/10/5	110mm Pipes laid in and including trenches not exceeding 1m deep	m	30
--------	--	---	----

Extra over uPVC pipes for fittings

4/10/6	110mm Bend	No	6
--------	------------	----	---

4/10/7	110mm Junction	No	6
--------	----------------	----	---

uPVC gulleys

4/10/8	110mm Gully not exceeding 750mm deep, including excavations, pre-cast concrete surround etc.	No	2
--------	--	----	---

TRAPS ETC

Marley

4/10/9	40 x 300mm Sink combination for double bowl with deepseal "P" trap	No	2
--------	--	----	---

TAPS, VALVES, ETC

4/10/10	Cobra Watertech 15mm gate valve plugged	No	1
---------	---	----	---

4/10/11	Cobra Watertech 15mm Elbow action pillar tap	No	1
---------	--	----	---

SANITARY PLUMBING

uPVC pipes

4/10/12	50mm Pipes	m	10
---------	------------	---	----

Carried Forward

R

Section No. 4
Section 4 - Girls Block of 5
Bill No. 10
PLUMBING AND DRAINAGE(PROVISIONAL)
Re-Solve Consulting

		Brought Forward		R
		<u>Extra over uPVC pipes for fittings</u>		
4/10/13	50mm Bend	No	2	
4/10/14	50mm Access bend	No	2	
4/10/15	50mm Junction	No	2	
		<u>WATER SUPPLIES</u>		
		<u>Class 0 copper pipes</u>		
4/10/16	15mm Pipes	m	20	
4/10/17	22mm Pipes	m	18	
		<u>Extra over class 0 copper pipes for capillary fittings</u>		
4/10/18	15mm Fittings	No	3	
4/10/19	22mm Pipes	No	3	
		<u>TESTING</u>		
4/10/20	Allow for testing all drains, sanitary plumbing, water supplies and installtion to the satisfaction of the Principle Agent.		Item	
Carried Forward to Summary of Section No. 4				R
Section No. 4				
Section 4 - Girls Block of 5				
Bill No. 10				
PLUMBING AND DRAINAGE(PROVISIONAL)				
Re-Solve Consulting				

Item No		Quantity	Rate	Amount
	<p><u>SECTION NO. 4</u></p> <p><u>BILL NO. 11</u></p> <p><u>GLAZING</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>GLAZING TO STEEL WITH PUTTY</u></p> <p><u>6.28mm Obscure safety glass</u></p>			
4/11/1	Panes not exceeding 0,1 m2	m2	4	
	Carried Forward to Summary of Section No. 4			R
	Section No. 4 Section 4 - Girls Block of 5 Bill No. 11 GLAZING Re-Solve Consulting			

Item No		Quantity	Rate	Amount
	<p><u>SECTION NO.4</u></p> <p><u>BILL NO. 12</u></p> <p><u>PAINTWORK</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>PAINTWORK ETC TO NEW WORK</u></p> <p><u>PREPARATORY WORK TO EXISTING WORK</u></p> <p><u>Previously painted plastered surfaces</u></p> <p><u>Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and cracks shall be opened, filled with a suitable filler and finished smooth</u></p> <p><u>Previously painted metal surfaces</u></p> <p><u>Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal</u></p> <p><u>Previously painted wood surfaces</u></p> <p><u>Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth</u></p> <p><u>ON FIBRE-CEMENT</u></p> <p><u>Prepare and brush to remove all loose contaminations, apply one coat primer and two coats PVA emulsion paint</u></p>			
4/12/1	On fascias and barge boards	m2	6	
	Carried Forward			R
	<p>Section No. 4 Section 4 - Girls Block of 5 Bill No. 12 PAINTWORK Re-Solve Consulting</p>			

Brought Forward

R

ON METAL

Prime and paint undercoat and 2 finishing coats in gloss enamel, colour TBC.

4/12/2 On door frames m2 19

Spot prining defects in pre-prime surface with zinc chromate primer and apply one universal undercoat and two coats EPWP. golden brown gloss enamel paint on steel

4/12/3 On windows with burglar bars m2 4

1 coat zinc chromate primer minimum and 2 coats gloss enamel (Exterior Quality)

4/12/4 On gates (Measured over the full flat area of both sides) m2 7

ON WOOD

Under coat and minimum 2 coats gloss enamel, colour TBC

4/12/5 On doors (External) m2 2

4/12/6 On doors (Internal) m2 8

Carried Forward to Summary of Section No. 4

R

Section No. 4
Section 4 - Girls Block of 5
Bill No. 12
PAINTWORK
Re-Solve Consulting

Section No. 4

Section 4 - Girls Block of 5

SECTION SUMMARY - Section 4 - Girls Block of 5

Bill No		Page No	Amount
4/1	EARTHWORKS(PROVISIONAL)	57	
4/2	CONCRETE, FORMWORK AND REINFORCEMENT	59	
4/3	MASONRY	62	
4/4	WATERPROOFING	63	
4/5	ROOF COVERINGS ETC	64	
4/6	CARPENTRY AND JOINERY	66	
4/7	IRONMONGERY	68	
4/8	METALWORK	70	
4/9	PLASTERING	71	
4/10	PLUMBING AND DRAINAGE(PROVISIONAL)	74	
4/11	GLAZING	75	
4/12	PAINTWORK	77	

Carried to Final Summary

R

Section No. 4
 Section 4 - Girls Block of 5
Re-Solve Consulting

Item No		Quantity	Rate	Amount
	<p><u>SECTION 5</u></p> <p><u>BILL NO. 1</u></p> <p><u>EARTHWORKS (PROVISIONAL)</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Nature of ground</u></p> <p><u>Use "assumed to be" if no trial holes, soils investigations, etc have been carried out - discuss with engineer. Use "Trial holes indicate that" where the ground has been investigated by means of trial holes</u></p> <p><u>Nature of ground</u></p> <p><u>A soils investigation has been carried out on site by the engineer and the report is annexed to these bills of quantities. Descriptions of excavations shall be deemed to include all ground conditions classifiable as "earth" described in the above report and where conditions of a more difficult character are indicated these are separately measured</u></p> <p><u>Carting away of excavated material</u></p> <p><u>Descriptions of carting away of excavated material shall be deemed to include loading excavated material onto trucks directly from the excavations or, alternatively, from stock piles situated on the building site</u></p> <p><u>Filling</u></p>			
	Carried Forward		R	
	<p>Section No. 5 Section 5 - Boys Block of 2 Bill No. 1 EARTHWORKS(PROVISIONAL) Re-Solve Consulting</p>			

Brought Forward							
<u>Notwithstanding the reference to prescribed multiple handling in clause 1 page 6 of the Standard System of Measuring Building Work, prices for filling and backfilling shall include for all selection and any multiple handling of material</u>							
<u>Soil poisoning</u>							
<u>Ant and weed poisoning will be applied in accordance to SABS specifications by Registered and Approved Specialists who will issue a five (5) year guarantee. The contractor will only be paid for this items once they have produced the said certificate to the Principal Agent</u>							
<u>SITE CLEARANCE ETC</u>							
<u>Site clearance</u>							
5/1/1	Digging up and removing rubbish, debris, vegetation, hedges, shrubs and trees not exceeding 200mm girth, bush, etc	m2		70			
5/1/2	Stripping average 100mm thick layer of top soil and stockpiling on site	m2		70			
<u>EXCAVATION, FILLING, ETC</u>							
<u>Excavation in earth not exceeding 2m deep</u>							
5/1/3	Trenches	m3		30			
5/1/4	Pits	m3		29			
5/1/5	Thickening under aprons	m3		0.4			
<u>Extra over trench and hole excavations in earth for excavation in</u>							
5/1/6	Soft rock	m3		4			
5/1/7	Hard rock	m3		2			
Carried Forward							R
Section No. 5 Section 5 - Boys Block of 2 Bill No. 1 EARTHWORKS(PROVISIONAL) Re-Solve Consulting							

Brought Forward			R
<u>Extra over all excavations for carting away</u>			
5/1/8	Surplus material from excavations on site to a dumping site to be located by the contractor	m3	46
<u>Risk of collapse of excavations</u>			
5/1/9	Sides of trench and hole excavations not exceeding 1,5m deep	m2	183
<u>Keeping excavations free of water</u>			
5/1/10	Keeping excavations free of all water other than subterranean water		Item
<u>Earth filling obtained from the excavations and /or prescribed stock piles on site including compacted to 93% Mod AASHTO density</u>			
5/1/11	Under floors, steps, paving, etc	m3	10
5/1/12	Backfilling to trenches, holes, etc	m3	13
<u>Compaction of surfaces</u>			
5/1/13	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density	m2	50
5/1/14	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density (Enviro Loo Tanks Pit)	m2	20
5/1/15	Ditto but to bottom of trenches and bases	m2	29
<u>Prescribed density tests on filling</u>			
5/1/16	Modified AASHTO Density	No	4
<u>SOIL POISONING</u>			
Carried Forward			R
Section No. 5 Section 5 - Boys Block of 2 Bill No. 1 EARTHWORKS(PROVISIONAL) Re-Solve Consulting			

Brought Forward					
	<u>Weedkiller mixed in accordance to supplier's specifications</u>				R
5/1/17	To bottoms and sides of trenches, etc.	m2	150		
5/1/18	Under floors etc including forming and poisoning shallow furrows against foundation walls etc, filling in furrows and ramming(pits)	m2	90		
	<u>Soil insecticide</u>				
5/1/19	To bottoms and sides of trenches etc	m2	150		
5/1/20	Under floors etc including forming and poisoning shallow furrows against foundation walls etc, filling in furrows and ramming(pits)	m2	70		
Carried Forward to Summary of Section No. 5					R
Section No. 5 Section 5 - Boys Block of 2 Bill No. 1 EARTHWORKS(PROVISIONAL) Re-Solve Consulting					

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 5</u>			
	<u>BILL NO. 2</u>			
	<u>CONCRETE, FORMWORK AND REINFORCEMENT</u>			
	For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades			
	<u>UNREINFORCED CONCRETE, ETC.</u>			
	<u>15MPa/19mm concrete</u>			
5/2/1	Surface blinding under footings and bases	m3	2	
5/2/2	Aprons cast in panels to falls	m3	2	
5/2/3	Extra over concrete in surface beds for thickening 85mm deep the bottom including all excavation, backfilling etc	m	22	
5/2/4	Extra over for concrete thickening in aprons size approximately 100mm deep, 400mm at top and tapering one side to 200mm at bottom, including all excavations, cart away, etc.	m	21	
	<u>25MPa/19mm concrete</u>			
5/2/5	Strip footings	m3	6	
5/2/6	Ramps	m3	2	
	<u>REINFORCED CONCRETE</u>			
	<u>25MPa/19mm concrete</u>			
5/2/7	Surface beds cast in panels on waterproofing.	m3	3	
5/2/8	Slabs (pits)	m3	3	
	Carried Forward			R
	Section No. 5 Section 5 - Boys Block of 2 Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT Re-Solve Consulting			

Brought Forward

R

TEST CUBES

5/2/9	Allow for preparing a set of three concrete strength test cubes, each size 150 x 150 x 150mm, sending them to an approved Testing Laboratory for testing and paying all charges in connection therewith	Sets	4.0
-------	---	------	-----

CONCRETE SUNDRIES

Finishing top surfaces of concrete smooth with a wood float/steel trowel

5/2/10	Surface beds, slabs, etc	m2	52
5/2/11	Surface beds, slabs, etc (pits)	m2	18
5/2/12	Aprons to falls	m2	20

SMOOTH FORMWORK (DEGREE OF ACCURACY I)

Rough formwork to sides

5/2/13	Edges, risers, ends and reveals not exceeding 300mm high or wide	m	22
--------	--	---	----

REINFORCEMENT (PROVISIONAL)

Fabric Reinforcement

5/2/14	Mesh ref. No. 395 fabric reinforcement fixed horizontalt in surface beds etc.	m2	68
--------	---	----	----

Carried Forward to Summary of Section No. 5

R

Section No. 5
 Section 5 - Boys Block of 2
 Bill No. 2
 CONCRETE, FORMWORK AND REINFORCEMENT
Re-Solve Consulting

Item No		Quantity	Rate	Amount
	<p><u>SECTION NO.5</u></p> <p><u>BILL NO.3</u></p> <p><u>MASONRY</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>BRICKWORK</u></p> <p><u>Sizes in descriptions</u></p> <p><u>Where sizes in descriptions are given in brick units, "one brick" shall represent the length and "half brick" the width of a brick</u></p> <p><u>Face bricks</u></p> <p><u>Bricks shall be ordered timeously to obtain uniformity in size and colour</u></p> <p><u>Pointing</u></p> <p><u>Descriptions of recessed pointing to fair face brickwork and face brickwork shall be deemed to include square recessed, hollow recessed, weathered pointing, etc</u></p> <p><u>FOUNDATIONS (PROVISIONAL)</u></p> <p><u>Brickwork of NFP bricks in class II mortar</u></p>			
5/3/1	One brick walls	m2	49	
	<p><u>FACE BRICKWORK</u></p>			
	Carried Forward			R
	<p>Section No. 5 Section 5 - Boys Block of 2 Bill No. 3 MASONRY Re-Solve Consulting</p>			

Brought Forward			R
<u>Face bricks (purchase price of R5 000.00/1000 delivered to site excluding VAT) pointed with flush horizontal and vertical joints</u>			
5/3/2	Extra over brickwork for face brickwork in foundations	m2	4
<u>SUPERSTRUCTURE</u>			
<u>Brickwork of NFP bricks in class II mortar</u>			
5/3/3	Half brick walls	m2	7
5/3/4	Half brick walls in beamfilling	m2	5
5/3/5	One brick walls	m2	63
<u>FACE BRICKWORK</u>			
5/3/6	Extra over brickwork for face brickwork	m2	59
5/3/7	Extra over brickwork for brick-on-edge header course lintel	m	7
5/3/8	220mm Wide sill set sloping and slightly protecting outside	m	7
5/3/9	Fair cutting fitting around pipe not exceeding 100mm	No	4
5/3/10	Fair cutting fitting around pipe exceeding 100mm and not exceeding 200mm diameter	No	3
<u>BRICKWORK SUNDRIES</u>			
<u>Brickwork reinforcement</u>			
5/3/11	75mm Wide reinforcement built in horizontally	m	7
5/3/12	150mm Wide reinforcement built in horizontally	m	113
<u>Galvanised wire ties etc</u>			
5/3/13	6mm Diameter roof tie 2m long with one end fixed to timber and other end built into brickwork	No	24
Carried Forward			R
Section No. 5 Section 5 - Boys Block of 2 Bill No. 3 MASONRY Re-Solve Consulting			

Brought Forward

R

Turning pieces to lintels etc.

5/3/14	230mm Wide turning pieces	m	5	
--------	---------------------------	---	---	--

Prestressed fabricated lintels

5/3/15	110 x 75mm Lintels in lengths exceeding 3m and not exceeding 6m	m	14	
--------	---	---	----	--

Air bricks etc.

5/3/16	230 x 152mm terra-cotta vermin proofed louvered air brick	No	2	
--------	---	----	---	--

Carried Forward to Summary of Section No. 5

Section No. 5
 Section 5 - Boys Block of 2
 Bill No. 3
 MASONRY
Re-Solve Consulting

R

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 5</u>			
	<u>BILL NO.4</u>			
	<u>WATERPROOFING</u>			
	For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades			
	<u>DAMP-PROOFING OF WALLS AND FLOORS</u>			
	<u>One layer of 375 micron Consol Plastic Brikgrip DPC" embossed damp proof course</u>			
5/4/1	In walls	m2	66	
	<u>One layer of 250 micron "Consol Plastic USB Green" waterproof sheeting sealed at laps with "Gunplas Pressure Sensitive Tape"</u>			
5/4/2	Under surface beds	m2	88	
5/4/3	Under aprons and ramps	m2	2	
	<u>FLOOR AND WALL SEALERS</u>			
	<u>Secomastic non setting mastic sealant applied cold with a hand pressure caulking gun and leave perfectly watertight</u>			
5/4/4	Around steel windows and door frames	m	10	
	Carried Forward to Summary of Section No. 5			R
	Section No. 5			
	Section 5 - Boys Block of 2			
	Bill No. 4			
	WATERPROOFING			
	Re-Solve Consulting			

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 5</u>			
	<u>BILL NO.5</u>			
	<u>ROOF COVERINGS ETC</u>			
	For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades			
	<u>PROFILED METAL SHEETING AND ACCESSORIES</u>			
	<u>0,6mm "Kliplok" roof sheeting in chromadek finish fixed to timber purlins (elsewhere)</u>			
5/5/1	Roof covering with pitch not exceeding 25 degrees	m2	30	
	<u>ROOF AND WALL INSULATION</u>			
5/5/2	12" Thermal resistance sisalition laid on purlins	m2	30	
	<u>RAINWATER DISPOSAL</u>			
	<u>For preambles see "Model Preambles for Trades (2008 Edition)" and Supplementary preambles as specified in the Trades</u>			
	<u>Aluminium Zinc Seamless Gutters</u>			
5/5/3	100 x 100mm sandard rainwater gutters fixed with gutter brackets	m	7	
5/5/4	Extra over eaves gutter for stopped end	No	2	
5/5/5	75 x 100mm Diameter rainwater down pipes fixed to wall	m	6	
5/5/6	Extra over eaves gutter for outlet for 75 x 100mm down pipe	No	2	
5/5/7	Ditto .for shoe	No	2	
	Carried Forward to Summary of Section No. 5			R
	Section No. 5 Section 5 - Boys Block of 2 Bill No. 5 ROOF COVERINGS ETC Re-Solve Consulting			

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 5</u>			
	<u>BILL NO. 6</u>			
	<u>CARPENTRY AND JOINERY</u>			
	For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades			
	<u>ROOFS, ETC.</u>			
	<u>Plate nailed timber roof truss construction</u>			
5/6/1	Design manufacture and deliver on site plate nailed roof truss construction to Ablutions Block size 6 767 x 3 964 mm overall on plan consisting of mono pitched trusses to suit with 350mm eaves overhang projecting including all necessary purlins runners bracing and cross bracing (wall plates elsewhere) all in accordance with suppliers and manufacturer's recommendations: Trusses are at maximum 110m centres. Roof covering is galvanised "IBR" roof sheeting (measured elsewhere) on 50 x 75mm purlins at 11m maximum centres. All timber to be sawn softwood in accordance with V4 or M4 as defined in SABS 563 or SABS 1245. Metal connector plates shall have a minimum yield strength of 228 MPa and a minimum ultimate tensile strength of 330 Mpa with hot-dip galvanised finish. All joints to be close fitted butt joints. Trusses shall be designed by a registered supplier of prefabricated trusses who shall issue an Engineers Certificate upon completion of the installation. The dimensions in the descriptions of the trusses are nominal and actual measurements are to be obtained on site before design or fabrication commences. Tenderers must study the roof plan and sections as attached to the back of these bills of quantities and must obtain prices from a qualified and registered roof truss supplier as no claims in this regard will be entertained.	No	1	
5/6/2	Profit (As per rate build build up)		Item	
	Carried Forward			R
	Section No. 5 Section 5 - Boys Block of 2 Bill No. 6 CARPENTRY AND JOINERY Re-Solve Consulting			

Brought Forward			R
5/6/3	Take delivery temporary store hoist in position and erect plate nailed timber roof trusses purlins gangboarding temporary and permanent bracing etc (measured on slope of roof)	Item	
<u>Sawn softwood</u>			
5/6/4	38 x 114mm Wall plates	m	24
<u>Sundries</u>			
5/6/5	Two coats creosote on sawn timbers	m2	27
5/6/6	6mm Diameter galvanised wire tie 3000mm girth wrapped around rafter and purlin with ends tied together	No	24
5/6/7	Hurricane clips	No	24
<u>EAVES, VERGES, ETC</u>			
<u>Pressed fibre-cement:</u>			
5/6/8	15 x 230mm Nutec Fascias and barge boards including galvanised steel H-profile jointing strips	m	21
<u>DOORS, ETC</u>			
<u>Wrought meranti doors hung to steel frames</u>			
5/6/9	44mm framed, ledged and braced door 877 x 2064mm high including external weather bar (D1)	No	1
5/6/10	44mm framed, ledged and braced door 813 x 1914mm high (door raised by 150mm from bottom) (D2)	No	2
5/6/11	44mm framed, ledged and braced door 915 x 2032mm high including external weather bar (disabled)	No	1
Carried Forward to Summary of Section No. 5			R
Section No. 5			
Section 5 - Boys Block of 2			
Bill No. 6			
CARPENTRY AND JOINERY			
Re-Solve Consulting			

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 5</u>			
	<u>BILL NO. 7</u>			
	<u>IRONMONGERY</u>			
	For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades			
	<u>HINGES, BOLTS, ETC</u>			
	<u>100mm Chrome plated "D" type handle 3 by solid brace hinges</u>			
	<u>CATCHES,CABIN HOOKS, ETC</u>			
5/7/1	100mm brace Cabin hook and eye including 70 x 70 x 20mm chamfered hardwood block twice oiled and plugged	No	1	
	<u>LOCKS</u>			
	<u>Approved</u>			
5/7/2	Three lever mortice lock set	No	2	
5/7/3	Indicator lock set	No	2	
5/7/4	Security double throw dead lock (no latch)	No	2	
	<u>HANDLES, ETC.</u>			
	<u>Aluminium Pull Handle</u>			
5/7/5	ASSA ABLOY Anodised Silver straight pull handle (Code: AL5515-300BBAS) with 300mm fixing centres.	No	3	
	<u>SUNDRIES</u>			
	Carried Forward			R
	Section No. 5 Section 5 - Boys Block of 2 Bill No. 7 IRONMONGERY Re-Solve Consulting			

Brought Forward			R
<u>ASSA ABLOY</u>			
5/7/6	38mm Diameter rubber door stop plugged	No	3
<u>Vaal Paragon</u>			
5/7/7	32mm Type 9 back grab rail 800mm long plugged	No	1
5/7/8	32mm Type 8 side grab rail 900mm girth plugged	No	1
<u>LETTERS, NAMEPLATES, ETC</u>			
<u>Dorma:</u>			
5/7/9	DSS-130 Engraved "Male" information sign, plugged	No	1
5/7/10	DSS-133 Engraved "Disabled" information sign, plugged	No	1
<u>BATHROOM FITTINGS</u>			
<u>Sundries</u>			
<u>Kimberley-Clark or Similar</u>			
5/7/11	SQ2 code 405607B white none lockable toilet roll holder	No	3
<u>stainless Steel</u>			
5/7/12	Stainless steel mirror size: 350 x 400mm plugged to wall with chrome plated screws.	No	1
Carried Forward to Summary of Section No. 5			R
Section No. 5			
Section 5 - Boys Block of 2			
Bill No. 7			
IRONMONGERY			
Re-Solve Consulting			

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 5</u>			
	<u>BILL NO. 8</u>			
	<u>METALWORK</u>			
	For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades			
	<u>WELDED SCREENS, GATES, ETC</u>			
	<u>Gates to external doors</u>			
5/8/1	Purpose made square hollow section mild steel single security gate and frame size to fit standard door, size 813 x 2032mm high	No	2	
5/8/2	Single gate and frame size to fit none standard door, size approximately 915 x 2032mm high (disable)	No	2	
	<u>PRESSED STEEL DOOR FRAMES</u>			
	<u>1,2mm Double rebated frames suitable for half brick walls</u>			
5/8/3	Frame for door size 813 x 1914mm high	No	2	
	<u>1,2mm Double rebated frames suitable for one brick walls</u>			
5/8/4	Frame for door size 914 x 2032mm high	No	1	
	<u>1,2mm Single rebate steel frame suitable for one brick wall</u>			
5/8/5	Frame for door size 813 x 2032mm high	No	1	
	<u>STEEL WINDOWS, DOORS, ETC</u>			
	Carried Forward			R
	Section No. 5 Section 5 - Boys Block of 2 Bill No. 8 METALWORK Re-Solve Consulting			

		Brought Forward		R
		<u>Nty steel or similar approved school windows with standard burglar bars formed of 20 x 5mm thick flat bars to all sashes</u>		
5/8/6	Window type NE1, size 533 x 654mm high	No	5	
5/8/7	Window type NE7, size 1022 x 654mm high	No	2	
Carried Forward to Summary of Section No. 5				R
Section No. 5				
Section 5 - Boys Block of 2				
Bill No. 8				
METALWORK				
Re-Solve Consulting				

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 5</u>			
	<u>BILL NO.9</u>			
	<u>PLASTERING</u>			
	For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades			
	<u>GRANOLITHIC</u>			
	<u>Untinted granolithic on concrete</u>			
5/9/1	20mm Thick on floors	m2	27	
	<u>INTERNAL PLASTER</u>			
	<u>Cement plaster on brickwork or blockwork</u>			
5/9/2	On internal plastered walls(pits)	m2	54	
	<u>FLOOR AND WALLS SEALERS</u>			
	<u>Minimum two coats approved epoxy coat:</u>			
5/9/3	On floors in pits	m2	1	
5/9/4	On internal plastered walls in pits	m2	54	
	Carried Forward to Summary of Section No. 5			
	Section No. 5			
	Section 5 - Boys Block of 2			
	Bill No. 9			
	PLASTERING			
	Re-Solve Consulting			
			R	

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 5</u>			
	<u>BILL NO. 10</u>			
	<u>PLUMBING AND DRAINAGE(PROVISIONAL)</u>			
	For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades			
	<u>SANITARY FITTINGS</u>			
	<u>"Vaal" or similar and approved</u>			
5/10/1	Ceramic wall mounted wash hand basin, complete with all fittings and accessories including cutting & making good wall & floor wherever required for disable toilets.	No	1	
	<u>SUPPLY AND INSTALL "ENVIRO-LOO" TOILET SYSTEMS</u>			
5/10/2	Supply and Install "Enviro-Loo" Industrial 1040 Model complete,installed strictly in accordance with manufacturers instructions, unit comprising of top unit and two x louvred inlets , drying plate , two x air inlets, standard toilet pan, seat and lid, 3500mm long outlet vent pipe, ventilation extraction unit fixed to wall with vent wall bracket, 1 bag mounting screws and organic starter, enzyme and toilet cleaner including all necessary inter connector piping between multiple tanks, emergency outlet piping,etc	No	2	
5/10/3	Supply and Erect disabled "Enviro-loo"Industrial 1040 Model set up and fixed complete as per manufacturers instructions, unit comprising of top unit and two x louvred inlets , drying plate , two x air inlets, paraplegic toilet pan, seat and lid, 3500mm long outlet vent pipe, ventilation extraction unit fixed to wall with vent wall bracket, 1 bag mounting screws and organic starter, enzyme and toilet cleaner including all necessary inter connector piping between multiple tanks, emergency outlet piping,etc	No	1	
	Carried Forward			R
	Section No. 5 Section 5 - Boys Block of 2 Bill No. 10 PLUMBING AND DRAINAGE(PROVISIONAL) Re-Solve Consulting			

Brought Forward

R

5/10/4	Supply and Erect "Enviro-loo" Urinal Evaporative Tank system fixed complete as per manufacturers specification unit comprising of urinal evaporative tank , urinal bowls including brackets , 3500mm long outlet vent pipe , ventilation extraction unit fixed to wall with vent wall bracket, 1 bag mounting screws and organic starter, enzyme and toilet cleaner including all necessary piping, traps, etc	No	3
--------	--	----	---

PRECAST CONCRETE WASH HAND TROUGH

5/10/5	Standard SABS approved Pre-Cast Concrete Double Wash Trough, 1080 x 650 x 850mm high with support legs fitted with standard 3/4 Brass Garden Taps, fixed complete to berick wall, including all necessary pipework, including soak away as per 'Engineers detail'.	No	1
--------	--	----	---

SOIL DRAINAGE

uPVC pipes

5/10/6	110mm Pipes laid in and including trenches not exceeding 1m deep	m	15
--------	--	---	----

Extra over uPVC pipes for fittings

5/10/7	110mm Bend	No	3
--------	------------	----	---

5/10/8	110mm Junction	No	3
--------	----------------	----	---

uPVC gulleys

5/10/9	110mm Gulley not exceeding 750mm deep, including excavations, pre-cast concrete sorround etc.	No	2
--------	---	----	---

TRAPS ETC

Marley

5/10/10	40 x 300mm Sink combination for double bowl with deepseal "P" trap	No	2
---------	--	----	---

TAPS, VALVES, ETC

5/10/11	Cobra Watertech 15mm gate valve plugged	No	1
---------	---	----	---

Carried Forward

R

Section No. 5
Section 5 - Boys Block of 2
Bill No. 10
PLUMBING AND DRAINAGE(PROVISIONAL)
Re-Solve Consulting

Brought Forward			R
5/10/12	Cobra Watertech 15mm Elbow action pillar tap	No	1
<u>SANITARY PLUMBING</u>			
<u>uPVC pipes</u>			
5/10/13	50mm Pipes	m	15
<u>Extra over uPVC pipes for fittings</u>			
5/10/14	50mm Bend	No	3
5/10/15	50mm Access bend	No	3
5/10/16	50mm Junction	No	3
<u>WATER SUPPLIES</u>			
<u>Class 0 copper pipes</u>			
5/10/17	15mm Pipes	m	20
5/10/18	22mm Pipes	m	18
<u>Extra over class 0 copper pipes for capillary fittings</u>			
5/10/19	15mm Fittings	No	3
5/10/20	22mm Pipes	No	3
<u>TESTING</u>			
5/10/21	Allow for testing all drains, sanitary plumbing, water supplies and installtion to the satisfaction of the Principle Agent.		Item
Carried Forward to Summary of Section No. 5			R
Section No. 5			
Section 5 - Boys Block of 2			
Bill No. 10			
PLUMBING AND DRAINAGE(PROVISIONAL)			
Re-Solve Consulting			

Item No		Quantity	Rate	Amount
	<p><u>SECTION NO. 5</u></p> <p><u>BILL NO. 11</u></p> <p><u>GLAZING</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>GLAZING TO STEEL WITH PUTTY</u></p> <p><u>6.28mm Obscure safety glass</u></p>			
5/11/1	Panes not exceeding 0,1 m2	m2	3	
	Carried Forward to Summary of Section No. 5			R
	Section No. 5 Section 5 - Boys Block of 2 Bill No. 11 GLAZING Re-Solve Consulting			

Item No		Quantity	Rate	Amount
	<p><u>SECTION NO.5</u></p> <p><u>BILL NO. 12</u></p> <p><u>PAINTWORK</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>PAINTWORK ETC TO NEW WORK</u></p> <p><u>PREPARATORY WORK TO EXISTING WORK</u></p> <p><u>Previously painted plastered surfaces</u></p> <p><u>Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and cracks shall be opened, filled with a suitable filler and finished smooth</u></p> <p><u>Previously painted metal surfaces</u></p> <p><u>Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal</u></p> <p><u>Previously painted wood surfaces</u></p> <p><u>Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth</u></p> <p><u>ON FIBRE-CEMENT</u></p> <p><u>Prepare and brush to remove all loose contaminations, apply one coat primer and two coats PVA emulsion paint</u></p>			
5/12/1	On fascias and barge boards	m2	6	
	Carried Forward			R
	<p>Section No. 5 Section 5 - Boys Block of 2 Bill No. 12 PAINTWORK Re-Solve Consulting</p>			

Brought Forward

R

ON METAL

Prime and paint undercoat and 2 finishing coats in gloss enamel, colour TBC.

5/12/2 On door frames m2 10

Spot prining defects in pre-prime surface with zinc chromate primer and apply one universal undercoat and two coats EPWP. golden brown gloss enamel paint on steel

5/12/3 On windows with burglar bars m2 3

1 coat zinc chromate primer minimum and 2 coats gloss enamel (Exterior Quality)

5/12/4 On gates (Measured over the full flat area of both sides) m2 7

ON WOOD

Under coat and minimum 2 coats gloss enamel, colour TBC

5/12/5 On doors (External) m2 2

5/12/6 On doors (Internal) m2 3

Carried Forward to Summary of Section No. 5

R

Section No. 5
 Section 5 - Boys Block of 2
 Bill No. 12
 PAINTWORK
 Re-Solve Consulting

Section No. 5

Section 5 - Boys Block of 2

SECTION SUMMARY - Section 5 - Boys Block of 2

Bill No		Page No	Amount
5/1	EARTHWORKS(PROVISIONAL)	82	
5/2	CONCRETE, FORMWORK AND REINFORCEMENT	84	
5/3	MASONRY	87	
5/4	WATERPROOFING	88	
5/5	ROOF COVERINGS ETC	89	
5/6	CARPENTRY AND JOINERY	91	
5/7	IRONMONGERY	93	
5/8	METALWORK	95	
5/9	PLASTERING	96	
5/10	PLUMBING AND DRAINAGE(PROVISIONAL)	99	
5/11	GLAZING	100	
5/12	PAINTWORK	102	

Carried to Final Summary

R

Section No. 5
 Section 5 - Boys Block of 2
Re-Solve Consulting

Item No		Quantity	Rate	Amount
	<p><u>SECTION 6</u></p> <p><u>BILL NO. 1</u></p> <p><u>EARTHWORKS (PROVISIONAL)</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Nature of ground</u></p> <p><u>Use "assumed to be" if no trial holes, soils investigations, etc have been carried out - discuss with engineer. Use "Trial holes indicate that" where the ground has been investigated by means of trial holes</u></p> <p><u>Nature of ground</u></p> <p><u>A soils investigation has been carried out on site by the engineer and the report is annexed to these bills of quantities. Descriptions of excavations shall be deemed to include all ground conditions classifiable as "earth" described in the above report and where conditions of a more difficult character are indicated these are separately measured</u></p> <p><u>Carting away of excavated material</u></p> <p><u>Descriptions of carting away of excavated material shall be deemed to include loading excavated material onto trucks directly from the excavations or, alternatively, from stock piles situated on the building site</u></p> <p><u>Filling</u></p>			
	Carried Forward		R	
	<p>Section No. 6 Section 6 - GR B1 Bill No. 1 EARTHWORKS(PROVISIONAL) Re-Solve Consulting</p>			

Brought Forward				R
<u>Notwithstanding the reference to prescribed multiple handling in clause 1 page 6 of the Standard System of Measuring Building Work, prices for filling and backfilling shall include for all selection and any multiple handling of material</u>				
<u>Soil poisoning</u>				
<u>Ant and weed poisoning will be applied in accordance to SABS specifications by Registered and Approved Specialists who will issue a five (5) year guarantee. The contractor will only be paid for this items once they have produced the said certificate to the Principal Agent</u>				
<u>SITE CLEARANCE ETC</u>				
<u>Site clearance</u>				
6/1/1	Digging up and removing rubbish, debris, vegetation, hedges, shrubs and trees not exceeding 200mm girth, bush, etc	m2	53	
6/1/2	Stripping average 100mm thick layer of top soil and stockpiling on site	m2	53	
<u>EXCAVATION, FILLING, ETC</u>				
<u>Excavation in earth not exceeding 2m deep</u>				
6/1/3	Trenches	m3	27	
6/1/4	Pits	m3	23	
6/1/5	Thickening under aprons	m3	0.3	
<u>Extra over trench and hole excavations in earth for excavation in</u>				
6/1/6	Soft rock	m3	3	
6/1/7	Hard rock	m3	2	
Carried Forward				R
Section No. 6 Section 6 - GR B1 Bill No. 1 EARTHWORKS(PROVISIONAL) Re-Solve Consulting				

Brought Forward			R
<u>Extra over all excavations for carting away</u>			
6/1/8	Surplus material from excavations on site to a dumping site to be located by the contractor	m3	38
<u>Risk of collapse of excavations</u>			
6/1/9	Sides of trench and hole excavations not exceeding 1,5m deep	m2	161
<u>Keeping excavations free of water</u>			
6/1/10	Keeping excavations free of all water other than subterranean water		Item
<u>Earth filling obtained from the excavations and /or prescribed stock piles on site including compacted to 93% Mod AASHTO density</u>			
6/1/11	Under floors, steps, paving, etc	m3	8
6/1/12	Backfilling to trenches, holes, etc	m3	12
<u>Compaction of surfaces</u>			
6/1/13	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density	m2	38
6/1/14	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density (Enviro Loo Tanks Pit)	m2	17
6/1/15	Ditto but to bottom of trenches and bases	m2	25
<u>Prescribed density tests on filling</u>			
6/1/16	Modified AASHTO Density	No	4
<u>SOIL POISONING</u>			
Carried Forward			R
Section No. 6 Section 6 - GR B1 Bill No. 1 EARTHWORKS(PROVISIONAL) Re-Solve Consulting			

Brought Forward					
<u>Weedkiller mixed in accordance to supplier's specifications</u>					R
6/1/17	To bottoms and sides of trenches, etc.	m2	137		
6/1/18	Under floors etc including forming and poisoning shallow furrows against foundation walls etc, filling in furrows and ramming(pits)	m2	66		
<u>Soil insecticide</u>					
6/1/19	To bottoms and sides of trenches etc	m2	137		
6/1/20	Under floors etc including forming and poisoning shallow furrows against foundation walls etc, filling in furrows and ramming(pits)	m2	49		
Carried Forward to Summary of Section No. 6					R
Section No. 6					
Section 6 - GR B1					
Bill No. 1					
EARTHWORKS(PROVISIONAL)					
Re-Solve Consulting					

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 6</u>			
	<u>BILL NO. 2</u>			
	<u>CONCRETE, FORMWORK AND REINFORCEMENT</u>			
	For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades			
	<u>UNREINFORCED CONCRETE, ETC.</u>			
	<u>15MPa/19mm concrete</u>			
6/2/1	Surface blinding under footings and bases	m3	2	
6/2/2	Aprons cast in panels to falls	m3	2	
6/2/3	Extra over concrete in surface beds for thickening 85mm deep the bottom including all excavation, backfilling etc	m	17	
6/2/4	Extra over for concrete thickening in aprons size approximately 100mm deep, 400mm at top and tapering one side to 200mm at bottom, including all excavations, cart away, etc.	m	16	
	<u>25MPa/19mm concrete</u>			
6/2/5	Strip footings	m3	5	
6/2/6	Ramps	m3	2	
	<u>REINFORCED CONCRETE</u>			
	<u>25MPa/19mm concrete</u>			
6/2/7	Surface beds cast in panels on waterproofing.	m3	2	
6/2/8	Slabs (pits)	m3	2	
	Carried Forward			R
	Section No. 6 Section 6 - GR B1 Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT Re-Solve Consulting			

Brought Forward

R

TEST CUBES

6/2/9	Allow for preparing a set of three concrete strength test cubes, each size 150 x 150 x 150mm, sending them to an approved Testing Laboratory for testing and paying all charges in connection therewith	Sets	4.0
-------	---	------	-----

CONCRETE SUNDRIES

Finishing top surfaces of concrete smooth with a wood float/steel trowel

6/2/10	Surface beds, slabs, etc	m2	34
6/2/11	Surface beds, slabs, etc (pits)	m2	14
6/2/12	Aprons to falls	m2	18

SMOOTH FORMWORK (DEGREE OF ACCURACY I)

Rough formwork to sides

6/2/13	Edges, risers, ends and reveals not exceeding 300mm high or wide	m	17
--------	--	---	----

REINFORCEMENT (PROVISIONAL)

Fabric Reinforcement

6/2/14	Mesh ref. No. 395 fabric reinforcement fixed horizontalt in surface beds etc.	m2	52
--------	---	----	----

Carried Forward to Summary of Section No. 6

R

Section No. 6
Section 6 - GR B1
Bill No. 2
CONCRETE, FORMWORK AND REINFORCEMENT
Re-Solve Consulting

Item No		Quantity	Rate	Amount
	<p><u>SECTION NO.6</u></p> <p><u>BILL NO.3</u></p> <p><u>MASONRY</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>BRICKWORK</u></p> <p><u>Sizes in descriptions</u></p> <p><u>Where sizes in descriptions are given in brick units, "one brick" shall represent the length and "half brick" the width of a brick</u></p> <p><u>Face bricks</u></p> <p><u>Bricks shall be ordered timeously to obtain uniformity in size and colour</u></p> <p><u>Pointing</u></p> <p><u>Descriptions of recessed pointing to fair face brickwork and face brickwork shall be deemed to include square recessed, hollow recessed, weathered pointing, etc</u></p> <p><u>FOUNDATIONS (PROVISIONAL)</u></p> <p><u>Brickwork of NFP bricks in class II mortar</u></p>			
6/3/1	One brick walls	m2	46	
	<p><u>FACE BRICKWORK</u></p>			
	Carried Forward			R
	<p>Section No. 6 Section 6 - GR B1 Bill No. 3 MASONRY Re-Solve Consulting</p>			

Brought Forward			R
<u>Face bricks (purchase price of R5 000.00/1000 delivered to site excluding VAT) pointed with flush horizontal and vertical joints</u>			
6/3/2	Extra over brickwork for face brickwork in foundations	m2	3
<u>SUPERSTRUCTURE</u>			
<u>Brickwork of NFP bricks in class II mortar</u>			
6/3/3	Half brick walls	m2	1
6/3/4	Half brick walls in beamfilling	m2	3
6/3/5	One brick walls	m2	45
<u>FACE BRICKWORK</u>			
6/3/6	Extra over brickwork for face brickwork	m2	42
6/3/7	Extra over brickwork for brick-on-edge header course lintel	m	5
6/3/8	220mm Wide sill set sloping and slightly protecting outside	m	5
6/3/9	Fair cutting fitting around pipe not exceeding 100mm	No	2
6/3/10	Fair cutting fitting around pipe exceeding 100mm and not exceeding 200mm diameter	No	2
<u>BRICKWORK SUNDRIES</u>			
<u>Brickwork reinforcement</u>			
6/3/11	75mm Wide reinforcement built in horizontally	m	1
6/3/12	150mm Wide reinforcement built in horizontally	m	90
<u>Galvanised wire ties etc</u>			
6/3/13	6mm Diameter roof tie 2m long with one end fixed to timber and other end built into brickwork	No	17
Carried Forward			R
Section No. 6 Section 6 - GR B1 Bill No. 3 MASONRY Re-Solve Consulting			

Brought Forward			R
<u>Turning pieces to lintels etc.</u>			
6/3/14	115mm Wide turning pieces	m	2
6/3/15	230mm Wide turning pieces	m	4
<u>Prestressed fabricated lintels</u>			
6/3/16	110 x 75mm Lintels in lengths exceeding 3m and not exceeding 6m	m	7
<u>Air bricks etc.</u>			
6/3/17	230 x 152mm terra-cotta vermin proofed louvered air brick	No	2
Carried Forward to Summary of Section No. 6			R
Section No. 6			
Section 6 - GR B1			
Bill No. 3			
MASONRY			
Re-Solve Consulting			

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 6</u>			
	<u>BILL NO.4</u>			
	<u>WATERPROOFING</u>			
	For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades			
	<u>DAMP-PROOFING OF WALLS AND FLOORS</u>			
	<u>One layer of 375 micron Consol Plastic Brikgrip DPC" embossed damp proof course</u>			
6/4/1	In walls	m2	42	
	<u>One layer of 250 micron "Consol Plastic USB Green" waterproof sheeting sealed at laps with "Gunplas Pressure Sensitive Tape"</u>			
6/4/2	Under surface beds	m2	64	
6/4/3	Under aprons and ramps	m2	2	
	<u>FLOOR AND WALL SEALERS</u>			
	<u>Secomastic non setting mastic sealant applied cold with a hand pressure caulking gun and leave perfectly watertight</u>			
6/4/4	Around steel windows and door frames	m	6	
	Carried Forward to Summary of Section No. 6			R
	Section No. 6			
	Section 6 - GR B1			
	Bill No. 4			
	WATERPROOFING			
	Re-Solve Consulting			

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 6</u>			
	<u>BILL NO.5</u>			
	<u>ROOF COVERINGS ETC</u>			
	For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades			
	<u>PROFILED METAL SHEETING AND ACCESSORIES</u>			
	<u>0,6mm "Kliplok" roof sheeting in chromadek finish fixed to timber purlins (elsewhere)</u>			
6/5/1	Roof covering with pitch not exceeding 25 degrees	m2	19	
	<u>ROOF AND WALL INSULATION</u>			
6/5/2	12" Thermal resistance sisalition laid on purlins	m2	19	
	<u>RAINWATER DISPOSAL</u>			
	<u>For preambles see "Model Preambles for Trades (2008 Edition)" and Supplementary preambles as specified in the Trades</u>			
	<u>Aluminium Zinc Seamless Gutters</u>			
6/5/3	100 x 100mm sandard rainwater gutters fixed with gutter brackets	m	5	
6/5/4	Extra over eaves gutter for stopped end	No	2	
6/5/5	75 x 100mm Diameter rainwater down pipes fixed to wall	m	6	
6/5/6	Extra over eaves gutter for outlet for 75 x 100mm down pipe	No	2	
6/5/7	Ditto .for shoe	No	2	
	Carried Forward to Summary of Section No. 6			R
	Section No. 6			
	Section 6 - GR B1			
	Bill No. 5			
	ROOF COVERINGS ETC			
	Re-Solve Consulting			

Item No		Quantity	Rate	Amount
	<p><u>SECTION NO. 6</u></p> <p><u>BILL NO. 6</u></p> <p><u>CARPENTRY AND JOINERY</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>ROOFS, ETC.</u></p> <p><u>Plate nailed timber roof truss construction</u></p>			
6/6/1	<p>Design manufacture and deliver on site plate nailed roof truss construction to Ablutions Block size 4 565 x 3 964 mm overall on plan consisting of mono pitched trusses to suit with 350mm eaves overhang projecting including all necessary purlins runners bracing and cross bracing (wall plates elsewhere) all in accordance with suppliers and manufacturer's recommendations: Trusses are at maximum 110m centres. Roof covering is galvanised "IBR" roof sheeting (measured elsewhere) on 50 x 75mm purlins at 11m maximum centres. All timber to be sawn softwood in accordance with V4 or M4 as defined in SABS 563 or SABS 1245. Metal connector plates shall have a minimum yield strength of 228 MPa and a minimum ultimate tensile strength of 330 Mpa with hot-dip galvanised finish. All joints to be close fitted butt joints. Trusses shall be designed by a registered supplier of prefabricated trusses who shall issue an Engineers Certificate upon completion of the installation. The dimensions in the descriptions of the trusses are nominal and actual measurements are to be obtained on site before design or fabrication commences. Tenderers must study the roof plan and sections as attached to the back of these bills of quantities and must obtain prices from a qualified and registered roof truss supplier as no claims in this regard will be entertained.</p>	No	1	
6/6/2	Profit (As per rate build build up)		Item	
	Carried Forward			R
	<p>Section No. 6 Section 6 - GR B1 Bill No. 6 CARPENTRY AND JOINERY Re-Solve Consulting</p>			

Brought Forward			R
6/6/3	Take delivery temporary store hoist in position and erect plate nailed timber roof trusses purlins gangboarding temporary and permanent bracing etc (measured on slope of roof)	Item	
<u>Sawn softwood</u>			
6/6/4	38 x 114mm Wall plates	m	17
<u>Sundries</u>			
6/6/5	Two coats creosote on sawn timbers	m2	19
6/6/6	6mm Diameter galvanised wire tie 3000mm girth wrapped around rafter and purlin with ends tied together	No	17
6/6/7	Hurricane clips	No	17
<u>EAVES, VERGES, ETC</u>			
<u>Pressed fibre-cement:</u>			
6/6/8	15 x 230mm Nutec Fascias and barge boards including galvanised steel H-profile jointing strips	m	18
<u>DOORS, ETC</u>			
<u>Wrought meranti doors hung to steel frames</u>			
6/6/9	44mm framed, ledged and braced door 877 x 2064mm high including external weather bar (D1)	No	1
6/6/10	44mm framed, ledged and braced door 915 x 2032mm high including external weather bar (disabled)	No	1
Carried Forward to Summary of Section No. 6			R
Section No. 6			
Section 6 - GR B1			
Bill No. 6			
CARPENTRY AND JOINERY			
Re-Solve Consulting			

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 6</u>			
	<u>BILL NO. 7</u>			
	<u>IRONMONGERY</u>			
	For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades			
	<u>HINGES, BOLTS, ETC</u>			
	<u>100mm Chrome plated "D" type handle 3 by solid brace hinges</u>			
	<u>CATCHES,CABIN HOOKS, ETC</u>			
6/7/1	100mm brace Cabin hook and eye including 70 x 70 x 20mm chamfered hardwood block twice oiled and plugged	No	1	
	<u>LOCKS</u>			
	<u>Approved</u>			
6/7/2	Three lever mortice lock set	No	2	
6/7/3	Security double throw dead lock (no latch)	No	2	
	<u>HANDLES, ETC.</u>			
	<u>Aluminium Pull Handle</u>			
6/7/4	ASSA ABLOY Anodised Silver straight pull handle (Code: AL5515-300BBAS) with 300mm fixing centres.	No	1	
	<u>SUNDRIES</u>			
	<u>ASSA ABLOY</u>			
6/7/5	38mm Diameter rubber door stop plugged	No	1	
	Carried Forward			R
	Section No. 6 Section 6 - GR B1 Bill No. 7 IRONMONGERY Re-Solve Consulting			

Brought Forward			R
<u>Vaal Paragon</u>			
6/7/6	32mm Type 9 back grab rail 800mm long plugged	No	1
6/7/7	32mm Type 8 side grab rail 900mm girth plugged	No	1
<u>LETTERS, NAMEPLATES, ETC</u>			
<u>Dorma:</u>			
6/7/8	DSS-130 Engraved "Male" information sign, plugged	No	1
6/7/9	DSS-133 Engraved "Disabled" information sign, plugged	No	1
<u>BATHROOM FITTINGS</u>			
<u>Sundries</u>			
<u>Kimberley-Clark or Similar</u>			
6/7/10	SQ2 code 405607B white none lockable toilet roll holder	No	2
<u>stainless Steel</u>			
6/7/11	Stainless steel mirror size: 350 x 400mm plugged to wall with chrome plated screws.	No	1
Carried Forward to Summary of Section No. 6			R
Section No. 6			
Section 6 - GR B1			
Bill No. 7			
IRONMONGERY			
Re-Solve Consulting			

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 6</u>			
	<u>BILL NO. 8</u>			
	<u>METALWORK</u>			
	For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades			
	<u>WELDED SCREENS, GATES, ETC</u>			
	<u>Gates to external doors</u>			
6/8/1	Purpose made square hollow section mild steel single security gate and frame size to fit standard door, size 813 x 2032mm high	No	2	
6/8/2	Single gate and frame size to fit none standard door, size approximately 915 x 2032mm high (disable)	No	2	
	<u>PRESSED STEEL DOOR FRAMES</u>			
	<u>1,2mm Double rebated frames suitable for one brick walls</u>			
6/8/3	Frame for door size 914 x 2032mm high	No	1	
	<u>1,2mm Single rebate steel frame suitable for one brick wall</u>			
6/8/4	Frame for door size 813 x 2032mm high	No	1	
	<u>STEEL WINDOWS, DOORS, ETC</u>			
	<u>Nty steel or similar approved school windows with standard burglar bars formed of 20 x 5mm thick flat bars to all sashes</u>			
6/8/5	Window type NE1, size 533 x 654mm high	No	3	
6/8/6	Window type NE7, size 1022 x 654mm high	No	2	
	Carried Forward to Summary of Section No. 6			R
	Section No. 6			
	Section 6 - GR B1			
	Bill No. 8			
	METALWORK			
	Re-Solve Consulting			

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 6</u>			
	<u>BILL NO.9</u>			
	<u>PLASTERING</u>			
	For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades			
	<u>GRANOLITHIC</u>			
	<u>Untinted granolithic on concrete</u>			
6/9/1	20mm Thick on floors	m2	18	
	<u>INTERNAL PLASTER</u>			
	<u>Cement plaster on brickwork or blockwork</u>			
6/9/2	On internal plastered walls(pits)	m2	43	
	<u>FLOOR AND WALLS SEALERS</u>			
	<u>Minimum two coats approved epoxy coat:</u>			
6/9/3	On floors in pits	m2	1	
6/9/4	On internal plastered walls in pits	m2	43	
	Carried Forward to Summary of Section No. 6			R
	Section No. 6			
	Section 6 - GR B1			
	Bill No. 9			
	PLASTERING			
	Re-Solve Consulting			

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 6</u>			
	<u>BILL NO. 10</u>			
	<u>PLUMBING AND DRAINAGE(PROVISIONAL)</u>			
	For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades			
	<u>SANITARY FITTINGS</u>			
	<u>"Vaal" or similar and approved</u>			
6/10/1	Ceramic wall mounted wash hand basin, complete with all fittings and accessories including cutting & making good wall & floor wherever required for disable toilets.	No	1	
	<u>SUPPLY AND INSTALL "ENVIRO-LOO" TOILET SYSTEMS</u>			
6/10/2	Supply and Install "Enviro-Loo" Industrial 1040 Model complete,installed strictly in accordance with manufacturers instructions, unit comprising of top unit and two x louvred inlets , drying plate , two x air inlets, standard toilet pan, seat and lid, 3500mm long outlet vent pipe, ventilation extraction unit fixed to wall with vent wall bracket, 1 bag mounting screws and organic starter, enzyme and toilet cleaner including all necessary inter connector piping between multiple tanks, emergency outlet piping,etc	No	1	
6/10/3	Supply and Erect disabled "Enviro-loo"Industrial 1040 Model set up and fixed complete as per manufacturers instructions, unit comprising of top unit and two x louvred inlets , drying plate , two x air inlets, paraplegic toilet pan, seat and lid, 3500mm long outlet vent pipe, ventilation extraction unit fixed to wall with vent wall bracket, 1 bag mounting screws and organic starter, enzyme and toilet cleaner including all necessary inter connector piping between multiple tanks, emergency outlet piping,etc	No	1	
	Carried Forward			R
	Section No. 6 Section 6 - GR B1 Bill No. 10 PLUMBING AND DRAINAGE(PROVISIONAL) Re-Solve Consulting			

Brought Forward

R

6/10/4	Supply and Erect "Enviro-loo" Urinal Evaporative Tank system fixed complete as per manufacturers specification unit comprising of urinal evaporative tank , urinal bowls including brackets , 3500mm long outlet vent pipe , ventilation extraction unit fixed to wall with vent wall bracket, 1 bag mounting screws and organic starter, enzyme and toilet cleaner including all necessary piping, traps, etc	No	2
--------	--	----	---

PRECAST CONCRETE WASH HAND TROUGH

6/10/5	Standard SABS approved Pre-Cast Concrete Double Wash Trough, 1080 x 650 x 850mm high with support legs fitted with standard 3/4 Brass Garden Taps, fixed complete to berick wall, including all necessary pipework, including soak away as per 'Engineers detail'.	No	1
--------	--	----	---

SOIL DRAINAGE

uPVC pipes

6/10/6	110mm Pipes laid in and including trenches not exceeding 1m deep	m	10
--------	--	---	----

Extra over uPVC pipes for fittings

6/10/7	110mm Bend	No	2
--------	------------	----	---

6/10/8	110mm Junction	No	2
--------	----------------	----	---

uPVC gulleys

6/10/9	110mm Gulley not exceeding 750mm deep, including excavations, pre-cast concrete sorround etc.	No	2
--------	---	----	---

TRAPS ETC

Marley

6/10/10	40 x 300mm Sink combination for double bowl with deepseal "P" trap	No	2
---------	--	----	---

TAPS, VALVES, ETC

6/10/11	Cobra Watertech 15mm gate valve plugged	No	1
---------	---	----	---

Carried Forward

R

Section No. 6
Section 6 - GR B1
Bill No. 10
PLUMBING AND DRAINAGE(PROVISIONAL)
Re-Solve Consulting

Brought Forward			R
6/10/12	Cobra Watertech 15mm Elbow action pillar tap	No	1
<u>SANITARY PLUMBING</u>			
<u>uPVC pipes</u>			
6/10/13	50mm Pipes	m	10
<u>Extra over uPVC pipes for fittings</u>			
6/10/14	50mm Bend	No	2
6/10/15	50mm Access bend	No	2
6/10/16	50mm Junction	No	2
<u>WATER SUPPLIES</u>			
<u>Class 0 copper pipes</u>			
6/10/17	15mm Pipes	m	20
6/10/18	22mm Pipes	m	18
<u>Extra over class 0 copper pipes for capillary fittings</u>			
6/10/19	15mm Fittings	No	3
6/10/20	22mm Pipes	No	3
<u>TESTING</u>			
6/10/21	Allow for testing all drains, sanitary plumbing, water supplies and installation to the satisfaction of the Principle Agent.		Item
Carried Forward to Summary of Section No. 6			R
Section No. 6			
Section 6 - GR B1			
Bill No. 10			
PLUMBING AND DRAINAGE(PROVISIONAL)			
Re-Solve Consulting			

Item No		Quantity	Rate	Amount
	<p><u>SECTION NO. 6</u></p> <p><u>BILL NO. 11</u></p> <p><u>GLAZING</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>GLAZING TO STEEL WITH PUTTY</u></p> <p><u>6.28mm Obscure safety glass</u></p>			
6/11/1	Panes not exceeding 0,1 m2	m2	2	
	Carried Forward to Summary of Section No. 6			R
	Section No. 6 Section 6 - GR B1 Bill No. 11 GLAZING Re-Solve Consulting			

Item No		Quantity	Rate	Amount
	<p><u>SECTION NO.6</u></p> <p><u>BILL NO. 12</u></p> <p><u>PAINTWORK</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>PAINTWORK ETC TO NEW WORK</u></p> <p><u>PREPARATORY WORK TO EXISTING WORK</u></p> <p><u>Previously painted plastered surfaces</u></p> <p><u>Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and cracks shall be opened, filled with a suitable filler and finished smooth</u></p> <p><u>Previously painted metal surfaces</u></p> <p><u>Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal</u></p> <p><u>Previously painted wood surfaces</u></p> <p><u>Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth</u></p> <p><u>ON FIBRE-CEMENT</u></p> <p><u>Prepare and brush to remove all loose contaminations, apply one coat primer and two coats PVA emulsion paint</u></p>			
6/12/1	On fascias and barge boards	m2	5	
	Carried Forward			R
	<p>Section No. 6 Section 6 - GR B1 Bill No. 12 PAINTWORK Re-Solve Consulting</p>			

Brought Forward

R

ON METAL

Prime and paint undercoat and 2 finishing coats in gloss enamel, colour TBC.

6/12/2 On door frames m2 4

Spot prining defects in pre-prime surface with zinc chromate primer and apply one universal undercoat and two coats EPWP. golden brown gloss enamel paint on steel

6/12/3 On windows with burglar bars m2 2

1 coat zinc chromate primer minimum and 2 coats gloss enamel (Exterior Quality)

6/12/4 On gates (Measured over the full flat area of both sides) m2 7

ON WOOD

Under coat and minimum 2 coats gloss enamel, colour TBC

6/12/5 On doors (External) m2 2

Carried Forward to Summary of Section No. 6

R

Section No. 6
 Section 6 - GR B1
 Bill No. 12
 PAINTWORK
 Re-Solve Consulting

Bill No	Section No. 6 Section 6 - GR B1 SECTION SUMMARY - Section 6 - GR B1	Page No	Amount
6/1	EARTHWORKS(PROVISIONAL)	107	
6/2	CONCRETE, FORMWORK AND REINFORCEMENT	109	
6/3	MASONRY	112	
6/4	WATERPROOFING	113	
6/5	ROOF COVERINGS ETC	114	
6/6	CARPENTRY AND JOINERY	116	
6/7	IRONMONGERY	118	
6/8	METALWORK	119	
6/9	PLASTERING	120	
6/10	PLUMBING AND DRAINAGE(PROVISIONAL)	123	
6/11	GLAZING	124	
6/12	PAINTWORK	126	
	Carried to Final Summary		R
	Section No. 6 Section 6 - GR B1 Re-Solve Consulting		

Item No		Quantity	Rate	Amount
	<p><u>SECTION 7</u></p> <p><u>BILL NO. 1</u></p> <p><u>EARTHWORKS (PROVISIONAL)</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Nature of ground</u></p> <p><u>Use "assumed to be" if no trial holes, soils investigations, etc have been carried out - discuss with engineer. Use "Trial holes indicate that" where the ground has been investigated by means of trial holes</u></p> <p><u>Nature of ground</u></p> <p><u>A soils investigation has been carried out on site by the engineer and the report is annexed to these bills of quantities. Descriptions of excavations shall be deemed to include all ground conditions classifiable as "earth" described in the above report and where conditions of a more difficult character are indicated these are separately measured</u></p> <p><u>Carting away of excavated material</u></p> <p><u>Descriptions of carting away of excavated material shall be deemed to include loading excavated material onto trucks directly from the excavations or, alternatively, from stock piles situated on the building site</u></p> <p><u>Filling</u></p>			
	Carried Forward		R	
	<p>Section No. 7 Section 7 - GR G3 Bill No. 1 EARTHWORKS(PROVISIONAL) Re-Solve Consulting</p>			

Brought Forward				R
<u>Notwithstanding the reference to prescribed multiple handling in clause 1 page 6 of the Standard System of Measuring Building Work, prices for filling and backfilling shall include for all selection and any multiple handling of material</u>				
<u>Soil poisoning</u>				
<u>Ant and weed poisoning will be applied in accordance to SABS specifications by Registered and Approved Specialists who will issue a five (5) year guarantee. The contractor will only be paid for this items once they have produced the said certificate to the Principal Agent</u>				
<u>SITE CLEARANCE ETC</u>				
<u>Site clearance</u>				
7/1/1	Digging up and removing rubbish, debris, vegetation, hedges, shrubs and trees not exceeding 200mm girth, bush, etc	m2	62	
7/1/2	Stripping average 100mm thick layer of top soil and stockpiling on site	m2	62	
<u>EXCAVATION, FILLING, ETC</u>				
<u>Excavation in earth not exceeding 2m deep</u>				
7/1/3	Trenches	m3	27	
7/1/4	Pits	m3	29	
7/1/5	Thickening under aprons	m3	0.4	
<u>Extra over trench and hole excavations in earth for excavation in</u>				
7/1/6	Soft rock	m3	4	
7/1/7	Hard rock	m3	2	
Carried Forward				R
Section No. 7 Section 7 - GR G3 Bill No. 1 EARTHWORKS(PROVISIONAL) Re-Solve Consulting				

Brought Forward			R
<u>Extra over all excavations for carting away</u>			
7/1/8	Surplus material from excavations on site to a dumping site to be located by the contractor	m3	44
<u>Risk of collapse of excavations</u>			
7/1/9	Sides of trench and hole excavations not exceeding 1,5m deep	m2	171
<u>Keeping excavations free of water</u>			
7/1/10	Keeping excavations free of all water other than subterranean water		Item
<u>Earth filling obtained from the excavations and /or prescribed stock piles on site including compacted to 93% Mod AASHTO density</u>			
7/1/11	Under floors, steps, paving, etc	m3	9
7/1/12	Backfilling to trenches, holes, etc	m3	12
<u>Compaction of surfaces</u>			
7/1/13	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density	m2	43
7/1/14	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density (Enviro Loo Tanks Pit)	m2	20
7/1/15	Ditto but to bottom of trenches and bases	m2	26
<u>Prescribed density tests on filling</u>			
7/1/16	Modified AASHTO Density	No	4
<u>SOIL POISONING</u>			
Carried Forward			R
Section No. 7 Section 7 - GR G3 Bill No. 1 EARTHWORKS(PROVISIONAL) Re-Solve Consulting			

	Brought Forward			R
	<u>Weedkiller mixed in accordance to supplier's specifications</u>			
7/1/17	To bottoms and sides of trenches, etc.	m2	136	
7/1/18	Under floors etc including forming and poisoning shallow furrows against foundation walls etc, filling in furrows and ramming(pits)	m2	79	
	<u>Soil insecticide</u>			
7/1/19	To bottoms and sides of trenches etc	m2	136	
7/1/20	Under floors etc including forming and poisoning shallow furrows against foundation walls etc, filling in furrows and ramming(pits)	m2	60	
Carried Forward to Summary of Section No. 7				R
Section No. 7 Section 7 - GR G3 Bill No. 1 EARTHWORKS(PROVISIONAL) Re-Solve Consulting				

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 7</u>			
	<u>BILL NO. 2</u>			
	<u>CONCRETE, FORMWORK AND REINFORCEMENT</u>			
	For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades			
	<u>UNREINFORCED CONCRETE, ETC.</u>			
	<u>15MPa/19mm concrete</u>			
7/2/1	Surface blinding under footings and bases	m3	2	
7/2/2	Aprons cast in panels to falls	m3	2	
7/2/3	Extra over concrete in surface beds for thickening 85mm deep the bottom including all excavation, backfilling etc	m	19	
7/2/4	Extra over for concrete thickening in aprons size approximately 100mm deep, 400mm at top and tapering one side to 200mm at bottom, including all excavations, cart away, etc.	m	17	
	<u>25MPa/19mm concrete</u>			
7/2/5	Strip footings	m3	5	
7/2/6	Ramps	m3	2	
	<u>REINFORCED CONCRETE</u>			
	<u>25MPa/19mm concrete</u>			
7/2/7	Surface beds cast in panels on waterproofing.	m3	2	
7/2/8	Slabs (pits)	m3	3	
	Carried Forward			R
	Section No. 7 Section 7 - GR G3 Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT Re-Solve Consulting			

Brought Forward

R

TEST CUBES

7/2/9	Allow for preparing a set of three concrete strength test cubes, each size 150 x 150 x 150mm, sending them to an approved Testing Laboratory for testing and paying all charges in connection therewith	Sets	4.0
-------	---	------	-----

CONCRETE SUNDRIES

Finishing top surfaces of concrete smooth with a wood float/steel trowel

7/2/10	Surface beds, slabs, etc	m2	42
7/2/11	Surface beds, slabs, etc (pits)	m2	18
7/2/12	Aprons to falls	m2	19

SMOOTH FORMWORK (DEGREE OF ACCURACY I)

Rough formwork to sides

7/2/13	Edges, risers, ends and reveals not exceeding 300mm high or wide	m	19
--------	--	---	----

REINFORCEMENT (PROVISIONAL)

Fabric Reinforcement

7/2/14	Mesh ref. No. 395 fabric reinforcement fixed horizontalt in surface beds etc.	m2	61
--------	---	----	----

Carried Forward to Summary of Section No. 7

R

Section No. 7
Section 7 - GR G3
Bill No. 2
CONCRETE, FORMWORK AND REINFORCEMENT
Re-Solve Consulting

Item No		Quantity	Rate	Amount
	<p><u>SECTION NO.7</u></p> <p><u>BILL NO.3</u></p> <p><u>MASONRY</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>BRICKWORK</u></p> <p><u>Sizes in descriptions</u></p> <p><u>Where sizes in descriptions are given in brick units, "one brick" shall represent the length and "half brick" the width of a brick</u></p> <p><u>Face bricks</u></p> <p><u>Bricks shall be ordered timeously to obtain uniformity in size and colour</u></p> <p><u>Pointing</u></p> <p><u>Descriptions of recessed pointing to fair face brickwork and face brickwork shall be deemed to include square recessed, hollow recessed, weathered pointing, etc</u></p> <p><u>FOUNDATIONS (PROVISIONAL)</u></p> <p><u>Brickwork of NFP bricks in class II mortar</u></p>			
7/3/1	One brick walls	m2	44	
	<p><u>FACE BRICKWORK</u></p>			
	Carried Forward			R
	<p>Section No. 7 Section 7 - GR G3 Bill No. 3 MASONRY Re-Solve Consulting</p>			

Brought Forward			R
<u>Face bricks (purchase price of R5 000.00/1000 delivered to site excluding VAT) pointed with flush horizontal and vertical joints</u>			
7/3/2	Extra over brickwork for face brickwork in foundations	m2	4
<u>SUPERSTRUCTURE</u>			
<u>Brickwork of NFP bricks in class II mortar</u>			
7/3/3	Half brick walls	m2	2
7/3/4	Half brick walls in beamfilling	m2	4
7/3/5	One brick walls	m2	50
<u>FACE BRICKWORK</u>			
7/3/6	Extra over brickwork for face brickwork	m2	47
7/3/7	Extra over brickwork for brick-on-edge header course lintel	m	6
7/3/8	220mm Wide sill set sloping and slightly protecting outside	m	6
7/3/9	Fair cutting fitting around pipe not exceeding 100mm	No	1
7/3/10	Fair cutting fitting around pipe exceeding 100mm and not exceeding 200mm diameter	No	4
<u>BRICKWORK SUNDRIES</u>			
<u>Brickwork reinforcement</u>			
7/3/11	75mm Wide reinforcement built in horizontally	m	2
7/3/12	150mm Wide reinforcement built in horizontally	m	95
<u>Galvanised wire ties etc</u>			
7/3/13	6mm Diameter roof tie 2m long with one end fixed to timber and other end built into brickwork	No	19
Carried Forward			R
Section No. 7 Section 7 - GR G3 Bill No. 3 MASONRY Re-Solve Consulting			

Brought Forward

R

Turning pieces to lintels etc.

7/3/14	115mm Wide turning pieces	m	4
7/3/15	230mm Wide turning pieces	m	4

Prestressed fabricated lintels

7/3/16	110 x 75mm Lintels in lengths exceeding 3m and not exceeding 6m	m	8
--------	---	---	---

Air bricks etc.

7/3/17	230 x 152mm terra-cotta vermin proofed louvered air brick	No	2
--------	---	----	---

Carried Forward to Summary of Section No. 7

R

Section No. 7
Section 7 - GR G3
Bill No. 3
MASONRY
Re-Solve Consulting

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 7</u>			
	<u>BILL NO.4</u>			
	<u>WATERPROOFING</u>			
	For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades			
	<u>DAMP-PROOFING OF WALLS AND FLOORS</u>			
	<u>One layer of 375 micron Consol Plastic Brikgrip DPC" embossed damp proof course</u>			
7/4/1	In walls	m2	47	
	<u>One layer of 250 micron "Consol Plastic USB Green" waterproof sheeting sealed at laps with "Gunplas Pressure Sensitive Tape"</u>			
7/4/2	Under surface beds	m2	76	
7/4/3	Under aprons and ramps	m2	2	
	<u>FLOOR AND WALL SEALERS</u>			
	<u>Secomastic non setting mastic sealant applied cold with a hand pressure caulking gun and leave perfectly watertight</u>			
7/4/4	Around steel windows and door frames	m	7	
	Carried Forward to Summary of Section No. 7			R
	Section No. 7			
	Section 7 - GR G3			
	Bill No. 4			
	WATERPROOFING			
	Re-Solve Consulting			

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 7</u>			
	<u>BILL NO.5</u>			
	<u>ROOF COVERINGS ETC</u>			
	For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades			
	<u>PROFILED METAL SHEETING AND ACCESSORIES</u>			
	<u>0,6mm "Kliplok" roof sheeting in chromadek finish fixed to timber purlins (elsewhere)</u>			
7/5/1	Roof covering with pitch not exceeding 25 degrees	m2	24	
	<u>ROOF AND WALL INSULATION</u>			
7/5/2	12" Thermal resistance sisalition laid on purlins	m2	24	
	<u>RAINWATER DISPOSAL</u>			
	<u>For preambles see "Model Preambles for Trades (2008 Edition)" and Supplementary preambles as specified in the Trades</u>			
	<u>Aluminium Zinc Seamless Gutters</u>			
7/5/3	100 x 100mm sandard rainwater gutters fixed with gutter brackets	m	6	
7/5/4	Extra over eaves gutter for stopped end	No	2	
7/5/5	75 x 100mm Diameter rainwater down pipes fixed to wall	m	6	
7/5/6	Extra over eaves gutter for outlet for 75 x 100mm down pipe	No	2	
7/5/7	Ditto .for shoe	No	2	
	Carried Forward to Summary of Section No. 7			R
	Section No. 7			
	Section 7 - GR G3			
	Bill No. 5			
	ROOF COVERINGS ETC			
	Re-Solve Consulting			

Item No		Quantity	Rate	Amount
	<p><u>SECTION NO. 7</u></p> <p><u>BILL NO. 6</u></p> <p><u>CARPENTRY AND JOINERY</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>ROOFS, ETC.</u></p> <p><u>Plate nailed timber roof truss construction</u></p>			
7/6/1	<p>Design manufacture and deliver on site plate nailed roof truss construction to Ablutions Block size 5 585 x 3 964 mm overall on plan consisting of mono pitched trusses to suit with 350mm eaves overhang projecting including all necessary purlins runners bracing and cross bracing (wall plates elsewhere) all in accordance with suppliers and manufacturer's recommendations: Trusses are at maximum 110m centres. Roof covering is galvanised "IBR" roof sheeting (measured elsewhere) on 50 x 75mm purlins at 11m maximum centres. All timber to be sawn softwood in accordance with V4 or M4 as defined in SABS 563 or SABS 1245. Metal connector plates shall have a minimum yield strength of 228 MPa and a minimum ultimate tensile strength of 330 Mpa with hot-dip galvanised finish. All joints to be close fitted butt joints. Trusses shall be designed by a registered supplier of prefabricated trusses who shall issue an Engineers Certificate upon completion of the installation. The dimensions in the descriptions of the trusses are nominal and actual measurements are to be obtained on site before design or fabrication commences. Tenderers must study the roof plan and sections as attached to the back of these bills of quantities and must obtain prices from a qualified and registered roof truss supplier as no claims in this regard will be entertained.</p>	No	1	
7/6/2	<p>Profit (As per rate build build up)</p>	Item		
	Carried Forward			R
	<p>Section No. 7 Section 7 - GR G3 Bill No. 6 CARPENTRY AND JOINERY Re-Solve Consulting</p>			

Brought Forward			R
7/6/3	Take delivery temporary store hoist in position and erect plate nailed timber roof trusses purlins gangboarding temporary and permanent bracing etc (measured on slope of roof)	Item	
<u>Sawn softwood</u>			
7/6/4	38 x 114mm Wall plates	m	19
<u>Sundries</u>			
7/6/5	Two coats creosote on sawn timbers	m2	22
7/6/6	6mm Diameter galvanised wire tie 3000mm girth wrapped around rafter and purlin with ends tied together	No	19
7/6/7	Hurricane clips	No	19
<u>EAVES, VERGES, ETC</u>			
<u>Pressed fibre-cement:</u>			
7/6/8	15 x 230mm Nutec Fascias and barge boards including galvanised steel H-profile jointing strips	m	19
<u>DOORS, ETC</u>			
<u>Wrought meranti doors hung to steel frames</u>			
7/6/9	44mm framed, ledged and braced door 877 x 2064mm high including external weather bar (D1)	No	1
7/6/10	44mm framed, ledged and braced door 915 x 2032mm high including external weather bar (disabled)	No	1
Carried Forward to Summary of Section No. 7			R
Section No. 7			
Section 7 - GR G3			
Bill No. 6			
CARPENTRY AND JOINERY			
Re-Solve Consulting			

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 7</u>			
	<u>BILL NO. 7</u>			
	<u>IRONMONGERY</u>			
	For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades			
	<u>HINGES, BOLTS, ETC</u>			
	<u>100mm Chrome plated "D" type handle 3 by solid brace hinges</u>			
	<u>CATCHES,CABIN HOOKS, ETC</u>			
7/7/1	100mm brace Cabin hook and eye including 70 x 70 x 20mm chamfered hardwood block twice oiled and plugged	No	1	
	<u>LOCKS</u>			
	<u>Approved</u>			
7/7/2	Three lever mortice lock set	No	2	
7/7/3	Security double throw dead lock (no latch)	No	2	
	<u>HANDLES, ETC.</u>			
	<u>Aluminium Pull Handle</u>			
7/7/4	ASSA ABLOY Anodised Silver straight pull handle (Code: AL5515-300BBAS) with 300mm fixing centres.	No	1	
	<u>SUNDRIES</u>			
	<u>ASSA ABLOY</u>			
7/7/5	38mm Diameter rubber door stop plugged	No	1	
	Carried Forward			R
	Section No. 7 Section 7 - GR G3 Bill No. 7 IRONMONGERY Re-Solve Consulting			

Brought Forward			R
<u>Vaal Paragon</u>			
7/7/6	32mm Type 9 back grab rail 800mm long plugged	No	1
7/7/7	32mm Type 8 side grab rail 900mm girth plugged	No	1
<u>LETTERS, NAMEPLATES, ETC</u>			
<u>Dorma:</u>			
7/7/8	DSS-130 Engraved "Female" information sign, plugged	No	1
7/7/9	DSS-133 Engraved "Disabled" information sign, plugged	No	1
<u>BATHROOM FITTINGS</u>			
<u>Sundries</u>			
<u>Kimberley-Clark or Similar</u>			
7/7/10	SQ2 code 405607B white none lockable toilet roll holder	No	4
<u>stainless Steel</u>			
7/7/11	Stainless steel mirror size: 350 x 400mm plugged to wall with chrome plated screws.	No	1
Carried Forward to Summary of Section No. 7			R
Section No. 7			
Section 7 - GR G3			
Bill No. 7			
IRONMONGERY			
Re-Solve Consulting			

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 7</u>			
	<u>BILL NO. 8</u>			
	<u>METALWORK</u>			
	For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades			
	<u>WELDED SCREENS, GATES, ETC</u>			
	<u>Gates to external doors</u>			
7/8/1	Purpose made square hollow section mild steel single security gate and frame size to fit standard door, size 813 x 2032mm high	No	1	
7/8/2	Single gate and frame size to fit none standard door, size approximately 915 x 2032mm high (disable)	No	1	
	<u>PRESSED STEEL DOOR FRAMES</u>			
	<u>1,2mm Double rebated frames suitable for one brick walls</u>			
7/8/3	Frame for door size 914 x 2032mm high	No	1	
	<u>1.2mm Single rebate steel frame suitable for one brick wall</u>			
7/8/4	Frame for door size 813 x 2032mm high	No	1	
	<u>STEEL WINDOWS, DOORS, ETC</u>			
	<u>Nty steel or similar approved school windows with standard burglar bars formed of 20 x 5mm thick flat bars to all sashes</u>			
7/8/5	Window type NE1, size 533 x 654mm high	No	4	
7/8/6	Window type NE7, size 1022 x 654mm high	No	2	
	Carried Forward to Summary of Section No. 7			R
	Section No. 7			
	Section 7 - GR G3			
	Bill No. 8			
	METALWORK			
	Re-Solve Consulting			

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 7</u>			
	<u>BILL NO.9</u>			
	<u>PLASTERING</u>			
	For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades			
	<u>GRANOLITHIC</u>			
	<u>Untinted granolithic on concrete</u>			
7/9/1	20mm Thick on floors	m2	22	
	<u>INTERNAL PLASTER</u>			
	<u>Cement plaster on brickwork or blockwork</u>			
7/9/2	On internal plastered walls(pits)	m2	54	
	<u>FLOOR AND WALLS SEALERS</u>			
	<u>Minimum two coats approved epoxy coat:</u>			
7/9/3	On floors in pits	m2	1	
7/9/4	On internal plastered walls in pits	m2	54	
	Carried Forward to Summary of Section No. 7			
	Section No. 7			
	Section 7 - GR G3			
	Bill No. 9			
	PLASTERING			
	Re-Solve Consulting			
			R	

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 7</u>			
	<u>BILL NO. 10</u>			
	<u>PLUMBING AND DRAINAGE(PROVISIONAL)</u>			
	For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades			
	<u>SANITARY FITTINGS</u>			
	<u>"Vaal" or similar and approved</u>			
7/10/1	Ceramic wall mounted wash hand basin, complete with all fittings and accessories including cutting & making good wall & floor wherever required for disable toilets.	No	1	
	<u>SUPPLY AND INSTALL "ENVIRO-LOO" TOILET SYSTEMS</u>			
7/10/2	Enviroloo Industrial Standard seat system complete, (Code: FG-1040STDCA/B3)	No	3	
7/10/3	Supply and Erect disabled "Enviro-loo"Industrial 1040 Model set up and fixed complete as per manufacturers instructions, unit comprising of top unit and two x louvred inlets , drying plate , two x air inlets, paraplegic toilet pan, seat and lid, 3500mm long outlet vent pipe, ventilation extraction unit fixed to wall with vent wall bracket, 1 bag mounting screws and organic starter, enzyme and toilet cleaner including all necessary inter connector piping between multiple tanks, emergency outlet piping,etc	No	1	
	<u>PRECAST CONCRETE WASH HAND TROUGH</u>			
7/10/4	Standard SABS approved Pre-Cast Concrete Double Wash Trough, 1080 x 650 x 850mm high with support legs fitted with standard 3/4 Brass Garden Taps, fixed complete to berick wall, including all necessary pipework, including soak away as per 'Engineers detail'.	No	1	
	Carried Forward			R
	Section No. 7 Section 7 - GR G3 Bill No. 10 PLUMBING AND DRAINAGE(PROVISIONAL) Re-Solve Consulting			

Brought Forward

R

SOIL DRAINAGE

uPVC pipes

7/10/5	110mm Pipes laid in and including trenches not exceeding 1m deep	m	20
--------	--	---	----

Extra over uPVC pipes for fittings

7/10/6	110mm Bend	No	5
--------	------------	----	---

7/10/7	110mm Junction	No	5
--------	----------------	----	---

uPVC gulleys

7/10/8	110mm Gully not exceeding 750mm deep, including excavations, pre-cast concrete surround etc.	No	2
--------	--	----	---

TRAPS ETC

Marley

7/10/9	40 x 300mm Sink combination for double bowl with deepseal "P" trap	No	2
--------	--	----	---

TAPS, VALVES, ETC

7/10/10	Cobra Watertech 15mm gate valve plugged	No	1
---------	---	----	---

7/10/11	Cobra Watertech 15mm Elbow action pillar tap	No	1
---------	--	----	---

SANITARY PLUMBING

uPVC pipes

7/10/12	50mm Pipes	m	20
---------	------------	---	----

Extra over uPVC pipes for fittings

7/10/13	50mm Bend	No	5
---------	-----------	----	---

7/10/14	50mm Access bend	No	5
---------	------------------	----	---

7/10/15	50mm Junction	No	5
---------	---------------	----	---

Carried Forward

R

Section No. 7
Section 7 - GR G3
Bill No. 10
PLUMBING AND DRAINAGE(PROVISIONAL)
Re-Solve Consulting

Brought Forward

R

WATER SUPPLIES

Class 0 copper pipes

7/10/16	15mm Pipes	m	20	
---------	------------	---	----	--

7/10/17	22mm Pipes	m	18	
---------	------------	---	----	--

Extra over class 0 copper pipes for capillary fittings

7/10/18	15mm Fittings	No	3	
---------	---------------	----	---	--

7/10/19	22mm Pipes	No	3	
---------	------------	----	---	--

TESTING

7/10/20	Allow for testing all drains, sanitary plumbing, water supplies and installtion to the satisfaction of the Principle Agent.			Item
---------	---	--	--	------

Carried Forward to Summary of Section No. 7

R

Section No. 7
 Section 7 - GR G3
 Bill No. 10
 PLUMBING AND DRAINAGE(PROVISIONAL)
Re-Solve Consulting

Item No		Quantity	Rate	Amount
	<p><u>SECTION NO. 7</u></p> <p><u>BILL NO. 11</u></p> <p><u>GLAZING</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>GLAZING TO STEEL WITH PUTTY</u></p> <p><u>6.28mm Obscure safety glass</u></p>			
7/11/1	Panes not exceeding 0,1 m2	m2	3	
	Carried Forward to Summary of Section No. 7			R
	Section No. 7 Section 7 - GR G3 Bill No. 11 GLAZING Re-Solve Consulting			

Item No		Quantity	Rate	Amount
	<p><u>SECTION NO.7</u></p> <p><u>BILL NO. 12</u></p> <p><u>PAINTWORK</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>PAINTWORK ETC TO NEW WORK</u></p> <p><u>PREPARATORY WORK TO EXISTING WORK</u></p> <p><u>Previously painted plastered surfaces</u></p> <p><u>Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and cracks shall be opened, filled with a suitable filler and finished smooth</u></p> <p><u>Previously painted metal surfaces</u></p> <p><u>Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal</u></p> <p><u>Previously painted wood surfaces</u></p> <p><u>Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth</u></p> <p><u>ON FIBRE-CEMENT</u></p> <p><u>Prepare and brush to remove all loose contaminations, apply one coat primer and two coats PVA emulsion paint</u></p>			
7/12/1	On fascias and barge boards	m2	5	
	Carried Forward			R
	<p>Section No. 7 Section 7 - GR G3 Bill No. 12 PAINTWORK Re-Solve Consulting</p>			

Brought Forward

R

ON METAL

Prime and paint undercoat and 2 finishing coats in gloss enamel, colour TBC.

7/12/2 On door frames m2 4

Spot prining defects in pre-prime surface with zinc chromate primer and apply one universal undercoat and two coats EPWP. golden brown gloss enamel paint on steel

7/12/3 On windows with burglar bars m2 3

1 coat zinc chromate primer minimum and 2 coats gloss enamel (Exterior Quality)

7/12/4 On gates (Measured over the full flat area of both sides) m2 7

ON WOOD

Under coat and minimum 2 coats gloss enamel, colour TBC

7/12/5 On doors (External) m2 2

Carried Forward to Summary of Section No. 7

R

Section No. 7
 Section 7 - GR G3
 Bill No. 12
 PAINTWORK
 Re-Solve Consulting

Bill No		Page No		Amount
	Section No. 7			
	Section 7 - GR G3			
	<u>SECTION SUMMARY - Section 7 - GR G3</u>			
7/1	EARTHWORKS(PROVISIONAL)	131		
7/2	CONCRETE, FORMWORK AND REINFORCEMENT	133		
7/3	MASONRY	136		
7/4	WATERPROOFING	137		
7/5	ROOF COVERINGS ETC	138		
7/6	CARPENTRY AND JOINERY	140		
7/7	IRONMONGERY	142		
7/8	METALWORK	143		
7/9	PLASTERING	144		
7/10	PLUMBING AND DRAINAGE(PROVISIONAL)	147		
7/11	GLAZING	148		
7/12	PAINTWORK	150		
	Carried to Final Summary			
	Section No. 7			
	Section 7 - GR G3			
	Re-Solve Consulting		R	

Item No		Quantity	Rate	Amount
	<u>SECTION NO.8</u>			
	<u>BILL NO. 1</u>			
	<u>ELEVATED WATER TANKS</u>			
	<u>SUPPLEMENTARY PREAMBLES</u>			
	For preambles see "Specifications of materials and methods to be used - PW 371"			
	<u>Excavation in earth not exceeding 2m deep</u>			
8/1/1	Holes	m3	21	
	<u>Extra over trench and hole excavations in earth for excavation in</u>			
8/1/2	Soft rock	m3	11	
8/1/3	Hard rock	m3	5	
	<u>Extra over all excavations for carting away</u>			
8/1/4	Surplus material from excavations on site to a dumping site to be located by the contractor	m3	16	
	<u>Risk of collapse of excavations</u>			
8/1/5	Sides of trench and hole excavations not exceeding 1,5m deep	m2	43	
	<u>Keeping excavations free of water</u>			
8/1/6	Keeping excavations free of all water other than subterranean water		Item	
	<u>Earth filling obtained from the excavations and /or prescribed stock piles on site including compacted to 93% Mod AASHTO density</u>			
8/1/7	Backfilling to trenches, holes, etc	m3	5	
	Carried Forward			R
	Section No. 8 Section 8 - External Works Bill No. 1 Elevated Water Tanks Re-Solve Consulting			

Brought Forward			R
<u>Compaction of surfaces</u>			
8/1/8	Ditto but to bottom of trenches and bases	m2	64
<u>SOIL POISONING</u>			
<u>Soil insecticide</u>			
8/1/9	To bottoms and sides of trenches etc	m2	64
<u>One layer of 250 micron "Consol Plastic USB Green" waterproof sheeting sealed at laps with "Gunplas Pressure Sensitive Tape"</u>			
8/1/10	Under surface beds	m2	64
<u>UNREINFORCED CONCRETE, ETC.</u>			
<u>15MPa/19mm concrete</u>			
8/1/11	Surface blinding under footings and bases	m3	3
<u>REINFORCED CONCRETE</u>			
<u>25MPa/19mm concrete</u>			
8/1/12	Bases	m3	16
8/1/13	Platform surface beds cast in panels	m3	13
<u>TEST CUBES</u>			
8/1/14	Allow for preparing a set of three concrete strength test cubes, each size 150 x 150 x 150mm, sending them to an approved Testing Laboratory for testing and paying all charges in connection therewith	Sets	
<u>CONCRETE SUNDRIES</u>			
<u>Finishing top surfaces of concrete smooth with a wood float/steel trowel</u>			
8/1/15	Platform surface beds	m2	64
Carried Forward			R
Section No. 8 Section 8 - External Works Bill No. 1 Elevated Water Tanks Re-Solve Consulting			

Brought Forward

R

8/1/16	Top of bases	m2	13
--------	--------------	----	----

"Jojo" or equal approved SANS PVC water tanks

8/1/17	5 000 Litre plastic water tank fitted onto and secured to tank platforms	No	
--------	--	----	--

8/1/18	10 000 Litre plastic water tank fitted onto and secured to tank platforms	No	4
--------	---	----	---

Galvanized medium normalized mild steel piping

8/1/19	25mm Pipes	m	160
--------	------------	---	-----

8/1/20	50mm Pipes	m	272
--------	------------	---	-----

Extra over galvanised mild steel water supply pipes for fittings:

8/1/21	25mm Fittings	No	27
--------	---------------	----	----

8/1/22	50mm Elbows	No	27
--------	-------------	----	----

8/1/23	50mm Union	No	27
--------	------------	----	----

8/1/24	50mm Reducing bush.	No	11
--------	---------------------	----	----

"Cobra Watertech" or other equal approved

8/1/25	15mm "Cobra Ref. 108LK" brass hose biptap.	No	11
--------	--	----	----

8/1/26	50mm Fullway gate valve	No	11
--------	-------------------------	----	----

The following in structural steel tank stands

Welded steel columns in single lengths with flat base, cap, bearer and connection plates, bolted to concrete

8/1/27	80 x 80mm x 6mm angle columns	t	3.97
--------	-------------------------------	---	------

Carried Forward

R

Section No. 8
Section 8 - External Works
Bill No. 1
Elevated Water Tanks
Re-Solve Consulting

Brought Forward

R

Steel members and girth, bolted to steel

8/1/28	30 x 30mm x 6mm Flat-bar	t	0.51
8/1/29	40 x 40mm x 5mm angle	t	0.51
8/1/30	125 x 75mm x 8mm unequal angle	t	0.59
8/1/31	125 x 50mm x 20 x 2mm Lipped channel	t	1.25

BOLTS, FASTENERS, ETC (LI)

8/1/32	High tensile bolts	t	1.33
8/1/33	12mm Diameter L-shaped threaded anchor bolt 350mm girth embedded in top of concrete	No	43

ON METAL

Undercoat and minimum 2 coat gloss enamel

8/1/34	Paint to structural steel	m	333
--------	---------------------------	---	-----

TESTING

Testing of water tanks

8/1/35	Testing for tank		Item
--------	------------------	--	------

Carried Forward to Summary of Section No. 8

R

Section No. 8
Section 8 - External Works
Bill No. 1
Elevated Water Tanks
Re-Solve Consulting

Item No		Quantity	Rate	Amount
	<u>SECTION 8</u>			
	<u>BILL NO. 2</u>			
	<u>PAVED WALKWAYS</u>			
	<u>SUPPLEMENTARY PREAMBLES</u>			
	For preambles see "Specifications of materials and methods to be used - PW 371"			
	<u>Site Clearance</u>			
8/2/1	Digging up and removing rubbish, debris, vegetation, hedges, shrubs, bush and trees not exceeding 200mm girth, etc	m2	256	
8/2/2	Stripping average 100mm thick layer of top soil and stockpiling on site	m2	256	
	<u>Open face excavation in earth over sloping site</u>			
8/2/3	Excavation in earth not exceeding 2m open face excavation to form platforms under parking areas etc and depositing excavated material over site, including haulage not exceeding 10m from perimeter of excavations exceeding 2m deep	m3	64	
	<u>Extra over all excavations for carting away</u>			
8/2/4	Surplus material from excavations and/stock piles on site to the dumping site to be located by the Contractor.	m3	64	
	<u>Earth filling supplied by the contractor under parking areas, roadways, etc</u>			
8/2/5	Sub-base course of G5 material in accordance with SABS 1200 DM, compacted to 93% Mod AASHTO density	m3	64	
	Carried Forward			R
	Section No. 8 Section 8 - External Works Bill No. 2 Paved Walkways Re-Solve Consulting			

Brought Forward				R
<u>Compaction of surfaces</u>				
8/2/6	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density	m2	256	
<u>Soil poisoning</u>				
8/2/7	Weedkiller (active ingredients metalaclor 102,8 g/l, terbitilasien 248,6 g/l and atrasion 248,6 g/l) mixed in the proportion of 100 ml weedkiller to 100 l water and applied at a rate of 10 l/m ² on cleared ground	m2	256	
<u>60mm Thick precast concrete DZZ interlocking heavy duty block paving of grey paving blocks in accordance with SANS 1058, laid to falls on and including 25mm thick sand layer with joints filled in with sand, compacted with a vibration compactor:</u>				
8/2/8	Paving to toilet areas etc to falls	m2	256	
8/2/9	Fig. 12 kerbs to sides of paving	m	398	
8/2/10	15Mpa/19mm unreinforced concrete in haunching	m3	12	
Carried Forward to Summary of Section No. 8				R
Section No. 8				
Section 8 - External Works				
Bill No. 2				
Paved Walkways				
Re-Solve Consulting				

Item No		Quantity	Rate	Amount
	<u>SECTION 8</u>			
	<u>BILL NO. 3</u>			
	<u>FENCING</u>			
	<u>SUPPLEMENTARY PREAMBLES</u>			
	For preambles see "Specifications of materials and methods to be used - PW 371"			
	<u>Alterations</u>			
	<u>Take down and removing</u>			
8/3/1	Steel palisade fencing not exceeding 2400mm high	m	541	
	<u>Steel palisade fence</u>			
	<u>Mild steel welded palisade fence including spot prime exposed metal surfaces and two coats high gloss enamel paint</u>			
8/3/2	Palisade fence 2400mm high of 40 x 40 x 3mm angle section continuous top and bottom rails and 30 x 30 x 3mm angle section pickets with top end split and sharpened at average 150mm centres, welded to rails, rails welded 2600mm high posts of 76 x 76 x 5mm square tube with steel pyramid shaped capping on top at 2475mm centres with 500mm bottom ends cast into and including 15Mpa concrete footing in ground including excavation, ramming, removal of spoil and leaving clean, neat and painted	m	541	
	Carried Forward to Summary of Section No. 8			R
	Section No. 8			
	Section 8 - External Works			
	Bill No. 3			
	Fencing			
	Re-Solve Consulting			

Section No. 8

Section 8 - External Works

SECTION SUMMARY - Section 8 - External Works

Bill No		Page No	Amount
8/1	Elevated Water Tanks	155	
8/2	Paved Walkways	157	
8/3	Fencing	158	
	Carried to Final Summary		R
	Section No. 8 Section 8 - External Works Re-Solve Consulting		

Section No	<u>FINAL SUMMARY</u>	Page No		Amount
1	Section 1 - Preliminaries and General	26		
2	Section 2 - Demolitions and Alterations	28		
3	Section 3 - Staff Ablutions	53		
4	Section 4 - Girls Block of 5	78		
5	Section 5 - Boys Block of 2	103		
6	Section 6 - GR B1	127		
7	Section 7 - GR G3	151		
8	Section 8 - External Works	159		
	SUB TOTAL		R	
	<u>ADD: CONTINGENCIES</u>			
	Contingencies	Item		541 497.00
	SUB TOTAL BEFORE VAT		R	
	<u>ADD: VALUE ADDED TAX</u>			
	Value Added Tax (15%)		R	
	TENDER SUM CARRIED FORWARD TO FORM OF OFFER AND ACCEPTANCE		R	
	Carried to Form of Tender		R	
	Re-Solve Consulting			