

| Item No | Quantity | Rate | Amount |
|---|--|------|--------|
| <u>SECTION NO. 1</u> | | | |
| <u>BILL NO. 1</u> | | | |
| <u>PRELIMINARIES</u> | | | |
| <u>BUILDING AGREEMENT AND PRELIMINARIES</u> | | | |
| <u>Principal Building Agreement Code 2101 Edition 4.1 March 2005 (including State Provisions)</u> | | | |
| <u>AND PRELIMINARIES Code 2103 May 2005</u> | | | |
| <u>PRELIMINARIES NOTES</u> | | | |
| i) | The agreement is to be the JBCC Series 2000 Principal Building Agreement, Edition 4.1 May 2005, and other contract documents that together form the contract between the employer and contractor | | |
| ii) | The preliminaries are to be the JBCC Series 2000 Code 2103 Preliminaries prepared by the Joint Building Contracts Committee, May 2005 edition and shall be deemed to be incorporated herein | | |
| iii) | Tenderers are referred to the abovementioned documents for the full intent and meaning of each clause thereof (hereinafter referred to by heading and clause number only) for which such allowance must be made as may be considered necessary | | |
| iv) | Where standard clauses or alternatives are not entirely applicable to this contract such modifications, corrections or supplements as will apply are given under each relevant clause heading | | |
| Carried Forward | | | R |
| Section No. 1 Section 1 - Preliminaries and General Bill No. 1 Preliminaries Re-Solve Consulting | | | |

| | Brought Forward | | R |
|--|------------------------|--|---|
| <p>v) Where any item is not relevant to this specific contract such item is marked N/A (signifying "not applicable")</p> <p>vi) If Alternative A as set out in clause B10.3 hereinafter is to be used for the adjustment of the preliminaries each item priced is to be allocated to one or more of the three categories, where "F" denotes a fixed amount (amount not to be varied), "V" denotes an amount variable in proportion to value and "T" denotes an amount in proportion to time</p> <p style="text-align: center;">-----</p> | | | |
| <p>Section No. 1 Section 1 - Preliminaries and General Bill No. 1 Preliminaries Re-Solve Consulting</p> | Carried Forward | | R |

| Brought Forward | | R |
|---|--|------|
| <u>SECTION A: PRINCIPAL BUILDING AGREEMENT</u> | | |
| <u>Definitions (A1)</u> | | |
| 1/1/1 | Definitions and interpretation (clause 1) | Item |
| <u>Objective and Preparation (A2 to A14)</u> | | |
| 1/1/2 | Offer acceptance and performance (clause 2) | Item |
| 1/1/3 | Documents (clause 3) | Item |
| 1/1/4 | Design responsibility (clause 4) | Item |
| 1/1/5 | Employer's agents (clause 5) | Item |
| 1/1/6 | Site representative (clause 6) | Item |
| 1/1/7 | Compliance with regulations (clause 7) | Item |
| 1/1/8 | Works risk (clause 8) | Item |
| 1/1/9 | Indemnities (clause 9) | Item |
| 1/1/10 | Works insurances (clause 10) | Item |
| 1/1/11 | Liability insurances (clause 11) | Item |
| 1/1/12 | Effecting insurance (clause 12) | Item |
| 1/1/13 | NO CLAUSE 13. | N/A |
| 1/1/14 | Security (clause 14) | Item |
| <u>Execution (A15-A23)</u> | | |
| 1/1/15 | Preparation for and execution of the works (clause 15) | Item |
| 1/1/16 | Access to the works (clause 16) | Item |
| 1/1/17 | Contract instructions (clause 17) | Item |
| Carried Forward | | R |
| Section No. 1 Section 1 - Preliminaries and General Bill No. 1 Preliminaries Re-Solve Consulting | | |

| Brought Forward | | R |
|---|--|------|
| 1/1/18 | Setting out of the works (clause 18) | Item |
| 1/1/19 | Assignment (clause 19) | Item |
| 1/1/20 | Nominated subcontractors (clause 20) | Item |
| 1/1/21 | Selected subcontractors (clause 21) | Item |
| 1/1/22 | Employer's Direct Contractors (clause 22) | Item |
| 1/1/23 | Contractor's Domestic Sub-Contractors (Clause 23) | Item |
| <u>Completion (A24-A30)</u> | | |
| 1/1/24 | Practical completion (clause 24) | Item |
| 1/1/25 | Works completion (clause 25) | Item |
| 1/1/26 | Final completion (clause 26) | Item |
| 1/1/27 | Latent defects liability period (clause 27) | Item |
| 1/1/28 | Sectional completion (clause 28) | Item |
| 1/1/29 | Revision of date of practical completion (clause 29) | Item |
| 1/1/30 | Penalty for non-completion (clause 30) | Item |
| <u>Payment (A31 - A35)</u> | | |
| 1/1/31 | Interim payment to the contractor (clause 31) | Item |
| 1/1/32 | Adjustment to the contract value (clause 32) | Item |
| 1/1/33 | Recovery of expense and loss (clause 33) | Item |
| 1/1/34 | Final account and final payment (clause 34) | Item |
| 1/1/35 | Payment to other parties (clause 35) | Item |
| Carried Forward | | R |
| Section No. 1 Section 1 - Preliminaries and General Bill No. 1 Preliminaries Re-Solve Consulting | | |

| | Brought Forward | | R |
|--------|--|------|---|
| | <u>Cancellation (A36-A39)</u> | | |
| 1/1/36 | Cancellation by employer - contractor's default (clause 36) | Item | |
| 1/1/37 | Cancellation by employer - loss and damage (clause 37) | Item | |
| 1/1/38 | Cancellation by contractor - employer's default (clause 38) | Item | |
| 1/1/39 | Cancellation - cessation of the works (clause 39) | Item | |
| | <u>Dispute (A40)</u> | | |
| 1/1/40 | Dispute Settlement (clause 40) | Item | |
| | <u>Substitute Provisions (A41)</u> | | |
| 1/1/41 | State clauses (Clause 41) | Item | |
| | <u>THE SCHEDULE</u> | | |
| | Information necessary for completion of those clauses contained in the schedule which are necessary for tender purposes is given hereunder | | |
| 1/1/42 | Pre-tender information (clause 42) | Item | |
| | <u>42.1 CONTRACTING AND OTHER PARTIES</u> | | |
| | 42.1.1 Employer: THE MVULA TRUST | | |
| | 42.1.2 Principal Agent: RE-SOLVE CONSULTING | | |
| | Carried Forward | | R |
| | Section No. 1 Section 1 - Preliminaries and General Bill No. 1 Preliminaries Re-Solve Consulting | | |

| | | | |
|--|------------------------|------------------------|--------|
| | Brought Forward | | R |
| 42.2 CONTRACT DETAILS | | | |
| 42.2.1 Works Description: | | | |
| Construction of sanitation facilities | | | |
| 42.2.2 Site Description: | | | |
| as per the information on the tender data | | | |
| 42.2.3 Work or installations by direct contractors: | | | |
| N/a | | | |
| 42.2.4 This agreement is for a government contract where there are specific options that are applicable to a State organ only | | | |
| | | | Yes |
| 42.2.5 Date on which possession of the site is intended to be given: | | | |
| As per the information provided in the Tender Data | | | |
| 42.2.6 Period for the commencement of the works after the contractor takes possession of the site | | | |
| | | | 7 DAYS |
| 42.2.7 For the works as a whole. Intended date of practical completion and the penalty per calendar day | | | |
| Intended Date of Practical Completion: As per the information provided in the Tender Data | | | |
| Penalty Amount: | | | |
| The penalty per calendar day shall be 7.5 cents per R100 of the Tendered Amount (inclusive of value added tax) | | | |
| | | | |
| | | Carried Forward | R |
| Section No. 1 | | | |
| Section 1 - Preliminaries and General | | | |
| Bill No. 1 | | | |
| Preliminaries | | | |
| Re-Solve Consulting | | | |

| | Brought Forward | | R |
|--|-------------------------------|--|---|
| 42.2.8 For the works in sections : Intended date of practical completion and the penalty per calender day | N/a | | |
| 42.2.9 The law applicable to this agreement shall be that of | <i>South Africa (country)</i> | | |
| <u>42.3 INSURANCES</u> | | | |
| 42.3.1 Contract works insurance to be effected by: Contractor: For the Sum of R Contract Amount + 10.00 % With a deductible of - to be determined by the contractor | | | |
| 42.3.2 Supplementary insurance is required | No | | |
| 42.3.3 Public liability insurance to be effected by:Contractor: For the Sum of R 5 000 000-00 With a deductible of - to be determined by the contractor | | | |
| <u>42.4 DOCUMENTS</u> | | | |
| 42.4.1 Waivers of contractors lien or right of continuing possession is required | Yes | | |
| 42.4.2 Number of construction document copies to be supplied to the contractor free of charge: | 3 <i>Number of</i> | | |
| 42.4.3 Bills of Quantities/Lump sum document schedule of rates drawn up in accordance with: "Standard System of Measuring Builders' Work" | | | |
| Carried Forward | | | R |
| Section No. 1 Section 1 - Preliminaries and General Bill No. 1 Preliminaries Re-Solve Consulting | | | |

| | Brought Forward | | R |
|--|------------------------|--|---|
| 42.4.4 On acceptance of the tender the bills of quantities/lump sum document is to be submitted within working days | | | |
| 5 working days | | | |
| 42.4.5 JBCC Engineering General Conditions are to be included in the contract documents: | | | |
| <i>No</i> | | | |
| 42.4.6 The contract value is to be adjusted using escalation adjustment indices | | | |
| <i>No</i> | | | |
| 42.4.7 Details of changes made to the provision of JBCC standard documentation: [An addendum is to be attached should the space provided be insufficient] | | | |
| Part 1 -Contract Data completed by Employer | | | |
| Carried Forward | | | |
| Section No. 1 Section 1 - Preliminaries and General Bill No. 1 Preliminaries Re-Solve Consulting | | | R |

| Brought Forward | | R |
|---|---|------|
| <u>SECTION B: PRELIMINARIES</u> | | |
| <u>Definitions and interpretation (B1)</u> | | |
| 1/1/43 | Definition and interpretation (B1.1 - B1.4.6) | Item |
| <u>Documents (B2)</u> | | |
| 1/1/44 | Checking of documents (B2.1) | Item |
| 1/1/45 | Provisional bills of quantities (B2.2) | Item |
| 1/1/46 | Availability of construction documentation (B2.3) | Item |
| 1/1/47 | Interests of agents (B2.4) | Item |
| 1/1/48 | Priced documents (B2.5) | Item |
| 1/1/49 | Tender submission (B2.6) | Item |
| <u>The site (B3)</u> | | |
| 1/1/50 | Defined works area (B3.1) | Item |
| 1/1/51 | Geotechnical investigation (B3.2) | Item |
| 1/1/52 | Inspection of the site (B3.3) | Item |
| 1/1/53 | Existing premises occupied (B3.4) | Item |
| 1/1/54 | Previous work - dimensional accuracy (B3.5) | Item |
| 1/1/55 | Previous work - defects (B3.6) | Item |
| 1/1/56 | Services - known (B3.7) | Item |
| 1/1/57 | Services - unknown (B3.8) | Item |
| 1/1/58 | Protection of trees etc (B3.9) | Item |
| 1/1/59 | Articles of value (B3.10) | Item |
| 1/1/60 | Inspection of adjoining properties etc (B3.11) | Item |
| Carried Forward | | R |
| Section No. 1 Section 1 - Preliminaries and General Bill No. 1 Preliminaries Re-Solve Consulting | | |

| Brought Forward | | R |
|---|--|------|
| <u>Management of contract (B4)</u> | | |
| 1/1/61 | Management of the works (B4.1) | Item |
| 1/1/62 | Programme for the works (B4.2) | Item |
| 1/1/63 | Progress meetings (B4.3) | Item |
| 1/1/64 | Technical meetings (B4.4) | Item |
| 1/1/65 | Labour and Plant records (B4.5) | Item |
| <u>Samples, Shop Drawings and Manufacturer's Instructions (B5)</u> | | |
| 1/1/66 | Samples of materials (B5.1) | Item |
| 1/1/67 | Workmanship samples (B5.2) | Item |
| 1/1/68 | Shop drawings (B5.3) | Item |
| 1/1/69 | Compliance with Manufacturer's Instructions (B5.4) | Item |
| <u>Temporary works and plant (B6)</u> | | |
| 1/1/70 | Deposits and fees (B6.1) | Item |
| 1/1/71 | Enclosure of the works (B6.2) | Item |
| 1/1/72 | Advertising (B6.3) | Item |
| 1/1/73 | Plant, equipment, sheds and offices (B6.4) | Item |
| 1/1/74 | Main notice board (B6.5) | Item |
| 1/1/75 | Subcontractors' notice board (B6.6) | Item |
| <u>Temporary services (B7)</u> | | |
| 1/1/76 | Location (B7.1) | Item |
| 1/1/77 | Water (B7.2) | Item |
| Option [A] shall apply | | |
| Carried Forward | | R |
| Section No. 1 Section 1 - Preliminaries and General Bill No. 1 Preliminaries Re-Solve Consulting | | |

| | | Brought Forward | | R |
|---|---|-------------------------------|------|---|
| 1/1/78 | Electricity (B7.3) | Option [A] shall apply | Item | |
| 1/1/79 | Telecommunication facilities (B7.4) | | Item | |
| 1/1/80 | Ablution facilities (B7.5) | Option [A] shall apply | Item | |
| <u>Prime cost amounts (B8)</u> | | | | |
| 1/1/81 | Responsibility for prime cost amounts (B8.1) | | Item | |
| <u>Attendance on N/S Subcontractors (B9)</u> | | | | |
| 1/1/82 | General attendance (B9.1) | | Item | |
| 1/1/83 | Special attendance (B9.2) | | Item | |
| 1/1/84 | Commissioning - Fuel, water and power (B9.3) | | Item | |
| <u>Financial aspects (B10)</u> | | | | |
| | Statutory taxes, duties and levies (B10.1) | | Item | |
| 1/1/85 | Payment of preliminaries (B10.2) | Option [B] shall apply | Item | |
| 1/1/86 | Adjustment of preliminaries (B10.3) | Option [A] shall apply | Item | |
| 1/1/87 | Payment certificate cash flow (B10.4) | | Item | |
| <u>General (B11)</u> | | | | |
| 1/1/88 | Protection of works (B11.1) | | Item | |
| 1/1/89 | Protection/isolation of existing/sectionally occupied works (B11.2) | | Item | |
| 1/1/90 | Security of the Works (B11.3) | | Item | |
| 1/1/91 | Notice before covering work (B11.4) | | Item | |
| | | Carried Forward | | R |
| Section No. 1 Section 1 - Preliminaries and General Bill No. 1 Preliminaries Re-Solve Consulting | | | | |

| | Brought Forward | | R |
|---------|---|------|----|
| 1/1/92 | Disturbance (B11.5) | Item | |
| 1/1/93 | Environmental Disturbance (B11.6) | Item | |
| 1/1/94 | Works cleaning and clearing (B11.7) | Item | |
| 1/1/95 | Vermin (B11.8) | Item | |
| 1/1/96 | Overhand work (B11.9) | Item | |
| 1/1/97 | Instruction manuals and guarantees (B11.10) | Item | |
| 1/1/98 | As built information (B11.11) | Item | |
| 1/1/99 | Tenant Installations (B11.12) | Item | |
| | <u>Schedule of variables (B12)</u> | | |
| 1/1/100 | Pre-tender information (B12.1) | Item | |
| | 12.1.1 Provisional bills of quantities (B2.2) The quantities are provisional: | | No |
| | 12.1.2 Availability of construction documentation (B2.3) Construction documentation is not complete | | No |
| | 12.1.3 Interest of agents (B2.4) | | |
| | 12.1.4 Defined works area (B3.1) | | |
| | 12.1.5 Geotechnical investigation (B3.2) N/a | | |
| | Carried Forward | | R |
| | Section No. 1 Section 1 - Preliminaries and General Bill No. 1 Preliminaries Re-Solve Consulting | | |

| | Brought Forward | | R |
|---|------------------------|-----|---|
| 12.1.11 Inspection of adjoining properties (B3.11) | | | |
| ?? | | | |
| | | | |
| | | | |
| 12.1.12 Enclosure of the works (B6.2) | | | |
| ?? | | | |
| | | | |
| | | | |
| 12.1.13 Offices (B6.4.3) | | | |
| Specific requirements: The contractor shall provide, maintain and remove, on completion of the works, an office for the exclusive use of the principal agent, minimum size 4 x 3 x 3m high internally, suitably insulated and ventilated, provided with electric lighting and fitted with boarded floor, desk, chair, drawing stool, drawing board and lock-up drawers for drawings. The office shall be kept clean and fit for use at all times | | | |
| 12.1.14 Main notice board (B6.5) | | | |
| Yes | | | |
| 12.1.15 Subcontractors notice board (B6.6) | | | |
| A notice board is required | | Yes | |
| 12.1.16 Water (B7.2) | | | |
| Alternative Selected: A | | | |
| 12.1.17 Electricity (B7.3) | | | |
| Alternative selected: A | | | |
| | Carried Forward | | R |
| Section No. 1 Section 1 - Preliminaries and General Bill No. 1 Preliminaries Re-Solve Consulting | | | |

| | Brought Forward | | R |
|---|------------------------|--|---|
| 12.1.18 Telecommunications (B7.4) | | | |
| 12.1.19 Ablution facilities (B7.5) Alternative selected: A | | | |
| 12.1.20 Protection of existing/sectionally occupied works (B11.2) | | | |
| 12.1.21 Special attendance (B9.2) Subcontractor (1) details: N/a | | | |
| 12.1.22 Protection of the works (B11.1) | | | |
| 12.1.23 Disturbance (B11.5) | | | |
| 12.1.24 Environmental Disturbance (B11.6) | | | |
| <u>Post tender information (B12.2)</u> | | | |
| 12.2.1 Payment of preliminaries Alternative selected: B | | | |
| 12.2.2 Adjustment of preliminaries Alternative selected: A | | | |
| 12.2.3 Additional agreed preliminaries items N/a | | | |
| | Carried Forward | | R |
| Section No. 1 Section 1 - Preliminaries and General Bill No. 1 Preliminaries Re-Solve Consulting | | | |

Brought Forward

R

SECTION C: SPECIFIC PRELIMINARIES??

Any special items to meet the parrtcular circumstances of a specific project are embodied in this section. Where required for an aspect of the works to be executed according to a design by a consulting engineer, a recital of the headings to the individual clauses of the JBCC Engineering General Conditions are included

1/1/101 **Site instructions**

Instructions issued on site are to be recorded in triplicate in a site instruction book which is to be maintained on site by the contractor

F:..... V:..... T:.....

Item

1/1/102 **Black economic empowerment and training**

F:..... V:..... T:.....

Item

1/1/103 **Proprietary branded products**

F:..... V:..... T:.....

Item

Carried Forward

R

Section No. 1
 Section 1 - Preliminaries and General
 Bill No. 1
 Preliminaries
Re-Solve Consulting

Brought Forward

1/1/104 **Testing of flat roof waterproofing for watertightness**

Flat roof waterproof areas shall be prepared with small sand dykes around them of a size and enclosing an area approved by the principal agent, flooded with water and kept "ponded" for at least 36 hours as a test to ensure the watertightness of the waterproofing and before any further construction work is carried out above the waterproofing

F:.....V:.....T:.....
 The contractor shall take delivery of, handle, store, use, apply and/or fix all proprietary branded products in strict accordance with the manufacturers' instructions after consultation with the manufacturer's authorised representative

Item

1/1/105 **Contract instructions**

F:..... V:..... T:.....

Contract instructions issued on site are to be recorded in triplicate in a contract instruction book which is to be supplied and maintained on site by the contractor

Item

1/1/106 **Labour record**

F:..... V:..... T:.....

At the end of each week the contractor shall provide the principal agent with a written record, in schedule form, reflecting the number and descriptions of tradesmen and labourers employed by him and all subcontractors on the works each day of that week

Item

Carried Forward

Section No. 1
 Section 1 - Preliminaries and General
 Bill No. 1
 Preliminaries
Re-Solve Consulting

R

R

Brought Forward

R

1/1/107 **Plant record**

F:..... V:..... T:.....

At the end of each week the contractor shall provide the principal agent with a written record, in schedule form, reflecting the number, type and capacity of all plant, excluding hand tools used on the works each day of that week

Item

1/1/108 **Guarantees**

F:..... V:..... T:.....

Where guarantees are called for, the contractor shall obtain a written guarantee, addressed to the employer, from the firm supplying the materials and/or doing the work and shall deliver same to the principal agent on the certified completion of the contract. The guarantee shall state that workmanship, materials and installation are guaranteed for a specified period from the date of certified completion of the contract, and that any defects that may arise during the specified period shall be made good at the expense of the firm supplying the materials and/or doing the work, upon written notice from the principal agent to do so. This guarantee will not be enforced if the work is damaged by defects in the construction of the building in which case the responsibility for replacement shall rest entirely with the contractor. The principal agent shall be the sole judge of the cause responsible for defects in the work and his decision shall be final and binding in terms of clause 40.2 of the agreement

Item

Carried Forward

R

Section No. 1
 Section 1 - Preliminaries and General
 Bill No. 1
 Preliminaries
Re-Solve Consulting

Brought Forward

R

1/1/109 **Overtime**

F:..... V:..... T:.....

Should overtime be required to be worked for any reason whatsoever, the costs of such overtime are to be borne by the contractor unless the principal agent has specifically authorised, in writing, prior to execution thereof, that costs for such overtime are to be borne by the employer

Item

1/1/110 **Co-operation of contractor for cost management**

F:..... V:..... T:.....

It is specifically agreed that the contractor accepts the obligation of assisting the professional consultants in implementing proper cost management. The contractor will be advised by the principal agent of all cost management procedures which will be implemented to ensure that the final building cost does not exceed the budget. The quantity surveyor undertakes to make available to the contractor all budgetary allowances and cost assessments/reports to enable the proper procedures to be implemented and the contractor will attend all cost plan review and cost management meetings. The contractor undertakes to extend these procedures in regard to all subcontractors

Item

Carried Forward

R

Section No. 1
Section 1 - Preliminaries and General
Bill No. 1
Preliminaries
Re-Solve Consulting

Brought Forward

R

1/1/111

Occupational Health and Safety Specification

F:..... V:..... T:.....

The contractor shall comply with all the requirements set out in the Construction Regulations, 2003 issued under the Occupational Health and Safety Act, 1993 (Act No 85 of 1993)

It is required of the contractor to thoroughly study the Health and Safety Specification that must be read together with and is deemed to be incorporated under this Section of the bills of quantities / lump sum document.

The contractor must take note that compliance with the Occupational Health and Safety Act, Construction Regulations and Health and Safety Specification is compulsory. In the event of partial or total non-compliance, the principal agent, notwithstanding the provisions of clause A31.0 of Section A or any other clause to the contrary, reserves the right to delay issuing any progress payment certificate until the contractor provides satisfactory proof of compliance.

The contractor shall not be entitled to any compensation of whatsoever nature, including interest, due to such delay of payment.

Provision for pricing of the Occupational Health and Safety Act, Construction Regulations and Health and Safety Specification is made under this clause, as well as the clauses that follow hereafter and it is explicitly pointed out that all requirements of the aforementioned are deemed to be priced under these clauses and no additional claims in this regard shall be entertained.

The contractor shall also comply with the additional requirements with regard to the Coronavirus pandemic in terms of all Covid-19 legislation, regulations and guidelines. It is explicitly pointed out that all requirements of the aforementioned are deemed to be priced under this clause and the specific related clauses hereafter and no additional claims in this regard shall be entertained.

Item

Carried Forward

R

Section No. 1
 Section 1 - Preliminaries and General
 Bill No. 1
 Preliminaries
Re-Solve Consulting

| | Brought Forward | | R |
|---------|--|------|---|
| 1/1/112 | <p>Occupational Health and Safety Specification</p> <p>F:..... V:..... T:.....</p> <p>Preparation of contractor's site specific health and safety plan, including compliance with Covid-19 legislation, regulations and guidelines</p> | Item | |
| 1/1/113 | <p>Occupational Health and Safety Specification</p> <p>F:..... V:..... T:.....</p> <p>Principal contractor's initial obligations in respect of the Health and Safety Act, Construction Regulations and Covid-19 regulations, etc</p> | Item | |
| 1/1/114 | <p>Occupational Health and Safety Specification</p> <p>F:..... V:..... T:.....</p> <p>Principal contractor's time related obligations in respect of the Health and Safety Act, Construction Regulations and Covid-19 regulations, etc</p> | Item | |
| 1/1/115 | <p>Provision of personal protective equipment (PPE)</p> <p>F:..... V:..... T:.....</p> <p>Provision of reflective vests</p> | Item | |
| 1/1/116 | <p>Provision of personal protective equipment (PPE)</p> <p>F:..... V:..... T:.....</p> <p>Provision of hard hats</p> | Item | |
| | Carried Forward | | R |
| | <p>Section No. 1 Section 1 - Preliminaries and General Bill No. 1 Preliminaries Re-Solve Consulting</p> | | |

| | Brought Forward | | | R |
|---------|--|------|--|---|
| 1/1/117 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... Provision of protective footwear | Item | | |
| 1/1/118 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... Provision of earplugs | Item | | |
| 1/1/119 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... Provision of dust masks | Item | | |
| 1/1/120 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... Provision of gloves | Item | | |
| 1/1/121 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... Provision of high visibility overalls to SARTSM Chapter 13 Level 3 | Item | | |
| 1/1/122 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... Provision of SANS approved ear defenders | Item | | |
| | Carried Forward | | | R |
| | Section No. 1 Section 1 - Preliminaries and General Bill No. 1 Preliminaries Re-Solve Consulting | | | |

| | Brought Forward | | R | |
|---------|---|------|---|--|
| 1/1/123 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... Provision of face masks (Covid -19) | Item | | |
| 1/1/124 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... Provision of face shields (Covid -19) | Item | | |
| 1/1/125 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... Provision of gloves (Covid -19) | Item | | |
| 1/1/126 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... Provision of hand sanitiser (min 70% alcohol), foot press stands and paper towels (Covid -19) | Item | | |
| 1/1/127 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... Provision of covered refuse bins and refuse bags and waste (including hazardous) management (Covid -19) | Item | | |
| | Carried Forward | | R | |
| | Section No. 1 Section 1 - Preliminaries and General Bill No. 1 Preliminaries Re-Solve Consulting | | | |

| | Brought Forward | | R | |
|---------|---|------|---|--|
| 1/1/128 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... Provision of digital infrared non-contact body thermometer (Covid -19, minimum of two per site entrance) | Item | | |
| 1/1/129 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... Provision of perspex screens for office staff (Covid -19, minimum size 600 x 500mm) | Item | | |
| 1/1/130 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... Provision of signage, including Covid -19 related signage | Item | | |
| 1/1/131 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... Provision of full time construction health and safety officer (SACPCMP Registered) | Item | | |
| 1/1/132 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... Medical certificates and medical surveillance including initial (baseline) medical examinations, periodic examinations, and exit examinations | Item | | |
| | Carried Forward | | R | |
| | Section No. 1 Section 1 - Preliminaries and General Bill No. 1 Preliminaries Re-Solve Consulting | | | |

Brought Forward

R

1/1/133 **Provision of personal protective equipment (PPE)**

F:..... V:..... T:.....

Medical screenings, examinations, etc in terms of Covid-19 regulations

Item

1/1/134 **Provision of personal protective equipment (PPE)**

F:..... V:..... T:.....

Induction training, including Covid-19 training

Item

1/1/135 **Provision of personal protective equipment (PPE)**

F:..... V:..... T:.....

Provision of first aid boxes to GSR requirements

Item

1/1/136 **Provision of personal protective equipment (PPE)**

F:..... V:..... T:.....

Noise monitoring including establishment of noise zones (plant), audiograms (personnel), etc

Item

1/1/137 **Provision of personal protective equipment (PPE)**

F:..... V:..... T:.....

Submission of health and safety file

Item

Carried Forward

R

Section No. 1
Section 1 - Preliminaries and General
Bill No. 1
Preliminaries
Re-Solve Consulting

Brought Forward

R

1/1/138

HIV/AIDS Awareness

F:..... V:..... T:.....

It is required of the contractor to thoroughly study the HIV/AIDS Specification (PW 1544) of the Department that must be read together with and is deemed to be incorporated under this Section of the bills of quantities / lump sum document. Provision for pricing of HIV/AIDS awareness is made under items C11.1 to C11.5 hereafter and it is explicitly pointed out that all requirements of the aforementioned specification are deemed to be priced hereunder, as the said items represent the only method of measurement and no additional items or extras to the contract in this regard shall be entertained.

The contractor must take note that compliance with the HIV/AIDS Specification is compulsory. In the event of partial or total non-compliance, the principal agent, notwithstanding the provisions of clause A 31.0 of Section A or any other clause to the contrary, reserves the right to delay issuing any progress payment certificate until the contractor provides satisfactory proof of compliance. The contractor shall not be entitled to any compensation of whatsoever nature, including interest, due to such delay of payment.

Item

SUMMARY OF CATEGORIES

Category : Fixed R.....

Category : Value R.....

Category : Time R.....

Carried to Final Summary

R

Section No. 1
 Section 1 - Preliminaries and General
 Bill No. 1
 Preliminaries
Re-Solve Consulting

| Item No | | Quantity | Rate | Amount |
|---------|---|----------|------|--------|
| | <p><u>SECTION 2</u></p> <p><u>BILL NO. 1</u></p> <p><u>ALTERATIONS</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> | | | |
| | Carried Forward | | R | |
| | <p>Section No. 2 Section 2 - Demolitions and Alterations Bill No. 1 Alterations Re-Solve Consulting</p> | | | |

| | Brought Forward | | | R |
|-------|--|----|----|---|
| | <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>View site</u></p> <p>Before submitting his tender the contractor shall visit the site and satisfy himself as to the nature and extent of the work to be done and the value of the materials contained in the buildings or portions of the buildings to be demolished. No claim for any variations of the contract sum in respect of the nature and extent of the work or of inferior or damaged materials will be entertained.</p> <p><u>Explosives</u></p> <p>No explosives whatsoever may be used for demolition.</p> <p><u>General</u></p> <p>The contractor shall carry out the whole of the works with as little mess and noise as possible and with a minimum of disturbance to adjoining premises and their tenants. He shall provide proper protection and provide, erect and remove when directed, any temporary tarpaulins that may be necessary during the progress of the works, all to the satisfaction of the principal agent. Water supply pipes and other piping that may be encountered and found necessary to disconnect or cut, shall be effectually stopped off or grubbed up and removed, and any new connections that may be necessary shall be made with proper fittings, to the satisfaction of the principal agent. Doors, fanlights, fittings, frames, linings, etc which are to be re-used shall be thoroughly overhauled before refixing including taking off, easing and rehangng, cramping up, re-wedging as required and making good cramps, dowels, etc, and easing, oiling, adjusting and repairing</p> <p><u>DEMOLITIONS AND ALTERATIONS</u></p> <p><u>Refurbishment of existing toilet seats</u></p> | | | |
| 2/1/1 | <p>Refurbish existing seats including fixing and/or replacement of seats, connector pans, toilet bowls, etc.</p> | No | 20 | |
| | Carried to Final Summary | | | R |
| | <p>Section No. 2 Section 2 - Demolitions and Alterations Bill No. 1 Alterations Re-Solve Consulting</p> | | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <p><u>SECTION 3</u></p> <p><u>BILL NO. 1</u></p> <p><u>EARTHWORKS (PROVISIONAL)</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p>Nature of ground</p> <p>Use "assumed to be" if no trial holes, soils investigations, etc have been carried out - discuss with engineer. Use "Trial holes indicate that" where the ground has been investigated by means of trial holes</p> <p>Nature of ground</p> <p>A soils investigation has been carried out on site by the engineer and the report is annexed to these bills of quantities. Descriptions of excavations shall be deemed to include all ground conditions classifiable as "earth" described in the above report and where conditions of a more difficult character are indicated these are separately measured</p> <p>Carting away of excavated material</p> <p>Descriptions of carting away of excavated material shall be deemed to include loading excavated material onto trucks directly from the excavations or, alternatively, from stock piles situated on the building site</p> <p>Filling</p> | | | |
| | Carried Forward | | R | |
| | <p>Section No. 3 Section 3 - Staff Ablutions Female Bill No. 1 Earthworks (Provisional Sums) Re-Solve Consulting</p> | | | |

| Brought Forward | | | | R |
|---|--|----|----|---|
| <p>Notwithstanding the reference to prescribed multiple handling in clause 1 page 6 of the Standard System of Measuring Building Work, prices for filling and backfilling shall include for all selection and any multiple handling of material</p> <p>Soil poisoning</p> <p><u>Ant and weed poisoning will be applied in accordance to SABS specifications by Registered and Approved Specialists who will issue a five (5) year guarantee. The contractor will only be paid for this items once they have produced the said certificate to the Principal Agent</u></p> <p><u>SITE CLEARANCE ETC</u></p> <p><u>Site clearance</u></p> | | | | |
| 3/1/1 | Digging up and removing rubbish, debris, vegetation, hedges, shrubs and trees not exceeding 200mm girth, bush, etc | m2 | 94 | |
| 3/1/2 | Stripping average 100mm thick layer of top soil and stockpiling on site | m2 | 94 | |
| <p><u>EXCAVATION, FILLING, ETC</u></p> <p><u>Excavation in earth not exceeding 2m deep</u></p> | | | | |
| 3/1/3 | Trenches | m3 | 45 | |
| 3/1/4 | Pits | m3 | 46 | |
| 3/1/5 | Thickening under aprons | m3 | 1 | |
| <p><u>Extra over trench and hole excavations in earth for excavation in</u></p> | | | | |
| 3/1/6 | Soft rock | m3 | 6 | |
| 3/1/7 | Hard rock | m3 | 3 | |
| Carried Forward | | | | R |
| <p>Section No. 3 Section 3 - Staff Ablutions Female Bill No. 1 Earthworks (Provisional Sums) Re-Solve Consulting</p> | | | | |

| Brought Forward | | | R |
|--|--|----|------|
| <u>Extra over all excavations for carting away</u> | | | |
| 3/1/8 | Surplus material from excavations on site to a dumping site to be located by the contractor | m3 | 71 |
| <u>Risk of collapse of excavations</u> | | | |
| 3/1/9 | Sides of trench and hole excavations not exceeding 1,5m deep | m2 | 282 |
| <u>Keeping excavations free of water</u> | | | |
| 3/1/10 | Keeping excavations free of all water other than subterranean water | | Item |
| <u>Earth filling obtained from the excavations and /or prescribed stock piles on site including compacted to 93% Mod AASHTO density</u> | | | |
| 3/1/11 | Under floors, steps, paving, etc | m3 | 14 |
| 3/1/12 | Backfilling to trenches, holes, etc | m3 | 20 |
| <u>Compaction of surfaces</u> | | | |
| 3/1/13 | Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density | m2 | 62 |
| 3/1/14 | Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density (Enviro Loo Tanks Pit) | m2 | 31 |
| 3/1/15 | Ditto but to bottom of trenches and bases | m2 | 44 |
| <u>Prescribed density tests on filling</u> | | | |
| 3/1/16 | Modified AASHTO Density | No | 3 |
| <u>SOIL POISONING</u> | | | |
| Carried Forward | | | R |
| Section No. 3 Section 3 - Staff Ablutions Female Bill No. 1 Earthworks (Provisional Sums) Re-Solve Consulting | | | |

| Brought Forward | | | R |
|--|---|----|-----|
| | <u>Weedkiller mixed in accordance to supplier's specifications</u> | | |
| 3/1/17 | To bottoms and sides of trenches, etc. | m2 | 227 |
| 3/1/18 | Under floors etc including forming and poisoning shallow furrows against foundation walls etc, filling in furrows and ramming(pits) | m2 | 123 |
| | <u>Soil insecticide</u> | | |
| 3/1/19 | To bottoms and sides of trenches etc | m2 | 227 |
| 3/1/20 | Under floors etc including forming and poisoning shallow furrows against foundation walls etc, filling in furrows and ramming(pits) | m2 | 103 |
| Carried Forward to Summary of Section No. 3 | | | R |
| Section No. 3 | | | |
| Section 3 - Staff Ablutions Female | | | |
| Bill No. 1 | | | |
| Earthworks (Provisional Sums) | | | |
| Re-Solve Consulting | | | |

| Item No | | Quantity | Rate | Amount |
|---------|---|----------|------|--------|
| | <u>SECTION 3</u> | | | |
| | <u>BILL NO. 2</u> | | | |
| | <u>CONCRETE, FORMWORK AND REINFORCEMENT</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>UNREINFORCED CONCRETE, ETC.</u> | | | |
| | <u>15MPa/19mm concrete</u> | | | |
| 3/2/1 | Surface blinding under footings and bases | m3 | 4 | |
| 3/2/2 | Aprons cast in panels to falls | m3 | 2 | |
| 3/2/3 | Extra over concrete in surface beds for thickening 85mm deep the bottom including all excavation, backfilling etc | m | 28 | |
| 3/2/4 | Extra over for concrete thickening in aprons size approximately 100mm deep, 400mm at top and tapering one side to 200mm at bottom, including all excavations, cart away, etc. | m | 23 | |
| | <u>REINFORCED CONCRETE</u> | | | |
| | <u>25MPa/19mm concrete</u> | | | |
| 3/2/5 | Strip footings | m3 | 9 | |
| 3/2/6 | Ramps | m3 | 2 | |
| 3/2/7 | Surface beds cast in panels on waterproofing. | m3 | 4 | |
| 3/2/8 | Slabs (pits) | m3 | 4 | |
| | Carried Forward | | | R |
| | Section No. 3 Section 3 - Staff Ablutions Female Bill No. 2 Concrete, Formwork and Reinforcement Re-Solve Consulting | | | |

| Brought Forward | | R |
|--|---|----------|
| <u>TEST CUBES</u> | | |
| 3/2/9 | Allow for preparing a set of three concrete strength test cubes, each size 150 x 150 x 150mm, sending them to an approved Testing Laboratory for testing and paying all charges in connection therewith | Sets 4.0 |
| <u>CONCRETE SUNDRIES</u> | | |
| <u>Finishing top surfaces of concrete smooth with a wood float/steel trowel</u> | | |
| 3/2/10 | Surface beds, slabs, etc | m2 74 |
| 3/2/11 | Surface beds, slabs, etc (pits) | m2 29 |
| 3/2/12 | Aprons to falls | m2 20 |
| <u>SMOOTH FORMWORK (DEGREE OF ACCURACY I)</u> | | |
| <u>Rough formwork to sides</u> | | |
| 3/2/13 | Edges, risers, ends and reveals not exceeding 300mm high or wide | m 28 |
| <u>REINFORCEMENT (PROVISIONAL)</u> | | |
| <u>Fabric Reinforcement</u> | | |
| 3/2/14 | Mesh ref. No. 395 fabric reinforcement fixed horizontal in surface beds etc. | m2 90 |
| Carried Forward to Summary of Section No. 3 | | R |
| Section No. 3 | | |
| Section 3 - Staff Ablutions Female | | |
| Bill No. 2 | | |
| Concrete, Formwork and Reinforcement | | |
| Re-Solve Consulting | | |

| Item No | | Quantity | Rate | Amount |
|---------|---|----------|------|--------|
| | <p><u>SECTION 3</u></p> <p><u>BILL NO. 3</u></p> <p><u>MASONRY</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>BRICKWORK</u></p> <p><u>Sizes in descriptions</u></p> <p>Where sizes in descriptions are given in brick units, "one brick" shall represent the length and "half brick" the width of a brick</p> <p>Face bricks</p> <p>Bricks shall be ordered timeously to obtain uniformity in size and colour</p> <p>Pointing</p> <p>Descriptions of recessed pointing to fair face brickwork and face brickwork shall be deemed to include square recessed, hollow recessed, weathered pointing, etc</p> <p><u>FOUNDATIONS (PROVISIONAL)</u></p> <p><u>Brickwork of NFP bricks in class II mortar</u></p> | | | |
| 3/3/1 | One brick walls | m2 | 74 | |
| | <p><u>FACE BRICKWORK</u></p> | | | |
| | Carried Forward | | | R |
| | <p>Section No. 3 Section 3 - Staff Ablutions Female Bill No. 3 Masonry Re-Solve Consulting</p> | | | |

| Brought Forward | | | R |
|--|---|----|-----|
| <u>Face bricks (purchase price of R5 000.00/1000 delivered to site excluding VAT) pointed with flush horizontal and vertical joints</u> | | | |
| 3/3/2 | Extra over brickwork for face brickwork in foundations | m2 | 6 |
| <u>SUPERSTRUCTURE</u> | | | |
| <u>Brickwork of NFP bricks in class II mortar</u> | | | |
| 3/3/3 | Half brick walls | m2 | 17 |
| 3/3/4 | Half brick walls in beamfilling | m2 | 6 |
| 3/3/5 | One brick walls | m2 | 82 |
| <u>FACE BRICKWORK</u> | | | |
| 3/3/6 | Extra over brickwork for face brickwork | m2 | 79 |
| 3/3/7 | Extra over brickwork for brick-on-edge header course lintel | m | 11 |
| 3/3/8 | 220mm Wide sill set sloping and slightly protecting outside | m | 11 |
| 3/3/9 | Fair cutting fitting around pipe exceeding 100mm and not exceeding 200mm diameter | No | 7 |
| <u>BRICKWORK SUNDRIES</u> | | | |
| <u>Brickwork reinforcement</u> | | | |
| 3/3/10 | 75mm Wide reinforcement built in horizontally | m | 17 |
| 3/3/11 | 150mm Wide reinforcement built in horizontally | m | 159 |
| <u>Galvanised wire ties etc</u> | | | |
| 3/3/12 | 6mm Diameter roof tie 2m long with one end fixed to timber and other end built into brickwork | No | 32 |
| Carried Forward | | | R |
| Section No. 3 Section 3 - Staff Ablutions Female Bill No. 3 Masonry Re-Solve Consulting | | | |

| Brought Forward | | | R |
|--|---|----|----|
| <u>Turning pieces to lintels etc.</u> | | | |
| 3/3/13 | 115mm Wide turning pieces | m | 12 |
| 3/3/14 | 230mm Wide turning pieces | m | 7 |
| <u>Prestressed fabricated lintels</u> | | | |
| 3/3/15 | 110 x 75mm Lintels in lengths exceeding 3m and not exceeding 6m | m | 33 |
| <u>Air bricks etc.</u> | | | |
| 3/3/16 | 230 x 152mm terra-cotta vermin proofed louvered air brick | No | 4 |
| Carried Forward to Summary of Section No. 3 | | | R |
| Section No. 3 | | | |
| Section 3 - Staff Ablutions Female | | | |
| Bill No. 3 | | | |
| Masonry | | | |
| Re-Solve Consulting | | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION 3</u> | | | |
| | <u>BILL NO. 4</u> | | | |
| | <u>WATERPROOFING</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>DAMP-PROOFING OF WALLS AND FLOORS</u> | | | |
| | <u>One layer of 375 micron Consol Plastic Brikgrip DPC" embossed damp proof course</u> | | | |
| 3/4/1 | In walls | m2 | 96 | |
| | <u>One layer of 250 micron "Consol Plastic USB Green" waterproof sheeting sealed at laps with "Gunplas Pressure Sensitive Tape"</u> | | | |
| 3/4/2 | Under surface beds | m2 | 120 | |
| 3/4/3 | Under aprons and ramps | m2 | 2 | |
| | <u>FLOOR AND WALL SEALERS</u> | | | |
| | <u>Secomastic non setting mastic sealant applied cold with a hand pressure caulking gun and leave perfectly watertight</u> | | | |
| 3/4/4 | Around steel windows and door frames | m | 21 | |
| | Carried Forward to Summary of Section No. 3 | | | R |
| | Section No. 3 | | | |
| | Section 3 - Staff Ablutions Female | | | |
| | Bill No. 4 | | | |
| | Waterproofing | | | |
| | Re-Solve Consulting | | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION 3</u> | | | |
| | <u>BILL NO. 5</u> | | | |
| | <u>ROOF COVERINGS ETC</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>PROFILED METAL SHEETING AND ACCESSORIES</u> | | | |
| | <u>0,6mm "Kliplok" roof sheeting in chromadek finish fixed to timber purlins (elsewhere)</u> | | | |
| 3/5/1 | Roof covering with pitch not exceeding 25 degrees | m2 | 43 | |
| | <u>ROOF AND WALL INSULATION</u> | | | |
| 3/5/2 | 12" Thermal resistance sisalition laid on purlins | m2 | 43 | |
| | <u>RAINWATER DISPOSAL</u> | | | |
| | For preambles see "Model Preambles for Trades (2008 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>Aluminium Zinc Seamless Gutters</u> | | | |
| 3/5/3 | 100 x 100mm sandard rainwater gutters fixed with gutter brackets | m | 10 | |
| 3/5/4 | Extra over eaves gutter for stopped end | No | 2 | |
| 3/5/5 | 75 x 100mm Diameter rainwater down pipes fixed to wall | m | 6 | |
| 3/5/6 | Extra over eaves gutter for outlet for 75 x 100mm down pipe | No | 2 | |
| 3/5/7 | Ditto .for shoe | No | 2 | |
| | Carried Forward to Summary of Section No. 3 | | | R |
| | Section No. 3 Section 3 - Staff Ablutions Female Bill No. 5 Roof Coverings Re-Solve Consulting | | | |

| Item No | | Quantity | Rate | Amount |
|---------|---|----------|------|--------|
| | <p><u>SECTION 3</u></p> <p><u>BILL NO. 6</u></p> <p><u>CARPENTRY AND JOINERY</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>ROOFS, ETC.</u></p> <p><u>Plate nailed timber roof truss construction</u></p> | | | |
| 3/6/1 | <p>Design, manufacture and deliver on site, plate nailed roof truss construction to Female Staff Ablutions Block, size 9 860 x 4 068 mm overall on plan consisting of mono pitched trusses to suit, with 350mm eaves overhang projecting , including all necessary purlins, runners, bracing and cross bracing (wall plates elsewhere) all in accordance with suppliers and manufacturer's recommendations:</p> <p>Trusses are at maximum 1,10m centres. Roof covering is galvanised "IBR" roof sheeting (measured elsewhere) on 50 x 75mm purlins at 1,1m maximum centres. All timber to be sawn softwood in accordance with V4 or M4 as defined in SABS 563 or SABS 1245. Metal connector plates shall have a minimum yield strength of 228 MPa and a minimum ultimate tensile strength of 330 Mpa with hot-dip galvanised finish. All joints to be close fitted butt joints. Trusses shall be designed by a registered supplier of prefabricated trusses who shall issue an Engineers Certificate upon completion of the installation. The dimensions in the descriptions of the trusses are nominal and actual measurements are to be obtained on site before design or fabrication commences. Tenderers must study the roof plan and sections as attached to the back of these bills of quantities and must obtain prices from a qualified and registered roof truss supplier as no claims in this regard will be entertained.</p> | No | 1 | |
| | Carried Forward | | | R |
| | <p>Section No. 3 Section 3 - Staff Ablutions Female Bill No. 6 Carpentry and Joinery Re-Solve Consulting</p> | | | |

| Brought Forward | | | R |
|--|---|----|------|
| 3/6/2 | Profit (As per rate build build up) | | Item |
| 3/6/3 | Take delivery, temporary store, hoist in position and erect plate nailed timber roof trusses, purlins, gangboarding, temporary and permanent bracing, etc (measured on slope of roof) | | Item |
| <u>Sawn softwood</u> | | | |
| 3/6/4 | 38 x 114mm Wall plates | m | 32 |
| <u>Sundries</u> | | | |
| 3/6/5 | Two coats creosote on sawn timbers | m2 | 40 |
| 3/6/6 | 6mm Diameter galvanised wire tie 3000mm girth wrapped around rafter and purlin with ends tied together | No | 32 |
| 3/6/7 | Hurricane clips | No | 32 |
| <u>EAVES, VERGES, ETC</u> | | | |
| <u>Pressed fibre-cement:</u> | | | |
| 3/6/8 | 15 x 230mm Nutec Fascias and barge boards including galvanised steel H-profile jointing strips | m | 10 |
| <u>DOORS, ETC</u> | | | |
| <u>Wrought meranti doors hung to steel frames</u> | | | |
| 3/6/9 | 44mm framed, ledged and braced door 877 x 2064mm high including external weather bar (D1) | No | 2 |
| 3/6/10 | 44mm framed, ledged and braced door 813 x 1914mm high (door raised by 150mm from bottom) (D2) | No | 7 |
| 3/6/11 | 44mm framed, ledged and braced door 915 x 2032mm high including external weather bar (disabled) | No | 1 |
| Carried Forward to Summary of Section No. 3 | | | R |
| Section No. 3 | | | |
| Section 3 - Staff Ablutions Female | | | |
| Bill No. 6 | | | |
| Carpentry and Joinery | | | |
| Re-Solve Consulting | | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION 3</u> | | | |
| | <u>BILL NO. 7</u> | | | |
| | <u>IRONMONGERY</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>HINGES, BOLTS, ETC</u> | | | |
| | <u>100mm Chrome plated "D" type handle 3 by solid brace hinges</u> | | | |
| | <u>CATCHES,CABIN HOOKS, ETC</u> | | | |
| 3/7/1 | 100mm brace Cabin hook and eye including 70 x 70 x 20mm chamfered hardwood block twice oiled and plugged | No | 2 | |
| | <u>LOCKS</u> | | | |
| | <u>Approved</u> | | | |
| 3/7/2 | Three lever mortice lock set | No | 3 | |
| 3/7/3 | Indicator lock set | No | 7 | |
| 3/7/4 | Security double throw dead lock (no latch) | No | 2 | |
| | <u>HANDLES, ETC.</u> | | | |
| | <u>Aluminium Pull Handle</u> | | | |
| 3/7/5 | ASSA ABLOY Anodised Silver straight pull handle (Code: AL5515-300BBAS) with 300mm fixing centres. | No | 10 | |
| | <u>SUNDRIES</u> | | | |
| | Carried Forward | | | R |
| | Section No. 3 Section 3 - Staff Ablutions Female Bill No. 7 Ironmongery Re-Solve Consulting | | | |

| Brought Forward | | | R |
|--|--|----|----|
| <u>ASSA ABLOY</u> | | | |
| 3/7/6 | 38mm Diameter rubber door stop plugged | No | 10 |
| <u>Vaal Paragon</u> | | | |
| 3/7/7 | 32mm Type 9 back grab rail 800mm long plugged | No | 1 |
| 3/7/8 | 32mm Type 8 side grab rail 900mm girth plugged | No | 1 |
| <u>LETTERS, NAMEPLATES, ETC</u> | | | |
| <u>Dorma:</u> | | | |
| 3/7/9 | DSS-130 Engraved "Female" information sign, plugged | No | 2 |
| 3/7/10 | DSS-133 Engraved "Disabled" information sign, plugged | No | 1 |
| <u>BATHROOM FITTINGS</u> | | | |
| <u>Sundries</u> | | | |
| <u>Kimberley-Clark or Similar</u> | | | |
| 3/7/11 | SQ2 code 405607B white none lockable toilet roll holder | No | 8 |
| <u>stainless Steel</u> | | | |
| 3/7/12 | Stainless steel mirror size: 350 x 400mm plugged to wall with chrome plated screws. | No | 3 |
| 3/7/13 | Brushed stainless steel body, rust resistant, she bin, approximately 330 x 280 x 180mm etc | No | 8 |
| Carried Forward to Summary of Section No. 3 | | | R |
| Section No. 3 | | | |
| Section 3 - Staff Ablutions Female | | | |
| Bill No. 7 | | | |
| Ironmongery | | | |
| Re-Solve Consulting | | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION 3</u> | | | |
| | <u>BILL NO. 8</u> | | | |
| | <u>METALWORK</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>WELDED SCREENS, GATES, ETC</u> | | | |
| | <u>Gates to external doors</u> | | | |
| 3/8/1 | Purpose made square hollow section mild steel single security gate and frame size to fit standard door, size 813 x 2032mm high | No | 2 | |
| 3/8/2 | Single gate and frame size to fit none standard door, size approximately 915 x 2032mm high (disable) | No | 1 | |
| | <u>PRESSED STEEL DOOR FRAMES</u> | | | |
| | <u>1,2mm Double rebated frames suitable for half brick walls</u> | | | |
| 3/8/3 | Frame for door size 813 x 1914mm high | No | 7 | |
| | <u>1,2mm Double rebated frames suitable for one brick walls</u> | | | |
| 3/8/4 | Frame for door size 914 x 2032mm high | No | 1 | |
| | <u>1.2mm Single rebate steel frame suitable for one brick wall</u> | | | |
| 3/8/5 | Frame for door size 813 x 2032mm high | No | 2 | |
| | <u>STEEL WINDOWS, DOORS, ETC</u> | | | |
| | Carried Forward | | | R |
| | Section No. 3 Section 3 - Staff Ablutions Female Bill No. 8 Metalwork Re-Solve Consulting | | | |

| | Brought Forward | | | R |
|--|--|----|---|---|
| | <u>Nty steel or similar approved school windows with standard burglar bars formed of 20 x 5mm thick flat bars to all sashes</u> | | | |
| 3/8/6 | Window type NE1, size 533 x 654mm high | No | 8 | |
| 3/8/7 | Window type NE7, size 1022 x 654mm high | No | 3 | |
| | <u>Sundries</u> | | | |
| | <u>Cage, etc</u> | | | |
| 3/8/8 | She bin cages, to fit 330 x 280 x 180mm width, she bin to be able to open, including pad lock and locking mechanism, complete, etc | No | 8 | |
| Carried Forward to Summary of Section No. 3 | | | | |
| Section No. 3 | | | | R |
| Section 3 - Staff Ablutions Female | | | | |
| Bill No. 8 | | | | |
| Metalwork | | | | |
| Re-Solve Consulting | | | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION 3</u> | | | |
| | <u>BILL NO. 9</u> | | | |
| | <u>PLASTERING</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>GRANOLITHIC</u> | | | |
| | <u>Untinted granolithic on concrete</u> | | | |
| 3/9/1 | 20mm Thick on floors | m2 | 39 | |
| | <u>INTERNAL PLASTER</u> | | | |
| | <u>Cement plaster on brickwork or blockwork</u> | | | |
| 3/9/2 | On internal plastered walls(pits) | m2 | 86 | |
| | <u>FLOOR AND WALLS SEALERS</u> | | | |
| | <u>Minimum two coats approved epoxy coat:</u> | | | |
| 3/9/3 | On floors in pits | m2 | 1 | |
| 3/9/4 | On internal plastered walls in pits | m2 | 86 | |
| | Carried Forward to Summary of Section No. 3 | | | R |
| | Section No. 3 | | | |
| | Section 3 - Staff Ablutions Female | | | |
| | Bill No. 9 | | | |
| | Plastering | | | |
| | Re-Solve Consulting | | | |

| Item No | | Quantity | Rate | Amount |
|---------|---|----------|------|--------|
| | <u>SECTION 3</u> | | | |
| | <u>BILL NO. 10</u> | | | |
| | <u>PLUMBING AND DRAINAGE(PROVISIONAL)</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>SANITARY FITTINGS</u> | | | |
| | <u>"Vaal" or similar and approved</u> | | | |
| 3/10/1 | Ceramic wall mounted wash hand basin, complete with all fittings and accesseries including cutting & making good wall & floor wherever required for disable toilets. | No | 1 | |
| | <u>SUPPLY AND INSTALL "ENVIRO-LOO" TOILET SYSTEMS</u> | | | |
| 3/10/2 | Supply and Install "Enviro-Loo" Industrial 1040 Model complete,installed strictly in accordance with manufacturers instructions, unit comprising of top unit and two x louvred inlets , drying plate , two x air inlets, standard toilet pan, seat and lid, 3500mm long outlet vent pipe, ventilation extraction unit fixed to wall with vent wall bracket, 1 bag mounting screws and organic starter, enzyme and toilet cleaner including all necessary inter connector piping between multiple tanks, emergency outlet piping,etc | No | 7 | |
| | <u>PRECAST CONCRETE WASH HAND TROUGH</u> | | | |
| 3/10/3 | Supply and install pre-cast concrete double wash-trough, complete with all necessary pipework including soakaway size 1000 x 1000 x 1000mm covered with "bidim" | No | 2 | |
| | <u>SOIL DRAINAGE</u> | | | |
| | Carried Forward | | | R |
| | Section No. 3 Section 3 - Staff Ablutions Female Bill No. 10 Plumbing and Drainage (Provisional) Re-Solve Consulting | | | |

Brought Forward

R

uPVC pipes

| | | | |
|--------|--|---|----|
| 3/10/4 | 110mm Pipes laid in and including trenches not exceeding 1m deep | m | 40 |
|--------|--|---|----|

Extra over uPVC pipes for fittings

| | | | |
|--------|------------|----|---|
| 3/10/5 | 110mm Bend | No | 8 |
|--------|------------|----|---|

| | | | |
|--------|----------------|----|---|
| 3/10/6 | 110mm Junction | No | 8 |
|--------|----------------|----|---|

uPVC gulleys

| | | | |
|--------|--|----|---|
| 3/10/7 | 110mm Gully not exceeding 750mm deep, including excavations, pre-cast concrete surround etc. | No | 3 |
|--------|--|----|---|

TRAPS ETC

Marley

| | | | |
|--------|--|----|---|
| 3/10/8 | 40 x 300mm Sink combination for double bowl with deepseal "P" trap | No | 3 |
|--------|--|----|---|

TAPS, VALVES, ETC

| | | | |
|--------|---|----|---|
| 3/10/9 | Cobra Watertech 15mm gate valve plugged | No | 2 |
|--------|---|----|---|

| | | | |
|---------|--|----|---|
| 3/10/10 | Cobra Watertech 15mm Elbow action pillar tap | No | 1 |
|---------|--|----|---|

SANITARY PLUMBING

uPVC pipes

| | | | |
|---------|------------|---|----|
| 3/10/11 | 50mm Pipes | m | 30 |
|---------|------------|---|----|

Extra over uPVC pipes for fittings

| | | | |
|---------|-----------|----|---|
| 3/10/12 | 50mm Bend | No | 8 |
|---------|-----------|----|---|

| | | | |
|---------|------------------|----|---|
| 3/10/13 | 50mm Access bend | No | 8 |
|---------|------------------|----|---|

| | | | |
|---------|---------------|----|---|
| 3/10/14 | 50mm Junction | No | 8 |
|---------|---------------|----|---|

WATER SUPPLIES

Carried Forward

R

Section No. 3
Section 3 - Staff Ablutions Female
Bill No. 10
Plumbing and Drainage (Provisional)
Re-Solve Consulting

Brought Forward

R

Class 0 copper pipes

| | | | |
|--|---------------|----|----|
| 3/10/15 | 15mm Pipes | m | 25 |
| 3/10/16 | 22mm Pipes | m | 20 |
| <u>Extra over class 0 copper pipes for capillary fittings</u> | | | |
| 3/10/17 | 15mm Fittings | No | 8 |
| 3/10/18 | 22mm Pipes | No | 5 |

TESTING

| | | | |
|---------|---|--|------|
| 3/10/19 | Allow for testing all drains, sanitary plumbing, water supplies and installtion to the satisfaction of the Principle Agent. | | Item |
|---------|---|--|------|

Carried Forward to Summary of Section No. 3

R

Section No. 3
 Section 3 - Staff Ablutions Female
 Bill No. 10
 Plumbing and Drainage (Provisional)
Re-Solve Consulting

| Item No | Quantity | Rate | Amount |
|--|----------|------|--------|
| <p><u>SECTION 3</u></p> <p><u>BILL NO. 12</u></p> <p><u>PAINTWORK</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>PAINTWORK ETC TO NEW WORK</u></p> <p><u>PREPARATORY WORK TO EXISTING WORK</u></p> <p><u>Previously painted plastered surfaces</u></p> <p>Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and cracks shall be opened, filled with a suitable filler and finished smooth</p> <p>Previously painted metal surfaces</p> <p>Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal</p> <p>Previously painted wood surfaces</p> <p>Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth</p> <p><u>ON FIBRE-CEMENT</u></p> | | | |
| Carried Forward | | R | |
| <p>Section No. 3 Section 3 - Staff Ablutions Female Bill No. 12 Paintwork Re-Solve Consulting</p> | | | |

Brought Forward

R

Prepare and brush to remove all loose contaminations, apply one coat primer and two coats PVA emulsion paint

3/12/1 On fascias and barge boards m2 5

ON METAL

Prime and paint undercoat and 2 finishing coats in gloss enamel, colour TBC.

3/12/2 On door frames m2 32

Spot prining defects in pre-prime surface with zinc chromate primer and apply one universal undercoat and two coats EPWP. golden brown gloss enamel paint on steel

3/12/3 On windows with burglar bars m2 5

ON WOOD

Under coat and minimum 2 coats gloss enamel, colour TBC

3/12/4 On doors (External) m2 4

3/12/5 On doors (Internal) m2 14

Carried Forward to Summary of Section No. 3

R

Section No. 3
 Section 3 - Staff Ablutions Female
 Bill No. 12
 Paintwork
Re-Solve Consulting

Section No. 3

Section 3 - Staff Ablutions Female

SECTION SUMMARY - Section 3 - Staff Ablutions Female

| Bill No | | Page No | Amount |
|---------|--------------------------------------|---------|--------|
| 3/1 | Earthworks (Provisional Sums) | 32 | |
| 3/2 | Concrete, Formwork and Reinforcement | 34 | |
| 3/3 | Masonry | 37 | |
| 3/4 | Waterproofing | 38 | |
| 3/5 | Roof Coverings | 39 | |
| 3/6 | Carpentry and Joinery | 41 | |
| 3/7 | Ironmongery | 43 | |
| 3/8 | Metalwork | 45 | |
| 3/9 | Plastering | 46 | |
| 3/10 | Plumbing and Drainage (Provisional) | 49 | |
| 3/11 | Glazing | 50 | |
| 3/12 | Paintwork | 52 | |
| | Carried to Final Summary | | R |
| | Section No. 3 | | |
| | Section 3 - Staff Ablutions Female | | |
| | Re-Solve Consulting | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <p><u>SECTION 4</u></p> <p><u>BILL NO. 1</u></p> <p><u>EARTHWORKS (PROVISIONAL)</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p>Nature of ground</p> <p>Use "assumed to be" if no trial holes, soils investigations, etc have been carried out - discuss with engineer. Use "Trial holes indicate that" where the ground has been investigated by means of trial holes</p> <p>Nature of ground</p> <p>A soils investigation has been carried out on site by the engineer and the report is annexed to these bills of quantities. Descriptions of excavations shall be deemed to include all ground conditions classifiable as "earth" described in the above report and where conditions of a more difficult character are indicated these are separately measured</p> <p>Carting away of excavated material</p> <p>Descriptions of carting away of excavated material shall be deemed to include loading excavated material onto trucks directly from the excavations or, alternatively, from stock piles situated on the building site</p> <p>Filling</p> | | | |
| | Carried Forward | | R | |
| | <p>Section No. 4 Section 4 - Staff Ablutions Male Bill No. 1 Earthworks (Provisional) Re-Solve Consulting</p> | | | |

| Brought Forward | | | | R |
|---|--|----|-----|---|
| <p>Notwithstanding the reference to prescribed multiple handling in clause 1 page 6 of the Standard System of Measuring Building Work, prices for filling and backfilling shall include for all selection and any multiple handling of material</p> <p>Soil poisoning</p> <p><u>Ant and weed poisoning will be applied in accordance to SABS specifications by Registered and Approved Specialists who will issue a five (5) year guarantee. The contractor will only be paid for this items once they have produced the said certificate to the Principal Agent</u></p> <p><u>SITE CLEARANCE ETC</u></p> <p><u>Site clearance</u></p> | | | | |
| 4/1/1 | Digging up and removing rubbish, debris, vegetation, hedges, shrubs and trees not exceeding 200mm girth, bush, etc | m2 | 132 | |
| 4/1/2 | Stripping average 100mm thick layer of top soil and stockpiling on site | m2 | 132 | |
| <p><u>EXCAVATION, FILLING, ETC</u></p> <p><u>Excavation in earth not exceeding 2m deep</u></p> | | | | |
| 4/1/3 | Trenches | m3 | 57 | |
| 4/1/4 | Pits | m3 | 57 | |
| 4/1/5 | Thickening under aprons | m3 | 1 | |
| <p><u>Extra over trench and hole excavations in earth for excavation in</u></p> | | | | |
| 4/1/6 | Soft rock | m3 | 8 | |
| 4/1/7 | Hard rock | m3 | 4 | |
| Carried Forward | | | | R |
| <p>Section No. 4 Section 4 - Staff Ablutions Male Bill No. 1 Earthworks (Provisional) Re-Solve Consulting</p> | | | | |

| Brought Forward | | | R |
|--|--|----|------|
| <u>Extra over all excavations for carting away</u> | | | |
| 4/1/8 | Surplus material from excavations on site to a dumping site to be located by the contractor | m3 | 90 |
| <u>Risk of collapse of excavations</u> | | | |
| 4/1/9 | Sides of trench and hole excavations not exceeding 1,5m deep | m2 | 352 |
| <u>Keeping excavations free of water</u> | | | |
| 4/1/10 | Keeping excavations free of all water other than subterranean water | | Item |
| <u>Earth filling obtained from the excavations and /or prescribed stock piles on site including compacted to 93% Mod AASHTO density</u> | | | |
| 4/1/11 | Under floors, steps, paving, etc | m3 | 19 |
| 4/1/12 | Backfilling to trenches, holes, etc | m3 | 25 |
| <u>Compaction of surfaces</u> | | | |
| 4/1/13 | Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density | m2 | 90 |
| 4/1/14 | Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density (Enviro Loo Tanks Pit) | m2 | 38 |
| 4/1/15 | Ditto but to bottom of trenches and bases | m2 | 56 |
| <u>Prescribed density tests on filling</u> | | | |
| 4/1/16 | Modified AASHTO Density | No | 3 |
| <u>SOIL POISONING</u> | | | |
| Carried Forward | | | R |
| Section No. 4 Section 4 - Staff Ablutions Male Bill No. 1 Earthworks (Provisional) Re-Solve Consulting | | | |

| Brought Forward | | R |
|---|---|--------|
| <u>Weedkiller mixed in accordance to supplier's specifications</u> | | |
| 4/1/17 | To bottoms and sides of trenches, etc. | m2 285 |
| 4/1/18 | Under floors etc including forming and poisoning shallow furrows against foundation walls etc, filling in furrows and ramming(pits) | m2 176 |
| <u>Soil insecticide</u> | | |
| 4/1/19 | To bottoms and sides of trenches etc | m2 285 |
| 4/1/20 | Under floors etc including forming and poisoning shallow furrows against foundation walls etc, filling in furrows and ramming(pits) | m2 148 |
| Carried Forward to Summary of Section No. 4 | | R |
| Section No. 4 | | |
| Section 4 - Staff Ablutions Male | | |
| Bill No. 1 | | |
| Earthworks (Provisional) | | |
| Re-Solve Consulting | | |

| Item No | | Quantity | Rate | Amount |
|---------|---|----------|------|--------|
| | <u>SECTION 4</u> | | | |
| | <u>BILL NO. 2</u> | | | |
| | <u>CONCRETE, FORMWORK AND REINFORCEMENT</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>UNREINFORCED CONCRETE, ETC.</u> | | | |
| | <u>15MPa/19mm concrete</u> | | | |
| 4/2/1 | Surface blinding under footings and bases | m3 | 5 | |
| 4/2/2 | Aprons cast in panels to falls | m3 | 3 | |
| 4/2/3 | Extra over concrete in surface beds for thickening 85mm deep the bottom including all excavation, backfilling etc | m | 38 | |
| 4/2/4 | Extra over for concrete thickening in aprons size approximately 100mm deep, 400mm at top and tapering one side to 200mm at bottom, including all excavations, cart away, etc. | m | 28 | |
| | <u>REINFORCED CONCRETE</u> | | | |
| | <u>25MPa/19mm concrete</u> | | | |
| 4/2/5 | Strip footings | m3 | 12 | |
| 4/2/6 | Ramps | m3 | 2 | |
| 4/2/7 | Surface beds cast in panels on waterproofing. | m3 | 6 | |
| 4/2/8 | Slabs (pits) | m3 | 5 | |
| | Carried Forward | | | R |
| | Section No. 4 Section 4 - Staff Ablutions Male Bill No. 2 Concrete, Formwork and Reinforcement Re-Solve Consulting | | | |

Brought Forward

R

TEST CUBES

| | | | |
|-------|---|------|-----|
| 4/2/9 | Allow for preparing a set of three concrete strength test cubes, each size 150 x 150 x 150mm, sending them to an approved Testing Laboratory for testing and paying all charges in connection therewith | Sets | 4.0 |
|-------|---|------|-----|

CONCRETE SUNDRIES

Finishing top surfaces of concrete smooth with a wood float/steel trowel

| | | | |
|--------|---------------------------------|----|-----|
| 4/2/10 | Surface beds, slabs, etc | m2 | 112 |
| 4/2/11 | Surface beds, slabs, etc (pits) | m2 | 36 |
| 4/2/12 | Aprons to falls | m2 | 28 |

SMOOTH FORMWORK (DEGREE OF ACCURACY I)

Rough formwork to sides

| | | | |
|--------|--|---|----|
| 4/2/13 | Edges, risers, ends and reveals not exceeding 300mm high or wide | m | 38 |
|--------|--|---|----|

REINFORCEMENT (PROVISIONAL)

Fabric Reinforcement

| | | | |
|--------|---|----|-----|
| 4/2/14 | Mesh ref. No. 395 fabric reinforcement fixed horizontalt in surface beds etc. | m2 | 126 |
|--------|---|----|-----|

Carried Forward to Summary of Section No. 4

R

Section No. 4
 Section 4 - Staff Ablutions Male
 Bill No. 2
 Concrete, Formwork and Reinforcement
Re-Solve Consulting

| Item No | | Quantity | Rate | Amount |
|---------|---|----------|------|--------|
| | <p><u>SECTION 4</u></p> <p><u>BILL NO. 3</u></p> <p><u>MASONRY</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>BRICKWORK</u></p> <p><u>Sizes in descriptions</u></p> <p>Where sizes in descriptions are given in brick units, "one brick" shall represent the length and "half brick" the width of a brick</p> <p>Face bricks</p> <p>Bricks shall be ordered timeously to obtain uniformity in size and colour</p> <p>Pointing</p> <p>Descriptions of recessed pointing to fair face brickwork and face brickwork shall be deemed to include square recessed, hollow recessed, weathered pointing, etc</p> <p><u>FOUNDATIONS (PROVISIONAL)</u></p> <p><u>Brickwork of NFP bricks in class II mortar</u></p> | | | |
| 4/3/1 | One brick walls | m2 | 91 | |
| | <p><u>FACE BRICKWORK</u></p> | | | |
| | Carried Forward | | | R |
| | <p>Section No. 4 Section 4 - Staff Ablutions Male Bill No. 3 Masonry Re-Solve Consulting</p> | | | |

| Brought Forward | | | R |
|--|---|----|-----|
| <u>Face bricks (purchase price of R5 000.00/1000 delivered to site excluding VAT) pointed with flush horizontal and vertical joints</u> | | | |
| 4/3/2 | Extra over brickwork for face brickwork in foundations | m2 | 7 |
| <u>SUPERSTRUCTURE</u> | | | |
| <u>Brickwork of NFP bricks in class II mortar</u> | | | |
| 4/3/3 | Half brick walls | m2 | 29 |
| 4/3/4 | Half brick walls in beamfilling | m2 | 8 |
| 4/3/5 | One brick walls | m2 | 96 |
| <u>FACE BRICKWORK</u> | | | |
| 4/3/6 | Extra over brickwork for face brickwork | m2 | 93 |
| 4/3/7 | Extra over brickwork for brick-on-edge header course lintel | m | 17 |
| 4/3/8 | 220mm Wide sill set sloping and slightly protecting outside | m | 17 |
| 4/3/9 | Fair cutting fitting around pipe not exceeding 100mm | No | 9 |
| 4/3/10 | Fair cutting fitting around pipe exceeding 100mm and not exceeding 200mm diameter | No | 8 |
| <u>BRICKWORK SUNDRIES</u> | | | |
| <u>Brickwork reinforcement</u> | | | |
| 4/3/11 | 75mm Wide reinforcement built in horizontally | m | 29 |
| 4/3/12 | 150mm Wide reinforcement built in horizontally | m | 193 |
| <u>Galvanised wire ties etc</u> | | | |
| 4/3/13 | 6mm Diameter roof tie 2m long with one end fixed to timber and other end built into brickwork | No | 38 |
| Carried Forward | | | R |
| Section No. 4 Section 4 - Staff Ablutions Male Bill No. 3 Masonry Re-Solve Consulting | | | |

| Brought Forward | | | R |
|--|---|----|----|
| <u>Turning pieces to lintels etc.</u> | | | |
| 4/3/14 | 115mm Wide turning pieces | m | 16 |
| 4/3/15 | 230mm Wide turning pieces | m | 12 |
| <u>Prestressed fabricated lintels</u> | | | |
| 4/3/16 | 110 x 75mm Lintels in lengths exceeding 3m and not exceeding 6m | m | 40 |
| <u>Air bricks etc.</u> | | | |
| 4/3/17 | 230 x 152mm terra-cotta vermin proofed louvered air brick | No | 4 |
| Carried Forward to Summary of Section No. 4 | | | R |
| Section No. 4 | | | |
| Section 4 - Staff Ablutions Male | | | |
| Bill No. 3 | | | |
| Masonry | | | |
| Re-Solve Consulting | | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION 4</u> | | | |
| | <u>BILL NO. 4</u> | | | |
| | <u>WATERPROOFING</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>DAMP-PROOFING OF WALLS AND FLOORS</u> | | | |
| | <u>One layer of 375 micron Consol Plastic Brikgrip DPC" embossed damp proof course</u> | | | |
| 4/4/1 | In walls | m2 | 122 | |
| | <u>One layer of 250 micron "Consol Plastic USB Green" waterproof sheeting sealed at laps with "Gunplas Pressure Sensitive Tape"</u> | | | |
| 4/4/2 | Under surface beds | m2 | 174 | |
| 4/4/3 | Under aprons and ramps | m2 | 2 | |
| | <u>FLOOR AND WALL SEALERS</u> | | | |
| | <u>Secomastic non setting mastic sealant applied cold with a hand pressure caulking gun and leave perfectly watertight</u> | | | |
| 4/4/4 | Around steel windows and door frames | m | 28 | |
| | Carried Forward to Summary of Section No. 4 | | | R |
| | Section No. 4 | | | |
| | Section 4 - Staff Ablutions Male | | | |
| | Bill No. 4 | | | |
| | Waterproofing | | | |
| | Re-Solve Consulting | | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION 4</u> | | | |
| | <u>BILL NO. 5</u> | | | |
| | <u>ROOF COVERINGS ETC</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>PROFILED METAL SHEETING AND ACCESSORIES</u> | | | |
| | <u>0,6mm "Kliplok" roof sheeting in chromadek finish fixed to timber purlins (elsewhere)</u> | | | |
| 4/5/1 | Roof covering with pitch not exceeding 25 degrees | m2 | 65 | |
| | <u>ROOF AND WALL INSULATION</u> | | | |
| 4/5/2 | 12" Thermal resistance sisalition laid on purlins | m2 | 65 | |
| | <u>RAINWATER DISPOSAL</u> | | | |
| | For preambles see "Model Preambles for Trades (2008 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>Aluminium Zinc Seamless Gutters</u> | | | |
| 4/5/3 | 100 x 100mm sandard rainwater gutters fixed with gutter brackets | m | 15 | |
| 4/5/4 | Extra over eaves gutter for stopped end | No | 2 | |
| 4/5/5 | 75 x 100mm Diameter rainwater down pipes fixed to wall | m | 6 | |
| 4/5/6 | Extra over eaves gutter for outlet for 75 x 100mm down pipe | No | 2 | |
| 4/5/7 | Ditto .for shoe | No | 2 | |
| | Carried Forward to Summary of Section No. 4 | | | R |
| | Section No. 4 | | | |
| | Section 4 - Staff Ablutions Male | | | |
| | Bill No. 5 | | | |
| | Roof Coverings | | | |
| | Re-Solve Consulting | | | |

| Item No | | Quantity | Rate | Amount |
|---------|---|----------|------|--------|
| | <p><u>SECTION 4</u></p> <p><u>BILL NO. 6</u></p> <p><u>CARPENTRY AND JOINERY</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>ROOFS, ETC.</u></p> <p><u>Plate nailed timber roof truss construction</u></p> | | | |
| 4/6/1 | <p>Design, manufacture and deliver on site, plate nailed roof truss construction to Male Staff Ablutions Block, size 15 012 x 3 964 mm overall on plan consisting of mono pitched trusses to suit, with 350mm eaves overhang projecting , including all necessary purlins, runners, bracing and cross bracing (wall plates elsewhere) all in accordance with suppliers and manufacturer's recommendations:</p> <p>Trusses are at maximum 1,10m centres. Roof covering is galvanised "IBR" roof sheeting (measured elsewhere) on 50 x 75mm purlins at 1,1m maximum centres. All timber to be sawn softwood in accordance with V4 or M4 as defined in SABS 563 or SABS 1245. Metal connector plates shall have a minimum yield strength of 228 MPa and a minimum ultimate tensile strength of 330 Mpa with hot-dip galvanised finish. All joints to be close fitted butt joints. Trusses shall be designed by a registered supplier of prefabricated trusses who shall issue an Engineers Certificate upon completion of the installation. The dimensions in the descriptions of the trusses are nominal and actual measurements are to be obtained on site before design or fabricaton commences. Tenderers must study the roof plan and sections as attached to the back of these bills of quantities and must obtain prices from a qualified and registered roof truss supplier as no claims in this regard will be entertained.</p> | | | |
| 4/6/2 | Profit (As per rate build build up) | | | |
| | Carried Forward | | | |
| | <p>Section No. 4 Section 4 - Staff Ablutions Male Bill No. 6 Carpentry and Joinery Re-Solve Consulting</p> | | R | |

| Brought Forward | | | R |
|--|---|------|----|
| 4/6/3 | Take delivery, temporary store, hoist in position and erect plate nailed timber roof trusses, purlins, gangboarding, temporary and permanent bracing, etc (measured on slope of roof) | Item | |
| <u>Sawn softwood</u> | | | |
| 4/6/4 | 38 x 114mm Wall plates | m | 38 |
| <u>Sundries</u> | | | |
| 4/6/5 | Two coats creosote on sawn timbers | m2 | 54 |
| 4/6/6 | 6mm Diameter galvanised wire tie 3000mm girth wrapped around rafter and purlin with ends tied together | No | 38 |
| 4/6/7 | Hurricane clips | No | 38 |
| <u>EAVES, VERGES, ETC</u> | | | |
| <u>Pressed fibre-cement:</u> | | | |
| 4/6/8 | 15 x 230mm Nutec Fascias and barge boards including galvanised steel H-profile jointing strips | m | 15 |
| <u>DOORS, ETC</u> | | | |
| <u>Wrought meranti doors hung to steel frames</u> | | | |
| 4/6/9 | 44mm framed, ledged and braced door 877 x 2064mm high including external weather bar (D1) | No | 2 |
| 4/6/10 | 44mm framed, ledged and braced door 813 x 1914mm high (door raised by 150mm from bottom) (D2) | No | 8 |
| 4/6/11 | 44mm framed, ledged and braced door 915 x 2032mm high including external weather bar (disabled) | No | 1 |
| Carried Forward to Summary of Section No. 4 | | | R |
| Section No. 4 | | | |
| Section 4 - Staff Ablutions Male | | | |
| Bill No. 6 | | | |
| Carpentry and Joinery | | | |
| Re-Solve Consulting | | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION 4</u> | | | |
| | <u>BILL NO. 7</u> | | | |
| | <u>IRONMONGERY</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>HINGES, BOLTS, ETC</u> | | | |
| | <u>100mm Chrome plated "D" type handle 3 by solid brace hinges</u> | | | |
| | <u>CATCHES,CABIN HOOKS, ETC</u> | | | |
| 4/7/1 | 100mm brace Cabin hook and eye including 70 x 70 x 20mm chamfered hardwood block twice oiled and plugged | No | 2 | |
| | <u>LOCKS</u> | | | |
| | <u>Approved</u> | | | |
| 4/7/2 | Three lever mortice lock set | No | 3 | |
| 4/7/3 | Indicator lock set | No | 7 | |
| 4/7/4 | Security double throw dead lock (no latch) | No | 3 | |
| | <u>HANDLES, ETC.</u> | | | |
| | <u>Aluminium Pull Handle</u> | | | |
| 4/7/5 | ASSA ABLOY Anodised Silver straight pull handle (Code: AL5515-300BBAS) with 300mm fixing centres. | No | 10 | |
| | <u>SUNDRIES</u> | | | |
| | Carried Forward | | | R |
| | Section No. 4 Section 4 - Staff Ablutions Male Bill No. 7 Ironmongery Re-Solve Consulting | | | |

Brought Forward

R

ASSA ABLOY

| | | | |
|-------|--|----|----|
| 4/7/6 | 38mm Diameter rubber door stop plugged | No | 10 |
|-------|--|----|----|

Vaal Paragon

| | | | |
|-------|---|----|---|
| 4/7/7 | 32mm Type 9 back grab rail 800mm long plugged | No | 1 |
|-------|---|----|---|

| | | | |
|-------|--|----|---|
| 4/7/8 | 32mm Type 8 side grab rail 900mm girth plugged | No | 1 |
|-------|--|----|---|

LETTERS, NAMEPLATES, ETC

Dorma:

| | | | |
|-------|---|----|---|
| 4/7/9 | DSS-130 Engraved "Male" information sign, plugged | No | 2 |
|-------|---|----|---|

| | | | |
|--------|---|----|---|
| 4/7/10 | DSS-133 Engraved "Disabled" information sign, plugged | No | 1 |
|--------|---|----|---|

BATHROOM FITTINGS

Sundries

Kimberley-Clark or Similar

| | | | |
|--------|---|----|---|
| 4/7/11 | SQ2 code 405607B white none lockable toilet roll holder | No | 9 |
|--------|---|----|---|

stainless Steel

| | | | |
|--------|---|----|---|
| 4/7/12 | Stainless steel mirror size: 350 x 400mm plugged to wall with chrome plated screws. | No | 3 |
|--------|---|----|---|

Carried Forward to Summary of Section No. 4

R

Section No. 4
 Section 4 - Staff Ablutions Male
 Bill No. 7
 Ironmongery
Re-Solve Consulting

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION 4</u> | | | |
| | <u>BILL NO. 8</u> | | | |
| | <u>METALWORK</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>WELDED SCREENS, GATES, ETC</u> | | | |
| | <u>Gates to external doors</u> | | | |
| 4/8/1 | Purpose made square hollow section mild steel single security gate and frame size to fit standard door, size 813 x 2032mm high | No | 2 | |
| 4/8/2 | Single gate and frame size to fit none standard door, size approximately 915 x 2032mm high (disable) | No | 1 | |
| | <u>PRESSED STEEL DOOR FRAMES</u> | | | |
| | <u>1,2mm Double rebated frames suitable for half brick walls</u> | | | |
| 4/8/3 | Frame for door size 813 x 1914mm high | No | 8 | |
| | <u>1,2mm Double rebated frames suitable for one brick walls</u> | | | |
| 4/8/4 | Frame for door size 914 x 2032mm high | No | 1 | |
| | <u>1,2mm Single rebate steel frame suitable for one brick wall</u> | | | |
| 4/8/5 | Frame for door size 813 x 2032mm high | No | 2 | |
| | <u>STEEL WINDOWS, DOORS, ETC</u> | | | |
| | Carried Forward | | | R |
| | Section No. 4 Section 4 - Staff Ablutions Male Bill No. 8 Metalwork Re-Solve Consulting | | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION 4</u> | | | |
| | <u>BILL NO. 9</u> | | | |
| | <u>PLASTERING</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>GRANOLITHIC</u> | | | |
| | <u>Untinted granolithic on concrete</u> | | | |
| 4/9/1 | 20mm Thick on floors | m2 | 60 | |
| | <u>INTERNAL PLASTER</u> | | | |
| | <u>Cement plaster on brickwork or blockwork</u> | | | |
| 4/9/2 | On internal plastered walls(pits) | m2 | 107 | |
| | <u>FLOOR AND WALLS SEALERS</u> | | | |
| | <u>Minimum two coats approved epoxy coat:</u> | | | |
| 4/9/3 | On floors in pits | m2 | 2 | |
| 4/9/4 | On internal plastered walls in pits | m2 | 107 | |
| | Carried Forward to Summary of Section No. 4 | | | R |
| | Section No. 4 | | | |
| | Section 4 - Staff Ablutions Male | | | |
| | Bill No. 9 | | | |
| | Plastering | | | |
| | Re-Solve Consulting | | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION 4</u> | | | |
| | <u>BILL NO. 10</u> | | | |
| | <u>PLUMBING AND DRAINAGE(PROVISIONAL)</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>SANITARY FITTINGS</u> | | | |
| | <u>"Vaal" or similar and approved</u> | | | |
| 4/10/1 | Ceramic wall mounted wash hand basin, complete with all fittings and accesseries including cutting & making good wall & floor wherever required for disable toilets. | No | 1 | |
| | <u>SUPPLY AND INSTALL "ENVIRO-LOO" TOILET SYSTEMS</u> | | | |
| 4/10/2 | Supply and Install "Enviro-Loo" Industrial 1040 Model complete ,installed strictly in accordance with manufacturers instructions, unit comprising of top unit and two x louvred inlets , drying plate , two x air inlets, standard toilet pan, seat and lid, 3500mm long outlet vent pipe, ventilation extraction unit fixed to wall with vent wall bracket, 1 bag mounting screws and organic starter, enzyme and toilet cleaner including all necessary inter connector piping between multiple tanks, emergency outlet piping,etc | No | 8 | |
| 4/10/3 | Supply and Erect disabled "Enviro-loo"Industrial 1040 Model set up and fixed complete as per manufacturers instructions, unit comprising of top unit and two x louvred inlets , drying plate , two x air inlets, paraplegic toilet pan, seat and lid, 3500mm long outlet vent pipe, ventilation extraction unit fixed to wall with vent wall bracket, 1 bag mounting screws and organic starter, enzyme and toilet cleaner including all necessary inter connector piping between multiple tanks, emergency outlet piping,etc | No | 1 | |
| | Carried Forward | | | R |
| | Section No. 4 Section 4 - Staff Ablutions Male Bill No. 10 Plumbing and Drainage (Provisional) Re-Solve Consulting | | | |

Brought Forward

R

| | | | |
|--------|--|----|---|
| 4/10/4 | Supply and Erect "Enviro-loo" Urinal Evaporative Tank system fixed complete as per manufacturers specification unit comprising of urinal evaporative tank , urinal bowls including brackets , 3500mm long outlet vent pipe , ventilation extraction unit fixed to wall with vent wall bracket, 1 bag mounting screws and organic starter, enzyme and toilet cleaner including all necessary piping, traps, etc | No | 9 |
|--------|--|----|---|

PRECAST CONCRETE WASH HAND TROUGH

| | | | |
|--------|---|----|---|
| 4/10/5 | Supply and install pre-cast concrete double wash-trough, complete with all necessary pipework including soakaway size 1000 x 1000 x 1000mm covered with "bidim" | No | 4 |
|--------|---|----|---|

SOIL DRAINAGE

uPVC pipes

| | | | |
|--------|--|---|----|
| 4/10/6 | 110mm Pipes laid in and including trenches not exceeding 1m deep | m | 50 |
|--------|--|---|----|

Extra over uPVC pipes for fittings

| | | | |
|--------|------------|----|----|
| 4/10/7 | 110mm Bend | No | 20 |
|--------|------------|----|----|

| | | | |
|--------|----------------|----|----|
| 4/10/8 | 110mm Junction | No | 20 |
|--------|----------------|----|----|

uPVC gulleys

| | | | |
|--------|---|----|---|
| 4/10/9 | 110mm Gulley not exceeding 750mm deep, including excavations, pre-cast concrete surround etc. | No | 4 |
|--------|---|----|---|

TRAPS ETC

Marley

| | | | |
|---------|--|----|---|
| 4/10/10 | 40 x 300mm Sink combination for double bowl with deepseal "P" trap | No | 5 |
|---------|--|----|---|

TAPS, VALVES, ETC

| | | | |
|---------|---|----|---|
| 4/10/11 | Cobra Watertech 15mm gate valve plugged | No | 4 |
|---------|---|----|---|

Carried Forward

R

Section No. 4
Section 4 - Staff Ablutions Male
Bill No. 10
Plumbing and Drainage (Provisional)
Re-Solve Consulting

| Brought Forward | | | R |
|--|---|----|------|
| 4/10/12 | Cobra Watertech 15mm Elbow action pillar tap | No | 1 |
| <u>SANITARY PLUMBING</u> | | | |
| <u>uPVC pipes</u> | | | |
| 4/10/13 | 50mm Pipes | m | 30 |
| <u>Extra over uPVC pipes for fittings</u> | | | |
| 4/10/14 | 50mm Bend | No | 9 |
| 4/10/15 | 50mm Access bend | No | 9 |
| 4/10/16 | 50mm Junction | No | 9 |
| <u>WATER SUPPLIES</u> | | | |
| <u>Class 0 copper pipes</u> | | | |
| 4/10/17 | 15mm Pipes | m | 30 |
| 4/10/18 | 22mm Pipes | m | 15 |
| <u>Extra over class 0 copper pipes for capillary fittings</u> | | | |
| 4/10/19 | 15mm Fittings | No | 10 |
| 4/10/20 | 22mm Pipes | No | 5 |
| <u>TESTING</u> | | | |
| 4/10/21 | Allow for testing all drains, sanitary plumbing, water supplies and installtion to the satisfaction of the Principle Agent. | | Item |
| Carried Forward to Summary of Section No. 4 | | | R |
| Section No. 4 | | | |
| Section 4 - Staff Ablutions Male | | | |
| Bill No. 10 | | | |
| Plumbing and Drainage (Provisional) | | | |
| Re-Solve Consulting | | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <p><u>SECTION 4</u></p> <p><u>BILL NO. 11</u></p> <p><u>GLAZING</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>GLAZING TO STEEL WITH PUTTY</u></p> <p><u>6.38mm Obscure safety glass</u></p> | | | |
| 4/11/1 | Panes not exceeding 0,1 m2 | m2 | 8 | |
| | Carried Forward to Summary of Section No. 4 | | | R |
| | Section No. 4 Section 4 - Staff Ablutions Male Bill No. 11 Glazing Re-Solve Consulting | | | |

| Item No | Quantity | Rate | Amount |
|--|----------|------|--------|
| <u>SECTION NO.4</u> | | | |
| <u>BILL NO. 12</u> | | | |
| <u>PAINTWORK</u> | | | |
| For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| <u>PAINTWORK ETC TO NEW WORK</u> | | | |
| <u>PREPARATORY WORK TO EXISTING WORK</u> | | | |
| <u>Previously painted plastered surfaces</u> | | | |
| Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and cracks shall be opened, filled with a suitable filler and finished smooth | | | |
| Previously painted metal surfaces | | | |
| Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal | | | |
| Previously painted wood surfaces | | | |
| Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth | | | |
| <u>ON FIBRE-CEMENT</u> | | | |
| Carried Forward | | | R |
| Section No. 4 Section 4 - Staff Ablutions Male Bill No. 12 Paintwork Re-Solve Consulting | | | |

Brought Forward

R

Prepare and brush to remove all loose contaminations, apply one coat primer and two coats PVA emulsion paint

4/12/1 On fascias and barge boards m2 7

ON METAL

Prime and paint undercoat and 2 finishing coats in gloss enamel, colour TBC.

4/12/2 On door frames m2 32

Spot prining defects in pre-prime surface with zinc chromate primer and apply one universal undercoat and two coats EPWP. golden brown gloss enamel paint on steel

4/12/3 On windows with burglar bars m2 8

ON WOOD

Under coat and minimum 2 coats gloss enamel, colour TBC

4/12/4 On doors (External) m2 4

4/12/5 On doors (Internal) m2 12

Carried Forward to Summary of Section No. 4

R

Section No. 4
Section 4 - Staff Ablutions Male
Bill No. 12
Paintwork
Re-Solve Consulting

Section No. 4

Section 4 - Staff Ablutions Male

SECTION SUMMARY - Section 4 - Staff Ablutions Male

| Bill No | | Page No | Amount |
|---------|--------------------------------------|---------|--------|
| 4/1 | Earthworks (Provisional) | 57 | |
| 4/2 | Concrete, Formwork and Reinforcement | 59 | |
| 4/3 | Masonry | 62 | |
| 4/4 | Waterproofing | 63 | |
| 4/5 | Roof Coverings | 64 | |
| 4/6 | Carpentry and Joinery | 66 | |
| 4/7 | Ironmongery | 68 | |
| 4/8 | Metalwork | 70 | |
| 4/9 | Plastering | 71 | |
| 4/10 | Plumbing and Drainage (Provisional) | 74 | |
| 4/11 | Glazing | 75 | |
| 4/12 | Paintwork | 77 | |
| | Carried to Final Summary | | R |
| | Section No. 4 | | |
| | Section 4 - Staff Ablutions Male | | |
| | Re-Solve Consulting | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <p><u>SECTION 5</u></p> <p><u>BILL NO. 1</u></p> <p><u>EARTHWORKS (PROVISIONAL)</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p>Nature of ground</p> <p>Use "assumed to be" if no trial holes, soils investigations, etc have been carried out - discuss with engineer. Use "Trial holes indicate that" where the ground has been investigated by means of trial holes</p> <p>Nature of ground</p> <p>A soils investigation has been carried out on site by the engineer and the report is annexed to these bills of quantities. Descriptions of excavations shall be deemed to include all ground conditions classifiable as "earth" described in the above report and where conditions of a more difficult character are indicated these are separately measured</p> <p>Carting away of excavated material</p> <p>Descriptions of carting away of excavated material shall be deemed to include loading excavated material onto trucks directly from the excavations or, alternatively, from stock piles situated on the building site</p> <p>Filling</p> <p>Notwithstanding the reference to prescribed multiple handling in clause 1 page 6 of the Standard System of Measuring Building Work, prices for filling and backfilling shall include for all selection and any multiple handling of material</p> | | | |
| | Carried Forward | | R | |
| | <p>Section No. 5 Section 5 - Girl Block of 9 Bill No. 1 Earthworks (Provisional) Re-Solve Consulting</p> | | | |

| Brought Forward | | | | | | | |
|-----------------|--|----|----|--|--|--|---|
| | Soil poisoning | | | | | | R |
| | <u>Ant and weed poisoning will be applied in accordance to SABS specifications by Registered and Approved Specialists who will issue a five (5) year guarantee. The contractor will only be paid for this items once they have produced the said certificate to the Principal Agent</u> | | | | | | |
| | <u>SITE CLEARANCE ETC</u> | | | | | | |
| | <u>Site clearance</u> | | | | | | |
| 5/1/1 | Digging up and removing rubbish, debris, vegetation, hedges, shrubs and trees not exceeding 200mm girth, bush, etc | m2 | 93 | | | | |
| 5/1/2 | Stripping average 100mm thick layer of top soil and stockpiling on site | m2 | 93 | | | | |
| | <u>EXCAVATION, FILLING, ETC</u> | | | | | | |
| | <u>Excavation in earth not exceeding 2m deep</u> | | | | | | |
| 5/1/3 | Trenches | m3 | 55 | | | | |
| 5/1/4 | Pits | m3 | 63 | | | | |
| 5/1/5 | Thickening under aprons | m3 | 1 | | | | |
| | <u>Extra over trench and hole excavations in earth for excavation in</u> | | | | | | |
| 5/1/6 | Soft rock | m3 | 8 | | | | |
| 5/1/7 | Hard rock | m3 | 4 | | | | |
| | <u>Extra over all excavations for carting away</u> | | | | | | |
| 5/1/8 | Surplus material from excavations on site to a dumping site to be located by the contractor | m3 | 94 | | | | |
| | Carried Forward | | | | | | R |
| | Section No. 5 Section 5 - Girl Block of 9 Bill No. 1 Earthworks (Provisional) Re-Solve Consulting | | | | | | |

| Brought Forward | | | R |
|--|--|----|------|
| <u>Risk of collapse of excavations</u> | | | |
| 5/1/9 | Sides of trench and hole excavations not exceeding 1,5m deep | m2 | 361 |
| <u>Keeping excavations free of water</u> | | | |
| 5/1/10 | Keeping excavations free of all water other than subterranean water | | Item |
| <u>Earth filling obtained from the excavations and /or prescribed stock piles on site including compacted to 93% Mod AASHTO density</u> | | | |
| 5/1/11 | Under floors, steps, paving, etc | m3 | 13 |
| 5/1/12 | Backfilling to trenches, holes, etc | m3 | 24 |
| <u>Compaction of surfaces</u> | | | |
| 5/1/13 | Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density | m2 | 75 |
| 5/1/14 | Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density (Enviro Loo Tanks Pit) | m2 | 42 |
| 5/1/15 | Ditto but to bottom of trenches and bases | m2 | 52 |
| <u>Prescribed density tests on filling</u> | | | |
| 5/1/16 | Modified AASHTO Density | No | 3 |
| <u>SOIL POISONING</u> | | | |
| <u>Weedkiller mixed in accordance to supplier's specifications</u> | | | |
| 5/1/17 | To bottoms and sides of trenches, etc. | m2 | 278 |
| Carried Forward | | | R |
| Section No. 5 Section 5 - Girl Block of 9 Bill No. 1 Earthworks (Provisional) Re-Solve Consulting | | | |

Brought Forward

R

| | | | | |
|--------|---|----|-----|--|
| 5/1/18 | Under floors etc including forming and poisoning shallow furrows against foundation walls etc, filling in furrows and ramming(pits) | m2 | 129 | |
|--------|---|----|-----|--|

Soil insecticide

| | | | | |
|--------|--------------------------------------|----|-----|--|
| 5/1/19 | To bottoms and sides of trenches etc | m2 | 278 | |
|--------|--------------------------------------|----|-----|--|

| | | | | |
|--------|---|----|-----|--|
| 5/1/20 | Under floors etc including forming and poisoning shallow furrows against foundation walls etc, filling in furrows and ramming(pits) | m2 | 129 | |
|--------|---|----|-----|--|

Carried Forward to Summary of Section No. 5

R

Section No. 5
 Section 5 - Girl Block of 9
 Bill No. 1
 Earthworks (Provisional)
Re-Solve Consulting

| Item No | | Quantity | Rate | Amount |
|---------|---|----------|------|--------|
| | <u>SECTION 5</u> | | | |
| | <u>BILL NO. 2</u> | | | |
| | <u>CONCRETE, FORMWORK AND REINFORCEMENT</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>UNREINFORCED CONCRETE, ETC.</u> | | | |
| | <u>15MPa/19mm concrete</u> | | | |
| 5/2/1 | Surface blinding under footings and bases | m3 | 5 | |
| 5/2/2 | Aprons cast in panels to falls | m3 | 3 | |
| 5/2/3 | Extra over concrete in surface beds for thickening 85mm deep the bottom including all excavation, backfilling etc | m | 32 | |
| 5/2/4 | Extra over for concrete thickening in aprons size approximately 100mm deep, 400mm at top and tapering one side to 200mm at bottom, including all excavations, cart away, etc. | m | 30 | |
| | <u>REINFORCED CONCRETE</u> | | | |
| | <u>25MPa/19mm concrete</u> | | | |
| 5/2/5 | Strip footings | m3 | 11 | |
| 5/2/6 | Ramps | m3 | 2 | |
| 5/2/7 | Surface beds cast in panels on waterproofing. | m3 | 5 | |
| 5/2/8 | Slabs (pits) | m3 | 6 | |
| | Carried Forward | | | R |
| | Section No. 5 Section 5 - Girl Block of 9 Bill No. 2 Concrete, Formwork and Reinforcement Re-Solve Consulting | | | |

Brought Forward

R

TEST CUBES

| | | | |
|-------|---|------|-----|
| 5/2/9 | Allow for preparing a set of three concrete strength test cubes, each size 150 x 150 x 150mm, sending them to an approved Testing Laboratory for testing and paying all charges in connection therewith | Sets | 4.0 |
|-------|---|------|-----|

CONCRETE SUNDRIES

Finishing top surfaces of concrete smooth with a wood float/steel trowel

| | | | |
|--------|---------------------------------|----|----|
| 5/2/10 | Surface beds, slabs, etc | m2 | 89 |
| 5/2/11 | Surface beds, slabs, etc (pits) | m2 | 40 |
| 5/2/12 | Aprons to falls | m2 | 25 |

SMOOTH FORMWORK (DEGREE OF ACCURACY I)

Rough formwork to sides

| | | | |
|--------|--|---|----|
| 5/2/13 | Edges, risers, ends and reveals not exceeding 300mm high or wide | m | 32 |
|--------|--|---|----|

REINFORCEMENT (PROVISIONAL)

Fabric Reinforcement

| | | | |
|--------|---|----|----|
| 5/2/14 | Mesh ref. No. 395 fabric reinforcement fixed horizontalt in surface beds etc. | m2 | 90 |
|--------|---|----|----|

Carried Forward to Summary of Section No. 5

R

Section No. 5
 Section 5 - Girl Block of 9
 Bill No. 2
 Concrete, Formwork and Reinforcement
Re-Solve Consulting

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <p><u>SECTION 5</u></p> <p><u>BILL NO.3</u></p> <p><u>MASONRY</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>BRICKWORK</u></p> <p><u>Sizes in descriptions</u></p> <p>Where sizes in descriptions are given in brick units, "one brick" shall represent the length and "half brick" the width of a brick</p> <p>Face bricks</p> <p>Bricks shall be ordered timeously to obtain uniformity in size and colour</p> <p>Pointing</p> <p>Descriptions of recessed pointing to fair face brickwork and face brickwork shall be deemed to include square recessed, hollow recessed, weathered pointing, etc</p> <p><u>FOUNDATIONS (PROVISIONAL)</u></p> <p><u>Brickwork of NFP bricks in class II mortar</u></p> | | | |
| 5/3/1 | One brick walls | m2 | 91 | |
| | <p><u>FACE BRICKWORK</u></p> | | | |
| | Carried Forward | | | R |
| | <p>Section No. 5 Section 5 - Girl Block of 9 Bill No. 3 Masonry Re-Solve Consulting</p> | | | |

| Brought Forward | | | R |
|--|---|----|-----|
| <u>Face bricks (purchase price of R5 000.00/1000 delivered to site excluding VAT) pointed with flush horizontal and vertical joints</u> | | | |
| 5/3/2 | Extra over brickwork for face brickwork in foundations | m2 | 6 |
| <u>SUPERSTRUCTURE</u> | | | |
| <u>Brickwork of NFP bricks in class II mortar</u> | | | |
| 5/3/3 | Half brick walls | m2 | 25 |
| 5/3/4 | Half brick walls in beamfilling | m2 | 7 |
| 5/3/5 | One brick walls | m2 | 85 |
| <u>FACE BRICKWORK</u> | | | |
| 5/3/6 | Extra over brickwork for face brickwork | m2 | 81 |
| 5/3/7 | Extra over brickwork for brick-on-edge header course lintel | m | 14 |
| 5/3/8 | 220mm Wide sill set sloping and slightly protecting outside | m | 14 |
| 5/3/9 | Fair cutting fitting around pipe exceeding 100mm and not exceeding 200mm diameter | No | 10 |
| <u>BRICKWORK SUNDRIES</u> | | | |
| <u>Brickwork reinforcement</u> | | | |
| 5/3/10 | 75mm Wide reinforcement built in horizontally | m | 25 |
| 5/3/11 | 150mm Wide reinforcement built in horizontally | m | 177 |
| <u>Galvanised wire ties etc</u> | | | |
| 5/3/12 | 6mm Diameter roof tie 2m long with one end fixed to timber and other end built into brickwork | No | 33 |
| Carried Forward | | | R |
| Section No. 5 Section 5 - Girl Block of 9 Bill No. 3 Masonry Re-Solve Consulting | | | |

| Brought Forward | | | R |
|--|---|----|----|
| <u>Turning pieces to lintels etc.</u> | | | |
| 5/3/13 | 115mm Wide turning pieces | m | 15 |
| 5/3/14 | 230mm Wide turning pieces | m | 9 |
| <u>Prestressed fabricated lintels</u> | | | |
| 5/3/15 | 110 x 75mm Lintels in lengths exceeding 3m and not exceeding 6m | m | 38 |
| <u>Air bricks etc.</u> | | | |
| 5/3/16 | 230 x 152mm terra-cotta vermin proofed louvered air brick | No | 4 |
| Carried Forward to Summary of Section No. 5 | | | R |
| Section No. 5 | | | |
| Section 5 - Girl Block of 9 | | | |
| Bill No. 3 | | | |
| Masonry | | | |
| Re-Solve Consulting | | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION 5</u> | | | |
| | <u>BILL NO.4</u> | | | |
| | <u>WATERPROOFING</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>DAMP-PROOFING OF WALLS AND FLOORS</u> | | | |
| | <u>One layer of 375 micron Consol Plastic Brikgrip DPC" embossed damp proof course</u> | | | |
| 5/4/1 | In walls | m2 | 106 | |
| | <u>One layer of 250 micron "Consol Plastic USB Green" waterproof sheeting sealed at laps with "Gunplas Pressure Sensitive Tape"</u> | | | |
| 5/4/2 | Under surface beds | m2 | 127 | |
| 5/4/3 | Under aprons and ramps | m2 | 2 | |
| | <u>FLOOR AND WALL SEALERS</u> | | | |
| | <u>Secomastic non setting mastic sealant applied cold with a hand pressure caulking gun and leave perfectly watertight</u> | | | |
| 5/4/4 | Around steel windows and door frames | m | 25 | |
| | Carried Forward to Summary of Section No. 5 | | | R |
| | Section No. 5 | | | |
| | Section 5 - Girl Block of 9 | | | |
| | Bill No. 4 | | | |
| | Waterproofing | | | |
| | Re-Solve Consulting | | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION 5</u> | | | |
| | <u>BILL NO.5</u> | | | |
| | <u>ROOF COVERINGS ETC</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>PROFILED METAL SHEETING AND ACCESSORIES</u> | | | |
| | <u>0,6mm "Kliplok" roof sheeting in chromadek finish fixed to timber purlins (elsewhere)</u> | | | |
| 5/5/1 | Roof covering with pitch not exceeding 25 degrees | m2 | 52 | |
| | <u>ROOF AND WALL INSULATION</u> | | | |
| 5/5/2 | 12" Thermal resistance sisalition laid on purlins | m2 | 52 | |
| | <u>RAINWATER DISPOSAL</u> | | | |
| | For preambles see "Model Preambles for Trades (2008 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>Aluminium Zinc Seamless Gutters</u> | | | |
| 5/5/3 | 100 x 100mm sandard rainwater gutters fixed with gutter brackets | m | 12 | |
| 5/5/4 | Extra over eaves gutter for stopped end | No | 2 | |
| 5/5/5 | 75 x 100mm Diameter rainwater down pipes fixed to wall | m | 6 | |
| 5/5/6 | Extra over eaves gutter for outlet for 75 x 100mm down pipe | No | 2 | |
| 5/5/7 | Ditto .for shoe | No | 2 | |
| | Carried Forward to Summary of Section No. 5 | | | R |
| | Section No. 5 | | | |
| | Section 5 - Girl Block of 9 | | | |
| | Bill No. 5 | | | |
| | Roof Coverings | | | |
| | Re-Solve Consulting | | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <p><u>SECTION 5</u></p> <p><u>BILL NO. 6</u></p> <p><u>CARPENTRY AND JOINERY</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>ROOFS, ETC.</u></p> <p><u>Plate nailed timber roof truss construction</u></p> | | | |
| 5/6/1 | <p>Design, manufacture and deliver on site, plate nailed roof truss construction to Girls Ablution Block of 9, size 11 965 x 3 964 mm overall on plan consisting of mono pitched trusses to suit, with 350mm eaves overhang projecting , including all necessary purlins, runners, bracing and cross bracing (wall plates elsewhere) all in accordance with suppliers and manufacturer's recommendations:</p> <p>Trusses are at maximum 1,10m centres. Roof covering is galvanised "IBR" roof sheeting (measured elsewhere) on 50 x 75mm purlins at 1,1m maximum centres. All timber to be sawn softwood in accordance with V4 or M4 as defined in SABS 563 or SABS 1245. Metal connector plates shall have a minimum yield strength of 228 MPa and a minimum ultimate tensile strength of 330 Mpa with hot-dip galvanised finish. All joints to be close fitted butt joints. Trusses shall be designed by a registered supplier of prefabricated trusses who shall issue an Engineers Certificate upon completion of the installation. The dimensions in the descriptions of the trusses are nominal and actual measurements are to be obtained on site before design or fabricaton commences. Tenderers must study the roof plan and sections as attached to the back of these bills of quantities and must obtain prices from a qualified and registered roof truss supplier as no claims in this regard will be entertained.</p> | No | 1 | |
| | Carried Forward | | R | |
| | <p>Section No. 5 Section 5 - Girl Block of 9 Bill No. 6 Carpentry and Joinery Re-Solve Consulting</p> | | | |

| Brought Forward | | R |
|--|---|-------|
| 5/6/2 | Profit on the above | Item |
| 5/6/3 | Take delivery, temporary store, hoist in position and erect plate nailed timber roof trusses, purlins, gangboarding, temporary and permanent bracing, etc (measured on slope of roof) | Item |
| <u>Sawn softwood</u> | | |
| 5/6/4 | 38 x 114mm Wall plates | m 33 |
| <u>Sundries</u> | | |
| 5/6/5 | Two coats creosote on sawn timbers | m2 47 |
| 5/6/6 | 6mm Diameter galvanised wire tie 3000mm girth wrapped around rafter and purlin with ends tied together | No 33 |
| 5/6/7 | Hurricane clips | No 33 |
| <u>EAVES, VERGES, ETC</u> | | |
| <u>Pressed fibre-cement:</u> | | |
| 5/6/8 | 15 x 230mm Nutec Fascias and barge boards including galvanised steel H-profile jointing strips | m 12 |
| <u>DOORS, ETC</u> | | |
| <u>Wrought meranti doors hung to steel frames</u> | | |
| 5/6/9 | 44mm framed, ledged and braced door 877 x 2064mm high including external weather bar (D1) | No 2 |
| 5/6/10 | 44mm framed, ledged and braced door 813 x 1914mm high (door raised by 150mm from bottom) (D2) | No 9 |
| 5/6/11 | 44mm framed, ledged and braced door 915 x 2032mm high including external weather bar (disabled) | No 1 |
| Carried Forward to Summary of Section No. 5 | | R |
| Section No. 5 | | |
| Section 5 - Girl Block of 9 | | |
| Bill No. 6 | | |
| Carpentry and Joinery | | |
| Re-Solve Consulting | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION 5</u> | | | |
| | <u>BILL NO. 7</u> | | | |
| | <u>IRONMONGERY</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>HINGES, BOLTS, ETC</u> | | | |
| | <u>100mm Chrome plated "D" type handle 3 by solid brace hinges</u> | | | |
| | <u>CATCHES,CABIN HOOKS, ETC</u> | | | |
| 5/7/1 | 100mm brace Cabin hook and eye including 70 x 70 x 20mm chamfered hardwood block twice oiled and plugged | No | 2 | |
| | <u>LOCKS</u> | | | |
| | <u>Approved</u> | | | |
| 5/7/2 | Three lever mortice lock set | No | 3 | |
| 5/7/3 | Indicator lock set | No | 9 | |
| 5/7/4 | Security double throw dead lock (no latch) | No | 3 | |
| | <u>HANDLES, ETC.</u> | | | |
| | <u>Aluminium Pull Handle</u> | | | |
| 5/7/5 | ASSA ABLOY Anodised Silver straight pull handle (Code: AL5515-300BBAS) with 300mm fixing centres. | No | 11 | |
| | <u>SUNDRIES</u> | | | |
| | Carried Forward | | | R |
| | Section No. 5 Section 5 - Girl Block of 9 Bill No. 7 Ironmongery Re-Solve Consulting | | | |

| Brought Forward | | | R |
|--|--|----|----|
| <u>ASSA ABLOY</u> | | | |
| 5/7/6 | 38mm Diameter rubber door stop plugged | No | 11 |
| <u>Vaal Paragon</u> | | | |
| 5/7/7 | 32mm Type 9 back grab rail 800mm long plugged | No | 1 |
| 5/7/8 | 32mm Type 8 side grab rail 900mm girth plugged | No | 1 |
| <u>LETTERS, NAMEPLATES, ETC</u> | | | |
| <u>Dorma:</u> | | | |
| 5/7/9 | DSS-130 Engraved "Female" information sign, plugged | No | 2 |
| 5/7/10 | DSS-133 Engraved "Disabled" information sign, plugged | No | 1 |
| <u>BATHROOM FITTINGS</u> | | | |
| <u>Sundries</u> | | | |
| <u>Kimberley-Clark or Similar</u> | | | |
| 5/7/11 | SQ2 code 405607B white none lockable toilet roll holder | No | 10 |
| <u>stainless Steel</u> | | | |
| 5/7/12 | Stainless steel mirror size: 350 x 400mm plugged to wall with chrome plated screws. | No | 1 |
| 5/7/13 | Brushed stainless steel body, rust resistant, she bin, approximately 330 x 280 x 180mm etc | No | 10 |
| Carried Forward to Summary of Section No. 5 | | | R |
| Section No. 5 | | | |
| Section 5 - Girl Block of 9 | | | |
| Bill No. 7 | | | |
| Ironmongery | | | |
| Re-Solve Consulting | | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION 5</u> | | | |
| | <u>BILL NO. 8</u> | | | |
| | <u>METALWORK</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>WELDED SCREENS, GATES, ETC</u> | | | |
| | <u>Gates to external doors</u> | | | |
| 5/8/1 | Purpose made square hollow section mild steel single security gate and frame size to fit standard door, size 813 x 2032mm high | No | 2 | |
| 5/8/2 | Single gate and frame size to fit none standard door, size approximately 915 x 2032mm high (disable) | No | 1 | |
| | <u>PRESSED STEEL DOOR FRAMES</u> | | | |
| | <u>1,2mm Double rebated frames suitable for half brick walls</u> | | | |
| 5/8/3 | Frame for door size 813 x 1914mm high | No | 9 | |
| | <u>1,2mm Double rebated frames suitable for one brick walls</u> | | | |
| 5/8/4 | Frame for door size 914 x 2032mm high | No | 1 | |
| | <u>1,2mm Single rebate steel frame suitable for one brick wall</u> | | | |
| 5/8/5 | Frame for door size 813 x 2032mm high | No | 2 | |
| | <u>STEEL WINDOWS, DOORS, ETC</u> | | | |
| | Carried Forward | | | R |
| | Section No. 5 Section 5 - Girl Block of 9 Bill No. 8 Metalwork Re-Solve Consulting | | | |

| | Brought Forward | | | R |
|--|--|----|----|---|
| | <u>Nty steel or similar approved school windows with standard burglar bars formed of 20 x 5mm thick flat bars to all sashes</u> | | | |
| 5/8/6 | Window type NE1, size 533 x 654mm high | No | 10 | |
| 5/8/7 | Window type NE7, size 1022 x 654mm high | No | 4 | |
| | <u>Sundries</u> | | | |
| | <u>Cage, etc</u> | | | |
| 5/8/8 | She bin cages, to fit 330 x 280 x 180mm width, she bin to be able to open, including pad lock and locking mechanism, complete, etc | No | 10 | |
| Carried Forward to Summary of Section No. 5 | | | | |
| Section No. 5 | | | | |
| Section 5 - Girl Block of 9 | | | | |
| Bill No. 8 | | | | |
| Metalwork | | | | |
| Re-Solve Consulting | | | | |
| | | | | R |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION 5</u> | | | |
| | <u>BILL NO.9</u> | | | |
| | <u>PLASTERING</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>GRANOLITHIC</u> | | | |
| | <u>Untinted granolithic on concrete</u> | | | |
| 5/9/1 | 20mm Thick on floors | m2 | 47 | |
| | <u>INTERNAL PLASTER</u> | | | |
| | <u>Cement plaster on brickwork or blockwork</u> | | | |
| 5/9/2 | On internal plastered walls(pits) | m2 | 118 | |
| | <u>FLOOR AND WALLS SEALERS</u> | | | |
| | <u>Minimum two coats approved epoxy coat:</u> | | | |
| 5/9/3 | On floors in pits | m2 | 2 | |
| 5/9/4 | On internal plastered walls in pits | m2 | 118 | |
| | Carried Forward to Summary of Section No. 5 | | | R |
| | Section No. 5 | | | |
| | Section 5 - Girl Block of 9 | | | |
| | Bill No. 9 | | | |
| | Plastering | | | |
| | Re-Solve Consulting | | | |

| Item No | | Quantity | Rate | Amount |
|---------|---|----------|------|--------|
| | <u>SECTION 5</u> | | | |
| | <u>BILL NO. 10</u> | | | |
| | <u>PLUMBING AND DRAINAGE (PROVISIONAL)</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>SANITARY FITTINGS</u> | | | |
| | <u>"Vaal" or similar and approved</u> | | | |
| 5/10/1 | Ceramic wall mounted wash hand basin, complete with all fittings and accessories including cutting & making good wall & floor wherever required for disable toilets. | No | 1 | |
| | <u>SUPPLY AND INSTALL "ENVIRO-LOO" TOILET SYSTEMS</u> | | | |
| 5/10/2 | Supply and Install "Enviro-Loo" Industrial 1040 Model complete, installed strictly in accordance with manufacturers instructions, unit comprising of top unit and two x louvred inlets, drying plate, two x air inlets, standard toilet pan, seat and lid, 3500mm long outlet vent pipe, ventilation extraction unit fixed to wall with vent wall bracket, 1 bag mounting screws and organic starter, enzyme and toilet cleaner including all necessary inter connector piping between multiple tanks, emergency outlet piping, etc | No | 9 | |
| | Carried Forward | | | R |
| | Section No. 5 Section 5 - Girl Block of 9 Bill No. 10 Plumbing and Drainage (Provisional) Re-Solve Consulting | | | |

| Brought Forward | | | R |
|--|---|----|----|
| 5/10/3 | Supply and Erect disabled "Enviro-loo"Industrial 1040 Model set up and fixed complete as per manufacturers instructions, unit comprising of top unit and two x louvred inlets , drying plate , two x air inlets, paraplegic toilet pan, seat and lid, 3500mm long outlet vent pipe, ventilation extraction unit fixed to wall with vent wall bracket, 1 bag mounting screws and organic starter, enzyme and toilet cleaner including all necessary inter connector piping between multiple tanks, emergency outlet piping,etc | No | 1 |
| <u>PRECAST CONCRETE WASH HAND TROUGH</u> | | | |
| 5/10/4 | Supply and install pre-cast concrete double wash-trough, complete with all necessary pipework including soakaway size 1000 x 1000 x 1000mm covered with "bidim" | No | 3 |
| <u>SOIL DRAINAGE</u> | | | |
| <u>uPVC pipes</u> | | | |
| 5/10/5 | 110mm Pipes laid in and including trenches not exceeding 1m deep | m | 45 |
| <u>Extra over uPVC pipes for fittings</u> | | | |
| 5/10/6 | 110mm Bend | No | 6 |
| 5/10/7 | 110mm Junction | No | 6 |
| <u>uPVC gulleys</u> | | | |
| 5/10/8 | 110mm Gully not exceeding 750mm deep, including excavations, pre-cast concrete surround etc. | No | 4 |
| <u>TRAPS ETC</u> | | | |
| <u>Marley</u> | | | |
| 5/10/9 | 40 x 300mm Sink combination for double bowl with deepseal "P" trap | No | 4 |
| Carried Forward | | | R |
| Section No. 5 Section 5 - Girl Block of 9 Bill No. 10 Plumbing and Drainage (Provisional) Re-Solve Consulting | | | |

Brought Forward

R

TAPS, VALVES, ETC

| | | | |
|---------|--|----|---|
| 5/10/10 | Cobra Watertech 15mm gate valve plugged | No | 3 |
| 5/10/11 | Cobra Watertech 15mm Elbow action pillar tap | No | 1 |

SANITARY PLUMBING

uPVC pipes

| | | | |
|---------|------------|---|----|
| 5/10/12 | 50mm Pipes | m | 20 |
|---------|------------|---|----|

Extra over uPVC pipes for fittings

| | | | |
|---------|------------------|----|---|
| 5/10/13 | 50mm Bend | No | 4 |
| 5/10/14 | 50mm Access bend | No | 4 |
| 5/10/15 | 50mm Junction | No | 4 |

WATER SUPPLIES

Class 0 copper pipes

| | | | |
|---------|------------|---|----|
| 5/10/16 | 15mm Pipes | m | 25 |
| 5/10/17 | 22mm Pipes | m | 30 |

Extra over class 0 copper pipes for capillary fittings

| | | | |
|---------|---------------|----|---|
| 5/10/18 | 15mm Fittings | No | 3 |
| 5/10/19 | 22mm Pipes | No | 3 |

TESTING

| | | | |
|---------|---|--|------|
| 5/10/20 | Allow for testing all drains, sanitary plumbing, water supplies and installtion to the satisfaction of the Principle Agent. | | Item |
|---------|---|--|------|

Carried Forward to Summary of Section No. 5

R

Section No. 5
 Section 5 - Girl Block of 9
 Bill No. 10
 Plumbing and Drainage (Provisional)
Re-Solve Consulting

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <p><u>SECTION NO. 5</u></p> <p><u>BILL NO. 11</u></p> <p><u>GLAZING</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>GLAZING TO STEEL WITH PUTTY</u></p> <p><u>6.38mm Obscure safety glass</u></p> | | | |
| 5/11/1 | Panes not exceeding 0,1 m2 | m2 | 6 | |
| | Carried Forward to Summary of Section No. 5 | | | R |
| | Section No. 5 Section 5 - Girl Block of 9 Bill No. 11 Glazing Re-Solve Consulting | | | |

| Item No | | Quantity | Rate | Amount |
|---------|---|----------|------|--------|
| | <p><u>SECTION NO.5</u></p> <p><u>BILL NO. 12</u></p> <p><u>PAINTWORK</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>PAINTWORK ETC TO NEW WORK</u></p> <p><u>PREPARATORY WORK TO EXISTING WORK</u></p> <p><u>Previously painted plastered surfaces</u></p> <p>Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and cracks shall be opened, filled with a suitable filler and finished smooth</p> <p>Previously painted metal surfaces</p> <p>Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal</p> <p>Previously painted wood surfaces</p> <p>Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth</p> <p><u>ON FIBRE-CEMENT</u></p> <p><u>Prepare and brush to remove all loose contaminations, apply one coat primer and two coats PVA emulsion paint</u></p> | | | |
| 5/12/1 | On fascias and barge boards | m2 | 6 | |
| | Carried Forward | | | R |
| | <p>Section No. 5 Section 5 - Girl Block of 9 Bill No. 12 Paintwork Re-Solve Consulting</p> | | | |

Brought Forward

R

ON METAL

Prime and paint undercoat and 2 finishing coats in gloss enamel, colour TBC.

5/12/2 On door frames m2 35

Spot prining defects in pre-prime surface with zinc chromate primer and apply one universal undercoat and two coats EPWP. golden brown gloss enamel paint on steel

5/12/3 On windows with burglar bars m2 6

ON WOOD

Under coat and minimum 2 coats gloss enamel, colour TBC

5/12/4 On doors (External) m2 4

5/12/5 On doors (Internal) m2 14

Carried Forward to Summary of Section No. 5

R

Section No. 5
Section 5 - Girl Block of 9
Bill No. 12
Paintwork
Re-Solve Consulting

Section No. 5
 Section 5 - Girl Block of 9

SECTION SUMMARY - Section 5 - Girl Block of 9

| Bill No | | Page No | Amount |
|---------|--|---------|--------|
| 5/1 | Earthworks (Provisional) | 82 | |
| 5/2 | Concrete, Formwork and Reinforcement | 84 | |
| 5/3 | Masonry | 87 | |
| 5/4 | Waterproofing | 88 | |
| 5/5 | Roof Coverings | 89 | |
| 5/6 | Carpentry and Joinery | 91 | |
| 5/7 | Ironmongery | 93 | |
| 5/8 | Metalwork | 95 | |
| 5/9 | Plastering | 96 | |
| 5/10 | Plumbing and Drainage (Provisional) | 99 | |
| 5/11 | Glazing | 100 | |
| 5/12 | Paintwork | 102 | |
| | Carried to Final Summary | | R |
| | Section No. 5 Section 5 - Girl Block of 9 Re-Solve Consulting | | |

| Item No | | Quantity | Rate | | Amount |
|---------|--|----------|------|---|--------|
| | <p><u>SECTION 6</u></p> <p><u>BILL NO. 1</u></p> <p><u>EARTHWORKS (PROVISIONAL)</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p>Nature of ground</p> <p>Use "assumed to be" if no trial holes, soils investigations, etc have been carried out - discuss with engineer. Use "Trial holes indicate that" where the ground has been investigated by means of trial holes</p> <p>Nature of ground</p> <p>A soils investigation has been carried out on site by the engineer and the report is annexed to these bills of quantities. Descriptions of excavations shall be deemed to include all ground conditions classifiable as "earth" described in the above report and where conditions of a more difficult character are indicated these are separately measured</p> <p>Carting away of excavated material</p> <p>Descriptions of carting away of excavated material shall be deemed to include loading excavated material onto trucks directly from the excavations or, alternatively, from stock piles situated on the building site</p> <p>Filling</p> <p>Notwithstanding the reference to prescribed multiple handling in clause 1 page 6 of the Standard System of Measuring Building Work, prices for filling and backfilling shall include for all selection and any multiple handling of material</p> | | | | |
| | Carried Forward | | | | |
| | <p>Section No. 6 Section 6 - Girl Block of 7 Bill No. 1 Earthworks (Provisional) Re-Solve Consulting</p> | | | R | |

| Brought Forward | | | | R |
|--|--|----|----|---|
| Soil poisoning | | | | |
| <u>Ant and weed poisoning will be applied in accordance to SABS specifications by Registered and Approved Specialists who will issue a five (5) year guarantee. The contractor will only be paid for this items once they have produced the said certificate to the Principal Agent</u> | | | | |
| <u>SITE CLEARANCE ETC</u> | | | | |
| <u>Site clearance</u> | | | | |
| 6/1/1 | Digging up and removing rubbish, debris, vegetation, hedges, shrubs and trees not exceeding 200mm girth, bush, etc | m2 | 99 | |
| 6/1/2 | Stripping average 100mm thick layer of top soil and stockpiling on site | m2 | 99 | |
| <u>EXCAVATION, FILLING, ETC</u> | | | | |
| <u>Excavation in earth not exceeding 2m deep</u> | | | | |
| 6/1/3 | Trenches | m3 | 47 | |
| 6/1/4 | Pits | m3 | 52 | |
| 6/1/5 | Thickening under aprons | m3 | 1 | |
| <u>Extra over trench and hole excavations in earth for excavation in</u> | | | | |
| 6/1/6 | Soft rock | m3 | 7 | |
| 6/1/7 | Hard rock | m3 | 3 | |
| <u>Extra over all excavations for carting away</u> | | | | |
| 6/1/8 | Surplus material from excavations on site to a dumping site to be located by the contractor | m3 | 78 | |
| Carried Forward | | | | R |
| Section No. 6 Section 6 - Girl Block of 7 Bill No. 1 Earthworks (Provisional) Re-Solve Consulting | | | | |

| Brought Forward | | | R |
|--|--|----|------|
| <u>Risk of collapse of excavations</u> | | | |
| 6/1/9 | Sides of trench and hole excavations not exceeding 1,5m deep | m2 | 302 |
| <u>Keeping excavations free of water</u> | | | |
| 6/1/10 | Keeping excavations free of all water other than subterranean water | | Item |
| <u>Earth filling obtained from the excavations and /or prescribed stock piles on site including compacted to 93% Mod AASHTO density</u> | | | |
| 6/1/11 | Under floors, steps, paving, etc | m3 | 14 |
| 6/1/12 | Backfilling to trenches, holes, etc | m3 | 20 |
| <u>Compaction of surfaces</u> | | | |
| 6/1/13 | Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density | m2 | 64 |
| 6/1/14 | Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density (Enviro Loo Tanks Pit) | m2 | 32 |
| 6/1/15 | Ditto but to bottom of trenches and bases | m2 | 45 |
| <u>Prescribed density tests on filling</u> | | | |
| 6/1/16 | Modified AASHTO Density | No | 3 |
| <u>SOIL POISONING</u> | | | |
| <u>Weedkiller mixed in accordance to supplier's specifications</u> | | | |
| 6/1/17 | To bottoms and sides of trenches, etc. | m2 | 236 |
| Carried Forward | | | R |
| Section No. 6 Section 6 - Girl Block of 7 Bill No. 1 Earthworks (Provisional) Re-Solve Consulting | | | |

Brought Forward

R

| | | | |
|--------|---|----|-----|
| 6/1/18 | Under floors etc including forming and poisoning shallow furrows against foundation walls etc, filling in furrows and ramming(pits) | m2 | 129 |
| | <u>Soil insecticide</u> | | |
| 6/1/19 | To bottoms and sides of trenches etc | m2 | 236 |
| 6/1/20 | Under floors etc including forming and poisoning shallow furrows against foundation walls etc, filling in furrows and ramming(pits) | m2 | 104 |

Carried Forward to Summary of Section No. 6

Section No. 6
 Section 6 - Girl Block of 7
 Bill No. 1
 Earthworks (Provisional)
Re-Solve Consulting

R

| Item No | | Quantity | Rate | Amount |
|---------|---|----------|------|--------|
| | <u>SECTION 6</u> | | | |
| | <u>BILL NO. 2</u> | | | |
| | <u>CONCRETE, FORMWORK AND REINFORCEMENT</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>UNREINFORCED CONCRETE, ETC.</u> | | | |
| | <u>15MPa/19mm concrete</u> | | | |
| 6/2/1 | Surface blinding under footings and bases | m3 | 4 | |
| 6/2/2 | Aprons cast in panels to falls | m3 | 2 | |
| 6/2/3 | Extra over concrete in surface beds for thickening 85mm deep the bottom including all excavation, backfilling etc | m | 28 | |
| 6/2/4 | Extra over for concrete thickening in aprons size approximately 100mm deep, 400mm at top and tapering one side to 200mm at bottom, including all excavations, cart away, etc. | m | 25 | |
| | <u>REINFORCED CONCRETE</u> | | | |
| | <u>25MPa/19mm concrete</u> | | | |
| 6/2/5 | Strip footings | m3 | 10 | |
| 6/2/6 | Ramps | m3 | 2 | |
| 6/2/7 | Surface beds cast in panels on waterproofing. | m3 | 4 | |
| 6/2/8 | Slabs (pits) | m3 | 5 | |
| | Carried Forward | | | R |
| | Section No. 6 Section 6 - Girl Block of 7 Bill No. 2 Concrete, Formwork and Reinforcement Re-Solve Consulting | | | |

| Brought Forward | | R |
|--|---|----------|
| <u>TEST CUBES</u> | | |
| 6/2/9 | Allow for preparing a set of three concrete strength test cubes, each size 150 x 150 x 150mm, sending them to an approved Testing Laboratory for testing and paying all charges in connection therewith | Sets 4.0 |
| <u>CONCRETE SUNDRIES</u> | | |
| <u>Finishing top surfaces of concrete smooth with a wood float/steel trowel</u> | | |
| 6/2/10 | Surface beds, slabs, etc | m2 71 |
| 6/2/11 | Surface beds, slabs, etc (pits) | m2 32 |
| 6/2/12 | Aprons to falls | m2 25 |
| <u>SMOOTH FORMWORK (DEGREE OF ACCURACY I)</u> | | |
| <u>Rough formwork to sides</u> | | |
| 6/2/13 | Edges, risers, ends and reveals not exceeding 300mm high or wide | m 28 |
| <u>REINFORCEMENT (PROVISIONAL)</u> | | |
| <u>Fabric Reinforcement</u> | | |
| 6/2/14 | Mesh ref. No. 395 fabric reinforcement fixed horizontalt in surface beds etc. | m2 96 |
| Carried Forward to Summary of Section No. 6 | | R |
| Section No. 6 | | |
| Section 6 - Girl Block of 7 | | |
| Bill No. 2 | | |
| Concrete, Formwork and Reinforcement | | |
| Re-Solve Consulting | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION 6</u> | | | |
| | <u>BILL NO.3</u> | | | |
| | <u>MASONRY</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| | <u>BRICKWORK</u> | | | |
| | <u>Sizes in descriptions</u> | | | |
| | Where sizes in descriptions are given in brick units, "one brick" shall represent the length and "half brick" the width of a brick | | | |
| | Face bricks | | | |
| | Bricks shall be ordered timeously to obtain uniformity in size and colour | | | |
| | Pointing | | | |
| | Descriptions of recessed pointing to fair face brickwork and face brickwork shall be deemed to include square recessed, hollow recessed, weathered pointing, etc | | | |
| | <u>FOUNDATIONS (PROVISIONAL)</u> | | | |
| | <u>Brickwork of NFP bricks in class II mortar</u> | | | |
| 6/3/1 | One brick walls | m2 | 77 | |
| | <u>FACE BRICKWORK</u> | | | |
| | Carried Forward | | | R |
| | Section No. 6 Section 6 - Girl Block of 7 Bill No. 3 Masonry Re-Solve Consulting | | | |

| Brought Forward | | | R |
|--|---|----|----|
| <u>Face bricks (purchase price of R5 000.00/1000 delivered to site excluding VAT) pointed with flush horizontal and vertical joints</u> | | | |
| 6/3/2 | Extra over brickwork for face brickwork in foundations | m2 | 6 |
| <u>SUPERSTRUCTURE</u> | | | |
| <u>Brickwork of NFP bricks in class II mortar</u> | | | |
| 6/3/3 | Half brick walls | m2 | 19 |
| 6/3/4 | Half brick walls in beamfilling | m2 | 1 |
| 6/3/5 | One brick walls | m2 | 12 |
| <u>FACE BRICKWORK</u> | | | |
| 6/3/6 | Extra over brickwork for face brickwork | m2 | 9 |
| 6/3/7 | Extra over brickwork for brick-on-edge header course lintel | m | 11 |
| 6/3/8 | 220mm Wide sill set sloping and slightly protecting outside | m | 11 |
| 6/3/9 | Fair cutting fitting around pipe exceeding 100mm and not exceeding 200mm diameter | No | 8 |
| <u>BRICKWORK SUNDRIES</u> | | | |
| <u>Brickwork reinforcement</u> | | | |
| 6/3/10 | 75mm Wide reinforcement built in horizontally | m | 19 |
| 6/3/11 | 150mm Wide reinforcement built in horizontally | m | 91 |
| <u>Galvanised wire ties etc</u> | | | |
| 6/3/12 | 6mm Diameter roof tie 2m long with one end fixed to timber and other end built into brickwork | No | 4 |
| Carried Forward | | | R |
| Section No. 6 Section 6 - Girl Block of 7 Bill No. 3 Masonry Re-Solve Consulting | | | |

| Brought Forward | | | R |
|--|---|----|----|
| <u>Turning pieces to lintels etc.</u> | | | |
| 6/3/13 | 115mm Wide turning pieces | m | 12 |
| 6/3/14 | 230mm Wide turning pieces | m | 7 |
| <u>Prestressed fabricated lintels</u> | | | |
| 6/3/15 | 110 x 75mm Lintels in lengths exceeding 3m and not exceeding 6m | m | 31 |
| <u>Air bricks etc.</u> | | | |
| 6/3/16 | 230 x 152mm terra-cotta vermin proofed louvered air brick | No | 4 |
| Carried Forward to Summary of Section No. 6 | | | R |
| Section No. 6 | | | |
| Section 6 - Girl Block of 7 | | | |
| Bill No. 3 | | | |
| Masonry | | | |
| Re-Solve Consulting | | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION 6</u> | | | |
| | <u>BILL NO.4</u> | | | |
| | <u>WATERPROOFING</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>DAMP-PROOFING OF WALLS AND FLOORS</u> | | | |
| | <u>One layer of 375 micron Consol Plastic Brikgrip DPC" embossed damp proof course</u> | | | |
| 6/4/1 | In walls | m2 | 27 | |
| | <u>One layer of 250 micron "Consol Plastic USB Green" waterproof sheeting sealed at laps with "Gunplas Pressure Sensitive Tape"</u> | | | |
| 6/4/2 | Under surface beds | m2 | 129 | |
| 6/4/3 | Under aprons and ramps | m2 | 2 | |
| | <u>FLOOR AND WALL SEALERS</u> | | | |
| | <u>Secomastic non setting mastic sealant applied cold with a hand pressure caulking gun and leave perfectly watertight</u> | | | |
| 6/4/4 | Around steel windows and door frames | m | 20 | |
| | Carried Forward to Summary of Section No. 6 | | | R |
| | Section No. 6 | | | |
| | Section 6 - Girl Block of 7 | | | |
| | Bill No. 4 | | | |
| | Waterproofing | | | |
| | Re-Solve Consulting | | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION 6</u> | | | |
| | <u>BILL NO.5</u> | | | |
| | <u>ROOF COVERINGS ETC</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>PROFILED METAL SHEETING AND ACCESSORIES</u> | | | |
| | <u>0,6mm "Kliplok" roof sheeting in chromadek finish fixed to timber purlins (elsewhere)</u> | | | |
| 6/5/1 | Roof covering with pitch not exceeding 25 degrees | m2 | 43 | |
| | <u>ROOF AND WALL INSULATION</u> | | | |
| 6/5/2 | 12" Thermal resistance sisalition laid on purlins | m2 | 43 | |
| | <u>RAINWATER DISPOSAL</u> | | | |
| | For preambles see "Model Preambles for Trades (2008 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>Aluminium Zinc Seamless Gutters</u> | | | |
| 6/5/3 | 100 x 100mm sandard rainwater gutters fixed with gutter brackets | m | 10 | |
| 6/5/4 | Extra over eaves gutter for stopped end | No | 2 | |
| 6/5/5 | 75 x 100mm Diameter rainwater down pipes fixed to wall | m | 6 | |
| 6/5/6 | Extra over eaves gutter for outlet for 75 x 100mm down pipe | No | 2 | |
| 6/5/7 | Ditto .for shoe | No | 2 | |
| | Carried Forward to Summary of Section No. 6 | | | R |
| | Section No. 6 | | | |
| | Section 6 - Girl Block of 7 | | | |
| | Bill No. 5 | | | |
| | Roof Coverings | | | |
| | Re-Solve Consulting | | | |

| Item No | | Quantity | Rate | Amount |
|---------|---|----------|------|--------|
| | <p><u>SECTION 6</u></p> <p><u>BILL NO. 6</u></p> <p><u>CARPENTRY AND JOINERY</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>ROOFS, ETC.</u></p> <p><u>Plate nailed timber roof truss construction</u></p> | | | |
| 6/6/1 | <p>Design, manufacture and deliver on site, plate nailed roof truss construction to Girls Ablution Block of 7, size 9 860 x 3 964 mm overall on plan consisting of mono pitched trusses to suit, with 350mm eaves overhang projecting , including all necessary purlins, runners, bracing and cross bracing (wall plates elsewhere) all in accordance with suppliers and manufacturer's recommendations:</p> <p>Trusses are at maximum 1,10m centres. Roof covering is galvanised "IBR" roof sheeting (measured elsewhere) on 50 x 75mm purlins at 1,1m maximum centres. All timber to be sawn softwood in accordance with V4 or M4 as defined in SABS 563 or SABS 1245. Metal connector plates shall have a minimum yield strength of 228 MPa and a minimum ultimate tensile strength of 330 Mpa with hot-dip galvanised finish. All joints to be close fitted butt joints. Trusses shall be designed by a registered supplier of prefabricated trusses who shall issue an Engineers Certificate upon completion of the installation. The dimensions in the descriptions of the trusses are nominal and actual measurements are to be obtained on site before design or fabricaton commences. Tenderers must study the roof plan and sections as attached to the back of these bills of quantities and must obtain prices from a qualified and registered roof truss supplier as no claims in this regard will be entertained.</p> | No | 1 | |
| | Carried Forward | | R | |
| | <p>Section No. 6 Section 6 - Girl Block of 7 Bill No. 6 Carpentry and Joinery Re-Solve Consulting</p> | | | |

| Brought Forward | | | R |
|--|---|----|------|
| 6/6/2 | Profit on the above | | Item |
| 6/6/3 | Take delivery, temporary store, hoist in position and erect plate nailed timber roof trusses, purlins, gangboarding, temporary and permanent bracing, etc (measured on slope of roof) | | Item |
| <u>Sawn softwood</u> | | | |
| 6/6/4 | 38 x 114mm Wall plates | m | 4 |
| <u>Sundries</u> | | | |
| 6/6/5 | Two coats creosote on sawn timbers | m2 | 39 |
| 6/6/6 | 6mm Diameter galvanised wire tie 3000mm girth wrapped around rafter and purlin with ends tied together | No | 4 |
| 6/6/7 | Hurricane clips | No | 4 |
| <u>EAVES, VERGES, ETC</u> | | | |
| <u>Pressed fibre-cement:</u> | | | |
| 6/6/8 | 15 x 230mm Nutec Fascias and barge boards including galvanised steel H-profile jointing strips | m | 10 |
| <u>DOORS, ETC</u> | | | |
| <u>Wrought meranti doors hung to steel frames</u> | | | |
| 6/6/9 | 44mm framed, ledged and braced door 877 x 2064mm high including external weather bar (D1) | No | 2 |
| 6/6/10 | 44mm framed, ledged and braced door 813 x 1914mm high (door raised by 150mm from bottom) (D2) | No | 7 |
| 6/6/11 | 44mm framed, ledged and braced door 915 x 2032mm high including external weather bar (disabled) | No | 1 |
| Carried Forward to Summary of Section No. 6 | | | R |
| Section No. 6 | | | |
| Section 6 - Girl Block of 7 | | | |
| Bill No. 6 | | | |
| Carpentry and Joinery | | | |
| Re-Solve Consulting | | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION 6</u> | | | |
| | <u>BILL NO. 7</u> | | | |
| | <u>IRONMONGERY</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>HINGES, BOLTS, ETC</u> | | | |
| | <u>100mm Chrome plated "D" type handle 3 by solid brace hinges</u> | | | |
| | <u>CATCHES,CABIN HOOKS, ETC</u> | | | |
| 6/7/1 | 100mm brace Cabin hook and eye including 70 x 70 x 20mm chamfered hardwood block twice oiled and plugged | No | 2 | |
| | <u>LOCKS</u> | | | |
| | <u>Approved</u> | | | |
| 6/7/2 | Three lever mortice lock set | No | 3 | |
| 6/7/3 | Indicator lock set | No | 7 | |
| 6/7/4 | Security double throw dead lock (no latch) | No | 3 | |
| | <u>HANDLES, ETC.</u> | | | |
| | <u>Aluminium Pull Handle</u> | | | |
| 6/7/5 | ASSA ABLOY Anodised Silver straight pull handle (Code: AL5515-300BBAS) with 300mm fixing centres. | No | 10 | |
| | <u>SUNDRIES</u> | | | |
| | Carried Forward | | | R |
| | Section No. 6 Section 6 - Girl Block of 7 Bill No. 7 Ironmongery Re-Solve Consulting | | | |

| Brought Forward | | | R |
|--|--|----|----|
| <u>ASSA ABLOY</u> | | | |
| 6/7/6 | 38mm Diameter rubber door stop plugged | No | 10 |
| <u>Vaal Paragon</u> | | | |
| 6/7/7 | 32mm Type 9 back grab rail 800mm long plugged | No | 1 |
| 6/7/8 | 32mm Type 8 side grab rail 900mm girth plugged | No | 1 |
| <u>LETTERS, NAMEPLATES, ETC</u> | | | |
| <u>Dorma:</u> | | | |
| 6/7/9 | DSS-130 Engraved "Female" information sign, plugged | No | 2 |
| 6/7/10 | DSS-133 Engraved "Disabled" information sign, plugged | No | 1 |
| <u>BATHROOM FITTINGS</u> | | | |
| <u>Sundries</u> | | | |
| <u>Kimberley-Clark or Similar</u> | | | |
| 6/7/11 | SQ2 code 405607B white none lockable toilet roll holder | No | 8 |
| <u>stainless Steel</u> | | | |
| 6/7/12 | Stainless steel mirror size: 350 x 400mm plugged to wall with chrome plated screws. | No | 1 |
| 6/7/13 | Brushed stainless steel body, rust resistant, she bin, approximately 330 x 280 x 180mm etc | No | 8 |
| Carried Forward to Summary of Section No. 6 | | | R |
| Section No. 6 | | | |
| Section 6 - Girl Block of 7 | | | |
| Bill No. 7 | | | |
| Ironmongery | | | |
| Re-Solve Consulting | | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION 6</u> | | | |
| | <u>BILL NO. 8</u> | | | |
| | <u>METALWORK</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>WELDED SCREENS, GATES, ETC</u> | | | |
| | <u>Gates to external doors</u> | | | |
| 6/8/1 | Purpose made square hollow section mild steel single security gate and frame size to fit standard door, size 813 x 2032mm high | No | 2 | |
| 6/8/2 | Single gate and frame size to fit none standard door, size approximately 915 x 2032mm high (disable) | No | 1 | |
| | <u>PRESSED STEEL DOOR FRAMES</u> | | | |
| | <u>1,2mm Double rebated frames suitable for half brick walls</u> | | | |
| 6/8/3 | Frame for door size 813 x 1914mm high | No | 7 | |
| | <u>1,2mm Double rebated frames suitable for one brick walls</u> | | | |
| 6/8/4 | Frame for door size 914 x 2032mm high | No | 1 | |
| | <u>1.2mm Single rebate steel frame suitable for one brick wall</u> | | | |
| 6/8/5 | Frame for door size 813 x 2032mm high | No | 2 | |
| | <u>STEEL WINDOWS, DOORS, ETC</u> | | | |
| | Carried Forward | | | R |
| | Section No. 6 Section 6 - Girl Block of 7 Bill No. 8 Metalwork Re-Solve Consulting | | | |

| | Brought Forward | | | R |
|--|--|----|---|---|
| | <u>Nty steel or similar approved school windows with standard burglar bars formed of 20 x 5mm thick flat bars to all sashes</u> | | | |
| 6/8/6 | Window type NE1, size 533 x 654mm high | No | 8 | |
| 6/8/7 | Window type NE7, size 1022 x 654mm high | No | 3 | |
| | <u>Sundries</u> | | | |
| | <u>Cage, etc</u> | | | |
| 6/8/8 | She bin cages, to fit 330 x 280 x 180mm width, she bin to be able to open, including pad lock and locking mechanism, complete, etc | No | 8 | |
| Carried Forward to Summary of Section No. 6 | | | | R |
| Section No. 6 | | | | |
| Section 6 - Girl Block of 7 | | | | |
| Bill No. 8 | | | | |
| Metalwork | | | | |
| Re-Solve Consulting | | | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION 6</u> | | | |
| | <u>BILL NO.9</u> | | | |
| | <u>PLASTERING</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>GRANOLITHIC</u> | | | |
| | <u>Untinted granolithic on concrete</u> | | | |
| 6/9/1 | 20mm Thick on floors | m2 | 39 | |
| | <u>INTERNAL PLASTER</u> | | | |
| | <u>Cement plaster on brickwork or blockwork</u> | | | |
| 6/9/2 | On internal plastered walls(pits) | m2 | 97 | |
| | <u>FLOOR AND WALLS SEALERS</u> | | | |
| | <u>Minimum two coats approved epoxy coat:</u> | | | |
| 6/9/3 | On floors in pits | m2 | 2 | |
| 6/9/4 | On internal plastered walls in pits | m2 | 97 | |
| | Carried Forward to Summary of Section No. 6 | | | R |
| | Section No. 6 | | | |
| | Section 6 - Girl Block of 7 | | | |
| | Bill No. 9 | | | |
| | Plastering | | | |
| | Re-Solve Consulting | | | |

| Item No | | Quantity | Rate | Amount |
|---------|---|----------|------|--------|
| | <u>SECTION 6</u> | | | |
| | <u>BILL NO. 10</u> | | | |
| | <u>PLUMBING AND DRAINAGE (PROVISIONAL)</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>SANITARY FITTINGS</u> | | | |
| | <u>"Vaal" or similar and approved</u> | | | |
| 6/10/1 | Ceramic wall mounted wash hand basin, complete with all fittings and accessories including cutting & making good wall & floor wherever required for disable toilets. | No | 1 | |
| | <u>SUPPLY AND INSTALL "ENVIRO-LOO" TOILET SYSTEMS</u> | | | |
| | <u>SECTION 5</u> | | | |
| 6/10/2 | Supply and Install "Enviro-Loo" Industrial 1040 Model complete, installed strictly in accordance with manufacturers instructions, unit comprising of top unit and two x louvred inlets, drying plate, two x air inlets, standard toilet pan, seat and lid, 3500mm long outlet vent pipe, ventilation extraction unit fixed to wall with vent wall bracket, 1 bag mounting screws and organic starter, enzyme and toilet cleaner including all necessary inter connector piping between multiple tanks, emergency outlet piping, etc | No | 7 | |
| | Carried Forward | | | R |
| | Section No. 6 Section 6 - Girl Block of 7 Bill No. 10 Plumbing and Drainage (Provisional) Re-Solve Consulting | | | |

| Brought Forward | | | R |
|--|---|----|----|
| 6/10/3 | Supply and Erect disabled "Enviro-loo"Industrial 1040 Model set up and fixed complete as per manufacturers instructions, unit comprising of top unit and two x louvred inlets , drying plate , two x air inlets, paraplegic toilet pan, seat and lid, 3500mm long outlet vent pipe, ventilation extraction unit fixed to wall with vent wall bracket, 1 bag mounting screws and organic starter, enzyme and toilet cleaner including all necessary inter connector piping between multiple tanks, emergency outlet piping,etc | No | 1 |
| <u>PRECAST CONCRETE WASH HAND TROUGH</u> | | | |
| 6/10/4 | Supply and install pre-cast concrete double wash-trough, complete with all necessary pipework including soakaway size 1000 x 1000 x 1000mm covered with "bidim" | No | 2 |
| <u>SOIL DRAINAGE</u> | | | |
| <u>uPVC pipes</u> | | | |
| 6/10/5 | 110mm Pipes laid in and including trenches not exceeding 1m deep | m | 40 |
| <u>Extra over uPVC pipes for fittings</u> | | | |
| 6/10/6 | 110mm Bend | No | 4 |
| 6/10/7 | 110mm Junction | No | 4 |
| <u>uPVC gulleys</u> | | | |
| 6/10/8 | 110mm Gully not exceeding 750mm deep, including excavations, pre-cast concrete surround etc. | No | 4 |
| <u>TRAPS ETC</u> | | | |
| <u>Marley</u> | | | |
| 6/10/9 | 40 x 300mm Sink combination for double bowl with deepseal "P" trap | No | 3 |
| Carried Forward | | | R |
| Section No. 6 Section 6 - Girl Block of 7 Bill No. 10 Plumbing and Drainage (Provisional) Re-Solve Consulting | | | |

Brought Forward

R

TAPS, VALVES, ETC

| | | | |
|---------|--|----|---|
| 6/10/10 | Cobra Watertech 15mm gate valve plugged | No | 2 |
| 6/10/11 | Cobra Watertech 15mm Elbow action pillar tap | No | 1 |

SANITARY PLUMBING

uPVC pipes

| | | | |
|---------|------------|---|----|
| 6/10/12 | 50mm Pipes | m | 25 |
|---------|------------|---|----|

Extra over uPVC pipes for fittings

| | | | |
|---------|------------------|----|---|
| 6/10/13 | 50mm Bend | No | 5 |
| 6/10/14 | 50mm Access bend | No | 5 |
| 6/10/15 | 50mm Junction | No | 6 |

WATER SUPPLIES

Class 0 copper pipes

| | | | |
|---------|------------|---|----|
| 6/10/16 | 15mm Pipes | m | 25 |
| 6/10/17 | 22mm Pipes | m | 25 |

Extra over class 0 copper pipes for capillary fittings

| | | | |
|---------|---------------|----|---|
| 6/10/18 | 15mm Fittings | No | 8 |
| 6/10/19 | 22mm Pipes | No | 8 |

TESTING

| | | | |
|---------|---|--|------|
| 6/10/20 | Allow for testing all drains, sanitary plumbing, water supplies and installtion to the satisfaction of the Principle Agent. | | Item |
|---------|---|--|------|

Carried Forward to Summary of Section No. 6

R

Section No. 6
 Section 6 - Girl Block of 7
 Bill No. 10
 Plumbing and Drainage (Provisional)
Re-Solve Consulting

| Item No | Quantity | Rate | Amount |
|--|----------|------|--------|
| <p><u>SECTION 6</u></p> <p><u>BILL NO. 12</u></p> <p><u>PAINTWORK</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>PAINTWORK ETC TO NEW WORK</u></p> <p><u>PREPARATORY WORK TO EXISTING WORK</u></p> <p><u>Previously painted plastered surfaces</u></p> <p>Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and cracks shall be opened, filled with a suitable filler and finished smooth</p> <p>Previously painted metal surfaces</p> <p>Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal</p> <p>Previously painted wood surfaces</p> <p>Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth</p> <p><u>ON FIBRE-CEMENT</u></p> | | | |
| Carried Forward | | R | |
| <p>Section No. 6 Section 6 - Girl Block of 7 Bill No. 12 Paintwork Re-Solve Consulting</p> | | | |

Brought Forward

R

Prepare and brush to remove all loose contaminations, apply one coat primer and two coats PVA emulsion paint

| | | | |
|--------|-----------------------------|----|---|
| 6/12/1 | On fascias and barge boards | m2 | 5 |
|--------|-----------------------------|----|---|

ON METAL

Prime and paint undercoat and 2 finishing coats in gloss enamel, colour TBC.

| | | | |
|--------|----------------|----|----|
| 6/12/2 | On door frames | m2 | 29 |
|--------|----------------|----|----|

Spot prining defects in pre-prime surface with zinc chromate primer and apply one universal undercoat and two coats EPWP. golden brown gloss enamel paint on steel

| | | | |
|--------|------------------------------|----|---|
| 6/12/3 | On windows with burglar bars | m2 | 5 |
|--------|------------------------------|----|---|

ON WOOD

Under coat and minimum 2 coats gloss enamel, colour TBC

| | | | |
|--------|---------------------|----|---|
| 6/12/4 | On doors (External) | m2 | 4 |
|--------|---------------------|----|---|

| | | | |
|--------|---------------------|----|----|
| 6/12/5 | On doors (Internal) | m2 | 11 |
|--------|---------------------|----|----|

Carried Forward to Summary of Section No. 6

R

Section No. 6
Section 6 - Girl Block of 7
Bill No. 12
Paintwork
Re-Solve Consulting

Section No. 6

Section 6 - Girl Block of 7

SECTION SUMMARY - Section 6 - Girl Block of 7

| Bill No | | Page No | Amount |
|---------|--|---------|--------|
| 6/1 | Earthworks (Provisional) | 107 | |
| 6/2 | Concrete, Formwork and Reinforcement | 109 | |
| 6/3 | Masonry | 112 | |
| 6/4 | Waterproofing | 113 | |
| 6/5 | Roof Coverings | 114 | |
| 6/6 | Carpentry and Joinery | 116 | |
| 6/7 | Ironmongery | 118 | |
| 6/8 | Metalwork | 120 | |
| 6/9 | Plastering | 121 | |
| 6/10 | Plumbing and Drainage (Provisional) | 124 | |
| 6/11 | Glazing | 125 | |
| 6/12 | Paintwork | 127 | |
| | Carried to Final Summary | | R |
| | Section No. 6 Section 6 - Girl Block of 7 Re-Solve Consulting | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <p><u>SECTION 7</u></p> <p><u>BILL NO. 1</u></p> <p><u>EARTHWORKS (PROVISIONAL)</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p>Nature of ground</p> <p>Use "assumed to be" if no trial holes, soils investigations, etc have been carried out - discuss with engineer. Use "Trial holes indicate that" where the ground has been investigated by means of trial holes</p> <p>Nature of ground</p> <p>A soils investigation has been carried out on site by the engineer and the report is annexed to these bills of quantities. Descriptions of excavations shall be deemed to include all ground conditions classifiable as "earth" described in the above report and where conditions of a more difficult character are indicated these are separately measured</p> <p>Carting away of excavated material</p> <p>Descriptions of carting away of excavated material shall be deemed to include loading excavated material onto trucks directly from the excavations or, alternatively, from stock piles situated on the building site</p> <p>Filling</p> <p>Notwithstanding the reference to prescribed multiple handling in clause 1 page 6 of the Standard System of Measuring Building Work, prices for filling and backfilling shall include for all selection and any multiple handling of material</p> | | | |
| | Carried Forward | | R | |
| | <p>Section No. 7 Section 7 - Boy Block of 5 Bill No. 1 Earthworks (Provisional) Re-Solve Consulting</p> | | | |

| Brought Forward | | R |
|--|--|-------|
| Soil poisoning | | |
| <u>Ant and weed poisoning will be applied in accordance to SABS specifications by Registered and Approved Specialists who will issue a five (5) year guarantee. The contractor will only be paid for this items once they have produced the said certificate to the Principal Agent</u> | | |
| <u>SITE CLEARANCE ETC</u> | | |
| <u>Site clearance</u> | | |
| 7/1/1 | Digging up and removing rubbish, debris, vegetation, hedges, shrubs and trees not exceeding 200mm girth, bush, etc | m2 98 |
| 7/1/2 | Stripping average 100mm thick layer of top soil and stockpiling on site | m2 98 |
| <u>EXCAVATION, FILLING, ETC</u> | | |
| <u>Excavation in earth not exceeding 2m deep</u> | | |
| 7/1/3 | Trenches | m3 48 |
| 7/1/4 | Pits | m3 40 |
| 7/1/5 | Thickening under aprons | m3 1 |
| <u>Extra over trench and hole excavations in earth for excavation in</u> | | |
| 7/1/6 | Soft rock | m3 6 |
| 7/1/7 | Hard rock | m3 3 |
| <u>Extra over all excavations for carting away</u> | | |
| 7/1/8 | Surplus material from excavations on site to a dumping site to be located by the contractor | m3 67 |
| Carried Forward | | R |
| Section No. 7 Section 7 - Boy Block of 5 Bill No. 1 Earthworks (Provisional) Re-Solve Consulting | | |

| Brought Forward | | | R |
|--|--|----|------|
| <u>Risk of collapse of excavations</u> | | | |
| 7/1/9 | Sides of trench and hole excavations not exceeding 1,5m deep | m2 | 282 |
| <u>Keeping excavations free of water</u> | | | |
| 7/1/10 | Keeping excavations free of all water other than subterranean water | | Item |
| <u>Earth filling obtained from the excavations and /or prescribed stock piles on site including compacted to 93% Mod AASHTO density</u> | | | |
| 7/1/11 | Under floors, steps, paving, etc | m3 | 14 |
| 7/1/12 | Backfilling to trenches, holes, etc | m3 | 21 |
| <u>Compaction of surfaces</u> | | | |
| 7/1/13 | Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density | m2 | 68 |
| 7/1/14 | Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density (Enviro Loo Tanks Pit) | m2 | 28 |
| 7/1/15 | Ditto but to bottom of trenches and bases | m2 | 45 |
| <u>Prescribed density tests on filling</u> | | | |
| 7/1/16 | Modified AASHTO Density | No | 3 |
| <u>SOIL POISONING</u> | | | |
| <u>Weedkiller mixed in accordance to supplier's specifications</u> | | | |
| 7/1/17 | To bottoms and sides of trenches, etc. | m2 | 241 |
| Carried Forward | | | R |
| Section No. 7 Section 7 - Boy Block of 5 Bill No. 1 Earthworks (Provisional) Re-Solve Consulting | | | |

| | Brought Forward | | | R |
|--|---|----|-----|---|
| 7/1/18 | Under floors etc including forming and poisoning shallow furrows against foundation walls etc, filling in furrows and ramming(pits) | m2 | 130 | |
| | <u>Soil insecticide</u> | | | |
| 7/1/19 | To bottoms and sides of trenches etc | m2 | 241 | |
| 7/1/20 | Under floors etc including forming and poisoning shallow furrows against foundation walls etc, filling in furrows and ramming(pits) | m2 | 108 | |
| Carried Forward to Summary of Section No. 7 | | | | |
| Section No. 7 | | | | |
| Section 7 - Boy Block of 5 | | | | |
| Bill No. 1 | | | | |
| Earthworks (Provisional) | | | | |
| Re-Solve Consulting | | | | |
| | | | | R |

| Item No | | Quantity | Rate | Amount |
|---------|---|----------|------|--------|
| | <u>SECTION NO. 7</u> | | | |
| | <u>BILL NO. 2</u> | | | |
| | <u>CONCRETE, FORMWORK AND REINFORCEMENT</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>UNREINFORCED CONCRETE, ETC.</u> | | | |
| | <u>15MPa/19mm concrete</u> | | | |
| 7/2/1 | Surface blinding under footings and bases | m3 | 4 | |
| 7/2/2 | Aprons cast in panels to falls | m3 | 2 | |
| 7/2/3 | Extra over concrete in surface beds for thickening 85mm deep the bottom including all excavation, backfilling etc | m | 30 | |
| 7/2/4 | Extra over for concrete thickening in aprons size approximately 100mm deep, 400mm at top and tapering one side to 200mm at bottom, including all excavations, cart away, etc. | m | 24 | |
| | <u>REINFORCED CONCRETE</u> | | | |
| | <u>25MPa/19mm concrete</u> | | | |
| 7/2/5 | Strip footings | m3 | 10 | |
| 7/2/6 | Ramps | m3 | 2 | |
| 7/2/7 | Surface beds cast in panels on waterproofing. | m3 | 5 | |
| 7/2/8 | Slabs (pits) | m3 | 4 | |
| | Carried Forward | | | R |
| | Section No. 7 Section 7 - Boy Block of 5 Bill No. 2 Concrete, Formwork and Reinforcement Re-Solve Consulting | | | |

Brought Forward

R

TEST CUBES

| | | | |
|-------|---|------|-----|
| 7/2/9 | Allow for preparing a set of three concrete strength test cubes, each size 150 x 150 x 150mm, sending them to an approved Testing Laboratory for testing and paying all charges in connection therewith | Sets | 4.0 |
|-------|---|------|-----|

CONCRETE SUNDRIES

Finishing top surfaces of concrete smooth with a wood float/steel trowel

| | | | |
|--------|---------------------------------|----|----|
| 7/2/10 | Surface beds, slabs, etc | m2 | 83 |
| 7/2/11 | Surface beds, slabs, etc (pits) | m2 | 25 |
| 7/2/12 | Aprons to falls | m2 | 22 |

SMOOTH FORMWORK (DEGREE OF ACCURACY I)

Rough formwork to sides

| | | | |
|--------|--|---|----|
| 7/2/13 | Edges, risers, ends and reveals not exceeding 300mm high or wide | m | 30 |
|--------|--|---|----|

REINFORCEMENT (PROVISIONAL)

Fabric Reinforcement

| | | | |
|--------|---|----|----|
| 7/2/14 | Mesh ref. No. 395 fabric reinforcement fixed horizontalt in surface beds etc. | m2 | 93 |
|--------|---|----|----|

Carried Forward to Summary of Section No. 7

R

Section No. 7
 Section 7 - Boy Block of 5
 Bill No. 2
 Concrete, Formwork and Reinforcement
Re-Solve Consulting

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <p><u>SECTION NO. 7</u></p> <p><u>BILL NO.3</u></p> <p><u>MASONRY</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>BRICKWORK</u></p> <p><u>Sizes in descriptions</u></p> <p>Where sizes in descriptions are given in brick units, "one brick" shall represent the length and "half brick" the width of a brick</p> <p>Face bricks</p> <p>Bricks shall be ordered timeously to obtain uniformity in size and colour</p> <p>Pointing</p> <p>Descriptions of recessed pointing to fair face brickwork and face brickwork shall be deemed to include square recessed, hollow recessed, weathered pointing, etc</p> <p><u>FOUNDATIONS (PROVISIONAL)</u></p> <p><u>Brickwork of NFP bricks in class II mortar</u></p> | | | |
| 7/3/1 | One brick walls | m2 | 79 | |
| | <p><u>FACE BRICKWORK</u></p> | | | |
| | Carried Forward | | | R |
| | <p>Section No. 7 Section 7 - Boy Block of 5 Bill No. 3 Masonry Re-Solve Consulting</p> | | | |

| Brought Forward | | | R |
|--|---|----|----|
| <u>Face bricks (purchase price of R5 000.00/1000 delivered to site excluding VAT) pointed with flush horizontal and vertical joints</u> | | | |
| 7/3/2 | Extra over brickwork for face brickwork in foundations | m2 | 6 |
| <u>SUPERSTRUCTURE</u> | | | |
| <u>Brickwork of NFP bricks in class II mortar</u> | | | |
| 7/3/3 | Half brick walls | m2 | 17 |
| 7/3/4 | Half brick walls in beamfilling | m2 | 1 |
| 7/3/5 | One brick walls | m2 | 12 |
| <u>FACE BRICKWORK</u> | | | |
| 7/3/6 | Extra over brickwork for face brickwork | m2 | 9 |
| 7/3/7 | Extra over brickwork for brick-on-edge header course lintel | m | 11 |
| 7/3/8 | 220mm Wide sill set sloping and slightly protecting outside | m | 11 |
| 7/3/9 | Fair cutting fitting around pipe not exceeding 100mm | No | 6 |
| 7/3/10 | Fair cutting fitting around pipe exceeding 100mm and not exceeding 200mm diameter | No | 6 |
| <u>BRICKWORK SUNDRIES</u> | | | |
| <u>Brickwork reinforcement</u> | | | |
| 7/3/11 | 75mm Wide reinforcement built in horizontally | m | 17 |
| 7/3/12 | 150mm Wide reinforcement built in horizontally | m | 92 |
| <u>Galvanised wire ties etc</u> | | | |
| 7/3/13 | 6mm Diameter roof tie 2m long with one end fixed to timber and other end built into brickwork | No | 4 |
| Carried Forward | | | R |
| Section No. 7 Section 7 - Boy Block of 5 Bill No. 3 Masonry Re-Solve Consulting | | | |

| Brought Forward | | | R |
|--|---|----|----|
| <u>Turning pieces to lintels etc.</u> | | | |
| 7/3/14 | 115mm Wide turning pieces | m | 10 |
| 7/3/15 | 230mm Wide turning pieces | m | 8 |
| <u>Prestressed fabricated lintels</u> | | | |
| 7/3/16 | 110 x 75mm Lintels in lengths exceeding 3m and not exceeding 6m | m | 27 |
| <u>Air bricks etc.</u> | | | |
| 7/3/17 | 230 x 152mm terra-cotta vermin proofed louvered air brick | No | 4 |
| Carried Forward to Summary of Section No. 7 | | | R |
| Section No. 7 | | | |
| Section 7 - Boy Block of 5 | | | |
| Bill No. 3 | | | |
| Masonry | | | |
| Re-Solve Consulting | | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION NO. 7</u> | | | |
| | <u>BILL NO.4</u> | | | |
| | <u>WATERPROOFING</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>DAMP-PROOFING OF WALLS AND FLOORS</u> | | | |
| | <u>One layer of 375 micron Consol Plastic Brikgrip DPC" embossed damp proof course</u> | | | |
| 7/4/1 | In walls | m2 | 25 | |
| | <u>One layer of 250 micron "Consol Plastic USB Green" waterproof sheeting sealed at laps with "Gunplas Pressure Sensitive Tape"</u> | | | |
| 7/4/2 | Under surface beds | m2 | 128 | |
| 7/4/3 | Under aprons and ramps | m2 | 2 | |
| | <u>FLOOR AND WALL SEALERS</u> | | | |
| | <u>Secomastic non setting mastic sealant applied cold with a hand pressure caulking gun and leave perfectly watertight</u> | | | |
| 7/4/4 | Around steel windows and door frames | m | 19 | |
| | Carried Forward to Summary of Section No. 7 | | | R |
| | Section No. 7 | | | |
| | Section 7 - Boy Block of 5 | | | |
| | Bill No. 4 | | | |
| | Waterproofing | | | |
| | Re-Solve Consulting | | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION NO. 7</u> | | | |
| | <u>BILL NO.5</u> | | | |
| | <u>ROOF COVERINGS ETC</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>PROFILED METAL SHEETING AND ACCESSORIES</u> | | | |
| | <u>0,6mm "Kliplok" roof sheeting in chromadek finish fixed to timber purlins (elsewhere)</u> | | | |
| 7/5/1 | Roof covering with pitch not exceeding 25 degrees | m2 | 48 | |
| | <u>ROOF AND WALL INSULATION</u> | | | |
| 7/5/2 | 12" Thermal resistance sisalition laid on purlins | m2 | 48 | |
| | <u>RAINWATER DISPOSAL</u> | | | |
| | For preambles see "Model Preambles for Trades (2008 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>Aluminium Zinc Seamless Gutters</u> | | | |
| 7/5/3 | 100 x 100mm sandard rainwater gutters fixed with gutter brackets | m | 11 | |
| 7/5/4 | Extra over eaves gutter for stopped end | No | 2 | |
| 7/5/5 | 75 x 100mm Diameter rainwater down pipes fixed to wall | m | 6 | |
| 7/5/6 | Extra over eaves gutter for outlet for 75 x 100mm down pipe | No | 2 | |
| 7/5/7 | Ditto .for shoe | No | 2 | |
| | Carried Forward to Summary of Section No. 7 | | | R |
| | Section No. 7 | | | |
| | Section 7 - Boy Block of 5 | | | |
| | Bill No. 5 | | | |
| | Roof Coverings | | | |
| | Re-Solve Consulting | | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <p><u>SECTION NO. 7</u></p> <p><u>BILL NO. 6</u></p> <p><u>CARPENTRY AND JOINERY</u></p> <p>For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>ROOFS, ETC.</u></p> <p><u>Plate nailed timber roof truss construction</u></p> | | | |
| 7/6/1 | <p>Design, manufacture and deliver on site, plate nailed roof truss construction to Boys Ablution Block of 5, size 10 995 x 3 964 mm overall on plan consisting of mono pitched trusses to suit, with 350mm eaves overhang projecting , including all necessary purlins, runners, bracing and cross bracing (wall plates elsewhere) all in accordance with suppliers and manufacturer's recommendations:</p> <p>Trusses are at maximum 1,10m centres. Roof covering is galvanised "IBR" roof sheeting (measured elsewhere) on 50 x 75mm purlins at 1,1m maximum centres. All timber to be sawn softwood in accordance with V4 or M4 as defined in SABS 563 or SABS 1245. Metal connector plates shall have a minimum yield strength of 228 MPa and a minimum ultimate tensile strength of 330 Mpa with hot-dip galvanised finish. All joints to be close fitted butt joints. Trusses shall be designed by a registered supplier of prefabricated trusses who shall issue an Engineers Certificate upon completion of the installation. The dimensions in the descriptions of the trusses are nominal and actual measurements are to be obtained on site before design or fabrication commences. Tenderers must study the roof plan and sections as attached to the back of these bills of quantities and must obtain prices from a qualified and registered roof truss supplier as no claims in this regard will be entertained.</p> | No | 1 | |
| | Carried Forward | | | R |
| | <p>Section No. 7 Section 7 - Boy Block of 5 Bill No. 6 Carpentry and Joinery Re-Solve Consulting</p> | | | |

| Brought Forward | | | R |
|--|---|----|------|
| 7/6/2 | Profit on the above | | Item |
| 7/6/3 | Take delivery, temporary store, hoist in position and erect plate nailed timber roof trusses, purlins, gangboarding, temporary and permanent bracing, etc (measured on slope of roof) | | Item |
| <u>Sawn softwood</u> | | | |
| 7/6/4 | 38 x 114mm Wall plates | m | 4 |
| <u>Sundries</u> | | | |
| 7/6/5 | Two coats creosote on sawn timbers | m2 | 44 |
| 7/6/6 | 6mm Diameter galvanised wire tie 3000mm girth wrapped around rafter and purlin with ends tied together | No | 4 |
| 7/6/7 | Hurricane clips | No | 4 |
| <u>EAVES, VERGES, ETC</u> | | | |
| <u>Pressed fibre-cement:</u> | | | |
| 7/6/8 | 15 x 230mm Nutec Fascias and barge boards including galvanised steel H-profile jointing strips | m | 11 |
| <u>DOORS, ETC</u> | | | |
| <u>Wrought meranti doors hung to steel frames</u> | | | |
| 7/6/9 | 44mm framed, ledged and braced door 877 x 2064mm high including external weather bar (D1) | No | 2 |
| 7/6/10 | 44mm framed, ledged and braced door 813 x 1914mm high (door raised by 150mm from bottom) (D2) | No | 5 |
| 7/6/11 | 44mm framed, ledged and braced door 915 x 2032mm high including external weather bar (disabled) | No | 1 |
| Carried Forward to Summary of Section No. 7 | | | R |
| Section No. 7 | | | |
| Section 7 - Boy Block of 5 | | | |
| Bill No. 6 | | | |
| Carpentry and Joinery | | | |
| Re-Solve Consulting | | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION NO. 7</u> | | | |
| | <u>BILL NO. 7</u> | | | |
| | <u>IRONMONGERY</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>HINGES, BOLTS, ETC</u> | | | |
| | <u>100mm Chrome plated "D" type handle 3 by solid brace hinges</u> | | | |
| | <u>CATCHES,CABIN HOOKS, ETC</u> | | | |
| 7/7/1 | 100mm brace Cabin hook and eye including 70 x 70 x 20mm chamfered hardwood block twice oiled and plugged | No | 2 | |
| | <u>LOCKS</u> | | | |
| | <u>Approved</u> | | | |
| 7/7/2 | Three lever mortice lock set | No | 2 | |
| 7/7/3 | Indicator lock set | No | 5 | |
| 7/7/4 | Security double throw dead lock (no latch) | No | 2 | |
| | <u>HANDLES, ETC.</u> | | | |
| | <u>Aluminium Pull Handle</u> | | | |
| 7/7/5 | ASSA ABLOY Anodised Silver straight pull handle (Code: AL5515-300BBAS) with 300mm fixing centres. | No | 8 | |
| | <u>SUNDRIES</u> | | | |
| | Carried Forward | | | R |
| | Section No. 7 Section 7 - Boy Block of 5 Bill No. 7 Ironmongery Re-Solve Consulting | | | |

| Brought Forward | | | R |
|--|---|----|---|
| <u>ASSA ABLOY</u> | | | |
| 7/7/6 | 38mm Diameter rubber door stop plugged | No | 8 |
| <u>Vaal Paragon</u> | | | |
| 7/7/7 | 32mm Type 9 back grab rail 800mm long plugged | No | 1 |
| 7/7/8 | 32mm Type 8 side grab rail 900mm girth plugged | No | 1 |
| <u>LETTERS, NAMEPLATES, ETC</u> | | | |
| <u>Dorma:</u> | | | |
| 7/7/9 | DSS-130 Engraved "Male" information sign, plugged | No | 2 |
| 7/7/10 | DSS-133 Engraved "Disabled" information sign, plugged | No | 1 |
| <u>BATHROOM FITTINGS</u> | | | |
| <u>Sundries</u> | | | |
| <u>Kimberley-Clark or Similar</u> | | | |
| 7/7/11 | SQ2 code 405607B white none lockable toilet roll holder | No | 6 |
| <u>stainless Steel</u> | | | |
| 7/7/12 | Stainless steel mirror size: 350 x 400mm plugged to wall with chrome plated screws. | No | 1 |
| Carried Forward to Summary of Section No. 7 | | | R |
| Section No. 7 | | | |
| Section 7 - Boy Block of 5 | | | |
| Bill No. 7 | | | |
| Ironmongery | | | |
| Re-Solve Consulting | | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION NO. 7</u> | | | |
| | <u>BILL NO. 8</u> | | | |
| | <u>METALWORK</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>WELDED SCREENS, GATES, ETC</u> | | | |
| | <u>Gates to external doors</u> | | | |
| 7/8/1 | Purpose made square hollow section mild steel single security gate and frame size to fit standard door, size 813 x 2032mm high | No | 2 | |
| 7/8/2 | Single gate and frame size to fit none standard door, size approximately 915 x 2032mm high (disable) | No | 1 | |
| | <u>PRESSED STEEL DOOR FRAMES</u> | | | |
| | <u>1,2mm Double rebated frames suitable for half brick walls</u> | | | |
| 7/8/3 | Frame for door size 813 x 1914mm high | No | 5 | |
| | <u>1,2mm Double rebated frames suitable for one brick walls</u> | | | |
| 7/8/4 | Frame for door size 914 x 2032mm high | No | 1 | |
| | <u>1,2mm Single rebate steel frame suitable for one brick wall</u> | | | |
| 7/8/5 | Frame for door size 813 x 2032mm high | No | 2 | |
| | <u>STEEL WINDOWS, DOORS, ETC</u> | | | |
| | Carried Forward | | | R |
| | Section No. 7 Section 7 - Boy Block of 5 Bill No. 8 Metalwork Re-Solve Consulting | | | |

| | | Brought Forward | | R |
|--|---|-----------------|---|---|
| | <u>Nty steel or similar approved school windows with standard burglar bars formed of 20 x 5mm thick flat bars to all sashes</u> | | | |
| 7/8/6 | Window type NE1, size 533 x 654mm high | No | 9 | |
| 7/8/7 | Window type NE7, size 1022 x 654mm high | No | 3 | |
| Carried Forward to Summary of Section No. 7 | | | | R |
| Section No. 7 | | | | |
| Section 7 - Boy Block of 5 | | | | |
| Bill No. 8 | | | | |
| Metalwork | | | | |
| Re-Solve Consulting | | | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION NO. 7</u> | | | |
| | <u>BILL NO.9</u> | | | |
| | <u>PLASTERING</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>GRANOLITHIC</u> | | | |
| | <u>Untinted granolithic on concrete</u> | | | |
| 7/9/1 | 20mm Thick on floors | m2 | 44 | |
| | <u>INTERNAL PLASTER</u> | | | |
| | <u>Cement plaster on brickwork or blockwork</u> | | | |
| 7/9/2 | On internal plastered walls(pits) | m2 | 75 | |
| | <u>FLOOR AND WALLS SEALERS</u> | | | |
| | <u>Minimum two coats approved epoxy coat:</u> | | | |
| 7/9/3 | On floors in pits | m2 | 1 | |
| 7/9/4 | On internal plastered walls in pits | m2 | 75 | |
| | Carried Forward to Summary of Section No. 7 | | | R |
| | Section No. 7 | | | |
| | Section 7 - Boy Block of 5 | | | |
| | Bill No. 9 | | | |
| | Plastering | | | |
| | Re-Solve Consulting | | | |

| Item No | | Quantity | Rate | Amount |
|---------|---|----------|------|--------|
| | <u>SECTION NO. 7</u> | | | |
| | <u>BILL NO. 10</u> | | | |
| | <u>PLUMBING AND DRAINAGE (PROVISIONAL)</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>SANITARY FITTINGS</u> | | | |
| | <u>"Vaal" or similar and approved</u> | | | |
| 7/10/1 | Ceramic wall mounted wash hand basin, complete with all fittings and accessories including cutting & making good wall & floor wherever required for disable toilets. | No | 1 | |
| | <u>SUPPLY AND INSTALL "ENVIRO-LOO" TOILET SYSTEMS</u> | | | |
| 7/10/2 | Supply and Install "Enviro-Loo" Industrial 1040 Model complete, installed strictly in accordance with manufacturers instructions, unit comprising of top unit and two x louvred inlets, drying plate, two x air inlets, standard toilet pan, seat and lid, 3500mm long outlet vent pipe, ventilation extraction unit fixed to wall with vent wall bracket, 1 bag mounting screws and organic starter, enzyme and toilet cleaner including all necessary inter connector piping between multiple tanks, emergency outlet piping, etc | No | 5 | |
| | Carried Forward | | | R |
| | Section No. 7 Section 7 - Boy Block of 5 Bill No. 10 Plumbing and Drainage (Provisional) Re-Solve Consulting | | | |

| Brought Forward | | | R |
|---|---|----|----|
| 7/10/3 | Supply and Erect disabled "Enviro-loo"Industrial 1040 Model set up and fixed complete as per manufacturers instructions, unit comprising of top unit and two x louvred inlets , drying plate , two x air inlets, paraplegic toilet pan, seat and lid, 3500mm long outlet vent pipe, ventilation extraction unit fixed to wall with vent wall bracket, 1 bag mounting screws and organic starter, enzyme and toilet cleaner including all necessary inter connector piping between multiple tanks, emergency outlet piping,etc | No | 1 |
| 7/10/4 | Supply and Erect "Enviro-loo" Urinal Evaporative Tank system fixed complete as per manufacturers specification unit comprising of urinal evaporative tank , urinal bowls including brackets , 3500mm long outlet vent pipe , ventilation extraction unit fixed to wall with vent wall bracket, 1 bag mounting screws and organic starter, enzyme and toilet cleaner including all necessary piping, traps, etc | No | 6 |
| <u>PRECAST CONCRETE WASH HAND TROUGH</u> | | | |
| 7/10/5 | Supply and install pre-cast concrete double wash-trough, complete with all necessary pipework including soakaway size 1000 x 1000 x 1000mm covered with "bidim" | No | 2 |
| <u>SOIL DRAINAGE</u> | | | |
| <u>uPVC pipes</u> | | | |
| 7/10/6 | 110mm Pipes laid in and including trenches not exceeding 1m deep | m | 30 |
| <u>Extra over uPVC pipes for fittings</u> | | | |
| 7/10/7 | 110mm Bend | No | 6 |
| 7/10/8 | 110mm Junction | No | 6 |
| <u>uPVC gulleys</u> | | | |
| 7/10/9 | 110mm Gulley not exceeding 750mm deep, including excavations, pre-cast concrete surround etc. | No | 3 |
| Carried Forward | | | R |
| Section No. 7 Section 7 - Boy Block of 5 Bill No. 10 Plumbing and Drainage (Provisional) Re-Solve Consulting | | | |

| Brought Forward | | | R |
|---|--|----|----|
| <u>TRAPS ETC</u> | | | |
| <u>Marley</u> | | | |
| 7/10/10 | 40 x 300mm Sink combination for double bowl with deepseal "P" trap | No | 3 |
| <u>TAPS, VALVES, ETC</u> | | | |
| 7/10/11 | Cobra Watertech 15mm gate valve plugged | No | 2 |
| 7/10/12 | Cobra Watertech 15mm Elbow action pillar tap | No | 1 |
| <u>SANITARY PLUMBING</u> | | | |
| <u>uPVC pipes</u> | | | |
| 7/10/13 | 50mm Pipes | m | 30 |
| <u>Extra over uPVC pipes for fittings</u> | | | |
| 7/10/14 | 50mm Bend | No | 6 |
| 7/10/15 | 50mm Access bend | No | 3 |
| 7/10/16 | 50mm Junction | No | 3 |
| <u>WATER SUPPLIES</u> | | | |
| <u>Class 0 copper pipes</u> | | | |
| 7/10/17 | 15mm Pipes | m | 22 |
| 7/10/18 | 22mm Pipes | m | 20 |
| <u>Extra over class 0 copper pipes for capillary fittings</u> | | | |
| 7/10/19 | 15mm Fittings | No | 5 |
| 7/10/20 | 22mm Pipes | No | 5 |
| Carried Forward | | | R |
| Section No. 7 Section 7 - Boy Block of 5 Bill No. 10 Plumbing and Drainage (Provisional) Re-Solve Consulting | | | |

Brought Forward

R

TESTING

7/10/21

Allow for testing all drains, sanitary plumbing, water supplies and installtion to the satisfaction of the Principle Agent.

Item

Carried Forward to Summary of Section No. 7

R

Section No. 7
 Section 7 - Boy Block of 5
 Bill No. 10
 Plumbing and Drainage (Provisional)
Re-Solve Consulting

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION NO. 7</u> | | | |
| | <u>BILL NO. 11</u> | | | |
| | <u>GLAZING</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>GLAZING TO STEEL WITH PUTTY</u> | | | |
| | <u>6.38mm Obscure safety glass</u> | | | |
| 7/11/1 | Panes not exceeding 0,1 m2 | m2 | 5 | |
| | Carried Forward to Summary of Section No. 7 | | | R |
| | Section No. 7 | | | |
| | Section 7 - Boy Block of 5 | | | |
| | Bill No. 11 | | | |
| | Glazing | | | |
| | Re-Solve Consulting | | | |

| Item No | Quantity | Rate | Amount |
|--|----------|------|--------|
| <u>SECTION NO. 7</u> | | | |
| <u>BILL NO. 12</u> | | | |
| <u>PAINTWORK</u> | | | |
| For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| <u>PAINTWORK ETC TO NEW WORK</u> | | | |
| <u>PREPARATORY WORK TO EXISTING WORK</u> | | | |
| <u>Previously painted plastered surfaces</u> | | | |
| Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and cracks shall be opened, filled with a suitable filler and finished smooth | | | |
| Previously painted metal surfaces | | | |
| Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal | | | |
| Previously painted wood surfaces | | | |
| Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth | | | |
| <u>ON FIBRE-CEMENT</u> | | | |
| Carried Forward | | | R |
| Section No. 7 Section 7 - Boy Block of 5 Bill No. 12 Paintwork Re-Solve Consulting | | | |

Brought Forward

R

Prepare and brush to remove all loose contaminations, apply one coat primer and two coats PVA emulsion paint

7/12/1 On fascias and barge boards m2 5

ON METAL

Prime and paint undercoat and 2 finishing coats in gloss enamel, colour TBC.

7/12/2 On door frames m2 23

Spot prining defects in pre-prime surface with zinc chromate primer and apply one universal undercoat and two coats EPWP. golden brown gloss enamel paint on steel

7/12/3 On windows with burglar bars m2 5

ON WOOD

Under coat and minimum 2 coats gloss enamel, colour TBC

7/12/4 On doors (External) m2 4

7/12/5 On doors (Internal) m2 8

Carried Forward to Summary of Section No. 7

R

Section No. 7
 Section 7 - Boy Block of 5
 Bill No. 12
 Paintwork
Re-Solve Consulting

Section No. 7
 Section 7 - Boy Block of 5

SECTION SUMMARY - Section 7 - Boy Block of 5

| Bill No | | Page No | Amount |
|---------|---|---------|--------|
| 7/1 | Earthworks (Provisional) | 132 | |
| 7/2 | Concrete, Formwork and Reinforcement | 134 | |
| 7/3 | Masonry | 137 | |
| 7/4 | Waterproofing | 138 | |
| 7/5 | Roof Coverings | 139 | |
| 7/6 | Carpentry and Joinery | 141 | |
| 7/7 | Ironmongery | 143 | |
| 7/8 | Metalwork | 145 | |
| 7/9 | Plastering | 146 | |
| 7/10 | Plumbing and Drainage (Provisional) | 150 | |
| 7/11 | Glazing | 151 | |
| 7/12 | Paintwork | 153 | |
| | Carried to Final Summary | | R |
| | Section No. 7 Section 7 - Boy Block of 5 Re-Solve Consulting | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION NO.8</u> | | | |
| | <u>BILL NO. 1</u> | | | |
| | <u>ELEVATED WATER TANKS</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>EXCAVATION, FILLING, ETC</u> | | | |
| | <u>Excavation in earth not exceeding 2m deep</u> | | | |
| 8/1/1 | Holes | m3 | 48 | |
| | <u>Extra over trench and hole excavations in earth for excavation in</u> | | | |
| 8/1/2 | Soft rock | m3 | 24 | |
| 8/1/3 | Hard rock | m3 | 12 | |
| | <u>Extra over all excavations for carting away</u> | | | |
| 8/1/4 | Surplus material from excavations on site to a dumping site to be located by the contractor | m3 | 36 | |
| | <u>Risk of collapse of excavations</u> | | | |
| 8/1/5 | Sides of trench and hole excavations not exceeding 1,5m deep | m2 | 96 | |
| | <u>Keeping excavations free of water</u> | | | |
| 8/1/6 | Keeping excavations free of all water other than subterranean water | | Item | |
| | <u>Earth filling obtained from the excavations and /or prescribed stock piles on site including compacted to 93% Mod AASHTO density</u> | | | |
| 8/1/7 | Backfilling to trenches, holes, etc | m3 | 12 | |
| | Carried Forward | | | R |
| | Section No. 8 Section 8 - External Works Bill No. 1 Elevated Water Tanks Re-Solve Consulting | | | |

| Brought Forward | | | R |
|--|---|------|-----|
| <u>Compaction of surfaces</u> | | | |
| 8/1/8 | Ditto but to bottom of trenches and bases | m2 | 144 |
| <u>SOIL POISONING</u> | | | |
| <u>Soil insecticide</u> | | | |
| 8/1/9 | To bottoms and sides of trenches etc | m2 | 144 |
| <u>One layer of 250 micron "Consol Plastic USB Green" waterproof sheeting sealed at laps with "Gunplas Pressure Sensitive Tape"</u> | | | |
| 8/1/10 | Under surface beds | m2 | 144 |
| <u>UNREINFORCED CONCRETE, ETC.</u> | | | |
| <u>15MPa/19mm concrete</u> | | | |
| 8/1/11 | Surface blinding under footings and bases | m3 | 6 |
| <u>REINFORCED CONCRETE</u> | | | |
| <u>25MPa/19mm concrete</u> | | | |
| 8/1/12 | Bases | m3 | 36 |
| 8/1/13 | Platform surface beds cast in panels | m3 | 30 |
| <u>TEST CUBES</u> | | | |
| 8/1/14 | Allow for preparing a set of three concrete strength test cubes, each size 150 x 150 x 150mm, sending them to an approved Testing Laboratory for testing and paying all charges in connection therewith | Sets | 4.0 |
| <u>CONCRETE SUNDRIES</u> | | | |
| <u>Finishing top surfaces of concrete smooth with a wood float/steel trowel</u> | | | |
| 8/1/15 | Platform surface beds | m2 | 144 |
| Carried Forward | | | R |
| Section No. 8 Section 8 - External Works Bill No. 1 Elevated Water Tanks Re-Solve Consulting | | | |

| Brought Forward | | | | R |
|--|---|----|------|---|
| 8/1/16 | Top of bases | m2 | 30 | |
| <u>"Jojo" or equal approved SANS PVC water tanks</u> | | | | |
| 8/1/17 | 10 000 Litre plastic water tank fitted onto and secured to tank platforms | No | 9 | |
| <u>Galvanized medium normalized mild steel piping</u> | | | | |
| 8/1/18 | 25mm Pipes | m | 360 | |
| 8/1/19 | 50mm Pipes | m | 612 | |
| <u>Extra over galvanised mild steel water supply pipes for fittings:</u> | | | | |
| 8/1/20 | 25mm Fittings | No | 60 | |
| 8/1/21 | 50mm Elbows | No | 60 | |
| 8/1/22 | 50mm Union | No | 60 | |
| 8/1/23 | 50mm Reducing bush. | No | 24 | |
| <u>"Cobra Watertech" or other equal approved</u> | | | | |
| 8/1/24 | 15mm "Cobra Ref. 108LK" brass hose biptap. | No | 24 | |
| 8/1/25 | 50mm Fullway gate valve | No | 24 | |
| <u>The following in structural steel tank stands</u> | | | | |
| <u>Welded steel columns in single lengths with flat base, cap, bearer and connection plates, bolted to concrete</u> | | | | |
| 8/1/26 | 80 x 80mm x 6mm angle columns | t | 8.94 | |
| <u>Steel members and girth, bolted to steel</u> | | | | |
| 8/1/27 | 30 x 30mm x 6mm Flat-bar | t | 1.14 | |
| Carried Forward | | | | R |
| Section No. 8 Section 8 - External Works Bill No. 1 Elevated Water Tanks Re-Solve Consulting | | | | |

| Brought Forward | | | R |
|---|---|------|------|
| 8/1/28 | 40 x 40mm x 5mm angle | t | 1.14 |
| 8/1/29 | 125 x 75mm x 8mm unequal angle | t | 1.32 |
| 8/1/30 | 125 x 50mm x 20 x 2mm Lipped channel | t | 2.82 |
| <u>BOLTS, FASTENERS, ETC (LI)</u> | | | |
| 8/1/31 | High tensile bolts | t | 3.00 |
| 8/1/32 | 12mm Diameter L-shaped threaded anchor bolt 350mm girth embedded in top of concrete | No | 96 |
| <u>ON METAL</u> | | | |
| <u>Undercoat and minimum 2 coat gloss enamel</u> | | | |
| 8/1/33 | Paint to structural steel | m | 750 |
| <u>TESTING</u> | | | |
| <u>Testing of water tanks</u> | | | |
| 8/1/34 | Testing for tank | Item | |
| Carried Forward to Summary of Section No. 8 | | | R |
| Section No. 8 | | | |
| Section 8 - External Works | | | |
| Bill No. 1 | | | |
| Elevated Water Tanks | | | |
| Re-Solve Consulting | | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION NO.8</u> | | | |
| | <u>BILL NO. 2</u> | | | |
| | <u>PAVED WALKWAYS</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>SITE CLEARANCE ETC</u> | | | |
| | <u>Site Clearance</u> | | | |
| 8/2/1 | Digging up and removing rubbish, debris, vegetation, hedges, shrubs, bush and trees not exceeding 200mm girth, etc | m2 | 239 | |
| 8/2/2 | Stripping average 100mm thick layer of top soil and stockpiling on site | m2 | 239 | |
| | <u>EXCAVATION, FILLING, ETC</u> | | | |
| | <u>Open face excavation in earth over sloping site</u> | | | |
| 8/2/3 | Excavation in earth not exceeding 2m open face excavation to form platforms under parking areas etc and depositing excavated material over site, including haulage not exceeding 10m from perimeter of excavations exceeding 2m deep | m3 | 60 | |
| | <u>Extra over all excavations for carting away</u> | | | |
| 8/2/4 | Surplus material from excavations and/stock piles on site to the dumping site to be located by the Contractor. | m3 | 60 | |
| | Carried Forward | | | R |
| | Section No. 8 Section 8 - External Works Bill No. 2 Paved Walkways Re-Solve Consulting | | | |

| Brought Forward | | | R |
|--|--|----|-----|
| | <u>Earth filling supplied by the contractor under parking areas, roadways, etc</u> | | |
| 8/2/5 | Sub-base course of G5 material in accordance with SABS 1200 DM, compacted to 93% Mod AASHTO density | m3 | 60 |
| | <u>Compaction of surfaces</u> | | |
| 8/2/6 | Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density | m2 | 239 |
| | <u>SOIL POISONING</u> | | |
| | <u>Soil poisoning</u> | | |
| 8/2/7 | Weedkiller (active ingredients metalaclor 102,8 g/l, terbitilasien 248,6 g/l and atrasiensien 248,6 g/l) mixed in the proportion of 100 ml weedkiller to 100 l water and applied at a rate of 10 l/m ² on cleared ground | m2 | 239 |
| | <u>PAVING, KERBS, ETC.</u> | | |
| | <u>60mm Thick precast concrete DZZ interlocking heavy duty block paving of grey paving blocks in accordance with SANS 1058, laid to falls on and including 25mm thick sand layer with joints filled in with sand, compacted with a vibration compactor:</u> | | |
| 8/2/8 | Paving to toilet areas etc to falls | m2 | 239 |
| 8/2/9 | Fig. 12 kerbs to sides of paving | m | 381 |
| 8/2/10 | 15Mpa/19mm unreinforced concrete in haunching | m3 | 11 |
| Carried Forward to Summary of Section No. 8 | | | R |
| Section No. 8 | | | |
| Section 8 - External Works | | | |
| Bill No. 2 | | | |
| Paved Walkways | | | |
| Re-Solve Consulting | | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION NO.8</u> | | | |
| | <u>BILL NO. 3</u> | | | |
| | <u>FENCING</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>DEMOLITIONS, ALTERATIONS, ETC.</u> | | | |
| | <u>Take down and removing existing works</u> | | | |
| 8/3/1 | Steel palisade fencing not exceeding 2400mm high | m | 568 | |
| | <u>STEEL PALISADE FENCING</u> | | | |
| | <u>Mild steel welded palisade fence including spot prime exposed metal surfaces and two coats high gloss enamel paint</u> | | | |
| 8/3/2 | Palisade fence 2400mm high of 40 x 40 x 3mm angle section continuous top and bottom rails and 30 x 30 x 3mm angle section pickets with top end split and sharpened at average 150mm centres, welded to rails, rails welded 2600mm high posts of 76 x 76 x 5mm square tube with steel pyramid shaped capping on top at 2475mm centres with 500mm bottom ends cast into and including 15Mpa concrete footing in ground including excavation, ramming, removal of spoil and leaving clean, neat and painted | m | 568 | |
| | Carried Forward to Summary of Section No. 8 | | | R |
| | Section No. 8 | | | |
| | Section 8 - External Works | | | |
| | Bill No. 3 | | | |
| | Fencing | | | |
| | Re-Solve Consulting | | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION NO.8</u> | | | |
| | <u>BILL NO. 4</u> | | | |
| | <u>SEPTIC TANKS, ETC.</u> | | | |
| | For preambles see "Model Preambles for Trades (2017 Edition)" and Supplementary preambles as specified in the Trades | | | |
| | <u>EXISTING SEPTIC TANKS</u> | | | |
| | <u>Inspection and cleaning of existing septic tanks</u> | | | |
| 8/4/1 | Existing septic tank | No | 1 | |
| | <u>SITE CLEARANCE ETC</u> | | | |
| | <u>Site clearance</u> | | | |
| 8/4/2 | Digging up and removing rubbish, debris, vegetation, hedges, shrubs and trees not exceeding 200mm girth, bush, etc | m2 | 33 | |
| | <u>EXCAVATION, FILLING, ETC</u> | | | |
| | <u>Excavation in earth exceeding 2m and not exceeding 4m deep</u> | | | |
| 8/4/3 | Holes | m3 | 88 | |
| | <u>Extra over trench and hole excavations in earth for excavation in</u> | | | |
| 8/4/4 | Soft rock | m3 | 9 | |
| 8/4/5 | Hard rock | m3 | 4 | |
| | Carried Forward | | | R |
| | Section No. 8 Section 8 - External Works Bill No. 4 Septic Tanks, etc. Re-Solve Consulting | | | |

| Brought Forward | | | R |
|--|---|----|------|
| <u>Extra over all excavations for carting away</u> | | | |
| 8/4/6 | Surplus material from excavations on site to a dumping site to be located by the contractor | m3 | 81 |
| <u>Risk of collapse of excavations</u> | | | |
| 8/4/7 | Sides of trench and hole excavations not exceeding 1,5m deep | m2 | 76 |
| <u>Keeping excavations free of water</u> | | | |
| 8/4/8 | Keeping excavations free of all water other than subterranean water | | Item |
| <u>Earth filling obtained from the excavations and /or prescribed stock piles on site including compacted to 93% Mod AASHTO density</u> | | | |
| 8/4/9 | Backfilling to trenches, holes, etc | m3 | 7 |
| <u>Compaction of surfaces</u> | | | |
| 8/4/10 | Ditto but to bottom of trenches and bases | m2 | 22 |
| <u>SOIL POISONING</u> | | | |
| <u>Soil insecticide</u> | | | |
| 8/4/11 | To bottoms and sides of trenches etc | m2 | 22 |
| <u>One layer of 250 micron "Consol Plastic USB Green" waterproof sheeting sealed at laps with "Gunplas Pressure Sensitive Tape"</u> | | | |
| 8/4/12 | Under surface beds | m2 | 22 |
| <u>UNREINFORCED CONCRETE, ETC.</u> | | | |
| <u>15MPa/19mm concrete</u> | | | |
| 8/4/13 | Surface blinding under footings and bases | m3 | 1 |
| <u>REINFORCED CONCRETE</u> | | | |
| Carried Forward | | | R |
| Section No. 8 Section 8 - External Works Bill No. 4 Septic Tanks, etc. Re-Solve Consulting | | | |

| Brought Forward | | | R |
|---|---|------|-----|
| <u>25MPa/19mm concrete</u> | | | |
| 8/4/14 | Bases | m3 | 7 |
| 8/4/15 | Slabs over septic tank | m3 | 4 |
| 8/4/16 | Concrete haunch formed below pipes | m3 | 0.4 |
| <u>TEST CUBES</u> | | | |
| 8/4/17 | Allow for preparing a set of three concrete strength test cubes, each size 150 x 150 x 150mm, sending them to an approved Testing Laboratory for testing and paying all charges in connection therewith | Sets | 4.0 |
| <u>CONCRETE SUNDRIES</u> | | | |
| <u>Finishing top surfaces of concrete smooth with a wood float/steel trowel</u> | | | |
| 8/4/18 | Surface beds, slabs, etc. | m2 | 22 |
| <u>Permanent formwork to soffits</u> | | | |
| 8/4/19 | Slab over septic tank | m2 | 22 |
| <u>SMOOTH FORMWORK (DEGREE OF ACCURACY I)</u> | | | |
| <u>Smooth formwork to sides</u> | | | |
| 8/4/20 | Edges, risers, ends and reveals not exceeding 300mm high or wide | m | 19 |
| <u>Smooth formwork to form</u> | | | |
| 8/4/21 | Opening not exceeding 1m girth through 170mm slab | No | 2 |
| <u>REINFORCEMENT (PROVISIONAL)</u> | | | |
| <u>Fabric Reinforcement</u> | | | |
| 8/4/22 | Mesh ref. No. 888 fabric reinforcement fixed horizontalt in surface beds etc. | m2 | 22 |
| Carried Forward | | | R |
| Section No. 8 Section 8 - External Works Bill No. 4 Septic Tanks, etc. Re-Solve Consulting | | | |

| Brought Forward | | | R |
|---|---|----|-----|
| <u>FOUNDATIONS (PROVISIONAL)</u> | | | |
| <u>Brickwork of NFP bricks in class II mortar</u> | | | |
| 8/4/23 | One brick walls | m2 | 76 |
| <u>BRICKWORK SUNDRIES</u> | | | |
| 8/4/24 | Leave of form 450 x 150mm high opening through a one brick wall | No | 2 |
| 8/4/25 | Leave or form opening through one brickwall for pipe 110mm dia | No | 3 |
| <u>Brickwork reinforcement</u> | | | |
| 8/4/26 | 150mm Wide reinforcement built in horizontally | m | 201 |
| <u>PLASTERING</u> | | | |
| <u>Watertight cement plaster on brickwork</u> | | | |
| 8/4/27 | On walls | m2 | 76 |
| <u>Screed</u> | | | |
| 8/4/28 | On floors | m2 | 22 |
| <u>Two coats approved epoxy coats</u> | | | |
| 8/4/29 | On walls and floors | m2 | 98 |
| <u>PLUMBING AND DRAINAGE</u> | | | |
| <u>uPVC pipes</u> | | | |
| 8/4/30 | 110mm Pipes | m | 45 |
| <u>Extra over uPVC pipes for fittings</u> | | | |
| 8/4/31 | 110mm Tee | No | 2 |
| Carried Forward | | | R |
| Section No. 8 Section 8 - External Works Bill No. 4 Septic Tanks, etc. Re-Solve Consulting | | | |

| Brought Forward | | | R |
|---|--|----|----|
| <u>Cover, etc</u> | | | |
| 8/4/32 | 600 x 600mm Type 2A cast iron single seal manhole cover and frame | No | 4 |
| 8/4/33 | Lifting key for manhole cover | No | 1 |
| <u>FRENCH DRAINS</u> | | | |
| <u>SITE CLEARANCE ETC</u> | | | |
| <u>Site clearance</u> | | | |
| 8/4/34 | Digging up and removing rubbish, debris, vegetation, hedges, shrubs and trees not exceeding 200mm girth, bush, etc | m2 | 20 |
| <u>EXCAVATION, FILLING, ETC</u> | | | |
| <u>Excavation in earth exceeding 2m and not exceeding 4m deep</u> | | | |
| 8/4/35 | Holes | m3 | 16 |
| <u>Extra over trench and hole excavations in earth for excavation in</u> | | | |
| 8/4/36 | Soft rock | m3 | 2 |
| 8/4/37 | Hard rock | m3 | 1 |
| <u>Extra over all excavations for carting away</u> | | | |
| 8/4/38 | Surplus material from excavations on site to a dumping site to be located by the contractor | m3 | 10 |
| <u>Risk of collapse of excavations</u> | | | |
| 8/4/39 | Sides of trench and hole excavations not exceeding 1,5m deep | m2 | 4 |
| Carried Forward | | | R |
| Section No. 8 Section 8 - External Works Bill No. 4 Septic Tanks, etc. Re-Solve Consulting | | | |

| Brought Forward | | | | R |
|-----------------|--|----|------|---|
| | <u>Keeping excavations free of water</u> | | | |
| 8/4/40 | Keeping excavations free of all water other than subterranean water | | Item | |
| | <u>Earth filling obtained from the excavations and /or prescribed stock piles on site including compacted to 93% Mod AASHTO density</u> | | | |
| 8/4/41 | On top of french drain as soil cover | m3 | 7 | |
| | <u>FILTER FABRIC</u> | | | |
| | <u>"Kaytech Engineered Fabric" or similar approved laid in strict accordance to the manufacturer's instructions</u> | | | |
| 8/4/42 | "Kaymat U14" or equal approved around stone filling in sub-soil drain trenches | m2 | 20 | |
| | <u>20mm Graded stone filling or similar approved</u> | | | |
| 8/4/43 | In holes | m3 | 5 | |
| | <u>200 - 300mm Diameter clean washed stone filling or similar approved by engineer</u> | | | |
| 8/4/44 | In holes | m3 | 15 | |
| | <u>WATERPROOFING</u> | | | |
| | <u>One layer of 250 micron "Tarkon USB Green" or equal approved waterproof sheeting sealed at laps with "Gunplas Pressure Sensitive Tape"</u> | | | |
| 8/4/45 | On top of pipes as protection of joints | m2 | 20 | |
| | <u>ROOF SHEETING</u> | | | |
| | <u>Roof sheeting</u> | | | |
| 8/4/46 | On top of french drain | m2 | 20 | |
| | Carried Forward | | | R |
| | Section No. 8 Section 8 - External Works Bill No. 4 Septic Tanks, etc. Re-Solve Consulting | | | |

| Brought Forward | | | R |
|---|--|----|----|
| <u>uPVC pipes</u> | | | |
| 8/4/47 | 110mm pipes laid in and including trenches | m | 15 |
| 8/4/48 | 160mm pipes laid in and including trenches | m | 10 |
| <u>Extra over uPVC pipes for fittings</u> | | | |
| 8/4/49 | 110mm End cap | No | 4 |
| 8/4/50 | 110mm Bend | No | 2 |
| Carried Forward to Summary of Section No. 8 | | | R |
| Section No. 8 Section 8 - External Works Bill No. 4 Septic Tanks, etc. Re-Solve Consulting | | | |

Section No. 8

Section 8 - External Works

SECTION SUMMARY - Section 8 - External Works

| Bill No | | Page No | Amount |
|---------|---|---------|--------|
| 8/1 | Elevated Water Tanks | 158 | |
| 8/2 | Paved Walkways | 160 | |
| 8/3 | Fencing | 161 | |
| 8/4 | Septic Tanks, etc. | 168 | |
| 8/5 | Borehole Refurbishment | 169 | |
| | Carried to Final Summary | | R |
| | Section No. 8 Section 8 - External Works Re-Solve Consulting | | |

| Section No | <u>FINAL SUMMARY</u> | Page No | Amount |
|------------|---|---------|------------|
| 1 | Section 1 - Preliminaries and General | 26 | |
| 2 | Section 2 - Demolitions and Alterations | 28 | |
| 3 | Section 3 - Staff Ablutions Female | 53 | |
| 4 | Section 4 - Staff Ablutions Male | 78 | |
| 5 | Section 5 - Girl Block of 9 | 103 | |
| 6 | Section 6 - Girl Block of 7 | 128 | |
| 7 | Section 7 - Boy Block of 5 | 154 | |
| 8 | Section 8 - External Works | 170 | |
| | SUB TOTAL | | R |
| | <u>ADD: CONTINGENCIES</u> | | |
| | Contingencies | Item | 836 886.00 |
| | SUB TOTAL BEFORE VAT | | R |
| | <u>ADD: VALUE ADDED TAX</u> | | |
| | Value Added Tax (15%) | | R |
| | TENDER SUM CARRIED FORWARD TO FORM OF OFFER AND ACCEPTANCE | | R |
| | Carried to Form of Tender | | R |
| | Re-Solve Consulting | | |