



#### GENERAL NOTES:

- ALL WORK TO BE CARRIED OUT IN ACCORDANCE WITH THE NATIONAL BUILDING REGULATION AND SABS 0400 OF 1990
- CONTRACTOR TO READ ONLY FIGURED DIMENSION
- CONTRACTOR TO VERIFY ALL DIMENSION ON SITE BEFORE COMMENCING WITH ANY WORK.

#### NOTES AND SPECIFICATIONS:

##### GENERAL

- Use dimensions provided and do not scale drawing.
- All work to comply with SANS, PW371 and SABS.
- All dimensions, levels and positions to be verified on site prior to construction.
- All concrete work to be as per Engineer's details and specifications.
- All pits to face North.
- All brickwork have brickforce at every 2nd course in pit lining and 3rd course in superstructure.

##### PIT EXCAVATION

- All stages of pit excavation to be inspected and approved by Engineer and signed off.
- All pit lining to be inspected by EnviroLoo Services before slab casting.

##### COMPACTION OF SURFACES

All ground surfaces receiving concrete floors / slab should be compacted to 150mm layers 93% ModAASHTO density before casting concrete.

##### CONCRETE WORKS

- All concrete to be as per Engineer's details and specifications.
- 25 MPa strength concrete to be used throughout construction:

Trial Concrete Mixes: Proportions

Concrete Strength at 28 Days 25Mpa:

1 : 2 : 2 (mix proportion by volume)

1 bag cement : 0.08m<sup>3</sup> Sand : 0.09m<sup>3</sup> Stone (Volume/Bag)

385 kg cement : 820 kg sand : 960 kg stone (Mass/m<sup>3</sup>)

- Pre-cast concrete lintels to be used as support under top slab of pit.

- All concrete aprons to be 1000mm wide..

##### MORTAR

Mixed proportions to be:

1 cement : 3 sand

(i.e.1 bag cement : 3 wheelbarrows (37 litres) sand)

##### BRICKWORK

Sub-structure

- All pit lining / foundation brickwork to be solid NFP clay brick.
- All internal surface of pit lining to be painted with two coats black epoxy paint installing Enviro-Loo units.

Super-structure

- All external walls / partitions to be of clay face brick to SABS quality.
- All cubicle partition walls to be 3 courses above door height.
- All brickwork above door openings should have brickforce on every course at least 3 courses.
- Air bricks: Standard 230X152mm terra-cotta vermin proofed louvered air grating to be used above all window openings.

##### ROOF SHEETING

- 0.6mm kliplock chromadek roof sheeting.

##### ROOF TIMBER / CEILING

- All roof timbers to be machined SABS treated wood with three coats of approved wood preservative.
- Timber connections (Hurricane Clips) are required all interconnections between timber rafters and purlins.
- Sisalation is to be applied interval under all roof surfaces.

##### METALWORK

- All metalwork should be primed before installation.
- All steel window should have 6x20mm flat bar burglar proofing.

##### PLUMBING

- Double concrete wash trough to be used.
- All wash troughs should be connected to the school's water supply system and the waste water should be piped to a soakaway.
- The soakaway should be as per Engineer's detail and position to be determined on site.
- Only 20mm and galvanised pipework should be used as connection from wall to the discharge points.

##### GLAZING

- 6.28mm obscure safety glass
- Stainless steel mirrors size 350x450mm high.

##### PAINTING

- All paintwork to comply with SABS and PW371 specification.
- All steel window and door frames including doors and fascia / barge boards to be discharge points.

WINDOW SCHEDULE	
WINDOW NO.	N2
CATALOGUE	NE2
FRAME	1222 x 1204mm HIGH STANDARD STEEL WINDOW FRAME
FRAME FINISH	SELF PRIMING INTERIOR IN PRIME-PURSE SURFACED WITH TWO COATS OF WHITE CHROMATE PRIMER & APPLIED COAT UNDER COAT & TWO COATS OF PRIME GOLDEN BROWN GLOSS ENAMEL PAINT IN STEEL
GLAZING	6.28mm OBSCURE SAFETY GLASS
NO. REQUIRED	2

ENTRANCE DOOR	
FRAME TYPE	DOUBLE DESHTE STEEL FRAME TO FIT 2000mm WALL (20)
FRAME FINISH	PRIME AND PRIME UNDERCOAT AND 2ND COAT PRIMER COATS IN GLOSS ENAMEL COLOUR 10C
DOOR LEAF	1200mm FRAMED GLASS AND BRASS DOOR SET 1200x2000mm INCLUDING EXTERNAL WEATHER STOP
LEAF FINISH	BRASS COAT LAM MINIMUM 2 COATS Q105 ENAMEL - COLOUR 10C
LOOK	3 LEVER WORKING LOOK SET
ROMANCERY	1000mm BRASS CHAIN HOOK

WINDOW SCHEDULE	
WINDOW NO.	N1
CATALOGUE	NE1
FRAME	1222 x 1204mm HIGH STANDARD STEEL WINDOW FRAME
FRAME FINISH	SELF PRIMING INTERIOR IN PRIME-PURSE SURFACED WITH TWO COATS OF WHITE CHROMATE PRIMER & APPLIED COAT UNDER COAT & TWO COATS OF PRIME GOLDEN BROWN GLOSS ENAMEL PAINT IN STEEL
GLAZING	6.28mm OBSCURE SAFETY GLASS
NO. REQUIRED	4

DOOR SCHEDULE	
DOOR NO.	DOOR 1
CATALOGUE	DOOR 1
DOOR LEAF	877 x 2000mm HIGH STANDARD STEEL DOOR LEAF
LEAF FINISH	2ND PRIME GOLDEN BROWN HIGH GLOSS ENAMEL PAINT
LOOK	3 LEVER WORKING LOOK SET
NO. REQUIRED	2

#### NOTES:

#### LEGEND:

DATE	NO.	REVISION / VARIATIONS	KUT
08.11.22	1	ISSUED FOR TENDER	BS

#### CLIENT:



#### IMPLEMENTING AGENT:



ROP 6 RHODES DRIFT OFFICE PARK  
RHODES DRIFT STREET  
BENDOR, POLOKWANE  
0699

#### PROJECT ENGINEERS:



2 HEUWELKRUIN  
THABAZIMBI EXT 1  
THABAZIMBI  
0380

Tel No.: 079 978 4501  
Fax No.: 086 674 3237  
E-mail: admin@kutloconsulting.co.za

#### PROJECT:

LIMPOPO DEPARTMENT OF EDUCATION

WATER , SANITATION AND FENCING  
PROGRAMME

#### TITLE:

AQUAVILLE COMBINED SCHOOL  
M2 (MALE TEACHERS)  
1x SEATS , 2x URINALS , 1x DISABLED

DRAWING No.: K1000-AC-009

SCALE:	1 : 75	DESIGNED:	BS
		DRAWN:	KN
DATE:	NOVEMBER 2022	APPROVED:	BS
REV. NO.	1		