

Item No		Quantity	Rate	Amount
	<u>SECTION 1</u>			
	<u>BILL No.1</u>			
	<u>PRELIMINARIES</u>			
	1. The Principal Building Agreement shall be the JBCC Series Edition 4.1, March 2005 as recommended by the Joint Building Contract Committee and as amended by this Tender Enquiry.			
	2. The Preliminaries shall be JBCC Series 2000, May 2005 for use with the Principal Building Agreement as recommended by the Joint Building Contracts Committee and as amended by this Tender Enquiry shall be deemed to be incorporated herein.			
	3. Tenderers are referred to the abovementioned documents for the full intent and meaning of each clause thereof. These clauses are hereinafter referred to by clause number and heading only.			
	4. Where standard clauses or alternatives are not entirely applicable to this contract, such modifications, corrections or additions as are necessary, are given as far as possible under each relevant clause heading. Additional Preliminary clauses are contained in Section C hereof.			
	5. No claim whatsoever shall be entertained in respect of errors or omissions in pricing due to brevity of descriptions of items which are fully described when read in conjunction with the relevant clauses of the said Principal Building Agreement, Preliminaries and Preambles.			
	6. The Tenderers shall allow opposite each of the clauses whatever costs and charges he may consider necessary for the carrying out, complying with and due observance of the provisions, conditions and requirements set out herein. Only priced items will be considered in respect of any adjustment of this Section. Any items left unpriced will be understood to be provided free of charge and no claim for any extras arising out of the Tenderer's omission to price any item will be entertained.			
	Carried to Collection		R	
	Section 1			
	Bill No. 1			
	Preliminaries			

7. Where modifications or amendments as described are made, such modifications and/or amendments shall supercede any conflicting provisions in the relevant clauses of the Standard Preliminaries or the Principal Building Agreement and the Tenderer shall make due allowance for whatever costs and charges he may consider necessary for the carrying out and observance of the provisions of the clauses as modified and/or amended.

8. Where any item is not relevant to this specific contract, such item is marked N/A.

9. If Alternative A as set out in clause B10.3 hereinafter is to be used for the adjustment of the preliminaries, each item priced is to be allocated to one or more of the three categories by insertion of "F","V","T" as the case may be against the price in the "rate" column immediately preceding the "amount" column, where "F" denotes a fixed amount (amount not to be varied), "V" denotes an amount variable in proportion to value, and "T" denotes an amount proportionate to time.

Carried to Collection

R

Section 1
Bill No. 1
Preliminaries

SECTION A: PRINCIPAL BUILDING AGREEMENT

DEFINITIONS

Definitions and interpretation (Clause 1).

1 F: V: T:

Item

OBJECTIVE AND PREPARATION

Offer, acceptance and performance (Clause 2).

2 F: V: T:

Item

Documents (Clause 3).

Clause 3.1 is deleted and substituted with: 'This tender is for a Government Contract. No Payment Guarantee will be provided.'

Clause 3.3 is deleted and substituted with:

The principal agent shall complete the schedule and arrange for formal signing of the agreement once the priced bill of quantities/lump sum document, security, insurances and waiver of lien, where acceptable, have been provided and effected'.

3 F: V: T:

Item

Design responsibility (Clause 4).

4 F: V: T:

Item

Employer's agents (Clause 5).

5 F: V: T:

Item

Site representative (Clause 6).

6 F: V: T:

Item

Compliance with regulations (Clause 7).

7 F: V: T:

Item

Carried to Collection

R

Section 1
Bill No. 1
Preliminaries

	Works risk (Clause 8)			
8	F: V: T: Indemnities (Clause 9). Clause 9.1.1 is deleted and substituted with: Claims from other parties consequent upon death of bodily injury or illness of any person or physical loss or damage to any property, other than the works, arising out or due to the execution of the works or occupation of the site by the contractor or his sub contractors'.	Item		
9	F: V: T: Works insurances (Clause 10).	Item		
10	F: V: T: Liability insurances (Clause 11).	Item		
11	F: V: T: Effecting insurances (Clause 12).	Item		
12	F: V: T: State Provisions (Clause 13).	Item		
13	F: V: T: Security (Clause 14).	Item		
14	F: V: T: <u>EXECUTION</u> Preparation for and execution of the works (Clause 15).	Item		
15	F: V: T: Access to the works (Clause 16).	Item		
16	F: V: T: Contract instructions (Clause 17).	Item		
Section 1 Bill No. 1 Preliminaries		Carried to Collection		R

17	F: V: T: Setting out of the works (Clause 18.3). The contractor shall notify the principal agent if any encroachments of adjoining foundations, buildings, structures, pavements, boundaries, etc., exist in order that the necessary arrangements may be made for the rectification of any such encroachments. Should incorrect information be given to the contractor in terms of 18.1 and 18.2, which causes the incorrect setting out of the works, the contractor shall not be liable for such incorrect setting out.	Item		
18	F: V: T: Assignment (Clause 19).	Item		
19	F: V: T: Nominated subcontractors (Clause 20).	Item		
20	F: V: T: Selected subcontractors (Clause 21).	Item		
21	F: V: T: Employer's Direct contractors (Clause 22).	Item		
22	F: V: T: Contractor's Domestic subcontractors (Clause 23).	Item		
23	F: V: T: <u>COMPLETION</u> Practical completion (Clause 24).	Item		
24	F: V: T: Works completion (Clause 25).	Item		
25	F: V: T: Final completion (Clause 26).	Item		
Carried to Collection			R	
Section 1 Bill No. 1 Preliminaries				

Latent defects liability period (Clause 27).

Clause 27.0 is amended by the addition of the following clauses:

"27.3 Any water leakage into the building, whether in the roof, external wall or other element of the building susceptible to water leakage shall, unless proven to be a design defect, or as a result of obvious storm damage, be classified as a latent defect in terms of clause 1.0 Definitions and Interpretations".

"27.4 The Contractor shall attend to defects during the Defects Liability Period on a progressive basis, to the satisfaction of the Principal Agent and will not be permitted to wait until the end of the Defect Liability Period or until the amount of defects accumulates in order to attend to a comprehensive list of defects"

26 F: V: T:

Item

Sectional completion (Clause 28).

27 F: V: T:

Item

Revision of date for practical completion (Clause 29).

28 F: V: T:

Item

Penalty for non-completion (Clause 30).

29 F: V: T:

Item

PAYMENT

Interim payment to the contractor (Clause 31).

The inclusion of materials and goods stored off site in the amount authorised for payment in terms of clause 31.3 shall be at the sole discretion of the principal agent and such inclusion shall only be considered upon the provision, by the contractor, of an approved guarantee issued by a registered commercial bank.

Carried to Collection

R

Section 1
Bill No. 1
Preliminaries

Where prices are submitted by the contractor or nominated/selected sub contractor during the progress of the works in respect of contract instructions or in regard to a claim under the terms of the contract and notwithstanding the fact that such prices may be used in an interim payment certificate, there is to be no presumption of acceptance. Should the principal agent wish to accept any such prices prior to the issue of the final certificate, it will be in writing.

Adjustment to the contract value (Clause 32).

30 F: V: T:

Item

Recovery of expense and loss (Clause 33).

31 F: V: T:

Item

Final account and final payment (Clause 34).

32 F: V: T:

Item

Payment to other parties (Clause 35).

33 F: V: T:

Item

CANCELLATION

Cancellation by Employer - Contractor's default (Clause 36).

34 F: V: T:

Item

Cancellation by Employer - Loss and damage (Clause 37).

35 F: V: T:

Item

Cancellation by Contractor - Employer's default (Clause 38).

36 F: V: T:

Item

Cancellation - Cessation of the works (Clause 39).

37 F: V: T:

Item

Carried to Collection

R

Section 1
Bill No. 1
Preliminaries

DISPUTE

Dispute Settlement (Clause 40)

38 F: V: T:

Item

SUBSTITUTE PROVISIONS

State Clauses (Clause 41)

39 F: V: T:

Item

CONTRACT VARIABLES

The Schedule: Pre-Tender information (Clause 42).

40 F: V: T:

Item

CONTRACTING AND OTHER PARTIES (Clause 42.1)

Employer: The Mvula Trust

Postal Address: 67 Devereux Avenue, Vincent, East London

Telephone: 043 726 2255

Facsimile: 043 726 5967

Physical address: 67 Devereux Avenue, Vincent, East London

Principal Agent: The Mvula Trust

Postal Address: 67 Devereux Avenue, Vincent, East London

Telephone: 043 726 2255

Facsimile: 043 726 5967

Physical address: 67 Devereux Avenue, Vincent, East London

Carried to Collection

R

Section 1
Bill No. 1
Preliminaries

CONTRACT DETAILS (Clause 42.2)

Clause 42.2.1

Works Description: Construction of new ablution facilities.

Clause 42.2.2

Site Description: The site is the existing school.

Clause 42.2.3

Work or Installations by Others: NIL

Clause 42.2.4

This Agreement is for a State Contract :- Yes

Payment will be made for materials and goods:- Yes

Dispute resolution :- Mediation (in terms of clause 40) followed by litigation.

Arbitration rules as recommended by the Association of Arbitrators (SA) :- N/A

Clause 42.2.5

Date on which possession of the site is intended to be given on :-

To be advised.

Clause 42.2.6

Period for the commencement of the works after the contractor takes possession of the site :- 5 Working days.

Completion in Sections are required : NO

Clause 42.2.7

Intended date of practical completion and the penalty per calendar day for the works as a whole :-

To be advised.

Carried to Collection

Section 1
Bill No. 1
Preliminaries

R

Penalty amount will be R 2000.00 per day.

Clause 42.2.8

Intended dates of practical completion and the penalties per calendar day for the works in sections :

N/A

Clause 42.2.9

The law applicable to this agreement shall be that of -
Republic of South Africa.

INSURANCES (Clause 42.3)

Clause 42.3.1

Contract works insurance to be effected by Contractor for the sum of: Contract Sum Plus 10%.

With a deductible of : Not exceeding 5% of each and every claim.

Clause 42.3.2

Supplementary insurance is required : Yes

SASRIA insurance required to be effected by the Contractor for the amount of: Contract Sum plus 20% (with a deductible to be determined by the Insurance company issuing the policy).

Clause 42.3.3

Public liability insurance to be effected by Contractor

For the amount of: R 5million

With a deductible of: Not exceeding 5% of each and every claim.

DOCUMENTS (Clause 42.4)

Clause 42.4.1

Waiver of the contractor's lien is required :- YES

Carried to Collection

Section 1
Bill No. 1
Preliminaries

R

	Clause 42.4.2 Number of construction document copies to be supplied to the Contractor free of charge :- 1		
	 Clause 42.4.3 Bills of Quantities drawn up in accordance with :- Standard System of Measuring Building Work - Seventh Edition including all amendments		
	 Clause 42.4.4 Number of days for submission of priced documents : 5 working days from the Letter of Appointment.		
	 Clause 42.4.5 JBCC Engineering General Conditions are to be included in the documents :- No		
	 Clause 42.4.6 The contract value is to be adjusted using CPAP:- NO		
	<u>SECTION B: PRELIMINARIES</u>		
	<u>DEFINITIONS AND INTERPRETATION (B1)</u>		
	Definitions and Interpretation (B1) F: V: T:	Item	
	<u>DOCUMENTS (B2)</u>		
	Checking of documents (B2.1) Notwithstanding the issue of the tender drawings, it will remain the responsibility of the Tenderer to study all available drawings at the offices of the Principal Agent during normal working hours in order to acquaint himself with all the cost implications of the design, programming, phasing, etc. F: V: T:	Item	
	 Provisional Bills of Quantities (B2.2) YES		
	Carried to Collection	R	
	Section 1 Bill No. 1 Preliminaries		

	Prime Cost Amounts, Budgetary Allowances, Provisional Amounts, etc., contained herein may be omitted or reduced at the Principal Agent's sole discretion and the Contractor shall not be entitled to claim for any loss by way of reduction or omission of any discount, or percentage relating to Prime Cost Amounts, Budgetary Allowances, Provisional Amounts, Provisional Quantities, etc., or loss of profit related thereto.			
43	F: V: T: Availability of construction documentation (B2.3)	Item		
44	F: V: T: Interests of Agents (B2.4)	Item		
45	F: V: T: Priced documents (B2.5)	Item		
46	F: V: T: Tender submission (B2.6)	Item		
	Notwithstanding anything contained in this clause, Tenders shall be valid for a period of 20 (Twenty) weeks from the closing date of tenders.			
47	F: V: T: <u>THE SITE (B3)</u> Defined works area (B3.1) The area of the works to be occupied by the contractor, any restriction on the area and the limit of access or exit will be pointed out to the contractor by the principal agent on handing over of the site. Workmen employed on the site are to be restricted to the immediate area of the site and access thereto. The Tenderer shall make all necessary provision in all rates to take into account these requirements as no claims for extras arising from these matters will be subsequently entertained or admitted.	Item		
48	F: V: T:	Item		
	Carried to Collection		R	
	Section 1 Bill No. 1 Preliminaries			

	Geotechnical investigation (B3.2)			
	A desktop geotechnical report is available upon request.			
49	F: V: T:	Item		
	Inspection of the Site (B3.3)			
50	F: V: T:	Item		
	Existing premises occupied (B3.4)			
51	F: V: T:	Item		
	Previous work - dimensional accuracy (B3.5)			
52	F: V: T:	Item		
	Previous work - defects (B3.6)			
53	F: V: T:	Item		
	Services - known (B3.7)			
54	F: V: T:	Item		
	Services - unknown (B3.8)			
55	F: V: T:	Item		
	Protection of trees (B3.9)			
56	F: V: T:	Item		
	Articles of value (B3.10)			
57	F: V: T:	Item		
	Inspection of adjoining properties (B3.11)			
58	F: V: T:	Item		
	<u>MANAGEMENT OF CONTRACT (B4)</u>			
	Management of the Works (B4.1)			
59	F: V: T:	Item		
	Carried to Collection		R	
	Section 1 Bill No. 1 Preliminaries			

	Programme for the Works (B4.2)			
60	F: V: T:	Item		
	Progress meetings (B4.3)			
61	F: V: T:	Item		
	Technical meetings (B4.4)			
62	F: V: T:	Item		
	SAMPLES AND SHOP DRAWINGS (B5)			
	Samples of materials (B5.1)			
63	F: V: T:	Item		
	Workmanship samples (B5.2)			
64	F: V: T:	Item		
	Shop drawings (B5.3)			
65	F: V: T:	Item		
	TEMPORARY WORKS AND PLANT (B6)			
	Deposits and fees (B6.1)			
66	F: V: T:	Item		
	Enclosure of the works (B6.2)			
	The contractor shall erect, maintain and remove at completion, hoardings, safety screens, barriers, access gates, covered gangways and the like as necessary for the enclosure of the works and elements thereof all for the protection of the public and others.			
67	F: V: T:	Item		
	Advertising (B6.3)			
68	F: V: T:	Item		
	Carried to Collection		R	
	Section 1 Bill No. 1 Preliminaries			

	Plant and equipment (B6.4)			
69	F: V: T: Main notice board (B6.5) One notice board shall be provided by the Contractor	Item		
70	F: V: T: Subcontractors notice board (B6.6) (N/A)	Item		
71	F: V: T: <u>TEMPORARY SERVICES (B7)</u> Location (B7.1)			
72	F: V: T: Water (B7.2) The contractor shall provide water for the works in accordance with: Alternative A (i.e. to be provided for by the Contractor).	Item		
73	F: V: T: Electricity (B7.3) The contractor shall provide electricity for the works in accordance with: Alternative A (i.e. to be provided for by the Contractor).	Item		
74	F: V: T: Telecommunication equipment (B7.4) The contractor shall provide telephones on site for the works in accordance with: Alternative A (i.e. to be provided for by the Contractor).	Item		
75	F: V: T:	Item		
	Carried to Collection		R	
	Section 1 Bill No. 1 Preliminaries			

	Ablution facilities (B7.5)			
	The contractor shall provide toilet facilities on site for the works in accordance with:			
	Alternative A (i.e. to be provided for by the Contractor).			
76	F: V: T:	Item		
	<u>PRIME COST AMOUNTS (B8)</u>			
	Responsibility for prime cost amounts (B8.1)			
77	F: V: T:	Item		
	<u>ATTENDANCE ON N/S SUBCONTRACTORS (B9)</u>			
	General Attendance (B9.1)			
78	F: V: T:	Item		
	Special Attendance (B9.2)			
79	F: V: T:	Item		
	Commissioning - fuel, water and power (B9.3)			
80	F: V: T:	Item		
	<u>FINANCIAL ASPECTS (B10)</u>			
	Statutory taxes, duties and levies (B10.1)			
	Provision is made in the Final Summary of these Bills of Quantities for the inclusion of Value Added Tax (VAT).			
81	F: V: T:	Item		
	Payment of Preliminaries (B10.2)			
82	F: V: T:	Item		
	Adjustment of Preliminaries (B10.3)			
83	F: V: T:	Item		
	Payment certificate cash flow (B10.4)			
	Carried to Collection		R	
	Section 1			
	Bill No. 1			
	Preliminaries			

84	F: V: T: Contractor information supply (B10.5)	Item		
85	F: V: T: <u>GENERAL (B11)</u> Protection of the Works (B11.1)	Item		
86	F: V: T: Protection/isolation of existing/sectionally occupied works (B11.2)	Item		
87	F: V: T: Site security (B11.3)	Item		
88	F: V: T: Notice before covering work (B11.4)	Item		
89	F: V: T: Disturbance (B11.5)	Item		
90	F: V: T: Works cleaning and clearing (B11.6)	Item		
91	F: V: T: Vermin (B11.7)	Item		
92	F: V: T: Overhand work (B11.8)	Item		
93	F: V: T:	Item		
Carried to Collection			R	
Section 1 Bill No. 1 Preliminaries				

SECTION C: SPECIFIC PRELIMINARIES

Section C: Specific Preliminaries:

C1. Proprietary branded products

The contractor shall take delivery of, handle, store, use, apply and/or fix all proprietary branded products in strict accordance with the manufacturer's instructions after consultation with the manufacturer's authorised representative.

94 F: V: T:

Item

C2. Trade Names, etc.

All materials, fittings, finishings, etc., specified hereinafter under a trade name, catalogue number or reference, must be exactly as described. The Architect's approval in writing must be obtained for the use of any alternative to the specification before the submission of tenders otherwise the specified materials, fittings, finishings, etc., will be assumed to have been allowed for in the tender.

The Contractor must take delivery of, handle, store, use, apply and/or fix all proprietary branded products in strict accordance with the manufacturer's instructions after consultation with the manufacturer's authorised representative.

95 F: V: T:

Item

C3. Contractors responsibility

The Employer, the Principal Agent and the other professional consultants shall not be responsible for any act or omission on the part of the Contractor which may result in any patent or latent defects, in materials or workmanship, breach or neglect of any local regulations. The Contractor shall at all times be responsible for any such neglect, deviation or wrong act, whether the same is discovered before or after the final certificate, or any other Certificate, has been approved.

96 F: V: T:

Item

C4. Overtime

Carried to Collection

R

Section 1
Bill No. 1
Preliminaries

	Should overtime be required to be worked for any reason whatsoever, the costs of such overtime are to be borne by the contractor unless the principal agent has specifically authorised in writing, prior to the execution thereof, that costs for such overtime are to be borne by the employer.		
97	F: V: T: C5. As built drawings The position of construction breaks and the extent of individual concrete pours are to be recorded by the contractor on the structural engineer's drawings and are to be submitted to the principal agent and the structural engineer for their records. Three full sets of as-built drawings shall be submitted to the Principal Agent no later than fourteen days after practical completion.	Item	
98	F: V: T: C6. Construction Instructions Contract instructions issued on site are to be recorded in triplicate in a site instruction book which is to be maintained on site by the Contractor. The Contractor shall supply and have available at the site of the works at all times, the following site books: a) Construction Instruction Book: Receiving and recording instructions in a suitable A4 size triplicate book kept on site. Instructions issued shall be recorded by the Architect or other Employer's Agents to whom the Architect has delegated authority to in the book. Only instructions issued in such book shall be recognised. b) Daily Record Book:	Item	
	Carried to Collection		R
	Section 1 Bill No. 1 Preliminaries		

	The Contractor shall record in triplicate in a suitable A4 size triplicate book kept at the site, a daily record of work done, all site visits by the Principal Agent and other professional personnel and all events affecting the Works, such as progress, issue of plans, breakdown of machinery, etc. The labour, plant and material on site shall be recorded as well as work performed. Entries must be made by the Contractor and must be signed and forwarded to the Principal Agent for his counter-signature on a daily basis. Copies of these records shall be for the Architect, Quantity Surveyor and Contractor.			
99	F: V: T: C7. Labour record At the end of each week the contractor shall provide the principal agent with a written record, in schedule form, reflecting the number and description of tradesmen and labourers employed by him and all subcontractors on the works each day.	Item		
100	F: V: T: C8. Plant record At the end of each week the contractor shall provide the principal agent with a written record, in schedule form, reflecting the number, type and capacity of all plant, excluding hand tools, currently used on the works.	Item		
101	F: V: T: C9. Encroachment During the course of the building operations, the Contractor shall be held entirely responsible for any encroachment onto any adjoining properties, buildings, etc., or servitudes and the cost of any remedial measures as required by the Principal Agent shall be borne by the Contractor.	Item		
102	F: V: T: C10. Method Statement	Item		
Carried to Collection			R	
Section 1				
Bill No. 1				
Preliminaries				

	The Tenderer shall produce, when required to do so by the Principal Agent, a Method Statement outlining the methods of construction and labour and plant resources that he proposes to use in the execution of the Works. Any approval given or observation made by the Principal Agent shall not relieve the Contractor of his sole responsibility to adopt the methods of construction and to provide the labour and plant resources necessary for the due and proper timeous execution of the Works.			
103	F: V: T: C11. Unauthorised Persons/Workmen on Premises The Contractor shall at all times strictly exclude all unauthorised persons from the Works and the site and shall set up notice boards to that effect. No workmen or labourers (except security guards) are to be allowed under any circumstances to sleep or deposit any kit on the premises. The Contractor must provide any necessary independent shelter or shed required for any labour or watchmen on site, to the approval of the Employer.	Item		
104	F: V: T: C12. Mode of Procedure Notwithstanding anything to the contrary contained herein the Principal Agent at all times reserves the right to direct the order in which the various parts of the Contract are to be executed. The Contractor shall give priority to any individual section or portion of the Works that, in the opinion of the Principal Agent, requires to be expedited. Should it appear, in the Principal Agent's opinion, that work in any area is not being executed in accordance with the requirements of the Contract Programme, the Contractor shall provide additional manpower and resources and shall work additional overtime and do everything else required to bring the work back to programme to the satisfaction of the Principal Agent and to the Contractor's cost.	Item		
105	F: V: T:	Item		
Carried to Collection			R	
Section 1				
Bill No. 1				
Preliminaries				

	C13. Location of Temporary Buildings and Temporary Services The Contractor shall provide all necessary temporary works, including temporary roads, tracks, crossings, hardstanding and services, hoardings, dust screens, tunnelling, etc., required for his own and sub-contractors use during the construction and maintenance period. There is no guarantee given or implied that Site conditions will be such that the Contractor will be able to erect such temporary works, roads, hardhats, offices, stores and temporary accommodation within the site boundaries and it shall be the Contractor's responsibility to adopt whatever measures he deems necessary in this regard and to obtain all necessary permission and pay all costs in connection therewith.			
106	F: V: T: <u>C14. Office accommodation</u> The contractor shall provide, maintain and remove on practical completion air conditioned office accommodation with suitable tables and chairs for meetings to be held on the site. Such offices shall be kept clean and fit for use at all times [12.2.18]	Item		
107	F: V: T: <u>C15. Storage Facilities</u>	Item		
108	The Contractor shall provide a Container for storage of materials.	Item		
109	F: V: T: C16. Removal and Making Good of Temporary Works, etc, on Completion The Contractor shall remove (except where specifically stated otherwise) all temporary works, roads, services and the like used for this contract and shall make good to the entire satisfaction of the Principal Agent any damage resulting therefrom.	Item		
110	F: V: T:	Item		
Carried to Collection			R	
Section 1				
Bill No. 1				
Preliminaries				

111	SUB - TOTAL: FIXED ITEMS	Item		
112	SUB - TOTAL: VALUE - RELATED ITEMS	Item		
113	SUB - TOTAL: TIME - RELATED ITEMS	Item		
Carried to Collection			R	
Section 1				
Bill No. 1				
Preliminaries				

Section 1

Bill No. 1

Preliminaries

COLLECTION

Total Brought Forward from Page No.

**Page
No**

Amount

1

2

3

4

5

6

7

8

9

10

11

12

13

14

15

16

17

18

19

20

21

Carried Forward

R

Section 1

Bill No. 1

Preliminaries

Section 1

Bill No. 1

Preliminaries

COLLECTION

Brought Forward

Total Brought Forward from Page No.

Page
No

22

23

Amount

R

Carried Forward to Summary of Section No. 1

R

Section 1

Bill No. 1

Preliminaries

Carried to Collection

R

OCCUPATIONAL HEALTH AND SAFETY

General:

1	Preparation of Contractor's site specific Health and Safety Plan.		Item
2	Submission of the Health and Safety File.		Item
3	Principal Contractor's initial obligations in respect of the OHS Act and Construction Regulations.		Item
4	Principal Contractor's time related obligations in respect of the OHS Act and Construction Regulations for the entire construction period.		Item
5	Provision of full time Health and Safety Officer for the entire construction period.		Item
6	Induction training of personnel.	No	22
7	Provision of first aid boxes.	No	2
8	SANS approved weld mesh type temporary barrier fencing 1,8m high covered with a net fixed to and including 100mm diameter gum poles set securely min 300mm deep in ground at max 3m spacing including excavation, backfilling, etc	m	250
9	Extra over mesh fence for pedestrian gate size 1.8 x 1,8m high.	No	3

Provision for Personal Protective Equipment and Protective Clothing:

10	Reflective vests.	No	45
11	Hard hats.	No	25
12	Protective foot wear.	No	25
13	Ear Plugs.	No	3 840
14	Dust Masks.	No	3 840

Costs of Medical Certificates and Medical Surveillance:

15	Initial (baseline) medical examinations. All personnel	No	1
----	--	----	---

Carried to Collection

R

Section 1
Bill No. 2
Health and Safety

MASIJONGANE JUNIOR PRIMARY SCHOOL
THE MVULA TRUST SAFE PROGRAMME

[illegible]

Section 1
Bill No. 2
Health and Safety

COLLECTION

Total Brought Forward from Page No.

Page No	Amount
------------	--------

26	
27	
28	

Carried Forward to Summary of Section No. 1
Section 1
Bill No. 2
Health and Safety

R

Section 1

SECTION SUMMARY - PRELIMINARIES

Bill
No

Preliminaries
Health and Safety

Page
No

25
29

Amount

Carried to Final Summary

R

Section 1

Carried to Collection

Section 2
Bill No. 1
Demolitions

Removal of asbestos material

All preparatory work, alterations, etc., to existing asbestos cement roof sheeting, gutters, rainwater pipes, etc., is to be carried out strictly by an approved and certified specialist company and in accordance with statutory requirements (Occupational Health and Safety Act, 1993 - Asbestos Regulations 2001) and all necessary precautions must be taken when working with and disposing of asbestos cement products and the disposal of waste water resulting from cleaning operations, etc.

The following shall apply in respect of asbestos removal

The removal of asbestos shall be carried out by a certified entity, registered in accordance with the Occupational Health and Safety Act, 1993 and the Asbestos Regulations 2001

Asbestos in all forms/building elements that is to be removed, shall be carried out in strict accordance with aforementioned regulation and a certificate issued by the entity as contemplated in the above, shall be provided per block for the removal thereof, where the term block shall in this context refer to any single, free standing building structure, regardless of size or purpose

Corresponding disposal certificates shall be issued by the facility at which the asbestos is disposed off, with said facility to, prior to the disposal of any asbestos material provide satisfactory proof that the facility is duly registered and fully compliant in terms of the act, to receive the asbestos material

Under no circumstances is the Contractor nor any of his duly authorised representatives to sell and/or give away asbestos material to any member/s of the school community, the community in general or the public at large. Should this be found to be occurring, the Contractor will be held responsible contractually and may further be prosecuted criminally

The cost for complying with the above, and all requirements of regulation as reflected above is to be priced for in terms for removal of asbestos material. No further claims in this regard will therefore be entertained

Carried to Collection

R

Section 2
Bill No. 1
Demolitions

DEMOLISHING AND REMOVING

1	Demolish pit latrine structure comprising of brick/block work with asbestos roof sheeting, approximate size 6 x 3m wide with 3,5m high top structure and 2,0m deep pit. Demolition is to only commence once the latrine has been completely emptied (elsewhere measured).	No	1
2	Cart away rubble from demolitions and dispose off site.		Item
3	Backfill existing hole with G7 fill material in max. 150mm layers and compact to 95% MOD AASHTO density.	m3	12
4	Allow for compaction tests by an approved laboratory to determine density of filling material.	No	2
5	Provision of a certificate of safe disposal for asbestos.		Item

SUNDRIES

Desludging

6	Clean out pit latrine by desludging including removal of all debris and waste including solid waste as per Health and Safety requirements and make good on completion including disposing of all debris and waste at an authorised municipal waste disposal facility. Contractor to price per seat, all the holes. The whole existing toilets	No	1
7	Issue of Certificate of Waste Disposal.		Item

Carried to Collection

R

Section 2
Bill No. 1
Demolitions

Section 2

Bill No. 1

Demolitions

COLLECTION

Total Brought Forward from Page No.

Page
No
Amount

31

32

33

Carried to Final Summary

R

Section 2
Bill No. 1
Demolitions

Item No		Quantity	Rate	Amount
	<u>SECTION 3</u> <u>BILL No. 1</u> <u>EARTHWORKS (PROVISIONAL)</u> <u>Quantity Split:</u> Note that the total quantity per each item is split into the various buildings and appears below each description as follows: A0 - DWG 14 Male Ablutions A1 - DWG 35 - Female Ablutions A6 - DWG 06 - Grade R Ablutions AD - DWG 04 - Staff Ablutions <u>MODEL PREAMBLES</u> The tenderer is referred to the "General Preambles for Trades 2017" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates. <u>SUPPLEMENTARY PREAMBLES</u> <u>Proprietary products in descriptions:</u> Proprietary products shall be used as specified. Substitute products of similar quality and specification may only be used with prior approval by the Principal Agent. <u>Nature of material to be excavated:</u> The material to be excavated is assumed to be predominantly of a composition that will allow excavation in "earth" as specified, but including a percentage of excavation in "soft rock" and "hard rock". <u>Carting away of excavated material:</u> Descriptions of carting away of excavated material shall be deemed to include loading excavated material onto trucks directly from the excavations, or alternatively, from stock piles situated on the building site.			
	Carried to Collection		R	
	Section 3			
	Bill No. 1			
	Earthworks (Provisional)			

Dewatering of excavations:

The Contractor shall allow for removing seepage and other water from subterranean sources from the excavations by pumping, baling or otherwise. Accurate records of all such dewatering shall be kept to determine the total volume of water so removed and a clear distinction shall be made between water from subterranean sources and other water

Density testing on filling:

Rates for filling, etc. shall include for all density and soil type testing to prove that the specified compaction is achieved. When additional testing is done on instruction of the Principal Agent and these tests are successful, they will be paid for additionally.

Imported fill:

"Filling and bedding to trenches etc. to be in compliance with SABS 1200 DB and LB respectively"

Classification of excavated material

"Hard rock" shall mean granite, quartzitic sandstone or other rock of similar hardness, the removal of which requires drilling, wedging and splitting or the use of explosives.

"Soft rock" shall mean hard material, the removal of which warrants the use of pneumatic tools and includes hard shale, ferricite, compact oukclip and material of similar hardness.

"Earth" shall mean all ground other than that classified as "hard rock" or "soft rock" and shall include made-up ground and any loose stones or pieces of concrete not exceeding 0,03m³ in volume.

Carried to Collection

R

Section 3
Bill No. 1
Earthworks (Provisional)

EXCAVATION OTHER THAN BULK

Excavation in earth not exceeding 2m deep:

1	Trenches. A0 : 5 A1 : 6 A6 : 5 AD : 6	m3	23
2	Reducing levels and depositing excavated material in prescribed stock piles on site. A0 : 9 A1 : 12 A6 : 10 AD : 12	m3	43

Extra over trench and hole excavations in earth for excavation in:

3	Soft rock. A0 : 2 A1 : 2 A6 : 6 AD : 2	m3	12
4	Hard rock. A0 : 1 A1 : 1 A6 : 3 AD : 1	m3	6

Extra over all excavations for carting away:

5	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the contractor. A0 : 14 A1 : 18 A6 : 15 AD : 19	m3	66
---	---	----	----

Risk of collapse of excavations:

6	Sides of trench and hole excavations not exceeding 1,5m deep. A0 : 25 A1 : 29 A6 : 26 AD : 30	m2	110
---	---	----	-----

Keeping excavations free of water:

7	Keeping excavations free from mud and all water including subterranean sources.	Item	
---	---	------	--

Carried to Collection

R

Section 3
Bill No. 1
Earthworks (Provisional)

EARTH FILLING, ETC.

Earth filling obtained from the excavations and / or prescribed stock piles on site (minimum G7 tested material) compacted to 93% Mod. AASHTO density:

8	Under floors, etc.	m3	16	
	A0 : 3 A1 : 5 A6 : 4 AD : 5			

Imported G5 filling, selected and supplied by the Contractor, including depositing in layers not exceeding 150mm thick and compacting to 98% modified AASHTO dry density to trenches, holes, etc.

9	Under floors, etc.	m3	16	
	A0 : 3 A1 : 5 A6 : 4 AD : 5			

Imported G7 filling, selected and supplied by the Contractor, including depositing in layers not exceeding 150mm thick and compacting to 98% modified AASHTO dry density to holes, trenches etc.

10	Under floors, etc.	m3	48	
	A0 : 10 A1 : 14 A6 : 11 AD : 14			

Coarse river sand filling supplied by the contractor:

11	Under floors etc.	m3	6	
	A0 : 1 A1 : 2 A6 : 2 AD : 2			

Compaction of surfaces:

12	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density.	m2	107	
	A0 : 22 A1 : 30 A6 : 24 AD : 31			

Prescribed density tests on filling:

13	Allow for compaction tests by an approved laboratory to determine density of filling material.	No	35	
	A0 : 8 A1 : 8 A6 : 8 AD : 11			

SOIL POISONING

Carried to Collection

R

Section 3
Bill No. 1
Earthworks (Provisional)

Approved brand of anti-termite soil poison applied
by a Registered Pest Control company and
guaranteed against termite infestation for ten years:

14 Under floors, etc., including forming and poisoning
shallow furrows against foundation walls, etc., filling in
furrows and ramming.

A0 : 22 A1 : 30 A6 : 24 AD : 31

m2

107

Carried to Collection

R

Section 3
Bill No. 1
Earthworks (Provisional)

Section 3

Bill No. 1

Earthworks (Provisional)

COLLECTION

Total Brought Forward from Page No.

Page
No

Amount

35

36

37

38

39

Carried Forward to Summary of Section No. 3

R

Section 3

Bill No. 1

Earthworks (Provisional)

Carried to Collection

Section 3
Bill No. 2
Concrete, Formwork and Reinforcement

Formwork:

Descriptions of formwork shall be deemed to include use and waste only (except where described as left in or permanent), for fitting together in the required forms, wedging, plumbing and fixing to true angles and surfaces as necessary to ensure easy release during stripping and for reconditioning as necessary before re-use.

The vertical strutting shall be carried down to such construction as is sufficiently strong to afford the required support without damage and shall remain in position until the newly constructed work is able to support itself.

Formwork to soffits of solid slabs etc., shall be deemed to be to slabs not exceeding 250mm thick unless otherwise described.

Formwork to sides of bases, pile caps, ground beams, etc., will only be measured where it is prescribed by the Engineer for design reasons. Formwork necessitated by irregularity or collapse of excavated faces will not be measured and the cost thereof shall be deemed to be included in the allowance for taking the risk of collapse of the sides of the excavations, provision for which is made in Earthworks.

Carried to Collection

Section 3
Bill No. 2
Concrete, Formwork and Reinforcement

R

**UNREINFORCED CONCRETE CAST AGAINST
EXCAVATED SURFACES**

15Mpa/19mm Concrete

- | | | | |
|---|--|----|---|
| 1 | Surface blinding under footings and bases. | m3 | 5 |
| | A0 : 1 A1 : 2 A6 : 1 AD : 2 | | |

**REINFORCED CONCRETE CAST AGAINST
EXCAVATED SURFACES**

30MPa/20mm concrete:

- | | | | |
|---|--|----|----|
| 2 | Concrete raft slab on waterproofing. | m3 | 30 |
| | A0 : 7 A1 : 8 A6 : 7 AD : 8 | | |

TEST BLOCKS

Test blocks:

- | | | | |
|---|---|----|----|
| 3 | Making and testing of 150x150x150mm concrete strength test cubes (Provisional). | No | 24 |
| | A0 : 6 A1 : 6 A6 : 6 AD : 6 | | |

FINISHING TOP SURFACE OF CONCRETE

Finishing top surfaces of concrete smooth with a wood float:

- | | | | |
|---|---|----|-----|
| 4 | Surface beds, suspended slabs, ground slabs, etc. | m2 | 107 |
| | A0 : 22 A1 : 30 A6 : 24 AD : 31 | | |

ROUGH FORMWORK (DEGREE OF ACCURACY III)

Rough Formwork to Sides:

- | | | | |
|---|---|---|----|
| 5 | Edges, risers, ends and reveals not exceeding 300mm high or wide. | m | 90 |
| | A0 : 24 A1 : 20 A6 : 21 AD : 25 | | |

Carried to Collection

Section 3
Bill No. 2
Concrete, Formwork and Reinforcement

R

SMOOTH FORMWORK (DEGREE OF ACCURACY I)

Smooth Formwork to Sides:

6	Edges, risers, ends and reveals not exceeding 300mm high or wide.	m2	45		
	A0 : 12 A1 : 10 A6 : 11 AD : 12				

MOVEMENT JOINTS ETC

Two layers of 375 micron damp proof course in slip joints between horizontal concrete and brick surfaces including cement mortar bed (Provisional)

7	Not exceeding 300mm wide.	m	134		
	A0 : 27 A1 : 36 A6 : 31 AD : 40				

Saw cut joints:

8	6 x 40mm Saw cut joints in top of concrete (Provisional).	m	81		
	A0 : 20 A1 : 20 A6 : 20 AD : 20				

REINFORCEMENT (PROVISIONAL)

9	High tensile steel reinforcement bars to structural concrete work.	t	2.95		
	A0 : 0.65 A1 : 0.80 A6 : 0.69 AD : 0.81				

Fabric reinforcement:

10	REF. 617 fabric reinforcement in concrete surface beds, raft slabs etc.	m2	107		
	A0 : 22 A1 : 30 A6 : 24 AD : 31				

Carried to Collection

R

Section 3
Bill No. 2
Concrete, Formwork and Reinforcement

Section 3
Bill No. 2
Concrete, Formwork and Reinforcement

COLLECTION

Total Brought Forward from Page No.

Page No	Amount
---------	--------

41	
42	
43	
44	

Carried Forward to Summary of Section No. 3
Section 3
Bill No. 2
Concrete, Formwork and Reinforcement

R	
---	--

Item No		Quantity	Rate	Amount
	<u>SECTION 3</u> <u>BILL No. 3</u> <u>MASONRY</u> <u>Quantity Split:</u> Note that the total quantity per each item is split into the various buildings and appears below each description as follows: A0 - DWG 14 Male Ablutions A1 - DWG 35 - Female Ablutions A6 - DWG 06 - Grade R Ablutions AD - DWG 04 - Staff Ablutions <u>MODEL PREAMBLES</u> The tenderer is referred to the "General Preambles for Trades 2017" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates. All references to SABS shall be deemed to be the relevant SANS specification <u>SUPPLEMENTARY PREAMBLES</u> <u>BRICKWORK</u> <u>Sizes in descriptions</u> Where sizes in descriptions are given in brick units, "one brick" shall represent the length and "half brick" the width of a brick <u>Hollow walls etc</u> Descriptions of hollow walls shall be deemed to include leaving every fifth perpend of the bottom course of the external skin open as a weep hole. Walls in two skins described as "bagged and sealed" shall be deemed to include having the outer face of the inner skin bagged with 1:6 cement and sand mixture and sealed with two coats "Brixal" bitumen emulsion waterproofing coating.			
	Carried to Collection		R	
	Section 3			
	Bill No. 3			
	Masonry			

Face bricks

Bricks shall be ordered timeously to obtain uniformity in size and colour

Pointing

Descriptions of recessed pointing to fair face brickwork and face brickwork shall be deemed to include square recessed, hollow recessed, weathered pointing, etc

Samples

Samples of all masonry building units, except those of walls described as "loadbearing", shall consist of a minimum of 6 units. Samples of building units to be used in walls described as "loadbearing" shall consist of 30 units from every 30 000 units delivered to site

Trade names

Where trade names are specified it will read "or equal approved"

Carried to Collection

R

Section 3
Bill No. 3
Masonry

BRICKWORK AND BLOCKWORK SUNDRIES

Galvanized brickwork reinforcement

1	115mm Wide reinforcement built in horizontally A0 : 18 A1 : 88 A6 : 53 AD : 35	m	195
2	230mm Wide reinforcement built in horizontally. A0 : 262 A1 : 286 A6 : 262 AD : 367	m	1 178

Cramps, ties, etc:

3	30 x 2mm Galvanized roof tie 1500mm long with one end fixed to timber and other built into brickwork or concrete. A0 : 26 A1 : 26 A6 : 26 AD : 26	No	104
---	---	----	-----

Air bricks etc:

4	229 x 152mm terracotta clay vermin proof air brick A0 : 12 A1 : 12 A6 : 12 AD : 12	No	48
---	--	----	----

Bagging and sealing the outer face of the inner skin of walls with 1:3 cement and sand mixture and seal with two coats "Brixal" bitumen emulsion waterproofing coating:

5	To walls (Provisional). A0 : 65 A1 : 80 A6 : 67 AD : 77	m2	289
---	---	----	-----

Samples

6	Prepare and construct for approval L-Shaped one brickwall faced and pointed both sides as per given specification, size: 1000x1000x1000mm high. same area (1000x1000mm) to be paved as per given specifications.	Item	
---	--	------	--

Turning pieces to lintels etc

7	230mm Wide turning pieces A0 : 8 A1 : 14 A6 : 10 AD : 13	m	46
---	--	---	----

Carried to Collection

R

Section 3
Bill No. 3
Masonry

FACE BRICK

"Rustgold FBS/Qunu Travertine" clay face brick or equal approved, size 222 x 106 x 73mm, bedded and jointed in Class II mortar and pointed with recessed vertical and recessed horizontal joints, suitable for exposure zones 1-2 (Cement to be 42.5N all-purpose cement):

8	Half brick wall in beam filling pointed one side including cutting and fitting around roof timbers and bedding roofing solid on top in cement mortar.	m2	23
	A0 : 5 A1 : 6 A6 : 5 AD : 6		
9	One brickwall pointed on both sides.	m2	362
	A0 : 81 A1 : 88 A6 : 81 AD : 113		
10	Half brickwall pointed on both sides.	m2	59
	A0 : 5 A1 : 27 A6 : 16 AD : 11		
11	Fair raking cutting.	m	36
	A0 : 9 A1 : 9 A6 : 9 AD : 9		

Face brick copings, lintels, sills, etc, of "Rustgold FBS/Qunu Travertine" or equal approved face bricks pointed with recessed joints on all exposed faces:

12	220mm Brick on edge sill bedded sloping and jointed in cement mortar and pointed on top, edge and projecting soffit including cutting and fitting between reveals and splay cutting brickwork under.	m	23
	A0 : 4 A1 : 7 A6 : 5 AD : 7		
13	220mm Wide header course to top of one brick wall bedded and jointed in cement mortar and pointed on both sides.	m	27
	A0 : 5 A1 : 8 A6 : 6 AD : 8		

Carried to Collection

Section 3
Bill No. 3
Masonry

R

Section 3

Bill No. 3

Masonry

COLLECTION

Total Brought Forward from Page No.

**Page
No**

Amount

46

47

48

49

Carried Forward to Summary of Section No. 3

R

Section 3
Bill No. 3
Masonry

Item No		Quantity	Rate	Amount
	<u>SECTION 3</u> <u>BILL No. 4</u> <u>WATERPROOFING</u> <u>Quantity Split:</u> Note that the total quantity per each item is split into the various buildings and appears below each description as follows: A0 - DWG 14 Male Ablutions A1 - DWG 35 - Female Ablutions A6 - DWG 06 - Grade R Ablutions AD - DWG 04 - Staff Ablutions <u>MODEL PREAMBLES</u> The tenderer is referred to the "General Preambles for Trades 2017" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates. <u>SUPPLEMENTARY PREAMBLES</u> <u>Proprietary products in descriptions:</u> Proprietary products shall be used as specified. Substitute products of similar quality and specification may only be used with prior approval by the Principal Agent. <u>Waterproofing</u> The product and its methodology for application must be approved by Principal Agent before it is used. It is a mandatory requirement for the Contractor to attend training to be provided by Supplier. Proof of attendance will be required prior to application of the approved waterproofing product. Contractor must prepare a 1m x 1m sample in the presence of the Principal Agent or Engineer. In this case, the Contractor must give at least 48 hours notice prior to the date when the application of the waterproofing product is intended to be done.			
	Carried to Collection		R	
	Section 3 Bill No. 4 Waterproofing			

Contractor to provide a Letter of Compliance confirming that waterproofing has been applied as per Manufacturer's instructions and data sheet.

Carried to Collection

Section 3
Bill No. 4
Waterproofing

R

DAMPPROOFING OF WALLS AND FLOORS

One layer of 250 micron 'USB GREEN' waterproof sheeting sealed at laps with 'Gunplas Pressure Sensitive Tape':

- | | | | |
|---|--|----|-----|
| 1 | Under surface beds, bases, etc. | m2 | 107 |
| | A0 : 22 A1 : 30 A6 : 24 AD : 31 | | |

One layer of 350 micron embossed dampcourse waterproof sheeting below walls, sills, etc:

- | | | | |
|---|--|----|----|
| 2 | Below walls, sills, etc. | m2 | 11 |
| | A0 : 2 A1 : 3 A6 : 2 AD : 3 | | |

JOINT SEALANTS ETC

Clear Neutral silicone sealant:

- | | | | |
|---|--|---|-----|
| 3 | In joint sealing and pointing all round external window and door frames. | m | 183 |
| | A0 : 31 A1 : 61 A6 : 38 AD : 55 | | |

Two-part grey polysulphide sealing compound including backing cord, bond breaker, primer, etc

- | | | | |
|---|---|---|----|
| 4 | 10 x 12mm In movement joints in floors or walls including raking out expansion joint filler as necessary (Provisional). | m | 81 |
| | A0 : 20 A1 : 20 A6 : 20 AD : 20 | | |

Carried to Collection

R

Section 3
Bill No. 4
Waterproofing

Section 3

Bill No. 4

Waterproofing

COLLECTION

Total Brought Forward from Page No.

**Page
No**

51

52

53

Amount

Carried Forward to Summary of Section No. 3

Section 3

Bill No. 4

Waterproofing

R

Item No		Quantity	Rate	Amount
	<u>SECTION 3</u> <u>BILL No. 5</u> <u>ROOF COVERINGS</u> <u>Quantity Split:</u> Note that the total quantity per each item is split into the various buildings and appears below each description as follows: A0 - DWG 14 Male Ablutions A1 - DWG 35 - Female Ablutions A6 - DWG 06 - Grade R Ablutions AD - DWG 04 - Staff Ablutions <u>MODEL PREAMBLES</u> The tenderer is referred to the "General Preambles for Trades 2017" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates. <u>SUPPLEMENTARY PREAMBLES</u> <u>Flashings</u> Flashings shall be approved by roof sheeting manufacturer and fixed to the sheeting with S10 clips to obviate any direct fixing perforations. Prior to flashings being fixed, all troughs at the apex shall be stop-ended to the full depth of the sheet in order to prevent any penetration of wind driven water. The trough shall be lipped at the eaves end to form a drip. Flashing flanges shall be notched to the sheet profile where necessary. All these operations must be performed with special tools available from the manufacturer. Care shall be taken to ensure that no sheeting or flashing will be cut with abrasive disc on roof surface in order to prevent steel splatter from penetrating colour coated areas. The flashings shall be supplied with a paint finish consisting of a full top coat silicon modified polyester Colour : White to one side <u>Quality Assurance</u> The manufacturer shall be assessed and certified as complying with ISO 9001: 2008 Quality Management System			
	Carried to Collection Section 3 Bill No. 5 Roof Coverings Etc.		R	

Guarantee

Z200 Galvanized Metal or equal approved sheeting shall be laid in strict accordance with manufacturer's specifications by an approved contractor. The employer shall be provided with a ten year written guarantee on materials by the manufacturer.

Safety

The contractor shall exercise special care when handling long length sheeting, particularly in windy conditions. Should work be interrupted for any reason, all loose sheeting and incomplete sections must be adequately secured against possible movement by wind and gravity

Handling and Storage

The contractor shall ensure that all materials used on site for cladding, etc are transported, handled and stored in accordance with the manufacturer's recommendations. Material damaged shall be rejected and replaced with undamaged material at the contractor's expense. Repair of damaged material will not generally be permitted. Rates are to include for preventing damage and protecting sheets through all stages of construction

Inspection Prior to Installation or Erection

Before commencing with installation, the contractor shall verify that the following items have been checked and accepted:

- a. The entire structure or the portion thereof to be sheeted has been correctly aligned, levelled and grouted
- b. Purlins and sheeting rails are at the correct spacing and are within the specified tolerances
- c. The corners of the roof are square and the wall framework is perpendicular or as specified
- d. No protrusions such as bolt heads, splice plates, cleats, etc. appear on the face of the framework
- e. All members to which roofing and cladding are to be fixed in aesthetically sensitive areas are true and square
- f. Paint and any other materials that may be incompatible with the sheeting, have been painted over or so dealt with that direct contact with the sheeting is avoided
- g. The contact faces between the purlins or the girts and the cladding are in the same plane. Should the alignment be inadequate, the contractor shall request instructions from the engineer before proceeding with the fixing of the cladding

Carried to Collection

Section 3
Bill No. 5
Roof Coverings Etc.

R

Protrusion through Sheeted Surfaces

Protrusions such as pipes, ducts and the like, shall be adequately flashed where they pass through the sheeting surface. Where ribs have to be cut away to permit penetration, additional framing is to be installed as required to support the sheeting. Depending on the position of the penetration through the roof, special attention shall be given to back flashing the sheeting to the ridge or point of water entry. In all cases, all cutting and flashings shall be so arranged that adequate provision is made for the drainage of all troughs and corrugation

Cleaning of Roofs, etc

All debris, etc arising from the fixing of the cladding shall be removed from the sheetin as the fixing progresses. In addition, off-cuts of insulation, surplus fastners and sealants, mandrels from pop rivets, off-cuts of flashings and sheeting, surplus flashing, food packaging, cartons, bottles, cans, etc shall not be left on the roof or in the gutters. Care shall be taken to ensure that no such material enters, blocks or partially impedes the flow of water into the outlets, downpipes, etc

Carried to Collection

Section 3
Bill No. 5
Roof Coverings Etc.

R

ROOF COVERINGS

PROFILED METAL SHEETING AND ACCESSORIES

0,58mm Thick Z200 "IBR Profile" galvanised metal roof sheeting, in single sheet lengths, with "Chromadek" finish to external face and standard backing coat to internal face :

- | | | | |
|---|--|----|-----|
| 1 | Roof sheeting laid to a mono-pitch. | m2 | 149 |
| | A0 : 31 A1 : 42 A6 : 34 AD : 42 | | |

0.58mm Flashings pre-painted to match roof sheeting and fixed in strict accordance with manufacturer's instructions:

- | | | | |
|---|--|---|----|
| 2 | Mono pitched ridge capping with 225mm lapping secured onto the roof. | m | 34 |
| | A0 : 7 A1 : 9 A6 : 8 AD : 10 | | |

ROOF AND WALL INSULATION

"Sisalation Grade FR430" or equal approved heavy industrial insulation

- | | | | |
|---|--|----|-----|
| 3 | Insulation laid taut over roof trusses (at approximately 1 100mm centres) and fixed concurrent with SA Pine purlins at 900mm centres, etc including galvanised steel straining wires | m2 | 149 |
| | A0 : 31 A1 : 42 A6 : 34 AD : 42 | | |

Carried to Collection

Section 3
Bill No. 5
Roof Coverings Etc.

R

Section 3

Bill No. 5

Roof Coverings Etc.

COLLECTION

Total Brought Forward from Page No.

**Page
No**

Amount

55

56

57

58

Carried Forward to Summary of Section No. 3

R

Section 3

Bill No. 5

Roof Coverings Etc.

All nailing of timber roof rafters, purlins, etc shall be done with galvanised nails. In coastal areas, copper, aluminium or stainless steel nails shall be used.

Section 3
Bill No. 6
Carpentry and Joinery

Amount

R

CARPENTRY

Sawn softwood:

1	38 x 114mm Wall plate. A0 : 14 A1 : 19 A6 : 15 AD : 19	m	67		
2	50 x 76mm Purlins. A0 : 56 A1 : 75 A6 : 62 AD : 76	m	269		
3	50 x 76mm Bracing. A0 : 12 A1 : 12 A6 : 12 AD : 12	m	48		
4	38 x 152mm Rafters. A0 : 44 A1 : 44 A6 : 44 AD : 44	m	178		

Sundries:

5	TRI FIX or equal approved hurricane clip fixed using 10 x 32mm galvanised clout nails (Provisional). A0 : 45 A1 : 45 A6 : 40 AD : 55	No	185		
---	--	----	-----	--	--

EAVES, VERGES, ETC

"Everite Nutec" or equal approved fibre cement

6	12 x 225mm Fascia board drilled and brass screwed to rafter feet including galvanised steel H-profile jointing strips, etc. A0 : 14 A1 : 19 A6 : 15 AD : 19	m	67		
7	85 x 275 x 6mm Barge board drilled and brass screwed to purlin ends including galvanised steel H-profile jointing strips, screws, holes, etc. A0 : 9 A1 : 9 A6 : 9 AD : 9	m	36		

Carried to Collection

R

Section 3
Bill No. 6
Carpentry and Joinery

DOORS ETC

SANS Approved meranti:

8	44mm Framed, ledged, and battened single door with flush ply panel internally size 813 x 2032mm high comprising 44 x 110mm top rail and stiles, 44 x 220mm bottom rail, 44 x 150mm lock rail and 22 x 70mm vertical "v" jointed boards (D1).	No	5
	A0 : 1 A1 : 1 A6 : 1 AD : 2		
9	44mm Framed, ledged, and battened single door with flush ply panel internally size 950 x 2032mm high comprising 44 x 110mm top rail and stiles, 44 x 220mm bottom rail, 44 x 150mm lock rail and 22 x 70mm vertical "v" jointed boards (D2).	No	2
	A0 : 0 A1 : 0 A6 : 1 AD : 1		
10	44mm Framed, ledged, and battened purpose made single door with flush ply panel internally size 813 x 1832mm high comprising 44 x 110mm stiles, 44 x 220mm bottom rail, 44 x 150mm lock rail and 22 x 70mm vertical "v" jointed boards (D4).	No	11
	A0 : 2 A1 : 6 A6 : 0 AD : 3		
11	44mm Braced and ledged door size 862 x 1000mm Type (D3).	No	3
	A0 : 0 A1 : 0 A6 : 3 AD : 0		

FRAMED FRAMES, ETC

Meranti Frames bolted to wall with expanding masonry bolts - four per style including quadrant beads on both sides:

12	70 x 108mm rebated meranti frame .	m	82
	A0 : 14 A1 : 32 A6 : 13 AD : 23		

Meranti Frames fixed against brickwall using galvanised steel lugs bolted with expanding masonry bolts - four per style including quadrant beads on both sides:

13	70 x 108mm rebated meranti frame .	m	10
	A0 : 0 A1 : 0 A6 : 5 AD : 5		

Carried to Collection

R

Section 3
Bill No. 6
Carpentry and Joinery

Section 3
Bill No. 6
Carpentry and Joinery
COLLECTION

Total Brought Forward from Page No.

Page
No
Amount

60
61
62

Carried Forward to Summary of Section No. 3
Section 3
Bill No. 6
Carpentry and Joinery

R

R

HINGES:

1	75 x 100mm Brass Medium duty ball bearing HMP butt hinges.	Pairs	21.0		
	A0 : 3.0 A1 : 7.0 A6 : 5.0 AD : 6.0				

LOCKS

2	"UNION 2277-78SS" or equal approved three lever sash mortice lockset.	No	7		
	A0 : 1 A1 : 1 A6 : 2 AD : 3				
3	"UNION w/c indicator bolt satin chrome - Code CZ80941SC	No	14		
	A0 : 2 A1 : 6 A6 : 3 AD : 3				

HANDLES

4	"Dorma DPH301B" or equal approved Stainless Steel Straight Tubular Pull handle flange fixing.	No	21		
	A0 : 3 A1 : 7 A6 : 5 AD : 6				

Sundries:

5	Stainless Steel Hat and coat hook, code DHC - SS-030-A or equal approved.	No	14		
	A0 : 2 A1 : 6 A6 : 3 AD : 3				
6	38mm Diameter black rubber door stop plugged and screwed to wall.	No	21		
	A0 : 3 A1 : 7 A6 : 5 AD : 6				

SIGN PLATES:

All sign plates are to be with engraved blue perspex all in accordance with the standard sign plates for Schools.

7	Sign plate plugged and screwed to walls with chromium plated dome headed screws.	No	7		
	A0 : 1 A1 : 1 A6 : 2 AD : 3				

Carried to Collection

R

Section 3
Bill No. 7
Ironmongery

SUNDRIES

Halcast or equal approved"

8	Thiefproof toilet roll holder plugged.	No	16	
	A0 : 2 A1 : 6 A6 : 4 AD : 4			

Grade 304 stainless steel ware:

9	32mm outside diameter x 1,6mm thick tubular wall mounted side stainless steel grab rail 1,06m girth with two 45 degree and two 90 degree formed bends and each end fitted with 80mm diameter x 5mm thick flange welded on and four times countersunk holed for and plugged and screwed to wall with stainless steel crews.	No	2	
	A0 : 0 A1 : 0 A6 : 1 AD : 1			

10	32mm outside diameter x 1,6mm thick tubular wall mounted around cistern back stainless steel grab rail 1,23m girth with two 90 degree formed bends and each end fitted with 80mm diameter x 5mm thick flange welded on and four times countersunk holed for and plugged and screwed to wall with stainless steel crews.	No	2	
	A0 : 0 A1 : 0 A6 : 1 AD : 1			

Carried to Collection

R

Section 3
Bill No. 7
Ironmongery

Section 3

Bill No. 7

Ironmongery

COLLECTION

Total Brought Forward from Page No.

**Page
No**

64

65

66

Amount

Carried Forward to Summary of Section No. 3

Section 3

Bill No. 7

Ironmongery

R

Carried to Collection

Section 3
Bill No. 8
Metalwork

Natural anodised aluminium windows glazed with 6.38mm safety laminated glass and plugged to brickwork:

- | | | | |
|---|---|----|----|
| 1 | Window Size 600 x 600mm high complete, including ironmongery etc, all as per Window Type W01.
A0 : 7 A1 : 12 A6 : 8 AD : 11 | No | 38 |
|---|---|----|----|

HOT DIP GALVANIZED STEEL GATES

Note: The contractor is to check on site measurements before placing of order.

Security Gate consisting of 25 x 25 x 2mm galvanised mild steel frame with 12mm galvanised mild steel square bars infill placed at 109mm centres, hung with one pair of galvanised mild steel hinges including locks, handles, ironmongery complete and fixed to brickwork:

- | | | | |
|---|---|----|---|
| 2 | Security gate size 900 x 2050mm high (G1).
A0 : 1 A1 : 1 A6 : 1 AD : 3 | No | 6 |
| 3 | Security double gate size 1800 x 2050mm high.
A0 : 0 A1 : 0 A6 : 0 AD : 1 | No | 1 |

Carried to Collection

R

Section 3
Bill No. 8
Metalwork

Section 3

Bill No. 8

Metalwork

COLLECTION

Total Brought Forward from Page No.

**Page
No**

68

69

Amount

Carried Forward to Summary of Section No. 3

Section 3

Bill No. 8

Metalwork

R

Section 3
Bill No. 9
Plastering

Amount

m	138
---	-----

R

TAPS, VALVES, ETC

Solid Cast brass taps, valves, etc:

6	"Cobra KM2-200" or other approved 15mm chrome plated metered bib tap with non-hold open feature and flow controller.	No	13
	A0 : 2 A1 : 4 A6 : 3 AD : 4		
7	15mm Ball-o-stop valve.	No	14
	A0 : 2 A1 : 4 A6 : 3 AD : 5		
8	22mm Non Return valve.	No	21
	A0 : 5 A1 : 5 A6 : 5 AD : 6		

WASTE UNIONS ETC

Outlets, traps, etc:

9	40mm 342/50 CP bottle trap.	No	1
	A0 : 0 A1 : 0 A6 : 0 AD : 1		
10	40mm Code 316 chrome plated unslotted waste outlet.	No	13
	A0 : 2 A1 : 4 A6 : 3 AD : 4		
11	40mm Rubber "P" or "S" trap	No	13
	A0 : 2 A1 : 4 A6 : 3 AD : 4		

Carried to Collection

R

Section 3
Bill No. 10
Plumbing and Drainage (Provisional)

SANITARY FITTINGS

Vaal or equal approved:

12	Lavatera White Vitreous china wall mounted bowl urinal with top inlet [code: 704001] 610x385mm, supplied with 38mm chromium plated domical grating [code: 8787], chromium plated spreader [code: 8543], and two hanger brackets [code: 8127] A0 : 0 A1 : 0 A6 : 0 AD : 1	No	1
13	Hibiscus White Vitreous china 510 x 405mm rounded basin [code: 7050] with one tap hole on left hand side, including integrated overflow, bolted to wall with two 8mm bolts [code 8448Z0], to manufacturer's specification. A0 : 2 A1 : 4 A6 : 3 AD : 4	No	13
14	Orchid back inlet white vitreous china wall hung pan [code 439016] with floor bracket [code 8082Z0] fitted as per manufacturer's specifications and combined with: GEBERIT Kombifix UP172 for wall hung WC, [G110.150.00.1], front actuated with Delta21 dual flush actuator [G115.125.46.1] in matt finish, including flushpipe and Pan connector, water supply connection with angle stop valve, Netting for direct plastering, protection cover for service opening and protection cover for flushpipe, fixed with included fastening materials inside a single solid wall [80mm] A0 : 2 A1 : 6 A6 : 1 AD : 4	No	13
15	Junior vitreous china low level suite colour White (Code: 751358), comprising 104° outlet washdown pan (Code: 751301) with matching 6 litre front single flush cistern (Code: 712034) including lid, fitments and flushpipe and Junior double flap wooden seat (Code: 8518Z0). A0 : 0 A1 : 0 A6 : 3 AD : 0	No	3

Carried to Collection

R

Section 3
Bill No. 10
Plumbing and Drainage (Provisional)

Franke Model TU101 or equal approved flush valve/cistern flat back wall mounted urinal:

16	SS-TU101-1830R Flat back stainless steel school trough urinal wall and floor mounted. manufactured from Grade 304 (18/10) Stainless Steel, 0,9 mm gauge. Urinal to be supplied with a concealed sparge pipe and a 22 mm inlet with chrome plated conex fitting for connecting to water inlet (Connection fitting not supplied). Urinal to include a tiling key to sides and rear walls. The back to be fully sound deadened with vermin proof bitumastic material. Outlet to be situated on the left or right of the urinal with a recess for 40 mm chrome plated waste outlet.	No	2
	A0 : 2 A1 : 0 A6 : 0 AD : 0		
17	Sanitary Towel Bin - White - Steel - 25L- Large	No	9
	A0 : 0 A1 : 0 A6 : 9 AD : 0		

SANITARY PLUMBING

PVC waste or vent pipes and fittings:

18	50mm Waste pipe.	m	124
	A0 : 30 A1 : 31 A6 : 30 AD : 33		
19	110mm Pipe.	m	16
	A0 : 2 A1 : 6 A6 : 4 AD : 4		
20	110mm Pipe and laying in ground or filling not exceeding 2m deep including excavation, filling in and ramming.	m	93
	A0 : 22 A1 : 21 A6 : 25 AD : 25		

uPVC gulleys

21	200mm Precast concrete gully dish and uPVC lowback assembly complete with 110mm P trap gulley (code UGB 40) including 190mm diameter head (code UGA 40) and grate (code UGG 40), not exceeding 750mm deep, jointed to 110mm drain pipe, including excavations for and encasing in concrete (15MPa crushing strength after 28 days) worked up to form kerb, finished smooth on top in 1:3 cement mortar.	No	4
	A0 : 1 A1 : 1 A6 : 1 AD : 1		

Extra for:

22	50mm Bend.	No	44
	A0 : 10 A1 : 12 A6 : 10 AD : 12		

Carried to Collection

R

Section 3
Bill No. 10
Plumbing and Drainage (Provisional)

23	50mm Access bend. A0 : 4 A1 : 3 A6 : 3 AD : 7	No	17
24	100mm Access bend. A0 : 2 A1 : 6 A6 : 4 AD : 4	No	16

WATER SUPPLIES

Polycop pipes:

Pipes shall be class 10.

Fixing of pipes

Unless specifically otherwise stated, descriptions of pipes shall be deemed to include for fixing to walls etc. casting in, building in or suspending not exceeding 1m below suspension level

Polycop pipes chased in walls:

Where pipes have been chased in walls, the price for making good of plaster and paint etc shall be deemed to be included in the description of pipe chased in walls.

Reducing fittings:

Where fittings have reducing ends or branches they are described as 'reducing'. In the case of pipes with diameters not exceeding 60mm only the largest end or branch size is given. Should the Contractor wish to use other fittings and bushes or reducers he may do so on the understanding that no claim in this regard will be entertained. In the case of pipes with diameters exceeding 60mm all sizes are given and no claim for extra bushes, reducers, etc will be entertained.

Class 10 Polycop pipes:

25	15mm Pipe chased into brick walls. A0 : 35 A1 : 35 A6 : 35 AD : 35	m	140
26	22mm Pipe chased into brick walls. A0 : 20 A1 : 20 A6 : 20 AD : 20	m	80

Extra over polycop pipes for compression fittings:

27	15mm Fittings. A0 : 31 A1 : 30 A6 : 29 AD : 30	No	120
28	22mm Fittings. A0 : 25 A1 : 23 A6 : 29 AD : 20	No	97

Carried to Collection

Section 3
Bill No. 10
Plumbing and Drainage (Provisional)

R

Connection to existing water supply

29 Allow for connection to existing water supply.

Item

Connection of water supply from Waste Water Treatment System (WWTS)

30 Allow for connecting water supply from waste water treatment system.

Item

Testing

31 Testing water pipe system

Item

Carried to Collection

R

Section 3
Bill No. 10
Plumbing and Drainage (Provisional)

Section 3
Bill No. 10
Plumbing and Drainage (Provisional)

COLLECTION

Total Brought Forward from Page No.

Page No	Amount
---------	--------

72	
73	
74	
75	
76	
77	

Carried Forward to Summary of Section No. 3

Section 3
Bill No. 10
Plumbing and Drainage (Provisional)

R	
---	--

R

PAINTWORK ETC TO NEW WORK

ON WOOD

Stop, sand down and prepare wood surfaces and apply one coat wood primer, one undercoat and two coats eggshell enamel paint as per Plascon or equal approved:

1	On doors	m2	66
	A0 : 10 A1 : 23 A6 : 13 AD : 21		

2	On door frames	m2	21
	A0 : 3 A1 : 7 A6 : 4 AD : 6		

Prepare and apply two coats carbolenium on:

3	On exposed timbers.	m2	51
	A0 : 11 A1 : 14 A6 : 12 AD : 14		

ON FIBRE-CEMENT

Prepare and apply two coats pure acrylic roof paint on:

4	On fascias and barge boards.	m2	36
	A0 : 8 A1 : 10 A6 : 8 AD : 10		

Carried to Collection

Section 3
Bill No. 11
Paintwork

R

Section 3

Bill No. 11

Paintwork

COLLECTION

Total Brought Forward from Page No.

**Page
No**

79

80

Amount

Carried Forward to Summary of Section No. 3

Section 3

Bill No. 11

Paintwork

R

Section 3

SECTION SUMMARY - BUILDING WORKS

**Bill
No**

**Page
No**

Amount

Earthworks (Provisional)

40

Concrete, Formwork and Reinforcement

45

Masonry

50

Waterproofing

54

Roof Coverings Etc.

59

Carpentry and Joinery

63

Ironmongery

67

Metalwork

70

Plastering

71

Plumbing and Drainage (Provisional)

78

Paintwork

81

Carried to Final Summary

R

Section 3

Item No		Quantity	Rate	Amount
	<u>SECTION No. 4</u>			
	<u>BILL No. 1</u>			
	<u>EXTERNAL WORKS (PROVISIONAL)</u>			
	<u>MODEL PREAMBLES</u>			
	The tenderer is referred to the "Model Preambles for Trades 2008" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates			
	<u>THE FOLLOWING IN PLATFORMS, ETC.</u>			
	<u>Site Clearance, ETC</u>			
1	Allow for clearing the area of the site to be built upon of all grass, weeds, shrubs, trees with trunks not exceeding 200mm girth, debris, etc., including grubbing up all roots, scoffling up as required and cart away all vegetation and debris.	m2	1 000	
2	Stripping average 200mm thick layer of topsoil and stockpiling on site.	m2	1 000	
	<u>Open face excavation not exceeding 2m deep:</u>			
3	Excavate to cut in open face, not exceeding 2m deep to reduce levels and grade to fill and compact to 93% mod AASHTO density at optimum moisture content.	m3	300	
	<u>Extra over all excavations for carting away:</u>			
4	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the contractor.	m3	100	
	<u>Earth filling from excavated material</u>			
5	Dig, load and remove filling selected from spoil heaps on site and deposit as filling in platforms including spreading and compacting to cambers and falls in layers not exceeding 150 mm thick to a minimum of 95% Modified AASHTO dry density.	m3	100	
	Carried to Collection			
	Section 4			
	Bill No. 1			
	External Works			
			R	

	<u>Filling supplied by the contractor to form platforms</u>				
6	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	200		
	<u>Surface Preparation:</u>				
7	Trim and level off surface of ground (excavated or filled under this Contract) including excavating or filling, ripping and scarifying as necessary and compacting the whole area for a depth of 300mm to a density of at least 90% Mod. AASHTO maximum density, part to falls.	m2	1 000		
	<u>Prescribed density tests on filling:</u>				
8	Modified AASHTO Density test.	No	4		
	<u>STORMWATER APRONS</u>				
	<u>Excavation not exceeding 2m deep</u>				
9	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	14		
	<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>				
10	Off site to a dumping site to be found by the Contractor.	m3	14		
	<u>Filling supplied by the contractor under floors, aprons, etc</u>				
11	G7 Base course material compacted to 98% Mod AASHTO density	m3	7		
12	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	7		
	<u>Coarse river sand filling supplied by the contractor:</u>				
13	Under floors etc.	m3	5		
	Carried to Collection			R	
	Section 4				
	Bill No. 1				
	External Works				

[illegible]

	<u>Excavation not exceeding 2m deep</u>				
23	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	38		
	<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>				
24	Off site to a dumping site to be found by the Contractor.	m3	38		
	<u>Filling supplied by the contractor under channels</u>				
25	G7 Base course material compacted to 98% Mod AASHTO density	m3	19		
26	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	19		
	<u>Cast in-situ Ref 395 mesh reinforced concrete (25MPa) open stormwater channels having V-shaped waterway formed in top, finished smooth on all exposed surfaces in 3:1 cement plaster trowelled smooth and with angles rounded, cast in suitable lengths not exceeding 2m, including all formwork, moulds, shallow excavation, filling and ramming, laying to falls, bedding and pointing in 3:1 cement mortar. Concrete apron to be tinted, colour to be specified by the Engineer.</u>				
27	700 x 80mm thick V' channel 150mm deep in centre laid in position in ground not exceeding 2000mm sections including all formwork, reinforcement, expansion joints, smooth finishing to top of concrete surface etc.	m	300		
28	Extra for 700mm angle	No	10		
29	Extra for forming 200mm thick 700mm wide spreader with 200mm high edges fanning out to 1 960mm width at furthest end with hard burnt bricks pitching cast in ass diffusers including working off concrete to a smooth finish and draining onto natural ground with 150 - 200mm diameter loose stones.	No	5		
	<u>Sundries:</u>				
30	Create earth berm for stormwater control with in situ material 1,5m wide at base x 500mm high	m	50		
Carried to Collection				R	
Section 4					
Bill No. 1					
External Works					

**THE FOLLOWING IN STORMWATER DISH
DRAIN, ETC.**

Excavation not exceeding 2m deep

31	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	5
----	--	----	---

Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):

32	Off site to a dumping site to be found by the Contractor.	m3	5
----	---	----	---

Filling supplied by the contractor under floors, aprons, channels etc

33	G7 Base course material compacted to 98% Mod AASHTO density	m3	3
----	---	----	---

34	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	3
----	--	----	---

Coarse river sand filling supplied by the contractor:

35	Under floors etc.	m3	3
----	-------------------	----	---

Compaction of surfaces:

36	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density.	m2	15
----	--	----	----

Prescribed density tests on filling:

37	In-situ dry density test.	No	3
----	---------------------------	----	---

Reinforced 25Mpa/19mm Concrete:

38	Surface beds cast in panels on waterproofing.	m3	3
----	---	----	---

Finishing top surfaces of concrete smooth with a wood float:

39	Surface beds, slabs, etc to falls and currents.	m2	40
----	---	----	----

Carried to Collection

R

Section 4
Bill No. 1
External Works

	<u>Test blocks:</u>				
40	Making and testing of 150x150x150mm concrete strength test cubes (Provisional).	No	3		
	<u>Expansion joints with bitumen impregnated softboard between vertical concrete or brick surfaces:</u>				
41	12mm Joints not exceeding 300mm high.	m	30		
	<u>Two-part grey polysulphide sealing compound including backing cord, bond breaker, primer, etc</u>				
42	10 x 12mm In movement joints in floors or walls including raking out expansion joint filler as necessary.	m	15		
	<u>Fabric reinforcement:</u>				
43	REF. 617 fabric reinforcement in concrete surface beds, slabs, etc.	m2	15		
<u>SEWER RETICULATION</u>					
<u>MODEL PREAMBLES</u>					
The tenderer is referred to the "Model Preambles for Trades 2008" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates					
<u>SUPPLEMENTARY PREAMBLES</u>					
<u>uPVC pipes and fittings</u>					
Soil, waste and vent pipes and fittings shall be solvent weld jointed.					
Sewer and drainage pipes and fittings shall be jointed and sealed with butyl rubber rings.					
<u>Excavations:</u>					
No claim for rock excavation will be entertained unless the Contractor has timeously notified the quantity surveyor thereof prior to backfilling.					
Soft rock and hard rock shall be as defined in Earthworks.					
Carried to Collection				R	
Section 4					
Bill No. 1					
External Works					

45	110mm Pipes laid in and including trenches exceeding 1m but not exceeding 2m deep	m	10		
	<u>Extra over heavy duty (Class 34) PVC-U sewer and drain pipes for fittings</u>				
46	110mm Bend	No	20		
47	160mm Bend	No	10		
48	110mm Rodding eye	No	10		
49	160 x 110mm Reducing junction	No	12		
	<u>PRE-CAST CONCRETE MANHOLES</u>				
	<u>Pre-cast concrete circular inspection chambers including pre-cast concrete cover slabs, covers and channels in benching</u>				
50	Manhole 1000mm diameter not exceeding 1m deep.	No	2		
51	Manhole 1000mm diameter exceeding 1m and not exceeding 2m deep.	No	1		
	<u>Manhole covers</u>				
52	620mm dia Type 2A Heavy duty cast iron manhole to SABS 558	No	3		
	<u>Connection</u>				
53	Allow for connecting to Waste Water Treatment System (WWTS).			Item	
	<u>Testing:</u>				
54	Testing drainage system.			Item	
	<u>THE FOLLOWING IN WALKWAYS</u>				
	<u>Excavation not exceeding 2m deep</u>				
55	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	75		
Carried to Collection					R
Section 4					
Bill No. 1					
External Works					

[illegible]

	<u>Precast or in situ mass concrete (25 MPa - 19 mm stone) kerbs cast in convenient lengths with exposed faces finished smooth from the mould and all salient angles rounded, jointed and pointed in 1:3 cement mortar, including excavations, formwork, etc.</u>			
63	Figure 8B (300 x 275 x 175mm) semi mountable kerb laid in lengths not exceeding 1000mm on a well rammed earth bottom or base course.	m	300	
64	Ditto but circular on plan.	m	30	
Carried to Collection				
Section 4 Bill No. 1 External Works				

**THE FOLLOWING IN ONE BRICK WALL
(GARDEN WALL)**

Excavation in earth not exceeding 2m deep:

65	Trenches.	m3	43		
----	-----------	----	----	--	--

Extra over all excavations for carting away:

66	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the Contractor.	m3	19		
----	---	----	----	--	--

Risk of collapse of excavations:

67	Sides of trench and hole excavations not exceeding 1,5m deep.	m2	213		
----	---	----	-----	--	--

Earth filling obtained from the excavations and/or prescribed stock piles on site compacted to 93% MOD AASHTO density:

68	Backfilling to trenches, holes, etc.	m3	24		
----	--------------------------------------	----	----	--	--

Earth filling (G7 material) supplied by the contractor in layers not exceeding 150mm thick and compacted to 98% Mod AASHTO density:

69	Under footings.	m3	6		
----	-----------------	----	---	--	--

Compaction of surfaces

70	Compaction of ground surface under floors, etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density.	m2	43		
----	---	----	----	--	--

25 Mpa/19mm Concrete

71	Strip footings.	m3	11		
----	-----------------	----	----	--	--

Test blocks:

72	Making and testing of 150x150x150mm concrete strength test cubes (Provisional).	No	5		
----	---	----	---	--	--

Carried to Collection

R

Section 4
Bill No. 1
External Works

[illegible]

	<u>Excavation in earth not exceeding 2m deep</u>				
80	Trenches.	m3	17		
	<u>Risk of collapse of excavations:</u>				
81	Sides of trench and hole excavations not exceeding 1,5m deep.	m2	57		
	<u>Keeping excavations free of water:</u>				
82	Keeping excavations free of all water other than subterranean water.			Item	
	<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>				
83	Off site to a dumping site to be found by the Contractor.	m3	9		
	<u>Filling with approved clean, hard, dry decomposed dolerite filling supplied and carted onto site by the Contractor, compacted to a density of at least 95% Mod. AASHTO maximum density:</u>				
84	Behind walls with selected backfilling supplied by the Contractor compacted to 98% Mod ASSHTO density	m3	5		
	<u>Compaction of surfaces</u>				
85	Compaction of ground surface under floors, etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density.	m2	16		
	<u>15Mpa/19mm Concrete</u>				
86	Surface blinding under footings and bases.	m3	2		
	<u>30Mpa/19mm Concrete</u>				
87	Strip footings.	m3	6		
88	Cavity walls.	m3	4		
Carried to Collection					R
Section 4					
Bill No. 1					
External Works					

	<u>Test blocks:</u>				
89	Making and testing of 150x150x150mm concrete strength test cubes (Provisional).	No	1		
	<u>Fabric reinforcement:</u>				
90	REF. 395 fabric reinforcement in concrete infill, strip footings.	m2	87		
	<u>Brickwork of NFX bricks (14 MPa nominal compressive strength) in Class I mortar (Cement to be 42.5N all-purpose cement):</u>				
91	330mm thick cavity brick Walls made of two leafs of 110mm wall with 110mm mesh reinforced concrete fill (concrete and reinforcement elsewhere measured).	m2	85		
	<u>Brickwork reinforcement:</u>				
92	230mm Wide reinforcement built in horizontally.	m	1 430		
	<u>"Rustgold FBS/Qunu Travertine" clay face brick or equal approved, size 222 x 106 x 73mm, bedded and jointed in Class II mortar and pointed with recessed vertical and recessed horizontal joints, suitable for exposure zones 1-2 (Cement to be 42.5N all-purpose cement):</u>				
93	Extra over brickwork for face brickwork externally.	m2	69		
	<u>Brick-on-edge header course copings, sills, etc, of "Rustgold FBS/Qunu Travertine" or equal Architect approved clay face brick size 222 x 106 x 73mm, pointed with recessed joints on all exposed faces:</u>				
94	220mm Wide header course to top of one brick wall bedded and jointed in cement mortar and pointed on top and both sides as described.	m	58		
	<u>Openings in Walls etc.</u>				
95	Leave or form 32mm weephole through one brick wall	No	38		
	<u>Membranes</u>				
96	"Geofabric filter blanket wrapped around stone with 150mm side and 300mm end laps, including stitching.	m2	87		
Carried to Collection					R
Section 4					
Bill No. 1					
External Works					

	Earth filling 300 x 300mm section of 19mm thick stone material surrounding 110mm uPVC pipe, supplied by the contractor compacted to 98% Mod AASHTO density:				
97	19mm Stone.	m3	30		
<u>THE FOLLOWING IN DISABLED ACCESS</u>					
<u>SCREEN WALL</u>					
<u>Excavation in earth not exceeding 2m deep:</u>					
98	Trenches.	m3	6		
<u>Extra over all excavations for carting away:</u>					
99	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the Contractor.	m3	3		
<u>Risk of collapse of excavations:</u>					
100	Sides of trench and hole excavations not exceeding 1,5m deep.	m2	27		
<u>Earth filling obtained from the excavations and/or prescribed stock piles on site compacted to 93% MOD AASHTO density:</u>					
101	Backfilling to trenches, holes, etc.	m3	3		
<u>Earth filling (G7 material) supplied by the contractor in layers not exceeding 150mm thick and compacted to 98% Mod AASHTO density:</u>					
102	Under footings.	m3	1		
<u>Compaction of surfaces</u>					
103	Compaction of ground surface under floors, etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density.	m2	6		
<u>25 Mpa/19mm Concrete</u>					
104	Strip footings.	m3	2		
Carried to Collection				R	
Section 4					
Bill No. 1					
External Works					

	<u>Test blocks:</u>				
105	Making and testing of 150x150x150mm concrete strength test cubes (Provisional).	No	2		
	<u>Reinforcement (Provisional)</u>				
106	High tensile steel reinforcement bars to structural concrete work.	t	0.15		
	<u>BRICKWORK IN FOUNDATIONS.</u>				
	<u>Brickwork of NFX bricks (14 MPa nominal compressive strength) in Class I mortar (Cement to be 42.5N all-purpose cement):</u>				
107	One brick walls.	m2	5		
	<u>BRICKWORK IN SUPERSTRUCTURE</u>				
	<u>Brickwork of NFP bricks (14 MPa nominal compressive strength) in Class II mortar (Cement to be 42.5N all-purpose cement):</u>				
108	One brick walls.	m2	10		
	<u>Brickwork reinforcement:</u>				
109	230mm Wide reinforcement built in horizontally.	m	40		
110	Ditto but in foundations.	m	20		
	<u>FACE BRICK</u>				
	<u>"Rustgold FBS/Qunu Travertine" clay face brick or equal approved, size 222 x 106 x 73mm, bedded and jointed in Class II mortar and pointed with recessed vertical and recessed horizontal joints, suitable for exposure zones 1-2 (Cement to be 42.5N all-purpose cement):</u>				
111	One brickwall faced on both sides.	m2	10		
Carried to Collection					R
Section 4					
Bill No. 1					
External Works					

	<u>Brick-on-edge header course copings, sills, etc, of "Rustgold FBS/Quinu Travertine" or equal approved face bricks pointed with recessed joints on all exposed faces, 220mm wide sill set sloping and slightly projecting:</u>				
112	230mm wide header course to top of one brick wall bedded and jointed in cement mortar and pointed on top and both sides as described.	m	10		
	<u>ACCESS RAMPS</u>				
	<u>Excavation not exceeding 2m deep</u>				
113	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	12		
	<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>				
114	Off site to a dumping site to be found by the Contractor.	m3	12		
	<u>Filling supplied by the contractor under floors, aprons, etc</u>				
115	G7 Base course material compacted to 98% Mod AASHTO density	m3	4		
116	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	4		
	<u>Coarse river sand filling supplied by the contractor:</u>				
117	Under floors etc.	m3	2		
	<u>Compaction of surfaces:</u>				
118	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density.	m2	12		
	<u>Prescribed density tests on filling:</u>				
119	In-situ dry density test.	No	4		
Carried to Collection					R
Section 4					
Bill No. 1					
External Works					

[illegible]

	<u>Filling supplied by the contractor under driveways</u>				
129	G7 Base course material compacted to 98% Mod AASHTO density	m3	45		
130	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	45		
	<u>Rip and Re - compact insitu material on site compacted to 93% Mod. AASHTO density:</u>				
131	Under floors,etc.	m2	450		
	<u>Prescribed density tests on filling:</u>				
132	In-situ dry density test.	No	5		
	<u>Approved brand of anti-termite soil poison applied by a Registered Pest Control Company and guaranteed against termite infestation for ten years:</u>				
133	Treat filling under paving with 'Chlordane Heptachlor Aldrin' or equal approved.	m2	450		
	<u>150-175mm diameter bollards</u>				
134	2100mm long tanalith treated gum pole planted 800mm deep including excavations, cartaways, concrete base etc.	No	30		
	<u>Vehicle access gravel</u>				
135	Gravel access gravel stones or similar approved	m2	20		
	<u>THE FOLLOWING IN RAINWATER TANKS AND STANDS</u>				
	<u>Excavation in earth not exceeding 2m deep:</u>				
136	Trenches.	m3	18		
	<u>Extra over all excavations for carting away:</u>				
137	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the Contractor.	m3	13		
	Carried to Collection			R	
	Section 4				
	Bill No. 1				
	External Works				

	<u>Risk of collapse of excavations:</u>				
138	Sides of trench and hole excavations not exceeding 1,5m deep. <u>Earth filling obtained from the excavations and/or prescribed stock piles on site compacted to 93% MOD AASHTO density:</u>	m2	35		
139	Backfilling to trenches, holes, etc. <u>Earth filling (G7 material) supplied by the contractor in layers not exceeding 150mm thick and compacted to 98% Mod AASHTO density:</u>	m3	8		
140	Under footings. <u>Compaction of surfaces</u>	m3	7		
141	Compaction of ground surface under floors, etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density. <u>25 Mpa/19mm Concrete</u>	m2	40		
142	Strip footings. <u>25 MPa/19mm Concrete:</u>	m3	9		
143	Tank concrete slab. <u>Test blocks:</u>	m3	5		
144	Making and testing of 150x150x150mm concrete strength test cubes (Provisional). <u>Finishing top surfaces of concrete smooth with a steel trowel including adding additional cement while concrete is still green to attain a smooth, hard surface:</u>	No	4		
145	Surface beds, slabs, etc. <u>Rough Formwork to Sides:</u>	m2	40		
146	Edges, risers, ends and reveals not exceeding 300mm high.	m	24		
Carried to Collection				R	
Section 4 Bill No. 1 External Works					

	<u>Allens Meshco Square Mesh Fabric reinforcement:</u>				
147	Type 617 fabric reinforcement in concrete slabs.	m2	40		
	<u>BRICKWORK IN FOUNDATIONS.</u>				
	<u>Brickwork of NFX bricks (14 MPa nominal compressive strength) in Class I mortar (Cement to be 42.5N all-purpose cement):</u>				
148	One brick walls.	m2	13		
	<u>BRICKWORK IN SUPERSTRUCTURE</u>				
	<u>Brickwork of NFP bricks (14 MPa nominal compressive strength) in Class II mortar (Cement to be 42.5N all-purpose cement):</u>				
149	One brick walls.	m2	19		
	<u>Brickwork reinforcement:</u>				
150	230mm Wide reinforcement built in horizontally.	m	243		
151	Ditto but in foundations.	m	90		
	<u>FACE BRICK</u>				
	<u>"Rustgold FBS/Qunu Travertine" clay face brick or equal approved, size 222 x 106 x 73mm, bedded and jointed in Class II mortar and pointed with recessed vertical and recessed horizontal joints, suitable for exposure zones 1-2(Cement to be 42.5N all-purpose cement):</u>				
152	Extra over brickwork for face brickwork externally.	m2	19		
	<u>Brick-on-edge header course copings, sills, etc. of "Rustgold FBS/Qunu Travertine" or equal approved face bricks pointed with recessed joints on all exposed faces, 220mm wide sill set sloping and slightly projecting:</u>				
153	230mm wide header course to top of one brick wall bedded and jointed in cement mortar and pointed on top and both sides as described.	m	19		
Carried to Collection					R
Section 4					
Bill No. 1					
External Works					

	<u>Plastic water tanks etc:</u>				
154	5000 Litre roto molded or equal approved plastic tank complete with lid, 15mm brass bibtap with handle suitable for locking and 4 No. galvanised stay wires 2.5m each long connected to tank, with and including 4 No. eye bolts cast into concrete.	No	5		
155	Hole top of tank for 100mm pipe.	No	5		
	<u>THE FOLLOWING IN SECURITY FENCING, ETC</u>				
	<u>Site clearance</u>				
156	Allow for clearing site for the width of 1 000 mm where fencing is to be erected including removing trees, shrubs etc. not exceeding 200 mm girth, grubbing up roots and roughly levelling.	m2	73		
	<u>Straining wires, fencing and razor wire:</u>				
157	Four strands of 4mm Class'A' galvanised straining wires secured to fencing posts with doubled 2 mm galvanised wire inserted through hole in post and turned a minimum of four turns around straining wire and attached to straining frame at one end with not less than four turns at the other end to straining bolts (elsewhere measured).	m	145		
158	3 Strands of galvanised barbed wire tied to standards, posts and eye bolts	m	145		
159	Fencing formed of 50 x 50 x 2.0mm diameter galvanised fencing 1 800mm high and fixed to each straining wire with 8 guage binding wire at 500mm centres including Y12 pegs at 900mm c/c between posts (straining wires elsewhere measured).	m	140		
	<u>Posts for 1 800mm high security fence:</u>				
160	60mm Diameter galvanised steel intermediate fencing post 1800mm long fitted with a pressed steel mushroom cap one end and 150 x 150 x 5 mm baseplate at bottom and embedded in and including 350 x 350 x 600 mm mass concrete (15 MPa) base.	No	45		
161	100mm Ditto as corner post, fitted with two 50mm diameter galvanised steel stay set raking and with top end flattened and bolted through post, with post and stay both embedded in mass concrete (15 MPa) bases as last.	No	15		
	Carried to Collection			R	
	Section 4				
	Bill No. 1				
	External Works				

**MASIJONGANE JUNIOR PRIMARY SCHOOL
THE MVULA TRUST SAFE PROGRAMME**

162	150mm Ditto as gate post 1 800mm long, fitted with two 50mm diameter galvanised steel stay set raking and with top end flattened and bolted through post, with post and stay both embedded in mass concrete (15 MPa) bases as last.	No	4		
163	12mm Diameter galvanised mild steel straining eye bolt with hook, threaded portion and two nuts and washers.	No	20		
164	Form 12mm diameter hole through fence post.	No	20		
	<u>Gates:</u>				
165	Security fence single gate, size 1 000 mm wide x 1 800 mm high, formed of 50 mm diameter nominal bore x 3,25 mm wall thickness hot dip galvanised mild steel pipe framing all round with mitred and welded angles and cross braces mullion and transome, scribed and welded into angles and at cross intersections, with two 50 mm diameter nominal bore x 3,25 mm wall thickness security posts each 600 mm long with one end welded to top rail of gate and closure plate to other end, the gate covered with 100 x 50 x 2,5 mm weld mesh with four straining wires as before described and with four 2,37 mm four point core diameter single "kampeon" wires with crimped droppers to security posts as before described; including three strands flat wrap razor barbed tape wire fixed as before described, leaf fitted with three 24 mm diameter x 300 mm long eyebolt hinges and stops including all holes, etc., welded or bolted to adjoining galvanised gatepost with and including 500 mm long approved chain spot welded to gate	No	1		
166	Two leafed vehicular swing gate. Size 5500mm x 1800mm high.	No	1		
	<u>PADLOCKS</u>				
167	Supply 50 mm "Viro" Padlocks and Keys (or equal approved)	No	3		
Carried to Collection				R	
Section 4					
Bill No. 1					
External Works					

Section 4
Bill No. 1
External Works
COLLECTION

External Works

COLLECTION

Amount

103

R

-106-

Section 4
Bill No. 1
External Works

Item No		Quantity	Rate	Amount
	<u>SECTION 5</u>			
	<u>BILL No. 1</u>			
	<u>PROVISIONAL SUMS</u>			
	<u>SUPPLEMENTARY PREAMBLES</u>			
	Tenderers are advised that no claim in respect of loss of profit or Preliminary charges based on the omission of these amounts will be considered and the said amounts will be omitted strictly without any financial compensation payable to the Contractor.			
	Provisional sums and Budgetary allowances contained herein may be omitted or reduced at the Employer's discretion and the Contractor shall not be entitled to claim for any loss by way of reductions or omission of any discount, or percentage relating to Provisional amounts and Budgetary sums or any loss of profit related thereto.			
	<u>BUDGETARY ALLOWANCES</u>			
	<u>The following budgetary allowances are for work to be executed at rates in the bills of quantities or to be agreed by the Principal agent:</u>			
	<u>COMMUNITY LIAISON OFFICER</u>			
1	Provide the sum of R58 500.00 for the employment of a Community Liaison Officer to be employed by the Main Contractor and be paid an allowance of R6 500.00 a month for the duration (9 months)	Item		58 500.00
2	Add: Mark-up		%	
	<u>WASTE WATER TREATMENT SYSTEM</u>			
3	Provide the sum of R 1 600 000.00 (One Million Six Hundred Thousand Rand) for design and construction of on-site waste water treatment system as per specification provided.	Item		1 600 000.00
4	Add: Profit		%	
	Carried to Collection		R	
	Section 5			
	Bill No. 1			
	Provisional Sums			

[illegible]

Section 5

Bill No. 1

Provisional Sums

COLLECTION

Total Brought Forward from Page No.

**Page
No**

108

109

Amount

Carried to Final Summary

R

Section 5

Bill No. 1

Provisional Sums

[illegible]