	Brought Forward			R	1
	Base course of earth filling supplied by the contractor under pavings, roads, etc				
165	Construct 150mm thick base layer of G5 materials obtained from commercial sources, compacted to a density of at least 95% Mod. AASHTO density.	m3	93		
	Prescribed density tests on filling				
166	Modified AASHTO Density tests	No	73		
	Weedkiller mixed with water and applied at a rate of 100grams/m2				
167	To sides and bottoms of trench excavations (LI)	m2	998		
	Concrete (CPAP Work Group No. 110)				
	Unreinforced concrete cast against excavated surfaces				
	15MPa/19mm concrete				
168	Blinding (LI)	m3	13		
	Reinforced concrete cast against excavated surfaces /or formworks				
	30MPa/19mm concrete				
169	Strip footings (LI)	m3	90		
	Test cubes				
170	Making and testing set of three 150 x 150 x 150mm concrete strength test cube (Provisional)	No	15		
	Formwork (CPAP Work Group No. 111)				
	Rough formwork to sides				
171	Strip footings (LI)	m2	138		
	Reinforcement (CPAP Work Group No. 114)				
	Carried Forward Bill No. 19 External Works			R	

NO 55

	Brought Forward	1	j	R
	Mild and high tensile steel reinforcement to structural concrete work			
172	Various diameter bars (LI)	t	13,50	
	Masonry (CPAP Work Group No. 116)			
	Brickwork of NFX bricks in class II mortar			
173	One and half brick walls in foundations (Li)	m2	224	
174	One and half brick walls (LI)	m2	86	
	Brickwork sundries			
	2.5mm Galvanised brickwork reinforcement			
175	155mm Wide reinforcement built in horizontally (LI)	m	2 430	
	Bagging of 1:3 cement and sand mixture			
176	On brick walls, piers, etc. (LI)	m2	131	
	Joint forming material in movement joints			
77	12mm Bitumen impregnated fibre board built in vertically through brick walls exceeding 300mm wide (LI)	m2	20	
	Face brickwork			
	"Corojem Nebraska FBS" or other equally approved face bricks pointed with tinted recessed horizontal and vertical joints			
78	Extra over brickwork for face brickwork on both sides of walls in foundations (LI)	m2	45	
79	Extra over brickwork for face brickwork on both sides of walls (LI)	m2	86	
30	Extra over brickwork for 345mm wide brick-on-edge header course bands one course high (LI)	m	172	
	Waterproofing (CPAP Work Group No. 120)			
	Carried Forward Bill No. 19 External Works			R
- 1	A <sub>2</sub>	- 1	- 1	

**3** -214-

N. 65

	Brought Forward	1		R	Ĭ
	Two coats emulsion bitumen emulsion waterproof coating as per approval				
181	On bagged brick walls, piers, etc. (LI)	m2	131		
	One Layer "Derbigum" or other equally approved CG4 waterproofing membrane sealed to solvent based bitumen primed surface by means of torch fusion with minimum 100mm side laps and minimum 150mm end laps				
182	On retaining walls	m2	172		
183	Extra over waterproofing to walls for one layer of 'interdek' or other equally approved sheeting with a minimum lap of 200mm to receive backfilling (Back filling else where measured)	m2	172		
	Joint sealants etc				
	Polyurethaneor other equally approved sealing compound including backing cord, bond breaker, primer, etc.		-		
184	12 x 12mm In vertical expansion joints including raking out expansion joint filler as necessary	m	57		
	Two-part grey or other equally approved polysulphide sealing compound including backing cord, bond breaker, primer, etc				
185	15 x 10mm In horizontal expansion joints including raking out expansion joint filler as necessary	m	206		
	Drainage (CPAP Work Ground No. 146 Unless Otherwise Stated)				
	Slotted HDPE flexible drainage pipes				
186	110mm HDPE flexible slotted agricultural pipes laid behind retaining walls for a depth not exceeding 3m including 19mm crushed stone encasing 300 x 300mm, "Kaymat' U34 geofabric filter blanket wrapped around encasing with 150mm side and 300mm end laps including stitching and 300 x 300mm river sand. (LI)	m	172		
187	Extra over for 110mm cap (LI)	No	12		
188	Extra over for 110mm bend (LI)	No	19		
	Carried Forward Bill No. 19 External Works			R	
J	P	100	1	1	1

	Brought Forward	1		R
189	Extra over for 110mm access junction (LI)	No	7	
	BOUNDARY WALLS, FENCE AND GATES			
	Earthworks (CPAP Work Group No. 104)			
	Excavation other than bulk			
190	Trenches (LI)	m3	1 733	
	Extra over all excavations for loading, carting and dumping surplus excavated material, rubble, etc. (no allowance made for increase in bulk)			
191	Off site to a dumping site to be found by the Contractor.	m3	768	
	Risk of collapse of excavations			
192	Sides of trench and hole excavations not exceeding 1,5m deep	m2	1 925	
	Keeping excavations free of water			
193	Keeping excavations free of all water other than subterranean water		ltem	
	Compaction of surfaces			
194	Compaction of ground surface under strip footings, etc. including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 95% Mod AASHTO density	m2	866	
	Earth filling obtained from the excavations and/or prescribed stock piles on site, compacted to 95% Mod AASHTO density.			
195	Backfilling to trenches, holes, etc. (LI)	m3	965	
	Base course of earth filling supplied by the contractor under pavings, roads, etc			
196	Construct 150mm thick base layer, under strip footings, of G5 materials obtained from commercial sources, compacted to a density of at least 95% Mod. AASHTO density. (LI)	m3	260	
	Carried Forward Bill No. 19 External Works			R
Į	P	J,		

N. 4 55

	Brought Forward	ĺ		R	
	Prescribed density tests on filling				
197	Modified AASHTO Density tests	No	204		
	Weedkiller mixed with water and applied at a rate of 100grams/m2				
198	To sides and bottoms of trench excavations (LI)	m2	2 791		
	Concrete (CPAP Work Group No. 110)				
	Unreinforced concrete cast against excavated surfaces				
	15MPa/19mm concrete				
199	Blinding (LI)	m3	36		
	Reinforced concrete cast against excavated surfaces /or formworks				
	30MPa/19mm concrete				
200	Strip footings (LI)	m3	253		
	Test cubes				
201	Making and testing set of three 150 x 150 x 150mm concrete strength test cube (Provisional)	No	42		
	Formwork (CPAP Work Group No. 111)				
	Rough formwork to sides				
202	Strip footings (LI)	m2	385		
	Reinforcement (CPAP Work Group No. 114)				
	Mild and high tensile steel reinforcement to structural concrete work				
203	Various diameter bars (LI)	t	37,95		
	Masonry (CPAP Work Group No. 116)				
	Carried Forward			R	
	Bill No. 19 External Works				
	Pa 247	, ,			į

-217

J.h 5

	Brought Forward			R	Ĭ
	Brickwork of NFX bricks in class II mortar				
204	One and half brick walls in foundations (LI)	m2	626		
205	One and half brick walls (LI)	m2	298		
	Brickwork sundries				
	2.5mm Galvanised brickwork reinforcement				
206	155mm Wide reinforcement built in horizontally (LI)	m	7 244		
	Brickwork sundries				
	Bagging of 1:3 cement and sand mixture				
207	On brick walls, piers, etc. (LI)	m2	423		
	Joint forming material in movement joints				
208	12mm Bitumen impregnated fibre board built in vertically through brick walls exceeding 300mm wide (LI)	m2	108		
	Face brickwork				
	"Corojem Nebraska FBS" or other equally approved face bricks pointed with tinted recessed horizontal and vertical joints				
209	Extra over brickwork for face brickwork on both sides in foundations (LI)	m2	125		
210	Extra over brickwork for face brickwork on both sides of walls (LI)	m2	298		
211	Extra over brickwork for 345mm wide brick-on-edge header course bands one course high (LI)	m	481		
	Waterproofing (CPAP Work Group No. 120)				
	Two coats emulsion bitumen emulsion waterproof coating as per approval				
212	On bagged brick walls, piers, etc. (LI)	m2	423		
	Joint sealants etc				
	Carried Forward Bill No. 19 External Works			R	
	A 210	,			

B

1.0 S

	Brought Forward	Ī		R∥	ĺ
213	Polyurethaneor other equally approved sealing compound including backing cord, bond breaker, primer, etc.  12 x 12mm In vertical expansion joints including raking out expansion joint filler as necessary  Metalwork (CPAP Work Group No. 136)  Welded Mesh Fencing or other equal and approved	m	616		
214	invisible wall panels  1.80m High double skim clamber proof fence in panels 3.39m width with aperture size 12 x 12mm with 5x staining wires. Installed all in accordance with manufacturer's details	m	481		
215	Fence Posts  3,02m High intermediate fence post mild steel galvanised, size 85mm tapering to 45mm. Post to be built into 600mm into concrete base. Concrete base size 600 x 600 x 700mm deep with and including excavations, cart away, backfilling, etc.	No	143		
	Minimum 600mm high galvanised high tensile steel flat wrap razor wire fixed on 3x straining wires, staining wires fixed on metal brackets. Bracket fixed on brick wall. Installed all in accordance to manufacturer's details				
216	600mm High flat wrap razor wire on top of brick walls  Minimum 600mm high galvanised high tensile steel flat wrap razor wire fixed on 3x straining wires, staining wires fixed steel posts (steel posts elsewhere measured). Installed all in accordance to manufacturer's details	m	481		
217	600mm High flat wrap razor wire on top of steel fence	m	481		
	100mm Electro-galvanized, 2mm thick, toughened steel security spikes fixed on top of walls, fence, etc., installed all in accordance to manufacturer's details				
218	100mm Electro-galvanized security spikes fixed on top steel fence	m	481		
	Carried Forward Bill No. 19 External Works			R	



1.67

	Brought Forward	1		R	Ĭ
	Gates, screens, etc.				
	Gates, etc.				
219	A motorized double swing gate side hung gate fixed to brick walls / brick piers, size 4900 x 2180mm high. The access gate shall be manufactured from the same materials used for perimeter fencing on street boundaries. Provide that the gate must be lockable with a heavy-duty padlock from inside the premises. Heavy duty frame and ironmongery by specialist. All steel to be galvanised and prepared to receive two coats of primer & paint for steel/metal by Dulux/Plascon/Duram O.O.E.A. all to paint manufacturer's specification & instruction. Type D19 Tenderer's are referred to Architect's drawing No. UKU-A-1006-03, annexed to these bills of quantities.	No	3		
220	1430 x 2250mm High Titan full height free rotation turnstile by "Turnstar" or other equally approved and comprises of rotalok rotation locking mechanism and electronic control panel incorporates of anti-trap safety system, suspended Rotor technology, mechanical key override, shock absorbing rubber coupling, lockable top cover, 50mm diameter tube arms spaced 120mm apart, access control reader mounting position, rotarun perpetual base bearing, wiring side entry point, wiring bottom entry point, floor bolting positions, wall bolting positions, etc. and installed all in accordance to manufacturer's specifications.	No	1		
	Drainage (CPAP Work Ground No. 146 Unless Otherwise Stated)				
	Class 34 heavy duty uPVC pipes				
221	395mm Long weep pipe built into one brick walls with one end left 50mm projection in front of walls	No	803		
	DRIVEWAY AND PARKING AREA				
	(CPAP WORK GROUP NO. 154 UNLESS OTHERWISE STATED)				
	Excavation other than bulk				
222	Excavate to reduced level	m3	1 961		
	Carried Forward Bill No. 19 External Works			R	
		Į.	1	1	



p.00 SS

	Brought Forward			R	
	Extra over all excavations for loading, carting and dumping surplus excavated material, rubble, etc. (no allowance made for increase in bulk)				
223	Off site to a dumping site to be found by the Contractor.	m3	1 961		
	Keeping excavations free of water				
224	Keeping excavations free of all water other than subterranean water		Item		
	Compaction of surfaces				
225	Compaction of ground surface under pavings, roads etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density	m2	3 992		
	Base course of earth filling supplied by the contractor under pavings, roads, etc				
226	150mm Thick layer of G7 sub-base course under roads, parking areas, etc., with selected and approved natural G7 quality material, supplied and carted onto site by the contractor, compacted in layers of 150mm thickness to at least 95% Mod. AASHTO density.	m3	603		
227	150mm Thick layer of G5 sub-base course under roads, parking areas, etc., with selected and approved natural G5 quality material, supplied and carted onto site by the contractor, compacted in layers of 150mm thickness to at least 95% Mod. AASHTO density.	m3	12		
228	150mm Thick layer of C4 stabilized sub-base course under roads, parking areas, etc., stabilised cement in accordance with SABS 1200 DM, with selected and approved natural G5 quality material, supplied and carted onto site by the contractor, compacted in layers of 150mm thickness to at least 98% Mod. AASHTO density.	m3	587		
229	200mm Thick layer of C4 stabilized sub-base course under roads, parking areas, etc., stabilised cement in accordance with SABS 1200 DM, with selected and approved natural G5 quality material, supplied and carted onto site by the contractor, compacted in layers of 200mm thickness to at least 98% Mod. AASHTO density.	m3	32		
	Carried Forward Bill No. 19 External Works			R	
	(3)				

	Brought Forward	l I	I	R	i i
230	150mm Thick layer of G3 sub-base course under roads, parking areas, etc., with selected and approved natural G3 quality material, supplied and carted onto site by the contractor, compacted in layers of 150mm thickness to at least 98% Mod. AASHTO density.	m3	591		
	Testing of material and filling				
	Descriptions of earth filling, compaction, etc shall be deemed to include for all necessary testing required in accordance with the SABS 1200 series				
	The items of testing given below are for additional testing which may be required by the Engineer over and above those required in accordance with the SABS 1200 series				
	Additional tests required by Engineer				
231	Maximum dry density and optimum moisture content test in accordance with Method A7 of TMH 1	No	103		
232	Atterberg limits test in accordance with methods A2 to A4 of TMH 1	No	68		
233	In-situ dry density test in accordance with method A10(b) of TMH 1		Item		
	Weedkiller mixed with water and applied at a rate of 100grams/m2				
234	Under parking area, etc. (LI)	m2	3 205		
	Bituminous premix road surfacing				
235	Supply and apply primer coat on crusher base layer. Prime that complies with the requirements of SABS 748 or 749. MC-30 or MC-70 that complies with the requirements of SABS 308.	m2	3 126		
236	Supply and construct continuously medium graded hot premix asphalt surfacing layer 40mm thick (compacted thickness) 40/50 pen bitument 9.5mm stone to roadways compacted to 96% Marshal density and laid to falls	m2	3 126		
	Carried Forward Bill No. 19 External Works			R	



M

	Brought Forward		Ì	R	
	Precast concrete finished smooth on exposed surfaces including bedding, jointing and pointing				
237	Kerb (SABS 927 fig 9) 150 x 300mm high with 525 x 100mm unreinforced concrete base including excavation, backfilling, haunching at back of each joint, etc. (Type: Barrier kerb BK2)	m	745		
238	Kerb (SABS 927 fig 9) 150 x 300mm high with 525 x 100mm unreinforced concrete base circular on plan not exceeding 4m radius formed with short lengths of straight kerb including excavation, backfilling, haunching at back of each joint, etc. (Type: Barrier kerb BK2)	m	49		
239	Kerb (SABS 927 fig 12) 75 x 150mm high with 286 x 70mm unreinforced concrete base including excavation, backfilling, haunching at back of each joint, etc. (Type: Edging E1)	m	400		
240	Kerb (SABS 927 fig 12) 75 x 150mm high with 300 x 70mm unreinforced concrete base including excavation, backfilling, haunching at back of each joint, etc. (Type: Edging E3)	m	120		
241	Barrier kerb and channel formed of kerb (SABS 927 fig 9) 150 x 300mm high and kerb (SABS 927 fig 8C) 300 x 200mm high with 935 x 100mm unreinforced concrete base including excavation, backfilling, haunching at back of each joint, etc. (Type: Barrier kerb and channel BK2 + C1)	m	50		
242	Barrier kerb and channel formed of kerb (SABS 927 fig 9) 150 x 300mm high and kerb (SABS 927 fig 8C) 300 x 200mm high with 935 x 100mm unreinforced concrete base circular on plan not exceeding 4m radius formed with short lengths of straight kerb including excavation, backfilling, haunching at back of each joint, etc. (Type: Barrier kerb and channel BK2 + C1)	m	34		
243	V-channel formed of 2x kerbs (SABS 927 fig 8C) 300 x 200mm high with 1010 x 100mm unreinforced concrete base including excavation, backfilling, haunching at back of each joint, etc. (Type: C1 + C1 V-channel)	m	160		
	<u>Masonry</u>				
244	80mm 'Corobrick' or other equally approved interlocking paving bricks laid in herringbone pattern to SANS 1200MJ, bricks laid on 25mm sand layer	m2	79		
	Carried Forward			R	
	Bill No. 19 External Works				



-223-

6 ss 31

	Brought Forward			R	
	<u>Paintwork</u>				
	Prepare and apply one coat non reflective road marking paint at a nominal rate of 0.42l/m² on bituminous road surfacing, pre-cast concrete paving blocks, etc.				
245	100mm Wide solid lines to parking demarcation bays, etc.	m	782		
246	5,0m Long directional arrows	No	16		
247	6,0m Long curved directional arrows	No	12		
248	1,3m Long letters to 'STOP' sign, etc.	No	4		
249	11 x 1,5m Wide pedestrian walkway	No	1		
250	Disabled parking bay sign approximately 1,2m high	No	5		
251	Ambulance parking sign approximately 1,2m high	No	1		
252	Painted white parking numbers	No	97		
	DOMESTIC WATER STORAGE TANKS AND PUMPS				
	Metalwork (CPAP Work Group No. 136)				
	Hot Dipped Galvanised Sundry Steelwork				
253	Supply, delivery, installation, connection, testing & commissioning of tank infill system pipe, ML, 50mm pipes		Item		
	Mechanical (CPAP Work Group No. 170)				
	Carried Forward			R	
	Bill No. 19 External Works				



-224-

mb 5 312

1	Brought Forward			R	
	Supply and deliver the following booster pumps ("KSB" or other approved), complete with all with electrical connection to isolator, intenal pump house reticulation piping- and drain piping, electrical control wiring, brackets, supports, steel bases, control panel and all necessary accessories, as per the specification and manufacturer's recommendation.				
254	Supply, delivery, installation, connection, testing & commissioning of complete domestic water Bi-Plex Electric pump set including valves, vacuum breaks, auto air vents, etc. Pumps to operate Duty and Standby. Each Pump sized for 270 L/m @2.18bar	No	1		
255	Supply, delivery, installation, connection, testing & commissioning of pump control panels		Item		
256	Supply, delivery, installation, connection, testing & commissioning of all electrical work in the pump house		Item		
257	190 x 190mm Photoluminescent pictograms statutory signs on chromadek or other equally approved material	No	11		
258	Supply, delivery, installation, connection, testing & commissioning of trunk mains from pump house to building		ltem		
	SABS approved Black Mild Steel pipes including all holderbats and couplings in the running length with welded type fittings to be used. All pipe in wall/floor chases to be wrapped twice in brown Kraft paper. Pipes passing through opening in brickwork or slab shall be coated with DENZO Protective pipe wrapping. All pipes to be painted with one coat primer and two coats signal red.				
259	40mm Pipes (LI)	m	31		
	Pipework, valves, fittings, etc.				
260	2500kPa Pressure gauge	No	8		
261	Domestic water pump test meter	No	1		
262	100mm Butterfly valve	No	2		
263	150mm Butterfly valves	No	3		
	Carried Forward Bill No. 19 External Works			R	
	(2)			m - F	m Ti



-225-

	Brought Forward			R
264	150mm Non-return valve	No	2	
265	150mm Expansion joints	No	4	
266	150mm Strainer	No	1	
267	150mm Gate valve	No	3	
268	250mm Gate valve	No	2	
269	Vortex impellers	No	2	
270	Pressure switch	No	5	
271	20mm Ball valve	No	5	
272	20mm Check valve	No	4	
273	50mm Rubber expansion joints	No	2	
274	50mm Check valve	No	1	
275	50mm Ball valve	No	1	
276	Membrane vessel	No	1	
277	100mm Brass elbows	No	5	
278	150mm Brass elbows	No	4	
279	250mm Brass elbows	No	3	
280	150mm Brass tee-pieces	No	2	
281	250mm Brass tee-pieces	No	1	
282	100mm Brass straight piping	No	8	
283	150mm Brass straight piping	No	30	
284	250mm Brass straight piping	No	18	
	FIRE WATER STORAGE TANKS AND PUMPS			
	Metalwork (CPAP Work Group No. 136)			
	Carried Forward Bill No. 19 External Works			R
ļ	2			



	Brought Forward	Ĩ	1	R	Ĩ
	Hot Dipped Galvanised Sundry Steelwork				
285	Supply, delivery, installation, connection, testing & commissioning of Cylindrical 235KL effective capacity dedicated fire storage tank for adequate supply of fire system including flanges, connections, fittings, hangers, brackets, vortex inhibitor, water level indicator, water inlets, water outlets to fire pumps, catladder, access hatches, valves, drains, etc complete. Reference to be made to DWG D0000-MF-A1-03 and technical specification when pricing, annexed to these bills of quantities.	No	1		
286	Supply, delivery, installation, connection, testing & commissioning of tank infill		Item		
	Mechanical (CPAP Work Group No. 170)				
	Supply and deliver the following booster pumps ("KSB" or other approved), complete with all with electrical connection to isolator, intenal pump house reticulation piping- and drain piping, electrical control wiring, brackets, supports, steel bases, control panel and all necessary accessories, as per the specification and manufacturer's recommendation.				
287	Supply, delivery, installation, connection, testing & commissioning of complete fire water (Electric) pump set including valves, vacuum breaks, auto air vents, etc. Electric pump sized for 2400 L/m @12.08bar, Electrical Jockey pump sized for 60 L/min @12.08bar)	No	1		
288	Supply, delivery, installation, connection, testing & commissioning of pump control panels		Item		
289	Supply, delivery, installation, connection, testing & commissioning of all electrical work in the pump house		ltem		
290	190 x 190mm Photoluminescent pictograms statutory signs on chromadek or other equally approved material	No	11		
291	Supply, delivery, installation, connection, testing & commissioning of trunk mains from pump house to installation of control valves		ltem		
	Carried Forward Bill No. 19 External Works			R	
			2		



-227

	Brought Forward	1	Ì	R	Ĭ
	SABS approved Black Mild Steel pipes including all holderbats and couplings in the running length with welded type fittings to be used. All pipe in wall/floor chases to be wrapped twice in brown Kraft paper. Pipes passing through opening in brickwork or slab shall be coated with DENZO Protective pipe wrapping. All pipes to be painted with one coat primer and two coats signal red.				
292	40mm Pipes (LI)	m	25	1	
293	100mm Pipes (LI)	m	23		
	Pipework, valves, fittings, etc.				
294	2500kPa Pressure gauge	No	8		
295	Fire water pump test meter	No	1		
296	100mm Butterfly valve	No	2		
297	150mm Butterfly valves	No	3		
298	150mm Non-return valve	No	2		
299	150mm Expansion joints	No	4		
300	150mm Strainer	No	1		
301	150mm Gate valve	No	3		
302	250mm Gate valve	No	2		
303	Vortex impellers	No	2	i	
304	Pressure switch	No	5		
305	20mm Ball valve	No	5		
306	20mm Check valve	No	4		
307	50mm Rubber expansion joints	No	2		
308	50mm Check valve	No	1		
309	50mm Ball valve	No	1		
	Carried Forward Bill No. 19 External Works			R	

-228-

	Brought Forward	Ī	1	R	
310	Membrane vessel	No	1		
311	100mm Black mild steel elbows	No	5		
312	150mm Black mild steel elbows	No	4		
313	250mm Black mild steel elbows	No	3		
314	150mm Black mild steel tee-pieces	No	2		
315	250mm Black mild steel tee-pieces	No	1		
316	100mm Black mild steel straight piping	No	8		
317	150mm Black mild steel straight piping	No	30		
318	250mm Black mild steel straight piping	No	18		
	Auxiliary equipment				
	Allow for all auxiliary equipment as specified in this document as well as the SANS 10287 code of practice, incl. valves, fittings supports, fire detection, ventilation, sprinkler protection to pumphouse, etc. Pricing to be in accordance with requirements of pump room as per D0000- MB-A1-03				
319	Ventilation fan sized for 30 Air changes per hour	No	1		
320	Upright Sprinkler head directly above pump inclusive of range piping	No	2		
321	250L Diesel tank with bund	No	1		
322	Pumproom alarm siren and strobe	No	1		
323	Fire retardant cable Class A wiring (ph 30)	m	10		
324	25mm PVC conduit in accordance with SANS 10139	m	10		
	WATER TANK BASE AND PLINTH				
	Earthworks (CPAP Work Group No. 104)				
	Excavation in earth not exceeding 2m deep				
325	Reduced levels under floors (LI)	m3	16		
	Carried Forward Bill No. 19 External Works			R	



	Brought Forward			R	
326	Edge thickening (LI)	m3	3		
	Extra over all excavations for carting away				
327	Surplus material from excavations and/or stock piles on site,to a dumping site to be located by the contractor	m3	19		
	Risk of collapse of excavations				
328	Sides of trench and hole excavations exceeding 1,5m and not exceeding 3m deep	m2	12		
	Compaction of surfaces				
329	Compaction of ground surface under floors, etc. including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% mod AASHTO density	m2	27		
	Earth filling of G5 material supplied by contractor from commercial sources in accordance with SABS 1200 DM compacted to 98% Mod AASHTO density in 150mm thick layers				
330	Under floors, steps, pavings, etc. (LI)	m3	8		
	Prescribed density tests on filling				
331	Modified AASHTO Density tests	No	2		
	Approved brand of anti-termite soil poison applied by a Registered Pest Control company and guaranteed against termite infestation for ten years				
332	Under floors, sides, etc. including forming and poisoning shallow furrows against foundation walls etc., filling in furrows and ramming (LI)	m2	39		
	Concrete (CPAP Work Group No. 110)				
	Reinforced concrete cast against excavated surfaces				
	30MPa/19mm concrete				
333	Surface base (LI)	m3	8		
	Bill No. 19 External Works			R	



\$ 19

Ì	Brought Forward			R	
334	Edge thickening (LI)	m3	3		
	Reinforced concrete cast against on/in formwork				
	30MPa/19mm concrete				
335	Upstand beams (Plinth) (LI)	m3	4		
	Test cubes				
336	Making and testing set of three 150 x 150 x 150mm concrete strength test cube (Provisional)	No	3		
	Concrete sundries				
	Finishing top surfaces of concrete smooth with a wood float				
337	Surface beds, slabs, etc. (LI)	m2	27		
	40Mpa Non-shrink grout:				
338	Bedding approximately 250 x 40mm thick	m	31		
	Formwork (CPAP Work Group No. 111)				
	Smooth formwork to sides				
339	Upstand beams (Plinth) (LI)	m2	28		
340	Edges, risers, ends and reveals not exceeding 300mm high or wide (LI)	m	21		
	Reinforcement (CPAP Work Group No. 114)				
	High tensile steel reinforcement to structural concrete work				
341	Bars of various diameters (LI)	t	2,55		
	Waterproofing (CPAP Work Group No. 120)			2.5	
	One layer of 375 micron waterproof sheeting sealed at laps as per approval				
342	Under surface beds including sides (LI)	m2	39		
	Carried Forward Bill No. 19 External Works			R	
		1 1	Į.)	J	



-231-

ĺ	Brought Forward		Ť	R
	Metalwork (CPAP Work Group No. 136)			
	80 x 8mm Thick heavy duty GMS plate fixed on to reinforced concrete plinth			
343	5180mm long flat plate	No	6	
	SAND, OIL AND GREASE TRAP			
	Earthworks (CPAP Work Group No. 104)			
	Excavation in earth not exceeding 2m deep			
344	Holes (LI)	m3	9	
	Extra over all excavations for carting away	,		
345	Surplus material from excavations and/or stock piles on site, to a dumping site to be located by the contractor	m3	8	
	Risk of collapse of excavations			
346	Sides of trench and hole excavations exceeding 1,5m and not exceeding 3m deep	m2	17	
	Compaction of surfaces			
347	Compaction of ground surface under floors, etc. including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% mod AASHTO density	m2	7	
	Earth filling obtained from excavations and/or prescribed stock piles on site, compacted to 95% Mod AASHTO density			
348	Backfilling to trenches, holes, etc. (LI)	m3	1	
	Prescribed density tests on filling			
349	Modified AASHTO Density tests	No	2	
	Ossuited Foreign			R
	Carried Forward Bill No. 19 External Works			IX.



55 ,5

	Brought Forward			R	
	Approved anti-termite soil insecticide applied by a Registered Pest Control Company and guaranteed against termite infestation for ten years including forming and poisoning shallow furrows along sides of foundation walls, etc., filling in and ramming:				
350	Under floors, sides, etc. including forming and poisoning shallow furrows against foundation walls etc., filling in furrows and ramming (LI)	m2	24		
	Concrete (CPAP Work Group No. 110)				
	Reinforced concrete cast against excavated surfaces and/or formwork				
	30MPa/19mm concrete				
351	Surface base (LI)	m3	2		
	Reinforced concrete cast against on/in formwork				
	30MPa/19mm concrete				
352	Slabs (LI)	m3	1		
	Test cubes				
353	Making and testing set of three 150 x 150 x 150mm concrete strength test cube (Provisional)	No	2		
	Concrete sundries				
	Finishing top surfaces of concrete smooth with a wood float				
354	Surface beds, slabs, etc. (LI)	m2	13		
	Formwork (CPAP Work Group No. 111)				
	Smooth formwork to soffits				
355	Slabs, propped up not exceeding 3.5m high (LI)	m2	6		
	Smooth formwork to sides				
356	Edges, risers, ends and reveals not exceeding 300mm high or wide (LI)	m	39		
	Carried Forward			R	
	Bill No. 19 External Works				



S ...

	Brought Forward	1		R		
	Boxing in smooth formwork to form					
357	Extra over formwork to form opening size 225 x 225mm through 180mm thick slab (LI)	No	2			
358	Extra over formwork to form opening size 550mm diameter through 180mm thick slab (LI)	No	3			
	Movement Joints, Etc.					
	Two sheets of tempered hardboard (smooth sides together) to form slip joint between abutting horizontal concrete and brickwork surfaces					
359	Not exceeding 300mm wide (LI)	m	14			
	Reinforcement (CPAP Work Group No. 114)					
	High tensile steel reinforcement to structural concrete work					
360	Bars of various diameters (LI)	t	0,15			
	Fabric reinforcement					
361	Type Ref. 193 fabric reinforcement in concrete surface beds, slabs, etc. <b>(LI)</b>	m2	7			
	Masonry (CPAP Work Group No. 116)					
	Brickwork of NFX bricks in class II mortar					
362	Half brick walls (LI)	m2	3			
363	One brick walls (LI)	m2	9			
	Brickwork sundries					
	2.5mm Galvanised brickwork reinforcement					
364	75mm Wide reinforcement built in horizontally (LI)	m	12			
365	155mm Wide reinforcement built in horizontally (LI)	m	35			
	Waterproofing (CPAP Work Group No. 120)					
	Carried Forward Bill No. 19 External Works			R		
		į j	l		1	£.



55 .00



	Brought Forward	1	ľ	R	
	One layer of 375 micron Brikgrip DPC embossed damp proof course as per approval				
366	In walls (LI)	m2	3		
	One layer of 375 micron waterproof sheeting sealed at laps as per approval				
367	Under surface beds (LI)	m2	7		
	Drainage (CPAP Work Ground No. 146 Unless Otherwise Stated)				
	uPVC pipes cast into concrete slabs, fixed to soffit and walls, or chased into walls, chased into concrete, etc. in accordance with manufacturers specifications				
368	110mm Pipes (LI)	m	9		
	Extra over uPVC pipes for:				
369	110mm Bend ( <b>LI</b> )	No	5		
370	110mm Junction (LI)	No	2		
	Gratings, covers, etc.				
371	225 x 255mm, cast iron cover and frame including	No	2		
372	550mm Diameter x 176kg, type 2A cast iron cover and frame including	No	3		
	ATTENUATION TANKS (2 NO.)				
	Earthworks (CPAP Work Group No. 104)				
	Excavation in earth not exceeding 2m deep				
373	Holes (LI)	m3	306		
	Excavation in earth exceeding 2m and not exceeding 4m deep				
374	Holes (LI)	m3	173		
	Carried Forward Bill No. 19 External Works			R	-
	-235-	85 \$	<b>(b)</b>	32.	3



	Brought Forward		1	R	
	Extra over bulk excavation in earth for excavation in:				
375	Intermediate material	m3	48		
376	Hard material	m3	24		
0,0	Extra over all excavations for loading, carting and dumping surplus excavated material, rubble, etc. (no allowance made for increase in bulk)				
377	Off site to a dumping site to be found by the Contractor.	m3	387		
	Keeping excavations free of water				
378	Keeping excavations free of all water other than subterranean water		Item		
	Risk of collapse of excavations				
379	Risk of collapse of sides of trenches and holes exceeding 1,5m deep	m2	228		
	Compaction of surfaces				
380	Compaction of ground surface under bases etc., including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 95% Mod. AASHTO density	m2	153		
	Earth filling obtained from excavations and/or prescribed stock piles on site, compacted to 95% Mod AASHTO density				
381	Backfilling to trenches, holes, etc. (Li)	m3	92		
	Earth filling of G5 material supplied by contractor from commercial sources in accordance with SABS 1200 DM compacted to 98% Mod AASHTO density in 150mm thick layers				
382	Under floors, steps, pavings, etc. (LI)	m3	69		
	Prescribed density tests on filling				
383	Modified AASHTO Density tests	No	27		
	Carried Forward Bill No. 19 External Works			R	
			J	J	



324

750 <<

	Brought Forward			R		
	Approved brand of anti-termite soil poison applied by a Registered Pest Control company and quaranteed against termite infestation for ten years					
384	Under floors, sides, etc. including forming and poisoning shallow furrows against foundation walls etc., filling in furrows and ramming (LI)	m2	381			
	Concrete (CPAP Work Group No. 110)					
	Unreinforced concrete cast against excavated surfaces					
	15MPa/19mm concrete					
385	Blinding (LI)	m3	10			
	Reinforced concrete cast against excavated surfaces and/or formwork					
	35MPa/19mm concrete					
386	Surface base (LI)	m3	36			
	Reinforced concrete cast against on/in formwork					
	35MPa/19mm concrete					
387	Walls (LI)	m3	37			
388	Slabs (LI)	m3	36			
	Test cubes					
389	Making and testing set of three 150 x 150 x 150mm concrete strength test cube (Provisional)	No	18			
	Concrete sundries					
	Finishing top surfaces of concrete smooth with a wood float					
390	Surface beds, slabs, etc. (LI)	m2	237			
	Formwork (CPAP Work Group No. 111)					
	Carried Forward Bill No. 19 External Works			R		
-		1			l,	1

6

-237-

N.99 45

	Brought Forward			R	
	Smooth formwork to sides				
391	Walls, propped up not exceeding 3.5m high (LI)	m2	125		
392	Edges, risers, ends and reveals not exceeding 300mm high or wide (LI)	m	130		
	Smooth formwork to soffits				
393	Slabs exceeding 250mm and not exceeding 500mm thick, propped up not exceeding 3.5m high (LI)	m2	119		
	Boxing in smooth formwork to form				
394	Extra over formwork to form opening size 375mm diameter through 300mm thick walls (LI)	No	4		
395	Extra over formwork to form opening size 1000 x 1000mm through 300mm thick slab (LI)	No	2		
	Reinforcement (CPAP Work Group No. 114)				
	High tensile steel reinforcement to structural concrete work				
396	Bars of various diameters (LI)	t	18,53		
	Galvanised wire support. Tenderer's are refer to Civil Engineer drawing no.: 23023-STR-007 for details, annexed to these bills of quantities.				
397	Approximate 300mm R10 clip (LI)	No	434		
398	Approximate 250mm Y10 clip (LI)	No	434		
	Drainage (CPAP Work Ground No. 146 Unless Otherwise Stated)				
	Gratings, covers, etc.				
399	1000 x 1000mm, cast iron cover and frame including	No	2		
	COVERED WALKWAY				
	Earthworks (CPAP Work Group No. 104)				
	Carried Forward			R	
	Bill No. 19 External Works				
					Į,



-238-

N.B <5

١	Brought Forward	1	1	R
	Excavation in earth not exceeding 2m deep			
400	Bases	m3	58	
	Extra over all excavations for carting away			
401	Surplus material from excavations and/or stock piles on site,to a dumping site to be located by the contractor	m3	30	
	Risk of collapse of excavations			
402	Sides of trench and hole excavations exceeding 1,5m and not exceeding 3m deep	m2	192	
	Compaction of surfaces			
403	Compaction of ground surface under bases, etc. including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% mod AASHTO density	m2	58	
	Earth filling obtained from excavations and/or prescribed stock piles on site, compacted to 95% Mod AASHTO density			
404	Backfilling to trenches, holes, etc.	m3	28	
	Earth filling of G5 material supplied by contractor from commercial sources in accordance with SABS 1200 DM compacted to 98% Mod AASHTO density in 150mm thick layers			
405	Under bases, etc.	m3	9	
	Prescribed density tests on filling			
406	Modified AASHTO Density tests	No	2	
	Concrete (CPAP Work Group No. 110)			
	Unreinforced concrete cast against excavated surfaces			
	15MPa/19mm concrete			
407	Surface blinding under bases	m3	3	
	Carried Forward			R
	Bill No. 19 External Works			



-239-

v. 85

	Brought Forward			R	1
	Reinforced concrete cast against excavated surfaces and/or formwork				
	30MPa/19mm concrete				
408	Base	m3	17		ı
	Reinforced concrete cast against on/in formwork				
	30MPa/19mm concrete				
409	Stub columns	m3	2		
	Test cubes				
410	Making and testing set of three 150 x 150 x 150mm concrete strength test cube (Provisional)	No	3		
	40Mpa Non-shrink grout				
411	Bedding approximately 25mm thick under base plate including chamfered edges all round	m2	2		
	Holding down bolts, etc				
412	Set out and embed 100mm long M12 holding down bolts with 30 x 30 end plates in top of concrete in exact				
	position	No	160		
	Formwork (CPAP Work Group No. 111)				
	Smooth formwork to sides				
413	Stub columns	m2	19		
	Reinforcement (CPAP Work Group No. 114)				
414	Various diameter bars in high tensite steel reinforcement	t	2,25		
	Roof Coverings, Etc. (CPAP Work Group No. 124)				
	Carried Forward Bill No. 19			R	
	External Works				

-240

	Brought Forward			R	
	0.6mm thick colour coated galvanised sheet metal double-interlocking concealed fix profiled roofing fixed to timber purlins (timber purlins elsewhere measured)				
415	Roof covering with pitches not exceeding 25 degrees fixed at walkways.	m2	142		
	Sundries				
416	Ridge capping 550mm girth 3 times bent and notched on site to suit roof profile	m	59		
417	Hip capping 550mm girth 3 times bent and notched on site to suit roof profile	m	5		
	0.6mm aluminium sheet				
418	Lining to valleys with riveted and sealed joints, with girth not exceeding 600mm.	m	5		
	Carpentry and Joinery (CPAP Work Group No. 126)				
	Pre-treatment of timber				
	This service falls within the areas defined in the National Building Regulations for treatment of timber against insect infestation / insect pest affecting softwood fixed permanently in all buildings.				
	The regulations require that the timber be treated in terms of SABS 05 and to comply with SABS 457, 753, 754 or 1288 as relevant. Tenderer's are to make allowance in there rates.				
	Sawn softwood:				
419	50 x 75mm Purlins	m	354		
420	50 x 228mm Rafter	m	113		
	Laminated Wrot Saligna				
421	76 x 222mm Beams	m	116		
	Carried Forward Bill No. 19 External Works			R	
1				0.90	E 01



Q.

1	Brought Forward			R	Ì
	"Everite Nutec" or other equally approved medium density pressed fibre-cement				
422	15 x 255mm Fascias, including galvanised steel H-profile joiners	m	116		
423	80 x 275mm Angle section barge board, including galvanised steel H-profile joiners	m	5		
	Metalwork (CPAP Work Group No. 136)				
	Hot Dipped Galvanised Sundry Steelwork				
	Brackets, posts, etc. to roof timbers, etc.				
424	100 x 100 x 3mm Hollow section post 2750mm high with 200 x 200 x 10mm thick base plate welded to one end and the other end welded to and including purpose made U-shaped bracket to suit 76 x 222mm high timber beam (Timber beam elsewhere measured) with 6 No. M8 pre-drilled holes on bracket and 4 No. M10 pre-drilled holes on base plate to suit site conditions.	No	40		
	Plumbing an Drainage (CPAP Work Group No. 148)				
	0.9mm Pre-coated aluminium seamless gutter colour brown with baked enamel finish, including hanger brackets, etc.				
425	Purpose made 150 x 125mm Eaves gutters	m	116		
426	Extra over gutter for stop end	No	4		
427	Extra over gutter for corner	No	8		
428	Extra over gutter for outlet	No	18		
	0.9mm Pre-coated aluminium seamless rainwater downpipes colour brown with baked enamel finish including holder butts, etc.				
429	100 x 100mm Rainwater downpipes	m	55		
430	Extra on rainwater pipe for bend	No	36		
431	Extra on rainwater pipe for shoe	No	18		
	Carried Forward			R	
	Bill No. 19 External Works				
					J.



-242-

55

1	Brought Forward		Ĩ	R	
	Paintwork (CPAP Work Group No. 152)				
	Two coats Carbolineum				
132	On exposed trusses (LI)	m2	122		
	One coat primer, one coat universal undercoat and two coats "Velvaglo Polyurethane Enamel" or equal and approved paint				
133	On fascia and barge boards (LI)	m	121		
	Prepare and apply one coat of zinc chromate primer one coat universal undercoat and two coats of universal SABS approved gloss enamel paint.  Colour to be chosen by Architect.				
134	On steel posts (LI)	m2	44		
	COVERED CARPORTS				
	Earthworks (CPAP Work Group No. 104)				
	Excavation in earth not exceeding 2m deep				
135	Bases (LI)	m3	213		
	Extra over all excavations for carting away				
136	Surplus material from excavations and/or stock piles on site,to a dumping site to be located by the contractor	m3	116		
	Risk of collapse of excavations				
137	Sides of trench and hole excavations exceeding 1,5m and not exceeding 3m deep	m2	656		
	Compaction of surfaces				
438	Compaction of ground surface under bases, etc. including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% mod AASHTO density	m2	186		
	Carried Forward Bill No. 19 External Works			R	
				1	



	Brought Forward			R	
	Earth filling obtained from excavations and/or prescribed stock piles on site, compacted to 95% Mod AASHTO density				
439	Backfilling to trenches, holes, etc. (LI)	m3	97		
	Earth filling of G5 material supplied by contractor from commercial sources in accordance with SABS 1200 DM compacted to 98% Mod AASHTO density in 150mm thick layers				
440	Under bases, etc. (LI)	m3	25		
	Prescribed density tests on filling				
441	Modified AASHTO Density tests	No	20		
	Concrete (CPAP Work Group No. 110)				
	Unreinforced concrete cast against excavated surfaces				
	15MPa/19mm concrete				
442	Surface blinding under bases (LI)	m3	9		
	Reinforced concrete cast against excavated surfaces and/or formwork				
	30MPa/19mm concrete				
443	Base (LI)	m3	65		
	Reinforced concrete cast against on/in formwork				
	30MPa/19mm concrete				
444	Stub columns (LI)	m3	18		
	Test cubes				
445	Making and testing set of three 150 x 150 x 150mm concrete strength test cube (Provisional)	No	14		
	40Mpa Non-shrink grout				
446	Bedding approximately 25mm thick under base plate including chamfered edges all round	m2	21		
	Carried Forward			R	
	Bill No. 19 External Works				
1			,I	<b>II</b> ,	ļ



-244

	Brought Forward			R	
	Holding down bolts, etc				
447	Set out and embed 100mm long M12 holding down bolts with 30 x 30 end plates in top of concrete in exact position	No	408		
	Formwork (CPAP Work Group No. 111)				
	Smooth formwork to sides				
448	Stub columns (LI)	m2	158		
	Reinforcement (CPAP Work Group No. 114)				
449	Various diameter bars in high tensile steel reinforcement (LI)	t	9,91		
	Structural Steel (CPAP Work Group No. 134)				
	Welded columns in single lengths with flat section base, top, bearer and connection plates bolted to reinforced concrete at bottom and parallel flanged channel at top				
450	100 x 100 x 4 SHS Columns	t	3,49		
	Welded beams in single lengths with flat section bearer and connection plates bolted to columns				
451	150 x 100 x 3 RHS Beams	t	3,94		
	Welded purlins, bracing, trimmers, eaves runner, etc. with flat section connection plates bolted to steel				
452	150 x 75 x 20 x 2.5 CFLC purlins	t	6,99		
453	45 x 45 x 3 Angle bracing	t	1,02		
454	50 x 50 x 5 Angle bracing	t	3,55		
	Sundry Steelwork				
455	Cleats, plates, gussets, connectors, etc.	t	8,75		
	Paintwork				
	Carried Forward Bill No. 19 External Works			R	

-245

N.00 <<

	Brought Forward	1	Î	R	l	Î
	Remove all grease and oil by washing with a water emulsifiable solvent degreaser and rinsing with potable water, dry abrasive blast to rear white metal in accordance with Sa 2.5 of the International Standard ISO 850-1 to obtain a surface profile of 25 - 75 microns and apply one coat Inter guard 269 galvanizing primer and two coats Interthane 990 recoatable polyurethane					
456	On columns, beams, purlins, angles, etc.	t	18,99			
457	On cleats, plates, gussets, connectors, etc.	t	8,75			
	Roof Coverings, Etc. (CPAP Work Group No. 124)					
	Profiled Metal Sheeting and Accessories					
	0.6mm thick colour coated galvanised sheet metal double-interlocking concealed fix profiled roofing fixed to steel purlins (steel purlins elsewhere measured)					
458	Roof covering with pitch not exceeding 25 degrees	m2	1 202			
	Sundries					
459	Barge flashing, 550mm girths	m	276			1
460	Fascia flashing, 550mm girths	m	206			
	Plumbing an Drainage (CPAP Work Group No. 148)					
	0.9mm Pre-coated aluminium seamless gutter colour brown with baked enamel finish, including hanger brackets, etc.					
461	Purpose made 150 x 125mm Eaves gutters	m	206			
462	Extra over gutter for stop end	No	22			
463	Extra over gutter for outlet	No	32			
	0.9mm Pre-coated aluminium seamless rainwater downpipes colour brown with baked enamel finish including holder butts, etc.					
464	100 x 100mm Rainwater downpipes	m	101			
	Carried Forward Bill No. 19 External Works			R		
					I	



N. SS

ĺ	Brought Forward		ľ	R	
465	Extra over rainwater pipe for bend	No	64		
466	Extra over rainwater pipe for shoe	No	32		
	RAINWATER TANKS AND BASES				
	Earthworks (CPAP Work Group No. 104)				
	Excavation in earth not exceeding 2m deep				
467	Reduced level (LI)	m3	19		
468	Edge thickening (LI)	m3	4		
	Extra over all excavations for carting away				
469	Surplus material from excavations and/or stock piles on site,to a dumping site to be located by the contractor	m3	23		
	Risk of collapse of excavations				
470	Risk of collapse of sides of trench excavations exceeding 1.5m deep	m2	23		
	Compaction of surfaces				
471	Compaction of ground surface under floors compacted to 95% Mod. AASHTO density	m2	34		
	Earth filling of G5 material supplied by contractor from commercial sources in accordance with SABS 1200 DM compacted to 98% Mod AASHTO density in 150mm thick layers				
472	Under floors, steps, pavings, etc. (LI)	m3	10		
	Prescribed density tests on filling				
473	Modified AASHTO Density tests	No	2		
	Carried Forward			R	
	Bill No. 19 External Works				
			'		"



N.W 55

Ц	Brought Forward	1		R
	Approved anti-termite soil insecticide applied by a Registered Pest Control Company and guaranteed against termite infestation for ten years including forming and poisoning shallow furrows along sides of foundation walls, etc., filling in and ramming:			
474	Under floors, sides, etc. including forming and poisoning shallow furrows against foundation walls etc., filling in furrows and ramming (LI)	m2	49	
	Concrete (CPAP Work Group No.110)			
	Reinforced concrete cast against excavated surfaces and/or formwork			
	30MPa/19mm concrete			
475	Surface bed (LI)	m3	8	
476	Edge thickening (LI)	m3	4	
	Test Cubes			
477	Making and testing set of three 150 x 150 x 150mm concrete strength test cube (Provisional)	No	2	
	Concrete Sundries			
	Finishing top surfaces of concrete smooth with a wood float			
478	Surface beds, slabs, etc. (LI)	m2	34	
	Formwork (CPAP Work Group No. 111)			
	Smooth formwork to sides			
479	Edges, risers, ends and reveals not exceeding 300mm high or wide (LI)	m	27	
	Reinforcement (CPAP Work Group No. 114)			
	Fabric reinforcement			
480	Type ref. 193 fabric reinforcement in concrete surface beds, slabs, etc. (LI)	m2	34	
	Carried Forward			F
	Bill No. 19 External Works			



	Brought Forward	1		R	
481	Type ref. 193 fabric reinforcement in concrete edge thickening (LI)	m2	24		
	Masonry (CPAP Work Group No. 116)				
	Brickwork of NFP bricks in class II mortar				
482	One brick walls (LI)	m2	7		
	Brickwork sundries				
	2.5mm Galvanised brickwork reinforcement				
483	155mm Wide reinforcement built in horizontally (LI)	m	27		
	Brickwork sundries				
	Bagging of 1:3 cement and sand mixture				
484	On brick walls, piers, etc. (LI)	m2	7		
	Face brickwork				
	"Corojem Nebraska FBS" or other equally approved face bricks pointed with tinted recessed horizontal and vertical joints	ı			
485	Extra over brickwork for face brickwork on both sides of wall (LI)	m2	7		
486	Extra over brickwork for brick-on-edge header course bands one course high (LI)	m	27		
	Waterproofing (CPAP Work Group No. 120)				
	Two coats emulsion bitumen emulsion waterproof coating as per approval				
487	On bagged brick walls, piers, etc. (LI)	m2	7		
	Plumbing (CPAP Work Group No. 148)				
	Carried Forward			R	
	Bill No. 19 External Works				

-249

wo ss 337

Ì	Brought Forward			R
	Polyethylene rainwater tanks, etc.			
488	5000 Litres "JoJo" rainwater tank or other equally approved, with 100 x 100mm opening for downpipe from gutter including 50mm diameter overflow opening and outlet union for 20mm tap (tap elsewhere measured) and place in position on plinth and secure with twisted double strand 4mm galvanised wire.	No	4	
	Taps, valves, etc.			
489	Hose bib tap, brass including 3/4 hose union, etc. (Code: COB-208-20)	No	4	
	Plastering (CPAP Work Group No. 142)			
	Screeds wood floated, on concrete			
490	Average 170mm thick on floors to falls (LI)	m2	34	
	FLAGPOLES			
	Earthworks (CPAP Work Group No. 104)			
	Excavation in earth not exceeding 2m deep			
491	Bases (LI)	m3	1	
	Extra over all excavations for carting away			
492	Surplus material from excavations and/or stock piles on site,to a dumping site to be located by the contractor	m3	1	
	Risk of collapse of excavations			
493	Sides of trench and hole excavations exceeding 1,5m and not exceeding 3m deep	m2	4	
	Compaction of surfaces			
494	Compaction of ground surface under bases, etc. including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% mod AASHTO density	m2	1	
	Concrete (CPAP Work Group No. 110)			
	Carried Forward Bill No. 19 External Works			R
	<i>Q</i> 250	d d		

-250

22 or

ĺ	Brought Forward		1	R	
	Reinforced concrete cast against excavated surfaces and/or formwork				
	30MPa/19mm concrete				
495	Base (LI)	m3	1		
	Test cubes				
496	Making and testing set of three 150 x 150 x 150mm concrete strength test cube (Provisional)	No	1		
	40Mpa Non-shrink grout				
497	Bedding approximately 25mm thick under base plate including chamfered edges all round	m2	1		
	Reinforcement (CPAP Work Group No. 114)				
498	Various diameter bars in high tensile steel reinforcement (LI)	t	0,12		
	Metalwork (CPAP Work Group No. 136)				
	<u>Flagpole</u>				
499	Flagpole comprises of 2x no. of 102mm x 50mm mild steel taper flange channels fixed to foundation, 200mm x 50mm x 6mm mild steel flat bar, 3x no. of 16mm diameter bolt with nut, 100mm diameter x 5000mm long aluminium pole with 4.2mm thickness, 100 x 50mm diameter aluminium reducer, 50mm diameter x 4000mm long aluminium pole with 4.2mm thickness, end cap, galvanised pulley, etc. all in accordance to flagpole details and specifications	No	2		
	LANDSCAPING				
	(CPAP WORK GROUP NO. 104 UNLESS OTHERWISE STATED)				
	Ground preparation				
500	Site clearance	m2	3 610		
501	Rip and prepare areas to receive planting/lawn/seeding	m2	3 610		
	Carried Forward Bill No. 19 External Works			R	
	O <sub>2</sub>				



-251-

	Brought Forward			R
	Topsoil, compost, lime and fertilizer			
502	Import topsoil for planting/lawn/seeding areas (100mm) (LI)	m3	361	
503	Final shaping of planting/lawn/seeding areas (LI)	m2	3 610	
504	Compost to planting areas (50mm) (LI)	m3	42	
505	Fertilizer to planting/lawn beds (50g/m²) (LI)	kg	72	
	Grassing, Trees, etc			
	Supply and plant the following plants			
506	Lampranthus at the rate of five per square metre (LI)	m2	141	
507	Chondropetalum at the rate of three per square metre (LI)	m2	141	
508	Heteropyxis Natalensis 200mm high (LI)	No	25	
509	Podocarpus Henkel 200mm high (LI)	No	25	
	Supply and plant the following grass			
510	Grass planting to level areas with Cynadon Dactylon continuous root planting described including all necessary fertiliser, weed killer, watering and rolling, mowing, etc. (LI)	m2	3 329	
	Maintenance			
511	Maintenance of grassed areas for a period of 4 months (total area approximately 3329m²) including regularly cutting, weeding and irrigating as necessary (LI)		Item	
	Outdoor furniture			
512	"Builders Merchant" or other equally approved quality garden concrete benches (two number) and table (one number), fixed to ground surfaces with approved epoxy glue (LI)	No	4	
513	"SA Bins" or other equally approved 500mm Diameter x 740mm high concrete ribbed round litter bin (grey colour finish), fixed to ground surfaces with approved epoxy glue (LI)	No	8	
	Carried to Summary Bill No. 19 External Works			R
	As ass			

-2

-252-

Ite No			Unit	Quantity	Rate	Amount
		BILL NO. 20				
		PROJECT ASSESSMENT SCHEME (PROVISIONAL)				
		PREAMBLES				
		The descriptions given in the various items below are not necessarily full and complete and reference must be made to the "General Preambles for Trades 2017" as published by the Association of South African Quantity Surveyors", and Supplementary Preambles for further description and amplification of work in this section				
		SUPPLEMENTARY PREAMBLE				
		Tenderer is advised to carefully price this section of the bills of quantities in conjunction with C1.2: Contract Data, C2.1: Pricing Assumptions and C3: Scope of Work incorporated in the tender documents for this tender				
		The profit and attendance priced herein under is inclusive of associated costs to the contractor for implementation. The profit and attendance % is to remain unchanged for the duration of contract - refer to C2.1 Pricing Assumptions				
		TARGETED ENTERPRISE DEVELOPMENT CPG				
		Enterprise Development of Targeted Enterprise or JV Partners				
v.	1	Needs Analysis and Enterprise Development Plan per Targeted Enterprise	No	3	5 000,00	15 000,00
	2	Monitoring and Interim reporting per Targeted Enterprise (Enterprise Development Co-ordinator and mentor)	PerQ	6	60 000,00	360 000,00
	3	Project Completion report per Targeted Enterprise	No	3	5 000,00	15 000,00
		SUB-TOTAL			R	390 000,00
		Carried Forward Bill No. 20 Project Assessment Scheme (Provisional)			R	
		Project Assessment Scheme (Provisional)				
		A 252			D .	



1.00 S

# Proposed New Makhaza Police Station Potion On ERF 75169 OF 59037 (Khayelitsha)

	Brought Forward		1	R	
4	Profit			390 000,00	
5	Attendance			390 000,00	
	CONTRACT SKILLS DEVELOPMENT GOALS - CSDG				
	The following allowance will be subject to adjustment based on the notional cost (see Table 3) as per Government Gazette No. 48491 of 28 April 2023 as amended in line with the training opportunity agreed with the employer.				
6	Minimum Contract Skills Development Goal (CSDG) (0.5% x "Sub total A" on the Final Summary)		0,50%		
7	Profit				
8	Attendance				
	0			R	
	Bill No. 20				
	Project Assessment Scheme (Provisional)				
		1			

-254-

M.D 55

# Proposed New Makhaza Police Station Potion On ERF 75169 OF 59037 (Khayelitsha)

Bill No	FINAL SUMMARY	Page No	Amount
1	Preliminaries	40	
2	Earthworks	44	
3	Concrete, Formwork and Reinforcement	50	
4	Masonry	55	
5	Waterproofing	58	
6	Roof Coverings, etc.	62	
7	Carpentry and Joinery	76	
8	Ceilings, Partitions and Access Flooring	79	
9	Floor Covering	81	
10	Ironmongery	93	
11	Metalwork	110	
12	Plastering	113	
13	Tiling	116	
14	Plumbing and Drainage (Provisional)	134	
15	Electrical Works	170	
16	Mechanical Works	184	
17	Glazing	187	
18	Paintwork	190	
19	External Works	252	
	Sub Total (A)		R
20	Project Assessment Scheme (Provisional)	254	
			R
	Sub Total		
	Carried Forward		R
		1	ti di h



1.6

# Proposed New Makhaza Police Station Potion On ERF 75169 OF 59037 (Khayelitsha)

	FINAL SUMMARY	1 _ 1	1	
Bill No		Page No		Amount
	Brought Forward		R	- 1
	Add: "Allow the amount of R 4 000 000.00 (Four Million Rand) for price escalation to be adjusted in terms of JBCC Contract Price Adjustment Provisions (CPAP)"	Item		4 000 000,00
	Sub Total		R	
	Add: Value Added Tax @ 15%		R	
	Carried to Form of Tender		R	

-256-

N.9 55

# CONSTRUCTION OF NEW MAKHAZA POLICE STATION: WESTERN CAPE PROVINCE

BID: 19/1/9/1/34 TB(25)

PART C:

**CONTRACT** 

Part C3

Scope of Work



# C3: SCOPE OF WORKS - CONSTRUCTION OF NEW MAKHAZA POLICE STATION

JBCC Series 2000

#### **CONTENTS**

Document reference	Document title	No. of Pages
C3	SCOPE OF WORKS	24–
		including this
		one

55 \$ 346



# C3: SCOPE OF WORKS

**JBCC** Series 2000

Project : Construction of New Makhaza Police Station

Employer : South African Police Service Reference : 19/1/9/1/34 TB (25)

#### C3.1. DESCRIPTION OF THE WORKS

#### C3.1.1. Employer's objectives

The South African Police Service endeavors to complete the Construction of New Makhaza Police Station.

In addition to the above, the project aims to achieve the following:

- to provide a minimum Contract Participation Goal (CPG) of 5% of the total contract value and develop targeted enterprises by the main or lead partner contractors
- to train learners in Occupational qualifications, trade qualification, work integrated learners – P1 and P2 learners, professional candidates (which ever is applicable after award of the tender
- c) to deliver public infrastructure using labour-intensive methods in accordance with EPWP Guidelines
- d) Small Micro and Medium Enterprises (SMME's) involvement of at least 30% of the contract value to be sourced from within the specified range from the project site that is Makaza (ward 95, 96), local, district and within the borders of the province the project is located.

The **employer** intends to appoint a suitable **contractor** to construct facilities and amenities as per the **employer** 's specifications

The general intent of this contract is that the **contractor** shall procure all items necessary to construct and complete the **works** in accordance with the terms of this contract, in a workmanlike and expeditious manner

# C3.1.2. Overview of the works

Works included in this contract comprise the construction of a new police station, including all associated services.

The total size of the site is approximately 1.0229 ha

In addition to the requirements specified, the design will ensure that the buildings comply with the national building regulations and standards of the country (SANS), the legal, safety, and health requirements, and should observe sustainable design principles

The extent of the works is detailed below, and the portion of the work relevant to the successful bidder of this document has also been stated below

\$ ,6





#### C3.1.3. Extent of the works

The following is the high-level scope for the project:

- a) Community service center
- b) Public ablution block
- c) Victim friendly facilities
- d) Office block to cater for:
  - Station commander office , including secretary with waiting area
  - ii. Visible policing offices
  - iii. Crime prevention office (open plan office)
  - iv. DPO office
  - v. Detective services spaces
- vi. Support services spaces
- vii. Administration offices
- viii. Store spaces
- e) Cell standard spaces (male, female and juveniles etc)
- f) Cleaners rest room
- g) Emergency generator room (generator must be provided)
- h) Emergency water storage
- i) Air-cons and dehumidifier must be provided where and if necessary
- j) Security fence with lights need to be provided
- k) Undercover parking
- I) Vertical transportation

#### C3.1.4. Location of the works

See C4: Site Information

#### C3.2. WORKS SPECIFICATION

# C3.2.1. Applicable national and international standards

The following, but not limited to, national specifications even though not bound apply to this document, refer to purpose written specifications for all national standards:

- a) Occupation Health and Safety Act, 1993
- b) SANS 10400: National Building Regulations
- c) SANS 10400-XA: Energy Usage in Buildings
- d) SANS 10400-X: Environmental sustainability
- e) SANS 1186-1: Symbolic safety signs Part 1: Standard signs and general requirements

5> ,0



- f) SANS 10142: The wiring pf premises (part 1 & 2)
- g) SANS 10389-1: Exterior lighting Part 1 Artificial lighting of exterior areas for work and safety
- h) SANS 10389-2: Exterior lighting Part 2 Exterior security lighting
- i) SANS 1765: Low voltage switchgear and control gear assemblies (distribution boards) with rated short circuit withastand strength up to and including 10kA
- SANS 10313: Protection against lightning physical damage to structures and life hazard
- k) SANS 62305: Protection against lightning
- SANS 62040: Uninterruptible Power Systems (UPS)
- m) SANS 10252-1: Water Supply Installations for Buildings
- n) SANS 10252-2: Drainage Installations for building
- o) Local Municipality by laws & requirements
- p) SAPS Project Five Star 2012 Specifications for New and Existing Police Cell

### C3.2.2. Particular or generic specifications

The following purpose written (project specific) specifications are applicable to the works and are attached as Annexures after C4: Site Information

- a) SANS 1200 A: General
- b) SANS 1200 C: Site Clearance
- c) SANS 1200 D: Earthworks
- d) SANS 1200 DB: Earthworks (Pipe Trenches)
- e) SANS 1200 DM: Earthworks (Roads, Subgrade)
- f) SANS 1200 G: Concrete (Structural)
- g) SANS 1200 GA: Concrete (Ordinary Building)
- h) SANS 1200 H: Structural Steelwork
- i) SANS 1200 L: Medium pressure pipelines
- i) SANS 1200 LD: Sewers
- k) SANS 1200 LE: Stormwater drainage
- I) SANS 1200 ME: Subbase
- m) SANS 1200 MF: Base
- n) SANS 1200 MK: Kerbing and channelling
- o) SANS 1200 MM: Ancillary works
- p) SANS 1123: Flange Specification
- g) SANS 10140: Part 3: Pipe marking
- r) SANS 10400: Part A: General principles and requirements
- s) SANS 10400: Part O: lighting and ventilation
- t) SANS 10400: Part S: stairways
- u) SANS 10400: Part T: fire protection





- v) SANS 10400: Part W: fire installation
- w) SANS 10177-Part 2-4: fire testing of materials
- x) SANS 543: fire hose reels (with semi-rigid hose)
- y) SANS 1128: Part 1: components of underground and above-ground hydrant systems
- z) SANS 1128: Part 2: hose couplings, connectors, and branch pipe and nozzle connections
- aa) SANS 1186: Part 1: symbolic safety sings: standard signs and general requirements
- bb) SANS 1186: Part 5: Symbolic safety signs: photo luminescent signs
- cc) SANS 1464: Part 22: Safety of luminaries: luminaries for emergency lighting
- dd) SANS 10139: fire detection and alarm system design and installation
- ee) The Occupational Health and Safety Act, Act 85/1993
- ff) SANS 10400-T:2020 Fire Protection
- gg) SANS 10139: 2021 Fire detection and alarm systems for buildings System design, installation and servicing
- hh) SANS 7240-16: Fire detection and alarm systems Part 16 Sound System Control and Indicating Equipment
- ii) SANS 7240-19: Fire detection and alarm systems Part 19 Design, Installation, Commissioning and Service of Sound Systems for Emergency Purposes
- jj) SANS 7240-24: Fire detection and alarm systems Part 24 Sound-system loudspeakers
- kk)SANS10400-A General Principles and Requirements
- II) SANS 10140-3: 2017 Identification colour markings Part 3: Contents of pipelines
- mm) SANS 543:2019 Fire hose reels (with semi-rigid hose)
- nn) SANS 1086:2015 Flexible poly(vinyl chloride) (PVC) pressure hose
- oo) SANS 10087-1:2013 The handling, storage, distribution and maintenance of liquefied petroleum gas in domestic, commercial, and industrial installations Part 1: Liquefied petroleum gas installations involving gas storage containers of individual water capacity not exceeding 500 L and a combined water capacity not exceeding 3 000 L per installation
- pp) BS EN 12101-Part 5 Smoke and Heat Control systems
- qq) Local Municipality Emergency Services By-Laws

# C3.2.3. Minimum Standard requirements

- a) CIDB Best Practice Project Assessment Scheme (Government Gazette No.43726 of 18 September 2020)
- b) Standard for Developing Skills through Infrastructure Contracts, published in Gazette Notice 48491 of 28 April 2023

