

ITEM	LIC	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
33.00		<b>MASS EARTHWORKS</b>				
33.01		<b>Cut and borrow to fill, including free- haul up to 0.5km</b>				
		(a) Gravel material in compacted layer thickness of 200 mm and less				
		(i) Compacted to 90% of modified AASHTO density	m³	1,350.00		
33.03		<b>Extra over item 33.01 for excavating and breaking down material in</b>				
		(a) Intermediate excavation	m³	250.00		
		(b) Hard excavation	m³	100.00		
		(c ) Boulder excavation class A	m³	50.00		
33.04		<b>Cut to spoil, including free-haul up to 0.5 km. Material obtained form:</b>				
		(a) Soft excavation	m³	900.00		
		(b) Intermediate excavation	m³	50		
33.07		(c ) Hard excavation	m³	10.00		
		<b>Removal of unsuitable material (including free-haul of 0.5km):</b>				
		<b>(a) In layer thickness of 200mm and less:</b>				
		(ii) Unstable material	m³	200.00		
33.09		<b>Material bladed to windrow</b>	m³	100.00		
33.10		<b>Roadbed preparation and the compaction of material</b>				
		(b) Compaction to 93% of modified AASHTO density	m³	1,080.00		
		(c) Compaction to 95% of modified AASHTO density	m³	900.00		
33.12		<b>In situ treatment of roadbed:</b>				
		(a) In situ treatment by ripping (200mm deep)	m³	560.00		
33.13		<b>Finishing-off cut and fill slopes, medians and interchange areas:</b>				
		(a) Cut slopes	m²	800.00		
		(b) Fill slopes	m²	500.00		
16.00		<b>OVERHAUL (Extra over items 33.01, 33.04 &amp; 33.07)</b>				

16.01		Overhaul on material hauled in excess of a free-haul distance of 0,5 km for haul up to or through 1,0km (ordinary overhaul)	m³	250.00		
16.02		Overhaul on material hauled in excess of 1,0km \				
		(ordinary overhaul)	m³-km	5,800.00		
TOTAL CARRIED FORWARD TO NEXT PAGE						