

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	TENDER AMOUNT
1200	GENERAL REQUIREMENTS AND PROVISIONS				
12.01	Community Liaison:				
	(a) Community Liaison Officer cost	Prov. Sum	1.00		
	(b) Monthly sitting allowance for PSC Members	Prov. Sum	1		
	(c) Handling costs and charges for Contractor on items 12.01 (a) to (b)	%			
12.02	Remedial Work				
	(a) Rehabilitation of borrow pits and quarry	Prov. Sum	1		
	(b) Removal of site establishment	Sum			
CARRIED FORWARD TO SUMMARY :					R0.00

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE
1300	CONTRACTOR'S ESTABLISHMENT ON SITE AND GENERAL OBLIGATIONS			
13.01	The contractor's general obligations:			
	(a) <u>Fixed obligations</u>	Lump sum	1	
	(b) <u>Value-related obligations</u>	Lump sum	1	
	(c) <u>Time-related obligations</u>	Month	6	
13.02	Occupational Health & Safety:	lump sum	1	
	(a) - Preparation of Contractor's site specific Health and Safety Plan			
	(b) - Principal Contractor's initial obligations in respect of the OHS Act and Construction Regulations			
	(c) - Principal Contractor's time related obligations in respect of the OHS Act and Construction Regulations			
	(d) - Provision for Personal Protective Equipment & Protective Clothing including the following items			
	(i) Reflective vests (15)			
	(ii) Work Suits(15)			
	(iii) Hard hats(15)			
	(iv) Protective foot wear(15)			
	(v) Earplugs and Goggles (15)			
	(vi) Dust masks (15)			
	(e) - Provision of full time Construction Health and Safety Officer for project duration			
	(f) - Induction Training			
	(g) - Provision of First Aid Boxes			
	(h) - Submission of the Health and Safety File			
	(i) Contractors Obligations for OHS COVID 19 & Construction Regulations			
	(j) Costs of Medical Certificates for all employees			

CARRIED FORWARD TO SUMMARY :

AMOUNT	

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
1400	HOUSING, OFFICES AND LABORATORIES FOR THE ENGINEER'S PERSONNEL				
14.08	Services: The provision of water, electricity, sewerage, septic tanks, sewage and rubbish removal, cleaning services, maintenance and repairs, all as specified in Clause 14.04, including the construction and maintenance of the access roads, footpaths, etc: (a) Services at office and laboratories (i) Fixed costs (ii) Running costs	Lump sum Month	1 6		
14.09	Combined office and laboratory accommodation: Office and laboratory accommodation, including fittings, furniture and equipment, car ports and housing in accordance with the details given in the project specification and on the drawings and airconditioning	Lump sum	1		
CARRIED FORWARD TO SUMMARY :					

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
1500	ACCOMODATION OF TRAFFIC				
15.01	Accomodation of traffic	km	4.80		
CARRIED FORWARD TO SUMMARY :					0

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
1600	OVEHAUL Overhaul on material hauled in excess of 1.0km (ordinary overhaul)	m³-km	18144.00		
CARRIED FORWARD TO SUMMARY :					0

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
1700	CLEARING AND GRUBBING				
17.01	Clear and grubbing	ha	0.20		
17.02	Removal and grubbing of large trees and tree stumps:				
	(a) Girth exceeding 1m up to and including 2m	No		Rate only	
17.04	Clearing and grubbing at inlets and outlets of hydraulic structures	m ²		Rate only	
CARRIED FORWARD TO SUMMARY :					-

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
2100	DRAINS				
21.01	Excavation of open drains				
	(a) Excavating soft material situated within the following depth ranges below the surface level				
	(i) 0m up to 1,5m	m ³	15.00		
	(b) Extra over subitem B21.01(a) for excavation in hard material irrespective of depth	m ³			Rate only
21.02	Clearing and shaping existing open drains	m ³	32.00		
21.14	Repairing or replacing of existing drainage systems	Prov Sum	1.00		
21.20	Clearing and shaping side and mitre drains by grader	m	30.00		
CARRIED FORWARD TO SUMMARY :					-

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
2200	PREFABRICATED CULVERTS				
22.01	Excavation				
	(a) Excavating soft material situated within the following depth ranges below the level surface level				
	(i) 0m up to 1,5m	m ³	28.00		
	(ii) Exceeding 1,5m and up to 3,0m	m ³	15.00		
	(b) Extra over subitem 22.01(a) for excavation in hard material, irrespective of depth	m ³			
22.02	Backfilling				
	(a) Using the excavated material	m ³	32.00		
	(b) Using imported selected material	m ³	22.00		
22.03	Concrete pipe culvert				
	(b) On class B bedding				
	(i) 600 mm dia class 100D	m	14.66		
22.07	Cast in situ concrete and formwork				
LIC	(c) concrete base lab excluding formword but including class U2 surface finish (25MPa / 19)	m ³	32.00		
22.17	Manholes, catch pits, inlet and outlet structurescomplete				
LIC	Complete inlet structures as per detail on drawing.....	No	2.00		
LIC	Complete outlet structures as per detail on drawing.....	No	2.00		
22.26	Hand excavation to determine the position of existing services				
LIC		m ³	15.00		
CARRIED FORWARD TO SUMMARY :					-

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
3100	BORROW MATERIALS				
31.01	Excess overburden (provisional)	m ³	85.00		
31.03	Finishing-off borrow areas				
	(a) Hard material	ha	0.80		
	(b) Intermediate material	ha	0.60		
	(c) Soft material	ha	0.90		
CARRIED FORWARD TO SUMMARY :					-

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
3300	MASS EARTHWORKS				
33.01	Cut and borrow to fill, including freehaul up to 0.5km :				
	(a) Material in compacted layer thickness of 150mm and less:				
	(ii) Compacted to 93% of mod AASHTO	m ³	3,600		
33	Cut to spoil, including free-haul up to 0.5km Material obtained from:				
	(a) Soft excavation	m ³	120		
	(b) Intermediate excavation	m ³	15		
	(c) Hard excavation	m ³	24		
33.07	<u>Removal of unsuitable material (including free-haul of 0.5km)</u>				
	(a) In layer thickness of 150mm and less:				
	(i) Stable Material	m ³	420		
33.10	<u>Roadbed preparation and compaction of material</u>				
	(b) Compaction to 93% Mod AASHTO density	m ³	450		
33.12	<u>Insitu treatment of roadbed</u>				
	(a) Insitu treatment by ripping	km	0		
CARRIED FORWARD TO SUMMARY :					

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
3400	PAVEMENT LAYERS OF GRAVEL MATERIAL				
34.01	Pavement layers constructed from gravel taken from cut or borrow including free haul up to 1,0km				
	(h) Gravel wearing course compacted to				
	(ii) 95% Mod AASHTO density: 150mm layer thickness	m ³	3600.00		
CARRIED FORWARD TO SUMMARY :					-

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
5100	PITCHING, STONEMWORK AND PROTECTION AGAINST EROSION				
51.01	Stone pitching				
LIC	(b) Grouted stone pitching	m ²	225.00		
51.03	Stone masonry walls:				
	(b) Cement-mortared stone walls	m ²		Rate only	
CARRIED FORWARD TO SUMMARY :					-

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
5900	FINISHING THE ROAD AND ROAD RESERVE AND TREATING OLD ROADS				
59.01	Finishing road and road reserve				
	b) Single carriageway road	km	4.80		
CARRIED FORWARD TO SUMMARY :					-

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
6200	FALSEWORK, FORMWORK AND CONCRETE FINISH				
62.01	Formwork to provide class F2 surface finish to concrete surface /slab	m²			
62.02	Vertical formwork to provide class F2 surface finish to concrete surface/slab	m²	138.00		
	0.00				
CARRIED FORWARD TO SUMMARY :					-

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
6300	STEEL REINFORCING FOR STRUCTURES				
63.01	Steel reinforcement for:				
	(a) Concrete				
	(3) Welded steel fabric mesh (ref 395)	kg	128		
CARRIED FORWARD TO SUMMARY :					-

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
6400	CONCRETE FOR STRUCTURES				
64.01	Cast in situ concrete				
LIC	(a) Class 25 /19	m ³	18.00		
CARRIED FORWARD TO SUMMARY :					-

SUMMARY OF SCHEDULE OF QUANTITIES

SECTION	DESCRIPTION	AMOUNT
1200	General Requirements and Provisions	R 0.00
		R 0.00
1300	Contractors Establishment and General Obligations	R 0.00
1400	House, Offices and Laboratory for Engineer's Personnel	R 0.00
1500	Accommodation of Traffic	R 0.00
		R 0.00
1600	Overhaul	R 0.00
		R 0.00
1700	Clearing and Grabbing	R 0.00
		R 0.00
2100	Drains	R 0.00
		R 0.00
2200	Prefabricated Culverts	R 0.00
		R 0.00
3100	Borrow Materials	R 0.00
		R 0.00
3300	Mass Earthworks	R 0.00
		R 0.00
3400	Pavement Layers of Gravel Material	R 0.00
		R 0.00
5100	Pitching, Stonework and Protection Against Erosion	R 0.00
		R 0.00
5600	Road signs	R 0.00
		R 0.00
5900	Finishing the Road Reserve and Treating of Old Roads	R 0.00
		R 0.00
6200	Falsework, Formwork and Concrete Finish	R 0.00
		R 0.00
6300	Steel reinforcing of Structures	R 0.00
		R 0.00
6400	Concrete for Structures	R 0.00
		R 0.00
8100	Testing Workmanship and Materials	R 0.00
Subtotal A		R 0.00
Add 5% Contingencies		R 0.00
Subtotal B		R 0.00
Add 15% VAT		R 0.00
Total Tender Amount		R 0.00

Signed :

Date:

Name of Tenderer :